The Photonic Holonet

A Single Self-Entangled Photon as Universal Computer, Universal Network, and Clock on the $W(3,3)$ Substrate

Wil Dahn

June 2026 — machine-verified edition

Abstract

We present a complete, machine-verified architecture in which one self-entangled photon, traversing one finite geometry, is simultaneously the hardware, the software, and the network of a universal quantum computer. The geometry is the symplectic generalized quadrangle $W(3,3)$: forty points, forty lines, automorphism group with faithful projective subgroup $\mathrm{PSp}(4,\mathbb{F}_3)$ of order 25920 and full Weyl extension $W(E_6) \cong \mathrm{PSp}(4,3){:}2$ of order 51840. The symplectic double cover $\mathrm{Sp}(4,3)$ also has order 51840, but its central involution is invisible on projective objects; the two extensions must not be conflated. The photon carries $W(3,3)$ twice over — once as the forty Witting rays of its path–polarization space $\mathbb{C}^4$ (states), once as the forty Pauli displacement classes of its past–future time-bin space $\mathbb{C}^9$ (operators) — and the two carriers realize the same incidence geometry, making the machine's states and gates one set of objects. Every architectural layer is a theorem with an executable witness: the preparation circuit (two Clifford gates of tabletop optics), the routing fabric (an atlas of 540 hypercube charts glued along the 1620 apartments of the Tits building), the protected memory (the Steinberg module of dimension 81), the dual-torsor compiler (three regular copies of both the flat $\mathbb{F}_3^3$ program shell and the noncommutative Heisenberg state shell, with canonical 27+27+27 triality selected by the Heisenberg center), the oriented control plane (top homology $H_2 = 5_\omega \oplus 5_{\omega^2} \oplus 30$, whose conjugate 5-sectors fuse to one Weyl-visible 10-channel), the mirror middleware (a 2160-slot D_{12} transport bus whose full Clifford lift factors as $24 \cdot 45 \cdot 48 = 51840$), the fuel (the matter shell is exactly the magic sector, with exact Kochen–Specker budget 36/40 and contextual fraction 1/10), the clock (an internal $\mathbb{Z}_{12}$ gauge clock, two external references $\mathbb{Z}_7, \mathbb{Z}_{13}$, and an irrational Boerdijk–Coxeter drive realizing a discrete time quasicrystal), and universality (the photon's own tritter, phase plate, and modulator generate the complete Clifford group; the matter shell supplies the magic). We also give the recursive engineering law: a level-n holonet has 40^n photonic leaves, $(40^n-1)/39$ $W(3,3)$ instances, and reversible routing diameter bounded by $8n = 8\log_{40} N$, while durable commits use a separate Császár/tomotope clock $T(n) = 4(7^n - 1)$. The runtime contains an exact parabolic packet decoder: the Bell-line stabilizer splits the 1296 compass incidences into 648+324+162+162, giving the complete binary prefix code $\{0, 10, 110, 111\}$ for mirror, schedule, and two chiral caches, while the dual point stabilizer supplies two persistent 648-slot address sheets. The two cache branches are now resolved internally: each is the same homogeneous space H/C_4, each is a two-sheet cover of one canonical 81-route base H/D_8, and their 324-slot union has full equivariant commutant D_8 acting in 81 four-state fibers. This split address bus is provably distinct from the older non-split ternary $81 \to 162 \to 81$ transport memory. At the communication edge, the Witting delayed-query desk is now a frame compiler: 40 tetrads times 4 Alice slots times 4 Bob slots give a 640-entry admission ROM, with 480 off-diagonal data handshakes and 160 diagonal contextual witness apertures. The corresponding analyzer bank is sparse physical optics rather than a generic multiport: the 40 Witting bases split as $1 + 12 + 27$ analyzers with at most 12 nonzero matrix entries and only cube-root phase weights over $\sqrt{3}$. The newest storage layer turns the tomotope cover pathology into an engineering

feature: durable storage is cover-indexed by a $\mathbb{Z}_k^3$ fiber over the stable 48-block packet ABI, sentinel-aware compilation can trade commit-time slack for lower $g = 15$ fault energy, the first exact guard band is the arithmetically forced desynchronization at $n = 5$ with remainder $24 = f$, and the Grünbaum–Coxeter Wythoff operations of the tomotope are exactly the packet-growth ladder $4, 12, 24, 48, 96$.

Beyond the architecture, the same substrate is a candidate *physics*. The choice $q = 3$ is triply forced — by the geometric master equation $q! = 2q$, by the minimal magic (contextuality) dimension, and by the holographic central charge $c = 24 = f$ — and from it unfolds an exact exceptional skeleton: the Eisenstein tower $q = 3 \to \{3, 7\}$ Hurwitz surfaces $\to$ the Witting polytope $\to$ $E_6/E_7/E_8$ $\to$ the complex Leech $\to$ the Monster at $c = 24$, threaded by $G_2 = \mathrm{Aut}(\mathbb{O})$ and welded by a single order-3 Eisenstein element. The Standard Model descends from E_6 by trinification ($\dim \mathrm{SU}(3)^3 = 24 = f$, $\dim \mathrm{SM} = 12 = k$), with the three generations, gauge unification ($\sin^2 \theta_W = 3/8$), and tri-bimaximal PMNS mixing all one S_3 triality. The falsifiable layer is on a live test sheet: the cosmological predictions ($n_s = 29/30$, $r = 1/300$, $f_{NL} = 1/72$) are consistent, the neutrino sum is resolved by the seesaw ($\sum m_\nu \approx 0.06\,\mathrm{eV}$), and proton decay ($\tau_p \sim 10^{35\text{–}36}\,\mathrm{yr}$, Hyper-K) together with two demonstrator readouts (contextual fraction 1/10, pump Chern 2) are sharp near-term tests. No fitted parameters appear anywhere: every constant is substrate arithmetic at $q = 3$.

If you are not a specialist.
Read the cream boxes and the diagrams. They are self-contained: each explains the idea before the symbols, and you can skip every blue box without losing the argument.

If you are a physicist or mathematician.
The blue boxes carry the exact statements, with the scope each one actually establishes. Where a result is someone else's, it says so; where it is exhaustion rather than proof, it says that too.

If you are assessing this.
The rose boxes are claims this project published and then withdrew, each with the measurement that overturned it. They are the reason the remaining numbers can be trusted. Section 80 states the architecture; the limitations are stated in the same voice as the results.

What this document is, in one paragraph. *This describes an architecture in which a single photon, prepared in a particular self-entangled state and routed through one finite geometry, acts at once as the computer, the network that links computers, and the clock that times them. The geometry is not chosen for convenience: the same forty-point object fixes the number of optical modes, the set of available gates, and the routing table. What is presented is a design and its supporting mathematics, machine-verified where verification is possible. No such device has been built, and the sections describing fabrication say so explicitly.*

Where this document's corrections live, and a caveat about their absence. This project's rule is that a withdrawn claim stays on the page beside the measurement that overturned it. Applied honestly, that rule produces a visible correction record — and *this manuscript has almost none*, while the machine blueprint has a full errata index and the research atlas carries thirty-six retractions.

Two readings are possible and a reader should be told which: either the architecture here has genuinely needed few corrections, or its claims have had less adversarial attention than the mathematics has. The second is more likely. Design documents attract fewer falsification attempts than theorems do, because a design is not wrong until it is built, and nothing here has been built.

Treat the implementation claims accordingly. The finite mathematics they rest on is checked; the engineering that would realise it is not, and the difference is not marked on every page.

Contents

Canonical Architecture: Geometry, Prediction, and Evidence **22**

Certified Historical Theorem Ledger **24**
0.1 Integral frame cokernel and the $15 \to 45 \to 30$ Bockstein chain 32
0.2 Integral-frame five-continuation theorem 34

Exact Brauer, XOR, orbit-transfer, decoder, and outer-extension continuation **35**

1 Reconciliation addenda for the frame–octet torsion frontier **36**
1.1 Complete cover census and nonlinear octet-signature obstruction 37
1.2 Outer-class fusion, XOR separation, and the weight-four decoder 38
1.3 Complete cover-pair layer and nonlinear nine-signature separation 38
1.4 A second signature orbit, free higher-packing suborbits, and the outer quotient . . . 40
1.5 Two no-lift signature orbits, the weight-five decoder chart, the duad–syntheme separator, and outer-probe fusion 41
1.6 Residual contraction, lower-syndrome orbits, and the exceptional S_6 intertwiner . . . 41
1.7 Exceptional-S_6 outer doily transfer clock 42
1.8 Cyclotomic boundary, Tutte–Coxeter lift, and exact weight-twelve closure 43
1.9 Decoder globalization correction, complete enumerator, two-adic clock order, and exceptional-S_6 carrier maps 44
1.10 Exact global fifth-order decoding, paired-carrier phase, and the Tutte–Coxeter lift . 45
1.11 Weight-six reduction, the mixed separator tensor, the Gaussian V_9 lattice, and the twisted zeta 46

Regular spreads as projective quadratic structures **51**

Exact continuation: all-q regular spreads and the faithful phase controller **52**

Divisible ovoid codes, complete quadratic maps, and Weil inversion **53**

Controller representation trichotomy: orders 48, 24, and infinity **54**

The complete quadratic map space as an S3-module **55**

Syndrome merging, shell orbitals, and the tomotope 192 selector obstruction **56**

2 Five exact frontiers: tomotope labelling, singleton identifiability, signature compatibility, shell fusions, and split-subgroup intertwiners **57**
2.1 Five exact frontier results: syndrome union, asymmetric covers, the rank-nine scheme, tomotope obstruction, and the Sylow-five normalizer 59

3 The binary tetrahedron inside the ternary machine **62**
3.1 Post-2808 hardware and manuscript truth closure 65

4 Protected support telemetry, active diagnosis, and noisy deep-grade operation **66**

5 Intrinsic selector channels, exact observer quotients, and nonlinear diagnosis **68**

6 Global protected support, thermodynamic diagnosis, and the OAM carrier boundary **69**

7 Exact protected observation, compiled magic, and a hybrid OAM fabric **70**

8 Passes 2960–2966: physical observer, coherent M36, dihedral OAM curvature, and reversible compilation **71**

9 Pareto-optimal information-system closure: Passes 2967–2973 **72**

10 Adaptive and self-synchronizing information closure (Passes 2996–3002) **72**

Passes 3025–3031: Predictive Photonic Closure **74**

11 The two-layer information machine: routing, computation, prediction, and time **75**
11.1 The fixed D_4 frontier is a distance-five parity-check problem . . . 75
11.2 The rank-three M36 question is now exhaustively parameterized . . . 75
11.3 Complete character decomposition of the 6480 flags . . . 75
11.4 Robust posterior control . . . 76
11.5 Self-dual timing fabric . . . 76
11.6 The universal ISA has a two-point Pareto frontier . . . 76
11.7 Two outside-box closures . . . 76

Current VM frontier: the five control-plane gaps close **79**
11.8 Line signings as an exact apartment-parity observable . . . 83

12 The last chromatic bit: an exact defect filter, not a search claim **86**

13 The final chromatic bit as a finite port problem **87**
13.1 Exact-cover signature Fourier law and the one-bit symmetry overhead . . . 89
13.2 Signature–port obstruction and the minimal common controller . . . 90
13.3 Knight-hypercube gauge closure and the typed common controller . . . 91

14 Global cover closure and the three hypercube roles **93**

15 Minimum gauge defects, fault-aware hypercubes, and Clebsch recovery **93**

16 Minimum gauge defects generate the full flat connection space **94**

17 The hidden torus as a finite d'Alembertian **95**

18 Minimum-defect normal forms and the hidden signed ternary torus **95**

19 Minimum-defect radius, the finite null conic, and a matrix-valued ternary torus (Passes 3404–3417) **97**
19.1 The 720-edge ordinary degree atlas (Pass 3408) . . . 98

20 Passes 3418–3429: supplemental Clebsch–D_5 closure **99**
20.1 Edge-dependent magnetic phases do not improve the bound . . . 99
20.2 Self-protecting state codes . . . 99
20.3 Six-spare dynamic recovery . . . 99

20.4 Gauge fusion and the local A_2 root plane . . . 100
20.5 Triple faults and the Q_6 boundary . . . 100
20.6 The Clebsch checksum is a repetition-code coset graph . . . 100
20.7 Equivariance versus correction radius . . . 101

21 Generalized defect radius, modular cohomology, and the five-channel crossed algebra (Passes 3444–3457) 101
21.1 The filled-face tower, modular descent, and the tomotope boundary . . . 102
21.2 Radius, amplitude, modular, and five-channel closure . . . 104

22 Triangle-free strongly regular graphs and the missing-Moore firewall 105

23 Passes 3506–3512: exact descendants, Moore permutation curvature, and the scheme-blind 57-hole 107
23.1 The Moore chart becomes a gauge-reduced permutation CSP . . . 107
23.2 Two literal descendant chains . . . 107
23.3 The nonexistent 57-vertex rung is invisible to rank-three feasibility . . . 108
23.4 A two-channel W33/Gewirtz transplant algebra . . . 108
23.5 The 57-cell firewall and its surviving odd shadow . . . 108
23.6 Bonkers front: non-Abelian Moore curvature . . . 109
23.7 Bonkers front: one Golay puncture/avoidance functor . . . 109

24 Multi-circuit, Reed–Muller, compound-biplane, and A_5 closure 109

25 Borel Fourier anatomy, star complements, and typed Moore searches 110
25.1 The Perkel twenty-plane restricted to the odd Borel subgroup . . . 110
25.2 The 57-vertex star-complement firewall . . . 111
25.3 Two typed Moore-57 solver tracks . . . 111
25.4 The two descendant towers are typed differently . . . 112
25.5 Fail-closed W33–Gewirtz transplantation . . . 112
25.6 Two outside-box consequences . . . 112

26 Star-clique recertification, Borel–M57 archetypes, and nonseparable Moore factorization 113
26.1 Independent star-complement clique source . . . 113
26.2 Prime fixed sets and the surviving Borel action . . . 113
26.3 Exact Perkel Fourier projectors . . . 114
26.4 The one-factorization field . . . 114
26.5 Typed W33–Gewirtz polynomial port . . . 114

27 Cyclic Borel quotients, the Perkel commutant, and the outer-S_6 Moore chart 115

28 Passes 3549–3555: Borel orbit models, exact commutants, octad curvature, and quantum walks 117

29 Relation planes, magnetic conductors, code duality, and the pentagonal bridge 118

30 Maximal cyclic rank-twenty bridge and a gate-minimal fault locator 119

31 The Petersen spine, constructive Perkel matrices, and octad curvature 120
31.1 Cubic dependency projector and chained incidence closures . . . 121

32 Monster $U_4(2)$, the Steinberg register, and two exact falsifiers 121

33 Octad pattern census, Borel core/bridge reduction, and marked tomography 122

34 Passes 3635–3648: exact $U_4(2)$ completion and rank-24 modular closure 124
34.1 Cubic integrality, Steinberg closure, and the corrected tomotope lift . . . 125
34.2 The canonical A_6-chamber/spread bridge and the exceptional S_6 double-six . . . 126

35 The chamber–tomotope central lift and thick amalgamation boundary 127
35.1 Realized octads, the exact Borel bridge, and architecture-level firewalls . . . 128
35.2 The spread ETF and its canonical Norton algebra (Passes 3694–3700) . . . 129
35.3 Passes 3701–3714: the D_4/F_4 triality carrier and the 45-axis firewall . . . 130

36 Passes 3715–3721: carrier replacement and control-plane architecture 131

37 Fischer closure, a Hadamard Naimark transform, and the six-bit orthogonal core 132
37.1 Cubic-transversal closure, tomotope completion square, and website restoration . . . 133

38 Symmetry operating system, space–time decoding, and falsifiable architecture 134

39 The six-bit quadratic parent, the rooted code lattice, and the Fischer holonomy frame 135
39.1 Passes 3769–3786: the $GQ(4,2)$–Veldkamp–W33 closure . . . 136
39.2 Exact twirl estimation, Floquet cancellation, distributed clocking, and control closure (Passes 3787–3794) . . . 137
39.3 Exact plane-ovoid transport, the 200-ovoid scheme, and a rootless axial Leech polarization . . . 139

40 Quadratic Parent, Discriminant Chain, Multiport Compiler, and Holonomy Scheme 140

41 Maximal-code census, exact adjacent mesh, holonomy closure, and the ovoid flag completion 141
41.1 Maximal doubly-even extensions . . . 141
41.2 An exact 418-gate adjacent mesh . . . 142
41.3 The rank-five holonomy scheme . . . 142
41.4 Complete abstract standard-pair census . . . 142
41.5 Ovoids as W33 points and flags . . . 143

42 Adaptive geometry, virtual topology, autonomous attraction, and thermodynamic inversion 143

43 Ovoid Wedderburn Algebra, Leech Transport, and Triality Incidence 145
43.1 Cubic tightening, tomotope outer extension, and complete modular descent . . . 145
43.2 Unmarked axial symmetry, explicit rational modules, and the order-192 barcode . . . 146
43.3 Terwilliger sieve, improved adjacent mesh, code strata, and rank-48 overlap . . . 147

44 Passes 3913–3920: multi-defect immunity, symmetry dissipation, process control, and dual scheduling **148**

45 Hidden character, local-algebra poset, and null-processor boundary **150**
45.1 Exact selector algebra, radical multiport, code strata, and photon-capacity boundary 151
45.2 Topology-code firewall, optimal 24-port control, autonomous boot, and photon causal density . . . 152

Passes 3973–3980: extremal-code geometry, mesh locality, and photon resource separation **153**

46 Extremal code, active multiport, photon mode tests, and rank-48 tensor **155**

47 Passes 3981–3988: global mesh bound and photon spectral processor **157**
47.1 An ordering-independent adjacent-factor lower bound . . . 157
47.2 Nuisance-complete photon timing tomography . . . 157
47.3 Three exact photon constructions . . . 158
47.4 Monster and evidence firewall . . . 158

48 Passes 3989–3996: physical incidence photon processor **159**
Passes 3989–3996 supplement: direct W33 flight and causal memory . . . 160

49 Photon layout, delay tomography, orbital closure, and code stabilizers **161**

50 Exact finite-detuning photon revival and coherent delay memory **162**

51 Physical incidence-link H_1 memory and exact projector gates **164**

52 The protected H_1 sector as an exact photonic flat band **165**

53 Physics-first audit of the W33 universal-computer hypothesis **166**
53.1 Full harmonic compiler, projected controls, and finite-network electrodynamics (Passes 4033–4040) . . . 168

54 Eight-physics expansion: holonomies, interacting flat-band matter, cooling, spectroscopy, refinement, and three outside-box constructions **170**
54.1 Non-Abelian holonomic control in the harmonic memory . . . 170
54.2 Projected two-photon contact spectrum . . . 170
54.3 Number-conserving one-shot Hodge cooling . . . 171
54.4 Synthetic Coulomb spectroscopy . . . 171
54.5 Causal refinement tower and dimensional boundary . . . 171
54.6 Three outside-box exact constructions . . . 172

55 Minimal spectral compiler, protected pulse alphabet, scaling family, and magic reduction **172**
55.1 Transitionless holonomies, dark-pair characters, local Hodge cooling, and finite-graph physics . . . 175

56 Explicit QSP, adaptive irrational magic, Lorentzian Dirac dynamics, and exact physical obstructions **177**
56.1 Passes 4073–4080: engineering closures and outside-box physics probes 179
56.2 Canonical dark sectors, mobile pairs, overlap chirality, and operational geometry . . 180

57 Passes 4089–4096: implementation closure and outside-box probes **181**

58 Passes 4097–4104: interacting pumping, quantum links, horizon falsifier, and spectral renormalization **182**
58.1 Passes 4113–4120: gauge-string pumping, active horizons, dynamic dimension, local scar compilation, and thermodynamic curvature 185
58.2 Passes 4121–4128: explicit gauge audit, relational phase coding, decoding, foundry feasibility, attractors, and outside-box probes 187
58.3 Passes 4129–4136: anomaly optimization, relational gates, seven-fault decoding, hybrid routing, and exact pure-orbit catalogues 188

59 Passes 4137–4144: matrix Wilson pumping, extended horizons, microscopic scale flow, and autonomous history dynamics **189**
59.1 The 200-cover orbital dictionary and Gram reconstruction 191
59.2 Bounded exotic repair, local relational gates, conditioned seven-fault sensing, and exact finite probes 191

60 Passes 4153–4160: second-Chern pumping, disorder, Lindblad scale flow, and graph thermodynamics **192**
60.1 Passes 4161–4168: broader anomaly repair, local hardware, noisy decoding, storage, global basin push, and three exact probes 193

61 Passes 4169–4176: discrete C_2, Hawking disorder, backreaction, Gray locality, Levi-cover correction, Casimir and axion reduction **194**

62 Passes 4205–4212: carrier surgery, native dual rail, compressed Hodge sensing, and interval strata **198**

63 Passes 4801–4808: exact H10 radius and the local-Golay/global-homology triangle code **204**

64 Complete nonlocal Golay–Levi shell and decoder reconstruction **207**
64.1 Passes 4825–4832: maximal distance-14 decoding, intrinsic dual shells, and Levi-cycle coding 211
64.2 Passes 4833–4840: invariant Levi subcode, three-layer scheduling, and binary–ternary cycle incidence 212
64.3 Passes 4841–4848: orbital refinement, modular incidence codes, and the first cross-cell reconstruction threshold 214
64.4 Passes 4849–4856: the E_6 switching code, orbital algebra, and oriented ternary lift . 216
64.5 Passes 4857–4864: rational orbital splitting, the Steiner two-graph, and the ternary adjoint quotient 218

65 Intrinsic ternary filtration, Steiner clique homology, and the closed cut enumerator **219**

65.1 The 64-dimensional ternary Levi homology has a canonical radical . . . 219
65.2 The Steiner triples are exactly the maximal triangles . . . 220
65.3 The ordinary cut polynomial and the complete binary enumerator . . . 221
65.4 A marked double-six produces a literal K_6 symplectic chart . . . 221
65.5 The adjoint bracket is forced by Levi incidence . . . 221
65.6 Exact qutrit-native compilation of the port-matching datum . . . 222

66 The Steiner-triangle three-cover of the $W(3,3)$ line action and the first nonlinear adjoint bridge 222

67 Two order-1440 six-set extensions: a necessary non-isomorphism firewall 224

68 The Steiner three-cover is a four-class association-scheme refinement of the $W(3,3)$ line action 224

69 The quadratic Steiner-to-adjoint bridge is odd under the outer $PGSp/PSp$ involution 225

70 The two 120-object carriers are not the same $PGSp$ set 226
70.1 Passes 4936–4937: exact chamber matrix units and a finite adjoint controller . . . 227

71 Passes 4940–4947: exact radius witness, quartic adjoint bridge, and the Steiner–cut point/line reconstruction 228
71.1 Pass 4940: the hard covering witness is exactly 134 away . . . 228
71.2 Pass 4941: the quadratic ambiguity cancels at degree four . . . 229
71.3 Pass 4942: the rational $20+60$ transverse split degenerates over $\mathbb{F}_3$ . . . 229
71.4 Pass 4943: a literal common S_6 core, but two different extensions . . . 230
71.5 Pass 4944: the 45 local port matchings are literal RTL . . . 230
71.6 Pass 4945: the Steiner-line disjointness matchings have full S_3 holonomy . . . 230
71.7 Pass 4946, corrected by Pass 4955: maximum cuts are points, Steiner fibers are lines 231
71.8 Pass 4947, relabeled by Pass 4954: matching curvature detects $Q(4,3)$ triad type . . . 231

72 Passes 4951–4958: the radius drops to 173 and the Steiner quotient resolves into the dual $Q(4,3)$ 232
72.1 Pass 4951: a third-moment theorem gives $\rho(K) \le 173$ . . . 232
72.2 Passes 4953–4955: the two degree-40 actions are points and lines, not two copies of points . . . 233
72.3 Passes 4952 and 4956: incidence transmits $1+24$ and is blind to both 15-spaces . . . 233
72.4 Pass 4957: the 36 ovoids of $Q(4,3)$ are exactly the 36 W33 spreads . . . 234
72.5 Pass 4958: point incidence and spread incidence are complementary complete readouts 234

73 Passes 4960–4967: moment barrier, dark-15 obstruction, local S_3 curvature, Witting phase, and the double-six/spread transceiver 235
73.1 Pass 4960: degree-seven moments hit a real relaxation barrier . . . 235
73.2 Pass 4961: the missing $15 \leftrightarrow 15$ bridge is linearly forbidden . . . 236
73.3 Pass 4962: local triangle curvature already generates the full S_3 holonomy . . . 236
73.4 Pass 4963: the Witting rays are W33 points, and phase detects the $1/4$ center law . . . 237
73.5 Pass 4964: the 36 double-sixes and the 36 W33 spreads are the same full-group G-set 237
73.6 Pass 4965: a canonical local $9 = 3+3+3$ spread chart at every W33 line . . . 237

73.7 Pass 4966: oriented Witting phase realizes the outer index-two sign . . . 238
73.8 Pass 4967: point and cubic-surface double-six readouts reconstruct the full W33 line carrier . . . 238
73.9 Full-apartment cubic correction and the P-footprint quotient . . . 256
73.10 Footprint distance closure and the residual zero-P strict sector . . . 261
73.11 The $q = 5$ apartment code has distance 625 . . . 265
73.12 Post-distance shell geometry and the odd-q footprint quotient . . . 266
73.13 Passes 5300–5307: the exact 576 bridge and the post-$q = 9$ frontier . . . 268
73.14 The Hoffman 576 stabilizer, D_4 triality, and the tomotope quotient . . . 270
73.15 Affine Latin colorings, D_4 triality, and the tomotope square-face action . . . 271
73.16 The $q = 5$ K_0 minimum shell: a noncommutative rank-21 orbital algebra . . . 272
73.17 Characteristic-rank complement and the binary kernel target . . . 273
73.18 Local A_5/V_4 fiber and exact induced branching . . . 273
73.19 The $q = 11$ footprint distance closes at 121 . . . 274
73.20 The odd-q footprint matrix is a binary two-periodic complex . . . 275
73.21 The Hoffman extraspecial lift is a real two-qubit Pauli group . . . 275
73.22 Seven spherical shadows of the 2340-word K_0 shell . . . 276
73.23 The $q = 5$ footprint hull is the $NO_5^+(5)$ adjacency code . . . 276
73.24 Canonical two-line pair space and the all-odd Steinberg-square law . . . 276
73.25 All-odd complex Wedderburn theorem for the pair Hecke algebra . . . 277
73.26 Characteristic-two firewall and the q mod 8 Klein clock . . . 278
73.27 Publication-DAG integrity: recursive frontier reachability . . . 279
73.28 The all-odd binary footprint theorem is closed . . . 279
73.29 Rank complement and zero-footprint generation . . . 280
73.30 The footprint image is generated by its complete minimum shell . . . 281
73.31 Binary point-code CSS corollary . . . 281
73.32 The logical module carries the same q mod 8 Weil clock . . . 282
73.33 All-q Levi flag distance scheme and Hodge cycle projector . . . 284
73.34 All-q Levi apartments form the Hodge cycle tight frame . . . 285
73.35 Unsigned apartment visibility: the full flag space before Hodge signing . . . 287
73.36 Canonical apartment tomography and the orientation Hodge filter . . . 292
73.37 Integral unsigned spectrum and exact Gram volume . . . 292
73.38 Characteristic-two radical quotient and the $q = 5$ post-minimum gap . . . 293
73.39 The $q = 3$ provenance decoder reaches eventual radius ten . . . 293
73.40 The apartment tight frame carries an exact basis-volume budget . . . 296
73.41 The two binary footprint kernels live at different stages . . . 296
73.42 The $q = 5$ weight-1040 support is forced into an exotic corner . . . 297
73.43 The $q = 3$ radius-eleven decoder frontier . . . 297
73.44 A negative-Pell square clock for the unsigned Gram determinant . . . 298
73.45 The Reye/tomotope family as a projectivity-graph incidence design . . . 298
73.46 Characteristic-two closure: the projectivity-frame rank is $(q+1)^2/2$ . . . 300
73.47 Projectivity-frame closure: automorphisms, extension fields, codes, and kinematic firewalls . . . 302
73.48 Projectivity fusion, exact distance, and the phase-sensitive dynamical frontier . . . 304
73.49 Heisenberg magnetic bulk, intrinsic vector lift, and finite gauge dynamics . . . 307
73.50 Deck parity, gauge transversality, magnetic composition, and causal boundaries . . . 309
73.51 Carrier-spinorial symmetry, gauge-action obstruction, and finite sheet dressing . . . 310
73.52 The q=5 zero shell reconstructs Reye and opens the natural seven-side to S_{12} . . . 311

73.53Equivariant BdG moduli, fiber locality, and connected voltage refinement 313
73.54Ramanujan refinement, affine orientation, and the vertical eight 315
73.55Passes 5691–5698: finite Yang–Mills candidate, duality, and Ramanujan depth 317

74 Passes 5725–5732: torsion-center pairing, 234-dimensional Jacobi defect, and the finite Heisenberg family bridge 321
74.1 A fixed quadratic code with 234 selectable symplectic W33 overlays 322
74.2 The q=5 Reye and heavy shells share one rank-nine Latin core 324
74.3 The q=5 Latin carrier as an affine $M_2(\mathbb{F}_2)$ left–right geometry 327
74.3.1 Transpose carries point–line Reye incidence to heavy–line disjointness 328
74.4 The $1+9+6$ line-carrier split is matrix-rank Fourier geometry 330
74.5 The common rational W_9 has distinct integral and binary forms 332
74.6 A frozen 51-point partial ovoid of $W(3,9)$ and its local rigidity 344
74.7 A blocker-deficiency reformulation and an involutory symmetry of the $q=9$ 51-set . 345
74.8 C_2 normal form, finite Gram reduction, and a semilinear six-witness configuration . 346
74.9 The C_2 quotient as a PGL_2 involution scheme and the semilinear hexad 347
74.10The Gram big cell, the hexad lifting invariant, and an audited E_8 boundary 349
74.11The E_8 root graph as a hexagonal lift of $W(3,3)$ 352
74.12The $E_8/W(3,3)$ fibre scheme, selected D_4 geometry, and the H_{27} matter cover . . . 354
74.13Double-six sections of the E_8/D_4 spread code recover the doily codes 356
74.14The thirty-six doily sections are a second generating system for C_{spread} 358
74.15The double-six doily system as a spectral design and ternary shadow 358
74.16A q=9 local-section obstruction and blocker-frame fingerprint 359
74.17A $7+10$ logical Hodge split and the curved integral 27–45–36 prism 360
74.18The exact C_2 branch of the $q=9$ partial-ovoid problem 361
74.19Coxeter phase selects a local $3K_4$ chart 361
74.20Corrected E8 local descent: 40 A_2 fibres, Clebsch and Petersen 361
74.21Depth-three reguli as unique E_8 completion addresses 365
74.22The Schlaefli scheme on the twenty-seven completion charts 365
74.23The 1080 obstruction carrier: full Wedderburn decomposition and three explicit Steinberg copies 366
74.24The doubled D_4 prism has nonsplit binary homology 366
74.25Port-gauged holonomy on the twenty-seven E_8 completion charts 367
74.26One 27×45 atlas and the $81\oplus 81\oplus 81$ Steinberg frame 367
74.27E6 odd-triangle and packet/global-$K_{3,3}$ no-go audits 368
74.28Explicit $M_3(\mathbb{Q})$ multiplicity algebra 368
74.29Binary 48: MeatAxe comparison without guessing Ext 368
74.30The two building homologies and their common obstruction router 368
74.30.1 Chain-level materialisation 369
74.31Outer parity, modular gluing, and the ternary logical Steinberg 370
74.32A typed universal microVM above the W33 routing fabric 372
74.33Persistent 40-ary memory and monotone W33 capabilities 373
74.34Validated guest code, reversible history, and heterogeneous execution 374
74.35Capability-backed guests, finite RTL refinement, and typed irreversibility 375
74.36Asynchronous components, typed checkpoints, and proof-carrying execution 376
74.37Revocation, deadlock control, and hardware passport admission 377
74.38Execution identity beyond the guest image: attestation, concurrency, revocation, retention, and magic 378

75 Native attestation, quorum authority, storage-aware placement, and replay receipts **380**
75.1 Raw attestation, BFT authority, nonlocal qutrit embedding, measured placement, and portable audit closure . . . 382
75.2 Sparse symplectic realization, Clifford compilation, TPM activation, BFT stress, and host capture . . . 383
75.3 Multi-minor locality tournament, W33 routing, distance-two decoding, and hardware capture request . . . 385

76 Optical primitive, circuit-noise, logical-quotient, and protected-store closure **386**
76.1 The 66-qutrit store and the K12 correction . . . 387
76.2 Physical admission boundary . . . 387
76.3 A two-punctured Hesse plane is the exact 11-bin gate–route alphabet . . . 388

77 Passes 4137–4144: matrix Wilson pumping, extended horizons, microscopic scale flow, and autonomous history dynamics **388**
77.1 The 200-cover orbital dictionary and Gram reconstruction . . . 390
77.2 The protected shells close into $O^+(8,2)$ and reach the exceptional six-space (Passes 4579–4586) . . . 403

Current protected frontier: finite D_4 triality from the W33 lift **405**
77.3 The two cubic incidence axes fuse to simplex/Hamming and enter Golay through the hexacode (Passes 4592–4615) . . . 407
77.4 The forty-five carrier closes, the sentinel shell becomes self-describing, and outer symmetry glues the exceptional six-space (Passes 4616–4623) . . . 410
77.5 The packet 45 closes onto the E6 carrier, while the 45-by-40 incidence exposes H10 and the hexacode choice space (Passes 4624–4631) . . . 412

78 Passes 4640–4647: explicit triality, Schlaefli carriers, spread sheets, and cover holonomy **415**
78.1 Triality closure, dark sheet modules, and internal Schlaefli reconstruction . . . 417

Current paired-axis frontier: homology, Golay stabilizers, and exact glue **419**

79 Passes 4664–4671: transverse triality symmetries and the integral protected incidence **423**

Affine Golay, Leech neighbor, and support-twelve apartment closure **427**
79.1 Invariant flag cohomology and the dual-shell $GQ(4,2)$ closure . . . 430
79.2 Exact routing-edge character kernels . . . 431
79.3 The S_3 connection reconstructs the selected geometry . . . 431
79.4 Capacity envelope and local Petersen coding . . . 432

Support-twelve involution and square-root cover closure **432**
The 270 involution residues are the complete minimum shell of H10 dual . . . 434
Passes 4737–4744: involution residues reconstruct selected270 . . . 435
Passes 4753–4760: algebra, odd-q distance, dependency cubes, and 24D boundary . . . 441
Passes 4777–4784: matrix units, BLT minima, D4 triality, and triangle router . . . 446

Support-12 minima reconstruct the protected 45 and Golay neighbor relations 448
Passes 4793–4800: BLT, chirality, F4/E6 crosswalk, qutrit triangle code . . . 450
79.5 The apartment-parity trace law for a general GQ(s,t) . . . 452
79.6 Correction: legacy "four-cycle frustration" versus apartment frustration . . . 453
79.7 Apartment parity and the protected binary label space (Passes 4469–4471) . . . 454
79.8 Apartment parity beyond the 10-space: module structure, zeta coefficients, and exact thermal duality . . . 455
79.9 Geometric generators and optimal protected readout (Passes 4480–4483) . . . 458
79.10 The repeated eight-core and the nonsplit apartment extension (Passes 4485–4488) . 459
79.11 Fixed-point obstruction and the cocycle-support code (Passes 4490–4492) . . . 461
79.12 Corrected symmetry-breaking boundary for the nonsplit apartment extension (Passes 4493, 4503–4504) . . . 462
79.13 Distance, extension cohomology, higher graph primes, and prism self-reconstruction (Passes 4495–4502) . . . 463
79.14 Maximal-subgroup obstruction and the corrected flag gauge (Passes 4503–4504) . . . 466
79.15 The full radical carries two obstruction bits (Pass 4505) . . . 466
79.16 The apartment bridge scales from 10 to 70 (Pass 4506) . . . 466
79.17 Three outside-box consequences (Passes 4508–4510) . . . 467
79.18 Dual completion, induced-subgraph enumerators, and higher zeta tomography (Passes 4511–4518) . . . 467
79.19 The splitting flag is the Sylow-3 normalizer/Borel (Pass 4519) . . . 470
79.20 Enumerator frontier, exact $Q(5,3)$ distance, and the orthogonal dual quotient (Passes 4520–4527) . . . 471
79.21 Borel maximality, local compilation, and protected-edge compression (Passes 4528–4535) . . . 473
79.22 The missing protected bit is parity, and the Borel cell already contains full H_{10} (Passes 4536–4543) . . . 476
79.23 The dual-module lattice, cubic transport, and higher zeta tomography (Passes 4544–4551) . . . 479
79.24 Protected parity geometry after the zeta bootstrap (Passes 4552–4559) . . . 482
79.25 Composition closure, executed enumerator mass, and exact cross-carrier boundaries (Passes 4571–4578) . . . 483
79.26 Doily quadratic-evaluation code and intrinsic exceptional S_6 symmetry . . . 486
79.26.1 The code reconstructs all 155 Veldkamp lines . . . 487
79.27 CE2 carrier/provenance correction: the native object is 27×3 . . . 488
79.28 $PG(3,2)$ Hamming-polar bridge . . . 489
79.29 The doily code as a point-derived bent biplane . . . 490
79.30 A full-group no-go for direct Schlaefli–W33 linear transport . . . 491
79.31 CE2 normal-form compression versus a blind derivation . . . 491
79.32 Finite curvature versus a K3 realization . . . 492
79.33 A repo-native 2026 Vogel split-Casimir certificate . . . 492
79.34 The bent biplane as the abstract Kummer configuration . . . 493
79.35 A common $\mathbb{Z}_{12}$ refinement of the CE2 and Kummer gradings of E_8 . . . 494
79.36 Vogel projector channels refined by the Kummer-adjacent order-four grading . . . 495
79.37 An intrinsic double-six decoder and a trace-corrected finite Pauli validator . . . 495
79.38 The corrected Leech interface reaches the common W33 code before selecting a polarity 502
79.39 Selector obstructions, explicit $\mathbf{F}_9$ coordinates, and cyclic phase clocks . . . 510

79.40 Index-protected residue, qutrit–chirality synthetic coordinate, and Koopman period-two boundary . . . 519
79.41 The central C_3 Clifford cover is locally C_9 on three fifths of the order-three directions 521
79.42 The C_9 obstruction is one affine Clifford conjugacy orbit . . . 522
79.43 The nonsplit C_9 species avoids both 36-fibre stabilizer geometries . . . 522
79.44 A 216×540 coherent circuit incidence geometry . . . 523
79.45 Duality turns the sentinel extension into the W33 line-code extension . . . 523
79.46 Integral Smith filtration of the $PG(3,4)$ polarity operator . . . 524
79.47 A seven-sector bicolour algebra on the 216 five-circuits . . . 524
79.48 All-five circuit frontier closure: Clifford restriction, Eisenstein sixes, kernel arithmetic, and rank-76 coherent geometry . . . 525
79.49 Second five circuit closure: Wedderburn blocks, kernel, Smith form, and Eisenstein no-go . . . 527

Current VM frontier: checkpoint placement is geometry, not policy 528

Current magic frontier: symmetric acceptance witnesses have no logical output 530

Runtime audit: retain recoverable state and require useful output 531
79.50 Shared counter archives and exact payload admission . . . 531
79.51 Joint admission of shared guest snapshots . . . 532

HoloVM process kernel: process identity above shared value state 532
79.52 Preemptible authenticated counter microcode . . . 533
79.53 Reye sector control and its symplectic obstruction . . . 536
79.54 Connected Reye registers and exact cross-fibre frames . . . 537
79.55 Routing costs, composite-control limits and frame normalizers . . . 537
79.56 Shared ports, echoed sectors and quartic-preserving frames . . . 537
79.57 Finite control costs and a phase-aware instruction algebra . . . 538
79.58 Coxeter–Todd orientation and an exact finite observer . . . 538
79.59 K12 and genus: an integral pairing with a Jacobian boundary . . . 539
79.60 The E_8 twisted register is the root-fibration quotient . . . 539
79.60.1 The Pauli powers are the two orientations of an A_2 fibre . . . 540
79.61 The A_8 fixed-sector support is the two-qutrit Pauli support . . . 540
79.62 Classification closes the A_8 fixed sector as the two-qutrit Pauli grading . . . 540
79.63 Explicit Pauli normalizer, Cartan system, A_8^3 glue, and the rank–24 six-qutrit bridge 541
79.64 Suzuki–E_6 incidence, instanton support, and quantum-computation frontiers . . . 542
79.65 The local $45 + 120$ split, cubic adjoint holonomy, exotic rank, and the non-Clifford boundary . . . 543
79.66 Sector return, dual covers, protected singlet directions, and the first nonlinear adjoint invariant . . . 545
79.67 The quartic determinant is a mod–3 matroid basis count, and every building apartment has phase one . . . 546
79.68 Affine-return control, vacuum-profile rank, determinant depth, decoder distance, and the quartic dark bridge . . . 547
79.69 The quartic determinant needs a geometry bit: six projective-basis orbits and a minimal two-trit classifier . . . 549

79.70 The Suzuki block stabilizer: symplectic double cover upstairs, inner projective action downstairs . . . 550
79.71 The local cubic carrier sees $PSp(4,3)$ in 2.Suz and the full $W(E_6)$ in 2.Suz:2 . . . 551
79.72 The hidden E_6 binary carrier inside the Suzuki W33 kernel . . . 552
79.73 Weyl involutions reconstruct the 36 double-sixes, the 45 tritangents, and their cross-incidence . . . 553
79.74 The full E_6 involution ladder closes on the cubic 36–45 incidence geometry . . . 555
79.75 The Suzuki outer involution is determinant-reversing on the six-qutrit Heisenberg carrier . . . 556
79.76 Conditional S_3 closure of the doubled determinant-phase sector . . . 557
79.77 Execute-all-five closure: the 270 carrier, doubled determinant phase, and the even-order heterotic branch . . . 557
79.78 Controlled determinant gate and outer-complete coherence . . . 560
79.79 Seventeen-term determinant compiler, photonic outer rail, and the corrected heterotic frontier . . . 561
79.80 Optimal determinant compiler, exact rail intertwiner, and the heterotic extension boundary . . . 562
79.81 External orbifold benchmark, two-invariant magic compiler, and the correct non-Abelian heterotic target . . . 563
79.82 Five-front plus three-physics closure: unique hypercharge, exact S_3 module, and spectral/commutator probes . . . 565
79.83 Entangling qutrit Wilson line, canonical $SU(5)$, and the all-q CZ weld . . . 566
79.84 An exact E8 lift of the oriented-Pauli label action, and the parity firewall . . . 567
79.85 Physical inner holonomies in E_8: Chevalley centralizers, triality, and the mod-three charge law . . . 568
79.86 The 72-slot packet frame is the full qutrit Hamming frame of the CZ_3 entangler . . . 569
79.87 Scope correction: the holonomy pair fixes the SM nonabelian factor, not the full SM group . . . 570
79.88 The physical E8 lift closes only after the local A_8 selector is included . . . 571
79.89 The translated CZ_3 cross bundle has determinant 80 . . . 571
79.90 The holonomy group acts on packet18 from the left and right . . . 572
79.91 Executed genus-six surface and computation models . . . 573
79.92 Harmonic storage, actual singlets, and testable model boundaries . . . 574
79.93 Hypercharge as a W33 duad vector and the five-dimensional neutral center cokernel 574
79.94 Affine-holonomy hull and a quantum-distance obstruction . . . 607
79.95 Pass 10941: triality VM five-front closure . . . 633
79.96 Pass 10942: the dark Strange ray opens a metaplectic universal port . . . 634
79.97 Pass 10943: protected metaplectic supply and a null-direction resource selector . . . 634
79.98 Pass 10944: a cubic universal opcode and the exact 54-dimensional obstruction . . . 635
79.99 Pass 10947: cubic VM lowering and the coloring-phase anomaly . . . 636
79.100 Pass 10948: the clock tetracode is a reciprocal negacyclic hyperbolic pair . . . 636
79.101 Pass 10949: the tick line's Freudenthal system, the quasiconformal cone, and the Lorentzian clock form . . . 637
79.102 Pass 10950: the clock Albert algebra carries so(1,9), a Weyl spinor, and matter parity as a 2π rotation . . . 638
79.103 Pass 10951: four clock ticks are the central spin sign . . . 638
79.104 Pass 10952: the order-eight clock has a complete-positivity grading . . . 638
79.105 Pass 10953: the minimal doubled Pin clock has an exact visibility word . . . 639

79.106 Pass 10954: the regular C_8 clock lives on the oriented A_2^4 cover . . . 639
79.107 Pass 10955: the clock determinant exchanges the two D_4 half-spin sheets . . . 639
79.108 Pass 10956: the Albert Peirce 16 contains the same D_4 half-spin transposition . . . 640
79.109 Pass 10957: a μ_4 determinant phase converts the two S_4 Schur cocycles . . . 640
79.110 Pass 10958: the missing μ_4 clock modes embed exactly in the Albert spinor . . . 641
79.111 Pass 10959: one Albert 16 cannot carry the full clock; $32 = 16 + 16$ is minimal . . . 641
79.112 Pass 10960: the FI term forces a $B - L = \pm 1$ condensate — exhaustive matter-even D-flat closure . . . 641
79.113 Pass 10961: exact Albert $Cl(9)$, doubled $Cl(10)$, and the clock grade obstruction . . . 642
79.114 Pass 10962: the hidden sector does not rescue matter parity . . . 642
79.115 Pass 10963: Clifford-grade stabilizers recover the tetrahedral $S_4 \to S_3$ chain . . . 643
79.116 Pass 10964: one E6-shaped U(1) forces the sneutrino . . . 643
79.117 Pass 10965: baryon triality is structurally impossible . . . 643
79.118 Pass 10967: the FI vacuum regenerates R-parity violation . . . 644
79.119 Pass 10969: harmless R-parity violation versus the Higgs quartic . . . 644
79.120 Pass 10968: plane-rotation R-parity; the flat-or-massive dichotomy . . . 644
79.121 Pass 10974: the established R-rules close the plane-rotation door . . . 644
79.122 Pass 10978: the E6 lattice fixes the admissible R-rule of $\mathbb{Z}_{12}$-I . . . 645
79.123 Pass 10979: the $W(3,3)$ twist on the prime orbifolds $T^6/\mathbb{Z}_3$ and $T^6/\mathbb{Z}_3 \times \mathbb{Z}_3$ . . . 645
79.124 Pass 10980: flavour structure does not hide the regenerated R-parity violation . . . 645
79.125 Pass 11024: the $\mathbb{Z}_3 \times \mathbb{Z}_3$ parity vacua are supersymmetric, and carry massless fractional charges . . . 645
79.126 Pass 11086: "flat-or-massive" is an unbroken R-symmetry, not a law . . . 646

80 Overture: the machine is the geometry is the carrier **647**

81 The substrate **648**
81.1 The two carriers and the operator–operand duality . . . 649
81.2 The five vacua and the Schläfli geography . . . 649
81.3 The parabolic router: address and route are dual . . . 650
81.4 The incidence transceiver and the route-dark lattice . . . 651

82 The carrier: how to self-entangle a photon **654**
82.1 Stage A: spatial (one element) . . . 655
82.2 Stage B: temporal (two Clifford gates) . . . 655

83 The network: atlas, building, and routing **655**
83.1 Hypercube networking, not hypercube decoration . . . 656

84 The middleware: tomotope mirrors and the runtime bus **657**
84.1 Product-grid closure ABI v2 . . . 658
84.2 ABI v2 consumer, E6 claim table v2, and D4/V4 branch audit . . . 659
84.3 BT1486–BT1488 ABI v2 retwined CSS and splice manifest . . . 659
84.4 BT1489–BT1491 row symmetry and Fano–E6 square . . . 659
84.5 BT1492–BT1494 canonical Fano fiber and pulse release lock . . . 660

85 The software: braids, teleported gates, universality **660**
85.1 Exact braid words . . . 660
85.2 The photon is its own gate . . . 660
85.3 Instruction set architecture . . . 660
85.4 The minimal classical shadow . . . 661
85.5 The Universality Theorem . . . 661

86 Fractal scaling: the computer is the network **661**

87 Runtime closure: compile, monitor, commit **662**
87.1 The infinite-cover warning . . . 663
87.2 Cover-indexed storage, rerouting, and guard bands . . . 664

88 The fuel: matter equals magic **665**

89 Memory, protection, and the immune system **667**

90 Time: three clocks and a quasicrystal **671**

91 Synchronization: beacons and schedules **672**

92 Build sheet and falsifiable witnesses **677**

93 Implications, corrections, and the ethos **678**
93.1 Physics . . . 678
93.2 Computing . . . 682
93.3 Networking . . . 683
93.4 The physics-to-architecture dictionary . . . 684
93.5 Beyond the laboratory . . . 685
93.6 The ethos . . . 686

A Verification ledger **687**

B Architecture Completeness and the Three Physical Residuals **689**
B.1 The architecture is the substrate's symplectic continuum . . . 690
B.2 The fault-tolerant layer is the substrate's lattice tower [Face 5] . . . 690
B.3 The universal gate set is degree two plus degree three . . . 691
B.4 The code lattices are the moonshine ladder [Face 5] . . . 692
B.5 What is physically needed: demonstrator versus fault-tolerant machine [Face 6] . . . 692
B.6 The gates are geometric: holonomic Clifford from the gauge connection . . . 693
B.7 The quantum power is the gauge curvature . . . 694
B.8 The fuel is contextuality: the register is a Wigner phase space and magic is its negativity . . . 694
B.9 From the matter-graph lattice to continuum Yang–Mills: the loop closes . . . 695
B.10 Why "holo-net": the network is a holographic code . . . 695
B.11 Rank 24: the finite moonshine/CFT comparison . . . 696
B.12 The falsifiability ledger, and the demonstrator as an experiment on the theory . . . 699
B.13 The geometric origin of the clock: the triangulation ladder $3 \to 4 \to 7$ . . . 700
B.14 The Heawood clock is a finite control layer, not a mass scale . . . 701

B.15 Four further faces of the machine: time, topological order, scrambling, and periodic orbits . . . 702
B.16 A near-term falsification test: the demonstrator as an experiment on the substrate . 703
B.17 BT1402 runtime-frontier handoff: readout, port, and certificate . . . 703
B.18 BT1403 eraser-lift port: the Hesse boundary is the readout boundary . . . 704
B.19 BT1404 holonet scope: one Hesse grid is one microframe . . . 705
B.20 BT1405 continuous Q6 path router . . . 705
B.21 BT1406 tomotope-body edge pulse scheduler . . . 706
B.22 BT1407 microframe transaction composer . . . 706
B.23 BT1408 Witting contextual communication bridge . . . 707
B.24 BT1409 Witting duplex admission scheduler . . . 707
B.25 BT1410 Witting delayed-query frame compiler . . . 708
B.26 BT1411 Witting basis analyzer unitaries . . . 708
B.27 BT1412 toroidal Q4 oscillator boundary . . . 709
B.28 BT1413 Q4 plaquette-tomotope compiler . . . 710
B.29 BT1414 Csaszar-Szilassi dual port . . . 710
B.30 BT1415 even-projection Steinberg/CSS syndrome ledger . . . 711
B.31 BT1416 sparse CSS intertwiner . . . 712
B.32 BT1417 linear-optical dual-port primitive synthesis . . . 712
B.33 BT1418 finite D4-quartic magic injection . . . 713
B.34 BT1697 typed packet ABI . . . 713
B.35 BT1698–BT1700 execution stack . . . 714
B.36 BT1701–BT1703 runtime safety layer . . . 717
B.37 BT1704–BT1706 replay and retry economics . . . 717

C The exceptional skeleton and its physics 718
C.1 The one object and its seven faces . . . 719
C.2 BT1707–BT1709 contextuality and Hesse crossover . . . 721
C.3 The $\{3, 7\}$ Hurwitz tower and the genus-7 crossover . . . 723
C.4 Two Schläfli families, a vertex-figure selection, and the Witting body . . . 724
C.5 The register atlas, the explicit E8 weld, and the Hesse engine . . . 724
C.6 The Eisenstein tower qutrit $\to$ E6 $\to$ E8, the Golay gap, and the quadrangle ladder . 725
C.7 A guardrail on the 27, and the Klein quartic as the E7 rung . . . 726
C.8 The three exceptional rungs made explicit . . . 726
C.9 The magic square, the complex Leech, and the icosian clock . . . 727
C.10 The ceiling, the Suzuki tower, and the G2 thread . . . 727
C.11 The ledger, the Standard Model, and the tower as one figure . . . 728
C.12 The measurable layer: a scorecard and a unification [Faces 2, 3, 7] . . . 728
C.13 Three live tests, scrutinised . . . 729
C.14 Fixing the neutrino, predicting the proton, and the balance sheet . . . 729
C.15 Why $q = 3$, and one triality for the neutrino [Faces 1, 4] . . . 729
C.16 Pass 1 — three closures: the neutrino matrix, the selection census, the threshold number . . . 730
C.17 Pass 2 — sharper: a Majorana invariant, a cyclotomic merge, a code curve . . . 732
C.18 Pass 3 — deeper: a cyclotomic skeleton, a projective Majorana ratio, a decoder correction . . . 734
C.19 Pass 4 — deepest: the cubic form, the Witting degrees, and the measured curve . . 734
C.20 Self-error-correction and why the primitive is one . . . 735

C.21 Why the primitive is one *massless* photon . . . 736
C.22 The single carrier, the geon, and the fractal of nested shells . . . 737
C.23 Pass 5 — the capstone: machine = world, gravity to a number, and a fittable sky template . . . 738
C.24 Pass 6 — sharpening the capstone: a fit, a derived frequency, and a running G . . . 739
C.25 Pass 7 — three edges pressed: a resolution reality, the last identification closed, and an honest hierarchy . . . 740
C.26 Pass 8 — the hierarchy's exponent, a designed closure test, and one clock for the whole sky . . . 741
C.27 Pass 9 — the breakthrough: the complete primordial spectrum, normalisation included 741
C.28 Pass 10 — the scale residue closed to one unit: amplitude as a law, all masses as integers, two exponents as one . . . 742
C.29 Pass 11 — the potential identified (Starobinsky R^2), the entropy derived, the tower audited . . . 743
C.30 Pass 12 — the residue as one number, the scalaron meets the neutrinos, and the tower as one plot . . . 743
C.31 Pass 13 — one particle for inflation and matter, the baryons, and the master ledger 744
C.32 Pass 14 — the tension resolved, three hierarchies reconciled, and dark matter completed 745
C.33 Pass 15 — the dark matter stress-tested, the lightest neutrino, and the mass ladder . 746
C.34 Pass 16 — the lightest neutrino pinned, the $0\nu\beta\beta$ mass, and the descent to dark energy 746
C.35 Pass 17 — the cosmological constant exact, neutrino dark energy, and the final ledger 747
C.36 Pass 18 — a mechanism for the cosmological constant, the joint sky test, and the standalone distillation . . . 749
C.37 Pass 19 — the floor derived from the 600-cell, and the dated decision . . . 749
C.38 Pass 20 — the one residual input, the floor base settled, and the look-elsewhere bound 750
C.39 Pass 21 — the computed look-elsewhere, the pinned Yukawa, and the tower on one axis . . . 751
C.40 Pass 22 — the depth-stable significance, an honest neutrino-mixing failure, and dated discovery years . . . 753
C.41 Pass 23 — the predicted mixing, the derivation ledger, and the separation from SO(10) 754
C.42 Pass 24 — machine = world: the code is the matter algebra, and why 3 . . . 754
C.43 Pass 25 — the protected 27 is one Standard-Model generation, and charge is 1/3 because $q = 3$ . . . 756
C.44 Pass 26 — why the Standard Model is consistent, and the weak angle as a 27-trace . 757
C.45 Pass 27 — the three forces meet at $M_{\rm Pl}e^{-\Phi_6}$ with $\alpha_{\rm GUT}^{-1} = f$, and the proton decays 757
C.46 Pass 28 — the Higgs sector, one structural supersymmetry, and the state of the solution . . . 758
C.47 Pass 29 — gravity is the spectral action, and the continuum gap is two theorems . . 759
C.48 Pass 30 — K3 as a candidate continuum target, with convergence still open . . . 760
C.49 Pass 31 — the convergence mechanism, demonstrated in 4D, and (T2′) narrowed to one input . . . 761
C.50 Pass 32 — cracking the frontier: both theorems collapse to one finite condition . . . 761
C.51 Pass 33 — one discretization link is a theorem; the physical chain remains conditional 762
C.52 Pass 34 — the system: the substrate as a computer and network architecture . . . 763
C.53 Pass 35 — the datapath: the router, the clock, and the reliability budget . . . 764
C.54 Pass 36 — the silicon questions: the ISA enumerated, the power budget, the floorplan 765
C.55 Pass 37 — the boundary questions: complexity class, distributed clock, I/O, and one group . . . 766

C.56 Pass 38 — the advantage measured, the scheduler, and the falsifiable datasheet . . . 768
C.57 Pass 39 — the planetary computer: the universal VM, the everyone-node fractal, and the bench test . . . 768
C.58 Pass 40 — the machine made runnable: the emulator and three frontier applications 769
C.59 Pass 41 — proof of life: the machine corrects, teleports, and reproduces, executed . . 770
C.60 Pass 42 — the benchtop number derived, and the quantum packet delivered 771
C.61 Pass 43 — consensus run against an adversary, the KS inequality, and the holonet CLI 771
C.62 Pass 44 — the experiment simulated, the magic dial turned, the tool installed 772
C.63 Pass 45 — the threshold curve measured, the quickstart, and the unified Machine paper . . . 773
C.64 Pass 46 — the minimal machine, the matched efficiency, the circuit-level threshold, and the scorecard . . . 773
C.65 Pass 47 — the router on a 4-bit CPU, the ternary encoding tax, and the live scorecard 774
C.66 Pass 48 — the assembler, packet energy, and the live router . . . 775
C.67 Pass 49 — exported retro targets and golden traces . . . 775
C.68 Pass 50 — firmware-to-fabric accounting . . . 776
C.69 Pass 51 — the machine audits itself, and the live playground . . . 777
C.70 Pass 52 — the parity law, and the performance face . . . 778
C.71 Pass 53 — parity not primality, a falsifiable prediction, and the table-free win 779
C.72 Pass 54 — the control arm: an explicit even-q ovoid, and the scaling win 780
C.73 Pass 55 — the two-arm discriminator, runnable end to end . . . 780
C.74 Pass 56 — two contextualities, separated; and why one photon in $\mathbb{C}^4$ 781
C.75 Pass 57 — the contextuality tax: the defect is one movable point-star 782
C.76 Pass 58 — the spread side of the tax, and the anatomy of the optima 783
C.77 Pass 59 — the tax orbits: one group moves the defect's ground states 783
C.78 Pass 60 — the perp states: the canonical orbit named, the spectrum explained . . . 784
C.79 Pass 61 — every node carries a qutrit phase space . . . 785
C.80 Pass 62 — the global phase-space bundle and Wigner fuel accounting 786
C.81 Pass 64 — the interrupt controller: the tax arc runs inside the VM 786
C.82 Pass 65 — the kernel fusion: programs, pages, and the walking defect 787
C.83 Pass 66 — kernel dynamics: stationarity, re-keying, and the self-logging fabric 788
C.84 Pass 67 — unifying the tracks: a self-auditing scheduler and an exact gap 789
C.85 Operator-on-photon self-applied circuit packet . . . 790
C.86 Internal optic algebra, physical dictionary, and falsifier regimes . . . 790
C.87 Internal Clifford census, lens calibration, and passive-active protocol 790
C.88 OAM recentering, exact optical calibration, protocol table, and literature bridge . . 790
C.89 Recentered witnesses, leakage regimes, and appendix splicer . . . 791
C.90 Appendix validation, recentered protocol table, and claim ledger . . . 791
C.91 Full operator/OAM appendix splice and recentered transaction ABI 791
C.92 LG radial covariance, full witness lane sheet, and OAM front end . . . 792
C.93 Lab tomography, LG alphabet, and the Hesse/T witness loop . . . 792
C.94 The Witting reject shell as the universal fuel rail . . . 793
C.95 Accepted control rail and the full Witting transaction cycle . . . 794
C.96 Physical automaton, Fano detector bins, and the universal ABI . . . 795
C.97 Fano charge, time-bin envelope, and guard-page closure . . . 796
C.98 Exact Schläfli–W33 transport capsule (Pass 1147) . . . 797

D Modular Hecke degeneration, triality gauge geometry, and cycle selectors 797

E Brauer-tree completion of the five-primary frame extension **798**

F Recovered write-ups **801**
F.1 Fano bus figure and retwined front-end closure . . . 801
F.2 The quartet fibre law . . . 802
F.3 Finite-delay support observability . . . 803

G Passes 3989–3996: physical incidence photon processor **803**

H Passes 3989–3996: physical incidence photon processor **805**
Passes 3989–3996 supplement: direct W33 flight and causal memory . . . 807
H.1 Folded Hashimoto propagation and the protected Hodge endpoint . . . 808
H.2 The E_2 duad–phase carrier and the complexified G_2 boundary . . . 809
H.3 Sentinel admission, two-adic chiral lift, native runtime, and eight-bin photonic compilation . . . 810
H.4 Discriminant automorphisms, native E_6 objects, and the optical admission loop . . . 811

I Errata **813**

Canonical Architecture: Geometry, Prediction, and Evidence

Purpose. This front matter replaces chronological accumulation as the primary reading order. The historical theorem inserts remain below as an auditable evidence ledger, but the machine is now specified through four layers: the finite object, the predictive controller, the optical implementation, and the evidence boundary.

The finite object

The substrate is the symplectic polar space $W(3,3)$. Its 40 isotropic lines, 36 spreads, and 540 unordered skew-line pairs generate the intrinsic flag bundle

$$\mathcal{F} = \{(\{\ell_1, \ell_2\}, S, t)\}, \qquad |\mathcal{F}| = 540 \cdot 3 \cdot 4 = 6480.$$

The projective symplectic group acts transitively. A flag stabilizer is V_4, with fixed-point character $6480, 288, 288, 24$; consequently the permutation rank and commutant dimension are

$$\dim \mathrm{End}_{PSp(4,3)} \mathbb{C}[\mathcal{F}] = 1770.$$

The equality $6480 = 27(81 + 120 + 24 + 15)$ is retained only as a dimensional bridge, not as an unproved representation identification.

The predictive machine

The live controller retains semantic mixed-radix state and performs physical work only when future observables require it. Its route-diagnostic hierarchy is

$$23 \text{ common nonabelian triangles } \longrightarrow \text{ at most two adaptive escalations,}$$

with exact adaptive worst case 25. The best fixed construction currently known uses 28 triangles; the existence of a 27-triangle fixed schedule remains open.

All address transfers require zero, one, or two rank-one symplectic transvections. Permutations, Pauli byproducts, gauge conjugations, route inverses, and covariant terminal phases remain in frame state instead of becoming gratuitous optical gates.

The optical and quantum layer

The A_4 shell is a tetrahedral four-outcome information geometry separated by a hardware type boundary from the nonabelian D_4 route core. Calibration is component-resolved: survival, OAM sorting, slot sorting, and dark counts remain separate sufficient statistics. Chirality, route curvature, and calibration photons are scheduled by one posterior controller rather than three independent clocks.

For the reproduced three-copy M_{36} witness family, 19 projective stabilizer states yield 18 orthogonal pairs. Every pair has common same-sign Pauli rank three, whereas a rank-two six-qubit stabilizer code requires rank five. The accepted projections are magic-bearing rank-two subspaces, not stabilizer codes.

Reversible time and synchronization

The balanced word

$$001032122313$$

has optimal cyclic distance nine and is self-dual under a D_4 slot reflection. Crossing it with the 89/233 Christoffel calendar produces a 2796-tick comb with 1068 calibration events and exactly 89 events in every twelve-phase sector. Its reversal is the single affine involution

$$R(t) = 1952 - t \pmod{2796}.$$

The construction is a logical, typed scheduling symmetry; it is not an autonomous time crystal or an observed optical frequency standard.

Information and thermodynamics

The controller retains the smallest statistic sufficient for the next action and its residual risk. For the explicit finite model, a causal interaction tensor

$$K(a, b) = I(S; Y_a, Y_b) - I(S; Y_a) - I(S; Y_b)$$

separates raw information volume from future consequence. This is an information-geometric ledger. Physical dissipation still requires a temperature, reset protocol, finite-time implementation, and measured device.

Claim ledger

Exact	28-row full-D_4 construction; M36 common-Pauli audit; 6480-flag commutant; tetrahedral channel algebra; self-dual comb census.
Exact model	Finite-horizon joint posterior policy and causal entropic-curvature values for the published synthetic channels and priors.
Bounded	The 27-row search: 259 feasible adversarial MILP schedules and 12,336 accumulated collision cuts without a witness; no infeasibility theorem.
Pending	Full 213,648,435-subspace M_{36} census; full irreducible flag-character decomposition; RTL simulation and placement; laboratory optics; three canonical PDF builds; physical reset energy.

Certified Historical Theorem Ledger

Exact frame-to-signed-turn bridge and current evidence boundary

Let $M \in \mathbb{Z}^{540\times 240}$ be the canonical frame cross-matching matrix: each of the 540 pairs of disjoint isotropic lines contributes its unique stabilizer-invariant four-edge matching. Every edge of $W(3,3)$ occurs in exactly nine rows, and

$$\operatorname{rank}_{\mathbb{Q}} M = 225, \qquad \operatorname{coker} M \cong \mathbb{Z}^{15} \oplus (\mathbb{Z}/2)^{30}.$$

Write N for the unsigned point–edge incidence matrix, ∂ for the oriented incidence matrix, A for the point adjacency matrix, and K for the signed-turn operator on the 240 oriented edge chains. In one common edge ordering the exact identity is

$$K\partial^{\mathsf{T}} = \partial^{\mathsf{T}}(6I - A).$$

Consequently the (-4) point eigenspace is carried to the 10-eigenspace of K. More precisely, with

$$P = (A - 12I)(A - 2I) = 96E_{-4}, \qquad F = \frac{1}{16}\,\partial^{\mathsf{T}} PN,$$

the matrix F is integral and satisfies

$$FM^{\mathsf{T}} = 0, \qquad (K - 10I)F = 0, \qquad \operatorname{rank}_{\mathbb{Q}} F = 15.$$

Thus F induces an explicit equivariant isomorphism

$$\operatorname{coker}(M) \otimes \mathbb{Q} \xrightarrow{\sim} \ker(K - 10I).$$

The earlier dimension-only shortcut failed because it compared the unsigned edge permutation action with the orientation-signed edge action. The natural incidence operator above supplies the missing twist and closes the module question without identifying the two coordinate subspaces literally.

Modulo 2, the bridge has rank 14 and square zero. It yields an intrinsic nilpotent flag

$$\operatorname{im} F \subset \operatorname{im} C \subset \operatorname{im} M^{\mathsf{T}} \subset \ker F, \qquad \dim = (14, 15, 195, 226),$$

where $C = N^{\mathsf{T}} PN/16$. This separates the two abstractly isomorphic 14-dimensional factors: the bridge selects the nontrivial reduction of the rational 15, while the second copy remains in the 31-dimensional torsion-side kernel.

The exact-cover frontier is also larger than the original sample indicated. Certified covers occur with stabilizers

$$C_2, \quad C_4, \quad C_2 \times C_2, \quad D_8, \quad C_4 \times C_2,$$

and sixteen deterministic C_2 orbits together with four further stabilizer types certify at least 226800 distinct covers. In particular, a C_2-stabilized cover fixes twelve selected frames, so cover stabilizers are not universally diagonal.

Evidence boundary. Everything above is an exact theorem about finite matrices, lattices, and group actions. It does not by itself establish a physically complete one-photon computer, an experimental contextual fraction, a measured pump Chern number, Standard-Model descent, particle parameters, spacetime dynamics, or cosmology. Those statements require additional physical assumptions and, where relevant, an operational probability model and experimental protocol. They remain conditional research hypotheses unless separately demonstrated.

Full-Weyl extension and the integral bridge defect

Let M be the 540×240 canonical frame cross-matching matrix, N the unsigned point–edge incidence matrix, d an oriented point–edge incidence matrix, A the adjacency matrix of $W(3,3)$, and K the signed-turn operator on the 240 integral edge chains. The integral map

$$F = \frac{1}{16}\, d^T(A-12I)(A-2I)N$$

annihilates $\mathrm{im}(M^T)$, has rank 15, and lands in $\ker(K-10I)$. In addition to its $\mathrm{PSp}(4,3)$ equivariance, it intertwines an outer symplectic similitude: if U_τ and S_τ denote respectively the unsigned and orientation-signed edge actions of $\tau = \mathrm{diag}(1,1,2,2)$ over $\mathbb{F}_3$, then

$$S_\tau K = K S_\tau, \qquad S_\tau F = F U_\tau.$$

Consequently the rational frame cokernel and $\ker(K-10I)$ are isomorphic as modules for the full group $\mathrm{PGSp}(4,3) \cong W(E_6)$ of order 51840, not only for its $\mathrm{PSp}(4,3)$ subgroup. The common degree-15 character has values

$$15^1,\ 6^{80},\ 3^{1320},\ 2^{2160},\ 1^{7920},\ 0^{25248},\ -1^{13635},\ -2^{1440},\ -5^{36}$$

over the full Weyl group; the displayed outer involution has trace 3.

The rational isomorphism is *not* an integral lattice isomorphism. The nonzero Smith invariants of F are

$$1^{10}, \qquad 3^4, \qquad 6,$$

so $\mathrm{im}\, F$ has index

$$486 = 2\cdot 3^5$$

in its saturation and finite defect $\mathbb{Z}/2 \oplus (\mathbb{Z}/3)^5$. Thus only the primes 2 and 3 obstruct integral equivalence.

The exact-cover frontier also increases. Six further disjoint $\mathrm{PSp}(4,3)$-orbits of canonical 60-frame resolutions contribute 71280 new covers, raising the certified lower bound from 226800 to

$$\boxed{298080}.$$

The exact total and complete orbit census remain open.

Scope firewall. These are exact finite-module, integral-lattice, and finite-orbit statements. They do not by themselves constitute a physical propagator, establish scalable single-photon universality, or derive an experimental contextual fraction, Chern response, Standard-Model parameter, or cosmological observable.

The frame cross-matching and the (-4)-eigenspace

Call a *frame* an unordered pair $\{L, L'\}$ of disjoint totally isotropic lines of $W(3,3)$; there are 540 of them, and the stabiliser of a frame in $\mathrm{PSp}(4,3)$ is $C_2 \times S_4 \cong O_h$ of order 48.

Lemma 0.1 (Faithful tetrahedral action)**.** *Let H be the stabiliser of a frame $\{L, L'\}$ and $A_4 = H'$ its derived subgroup. Then A_4 acts faithfully, as the natural degree-four alternating group, on the four points of L and on the four points of L', with orbits $[4,4]$ on the eight points of the frame.*

Proposition 0.2 (Canonical cross-matching)**.** *For every frame there is exactly one A_4-equivariant bijection $L \to L'$, and it is invariant under the full stabiliser H, not merely under A_4.*

Proof. A faithful action on both four-element sets embeds A_4 into $\mathrm{Sym}(L) \times \mathrm{Sym}(L')$ with both projections onto, so its image is the graph of an isomorphism and an equivariant bijection exists. Uniqueness is general: on a transitive A-set an equivariant bijection is determined by the image of one point, since $f(a \cdot x_0) = a \cdot f(x_0)$ for all a. Invariance under H then follows because H permutes the set of A_4-equivariant bijections, which is a singleton. Exhaustive verification over all 540 frames is recorded in the certificate. □

Write $\mu(\{L, L'\}) \subseteq E$ for the resulting set of four *cross-pairs*.

Theorem 0.3 (The matching lands on edges, 9 to 1)**.** *Every cross-pair is an edge of $W(3,3)$; the 540 matchings use exactly the 240 edges, each edge lying in exactly nine of them; and μ is injective.*

Proof. The 240 cross-pairs form a single Aut-orbit with point stabiliser of order $108 = C_3 \times S_3 \times S_3$, and $|\mathrm{PSp}(4,3)|/240 = 108$; uniformity of the multiplicity follows, and $540 \cdot 4/240 = 9$. Injectivity holds because the endpoints of the four cross-pairs are exactly $L \cup L'$ and each line is a maximal clique of the collinearity graph, so the eight points recover the frame. That every cross-pair is collinear is not forced by the construction — L and L' are disjoint — and is verified. □

Let $M \colon \mathbb{Z}^{540} \to \mathbb{Z}^{240}$ send a frame to the sum of its four cross-pairs.

Theorem 0.4 (Cokernel)**.** $\operatorname{rank} M = 225$*, the invariant factors are $1^{195}, 2^{30}$, and*

$$\operatorname{coker}(M) \;\cong\; \mathbb{Z}^{15} \oplus (\mathbb{Z}/2)^{30}.$$

Moreover $\operatorname{coker}(M) \otimes \mathbb{Q}$ *is* irreducible *of degree* 15*, and it is the same constituent that occurs in the* 40*-point permutation module. Equivalently,*

$$\operatorname{coker}(M) \otimes \mathbb{Q} \;\cong\; \ker(A + 4I),$$

the (-4)-eigenspace of the adjacency operator.

The last identification is the point. The 40-point module splits as $1 + 15 + 24$, matching the eigenvalue multiplicities of $12, -4, 2$; among those three blocks it is the (-4)-block alone that the frame geometry reproduces, and it does so through an explicitly named equivariant map rather than through an equality of dimensions.

Remark 0.5 (What is *not* claimed)**.** *Theorem 0.4 is rational. Integrally the situation differs:* 2 *is the only bad prime (*$\operatorname{rank}_{\mathbb{F}_2} M = 195$ *while* $\operatorname{rank}_{\mathbb{F}_3} M = \operatorname{rank}_{\mathbb{F}_5} M = 225$*), and the mod-*2 *quotient is* not *irreducible — its composition factors have dimensions* $1, 1, 1, 6, 8, 14, 14$*. So the degree-*15 *rational constituent reduces to* $1 + 14$ *modulo* 2*, and the torsion contributes* $1, 1, 6, 8, 14$*; the two degree-*14 *factors are isomorphic, so the torsion carries a second copy of the reduction rather than an unrelated module. This is consistent with the coalescence theorem:* $\mathrm{spec}(A) = \{12, 2, -4\}$ *collapses completely modulo* 2*, while modulo* 3 *and* 5 *it does not.*

The corresponding statement for the signed-turn operator is a theorem*, established in Passes 1416–1420 and not here. With N the unsigned point–edge incidence and ∂ the oriented one,*

$$F = \tfrac{1}{16}\, \partial^{\mathsf{T}} (A - 12I)(A - 2I) N$$

is integral and satisfies $FM^{\mathsf{T}} = 0$, $(K - 10I)F = 0$ and $\operatorname{rank}_{\mathbb{Q}} F = 15$, so it induces an equivariant isomorphism $\operatorname{coker}(M) \otimes \mathbb{Q} \cong \ker(K - 10I)$*. A dimension-only argument does* not *suffice, and the*

reason is worth recording: the 240*-edge* permutation *module contains two non-isomorphic degree-*15 *constituents, but* K *acts on the orientation-*signed *edge action, so* $\ker(K - 10I)$ *is not a submodule of that permutation module at all. The intertwiner supplies the missing twist. Modulo* 2 *the same map has rank* 14 *and square zero, and it separates the two abstractly isomorphic degree-*14 *factors: it selects the nontrivial reduction of the rational* 15*, while the second copy remains in the torsion-side kernel.*

The Hodge decomposition of the edge module, and what it does not contain

The clique complex of $W(3,3)$ is three-dimensional: every totally isotropic line is a 4-clique, hence a tetrahedron, giving $(C_0, C_1, C_2, C_3) = (40, 240, 160, 40)$ with $\chi = -80$ and Betti numbers $(b_0, b_1, b_2, b_3) = (1, 81, 0, 0)$ — the complex is homotopy equivalent to a bouquet of 81 circles.

Theorem 0.6 (Hodge blocks of the signed edge module)**.** *Under the orientation-signed action of* Aut *on the* 240 *edge* 1*-chains, the Hodge decomposition is multiplicity-free and splits into six irreducibles:*

$$\underbrace{15 \oplus 24}_{\textit{exact, } 39} \oplus \underbrace{81}_{\textit{harmonic}} \oplus \underbrace{30 \oplus 45 \oplus 45}_{\textit{coexact, } 120} = 240.$$

The harmonic block is irreducible *of degree* 81 *and is the Steinberg module. The exact block* $15 \oplus 24$ *is precisely the* 40*-point permutation module modulo its trivial constituent, i.e. the* (-4)*- and* $(+2)$*-eigenspaces of* A*.*

In gauge-theoretic language this is the pure-gauge / physical / constraint split, with the Gauss-law count $39 = 40 - 1$ realised representation-theoretically and a physical sector that is a single irreducible.

Proposition 0.7 (The blocks behave oppositely under the outer automorphism)**.** $\mathrm{PSp}(4,3)$ *has index two in* $\mathrm{PGSp}(4,3) \cong W(E_6)$*. Under that extension:*

$15,\ 24,\ 81 \longmapsto$ *two extensions each (a sign character),* $\qquad 45 \oplus 45 \longmapsto$ *a single irreducible of degree* 90*.*

Concretely, $\mathrm{PGSp}(4,3)$ *has four degree-*15*, two degree-*24 *and two degree-*81 *irreducibles, and* no *degree-*45 *irreducible but one of degree* 90*.*

So the gauge and physical blocks are *split* by the outer element — each constituent survives and acquires a sign — while the two halves of the constraint block are *exchanged* by it. The chirality of the constraint sector is of a different kind from that of the physical sector, not merely of a different magnitude. Over $\mathrm{PGSp}(4,3)$ the module reads

$$\underbrace{15 \oplus 24}_{39} \oplus \underbrace{81}_{81} \oplus \underbrace{30 \oplus 90}_{120},$$

five irreducibles rather than six, the fusion $45 \oplus 45 \to 90$ being the only change; the harmonic block carries one definite extension of the Steinberg.

Proposition 0.8 (The sign is read by frames and spreads)**.** *The two degree-*81 *extensions agree on* $\mathrm{PSp}(4,3)$ *and differ on exactly six outer classes. Two of those are involution classes, and both are geometric:*

class	*size*	*object*	*separation*
involutions	540	*frames*	$\chi = \mp 3$
involutions	36	*spreads*	$\chi = \mp 9$ (*maximal*)

*The size-*36 *class has centraliser of order* $1440 = |\mathrm{PGSp}(4,3)|/36$*, fixes no point and exactly ten lines, and a spread of* $W(3,3)$ *is precisely ten pairwise disjoint lines covering all forty points.*

The physical sector's chirality is therefore detected by two of the substrate's own combinatorial families, most strongly by the spreads — not by an auxiliary construction.

Remark 0.9 (No Hodge star, and where one must come from)**.** *A Hodge star requires $C_k \cong C_{3-k}$. Here $C_0 = C_3 = 40$ but $C_1 = 240 \neq 160 = C_2$, the discrepancy being exactly $|\chi|$; and on the physical sector $\star$ would map $H^1 \to H^2$ with $b_2 = 0$. So the* 81 *physical modes admit no dual, there is no $F \wedge \star F$, and no variational dynamics can be written on this complex. The finite geometry supplies the* kinematics *and withholds the* dynamics*.*

In an almost-commutative geometry $M^4 \times F$ the volume form, the star and the variational principle belong to the continuum factor; the finite factor contributes an algebra and a module. That division is now explicit: the finite side supplies $\langle I, A, J\rangle$ and the Steinberg module of Theorem 0.6, and the star must be supplied by M^4. The absence is established by computation ($b_2 = 0$), not by omission, and cannot be repaired internally.

Proposition 0.10 (Resolutions of the edge set)**.** *There exist sets of* 60 *frames whose cross-matchings partition E. No cover is* Aut*-invariant, since* Aut *is transitive on the* 540 *frames and a cover uses* 60*. Cover stabilisers have order* 2*,* 4 *or* 8 *(types C_2, C_4, $C_2 \times C_2$, $C_4 \times C_2$, D_8), so a cover is close to rigid — but the residual symmetry is* not *uniformly diagonal: a C_2-stabilised cover fixes twelve of its sixty frames (orbit profile $1^{12}2^{24}$), whereas the C_4 covers fix none. A compiled census (Pass 1505) exhibits* 327 *pairwise disjoint complete* $\mathrm{PSp}(4,3)$*-orbits, certifying at least*

$$228 \cdot 12960 + 75 \cdot 6480 + 9 \cdot 6480 + 9 \cdot 3240 + 6 \cdot 3240 = 3\,547\,800$$

covers; this is a lower bound and no exhaustive count is claimed. Note that the orbit census is heavily C_2-weighted — about 83% *of covers lie in C_2 orbits — so a small sample drawn by a depth-first search, however its branch order is permuted, is* not *a uniform sample and its observed proportions estimate nothing.*

Exact-cover census, prime-local bridge arithmetic, and an M_{20} qutrit chart

A compiled exact-cover search enumerated the first 100000 covers containing a fixed canonical frame and reduced them under the full $\mathrm{PSp}(4,3)$ action. The prefix meets 327 complete, pairwise distinct cover orbits whose sizes sum to

$$3547800.$$

The stabilizer-type counts in this certified frontier are

$$C_2 : 228, \qquad C_4 : 75, \qquad C_2^2 : 9, \qquad D_8 : 9, \qquad C_4 \times C_2 : 6.$$

This number is a lower bound: the deterministic search prefix is exact, but the complete cover census remains open.

Retain the integral matrices

$$C = \frac{1}{16} N^{\mathsf{T}} P N, \qquad F = \frac{1}{16} \partial^{\mathsf{T}} P N, \qquad Q = \frac{1}{8}(K + 6I)(K - 2I)(K - 4I).$$

Their nonzero Smith invariants are

$$\mathrm{SNF}(C) = 1^{10}3^5, \qquad \mathrm{SNF}(F) = 1^{10}3^4 6, \qquad \mathrm{SNF}(Q) = 1^{10}3^4 12.$$

Moreover

$$C^2 = 48C, \quad Q^2 = 96Q, \quad F^{\mathsf{T}}F = 96C, \quad FF^{\mathsf{T}} = 48Q.$$

Thus, over $\mathbb{Q}$, the elements

$$e = C/48, \quad q = Q/96, \quad x = F/48, \quad y = F^{\mathsf{T}}/96$$

satisfy $xy = q$ and $yx = e$. The unsigned and signed 15-dimensional corners are therefore equivalent idempotents, giving an explicit Morita context. The only bad primes are 2 and 3: modulo 2 the orientation-twisted channel drops from rank 15 to 14, while modulo 3 all three lattices have rank 10.

The algebra generated by

$$M^{\mathsf{T}}M,\ K,\ N^{\mathsf{T}}N,\ \partial^{\mathsf{T}}\partial,\ C,\ F,\ F^{\mathsf{T}},\ Q$$

has dimension at least 301 over $\mathbb{Q}$, certified by 301 words that remain independent modulo 1009. This is not yet a complete Wedderburn decomposition.

Finally, a deterministic exact cover contains five pairwise edge-disjoint 16-edge packets, each having exactly three four-frame resolutions. Independent resolution choices give a literal Hamming chart

$$H(5,3) \cong \{0,1,2\}^5$$

of 243 exact covers, with shells

$$1,\ 10,\ 40,\ 80,\ 80,\ 32.$$

Its setwise stabilizer inside $\mathrm{PSp}(4,3)$ has elementary abelian kernel 2^4 on the five coordinates, image A_5, and an explicit A_5 complement. Hence

$$\mathrm{Stab}(H(5,3)) \cong 2^4{:}A_5 = M_{20},$$

the Mathieu group of order 960.

Operational contextuality boundary. The ratio 4/40 is a finite incidence deficit, not by itself a contextual fraction. The latter is defined from a complete empirical probability model and a linear program. The accompanying falsifier therefore requires raw context–outcome data, normalization, no-disturbance checks, source and detector models, loss and postselection rules, and the implemented measurement phases. No contextual fraction is promoted until those inputs exist.

Bidirectional exact-cover saturation

A second deterministic exact-cover search was performed by reversing the candidate-frame order at every depth of the Pass-1505 search. The forward and reverse prefixes each contain 100000 covers through the fixed canonical frame, and they are disjoint as raw solution sets. Exact orbit traversal nevertheless shows that each prefix meets the identical 327 complete $\mathrm{PSp}(4,3)$-orbits. Their common certified cover lower bound remains

$$3547800,$$

with stabilizer-order census

$$2^{228}, \qquad 4^{84}, \qquad 8^{15}.$$

Canonical orbit representatives agree objectwise, not merely numerically.

The two DFS orders are not uniform samplers. If f_i and r_i denote their hits in the ith orbit, only seven of 327 hit counts agree, while

$$\sum_i |f_i - r_i| = 10244, \qquad \sum_i (f_i - r_i)^2 = 463520.$$

Their Pearson correlation is 0.9280509607335599. Thus deterministic DFS is valid for exhibited-orbit lower bounds but not for frequency inference. Agreement of the two prefixes is a saturation certificate for the observed frontier, not a proof that the global exact-cover orbit census is complete.

Disjoint exact covers and a residual integrality gap

The deterministic cover prefixes used above fix one frame before recursion. Consequently every sampled cover contains that frame, so pairwise intersection inside those prefixes is forced by the symmetry break and cannot establish that the global exact-cover family is intersecting. Direct exact search gives two 60-frame covers with empty intersection, each covering all 240 edge columns exactly once.

Fix one canonical cover. Acting on the frozen 327 cover-orbit representatives by $\mathrm{PSp}(4,3)$ produces 13648 distinct covers disjoint from it, and every frozen orbit type contributes. Their disjointness graph has

$$|V| = 13648, \qquad |E| = 188338, \qquad \#K_3 = 494, \qquad \#K_4 = 0.$$

Thus its clique number is three, and adjoining the fixed cover yields an explicit four-cover packing inside the certified frontier.

The involution classes in $\mathrm{PSp}(4,3)$ have sizes 45 and 270. All 228 frozen cover orbits with stabilizer C_2 use the class-45 involution; it fixes 84 of the 540 frames globally and exactly 12 frames of the stabilized cover.

Removing the selected four covers leaves a 300×240 incidence system that is 4-uniform by rows and 5-regular by columns. Hence the constant weight $x_r = 1/5$ is a fractional exact cover of total weight 60. Nevertheless, exhaustive Algorithm X proves that the residual system has no integral exact cover. The selected four-packing therefore admits a fractional fifth layer but no integral fifth layer.

Boundary. The no-fifth-layer result applies to the displayed four-packing. The clique calculation is exhaustive inside the frozen 327-orbit frontier. Neither claim settles the global packing number over as-yet undiscovered cover orbits or over all possible four-packings.

The frame-resolution problem is a Hoffman-colouring problem

Let $M \in \{0,1\}^{540\times 240}$ be the canonical frame–edge incidence matrix: each row is the four-edge cross-matching carried by a pair of disjoint isotropic lines, and each W33 edge occurs in nine rows. Let H be the graph on the 540 frames, adjacent when their matchings share an edge. Direct construction from $W(3,3)$ gives

$$H + 4I_{540} = MM^{\mathsf{T}}, \qquad \deg(H) = 32,$$

and the exact spectrum

$$\mathrm{spec}(H) = 32^1 \oplus 14^{44} \oplus 8^{15} \oplus 4^{81} \oplus 2^{84} \oplus (-4)^{315}.$$

Hence Hoffman's bounds give

$$\chi(H) \geq 9, \qquad \alpha(H) \leq 60.$$

A 60-vertex independent set is exactly an exact cover of the 240 W33 edges by 60 frame matchings, and every exact cover attains equality. Thus

$$\boxed{\text{nine-cover resolution} \iff \text{Hoffman 9-colouring of } H.}$$

Every exact-cover indicator x satisfies

$$Hx = 4(\mathbf{1} - x),$$

so each outside frame meets the cover in exactly four neighbours. If $X = [x_1|\cdots|x_9]$ is a resolution, then its forced quotient matrix is

$$HX = X\,4(J_9 - I_9).$$

The centred vectors $y_i = x_i - \mathbf{1}/9$ lie in $\ker(M^{\mathsf{T}}) = E_{-4}(H)$ and obey

$$\langle y_i, y_i\rangle = \frac{160}{3}, \qquad \langle y_i, y_j\rangle = -\frac{20}{3} \quad (i \neq j),$$

so a resolution is a regular 8-simplex of binary affine-fibre points in the 315-dimensional (-4)-eigenspace.

Boundary. The theorem does not assert that $\chi(H) = 9$. It converts the still-open global resolution question into the equality case of the Hoffman bound, with a forced equitable quotient and simplex certificate.

Frame resolution, obstruction modules, and the harmonic bridge

Exact decision instance. The nine-cover resolution is exactly a 9-colouring of the 540-vertex frame graph. After fixing the colours on one edge K_9, the deterministic DIMACS instance has 4860 variables and 99909 clauses. No satisfying assignment or infeasibility certificate is presently known, so $\chi(H) = 9$ remains open.

The obstruction module. The independently rebuilt orbital commutants give the stable $\mathrm{PSp}(4,3)$ profile

$$E_{-4}(H) \sim 64 \oplus 81 \oplus 20 \oplus 60^{\oplus 2} \oplus 15^{\oplus 2}_{\mathrm{other}}.$$

For the full $\mathrm{PGSp}(4,3)$ action, the two 15-blocks separate into the two outer extensions while the 60-block remains multiplicity two. This is recorded as a commutant fingerprint pending a literal character-table inner-product certificate.

The four-packing fiber. For the certified pairwise-disjoint covers $x_1, \ldots, x_4$, put $y_i = x_i - \frac{1}{9}\mathbf{1}$. Then

$$\langle y_i, y_i\rangle = \frac{160}{3}, \qquad \langle y_i, y_j\rangle = -\frac{20}{3} \quad (i \neq j).$$

Any fifth layer has forced projection

$$y_{\mathrm{frac}} = -\frac{1}{5}\sum_{i=1}^{4} y_i, \qquad \|y_{\mathrm{frac}}\|^2 = \frac{16}{3},$$

which is exactly the residual uniform weight $1/5$. Its integral correction would have to lie on an orthogonal shell of squared norm 48; the frozen exact-cover trace proves that shell empty for this four-packing.

Integral harmonic bridge. Let

$$P_4 = (H - 32I)(H - 14I)(H - 8I)(H - 2I)(H + 4I).$$

An integral Reynolds map $T : \mathbb{Z}^{540} \to \mathbb{Z}^{240}$ gives $B = TP_4$ with

$$\operatorname{rank} B = 81, \qquad d_1 B = 0, \qquad d_2^{\mathsf{T}} B = 0, \qquad BH = 4B,$$

and B intertwines the four generators of $\mathrm{PSp}(4, 3)$. Hence

$$\boxed{E_{+4}(H) \cong \ker d_1 \cap \ker d_2^{\mathsf{T}}},$$

identifying the frame $+4$ eigenspace with the harmonic Steinberg sector by a literal integer map. This is a finite-module statement and does not supply a Hodge star or continuum dynamics.

Pass 1536: the frame dual is the intrinsic $K_{4,4}$ code

Let $M \in \{0, 1\}^{540\times 240}$ be the canonical incidence matrix whose rows are the four-edge matchings attached to disjoint W33 line pairs. Over $\mathbb{F}_2$, the exact frame code and dual code are

$$\operatorname{row}(M) = [240, 195, 4]_2, \qquad \ker(M) = [240, 45, 16]_2.$$

The dual has a canonical geometric parity-check basis. W33 contains exactly 45 induced $K_{4,4}$ octets. If $K \in \{0, 1\}^{45\times 240}$ records their edge supports, then

$$MK^{\mathsf{T}} = 0 \pmod 2, \qquad \operatorname{rank}_2 K = 45, \qquad \operatorname{row}_{\mathbb{F}_2}(K) = \ker_{\mathbb{F}_2}(M).$$

An exhaustive exact parity optimization proves that the minimum dual weight is 16 and that the 45 rows of K are exactly all minimum words. Thus the minimum words themselves form a basis of the complete modular frame cokernel. The parity-check realization is $(3, 16)$-regular with Tanner girth six. Its minimum-word overlap and disjointness graphs are respectively $\mathrm{SRG}(45, 32, 22, 24)$ and $\mathrm{SRG}(45, 12, 3, 3)$, while

$$\operatorname{spec}(KK^{\mathsf{T}}) = 48^1 \oplus 12^{20} \oplus 18^{24}, \qquad \operatorname{rank}_2(KK^{\mathsf{T}}) = 14, \qquad \operatorname{rank}_3(KK^{\mathsf{T}}) = 15.$$

BT766 owns the intrinsic octet census and overlap geometry; Pass 1416 owns the binary frame rank. The new result is their exact code-theoretic identification, including the exhaustive minimum-word theorem. This is a finite binary-code statement, not a decoding-threshold or physical-noise claim.

0.1 Integral frame cokernel and the $15 \to 45 \to 30$ Bockstein chain

Let $M \in \{0, 1\}^{540\times 240}$ be the canonical frame–edge incidence matrix. Exact 2-adic elimination, together with a literal 225×225 minor of determinant 2^{30}, gives

$$\mathrm{SNF}(M^{\mathsf{T}}) = 1^{195} \oplus 2^{30} \oplus 0^{15}.$$

Hence

$$\operatorname{coker}(M^{\mathsf{T}}) \cong \mathbb{Z}^{15} \oplus (\mathbb{Z}/2\mathbb{Z})^{30}.$$

The forty-five intrinsic induced $K_{4,4}$ octets form a basis of $\ker_{\mathbb{F}_2} M$. If K is their 45×240 edge-incidence matrix, then the integral half-incidence matrix

$$J = \frac{1}{2} MK^{\mathsf{T}} \in \{0, 1\}^{540\times 45}$$

is well defined. It has row degree 6, column degree 72, and

$$J^{\mathsf{T}}J = 66I + 3A_{45} + 6\mathbf{J},$$

where A_{45} is the octet-overlap graph $\mathrm{SRG}(45, 32, 22, 24)$. Thus

$$\mathrm{spec}(J^{\mathsf{T}}J) = 432^{1} \oplus 72^{24} \oplus 54^{20}.$$

The associated Bockstein sequence is

$$0 \longrightarrow \ker_{\mathbb{Z}} M/2\ker_{\mathbb{Z}} M \longrightarrow \ker_{\mathbb{F}_2} M \xrightarrow{\beta} \mathrm{Tor}_2(\mathrm{coker}\, M) \longrightarrow 0, \qquad \beta(y) = \frac{M\widetilde{y}}{2} \bmod \mathrm{im}\, M.$$

Its dimensions are exactly

$$15 \longrightarrow 45 \longrightarrow 30.$$

For the integral rational-cokernel projector C and the oriented bridge F from the signed-turn construction, the nonzero Smith forms refine to

$$\mathrm{SNF}(C) = 1^{10} \oplus 3^{5}, \qquad \mathrm{SNF}(F) = 1^{10} \oplus 3^{4} \oplus 6.$$

Consequently the old 31-dimensional ambient mod-2 bridge kernel splits arithmetically as $30 + 1$: thirty dimensions are genuine elementary cokernel torsion, while the final dimension is the parity defect of the single even invariant factor in the embedded bridge lattice.

This is an exact finite lattice theorem. The torsion modes may be used as certified XOR preprocessing, but they do not by themselves decide the open global nine-cover resolution.

Exact frame-dual continuation: modular lifts, parity cuts, and decoding

Let $M \in \{0,1\}^{540\times 240}$ be the canonical frame–edge matrix and $K \in \{0,1\}^{45\times 240}$ the intrinsic $K_{4,4}$ octet matrix. The exact continuation of the frame-dual theorem gives

$$\mathrm{SNF}(K) = \mathrm{diag}(1^{44}, 3), \qquad \mathrm{sat}(\mathrm{row}_{\mathbb{Z}} K)/\mathrm{row}_{\mathbb{Z}} K \cong \mathbb{Z}/3.$$

The saturation is obtained by adjoining the all-ones edge vector, since the sum of the forty-five octet rows is three times that vector.

Writing $G_K = KK^{\mathsf{T}}$, one has

$$\mathrm{rank}_2\, G_K = 14, \qquad \mathrm{rank}_3\, G_K = 15, \qquad G_K^2 = 0 \pmod 2, \pmod 3.$$

The characteristic-two image is an absolutely irreducible 14 and maps literally onto the Pass-1416 signed-turn image. In characteristic three the rank-15 image is not irreducible: it splits canonically as $\mathbf{1} \oplus V_{14}$.

The signed bipartition incidence of the octets yields an integral map $V = 4U + Sd$ satisfying

$$dV^{\mathsf{T}} = 0, \qquad L_1 V^{\mathsf{T}} = 4V^{\mathsf{T}}, \qquad \mathrm{rank}_{\mathbb{Q}}\, V = 30.$$

Thus the natural oriented $K_{4,4}$ lift realizes the coexact irreducible 30, not either of the two degree-45 constituents fused into the full-Weyl 90.

For the unresolved nine-cover problem, every octet and every color obey the exact cardinality law

$$\sum_{f:\,|f\cap o|=2} x_{fc} = 8.$$

The 405 equations are rational combinations of the edge equations, but modulo two they add 240 independent global XOR directions: the parity rank rises from 2100 to 2340 (and from 2109 to 2349 after the standard K_9 symmetry fixing). This strengthens propagation without deciding existence.

For a subset X of octets, codeword weight is

$$w(X) = 16|X| - 2e(X) + 4t(X),$$

where $e(X)$ counts induced edges in the 45-point overlap graph and $t(X)$ counts distinguished edge-signature triples. Ordinary and distinguished triangles have the same $|X| = 3$ and $e(X) = 3$ but weights 42 and 46, so the ordinary strongly regular association algebra alone cannot determine the full weight enumerator.

Finally, the parity-check matrix K gives exact finite decoding data: every single-edge error has a unique syndrome; among all $\binom{240}{2}$ double errors, 25440 are uniquely identifiable and 3240 are ambiguity-declared. The conditional unique fraction is 212/239. The 540 first weight-four dependencies are exactly the canonical frame matchings. Seeded min-sum trials are retained only as a falsifier of naive threshold claims.

Boundary. These are finite module, lattice, parity, partial-enumerator, and decoder results. The global Hoffman 9-coloring and complete 2^{45} weight census remain open; no physical or quantum-code threshold is asserted.

0.2 Integral-frame five-continuation theorem

Let M be the 540×240 frame–edge incidence matrix and let K be the 45×240 incidence matrix of the intrinsic induced $K_{4,4}$ octets. The 30-dimensional Bockstein torsion module has a nonsplit composition series with factors

$$1,\ 6,\ 8,\ 1,\ 14,$$

where the head 14 and the factor 6 are absolutely irreducible over $\mathbb{F}_2$, while the irreducible factor 8 has endomorphism field $\mathbb{F}_4$.

The octet exact-cardinality relations yield 240 independent global XOR strengthenings of the nine-colour frame-resolution system:

$$\mathrm{rank}_2 : 2100 \longrightarrow 2340.$$

The certified four-cover packing and its anti-symplectic mirror form two free $PSp(4,3)$ orbits of size 25920, fused into one $PGSp(4,3)$ orbit of size 51840; their binary Bockstein signatures coincide.

For the free rank-15 lattice, the saturated unsigned-to-oriented transition has

$$\mathrm{SNF} = 1^{14} \oplus 2, \qquad |\det| = 2.$$

Finally, the joint action on 540 frames and 45 octets is a two-fibre coherent configuration of rank

$$32 + 3 + 5 + 5 = 45.$$

For the half-incidence cross orbital J,

$$(H - 32I)(H - 14I)(H - 2I)J = 0, \qquad \mathrm{rank}[J, HJ] = 69.$$

These are exact finite-module and lattice statements. They do not decide the existence of a global nine-cover resolution.

Exact Brauer, XOR, orbit-transfer, decoder, and outer-extension continuation

Let $M \in \{0,1\}^{540\times 240}$ be the canonical frame–edge incidence matrix and let $K \in \{0,1\}^{45\times 240}$ be the incidence matrix of the intrinsic induced $K_{4,4}$ octets. The following statements are rebuilt from projective coordinates by the Passes 1801–1805 verifier.

Brauer refinement of the Bockstein module. The Bockstein quotient has dimension 30 over $\mathbb{F}_2$, and

$$\ker \beta = \langle \mathbf{1}_{45} \rangle \oplus \operatorname{im}(KK^{\mathsf{T}} \bmod 2), \qquad \dim \ker \beta = 15.$$

A compatible invariant filtration has dimensions

$$1 < 9 < 10 < 16 < 30$$

and successive factors

$$1, \quad 8_{\mathbb{F}_2}, \quad 1, \quad 6, \quad 14.$$

The generated algebras of the 6- and 14-factors are respectively $M_6(\mathbb{F}_2)$ and $M_{14}(\mathbb{F}_2)$. The 8-factor has endomorphism field $\mathbb{F}_4$: a non-scalar endomorphism z satisfies $z^2+z+I=0$. Over an algebraic closure it is the unordered pair of four-dimensional Brauer factors $\{4a, 4b\}$, and the canonical outer similitude acts by

$$szs^{-1} = z^2,$$

therefore exchanging $4a$ and $4b$. The factor labels use the published characteristic-two decomposition matrix of $U_4(2)$; no uncomputed Brauer character values are asserted.

XOR-native resolution attack. For every octet o and color c, a resolution must satisfy

$$\sum_{f : J_{fo}=1} x_{fc} = 8, \qquad J = \frac{1}{2} M K^{\mathsf{T}}.$$

The exact binary ranks are

$$2100 \longrightarrow 2340, \qquad 2109 \longrightarrow 2349$$

after adding the octet equations, before and after the standard symmetry fixing respectively. Thus the cuts add exactly 240 global XOR directions. A separate reproducible HiGHS model contains 4860 binary variables, 3105 equality constraints, and all 405 exact-eight equations. Its frozen 20-second run ended without an incumbent; this is a bounded computational falsifier and is not a SAT or UNSAT certificate.

Three-body orbit-transfer algebra. For an octet subset X, codeword weight obeys

$$w(X) = 16|X| - 2e(X) + 4t(X),$$

where $t(X)$ counts distinguished W33 edge-signature triples. There are exactly six $PSp(4,3)$-orbits on three-subsets and twenty on four-subsets. If U and D are the exact upward and downward orbit-incidence matrices and n_3, n_4 are the orbit-size vectors, then

$$\operatorname{diag}(n_3)U = \big(\operatorname{diag}(n_4)D\big)^{\mathsf{T}}.$$

This is the first transfer layer retaining the essential three-body invariant that is invisible to the ordinary rank-three octet association scheme.

Exact ambiguity-declaring decoding through weight three. Using K as a parity-check matrix for the $[240, 195, 4]_2$ frame code, the numbers of errors having a unique minimum-weight syndrome representative are

$$N_0 = 1, \qquad N_1 = 240, \qquad N_2 = 25440, \qquad N_3 = 1576000.$$

Hence the exact BSC success contribution through weight three is

$$(1-p)^{240} + 240p(1-p)^{239} + 25440p^2(1-p)^{238} + 1576000p^3(1-p)^{237}.$$

Among the $\binom{240}{3} = 2275280$ weight-three errors, 697120 are ambiguous at minimum weight and 2160 are shadowed by a weight-one syndrome. The weight-three syndrome buckets form exactly 110 inner-group orbits. This does not claim unrestricted maximum-likelihood decoding or a threshold.

Canonical outer extension of the coexact degree-30 carrier. With signed point incidence S, oriented octet incidence U, and edge boundary d, define

$$V = 4U + Sd.$$

Then

$$dV^{\mathsf{T}} = 0, \qquad L_1 V^{\mathsf{T}} = 4V^{\mathsf{T}}, \qquad \operatorname{rank}_{\mathbb{Q}} V = 30.$$

For the canonical multiplier-minus-one similitude $s = \operatorname{diag}(1, -1, 1, -1)$, the induced operator on this coexact carrier satisfies

$$s^2 = I, \qquad \operatorname{tr}(s) = 2, \qquad \dim E_+(s) = 16, \qquad \dim E_-(s) = 14, \qquad \det(s) = 1.$$

The sign-twisted extension has trace -2. No ATLAS class label is attached without a separate standard-generator fusion certificate.

Boundary. The module, rank, orbit-transfer, syndrome, and outer-extension statements are exact finite certificates. The global Hoffman nine-cover resolution, the complete 2^{45} weight enumerator, and physical decoding thresholds remain open.

1 Reconciliation addenda for the frame–octet torsion frontier

The primary Loewy, minimal-XOR, chiral-packing, determinant-two, and coherent- configuration results are recorded in Passes 1701–1705. The present addendum freezes five complementary exact facts.

First, the 30-dimensional binary Bockstein module admits an alternative composition series with factors

$$1, 8, 1, 6, 14,$$

whose multiset agrees with the primary Loewy profile $1 \mid (6 \oplus 8) \mid 1 \mid 14$. Orbit-span tests prove each displayed factor irreducible; the 8-factor has endomorphism field $\mathbb{F}_4$, while the 6- and 14-factors have scalar endomorphism field $\mathbb{F}_2$.

Second, a color-symmetric native-XOR generator contains $270 = 30 \cdot 9$ equations, but only 240 new global directions. The exact thirty-dimensional redundancy is the sum over colors forced by the one-color-per-frame equations; removing one color gives the minimal $30 \cdot 8 = 240$ basis.

Third, every exact-cover indicator x satisfies

$$M^{\mathsf{T}}x = \mathbf{1} \quad \Longrightarrow \quad J^{\mathsf{T}}x = 8\mathbf{1}_{45}.$$

Thus every four-packing has signature 32**1** and every complementary 300-frame residual has signature 40**1**. Linear Bockstein signatures cannot distinguish cover orbits or extendibility.

Fourth, the unique determinant-two orientation defect has an explicit primitive edge representative of support 128 and squared norm 152.

Finally, the five-valued frame Gram partition

$$6^1,\ 3^{32},\ 2^{15},\ 1^{300},\ 0^{192}$$

is not closed under multiplication: the square of the intersection-one relation takes eight values on that relation. The full rank-32 frame orbital algebra, not the coarse Gram partition, is required.

1.1 Complete cover census and nonlinear octet-signature obstruction

Let $\mathcal{C}$ denote the exact covers of the canonical 540×240 frame–edge incidence matrix. A complete Algorithm-X enumeration through one fixed frame gives

$$|\mathcal{C}_{f_0}| = 394200.$$

Since $PSp(4,3)$ is transitive on the 540 frames and every cover has 60 frames,

$$60|\mathcal{C}| = 540|\mathcal{C}_{f_0}|, \qquad \boxed{|\mathcal{C}| = 3547800}.$$

The complete family consists of exactly 327 projective-group orbits, with stabilizer-order census $2^{228}, 4^{84}, 8^{15}$.

The rank-45 frame/octet coherent configuration contains a unique cross orbital of frame degree one and octet degree twelve. For a cover x, let $t_o(x)$ count the selected frames assigned to octet o by this orbital. The five cross-orbital signatures are then

$$\boxed{(8\mathbf{1}, 32\mathbf{1}, 16\mathbf{1} - 4t, 4\mathbf{1} + 3t, t)}.$$

If A_{45} is the adjacency matrix of $\mathrm{SRG}(45, 32, 22, 24)$, then

$$(A_{45} + 4I)t = 48\mathbf{1}, \qquad t - \frac{4}{3}\mathbf{1} \in E_{-4}(A_{45}).$$

Each signature has a unique anchor octet whose 32 neighbors all have value one. The anchor's 12 nonneighbors induce $K_{4,4,4}$, with three canonical four-cells. Their value patterns are

$$(2,2,2), \quad (0,3,3), \quad (1,2,3), \quad (0,2,4),$$

so the total is $45(1 + 3 + 6 + 6) = 720$.

Exactly 720 signature vectors occur globally, in four orbits:

type	coordinate histogram	$\|t\|^2$	$\|PSp \cdot t\|$	# cover orbits	# covers
T_{128}	$0^4 1^{32} 2^4 4^5$	128	270	270	3149280
T_{120}	$0^4 1^{32} 3^8 4$	120	135	6	38880
T_{104}	$1^{36} 2^4 3^4 4$	104	270	24	233280
T_{96}	$1^{32} 2^{12} 4$	96	45	27	126360

For the certified four-cover packing, the type sequence is $T_{128}, T_{96}, T_{104}, T_{128}$. Five additional covers would have to sum to its residual capacity $c = 12\mathbf{1} - \sum_{i=1}^{4} t_i$. Although 632 of the 720 single-cover signatures satisfy $t \leq c$, an exact meet-in-the-middle search over 117548 unique admissible pair sums and 305488 admissible triple sums finds no complement. Hence

$$\boxed{\nexists\, u_1, \ldots, u_5 \in \mathcal{T} : u_1 + \cdots + u_5 = c},$$

where $\mathcal{T}$ is the complete global signature set. Thus this four-packing is nonextendible already in the 45-coordinate nonlinear quotient. This does not decide whether an unrelated nine-cover resolution exists.

1.2 Outer-class fusion, XOR separation, and the weight-four decoder

Theorem 1.1 (Passes 1826–1830)**.** *For the canonical multiplier-minus-one similitude of the W33 carrier:*

1. *its class in* $\mathrm{PSp}(4,3){:}2 \cong U_4(2){:}2$ *is the outer involution class* $2D$*; its traces on the chiral constituents of degrees* $15, 24, 30, 81$ *are* $(3, 4, 2, 3)$*;*
2. *the symmetry-fixed resolution XOR system has* 4860 *variables, rank* 2349*, and affine solution dimension* 2511*, but its canonical exact parity witness is not an integer Hoffman resolution;*
3. *the code-weight layers* 0 *through* 10 *and* 35 *through* 45 *are exact, while the full subset action has* 1,358,719,936 *orbits, so the complete* 2^{45} *enumerator remains open;*
4. *among the* $\binom{240}{4} = 134{,}810{,}340$ *weight-four errors, exactly* 63,416,280 *have a unique minimum-weight syndrome representative;*
5. *after imposing the complete set of* 720 *globally realizable nonlinear cover signatures, the certified four-cover packing has no five-signature completion, despite consistency of the linear XOR relaxation.*

The resulting binary-symmetric-channel success contribution through weight four is

$$(1-p)^{240} + 240p(1-p)^{239} + 25440p^2(1-p)^{238} + 1576000p^3(1-p)^{237} + 63416280p^4(1-p)^{236}.$$

The nonlinear obstruction is packing-specific and does not settle the existence of an unrelated nine-cover resolution.

1.3 Complete cover-pair layer and nonlinear nine-signature separation

The complete exact-cover census contains 3,547,800 covers in 327 $\mathrm{PSp}(4,3)$-orbits. We now classify the complete disjoint-pair layer. If C_i is a representative of orbit $\mathcal{O}_i$, define

$$D_{ij} = \#\{C \in \mathcal{O}_j : C \cap C_i = \varnothing\}.$$

All 327^2 entries are reconstructed exactly and satisfy

$$|\mathcal{O}_i| D_{ij} = |\mathcal{O}_j| D_{ji}.$$

Of the 106,929 ordered orbit-type cells, 106,761 are compatible and 168 are incompatible. There are 23,276,276,640 unordered disjoint cover pairs globally. Ten orbit types are not self-compatible, but every orbit type has a disjoint partner.

The nonlinear octet signatures admit exact nine-layer integer solutions. For the complete set $\mathcal{T}$ of 720 realizable signatures, the equations

$$\sum_{t\in\mathcal{T}} y_t = 9, \qquad \sum_{t\in\mathcal{T}} y_t t = 12\mathbf{1}, \qquad y_t \in \mathbb{Z}_{\geq 0}$$

have a witness consisting of six signatures of norm 128 and three of norm 96. Its setwise stabilizer has order 9, so its inner orbit has size 2880.

The four signature classes have an intrinsic representation-theoretic explanation. The stabilizer of an anchor octet has order 576 and acts on the three $K_{4,4,4}$ non-neighbour cells through a quotient S_3 with kernel of order 96. The four local patterns

$$(0,2,4), \quad (0,3,3), \quad (1,2,3), \quad (2,2,2)$$

have local orbit sizes $6, 3, 6, 1$, yielding the global orbit sizes $270, 135, 270, 45$ and stabilizer orders $96, 192, 96, 576$.

The canonical outer involution preserves these four classes but acts nontrivially inside them. It fixes 28 of the 720 signatures. On the 327 inner cover orbits it fixes only five and exchanges 161 pairs; the complete disjointness matrix is invariant under this outer action.

Finally, the displayed nine-signature witness does not lift to nine disjoint exact covers. The nine candidate fibres have sizes

$$11664, 11664, 2808, 11664, 2808, 2808, 11664, 11664, 11664.$$

A deterministic exhaustive nine-partite search closes after 4421 nodes and 4188 dead ends with no lift. This proves non-liftability for one 2880-element signature-resolution orbit. It does *not* decide the existence of a different nine-cover resolution arising from another nonlinear signature orbit.

Exact signature, duad-compression, decoder, and outer-class continuation

The complete set of 720 nonlinear cover signatures admits an exact nine-vector capacity witness,

$$t_1 + \cdots + t_9 = 12\mathbf{1}, \qquad \{\text{types}\} = 6T128 + 3T96.$$

Thus the nonlinear signature quotient is feasible. The parallel Pass 1835 exact lift worker proves that this specific $6T128 + 3T96$ signature orbit has no frame-level lift, sharply separating signature feasibility from exact-cover realizability.

The proposed 9×5 middle-layer spread does not exist. In the complement of $\mathrm{SRG}(45, 32, 22, 24)$, the maximum number of mutually disjoint five-cliques is six. There are 72 maximum partial spreads, and the residual fifteen vertices induce

$$\mathrm{SRG}(15, 6, 1, 3) \cong KG(6, 2).$$

Hence the exact separator is $45 = 6 \cdot 5 + 15$, with a canonical duad residual.

For the binary $[240, 195, 4]_2$ frame code, equal-syndrome triple pairing gives exactly

$$A_6 = 9600$$

weight-six codewords. Exactly 185040 weight-five errors are shadowed by a unique singleton error. The complete weight-five decoder coefficient remains conditional on the weight-eight and weight-ten dependency atlas.

The four chiral modules of degrees $15, 24, 30, 81$ are separated by four geometrically fingerprinted outer probes with trace matrix

$$\begin{pmatrix} 3 & 4 & 2 & 3 \\ -1 & 0 & 4 & -3 \\ -2 & 1 & -1 & 0 \\ 1 & 0 & 0 & -1 \end{pmatrix}, \qquad \det = 80.$$

Finally, an ATLAS-standard pair (c, d) satisfies $c \in 2C$, $|d| = 9$, $|cd| = 10$, and generates $\mathrm{PSp}(4, 3){:}2$. If $D = d^{-1}$, the canonical $2D$ similitude is

$$s = cdcD^2cdcd^2cDcD^2cD^2.$$

All statements are frozen in the Passes 1836–1840 exact certificates. No frame-cover resolution, complete middle-layer enumerator, or weight-five threshold is inferred.

1.4 A second signature orbit, free higher-packing suborbits, and the outer quotient

The nonlinear signature equations admit at least two $PSp(4, 3)$-orbits of distinct nine-signature solutions. The first has size 2880, stabilizer order 9, and type $6T_{128} + 3T_{96}$. Blocking all 2880 supports of that orbit yields a second exact solution with trivial stabilizer, hence orbit size 25920, and type

$$3T_{128} + 2T_{120} + 2T_{104} + 2T_{96}.$$

Thus at least 28800 signature-level resolutions exist across two inner orbits. The census is not yet exhaustive.

The certified chiral four-packing has trivial inner setwise stabilizer. Its six pairs, four triples, and one quadruple therefore generate six, four, and one distinct $PSp(4, 3)$-orbits, each of size 25920. The canonical outer similitude exchanges every one of these eleven inner subpacking orbits with a distinct mirror orbit. This classifies the higher-packing structure inside the certified family, not globally.

The new free signature orbit also fails to lift. The nine exact candidate-cover populations are

$$11664,\ 2808,\ 864,\ 864,\ 11664,\ 288,\ 288,\ 2808,\ 11664,$$

and deterministic nine-partite search returns UNSAT after 289 nodes and 288 dead ends. Together with the earlier 2880-orbit obstruction, two inner signature orbits containing 28800 solutions are excluded from frame-level resolution; this is not a global no-resolution theorem.

The order-nine stabilizer of the first signature orbit is elementary abelian:

$$G_{\mathrm{sig}} \cong C_3 \times C_3.$$

Its three point-orbits are two T_{128} triangles and one T_{96} triangle. On the six T_{128} signatures, Gram value 74 is exactly $2K_3$, Gram value 70 is exactly $K_{3,3}$, and the remaining 21 pairs have Gram value 78.

Finally, the canonical outer involution fixes both certified inner signature orbits. The first extended setwise stabilizer is

$$(C_3 \times C_3) \rtimes C_2 \cong C_3 \times S_3$$

of order 18, while the free inner orbit acquires a setwise stabilizer C_2 in $PGSp$. These statements concern the two certified orbits only.

1.5 Two no-lift signature orbits, the weight-five decoder chart, the duad–syntheme separator, and outer-probe fusion

The independently owned Passes 1841–1845 packet certifies two distinct inner orbits of nonlinear nine-signature resolutions, of sizes 2880 and 25920, and proves by exact multipartite search that neither orbit lifts to nine disjoint frame covers. The binary signature-orbit census remains incomplete, so this is not a global no-resolution theorem.

For the binary frame code the complete low-weight enumerator through ten is

$$A_4 = 540, \qquad A_6 = 9600, \qquad A_8 = 424170, \qquad A_{10} = 17523360.$$

The fixed-coordinate syndrome sort gives the exact chart partition

$$\binom{239}{4} = 132563501 = 1754193 + 62359342 + 68449966.$$

The earlier globalization of the chart singleton count by the factor $240/5$ is superseded by Pass 1882. Equal-syndrome weight-five errors differing by a weight-w codeword share only $5 - w/2$ coordinates; in particular all

$$2{,}207{,}943{,}360$$

weight-ten collision pairs are disjoint and invisible in every fixed-coordinate chart. Thus

$$\boxed{U_5 \le 2{,}993{,}248{,}416}$$

is a certified upper bound for the global unique-minimum count, not an exact fifth-order coefficient. The exact global lower-shadow count remains 84,201,264, and the exact minimum-weight-five population is 6,278,846,784.

The $6 \times 5 + KG(6, 2)$ separator has an exact check decomposition

$$\boxed{240 = 20 + 15 \cdot 12 + 20 \cdot 2}.$$

The 20 residual checks are the triangles of K_6 on the fifteen duads; each of the fifteen fiber pairs determines one of the fifteen synthemes, yielding the classical duad–syntheme realization of the exceptional outer automorphism of S_6; and every fiber triple carries two phase checks.

The remaining outer probes fuse exactly to ATLAS classes

$$2D, \qquad 4C, \qquad 6H, \qquad 8A,$$

with verified centralizers $96, 96, 36, 8$ and literal shortest words of lengths $18, 12, 16, 17$ in the project ATLAS-standard pair. Finally, an exact tuple-conjugacy algorithm is supplied and passes a deterministic relabelling test, but the official ATLAS GAP payload server was inaccessible during this run. Therefore no literal official-tuple conjugacy claim is made without the primary-source bytes.

1.6 Residual contraction, lower-syndrome orbits, and the exceptional S_6 intertwiner

The certified $6 \times 5 + 15$ separator admits an exact residual contraction. The 15-duad sector has 156 natural S_6-orbits; every one of the fifteen pair-transfer tensors has binary rank 7, while every one of the twenty phase tensors has rank 2. The complete six-fiber contraction remains open, with a separator-first induced-width certificate equal to 40.

All syndromes reachable at odd weight below five form exactly

$$1{,}892{,}792$$

distinct vectors and exactly 110 inner-group orbits: one minimum-weight-one orbit and 109 minimum-weight-three orbits. This gives a fail-closed symmetry-compressed decoder for every lower shadow of a weight-five error.

The duad-to-syntheme map is represented by an integral permutation matrix $P \in GL_{15}(\mathbb{Z})$ with

$$\det P = -1.$$

For each Coxeter generator s_i of S_6,

$$P\rho_{\mathrm{duad}}(s_i) = \rho_{\mathrm{syntheme}}(\alpha(s_i))P,$$

where every $\alpha(s_i)$ is a triple transposition and the five images generate all of S_6. Thus the W33 separator carries a literal integral realization of the exceptional outer automorphism.

Finally, a deterministic 500,000,000-node proof search establishes

$$A_{12} \geq 5{,}323{,}560.$$

The weight-six equal-syndrome collision count therefore satisfies

$$E_6 = 1{,}312{,}130{,}546{,}100 + 462A_{12} \geq 1{,}314{,}590{,}030{,}820.$$

Because A_{12} is not yet closed, no sixth-order unique-minimum decoder coefficient is claimed. The independently owned Pass 1855 computation additionally freezes the official ATLAS 40a generator bytes and proves a unique simultaneous conjugator to the project standard pair; Pass 1858 reconciles both payload hashes and the literal two-generator conjugacy certificate.

1.7 Exceptional-S_6 outer doily transfer clock

Let D be the 15×15 syntheme–duad incidence matrix and let $P \in GL_{15}(\mathbb{Z})$ be the exact Pass 1859 permutation matrix realizing the exceptional outer automorphism of S_6. Define $T = P^{\mathsf{T}}D$. Then

$$\operatorname{rank}_{\mathbb{Q}} T = \operatorname{rank}_{\mathbb{F}_2} T = 10, \qquad \dim\ker T = 5,$$

and its ten nonzero Smith invariants are all 1. Its exact polynomials are

$$\chi_T(x) = x^5(x-3)(x-2)(x+2)^2(x^2+4)(x^4+16), \qquad \mu_T(x) = x(x-3)(x^8-256).$$

On the balanced nonzero image

$$W = \operatorname{im}(T) \cap \mathbf{1}^{\perp}, \qquad \dim W = 9,$$

one has

$$\boxed{(T/2)^8 = I_W}, \qquad (T^8 - 256I)T = 1261J,$$

and

$$\operatorname{tr}(T^n) = 3^n + (-2)^n + 8\,2^n[8 \mid n] \qquad (n \geq 1).$$

For the exceptional automorphism α frozen in Pass 1859,

$$T\rho(g) = \rho(\alpha^{-1}(g))T \qquad (g \in S_6).$$

Finally

$$T^{\mathsf{T}}T = D^{\mathsf{T}}D, \qquad TT^{\mathsf{T}} = T^{\mathsf{T}}T.$$

Thus T is normal but nonsymmetric and $T/2$ is orthogonal on W. The fold preserves the doily singular spectrum $9^1+4^9+0^5$, and $T^{\mathsf{T}}T-3I$ is the SRG$(15,6,1,3)$ point graph of $W(2)$. The clock terminology is strictly finite and representation-theoretic; no physical time evolution or continuum dynamics is inferred.

1.8 Cyclotomic boundary, Tutte–Coxeter lift, and exact weight-twelve closure

Let $T = P^{\mathsf{T}}D$ be the exceptional-S_6 outer-doily transfer operator of Passes 1867–1871 and let $\Lambda = \mathrm{im}_{\mathbb{Z}}(T) \cap \mathbf{1}^{\perp}$. The integral clock lattice has rank 9, discriminant

$$\det(\Lambda^{\mathsf{T}}\Lambda) = 2560 = 2^9 \cdot 5,$$

and characteristic polynomial

$$(x-2)(x+2)^2(x^2+4)(x^4+16).$$

The normalized action $T/2$ does not preserve Λ; indeed

$$\Lambda/(T+2I)\Lambda \cong \mathbb{Z}^2 \oplus (\mathbb{Z}/4)^3.$$

Thus the regular eight-phase packet is a rational, or 2-local, decomposition and not a global integral $\mathbb{Z}[\zeta_8]$ splitting.

The bipartite lift

$$A_{\mathrm{TC}} = \begin{pmatrix} 0 & D^{\mathsf{T}} \\ D & 0 \end{pmatrix}$$

is the Tutte–Coxeter graph, with intersection array $\{3,2,2,2;1,1,1,3\}$. The exceptional fold has off-diagonal blocks T^{T}, T. The rank-nine separator projector is

$$E_9 = \frac{G(9I-G)}{20}, \qquad G = T^{\mathsf{T}}T,$$

so $\mathbb{Q}^{15} = \mathbf{1} \oplus V_5 \oplus V_9$ and V_9 occurs once. The exact $W(E_6)$ character degrees contain no 9, hence this module is an S_6 separator constituent and not a full-$W(E_6)$ irreducible sector.

A correction to Passes 1867–1871 is also exact:

$$TT^{\mathsf{T}} = T^{\mathsf{T}}T.$$

Therefore T is normal but nonsymmetric, and $T/2$ is orthogonal on the balanced nine-space. The directed graph has automorphism group C_4. Moreover the twisted Hom-space is two-dimensional, and the only row-sum-three solutions with the same Gram matrix are T and $2J/5-T$; consequently T is the unique integral, and unique 0/1, solution.

Finally, exhaustive enumeration of all 2^{45} dual words and exact MacWilliams transform gives

$$\boxed{A_{12} = 891{,}792{,}940}, \qquad \boxed{E_6 = 1{,}724{,}138{,}884{,}380}.$$

Here E_6 is the total weight-six equal-syndrome pair count. The sixth-order unique-minimum decoder coefficient remains open because collision incidences must still be deduplicated by syndrome orbit and lower shadow.

1.9 Decoder globalization correction, complete enumerator, two-adic clock order, and exceptional-S_6 carrier maps

A fixed-coordinate syndrome chart does not determine global syndrome multiplicity. If two equal-syndrome weight-five errors differ by a codeword of weight w, then they share exactly $5 - w/2$ coordinates. In particular the exact weight-ten contribution

$$2{,}207{,}943{,}360$$

consists of disjoint collision pairs invisible in every coordinate chart. This proves that the formerly stated number 2,993,248,416 was only an upper bound. Pass 1887 subsequently completes the complementary global census and supersedes that bound with

$$\boxed{U_5 = 1{,}531{,}165{,}872}.$$

The exact sixth-order collision count remains

$$E_6 = 1{,}724{,}138{,}884{,}380,$$

but the corresponding singleton-syndrome coefficient remains open pending a true global component enumeration.

The complete MacWilliams transform of the frozen dual histogram gives the full binary $[240, 195, 4]$ primal enumerator. Its newly closed low coefficients include

$$A_{12} = 891{,}792{,}940, \qquad A_{14} = 54{,}326{,}090{,}880, \qquad A_{16} = 3{,}770{,}230{,}198{,}995.$$

Edge transitivity makes these support shells 1-designs, while their required pair multiplicities have denominator 239; hence the weight-12, 14, and 16 shells are not 2-designs.

For the balanced clock order,

$$\mathbb{Q}[C] \cong \mathbb{Q} \times \mathbb{Q} \times \mathbb{Q}(i) \times \mathbb{Q}(\zeta_8),$$

and the normalization of $\mathbb{Z}[C]$ is

$$\mathbb{Z} \times \mathbb{Z} \times \mathbb{Z}[i] \times \mathbb{Z}[\zeta_8].$$

The exact index and conductor are

$$[\mathcal{O}_{\max} : \mathbb{Z}[C]] = 2^{35},$$

$$\mathfrak{f} = 1024\mathbb{Z} \times 1024\mathbb{Z} \times 512\mathbb{Z}[i] \times 256\mathbb{Z}[\zeta_8].$$

Thus the failure of the integral cyclotomic splitting is purely two-adic.

The setwise stabilizer of the canonical six fibers is an exceptional S_6 of order 720. For its natural nine-dimensional separator constituent $V_{[4,2]}$, the multiplicities in the signed-edge sectors $(15, 24, 30, 81, 90)$ are

$$\boxed{(0, 1, 0, 0, 1)}.$$

Literal equivariant maps

$$A_{24} = N_{24}/2, \qquad A_{90} = N_{90}/2$$

have rank nine, satisfy all 720 intertwining identities, and obey

$$N_{24}^{\mathsf{T}} N_{24} = N_{90}^{\mathsf{T}} N_{90} = 4E_{9,\mathrm{num}}, \qquad N_{24}^{\mathsf{T}} N_{90} = 0.$$

Hence the two natural V_9 copies are isometric and orthogonal. The occurrence theorem alone did not choose a phase; Pass 1889 later glues the paired copies into an exact exceptional-S_6-equivariant complex structure. The odd 81-sector remains parity-obstructed.

Finally,

$$\mathrm{Aut}_{\to}(T) = \mathrm{Fix}(\alpha) \cong C_4,$$

generated on the six labels by $(0\,1\,4\,5)(2\,3)$. Its duad orbits have sizes

$$4 + 4 + 4 + 2 + 1,$$

and the unique loop is the fixed duad $\{2, 3\}$. The resulting five-vertex graph-of-groups voltage table reconstructs all 45 arcs of the exceptional one-part fold $T = P^{\mathsf{T}}D$ of the Tutte–Coxeter graph. These voltage labels are finite graph phases, not physical time or optical phase.

1.10 Exact global fifth-order decoding, paired-carrier phase, and the Tutte–Coxeter lift

The fixed-coordinate decoder chart is completed by an exact complementary codeword census. A partner retaining the fixed coordinate is already visible in the chart; a partner omitting it differs by a weight-$4, 6, 8$, or 10 codeword containing that coordinate. Exhausting both cases gives

$$\boxed{U_5 = 1{,}531{,}165{,}872}, \qquad \boxed{A_5^{\mathrm{amb}} = 4{,}747{,}680{,}912},$$

and the exact partition

$$6{,}363{,}048{,}048 = 84{,}201{,}264 + 1{,}531{,}165{,}872 + 4{,}747{,}680{,}912.$$

Thus the corrected fifth-order BSC contribution is

$$\boxed{1{,}531{,}165{,}872\, p^5(1-p)^{235}}.$$

The weight-six equal-syndrome edge count remains exact, but its singleton component count remains open.

For the separator decomposition

$$240 = 20_{\mathrm{residual}} + 180_{\mathrm{pair}} + 40_{\mathrm{phase}},$$

the complete rank-30 fiber subcode has an exact 563-bin $(w_{\mathrm{pair}}, w_{\mathrm{phase}})$ enumerator over all 2^{30} words. The rank-15 residual subcode has exactly 156 exceptional-S_6 orbits with exact $(w_{\mathrm{residual}}, w_{\mathrm{pair}}, w_{\mathrm{phase}})$ records. The full mixed 2^{45} refined contraction is not inferred from these marginals.

Let $A_{24} = N_{24}/2$ and $A_{90} = N_{90}/2$ be the two literal natural V_9 carrier maps. Each rank-nine image lattice has Gram Smith invariants

$$2, 10, 10, 10, 20, 40, 40, 40, 40$$

and discriminant $2^{18}5^8$. The paired orthogonal rank-18 lattice carries an exact exceptional-S_6-equivariant complex structure

$$J(A_{24}v) = A_{90}v, \qquad J(A_{90}v) = -A_{24}v, \qquad J^2 = -I.$$

Its half-integral enlargement has index 2^{18} and therefore does not absorb the independent 2^{35} maximal-order defect of the clock algebra.

On the full $24 \oplus 90$ carrier the exceptional-S_6 commutant has real dimension 23 and the odd real-type multiplicities obstruct a complex structure. Restriction to the residual clock subgroup C_4 gives

$$28\mathbf{1} \oplus 26\,\mathrm{sgn} \oplus 30\mathbb{R}^2_{\mathrm{rot}},$$

with commutant

$$M_{28}(\mathbb{R}) \times M_{26}(\mathbb{R}) \times M_{30}(\mathbb{C}),$$

of real dimension 3260; both the 24- and 90-sectors then admit C_4-invariant complex structures.

Finally, every one of the 180 pair-transfer coordinates is uniquely a nonincident syntheme–duad pair, so this sector is exactly the bipartite complement of the Tutte–Coxeter Levi graph. The exceptional C_4 fixes two of its 90 octagons and has 22 free octagon orbits. On the 90 directed Hashimoto states its four powers fix

$$90, 2, 10, 2$$

states. The natural V_9 lies in the adjacency eigenspaces $\lambda = \pm 2$ and feeds the four cyclotomic nonbacktracking factors

$$(x^2 - 2x + 2)^9, \qquad (x^2 + 2x + 2)^9.$$

All phase and voltage statements here are finite representation and graph holonomies; no physical time evolution or optical phase law is inferred.

1.11 Weight-six reduction, the mixed separator tensor, the Gaussian V_9 lattice, and the twisted zeta

The exact weight-six collision ledger is

$$(E_6(4), E_6(6), E_6(8), E_6(10), E_6(12)) = (204105833100, 202385664000, 397812076200, 507826972800, 412008338280)$$

so $E_6 = 1724138884380$. The weight-twelve term consists of disjoint pairs invisible in every fixed-coordinate chart and contributes

$$44589647\binom{11}{5} = 20600416914$$

fixed-coordinate external-partner incidences with multiplicity. Hence the sixth-order singleton coefficient is not a collision moment; an exact external-memory component worker is supplied and the final heavy run remains open.

The complete mixed separator enumerator is the exact partition function of six five-bit fiber variables and fifteen residual bits, with

$$\boxed{240 = 20_{\mathrm{residual}} + 180_{\mathrm{pair}} + 40_{\mathrm{phase}}}.$$

The 45 absent pair/residual incidences are the Tutte–Coxeter edges, the 180 present incidences are their complement, and the residual and phase families are the complete twenty-triple systems on six labels. A chunkable worker contracts the resulting 155841-bin tensor over the 156 residual S_6 orbits; the final all-orbit merge is not inferred from the marginals.

The paired natural V_9 carrier is a rank-nine Gaussian lattice of minimum norm 24, with 60 minimal vectors and Smith invariants

$$2, 10, 10, 10, 20, 40, 40, 40, 40.$$

Its fifteen minimal lines form $KG(6,2)$, whence

$$\boxed{U(L) \cong C_4 \times S_6, \qquad |U(L)| = 2880.}$$

On the real 90-sector, $\mathrm{End}_{PSp(4,3)}(90) \cong \mathbb{C}$, so the invariant complex structures are exactly $\pm J$; the outer involution of $W(E_6)$ sends J to $-J$ and removes the full-Weyl phase. Exceptional S_6 obstructs J on the full 24, 90, and 114 carriers but preserves the paired-V_9 structure. The named chain and every cyclic subgroup class are exact; a GAP worker completes the remaining noncyclic classes.

Finally the residual C_4 decomposes the 90 Hashimoto states into dimensions $26+20+24+20$, with reciprocal factors

$$\begin{aligned} Z_0^{-1} &= (1-4u^2)(1-u^2)^4(1+2u^2)^2(1-2u+2u^2)^3(1+2u+2u^2)^3, \\ Z_1^{-1} = Z_3^{-1} &= (1-u^2)^4(1+2u^2)^2(1-2u+2u^2)^2(1+2u+2u^2)^2, \\ Z_2^{-1} &= (1-u^2)^4(1+2u^2)^4(1-2u+2u^2)^2(1+2u+2u^2)^2. \end{aligned}$$

The natural V_9 channel contributes $12, 8, 8, 8$ dimensions across the four characters. These are finite representation and graph invariants, not physical propagation laws.

Passes 1907–1911: split enumerator and phase–holonomy closure

The complete rank-45 dual-code split enumerator for the canonical 20+180+40 coordinate partition has 2^{45} words and exactly 7355 nonzero trivariate coefficients. Its three complement symmetries are literal code translations: the sum of the thirty fibre generators is the phase-40 mask, the sum of the fifteen residual generators is the residual-plus-pair-200 mask, and together they generate a $C_2 \times C_2$ complement subcode containing the all-one word.

Building on the Weil-chirality and Frobenius–Schur results already owned by Passes 353/355 (Gow–Vinroot), all 56 conjugacy classes of subgroups of the exceptional S_6 have been classified by Frobenius–Schur parity. Exactly 26, 22, and 12 classes admit invariant complex structures on the 24, 90, and $24 \oplus 90$ carriers, respectively, while the paired natural V_9 admits one for every class. On A_6, the S_6-paired complex structure and the restricted $PSp(4,3)$ structure are distinct adjacent rotations on three equivalent real V_9 copies and generate $\mathfrak{so}(3)$ rather than a quaternionic algebra.

The 15 projective Gaussian minimal lines form $KG(6,2)$, but this projectivization forgets the central C_4 unit orientation. Sound outer-conjugation cuts therefore live on the 60-vector oriented lift: a transported pair satisfies $\Phi(c') = -\Phi(c)$ and a transported fixed color satisfies $\Phi(c) = 0$. No pointwise bound is inferred from the spread mean $45/9 = 5$.

Finally, stabilizer-weighted primitive holonomy splits the 90-state Hashimoto representation into the shared 36-dimensional natural-V_9 channel and a 54-dimensional complement. The graph invariant cannot separate the two literal V_9 carrier embeddings. The global sixth-order decoder coefficient remains behind an explicit external-memory boundary; a complete 2,190,670-error shard, including lower-shadow removal, is certified without promoting a global value.

Passes 1939–1943: split MacWilliams, integral phase order, and Hodge–field separation

A merged fixed-coordinate weight-six super-shard containing 58,282,126 errors exposes 5,389,182 collision edges that are invisible in independent shard counts and destroys 3,210,241 apparent sin-

gleton groups. The global sixth-order coefficient remains open because shards outside the certified super-shard and external complementary partners are not yet merged.

The complete $20 + 180 + 40$ split MacWilliams transform has 2^{195} primal words and exactly 39,081 nonzero coefficients. The complement $C_2 \times C_2$ lies in the code hull, forcing h and $r + p$ to be even while also generating the three split-complement symmetries. The weight-four shell splits exactly as

$$15\,(4,0,0) + 120\,(1,3,0) + 225\,(0,4,0) + 180\,(0,2,2) = 540.$$

The fifteen Gaussian projective minimal lines identify literally with the fifteen residual duads, but the projective/color quotient annihilates all 135 conjugation-odd moments. Consequently no nonzero phase-odd cut descends to the unoriented color variables; a C_4-oriented solver lift is necessary.

On the three-copy A_6 multiplicity lattice, the Gaussian quarter-turn on the $A + B$ copies and the Eisenstein sixth-order unit on the $B + C$ copies generate

$$\mathbb{Z}[R_4, U_6] = M_3(\mathbb{Z}).$$

The common commutant is scalar and the generated unit group is infinite, so there is no quaternionic or finite $SU(2)$ enhancement.

Finally, the two literal V_9 embeddings are separated by $L_1A_{24} = 10A_{24}$ and $L_1A_{90} = 4A_{90}$, and independently by ambient character fields $\mathbb{Q}$ and $\mathbb{Q}(\omega)$. The unique sixfold Eisenstein phase therefore lies in the coexact, divergence-free 90-sector, not in the exact Gauss-law/source block. Its structurally supported reading is a flux or holonomy phase; identifying its six units with electric charges remains a physical hypothesis rather than a derivation.

Passes 1950–1954: frame geometry, arithmetic closure, and the internal phase boundary

The 28 primitive shards in the current sixth-order decoder super-shard form a complete weighted collision graph with 125 distinct edge labels and trivial automorphism group. The fixed-edge geometric stabilizer has 230 orbits on all pair charts, so the present ordering-based partition has no useful symmetry compression; the global sixth-order coefficient remains open.

The 540 minimum primal words are exactly the 540 frame matchings. Under the exceptional S_6 they split into orbits of sizes $15, 45, 120, 180, 180$. The 225 pair-only words split into a 45-orbit of parallel tetrads, partitioning all 180 pair coordinates, and a 180-orbit of pair rectangles. The residual 15-orbit is the set of tetrahedral boundaries on four-subsets of six.

A literal binary 540×15 frame–residual-duad incidence matrix has rank 15 over $\mathbb{Q}$ and over $\mathbb{F}_p$ for $p = 2, 3, 5, 7$, with all 720 exceptional-S_6 equivariance equations exact. A corrected prefix-equality lex leader is certified nonvacuous by a feasible colouring that it removes and a symmetry-equivalent representative that it preserves. A bounded unpinned nine-colour run remains `UNKNOWN`; no chromatic claim is promoted.

On the three-copy A_6 multiplicity lattice, the Gaussian quarter-turn and the Eisenstein sixth-turn generate all elementary transvections. Hence their group is exactly $\mathrm{SL}_3(\mathbb{Z})$. Finally, the internal endomorphism C_6 and the E_8 Coxeter hexagon C_6 are inequivalent on their full 240-dimensional carriers: their character multiplicities are $(150, 45, 0, 0, 0, 45)$ and $(40, 40, 40, 40, 40, 40)$, respectively. The internal μ_3 also fails to commute with the exceptional-S_6 pairing on the shared V_9 sector.

The order-six symmetry is therefore retained only as an internal endomorphism of the coexact 90. No homological flux quantum, electric-charge derivation, QCD-colour identification, generation assignment, or neutrino identification is asserted.

Passes 1966–1970: combined spread symmetry, the intrinsic phase role, and the standalone draft

The 36 spread-by-colour counts and the geometric group action now coexist in a single exact signature model. Forty point-transvection orbit-minimum cuts grow the nine-colour formulation from 3033 to 3073 constraints. On the complete 25920-element $PSp(4,3)$ orbit of a known proper 14-colouring, one cut leaves 13021 images, eight leave 3244, and all forty leave 807. The forty cut directions are linearly independent. This is a certified symmetry reduction, not a chromatic decision: the bounded nine-colour run remains `UNKNOWN`.

The internal Eisenstein phase also has a representation-theoretic role that does not require a physical label. The finite integral centralizer torsion is $(C_2)^4 \times C_6$; its unique odd Sylow $C_3 = \langle \mu_6^2 \rangle$ is characteristic. Every nontrivial phase power fixes the rational 150-dimensional block sum and acts on the coexact Eisenstein 90. The outer involution sends μ_6 to μ_6^{-1}, so the phase and chirality generate a D_{12} normalizer. No charge, flux, colour, generation, or particle interpretation is asserted.

A backward audit now distinguishes vacuous constraints, scope errors, restrictive but invalid cuts, and verified constraints that were never inserted. The exact replay includes the false spread cap $5 < 13$, the vacuous $x \leq y + 8$ inequality, and positive model-growth and orbit-removal witnesses for the corrected cuts. Two oldest executable builders were not located and remain explicitly postmortem-derived.

Finally, `analysis/W33_SPREAD_OBSTRUCTION_REFEREE_DRAFT.tex` collects the frame graph, spread trap, finite $1/q$ law, spread involution, and signed-edge-module results in a referee-shaped standalone article with theorem status labels, ownership boundaries, reproducibility evidence, consolidated withdrawals, and open problems. It keeps $\chi(H) = 9$ open and is not presented as peer review or publication.

Passes 1971–1975: corrected spread obstruction, scoped proof, and engineering boundary

The independent treatments of the spread obstruction have been reconciled. One repeated statement is withdrawn: the 45 frames determined by a spread are not a maximal independent set. At $q = 3$ there are exactly 15 residual candidate frames, each nonadjacent to the spread seed. Their union meets only 20 of the 60 residual edges, however, so 40 residual edges occur in no candidate. The exact obstruction is therefore support deficiency: no 60-frame exact cover extends the spread seed.

Uniformly, spread pairs form an independent seed and leave $(q^2+1)q(q+1)/2$ internal spread-line edges. If the spread carries a fixed-point-free linewise involution σ, the line orbits $\{A, \sigma(A)\}$ supply $q(q^2+1)/2$ residual candidates, supported on $(q^2+1)(q+1)/2$ residual edges with multiplicity q. The statement that these are all candidates is the additional candidate-orbit property. It is verified for the repository's $q = 3, 5, 7$ examples but is not proved uniformly. A nonsquare similitude $g^2 = \mu I$ constructs the involution for the associated Desarguesian symplectic spread for every odd q; it does not by itself prove the candidate-orbit converse. Existence and uniqueness for arbitrary symplectic spreads are not claimed; uniqueness is exact at $q = 3$.

The nine-colour decision remains open. Spread-variable branching is still the best frozen search at 60,909 branches. Combining it with eight or forty geometric lex generators gives 451,460 and 512,714 branches, respectively. Thus the exact orbit reduction 25,920 $\to$ 807 is not a search-performance theorem. Full-scale constraints are now audited by named feasible witnesses or explicit finite feasible orbits rather than truncated enumeration.

The internal Eisenstein C_6 remains confined, under equivariant linear maps, to the coexact 90 and is inverted by chirality, giving a D_{12} phase normalizer. Charge and homological-flux readings remain withdrawn. The computer-engineering consequences are architectural proposals only: external symmetry canonicalisation, geometric cube deduplication, wide-bit exact-cover acceleration, Hodge-separated control planes, and an isolated six-phase calibration domain.

Passes 2011–2015: decorated spread pairs, subgroup schedules, and quadratic readout

The 270 unordered spread pairs meeting in four lines carry stabilizer $S_4 \times D_8$ of order 192. Two order-four conjugacy-class carriers are literal decoration bundles over these pairs: the size-540 class chooses one of two inverse coherent linewise quarter-turns, while the size-1620 class chooses one of six cyclic orders of the four common lines. Their stabilizers have orders 96 and 32, respectively; the identifications use the induced local actions and stabilizer conjugacy, not cardinality alone.

Complete enumeration of the 1026 subgroups of one such pair stabilizer gives 234 stabilizer-conjugacy classes. Exactly 33 classes construct a 60-frame exact cover from whole frame orbits. Every successful subgroup has order 2, 4, or 8, and no subgroup of order at least 12 succeeds. A literal D_8 witness uses twelve orbits of sizes $2, 2, 4, 4, 4, 4, 4, 4, 8, 8, 8, 8$ and covers each of the 240 edges once.

The 36 spreads form a rank-three association scheme. The four-line relation is $\mathrm{SRG}(36, 15, 6, 6)$ and its adjacency matrix satisfies

$$A^2 = 9I + 6J.$$

Since every line belongs to nine spreads, a fixed spread has total intersection 80 with the other spreads. Its fifteen four-line neighbours account for 60, forcing each of the remaining twenty spreads to meet it in exactly one line. Thus distinct spreads meet in one or four lines, with no other value.

The 360 one-line spread pairs do not form an eightfold bundle over the 45 octets: their stabilizer has octet orbits of lengths $6, 9, 12, 18$ and fixes no octet. Removing the common line instead reveals the bipartite double cover of the 3×3 rook graph on the two banks of nine noncommon lines. This local graph has automorphism group order 144, exactly the spread-pair stabilizer.

The degree-safety audit must mark degrees 240 and 540 unsafe for count-only identification. At degree 240 two order-216 stabilizers are nonconjugate; at degree 540 the three order-96 class centralizers are pairwise nonconjugate. The Eisenstein 90 remains linearly confined, but its quadratic channels are nontrivial: $\mathrm{Sym}^2(90)$ contains all four rational blocks, whereas $\Lambda^2(90)$ contains no copy of the gauge 15. This yields a precise symmetric-versus-antisymmetric readout selection rule without restoring any withdrawn charge or flux interpretation.

The computer-engineering consequences are proposals: a 36-lane rank-three mixer, a two-bank rook-double crossbar, a D_8 orbit-compressed scheduler, a quadratic phase-readout stage, and stabilizer-aware group-set interfaces. The chromatic decision remains open, the subgroup census is scoped to one fixed $S_4 \times D_8$ stabilizer, and no device or particle identification is claimed.

Passes 2050–2053 and 2064: full-group schedules, explicit quadratic maps, and the regular-spread family

The 33 subgroup classes inside a fixed four-line spread-pair stabilizer that construct orbit-built parallel classes fuse into 14 subgroup conjugacy types in $\mathrm{PGSp}(4,3)$. Taking the first deterministic exact-cover witness from each local class gives 32 distinct frame sets in 12 full-group schedule orbits. The subgroup fusion is complete for those 33 classes; the 12 schedule orbits are not a classification of every cover generated by them.

The quadratic connectivity of the signed coexact 90 is now literal rather than character-only. Vertex-energy gradients give surjections $\mathrm{Sym}^2(90) \to 15$ and $\mathrm{Sym}^2(90) \to 24$. Graph-restricted skew-matrix commutators give surjections $\Lambda^2(90) \to 30$ and $\Lambda^2(90) \to 81$. Twisting the commutators by the canonical complex structure gives chirality-odd symmetric maps to 30 and 81. All seven constructed maps have verified rank, equivariance, chirality parity, and internal μ_6 phase response. They are canonical generators, not a complete basis of all quadratic Hom spaces or physical coupling constants.

The frozen D_8 schedule expands twelve frame orbits of sizes $2,2,4,4,4,4,4,4,8,8,8,8$ to 60 frames and covers all 240 edges exactly once. An executable reference model composes this orbit scheduler with a 240-bit exact-cover validator, the 36-lane spread mixer satisfying $A^2 = 9I + 6J$, and the 18-lane rook-double crossbar. These are software and hardware-architecture proposals, not a fabricated device.

The 36-spread four-line intersection graph is identified literally as the rank-three graph $NO_6^-(2)$, equivalently $NO_5^{-\perp}(3)$. A fixed vertex has local graph $K(6,2)$ and second subconstituent $J(6,3)$, and the full automorphism group has order 51,840. The subconstituent isomorphisms and rank-three action are load-bearing because the parameters $(36,15,6,6)$ alone are highly nonunique.

Finally, complete regular-symplectic-spread orbits at $q = 3,5,7$ have sizes $36, 300, 1176$. In each case two distinct spreads meet in exactly 1 or $q+1$ lines, and the $q+1$ relation is strongly regular. The three cases match a single polynomial parameter family, but the all-odd-q statement remains a conjectural extrapolation here; non-Desarguesian symplectic spreads are not classified by this computation. The nine-colour decision remains open.

Regular spreads as projective quadratic structures

Let q be odd, let $\mu \in \mathbb{F}_q^\times$ be nonsquare, and write $K = \mathbb{F}_{q^2} = \mathbb{F}_q[t]/(t^2 - \mu)$. Regard $V = K^2$ as a four-dimensional $\mathbb{F}_q$-space. If

$$\Omega(x,y) = x_1y_2 - x_2y_1$$

and $\beta(x,y)$ is the t-coefficient of $\Omega(x,y)$, then β is a nondegenerate alternating $\mathbb{F}_q$-form. The one-dimensional K-subspaces of K^2 are totally isotropic two-dimensional $\mathbb{F}_q$-subspaces and form a regular symplectic spread.

Multiplication by t defines J with

$$J^2 = \mu I, \qquad \beta(Jx, Jy) = \mu\beta(x,y).$$

Thus $\sigma = [J] \in PGSp(4,q)$ is a projective involution. The spread is exactly the set of J-invariant projective lines. Since $K^\times/\mathbb{F}_q^\times \cong C_{q+1}$ has a unique involution, each regular field-reduction spread carries a unique projective quadratic structure. For $q \equiv 3 \pmod 4$ one may take $\mu = -1$, recovering the geometric i; for $q \equiv 1 \pmod 4$ a different nonsquare is required.

Restricting the classical Desarguesian-spread stabilizer to symplectic similitudes gives

$$C_{PGSp(4,q)}(\sigma) \cong C_2 \times P\Sigma L_2(q^2), \qquad \left|C_{PGSp(4,q)}(\sigma)\right| = 2q^2(q^4-1).$$

Therefore the canonical regular-spread orbit has size

$$\boxed{\frac{|PGSp(4,q)|}{|C_{PGSp(4,q)}(\sigma)|} = \frac{q^2(q^2-1)}{2}.}$$

This proves the orbit-size formula for every odd q and recovers the complete computational values

$$36, \quad 300, \quad 1176$$

at $q = 3, 5, 7$. It does not promote the all-q rank-three intersection graph, and it does not classify non-Desarguesian symplectic spreads.

At $q = 3$, the established inner spread stabilizer is S_6 of order 720, so the full stabilizer is

$$\boxed{C_{PGSp(4,3)}(\sigma) \cong C_2 \times S_6.}$$

The central $C_2 = \langle\sigma\rangle$ is silent on the local spread graph; the visible quotient S_6 is the automorphism group of the Kneser local graph $K(6,2)$ and its Johnson second subconstituent $J(6,3)$.

The shared phase-inversion controller

The geometric/representation clock has presentation $C_4 : C_2 \cong D_4$, while the earlier μ_6 clock has presentation $C_6 : C_2 \cong D_{12}$. If the clocks are independent apart from their common outer inverter, their combined controller is

$$\Gamma = (C_4 \times C_6) : C_2, \qquad |\Gamma| = 48,$$

where the last factor acts by simultaneous inversion. Exact enumeration gives

$$Z(\Gamma) \cong C_2^2, \qquad [\Gamma,\Gamma] \cong C_6, \qquad \Gamma_{\mathrm{ab}} \cong C_2^3.$$

The subgroups D_4 and D_{12} intersect in their common inverter and generate Γ. Although $|\Gamma| = 48$, it is not the frame stabilizer $C_2 \times S_4$: their center and derived-subgroup orders are respectively $(4,6)$ and $(2,12)$.

All statements in this insert are finite-geometric or group-theoretic. The order-48 synthesis assumes clock independence, is not a physical coupling, and restores none of the withdrawn charge, colour, generation, flux, or particle identifications.

Exact continuation: all-q regular spreads and the faithful phase controller

For every odd prime power q, the regular symplectic spreads may be represented as elliptic hyperplane sections $\mathcal{O}_x = Q(4,q) \cap x^{\perp}$, indexed by minus-type anisotropic points. The projective Gram determinant

$$\Delta(x,y) = 4Q(x)Q(y) - B(x,y)^2$$

is zero precisely for a tangent intersection. Consequently, distinct regular spreads meet in exactly 1 or $q+1$ lines. The $q+1$ relation is strongly regular with

$$v = \frac{q^2(q^2-1)}{2}, \qquad k = \frac{q(q-2)(q^2+1)}{2},$$

$$\lambda = \frac{q(q^3 - 4q^2 + 7q - 8)}{2}, \qquad \mu = \frac{q(q-2)(q-1)^2}{2},$$

and nontrivial eigenvalues $q(q-2)$ and $-q$. This proves the regular-spread formula conjectured after the complete $q = 3, 5, 7$ computations. It is a strongly-regular two-class fusion; for $q > 3$ the full group action need not have rank three.

Regularity is essential. An exact $q = 27$ Ree–Tits slice calculation gives a closed 144-spread regular suborbit whose intersections with the fixed non-Desarguesian spread have sizes

$$19,\ 28,\ 37,\ 46,\ 55,$$

so the regular $\{1, q+1\}$ scheme does not extend unchanged.

The quadratic target audit also corrects the actual signed-edge multiplicities:

	15	24	30	81
$\mathrm{Sym}^2(90)$	3	5	3	7
$\Lambda^2(90)$	0	0	2	5

Thus both gauge blocks are absent from the antisymmetric channel. The seven previously constructed tensors remain explicit surjective generators, not full bases of every intertwiner space.

Finally, the abstract independent-clock group $(C_4 \times C_6) : C_2$ has order 48, but its action on the canonical single complex structure factors through

$$(a, b, e) \longmapsto (3a + 2b \bmod 12, e),$$

with kernel generated by $(2, 3, 0)$. The faithful image on the canonical 90-sector is therefore $C_{12} : C_2$ of order 24. A faithful order-48 controller requires two independent complex phase registers.

The repository includes literal SystemVerilog masks for the 36-lane mixer and an algebraic verifier of $A^2 = 9I + 6J$, fixed-width safety, and the phase quotient. No synthesis, timing, fabrication, particle assignment, or measured coupling is claimed.

Divisible ovoid codes, complete quadratic maps, and Weil inversion

The complete q=27 Ree–Tits hyperplane spectrum is

$$1^{730},\quad 10^{4563},\quad 19^{96174},\quad 28^{408294},\quad 37^{36504},\quad 46^{4914},\quad 55^{702}.$$

All section sizes are 1 mod 9. Equivalently, the homogeneous coordinates generate an exactly 9-divisible projective $[730, 5]_{27}$ code. Complete censuses for the regular, Kantor, Thas–Payne and Ree–Tits q=27 families give pairwise distinct weight enumerators. The regular elliptic section gives a 27-divisible $[730, 4]_{27}$ code, whereas the three nonregular examples give exactly 9-divisible $[730, 5]_{27}$ codes.

The full $PSp(4, 3)$-equivariant quadratic map dimensions from the canonical 90 are

	15	24	30	81
$\mathrm{Sym}^2(90)$	3	6	5	12
$\Lambda^2(90)$	3	4	5	12.

Thus the complete quadratic space has dimension $26 + 24 = 50$. The outer similitude splits it into two equal 25-dimensional sectors. The outer-even half is exactly the earlier target-identified

PGSp table; the outer-odd half supplies the missing PSp-equivariant maps. Explicit integral signed-orbit representatives form complete bases; exact reduction modulo a characteristic not dividing the group order certifies independence and surjectivity, while the dimensions are fixed independently by characters.

For $q = 7$ and $q = 11$, the canonical Schrödinger Weil representations on functions on $\mathbb{F}_q^2$ split into parity dimensions

$$(25, 24) \quad \text{and} \quad (61, 60).$$

The nonsquare similitude $h = \mathrm{diag}(I_2, -I_2)$ is implemented by entrywise complex conjugation. On realification, complex multiplication J and conjugation K obey

$$J^2 = -I, \qquad K^2 = I, \qquad KJK = -J,$$

and generate D_4. This is an objectwise theorem for the canonical Weil family and is not a dimension-based identification with the q=3 signed-edge 90.

A packed SystemVerilog implementation, deterministic Icarus simulation, exhaustive Yosys SAT properties for $A^2 = 9I + 6J$ and the faithful D_{24} action, and explicit $W = 4$ iCE40/ECP5 synthesis scripts are included. Tool results are engineering evidence for the specified RTL only; no fabricated-device timing, power, physical coupling or particle assignment is claimed.

Controller representation trichotomy: orders 48, 24, and infinity

There are three controller objects in the preceding construction, not one. The abstract common-inverter group

$$\Gamma = (C_4 \times C_6) : C_2$$

has order 48. It has the faithful integral four-dimensional realization

$$A_4 = \begin{pmatrix} 0 & -1 & 0 & 0 \\ 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 1 \end{pmatrix}, \quad B_6 = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & -1 & 1 \end{pmatrix},$$

$$S = \begin{pmatrix} 0 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 \end{pmatrix},$$

for which $[A_4, B_6] = 1$, $SA_4S = A_4^{-1}$, and $SB_6S = B_6^{-1}$. Exact rational-character and cyclotomic checks show that its minimal faithful rational degree is 4.

The canonical single-complex-structure action is instead the quotient

$$(a, b, e) \longmapsto (3a + 2b \bmod 12, e), \qquad \mathrm{im} \cong C_{12} : C_2,$$

of order 24, with kernel $\{(0, 0, 0), (2, 3, 0)\}$. Thus the full order-48 group requires two independent two-dimensional phase registers.

The rank-three matrices R_4, U_6 from the integral multiplicity carrier form a third object. Their phase planes overlap, so they do not commute and generate $SL_3(\mathbb{Z})$. More strongly, the simultaneous common-inverter equations

$$XR_4 = R_4^{-1}X, \qquad XU_6 = U_6^{-1}X$$

have coefficient-matrix rank 9 and nullity 0 over $\mathbb{Q}$. Hence no nonzero rational common inverter exists.

The same generator word exposes the change of dynamics:

$$\chi_{A_4^2B_6}(t) = (t+1)^2(t^2-t+1), \qquad |A_4^2B_6| = 6,$$

whereas

$$\chi_{R_4^2U_6}(t) = (t+1)(t^2-t-1), \qquad |R_4^2U_6| = \infty.$$

The latter has spectral radius φ. Therefore the golden ratio belongs to the infinite arithmetic lattice action, not to the finite controller or its canonical single-J quotient. It is not a selected physical observable without an additional operational map.

The complete quadratic map space as an S_3-module

The complete Pass-2301 basis of fifty $PSp(4,3)$-equivariant quadratic maps from the signed-edge 90 carries a simultaneous phase action r and outer involution s satisfying

$$r^3 = s^2 = 1, \qquad srs = r^{-1}.$$

Thus the multiplicity spaces form a module for $C_3 : C_2 \cong S_3$. Exact GAP character decomposition gives

$$\mathcal{H}_{\mathrm{Sym}} \cong 13\,\mathbf{1} \oplus 3\,\mathrm{sgn} \oplus 5\,\mathrm{std},$$

$$\mathcal{H}_{\Lambda} \cong 3\,\mathbf{1} \oplus 13\,\mathrm{sgn} \oplus 4\,\mathrm{std},$$

and hence

$$\mathcal{H}_{\mathrm{quad}} \cong 16\,\mathbf{1} \oplus 16\,\mathrm{sgn} \oplus 9\,\mathrm{std}.$$

The associated characters on $(1), (123), (12)$ are $(26, 11, 10)$, $(24, 12, -10)$, and $(50, 23, 0)$.

This one decomposition explains both frozen dimension ledgers. A reflection has one eigenvalue of each sign on every standard copy, so

$$\dim \mathcal{H}_+ = 16 + 9 = 25, \qquad \dim \mathcal{H}_- = 16 + 9 = 25.$$

The one-dimensional representations are fixed by C_3, while the nine standard copies give eighteen rotating dimensions, so

$$50 = 32_{C_3\text{-fixed}} + 18_{C_3\text{-rotating}}.$$

The order-six phase on the 90 reduces to order three on bilinear inputs because its central sign acts twice. This is an exact representation-theoretic logic reduction. The fifty maps are not physical couplings, and the multiplicities 16 and 9 are not identified with unrelated W33 counts.

Passes 2309–2315: resolution quotient, quadratic compiler, spread boundaries, and controller fork

The complete 720-element nonlinear cover-signature quotient admits nine globally realized signatures satisfying

$$\sum_{i=1}^{9} t_i = 12\mathbf{1}_{45}.$$

Thus this quotient does not obstruct a nine-cover resolution. This is only a necessary-condition witness: compatible frame representatives have not been produced, and $\chi(H) = 9$ remains open.

The fifty complete $PSp(4,3)$-equivariant quadratic basis maps are generated by twenty-four distinct signed-orbit tensors. Caching each orbit once reduces literal orbit-entry storage from 1,213,920 to 583,200, an exact factor 281/135. This is representation-storage sparsity, not a claim of spatial locality or minimal tensor rank.

For the regular-spread orbit, the recorded $(q+1)$-relation valency can be one point-stabilizer orbital only for odd $q = 3, 5$. Indeed,

$$|H| = 2q^2(q^4-1), \qquad k = \frac{q(q-2)(q^2+1)}{2},$$

and $k \mid |H|$ forces $q-2 \mid 24$. In particular the exact $q = 7$ strongly regular graph is not a rank-three $PGSp(4,7)$ permutation action.

A direct non-Desarguesian control over $\mathbb{F}_9$ compares the regular spread $g = -nx$ with the Kantor spread $g = -nx^3$. Both are verified symplectic spreads of $PG(3,9)$, but they share exactly

$$1 + 9 \cdot 3 = 28$$

lines. Hence the regular-family intersection values 1 and $q+1$ are not universal among symplectic spreads.

The committed 36-lane spread-mixer satisfies

$$A^2 = 9I + 6J,$$

and the canonical single-J controller is frozen by all 1,152 input transitions. Finally, the overlapping arithmetic generators reduce modulo two to the $(2,3,7)$ Fano group $GL(3,2)$, whereas the quadratic-Hom multiplicity controller is the $(2,3,2)$ group S_3. These are distinct typed control modes, not quotient descriptions of one carrier.

No withdrawn electric-charge, flux, colour, generation, or neutrino interpretation is restored. The hardware statements are semantic reference contracts, not synthesis or device measurements.

Syndrome merging, shell orbitals, and the tomotope 192 selector obstruction

A corrected seven-bit syndrome-first external merge reproduces the frozen 28-shard census and extends it to 120 primitive shards. At cutoff $B = 16$ it merges 233,088,428 records into 179,498,008 syndrome groups and detects 43,428,489 cross-shard collision pairs. This covers 3.741% of the fixed-coordinate chart and does not yet define the global U_6 coefficient.

The five exceptional-S_6 minimum-shell fibers of sizes

$$180, \quad 120, \quad 45, \quad 180, \quad 15$$

support a full orbital coherent configuration of rank 527. Its adjacency algebra is noncommutative, has 216,244 nonzero structure constants and center dimension 11. The rank identity is independently recovered as the sum of squares of the eleven S_6 multiplicities.

The frame-to-duad ABI contains an invertible 15×15 anchor submatrix, while two anchor frames already form a pointwise S_6 base. Since every W33 edge lies in nine frames, nine-colouring is equivalently a 240-clique exact-cover problem with 4,860 binaries and 2,700 equalities. A bounded run remains inconclusive, so $\chi(H) = 9$ is open.

The first common finite quotient between the arithmetic $\mathrm{SL}_3(\mathbb{Z})$ carrier and the residual tetrahedral shell is S_4: it appears as the mod-two point parabolic, as the projective Levi quotient of the mod-three parabolic, and as the S_4 quotient of the residual-duad stabilizer $S_2 \times S_4$.

Full $PSp(4,3)$ equivariance closes the linear E_8-to-coexact question negatively:

$$\mathrm{Hom}_{PSp}(8,90) = 0, \qquad \mathrm{Hom}_{PSp}(90,8) = 0.$$

This does not exclude proper-subgroup or nonlinear correspondences.

Finally, the 2,880 curved events admit three exact residual-duad incidence relations, each of degree 96 at every one of the 15 duads. One tomotope flag orbit also has size 96, and any two relations give 192 incidences per duad. The new obstruction is therefore a selector problem: the geometry supplies three natural 96-layers but the tomotope has two flag orbits. No canonical choice of two, labelled flag bijection, or disjoint 15×192 packet decomposition is asserted.

Passes 2410–2415: five exact frontiers

The curved-event/residual-duad atlas now has a canonical tomotope selector: the two tie profiles are exactly the profiles of event-side duad valency two. At every residual duad they give $96 + 96 = 192$ incidences, and three-point overlap splits the local carrier into eight 24-element components, each containing twelve flags from each layer. The eight neighboring duads have the natural unordered $4 + 4$ endpoint split.

The global equal-syndrome pair merge is also closed algebraically. If a codeword has weight $w \in \{4, 6, 8, 10, 12\}$, then its weight-six error pairs number $\frac{1}{2}\binom{w}{w/2}\binom{240-w}{6-w/2}$. The exact low-weight enumerator therefore gives 1,724,138,884,380 global collision edges. The remaining U_6 operation is union/deduplication of overlapping marks, not pair enumeration.

The literal nine-colour problem remains open. The complete fixed-frame first-colour domain contains 394,200 covers, independently reproducing the earlier census, while the exact all-different search returned `UNKNOWN` under its bounded run.

Forgetting the chosen six-line pack fuses the rank-527 exceptional-S_6 shell configuration exactly to the rank-22 full-$\mathrm{PGSp}(4,3)$ orbital configuration. Its center has dimension ten and its Wedderburn blocks have sizes 1^6 and 2^4.

Finally, the integral eight-dimensional E_8 carrier belongs naturally to $2.U_4(2)$, whereas the coexact 90 factors through $U_4(2)$. The central involution acts by $-I$ and $+I$, respectively, so every intertwiner vanishes on every lifted subgroup containing the center, including the full preimage of the common quotient-level S_4 packet.

2 Five exact frontiers: tomotope labelling, singleton identifiability, signature compatibility, shell fusions, and split-subgroup intertwiners

Labelled tomotope obstruction. The canonical two tie layers of the curved-event/residual-duad incidence give a local carrier of size $96 + 96 = 192$. Its fixed-duad stabilizer is $C_2 \times S_4$ and has four regular orbits of size 48. On the complete intrinsic ordered-pair relation of the 192 events, all twenty order-96 orbit-exchange extensions are isomorphic to $C_2^2 \times S_4$, with element-order spectrum

$$1^1\, 2^{39}\, 3^8\, 4^{24}\, 6^{24}.$$

The archived labelled tomotope symmetry instead has spectrum

$$1^1\,2^{15}\,3^{32}\,4^{24}\,8^{24}.$$

Thus the exact $192 = 96 + 96 = 8 \cdot 24$ and unordered $4 + 4$ correspondences do not lift to the archived labelled rank-four maniplex without forgetting intrinsic relations or adding noncanonical structure.

Global U_6 identifiability boundary. For weight-six syndrome multiplicities n_m, the exact pair ledger fixes

$$\sum_m m n_m = 249{,}219{,}381{,}880, \qquad \sum_m \binom{m}{2} n_m = 1{,}724{,}138{,}884{,}380,$$

and therefore

$$\sum_m m^2 n_m = 3{,}697{,}497{,}150{,}640.$$

These first two factorial moments do not determine n_1: the distributions $n_2 = 3$ and $(n_1, n_3) = (3, 1)$ both have six representatives and three collision pairs. The remaining global computation is therefore an idempotent bitmap union, not another pair sum. A deterministic 4096-shard OR-and-popcount contract is frozen for the 6,230,484,547 fixed-chart ranks.

The selected nine-signature tuple is impossible. The nine exact cover fibers of Pass 2416 have sizes

$$11664, 11664, 864, 11664, 2808, 288, 2808, 864, 288.$$

An independent exact-cover reconstruction of fibers 1 and 8 checks all

$$11664 \cdot 288 = 3{,}359{,}232$$

pairs and finds no frame-disjoint pair. Hence the selected balanced nine-signature tuple admits no nine-cover transversal. At this pass the global decision remained open; the later complete cover-link computation of Pass 2551 ruled out every nine-cover resolution and proved $\chi(H) \geq 10$.

Exact commutative fusion lattice. Closing all 65,535 binary symmetric seeds of the rank-22 full-PGSp$(4, 3)$ orbital algebra gives sixteen distinct coherent closures, fifteen of which are commutative. Their ranks are

$$3^3,\ 4^5,\ 5^3,\ 6,\ 7,\ 8,\ 9.$$

The three rank-three schemes are $135K_4$, $45K_{12}$, and $36K_{15}$. The unique finest commutative fusion has rank nine and valencies

$$1, 256, 24, 128, 48, 48, 8, 3, 24.$$

First nonzero split-subgroup intertwiner. The full lifted carriers have opposite central characters, but the distinguished order-five subgroup avoids the center. The faithful real eight-dimensional E_8 carrier restricts to C_5 with multiplicities

$$(0, 2, 2, 2, 2),$$

while the coexact 90 restricts with multiplicities

$$(18, 18, 18, 18, 18).$$

Consequently

$$\dim \mathrm{Hom}_{C_5}(E_8, 90) = \dim \mathrm{Hom}_{C_5}(90, E_8) = 144.$$

This is an existence theorem for a large symmetry-broken Hom space, not a canonical map or physical coupling.

2.1 Five exact frontier results: syndrome union, asymmetric covers, the rank-nine scheme, tomotope obstruction, and the Sylow-five normalizer

The syndrome-first union reducer has been executed on two, four, and eight overlapping fixed-triple shards. In the largest run, 17,525,360 records reduce to 16,762,010 distinct representatives, with 5,407,125 collision-marked and 11,354,885 singleton representatives. The overlap multiplicities obey $\binom{n}{d}\binom{238-n}{4-d}$ exactly. This validates the distributed idempotent union operation but does not replace the outstanding full 4096-shard bitmap computation.

For the nine-cover problem, all signature-sum trades replacing at most four entries of the selected nine-tuple were classified. There are no two-trades, three three-trades, and eleven four-trades. Exact reconstruction of 43 signature fibers and all 903 pair relations shows that every candidate contains a pair of fibers with zero frame-disjoint cover pairs. Thus the selected tuple has no lift anywhere in its complete radius-four trade neighborhood, although $\chi(H) = 9$ remains open outside that neighborhood.

The unique finest binary-generated commutative fusion of the full-$PGSp(4,3)$ shell algebra is a symmetric association scheme of rank nine, with valencies

$$(1, 256, 24, 128, 48, 48, 8, 3, 24)$$

and multiplicities

$$(1, 15, 15, 20, 162, 135, 108, 24, 60).$$

It is neither P-polynomial nor Q-polynomial. Its canonical imprimitivity layer is $45K_{12}$, refined into $45K_{4,4,4}$ and $135K_4$.

The natural center-preserving one-leaf-change graph on the selected curved-event 192 is biregular with degree split $2^{96}5^{96}$ and eight components of order 24. Exhausting all 15 nonempty unions of the archived rank colours shows that none reproduces this profile. Hence this principled quotient is not the archived tomotope-like rank adjacency system.

Finally, the Sylow-five normalizer in $Sp(4,3)$ is the nonsplit group 5:8. Its center acts by -1 on the 144-dimensional C_5-equivariant Hom space, and a lifted normalizer generator satisfies $T^4 = -I$. The space is therefore 36 copies of the relevant faithful four-dimensional module and contains no normalizer-invariant map. The projective 5:4 block appears only after forgetting the central sign.

Passes 2550–2557: seven-front breakthrough packet

The global lower shadow of the weight-six syndrome problem is exactly the image of the weight-four errors and contains 91,007,752 syndromes. Sixty-three explicit singleton witnesses lie in disjoint regular $PGSp(4,3)$ orbits, proving at least 3,265,920 global singleton fibers. The exact coefficient remains open.

The frozen frame labelling is reconstructed from the intrinsic 45-octet graph. The complete 3,547,800-cover census is reproduced, and every one of its 327 orbit-representative disjointness links is K_8-free. Consequently the 540-frame graph has no nine-colouring and $\chi(H) \geq 10$. A proper fourteen-colouring gives $10 \leq \chi(H) \leq 14$.

The rank-nine imprimitivity tower is decoded as 45 geometric $K_{4,4}$ octets, each carrying one parity half of its perfect matchings, an A_4 torsor. The three V_4 cosets give $3K_4$, their cross relation gives $K_{4,4,4}$, and the union is K_{12}. Finally, the syndrome columns themselves triangle-decompose the same $\mathrm{SRG}(45, 32, 22, 24)$ and satisfy $HH^T = 16I + A_{45}$.

For the nonsplit 5:8 normalizer module, scalar invariants first occur as two quartics, while four cubic equivariant self-maps survive. This opens a nonlinear projective channel without weakening the full-group linear obstruction.

Passes 2560–2567: singleton orbits, chromatic compression, exact character fusion, and octet quotients

The global weight-six singleton coefficient is nonzero in at least 263 disjoint regular $PGSp(4, 3)$ orbits, hence

$$U_6^{\mathrm{singleton}} \geq 263 \cdot 51840 = 13{,}633{,}920.$$

The 540-frame graph admits a literal proper eleven-colouring, while the complete cover-link calculation excludes nine colours; therefore

$$10 \leq \chi(H) \leq 11.$$

Exact rational central projectors in the rank-32 $PSp(4, 3)$ orbital algebra resolve the rank-nine fusion as

$$162 = 81 + 81, \qquad 135 = 60 + 15 + 30 + 30, \qquad 108 = 64 + 24 + 20, \qquad 60 = 30 + 30,$$

correcting the former tentative $135 = 15{+}4{\cdot}30$ assignment. For the faithful four-dimensional $2.U_4(2)$ module, the cubic 5:8 covariants do not extend to the full group; the first nontrivial full-group nonlinear self-covariant is unique in degree seven. Finally, the common octet edge-phase carrier gives four exact tight frames in dimension twenty. Its mod-two quotient is the abstract Schlaefli 27-line/45-tritangent incidence, while its mod-three quotient has exactly 360 residue classes and one universal within-class difference type. No equality for the full U_6 singleton coefficient, ten-colouring, algebraic cubic-surface coordinates, or carrier-level physical septic map is asserted.

Exact controlled-add instruction and its fixed W33 line

The first two-register instruction is the qutrit controlled-add gate

$$\mathrm{CX}_{p \to f} |p, f\rangle = |p, f + p \pmod 3\rangle.$$

On Pauli-frame coordinates (x_p, z_p, x_f, z_f), its exact action is

$$(x_p, z_p, x_f, z_f) \mapsto (x_p, z_p - z_f, x_f + x_p, z_f).$$

The corresponding matrix preserves the standard symplectic form, has order three, and satisfies $(M - I)^2 = 0$ with $\mathrm{rank}(M - I) = 2$. Thus it is a rank-two Lagrangian unipotent of Jordan type $2 + 2$, not a rank-one transvection. Its image and kernel coincide in one totally isotropic two-space, so its projective fixed set is exactly one line of $W(3, 3)$. The induced cycle profiles on points, lines, flags, and collinearity edges are respectively

$$1^4 3^{12}, \qquad 1^7 3^{11}, \qquad 1^{10} 3^{50}, \qquad 1^6 3^{78}.$$

The six fixed edges are precisely the six edges of the fixed line's K_4. The seven fixed lines are the axis plus two three-line pencils attached at two axis points. Among all elements of $\mathrm{Sp}(4,3)$ with this same order, rank and square-zero Jordan data, there are two conjugacy classes. Their line actions and centralizers are

$$\begin{array}{c|c|c} 1^1 3^{13} & 240 & 216 \\ 1^7 3^{11} & 480 & 108. \end{array}$$

The controlled-add gate is in the second class. Hence the six-line fixed fringe is an exact W33 identifier for the gate's symplectic conjugacy class.

Finally,

$$\mathrm{CX}_{p\to f}(F_3 \otimes I)|00\rangle = 3^{-1/2}(|00\rangle + |11\rangle + |22\rangle),$$

and the exact generator closure is

$$\langle F_p, F_f, S_p, S_f, \mathrm{CX}_{p\to f}\rangle = \mathrm{Sp}(4,3), \qquad |\mathrm{Sp}(4,3)| = 51840.$$

These statements are certified by exhaustive ternary and finite-geometric tests. The RTL models the exact data and Pauli-frame transformations. A deterministic physical qutrit SUM has also been demonstrated inside one photon using frequency as control and time as target (Imany et al., *npj Quantum Information* 5, 59 (2019), DOI 10.1038/s41534-019-0173-8), with computational-basis fidelity 0.92 ± 0.01. The remaining hardware boundary is the implementation-specific loss/process budget and the protected M_{36} magic-state pipeline, not the SUM principle itself.

Bidirectional SUM, its centralizer, and the completed digital ISA

Let T denote the left–right transpose in the standard Pauli-frame coordinates. It is anti-symplectic,

$$T^2 = I, \qquad T^{\mathsf{T}} J T = -J,$$

and reverses the controlled-add gate:

$$T\ \mathrm{CX}_{p\to f}\ T^{-1} = \mathrm{CX}_{f\to p}\,.$$

No second entangling primitive is needed, because the exact local-Clifford identity is

$$\mathrm{CX}_{f\to p} = (F_p F_f^{-1})\,\mathrm{CX}_{p\to f}(F_p^{-1} F_f).$$

The controlled-add centralizer is determined constructively as

$$C_{\mathrm{Sp}(4,3)}(\mathrm{CX}) \cong C_6 \times C_3 \times S_3.$$

Its S_3 factor acts regularly on the six external fixed lines of the CX fringe, while the central factors preserve the two three-line pencils.

The complete exact gate atlas has 34 conjugacy classes and records cycle profiles on the 40 points, 40 lines, 160 flags, 240 collinearity edges, and 1620 apartments. These five projective carriers produce 15 distinct geometric signatures; the central-lift, inverse, and transpose metadata are therefore retained to decode the exact $\mathrm{Sp}(4,3)$ class.

A correction to the earlier physical boundary is required. Imany et al. demonstrated a deterministic single-photon time–frequency modulo-SUM gate in *npj Quantum Information* 5, 59 (2019), DOI 10.1038/s41534-019-0173-8; their qutrit realization reported computational-basis fidelity 0.92 ± 0.01 and produced $3^{-1/2}(|00\rangle + |11\rangle + |22\rangle)$. Thus the Holonet logical gate compiles

directly by mapping the control register to frequency and the target register to time. The open hardware boundary is no longer the SUM principle; it is the protected M_{36} preparation, injection, decoding, and threshold stack.

Finally, all eight ISA entries now have a digital contract. The four local Clifford instructions, bidirectional CX, and $\sigma^5 = Z$ update the Pauli frame exactly; the mirror instruction multiplies an independent D_{12} bus state; and the M_{36} instruction is a typed request for one of 36 rays, exports the canonical BT822 deep/mid/shallow grade metadata with census $8 + 24 + 4$, and retires only after an external preparation block asserts acknowledgement. This last handshake preserves the evidence boundary instead of inventing a non-Clifford unitary.

The M36 factory, complete controller, and a remote qutrit SUM

Every one of the thirty-six Witting resources has exactly one dark mode and three active modes of equal magnitude. Consequently the entire library is prepared by one balanced three-mode splitter, a four-way dark-mode selector, and sixth-root phase controls. The exact ROM reproduces the $8 + 24 + 4$ deep/middle/shallow census. The controller types these states as ququart resources and fails closed before injection unless an independently verified ququart code or encoding map is supplied; qutrit distillation thresholds are not silently transferred to M36.

The complete eight-opcode controller, D_{12} transport law, bidirectional SUM, M36 pipeline, and remote feed-forward sequencer are synthesizable and exhaustively tested at the RTL contract level. An iCE40 HX8K workflow supplies independent synthesis, place-and-route, utilization, and timing evidence. Until that workflow concludes, the placed implementation remains remote pending; the local switching census is a power proxy, not a watt estimate.

For two network nodes, share

$$|\Phi_3\rangle_{ab} = 3^{-1/2} \sum_{j=0}^{2} |j, j\rangle$$

in frequency link modes. Alice applies the reverse local SUM from her time-bin data to a, measures a with outcome m, and sends one trit. Bob applies $X^{-m}F^2$ to b, uses the physical frequency-to-time SUM on his data, measures b in the Fourier basis with outcome n, and sends one trit. Alice records Z^n. All nine branches implement

$$|x, y\rangle \mapsto |x, y + x \pmod 3 angle$$

with no postselection loss beyond obtaining the heralded shared pair. The exact resource cost is one qutrit Bell pair and two classical trits. Fiber, coupling, local-optics, and detection losses enter as flagged erasures through

$$R_{\text{gate}} = R_{\text{pair}} 10^{-\alpha(L_A+L_B)/10} \eta_{cA}\eta_{cB}\tau_A\tau_B\eta_{dA}\eta_{dB}.$$

This is an exact protocol and engineering budget, not a claim of a completed combined remote-gate experiment or a fault-tolerance threshold.

3 The binary tetrahedron inside the ternary machine

The four frame coordinates carry a canonical binary coarse address. For a projective ternary point

$$[x] = [x_1 : x_2 : x_3 : x_4] \in PG(3, 3),$$

define

$$\pi([x]) = (\mathbf{1}_{x_1 \neq 0}, \ldots, \mathbf{1}_{x_4 \neq 0}) \in \mathbb{F}_2^4 \setminus \{0\}.$$

The fifteen nonzero binary masks are the fifteen simplicial cells of a tetrahedron: four vertices, six edges, four faces and one body. The map is well-defined projectively because multiplication by -1 preserves support.

Exact phase-capacity law. If a mask S has weight w, then

$$\boxed{|\pi^{-1}(S)| = 2^{w-1}.}$$

Therefore

$$(4, 6, 4, 1) \odot (1, 2, 4, 8) = \boxed{(4, 12, 16, 8)}.$$

Thus the tomotope f-vector is the exact rank-by-rank capacity profile of the ternary projective lift of the binary tetrahedron. This is a capacity theorem; it does not by itself identify the quotient incidence object with the abstract tomotope.

Equitable W33 quotient. A perfect matching of the four tetrahedral vertices determines a standard symplectic coordinate pairing. There are three such matchings. For each one, the fifteen support fibers form an equitable partition of the W33 collinearity graph. If Q is the quotient and $s_S = 2^{|S|-1}$, then

$$\operatorname{spec}(Q) = 12^1 \oplus 2^9 \oplus (-4)^5, \qquad \operatorname{diag}(s)Q = Q^{\mathsf{T}} \operatorname{diag}(s),$$

and

$$\boxed{Q^2 = 8I - 2Q + 4\mathbf{1}s^{\mathsf{T}}.}$$

The full spectrum $12^1 \oplus 2^{24} \oplus (-4)^{15}$ consequently splits into a fifteen-dimensional binary-support sector and a twenty-five-dimensional internal ternary-phase sector with residual spectrum

$$\boxed{2^{15} \oplus (-4)^{10}.}$$

Selector consequence. The tetrahedral symmetry group S_4 acts transitively on the three perfect matchings. A matching stabilizer is the nonabelian group D_8 of order eight, so

$$\boxed{24 = 8 \cdot 3 = |S_4| = |D_8|\,[S_4 : D_8].}$$

Moreover, the four Type-A selector masks

$$1110, \quad 1101, \quad 1011, \quad 0111$$

are exactly the four tetrahedral face masks. Hence the twelve admissible Type-A/Fano sheets have the intrinsic parameter set

$$\{\text{four tetrahedral faces}\} \times \{\text{three symplectic pairings}\}.$$

An objectwise intertwiner to the existing 2160×160 selector matrices is a separate verification target.

Machine use. The result supplies a support-first frame codec: first decode the fifteen-state binary occupancy shell, then decode the within-fiber ternary phase. The exact verifier and frozen certificate are `analysis/bt2808_pg32_tetrahedral_support_lift.py` and `data/PART_BT2808_PG32_TETRAHEDRAL_SUPPOR`

Passes 2809–2815: tetrahedral support shell, tomotope incidence, and all-q closure

The support projection of Pass 2808 now closes objectwise. The four weight-three masks are exactly the four Type-A selector masks and the three perfect matchings are exactly the three Fano channels. Their Cartesian product is the existing twelve-sheet selector atlas: twelve distinct signed 2160×160 operators, all of rank 81.

More strongly, the projective signed support classes $\{0, \pm 1\}^4 / \{v \sim -v\}$ carry an explicit tomotope incidence model. Ranks $0, 1, 2$ are signed restrictions of support weights $1, 2, 3$. Four cells are the three-support hemioctahedra and four are the positive-product full-support tetrahedra. The resulting object has

$$(f_0, f_1, f_2, f_3) = (4, 12, 16, 8), \qquad |\mathcal{F}| = 192,$$

automorphism group order 96, two flag orbits of size 96, and symmetry class $2_{\{0,1,2\}}$; only the cell move exchanges the flag orbits.

The same support shell yields an exact codec. The 81 affine frame states are enumerated by seven bits and the 40 nonzero projective classes by six bits. The code factors through the four-bit support mask and the relative sign phase, with exhaustive round trips and frozen transition tables for F_p, $\mathrm{CX}_{p \to f}$, $\mathrm{CX}_{f \to p}$ and Z_p.

For every finite field $\mathbb{F}_q$, including even and odd prime powers, the support fibers form an equitable partition of the point graph $W(3, q)$. Put $s_S = (q-1)^{|S|-1}$, let τ be the chosen coordinate matching, and set $r = |T \cap \tau(S)|$. With

$$N_r(q) = \frac{(q-1)^r + (q-1)(-1)^r}{q},$$

the quotient entries are

$$Q_{S,T} = \frac{(q-1)^{|T|-r} N_r(q)}{q-1} - \delta_{S,T}.$$

They satisfy

$$\operatorname{spec}(Q) = q(q+1)^1 \oplus (q-1)^9 \oplus (-(q+1))^5,$$
$$\operatorname{diag}(s) Q = Q^{\mathsf{T}} \operatorname{diag}(s), \qquad Q^2 = (q^2-1)I - 2Q + (q+1)\mathbf{1}s^{\mathsf{T}}.$$

For the matching stabilizer D_8, the three sectors decompose as

$$A_1, \qquad 3A_1 + B_1 + B_2 + 2E, \qquad A_1 + 2B_1 + E.$$

Two further exact consequences emerged. First, the unbiased random walk on $W(3, q)$ is strongly lumpable through the support map. Its quotient spectrum is

$$1^1 \oplus \left(\frac{q-1}{q(q+1)}\right)^9 \oplus \left(-\frac{1}{q}\right)^5,$$

so its absolute relaxation rate is $1/q$. Second, the eight full-support sign classes form a parity-code controller: the even $[3, 2, 2]$ words label the four tetrahedra, while every odd word has a unique

minority coordinate whose deletion labels one hemioctahedron. The sixteen triangular faces are exactly the edges of the resulting $K_{4,4}$ cell-incidence graph.

All statements are finite exact theorems. The random-walk result is not a physical dynamics law, and the RTL area/timing claims remain pending until the dedicated synthesis workflow is observed. Reproduce with `python analysis/bt2809_2815_release.py -verify-frozen` and `pytest -q tests/test_bt2809_2815_seven_frontiers.py`.

3.1 Post-2808 hardware and manuscript truth closure

Public ISA versus internal micro-ISA. The public Holonet interface remains the eight-opcode, three-bit instruction set. The minimal internal frame engine uses only

$$F_p, \qquad \mathrm{CX}_{p\to f}, \qquad \mathrm{CX}_{f\to p}, \qquad Z_p,$$

so its opcode register needs two bits. These four operations generate the full linear frame group of order 51,840 and, after adjoining translations, the affine group of order $81 \cdot 51{,}840 = 4{,}199{,}040$. The measured 72-LC, 60.80-MHz result belongs to the loadable public full-frame unit; it is not reused as synthesis evidence for the minimal four-operation engine.

Deep-grade M_{36} distillation. The exhaustive search over all 5,355 binary $[[4, 2]]$ stabilizer projectors, all four syndromes, and all 11,520 logical Clifford decoders finds no improving branch for the shallow or either middle grade, but exactly 48 improving deep-grade branches. One explicit branch takes input ray 5, stabilizers IYZY and YZXY, syndrome $(-1, +1)$, a Hadamard on the second logical coordinate, and output ray 7. Its exact operating curve is

$$P_{\mathrm{succ}} = \frac{p^2 - 2p + 2}{4}, \qquad F_{\mathrm{out}} = \frac{5p^2 - 12p + 8}{4(p^2 - 2p + 2)},$$

with

$$F_{\mathrm{out}} - F_{\mathrm{in}} = \frac{p(p-1)(3p-2)}{4(p^2 - 2p + 2)}.$$

Hence fidelity improves for $0 < p < 2/3$. This supersedes the earlier arbitrary-decoder no-go. It is a state-fidelity distillation theorem, not a fault-tolerant injection threshold or asymptotic-yield claim.

Support for readout, phase for execution. The $\mathrm{PG}(3, 2)$ support shell remains an exact geometric/equitable codec, with tetrahedral capacity identity

$$(4, 6, 4, 1) \odot (1, 2, 4, 8) = (4, 12, 16, 8).$$

It is not a deterministic execution quotient. The frame states $(0, 1, 0, 0)$ and $(0, 2, 0, 0)$ have the same binary support mask, but Z_p sends them to different support masks. Deterministic refinement under the selected four-operation micro-ISA gives

$$\boxed{16 \longrightarrow 40 \longrightarrow 78 \longrightarrow 81}.$$

Thus the support shell is sufficient for readout, routing, and visualization, while the full ternary phase state is required for lossless execution.

Evidence scope. For the finite μ_{12} sensor lift the exponent is 3 at odd depth and 9 at even depth; arbitrary $U(1)$ representatives require exponent 3^n. Transpose is an anti-symplectic involution that exchanges the two controlled-add directions, with an inner projective class at $q = 5$ and an outer diagonal class at $q = 7$. The live mixer is `rtl/w33_pass2773_spread_mixer36_synth.sv`; the historical dead source was removed. Exact finite computations and remote synthesis/place-and-route measurements remain distinct evidence classes.

4 Protected support telemetry, active diagnosis, and noisy deep-grade operation

The protected support observer admits two distinct exact compression theorems. If the historical twelve-operation trajectory is held fixed, binary integer programming proves that its 52 raw support bits can be punctured to 28, but not fewer, while preserving minimum distance four. Across the eight distance-four trajectory words the exact optima are

$$(28, 29, 29, 29, 28, 29, 28, 28).$$

The canonical optimum is certified by coincident primal and dual bounds and zero MIP gap.

A second construction changes the measurement schedule. Every support observation after an affine Clifford evolution is an affine-square function

$$\mathbf{1}[a \cdot x + b \neq 0] = (a \cdot x + b)^2 \qquad \text{over } \mathbb{F}_3.$$

The 52 trajectory columns collapse to fourteen distinct functions. The optimal integer-repetition distance-four code uses twelve of them twice, for only 24 samples. This is not a puncturing theorem: it requires independent resampling of selected affine features.

The hidden symmetry is exact. The distance-four word digraph has automorphism order 32 and consists of two directed $K_{2,2}$ components. The 48 minimum eight-tap fast selectors form one block orbit under a group of order

$$6912, \qquad S_3 \times (S_4 \wr S_2).$$

Under an independent asymmetric support channel, maximum-likelihood decoding weights $0 \to 1$ and $1 \to 0$ events separately. It agrees with Hamming decoding in the symmetric model and reduces deterministic modelled word-error counts by more than seventy percent in each tested asymmetric profile. These are synthetic-channel results, not detector calibration.

For the explicit deep-grade M_{36} branch, let

$$R(p) = \frac{p(4-p)}{3(p^2 - 2p + 2)}.$$

A phenomenological output depolarization g gives $T_g(p) = g + (1-g)R(p)$ and fixed-point polynomial

$$(p-1)\big(3p^2 - (2+4g)p + 6g\big).$$

The useful and unstable fixed points merge at

$$g_c = \frac{7 - 3\sqrt{5}}{4} = 0.072949016875\ldots, \qquad p_c = \frac{3 - \sqrt{5}}{2} = 0.381966011250\ldots.$$

This is a symbolic phenomenological boundary, not a circuit-level logical threshold.

Finally, support feedback can select the next probe. Exact adaptive-policy search lowers the no-reset identification horizon from six preset operations to four, with uniform mean $94/27$ operations among minimum-depth policies. The machine therefore has three honest telemetry modes: eight-bit fast preset readout, twenty-four-sample protected affine readout, and four-operation worst-case active diagnosis.

Passes 2854–2860: polarization groupoids, Boolean harmonics, and exact support coarse graining

The five continuations of the tetrahedral support program and two further outside-box probes now close with exact witnesses. First, the requested full signed-monomial S_4 lift has a sharp obstruction: in one fixed symplectic polarization the coordinate-permutation projection is only the matching stabilizer D_8. Full S_4 instead lifts between the three perfect-matching polarizations as a three-object groupoid with 288 projective and 576 affine arrows. Every projective hom-set has order 32, composition closes, and the zero/nonzero symplectic relation is preserved.

The fifteen nonempty supports form the punctured Boolean permutation module

$$\mathbb{C}[\mathcal{P}([4]) \setminus \{\varnothing\}] \cong 4[4] \oplus 3[31] \oplus [22].$$

For the full four-cube, adjacency together with dual adjacency generates the Terwilliger algebra of dimension 35, with module strings of dimensions $5, 3, 1$ and multiplicities $1, 3, 2$; equivalently its Wedderburn type is $M_5(\mathbb{C}) \oplus M_3(\mathbb{C}) \oplus M_1(\mathbb{C})$. Restriction to a matching stabilizer recovers $5A_1 + 3B_1 + B_2 + 3E$ exactly.

The affine frame codec remains information-optimal: all 81 states round-trip through codes $0, \dots, 80$ in seven bits, while the 40 nonzero projective classes require six bits. A registered benchmark isolates the one-bit storage saving from its combinational encode/decode cost; new logic-cell and timing figures remain unpromoted until the dedicated FPGA workflow completes. The existing same-harness measurements remain 43 logic cells at 72.40 MHz for the four-operation engine and 72 logic cells at 60.80 MHz for the public six-operation unit.

A typed seven-bit controller now fuses the four Type-A faces, three matching channels and eight parity-coded phase classes. It has exactly $4 \cdot 3 \cdot 8 = 96$ valid states, selecting one of twelve sheets and one of the eight tomotope cells. Equality with the tomotope automorphism-group order is recorded only as a bijective count, not yet as a regular action.

For quantum coarse graining, let $\mathcal{E}$ be the conditional expectation onto observables constant on the sixteen computational-basis support blocks of $\mathbb{F}_3^4$. An invertible affine gate descends through $\mathcal{E}$ iff its linear part is signed monomial and its translation is zero; there are exactly $2^4 4! = 384$ such maps. A Weyl displacement channel descends iff its X-displacement marginal is constant on each support fiber; the exact constraint system has rank 65 on 81 variables and a 16-dimensional solution space. The Z-phase marginal is unrestricted for support observables. This is not a coherence-preservation theorem.

Two further identities sharpen the architecture. With

$$L_q = \begin{pmatrix} 1 & q-1 \\ 1 & -1 \end{pmatrix}, \qquad L_q^2 = qI_2,$$

and $H_q = P_\tau L_q^{\otimes 4}$, one has

$$H_q^2 = q^4 I_{16}, \qquad \operatorname{spec}(H_q) = (+q^2)^{10} \oplus (-q^2)^6,$$

while for nonempty supports

$$Q_{S,T} + \delta_{S,T} = \frac{1}{q}\left((q-1)^{|T|-1} + (H_q)_{S,T}\right).$$

Thus the support quotient admits a four-stage, 32-butterfly realization. Finally, for its Markov matrix P and stationary projector Π,

$$(I - P + \Pi)^{-1} = \alpha I + \beta P + \gamma \Pi,$$

where

$$\alpha = \frac{q(q^2+q+2)}{(q+1)(q^2+1)}, \quad \beta = \frac{q^2}{q^2+1}, \quad \gamma = -\frac{q^3+q^2+q-1}{(q+1)(q^2+1)}.$$

At $q = 3$, the 210 directed first-passage times take only thirteen values, from 9/2 to 42, and the Kemeny constant is 291/20.

The frozen release contains 68/68 exact checks and 7/7 focused tests. The fixed-polarization obstruction, coherence boundary, typed-token boundary, and pending new FPGA measurement are retained explicitly.

5 Intrinsic selector channels, exact observer quotients, and nonlinear diagnosis

The residual three-channel selector is not intrinsically a numbered set. For a pointed hyperbolic line $(x, y; c)$, the multiplier-one stabilizer induces the translation group C_3 on the remaining common neighbours, whereas the full projective similitude stabilizer induces $\mathrm{AGL}(1,3) \cong S_3$. Thus the channel is canonically an affine line with S_3 transition functions, but has no globally equivariant origin or orientation. The exact group orders are

$$|\,\mathrm{PSp}(4,3)| = 25920, \qquad |\,\mathrm{PGSp}(4,3)| = 51840,$$

and the pointed stabilizer orders are 12 and 24, respectively, with $51840/24 = 2160$ pointed hyperbolic lines.

The $q = 3$ support quotient now has a literal sequential realization. Four stages of eight butterflies

$$(u, v) \longmapsto (u + 2v, u - v)$$

followed by fifteen border-corrected outputs require 47 cycles, versus 225 cycles for a serial dense 15×15 reference. Equality was checked on all fifteen basis vectors and thirty-two signed probes. The exact cycle reduction is 178/225; routed area and timing remain measurements pending the dedicated FPGA workflow.

The complete deterministic-congruence atlas sharpens the readout/execution boundary. For the full four-operation micro-ISA the support partition refines as

$$16 \longrightarrow 40 \longrightarrow 78 \longrightarrow 81,$$

and the discrete 81-state partition is the coarsest exact execution quotient refining support. Indeed F_p, Z_p, and either controlled-add direction already force all 81 states. The intermediate partitions are therefore observer states, not compressed execution states.

The natural order-96 signed-permutation action on the typed selector–tomotope tokens has two 48-element orbits, distinguished by tetrahedral versus hemioctahedral phase parity. Imposing the determinant-twisted condition

$$\Big(\prod_i \epsilon_i\Big)\,\mathrm{sgn}(\pi) = 1$$

produces another order-96 projective subgroup that acts freely and transitively. Hence the 96 control tokens form an exact group torsor, although this twisted runtime symmetry is not the natural incidence-preserving tomotope embedding.

For the $q = 3$ support walk, the 210 directed passage costs form 39 orbits under the matching stabilizer and are determined by

$$|T|, \qquad |T \cap \tau(T)|, \qquad |T \cap \tau(S)|.$$

An exact Held–Karp search gives an optimal Hamiltonian diagnostic cycle of cost 315, with 8336 rooted optima. The best $\mathrm{GL}(4,2)$ Singer-cycle schedule costs $1317/4$, leaving an exact nonlinear advantage of $57/4$. Thus the optimal mask scheduler is a nonlinear fifteen-entry permutation, not an LFSR traversal.

Finally, the first observer refinement has forty classes but is not $W(3,3)$. Its class sizes are $1^7 2^{29} 4^4$, symplectic orthogonality is ambiguous on 216 unordered class pairs, and none of the 1459 Hamming-distance unions with 240 edges yields $\mathrm{SRG}(40,12,2,4)$. This falsifies a count-based identification while leaving the independent projective symplectic construction untouched.

Evidence boundary. The packet carries 64 exact checks and seven focused regressions. Arithmetic, group-action, congruence, optimization, and falsifier claims are exact. FPGA cells, routed frequency, switching activity, and physical passage times remain measured or open quantities as labelled in the blueprint.

6 Global protected support, thermodynamic diagnosis, and the OAM carrier boundary

The full affine-Clifford orbit has 120 nonconstant binary support observables $f_{a,b}(x) = \mathbf{1}[a \cdot x + b \neq 0] = (a \cdot x + b)^2$ on $\mathbf{F}_3^4$. An exact integer program gives local $AG(3,3)$ distance-four optimum 12. There are 120 affine three-flats and each probe is nonconstant on 117, so $n \geq \lceil 120 \cdot 12/117 \rceil = 13$. An explicit sixteen-probe code on all 81 frames has distance four:

$$\boxed{13 \leq n_{\text{affine support,d=4}} \leq 16.}$$

The probes pair into an isodual but non-self-dual $[8,4,4]_3$ code. Its coordinate automorphism group is S_4, its monomial group is $C_2 \times S_4$, and its sixteen one-symbol syndromes are distinct. A four-trit syndrome and sixteen-entry correction table therefore replace an eighty-one-codeword binary scan.

For a uniform frame, every deterministic exact diagnostic transcript obeys $H(T) = H(X) = \log_2 81$. Adaptivity reduces latency or raw storage but cannot lower this optimally compressed Landauer information floor. Finite-time reset adds a positive, protocol-dependent excess and is not assigned a device-independent joule number.

OAM is optional at the abstract level but explicit in the operator/OAM ABI and OAM/GKP hardware profile. Exhausting all 51,840 projective symplectic-similitude actions on the forty points gives maximum cyclic orbit length 12 and no 40-cycle. One cyclic OAM shift therefore cannot implement the full geometry-preserving address bus; a physical implementation needs a multi-cycle

sorter/interferometer or a hybrid mode register. The repository's radial-shell leakage figures remain symbolic falsifiers, not measurements.

For the deep-M_{36} branch the circuit-independent adversarial accepted-fault budget is $g_c = (7 - 3\sqrt{5})/4$. A circuit with L independent locations is inside this pessimistic envelope when $q < 1 - (1 - g_c)^{1/L}$; this is not promoted as a compiled-circuit threshold.

7 Exact protected observation, compiled magic, and a hybrid OAM fabric

The complete affine-support family on $\mathbf{F}_3^4$ has an exact binary minimum-length theorem at distance four:

$$\boxed{n_{\text{affine support},d=4} = 15.}$$

The lower bound combines the exact $AG(3,3)$ minimum twelve, a four-complete- direction-triplet classification of every local optimum, orbit-reduced infeasibility certificates for lengths thirteen and fourteen, and a doubled- direction packet obstruction. Equality is attained by taking all three support offsets of the ternary $[5,4,2]_3$ single-parity-check code.

The deep-M_{36} branch is now compiled explicitly. A Clifford decoder sends $IYZY \mapsto -Z_0$ and $YZXY \mapsto -Z_1$, so syndrome $(-1,+1)$ is the decoded bit test 01. After decomposing two swaps, the branch uses twelve CNOTs, three Hadamards, and two Z measurements; it accepts with probability $1/2$ and maps two copies of ray 5 to ray 7. In the stated stochastic Pauli and measurement- flip model its first-order output infidelity is

$$\frac{2}{3}p + \frac{140}{81}q_1 + \frac{2084}{405}q_2 + \frac{4}{9}q_m + O(2).$$

This is a circuit law for that model, not a coherent-error or leakage threshold.

An exact spread gives a hybrid photonic address register

$$\boxed{10 \text{ OAM line modes} \times 4 \text{ time/frequency slots} = 40}$$

with sixty intra-line and one hundred eighty inter-line edges. Every ordered line pair is a four-channel permutation. Across all 120 spread-line triangles, the routing holonomy consists of sixty transpositions and sixty double transpositions; every triangular holonomy is an involution.

The canonical eight-tap observer extends to a 256-state reversible permutation whose valid outputs are the seven-bit frame ranks. Its marginal-bit entropy exceeds the joint entropy by 1.0065166696 bits, which can be exposed by reversible correlation compression; erasing the final rank still costs the $\log_2 81$ information floor.

The isodual outer code is an LCD $[8,4,4]_3$ code of covering radius two and published spectrum type $(3,4,10,12,11)$. The explicit isodual map obeys

$$D^2 = -I, \qquad D^4 = I,$$

so one four-lane signed-bin mixer can alternate between generator and parity- check roles. Finally, after correcting and uncomputing the optimal fifteen-probe record, the frame and forty-way route fuse into

$$R = 40(27x_p + 9z_p + 3x_f + z_f) + (4\ell + s),$$

a twelve-bit rank for all 3240 valid joint states. Optical loss, crosstalk, finite-time reset energy, and FPGA placement remain measured-evidence tasks.

8 Passes 2960–2966: physical observer, coherent M36, dihedral OAM curvature, and reversible compilation

The exact fifteen-probe affine-support observer admits a minimum-incidence factorization through the ternary single-parity-check code $[5,4,2]_3$. Up to monomial equivalence its five linear forms are

$$x_0,\ x_1,\ x_2,\ x_3,\ x_0+x_1+x_2+x_3.$$

Computing each form once and sharing its three support offsets reduces linear-form incidence from 24 to 8. Only one non-native four-trit mixer is required; a balanced implementation uses three ternary adders at depth two. The corrected systematic triplets recover the four trits with eight NOT and eight CNOT operations, while the fifth triplet remains a parity syndrome.

For the compiled deep-M_{36} branch, exhaustive coherent Pauli-axis perturbation gives 189 single-location quadratic susceptibilities with spectrum

$$0^{14},\quad (1/18)^{66},\quad (2/27)^{41},\quad (1/6)^{22},\quad (2/9)^{46}.$$

Common systematic H-axis rotations have coefficients $7/18, 7/54, 7/18$ for X, Y, Z, respectively. The complete two-location Pauli census contains 16,497 events. A flagged-leakage monitor of efficiency η gives the adversarial first-order bound $p_{\mathrm{bad}} \le 34(1-\eta)\ell + O(\ell^2)$ for per-location leakage probability ℓ across the seventeen circuit locations.

All 36 spreads of the present $W(3,3)$ realization have the same routing curvature. Their 120 triangle holonomies split as sixty transpositions and sixty double transpositions. After tree gauge fixing, the thirty-six residual chords split $18+18$ and generate

$$\mathrm{Hol} = D_4, \qquad |D_4| = 8,$$

with element-order profile $1^1 2^5 4^2$. The sign projection obeys all 210 tetrahedral Bianchi checks, so the surviving obstruction is nonabelian rather than an abelian parity cocycle.

A configurable ten-OAM by four-slot channel model now includes coherent nearest-neighbour OAM coupling, phase noise in a four-port Fourier multiport, insertion loss, detector efficiency, and dark counts. Its supplied parameter profiles are synthetic engineering probes and are not hardware calibrations.

The reversible compiler is no longer a truth-table placeholder. A generic completion of the 8192-state frame-route permutation has an optimized star upper bound of 39,472 multi-controlled swaps. Exploiting

$$R = 40r + a = (r \ll 5) + (r \ll 3) + a$$

produces an explicit valid-subspace network of 120 Toffoli and 79 CNOT gates. Exhaustive simulation covers all $81 \cdot 40 = 3240$ valid inputs and returns all twenty-four scratch bits to zero.

Two additional closures follow. First, three distinct pilot slots are necessary and sufficient to detect every arbitrary nonidentity S_4 permutation inserted on one edge of one spread triangle: one pilot detects 18/23, two detect 22/23, and three detect all 8280 exact fault cases. Second, the involution

$$K(x_0,x_1,x_2,x_3) = (x_1,x_0,x_3,x_2)$$

is anti-symplectic, $K^T J K = -J$. The phase transducer $\sigma(x,p) = x^T J p$ simultaneously implements the $W(3,3)$ commutation test, the route-dependent qutrit phase, and the affine-support probe triplet. Globally its three phase values occur 1080 times each. On the deep-M_{36} family-zero labels, K swaps $(\mu,\nu) = (1,2)$ for ray 5 to $(2,1)$ for ray 7. This is an exact label-level covariance, not a replacement for the compiled distillation circuit.

9 Pareto-optimal information-system closure: Passes 2967–2973

The optimized architecture retains the live controller in native mixed radix: four frame trits, ten spread-line modes, four intra-line slots, and one encode/check sector. Binary joint ranking is deferred to archive, export, or reset boundaries. This removes Boolean rank arithmetic from the live path while retaining a reversible boundary encoder.

Component-resolved Bayesian calibration is structurally necessary: the aggregate correct/wrong/erasure map has Jacobian rank two for four component parameters, so survival, OAM sorting, slot sorting, and dark counts cannot be inferred separately without intermediate counters. The committed numerical reference is synthetic and serves only to validate the inference engine.

For the K_{10} spread-line routing complex, twenty-three measured triangles are necessary and sufficient to localize one faulty edge. The lower bound follows from $3m \geq m + 2(45 - m)$, and an explicit schedule attains $m = 23$. The complete D_4-valued triangle syndrome is injective on the no-fault state and all one- and two-edge nonidentity faults, a total of 48,826 hypotheses. A 29-triangle subschedule distinguishes all of them, although minimality at weight two remains open.

The binary frame-route compiler has an exact schedule of 120 Toffoli and 79 CNOT gates, dependency depth 94, and 86 Toffoli-bearing layers. Its best architectural use is at the information boundary rather than in the live controller. Published Clifford+T, measurement-assisted, and relative-phase decompositions give distinct resource points, but their physical ranking is platform-dependent.

Two terminal SWAPs in the deep-M_{36} decoder are static detector/output relabelings. Absorbing them produces a dominating branch with six CNOTs, three Hadamards, and two Z measurements, while preserving success probability $1/2$ and exact ray-7 output. In the stated stochastic model,

$$p_{\mathrm{out}} = \frac{2}{3}p + \frac{140}{81}q_1 + \frac{956}{405}q_2 + \frac{1}{3}q_m + O(2).$$

The native controller group on $2 \cdot 81 \cdot 40 = 6480$ states has order

$$30{,}233{,}088 = 2^9 3^{10}.$$

Its route subgroup has order 192. Adding one symplectic transvection generates A_{40} on route addresses; this is an address-controller group, not an identification with the W33 automorphism group, and arbitrary words need not be physically local.

Exact Moore minimization for outputs consisting of duality sector, spread line, and symplectic phase stabilizes at 6048 future-distinguishable states. The quotient still requires thirteen fixed bits and therefore is used as a verification-level sufficient statistic rather than as the physical live representation.

Finally, translation by $a = (1, 2, 0, 0)$ combined with the order-four slot rotation gives a clock step C of order twelve. Anti-symplectic reversal combined with slot reflection gives $R^2 = 1$ and $RCR = C^{-1}$, hence a D_{12} logical clock. The full controller state space partitions into exactly 540 twelve-cycles. This is a reversible logical phase counter, not an autonomous time crystal or a demonstrated physical time standard.

10 Adaptive and self-synchronizing information closure (Passes 2996–3002)

The fixed diagnostic problem is replaced by an exact adaptive one. The frozen 23-triangle single-edge-optimal panel already separates 44,848 of the 48,826 no-, one-, and two-edge D_4 fault hypotheses. Its 1,436 remaining collision classes have size at most three. Holding those 23 triangles fixed,

a binary MILP proves that six further triangles are necessary and sufficient for a fixed completion. Global fixed-schedule optimality of 29 remains open:

$$23 \le m^{\star}_{\mathrm{fixed}} \le 29.$$

However, a collision-specific exact decision tree resolves all hypotheses with at most two additional tests. Its depth census is

$$44848 \times 23, \qquad 3566 \times 24, \qquad 412 \times 25,$$

with uniform mean 23.0899111129. Thus the adaptive protocol strictly dominates every fixed 29-triangle protocol operationally.

The earlier equality between 540 clock cycles and 540 skew-line frames does not extend to the natural order-three actions. The clock translation fixes all 540 cycle labels, whereas the corresponding W33 symplectic transvection fixes no skew-line frame and has 180 three-cycles. Their permutation characters are therefore 540 and zero. The numerical factorization $2 \cdot 27 \cdot 10 = 40 \cdot 27/2$ survives, but the natural C_3-equivariant identification is obstructed.

All ordered W33 address transfers admit exact symplectic-transvection words of length at most two. The distance census is

$$40 \times 0, \qquad 1080 \times 1, \qquad 480 \times 2.$$

One transvection suffices exactly for noncommuting address pairs; distinct commuting pairs require two.

For the explicit sparse decision prior $P_0 = 0.995$, $P_1 = 0.0045$, and $P_2 = 0.0005$, the adaptive controller escalates after the common 23 rows with probability 0.00423797155 and uses 23.0062407751 triangles on average. Its fourteen next actions need four fixed bits and have entropy only 0.0517343817 bits. This motivates a predictive controller that retains the next action and residual risk rather than an opaque sixteen-bit fault-hypothesis index.

Eight exact rewrite classes remove operations that are merely terminal wire permutations, diagonal measurement phases, Pauli byproducts, gauge-coordinate changes, route inversions, shared affine decoders, boundary-only binary ranks, or covariant ternary label inversions. The governing synthesis rule is that no operation is promoted to a physical gate until it changes a future observable in every permissible frame representation.

Finally, the balanced cyclic word

$$102332001123$$

has twelve distinct shifts, maximum off-phase autocorrelation three, and optimal cyclic distance nine. It corrects four arbitrary slot-symbol substitutions. At tick t, slot w_t is omitted and the existing three curvature pilots are sent in the remaining slots. The omitted slot supplies the mod-12 synchronization symbol while the same three pilots retain arbitrary single-edge S_4 permutation detection. No additional pilot channel is required.

Claim boundary. The conditional six-row optimum, adaptive depth, equivariance obstruction, transvection diameter, and cyclic-code properties are exact in their frozen finite models. The fault prior is synthetic; global fixed-schedule minimality of 29, noisy optical decision policies, measured transvection loss, RTL placement, and physical Landauer energy remain open.

Passes 3025–3031: Predictive Photonic Closure

Fixed and adaptive curvature diagnosis. An independent 28-triangle schedule separates all 48,826 no-, one-, and two-edge nonidentity D_4 faults and all 1,036 central-involution supports of weight at most two. A resumable 27-row cutting-plane search examined 259 feasible adversarial schedules and accumulated 12,336 exact collision cuts without finding a witness; this is bounded evidence, not a proof. Thus

$$23 \le m^{(2)}_{\text{fixed}} \le 28, \qquad m^{(2)}_{\text{adaptive,worst}} = 25.$$

Three-copy M_{36} audit. The displayed seeded Clifford search reproduces 19 projective stabilizer witnesses and 18 orthogonal pairs. Every pair has common same-sign Pauli subgroup order 8 and rank 3, not the rank 5 required for a six-qubit rank-two stabilizer code. Each clean projection succeeds with probability 1/6, has stabilizer Rényi-2 entropy 1.540568381363 bits, and admits a two-stabilizer decomposition with extent upper bound 2. These are magic-bearing rank-two subspaces, not stabilizer codes.

The 6,480-flag algebra. The objectwise skew-pair/spread/transversal flags form

$$\mathcal{F} \cong PSp(4,3)/V_4, \qquad |\mathcal{F}| = 6480.$$

The flag stabilizer has fixed-point character $6480, 288, 288, 24$; hence

$$\dim \operatorname{End}_{PSp(4,3)} \mathbb{C}[\mathcal{F}] = \frac{6480 + 288 + 288 + 24}{4} = 1770.$$

The numerical equality $6480 = 27(81 + 120 + 24 + 15)$ does not by itself identify the flag module with 27 Hodge copies.

Typed optical inference. A component-resolved tetrahedral A_4 shell, a route-curvature channel, and a sequential chirality channel are combined in one finite posterior controller. For the published synthetic prior and horizon, it uses route, calibration, and chirality actions in 5.12892194 expected measurements, versus a seven-action silo baseline.

Causal information geometry. The interaction

$$K(a,b) = I(S; Y_a, Y_b) - I(S; Y_a) - I(S; Y_b)$$

is nonzero because the action channels share calibration uncertainty. Raw information-per-erased-bit favors chirality, while downstream consequence-weighted dynamic programming selects route diagnosis first. Information quantity and causal decision value are therefore distinct controller resources.

Self-dual comb. Among all $369,600$ balanced length-12 four-symbol words, 384 are both distance-nine and self-dual under a D_4 reflection. The selected maximum-run-two word is

$$001032122313.$$

Crossed with the 89/233 Christoffel calendar, it yields 1,068 events in 2,796 ticks, 89 in each phase, and the exact reversal

$$R(t) = 1952 - t \pmod{2796}.$$

This is a source-complete logical schedule; optical comb coherence and autonomous timing remain unmeasured.

11 The two-layer information machine: routing, computation, prediction, and time

The newest exact results force a sharper architecture than a single universal controller graph. The machine separates six typed layers: collision-free translation routing; a selectable universal compute ISA; nonabelian D_4 route localization; high-distance self-dual phase synchronization; symmetry-quotiented prediction when invariance is certified; and irreversible readout only at the posterior decision boundary.

11.1 The fixed D_4 frontier is a distance-five parity-check problem

For the central involution r^2, the 120 triangles of K_{10} are binary parity-check rows on its 45 edges. Separating all supports of weight at most two is equivalent to hitting every nonzero edge word of weight at most four. The exact 27-row feasibility model has

$$\binom{45}{1} + \binom{45}{2} + \binom{45}{3} + \binom{45}{4} = 164220$$

constraints. A new 66-round cutting-plane run accumulated 1860 exact cuts and reached eight residual collisions, but did not produce a witness or an infeasibility proof. Hence

$$23 \le m^{(2)}_{\text{fixed}} \le 28$$

remains the theorem.

11.2 The rank-three M36 question is now exhaustively parameterized

A rank-three commuting Pauli subgroup has eight signed eigenspaces of dimension eight. The duplicate-free RREF census contains 220 pivot patterns and exactly

$$50{,}868{,}675$$

totally isotropic three-subspaces of $\mathbb{F}_2^{12}$. A local 4096-assignment pilot found no zero-leak code; the best pilot syndrome retained clean probability $1/216$ with maximum single-error probability $5/72$. This is an obstruction, not a no-go theorem; the full sharded census is the decision procedure.

11.3 Complete character decomposition of the 6480 flags

The flag stabilizer is $H \cong V_4$ and fuses as

$$H = 1A + 2(2A) + 1(2B), \qquad |2A| = 45, \quad |2B| = 270.$$

Thus

$$m_\chi = \frac{\chi(1) + 2\chi(2A) + \chi(2B)}{4}.$$

For irreducible degrees

$$1, 5, 5, 6, 10, 10, 15, 15, 20, 24, 30, 30, 30, 40, 40, 45, 45, 60, 64, 81,$$

the multiplicities in $\mathbb{C}[X]$ are

$$1, 0, 0, 1, 3, 3, 3, 8, 8, 10, 3, 11, 11, 6, 6, 9, 9, 14, 16, 24.$$

They satisfy

$$\sum_{\chi} \chi(1) m_\chi = 6480, \qquad \sum_{\chi} m_\chi^2 = 1770.$$

Consequently $6480 = 27(81 + 120 + 24 + 15)$ is dimensional arithmetic, not a decomposition into 27 repeated Hodge copies: the 81 occurs 24 times, the 24 occurs 10 times, the two 15's occur 3 and 8 times, and no irreducible of degree 120 exists.

11.4 Robust posterior control

The explicit hidden state

$$(\text{route}, \text{calibration}, \text{chirality}, \text{drift}, \text{regime})$$

has 32 states. A horizon-five Bayes controller treats the nominal/adverse observation regime as hidden. Under the frozen synthetic model, its adverse-case objective is 0.3065079301, compared with 0.3199090606 for the nominal-only policy, a 4.189% reduction. The first action is route diagnosis. These are exact Bellman values for the stated model, not measured receiver performance.

11.5 Self-dual timing fabric

The word 001032122313 and the 89/233 Christoffel calendar form a 2796-tick fabric with

$$R(t) = 1952 - t \pmod{2796}.$$

All ticks satisfy phase and calibration-event covariance. There are 1068 events, exactly 89 in every D_{12} phase, with global gaps 2 or 3 and per-phase gaps $24, 36, 60$. The synthesizable controller enforces a typed A_4 shell/D_4 core boundary: unauthorized core commands cannot mutate route state.

11.6 The universal ISA has a two-point Pareto frontier

Of the 210 four-opcode subsets considered, 80 are connected on the 81 frames and 24 generate the full linear group $Sp(4, 3)$ of order 51840. The minimum collision count among fully universal sets is 36, achieved for example by

$$\{CX_{fp}, F_f, F_p, Z_2\},$$

with normalized symmetrized second eigenvalue 0.8942150876. The current ISA has 45 collisions but faster mixing, 0.8290244059. Thus collision count and mixing do not share a single optimum; the compiler must select the compute ISA by task while preserving the separate collision-free translation-routing graph.

11.7 Two outside-box closures

The V_4 stabilizer partitions the 6480 flags into 1770 orbits: 24 of size one, 264 of size two, and 1482 of size four. For H-invariant transition, observation, cost, and loss kernels, Bellman recursion factors exactly through these orbits. The quotient saves two fixed register bits and 1.9111111111 average uniform bits.

Finally, the product of 48826 route hypotheses with 12 phase offsets gives 585912 noiseless route-time states. The phase code has minimum distance 21 over 28 symbols, whereas the route syndrome code has minimum distance one. The product therefore supplies strong synchronization correction but only exact route localization; route-syndrome errors require authentication or remeasurement.

Claim boundary. No 27-row impossibility, complete rank-three M36 census, laboratory optical result, physical Landauer heat, autonomous clock, or observed RTL/PDF evidence is inferred here.

Current VM frontier: finite certified control, extensible guest state

The current software theorem should be stated more narrowly, and more usefully, than "the finite geometry is itself an infinite computer." The executable MicroVM separates the two roles. Universal semantics belong to a two-counter guest over $\mathbb{N}^2$ (or an equivalent extensible memory model); the finite $W(3,3)$ substrate supplies typed routing, control, capability and proof structure. Thus the present architecture is

$$\boxed{\text{universal guest semantics} \quad + \quad \text{finite proof-carrying control plane.}}$$

No finite forty-node device is thereby claimed to realise an unbounded physical tape. The universality statement is the standard abstract-machine one: a fixed finite transition/control mechanism acts on storage whose extent is not fixed in the model. The Merkle-memory, reversible-history, checkpoint and execution-passport layers are the systems implementation of that separation.

The 1296-state object is a hypervisor, not a carrier conversion

The two verified 216-state carriers remain inequivalent construction-time forks. The canonical relation between them is their fibre product over the common 36-state base,

$$\boxed{216 \times_{36} 216 = 36 \times 6 \times 6 = 1296.}$$

Write a composite address as

$$h = (b, a, c) \in 36 \times 6 \times 6.$$

Its two projections are

$$\pi_{81}(h) = 6b + a, \qquad \pi_{64}(h) = 6b + c.$$

Both are onto and exactly six-to-one. Fixing either projection leaves six possibilities for the other, so the composite does not define an opcode converting one carrier into the other. Architecturally the correct third deployment mode is therefore a *hypervisor* machine type,

`w33.fibre1296.steinberg81+64`,

which synchronises the two immutable guest forks on their shared base while retaining both logical modules. The associated Holotrade fibre-product certificate gives a transitive 1296-point $\mathrm{PSp}(4,3)$ orbit with stabiliser of order 20 and Frobenius signature $F_{20} \cong \mathrm{AGL}(1,5)$.

Bounded control latency is independent of guest magnitude

The local verifier checks every ordered W33 portal pair and obtains route-hop histogram

$$0^{40}, \qquad 1^{480}, \qquad 2^{1080},$$

so the routing diameter is exactly two. On the qutrit symplectic side, the forty projective axes and two nonzero field scalars give

$$\boxed{40 \cdot 2 = 80}$$

distinct transvection micro-operations; the two operations on one axis are mutual inverses. The current Holotrade exhaustive compiler independently verifies all 51,840 elements of $\mathrm{Sp}(4,3)$ and emits pointwise-minimal transvection words of length at most

$$\boxed{5}.$$

Consequently the finite control envelope—W33 placement plus symplectic microcode—is bounded by substrate constants and does not grow when a guest counter or Merkle-backed semantic object grows.

The control target needs a central-lift bit

Projective scheduling and matrix-level execution are not the same namespace. In $\mathrm{Sp}(4,3)$ the two matrices g and $-g$ are distinct, whereas their actions on the forty W33 projective points coincide. Hence a projective target alone is insufficient to specify matrix-level execution. The current control ABI is therefore the ladder

$$\boxed{\text{projective action} \longrightarrow \text{Sp central-lift bit} \longrightarrow \text{Clifford phase/calibration evidence} \longrightarrow \text{non-Clifford resource evi}}$$

The first arrow restores the twofold $\mathrm{Sp} \to \mathrm{PSp}$ information loss only; it is *not* a complete qutrit Clifford phase lift. This distinction is operationally necessary in the newest cost geometry: forty-five expensive projective target classes form $GQ(4,2)$ under the relation $gh = -hg$ on their Sp lifts. That sign relation becomes invisible projectively because $-I$ is quotiented out. A physical execution passport must therefore bind the projective action and the intended central lift separately. Measured optical calibration and a non-Clifford resource remain independent fail-closed admission requirements.

Virtual-hardware interpretation

The resulting machine stack is:

layer	current virtual object	role
vCPU	two-counter/compiled guest	universal semantic transition
vALU-control	80 qutrit transvections	finite symplectic microcode
vRouter	40 W33 portals, diameter 2	placement and transport
vHypervisor	$36 \times 6 \times 6$ fibre product	pair ST81/ST64 without conversion
vMMU	Merkle capability memory	extensible content-addressed state
vClock	causal ledger + reversible history	logical time, replay and rewind
vTPM/passport	evidence/epoch/revocation roots	proof-carrying execution identity
quantum backend	calibrated qutrit primitives	optional physical accelerator
non-Clifford port	explicit resource token	required for quantum universality

The architectural conclusion is therefore precise:

$$\boxed{\text{compute} = \text{finite certified transformation} + \text{advance extensible semantic/history state} + \text{retain enough proof to v}}$$

Executable witnesses are `analysis/w33_finite_control_unbounded_guest_hypervisor.py` and `analysis/w33_projective_symplectic_lift_control_abi.py`, with frozen result certificates under `data/PASS20260903_*`. The corresponding Holotrade runtime object is `js/w33-fibre-hypervisor-profil`

Boundary. This insert proves and records a software/control architecture. It does not identify the two 216-state carriers, does not make finite physical storage unbounded, does not turn a symplectic word into a measured optical gate, and does not promote a finite Clifford kernel to quantum universality without a separately validated non-Clifford resource.

Current VM frontier: the five control-plane gaps close

Scope. This insert records a software/architecture closure, not a fabricated-machine claim. The finite $W(3,3)$ substrate is used as a certified control plane around extensible semantic and Merkle-history state. The five previously named VM frontiers now have explicit interfaces and executable reference implementations.

1. The 45 slow targets are a boot-verifiable control store. The Holotrade anomaly catalogue now carries an explicit fixed isomorphism from its 45 real projective expensive targets to the 45 points of an independently built $H(3,4) = GQ(4,2)$. The runtime decoder normalises $g \sim -g$ and, before admitting the ROM, checks 27 banks of 5, 135 incidences, three banks per target, the $\mathrm{SRG}(45,12,3,3)$ collinearity graph, the generalized-quadrangle axiom, and equality of the transported concrete and abstract line sets. The labelling is a fixed verified engineering contract; it is not claimed canonical.

2. A memory address now carries its own authority. A first-class capability pointer commits

(Merkle root, base-40 address, bounds, rights, epoch, carrier, evidence floor, seal state).

Bounds, permissions and evidence requirements may be narrowed but not widened. Dereference checks the committed Merkle snapshot, construction-time carrier, revocation epoch, address prefix, requested right and backend evidence level. A persistent store returns a pointer rebound to the new root; the old pointer remains a pointer to the old snapshot rather than silently becoming mutable memory. This is a software capability semantics, not yet a hardware-tag implementation.

3. The qutrit transvection ISA has an explicit Clifford phase lift. For the odd-prime Weyl convention

$$D(q,p) = \omega^{(q\cdot p)/2} X^q Z^p,$$

and $T(v,\lambda)x = x + \lambda\langle x, v\rangle v$, define

$$U(v,\lambda) = \sum_{k\in\mathbb{F}_3} \omega^{\lambda k^2/2} P_k(D_v).$$

The resulting conjugation law is

$$U(v,\lambda) D_x U(v,\lambda)^\dagger = D_{T(v,\lambda)x}.$$

The reference verifier enumerates all 40 projective axes and both nonzero values of λ, hence all 80 primitive transvection opcodes, and also tracks affine Weyl displacements and the global composition cocycle. Physical optical admission remains fail-closed unless an accepted W33 device calibration packet explicitly covers the Weyl-displacement and transvection-quadratic-phase primitives.

4. Universal guest semantics now lower to proof-carrying packets. The repository already contains a real WebAssembly binary frontend. Beneath it, the new universal core IR is a labelled presentation of the exact two-counter guest: `inc`, `decjz`, and `halt` blocks with named control-flow edges. Every finite existing two-counter `Program` has a lossless labelled encoding and compiles back to the identical instruction tuple. Universality is thus inherited from the existing Minsky core rather than asserted for an arbitrarily small Wasm subset. After validation, every executed guest transition lowers to a proof-carrying W33 control packet committing semantic pre/post state, canonical $\leq$ 2-hop route, finite transvection word, projective target, central lift bit and the Clifford phase-frame digest.

5. Reversible storage has an explicit time–space–GC trade surface. For a local undo segment of B guest steps and a workload padded to $B2^L$, the explicit recursive schedule uses

$$C(0) = B, \qquad C(L) = 3C(L-1),$$

so compute–copy–uncompute has the conservative traversal bound

$$T = 2B3^L.$$

Its modeled peak retained software state is

$$B\, s_{\text{token}} + (L+1)s_{\text{checkpoint}} + s_{\text{output}},$$

with the byte coefficients obtained by serializing the committed reference VM, not by inventing hardware numbers. Temporary checkpoints are STRONG Merkle roots while live and become GC-reclaimable after their reverse branch; HASH_ONLY audit roots do not pin bytes. A destructive-discard control is reported separately and excluded from the reversible Pareto frontier. No Joule estimate is inferred from logical erasure counts.

Current virtual-machine contract. Validated source → authority-bearing address → semantic state transition → W33 route → exact symplectic micro-word → phase-specified qutrit Clifford → geometry-checked exceptional control store → reversible checkpoint/GC policy.

A compact systems reading is now possible:

computation = authorized state transition + certified finite control + retained causal provenance.

The statement is intentionally architectural. It does not turn finite geometry into literal infinite memory, nor does it promote software verification into a physical quantum-universality or hardware-calibration claim.

Artifacts and verification boundary. The W33 implementations are `analysis/w33_capability_address_is` `analysis/w33_qutrit_clifford_phase_displacement_lift.py`, `analysis/w33_structured_counter_bytecoo` and `analysis/w33_reversible_storage_economics.py`; the cross-front test is `tests/test_w33_universal_vm_i` Holotrade owns the concrete 45-slot certificate and `js/w33-slowpath-rom-decoder.js`. The dedicated W33 Actions run `33830617595` completed successfully: all four reference implementations and the cross-front ABI assertions passed. Holotrade's exhaustive explicit-bijection generator reports 178 shape-catalogue tests with zero failures; for the new production decoder, RTL formal/synthesis had also passed while its Node-test job was still executing when this status line was recorded. Physical calibration remains a separate evidence gate throughout.

September 2026 exact continuation: Heawood symmetry, Schubert trace fibres, and observer quotients

Full $\mathrm{PGSp}(4,3)$ **Heawood–spread dictionary.** The intrinsic execution-slot graph has 1620 vertices and decomposes into 270 six-cycles. The previously constructed dictionary sends each such C_6 to the unique unordered pair of $W(3,3)$ spreads whose intersection has four lines and whose symmetric difference is the same twelve-line axis union. The eight audited symplectic transvections make this bijection $\mathrm{PSp}(4,3)$-equivariant. The multiplier-two similitude

$$D = \mathrm{diag}(2,2,1,1), \qquad \omega(Dx,Dy) = 2\,\omega(x,y) \pmod 3,$$

commutes with the same dictionary, closing the missing outer coset. Hence the bijection is equivariant for the full projective similitude action. With the certified group orders 25920 and 51840, orbit–stabilizer gives

$$|\,\mathrm{Stab}_{\mathrm{PSp}}(C_6)| = 96, \qquad |\,\mathrm{Stab}_{\mathrm{PGSp}}(C_6)| = 192.$$

The latter agrees with the independent spread-pair stabilizer $D_8 \times S_4$.

The declared outer involution has cycle structure

$$270 = 12 + 129 \cdot 2$$

on both the C_6 set and the four-intersection spread-pair set. The twelve fixed pairs split exactly $6+6$: six consist of two individually fixed spreads, and six consist of two spreads exchanged by the outer involution. On the underlying W33 objects the same involution fixes 8 of 40 points, 6 of 40 lines, and 4 of 36 spreads.

The order-96 stabilizer is a split fibre product, not the tomotope group. Let $D_8 = \langle r, s \mid r^4 = s^2 = 1,\ srs = r^{-1}\rangle$ and define $\chi(r^i s^j) = i \pmod 2$. The exact stabilizer model is

$$H = \{(d,\sigma) \in D_8 \times S_4 : \chi(d) = \mathrm{sgn}(\sigma)\} = D_8 \times_{C_2} S_4.$$

Its D_8-character kernel is $V = \langle z = r^2, u = s\rangle \cong C_2^2$. Since $t = rs$ has order two and $\chi(t) = 1$, the map

$$\sigma \longmapsto (t^{\mathrm{sgn}(\sigma)}, \sigma)$$

is a splitting, so

$$H \cong V_4 \rtimes S_4,$$

where the action factors through sign: even permutations centralize V_4, while odd permutations fix z and send $u \mapsto zu$. A four-generator presentation is certified by

$$z^2 = u^2 = a^2 = b^4 = (ab)^3 = 1, \qquad [z,u] = [z,a] = [z,b] = 1,$$
$$aua^{-1} = zu, \qquad bub^{-1} = zu,$$

with $a = (01)$ and $b = (0123)$. Exhaustive normal-closure enumeration gives exactly twelve normal subgroups, with order census

$$1^1,\ 2^1,\ 4^2,\ 8^1,\ 12^1,\ 16^1,\ 24^1,\ 48^3,\ 96^1.$$

In particular

$$Z(H) \cong C_2, \qquad H' \cong C_2 \times A_4, \qquad H/H' \cong C_2^2.$$

This is a structural firewall against the tempting order coincidence with the tomotope automorphism group: the repo-certified tomotope group has trivial centre and derived subgroup of order 48, whereas H has centre order 2 and derived subgroup order 24.

All-n Schubert law for the Marcelis trace gauge. Fix ordered coordinates on $\mathrm{PG}(n,4)$, scale the first nonzero coordinate to ω, and apply $\mathrm{Tr}_{\mathbb{F}_4/\mathbb{F}_2}$ coordinatewise. Relative to the complete coordinate flag

$$F_j = \{x_0 = \cdots = x_{j-1} = 0\},$$

the resulting gauge-fixed map τ_ω obeys the exact point law

$$\left|\tau_\omega^{-1}(b)\right| = 2^{n-j}, \qquad b \in F_j \setminus F_{j+1}.$$

For a binary projective line $\ell \subseteq F_j$ but $\ell \nsubseteq F_{j+1}$, the number of $\mathbb{F}_4$ projective lines whose setwise image is exactly ℓ is

$$N_{\mathrm{line}}(\ell) = 2^{n-1-j}.$$

There are $2^{n-j-1}(2^{n-j}-1)$ binary lines in that stratum, giving total incidence-preserving line mass

$$\sum_{j=0}^{n-1} 2^{n-j-1}(2^{n-j}-1)2^{n-j-1} = \frac{2(8^n-1)}{7} - \frac{4^n-1}{3}.$$

The line law is constructive: after matching the two RREF pivot columns, every remaining free column has exactly two admissible $\mathbb{F}_4$ lifts. The implementation exhausts all points for $1 \le n \le 6$, all lines for $1 \le n \le 5$, and symbolic mass identities through $n = 9$. At $n = 3$ it recovers $28 \cdot 4 + 6 \cdot 2 + 1 = 125$; at $n = 5$ it finds 9021 preserving lines among 93093 $\mathrm{PG}(5,4)$ lines mapping onto all 651 binary lines.

Deterministic global law, stochastic observer quotient. The same trace fibres give an exact finite model of observer-relative randomness. Take the 85 points of $\mathrm{PG}(3,4)$ as microstates, let the observer retain only

$$B = \tau_\omega(S) \in \mathrm{PG}(3,2),$$

and evolve the microstate by the deterministic projective bijection

$$U_1(x_0,x_1,x_2,x_3) = (x_1,x_2,x_3,x_0).$$

With a uniform conditional prior within each finite fibre, the induced macro transition law is

$$P(B' = b' \mid B = b) = \frac{\#\{s \in \tau_\omega^{-1}(b) : \tau_\omega(U_1 s) = b'\}}{|\tau_\omega^{-1}(b)|}.$$

Although U_1 is globally deterministic and invertible, exactly seven of the fifteen observer states have deterministic next macrostates and eight have nontrivial transition distributions. The boundary is the first Schubert hyperplane:

$$B \in F_1 = \{x_0 = 0\} \Longleftrightarrow \text{deterministic macro update},$$

while every state in $F_0 \setminus F_1 = \{x_0 = 1\}$ is stochastic. Quantitatively,

$$H(B' \mid B) = \frac{156}{85} \text{ bits}, \qquad P_{\mathrm{guess}}(B' \mid B) = \frac{43}{85}.$$

If K records the exact microstate index inside the observed fibre, then

$$H(B' \mid B, K) = 0.$$

Thus this geometry supplies a literal finite example of deterministic global information becoming probabilistic relative to a many-to-one observer map, with side information restoring predictability. This is an information-theoretic quotient theorem, not a claim that Bell-certified quantum randomness is a classical hidden-variable phenomenon or that the fibre index is a cryptographic secret key. Exhaustive checks through $n = 5$ show the more general horizon law for a k-step cyclic coordinate shift: the macro update is stochastic exactly when the first nonzero binary coordinate occurs before k, and deterministic exactly on F_k.

Reproducibility. The claims in this insert are regenerated and regression-gated by `w33_crypto_network_marcel` the authoritative machine-readable witnesses are the five JSON certificates named in the header of this insert.

Authenticated binary-counter execution (6 September 2026)

The existing universal two-counter guest now has a persistent binary-list backend, implemented in `analysis/w33_authenticated_counter_machine.py`. An increment or nonzero decrement opens only its carry or borrow prefix; the remaining tail and the other counter are shared by content identity. A verifier supplied with the trusted pre-state, program and placement reconstructs the arithmetic result and branch from those openings without accessing the memory store. A portable receipt binds the resulting roots, instruction sequence, carrier, session and W33 dispatch route.

For canonical lists, $V(b, t) = b + 2V(t)$. Increment changes low ones to zeros until a zero is changed to one; decrement changes low zeros to ones until a one is changed to zero, removing a redundant highest zero. These identities give one-step refinement on inductive lists and, by induction, every finite execution prefix of that abstract representation. The fixed-digest backend implements collision-free finite executions; fixed SHA-256 identities cannot injectively encode all natural numbers. Abstract universality is inherited with extensible lists, not asserted for a fixed finite device. The mathematical argument is not a mechanized proof of the Python source.

The certificate checks 1024 small arithmetic transitions and the existing addition program under 40 placement shifts. Incrementing 2^{4096} opens one node; incrementing $2^{4096} - 1$ opens 4096 nodes. Worst-case proof size therefore grows with counter bit length. The diameter-two route bounds instruction dispatch only, not memory access or proof transfer.

The construction uses established authenticated-data-structure principles and requires trusted canonical genesis and collision-resistant hashes. Authorization, availability, physical gate implementation, quantum advantage, and a static arbitrary-input Wasm compiler remain separate obligations. The detailed argument, prior-art references and replay commands are in `analysis/W33_AUTHENTICATED_COU`

11.8 Line signings as an exact apartment-parity observable

The signing and building threads admit a sharper common formulation than the numerical Wilson-loop comparison alone. Let G be the 40-vertex collinearity graph of $W(3, 3)$ and let $\mathcal{L}$ be its 40 geometric lines. The six edges of each K_4 line are disjoint from the six-edge sets of the other lines, so the 40 line supports partition all 240 graph edges. Choose a sign $\sigma_\ell \in \{\pm 1\}$ for each $\ell \in \mathcal{L}$, and give every collinearity edge on ℓ that sign. Write A_σ for the signed adjacency matrix and N for the 40×40 point–line incidence matrix. Then the signed graph has the exact incidence factorization

$$\boxed{A_\sigma = N\ \mathrm{diag}(\sigma) N^T - \mathrm{diag}(N\sigma).} \tag{1}$$

The subtraction removes the diagonal point-wise signed line sums.

There are exactly 1620 simple quadrangles in the point collinearity graph. Indeed, the graph has 540 nonedges; each nonedge has $\mu = 4$ common neighbours, so choosing two common neighbours gives $540\binom{4}{2}/2 = 1620$ quadrangles. For every such quadrangle its four edge-lines are distinct and induce a quadrangle in the dual line-collinearity graph. Equivalently, inserting the four side-lines produces the corresponding simple 8-cycle in the point–line Levi graph. Thus the 1620 point-graph quadrangles, the 1620 dual line-graph quadrangles, and the 1620 Levi apartments are three shadows of the same rank-two-building apartments.

For an apartment a, define its line parity

$$\chi_a(\sigma) = \prod_{\ell \in a} \sigma_\ell, \qquad W_4(\sigma) = \sum_a \chi_a(\sigma).$$

A direct closed-walk count gives the exact moment identities

$$\boxed{\operatorname{tr}(A_\sigma^2) = 480,} \qquad \boxed{\operatorname{tr}(A_\sigma^3) = 24 \sum_\ell \sigma_\ell,} \tag{2}$$

and, crucially,

$$\boxed{\operatorname{tr}(A_\sigma^4) = 12000 + 8W_4(\sigma).} \tag{3}$$

If f_4 is the fraction of apartments with negative parity, then $W_4 = 1620(1 - 2f_4)$ and therefore

$$\boxed{\operatorname{tr}(A_\sigma^4) = 24960 - 25920 f_4.} \tag{4}$$

The coefficient $25920 = 16 \cdot 1620$ is used here only as the combinatorial coefficient in the trace identity; its numerical equality with $|\operatorname{PSp}(4,3)|$ is not a group-theoretic inference. Likewise, Pass 4434 remains correct that fourth-moment pressure is a generic even-moment feature of signed graphs. The $W(3,3)$-specific statement is instead that the *entire variable part* of the fourth moment is exactly the apartment-parity observable of the building. This is the precise geometric content behind the length-four signal without reintroducing the withdrawn claim that $\mu = 4$ causes spectral optimization in general.

The apartment family itself has a compact Bose–Mesner certificate. Let $H \in \{0,1\}^{40 \times 1620}$ be line–apartment incidence and A^* the dual line-collinearity adjacency matrix. Each line lies in 162 apartments, each intersecting pair of lines in 27, and each disjoint pair in 6. Hence

$$\boxed{HH^T = 156I + 21A^* + 6J,} \qquad \boxed{\operatorname{spec}(HH^T) = 648^1 \oplus 198^{24} \oplus 72^{15}.} \tag{5}$$

This gives an explicit point/line-dual carrier for the apartment observable, even though the projective point and line actions should not be conflated.

Exact random-line baseline. The 1620 apartment supports are 1620 distinct four-subsets of the 40 line bits. Under independent Rademacher line signs the apartment parities are therefore distinct Walsh characters. Orthogonality immediately gives

$$\mathbb{E}W_4 = 0, \qquad \mathbb{E}W_4^2 = 1620, \qquad \mathbb{E}f_4 = \frac{1}{2}, \qquad \operatorname{sd}(f_4) = \frac{1}{2\sqrt{1620}}.$$

Pass 4462 computes the higher null moments by exact symmetric-difference counts:

$$\boxed{\mathbb{E}W_4^3 = 12960, \qquad \mathbb{E}W_4^4 = 9891720.} \tag{6}$$

Thus the line-signing null is not exactly Gaussian: its standardized skewness is $0.1987615979\ldots$ and its excess kurtosis is $0.7691358025\ldots$. The corresponding fourth-trace null has

$$\mathbb{E}\,\mathrm{tr}(A_\sigma^4) = 12000, \qquad \mathrm{Var}\big(\mathrm{tr}(A_\sigma^4)\big) = 103680.$$

This is an analytic control distribution, not a search result. Its purpose is to make the baseline mandatory and reproducible before any optimized line signing is called exceptional.

Apartment-parity tomography. Encode the line signs by $b \in \mathbb{F}_2^{40}$ through $\sigma_\ell = (-1)^{b_\ell}$. The full apartment-parity record is then simply

$$y = H^T b \in \mathbb{F}_2^{1620}.$$

Pass 4463 row-reduces the exact incidence matrix and obtains

$$\boxed{\mathrm{rank}_{\mathbb{F}_2} H = 39,} \qquad \boxed{\ker(H^T) = \langle \mathbf{1}_{40} \rangle.} \tag{7}$$

Hence the 1620 apartment parities determine all 40 line signs up to the one unavoidable ambiguity $\sigma \mapsto -\sigma$. Global reversal is necessarily invisible because every apartment contains four lines; the rank theorem says there is no second hidden signing gauge. Equivalently, the apartment-parity image is a binary $[1620, 39]$ code. A one-line generator has Hamming weight 162, while the XOR of two line generators has weight 270 for intersecting lines and 312 for disjoint lines. Reducing Eq. (5) modulo two gives the especially compact identity

$$\boxed{HH^T = A^* \quad \text{over } \mathbb{F}_2.} \tag{8}$$

This is a finite-geometric identifiability theorem, not a statement that an optical experiment automatically measures all 1620 apartment products.

The nondegenerate parity core. The binary code $C = \mathrm{rowspan}_{\mathbb{F}_2}(H)$ has dimension 39, but the ambient dot product on C is highly degenerate. Pass 4464 computes

$$\mathrm{rank}_{\mathbb{F}_2}(A^*) = 10, \qquad \dim\ker(A^*) = 30.$$

Because the global-reversal vector $\mathbf{1}_{40}$ lies in this kernel and is already the one-dimensional kernel of the coefficient-to-code map, the radical of C has dimension $30 - 1 = 29$. Therefore

$$\boxed{\dim C = 39, \qquad \dim \mathrm{rad}(C) = 29, \qquad \dim C/\mathrm{rad}(C) = 10.} \tag{9}$$

The form is alternating because A^* has zero diagonal; after quotienting by the radical it is nondegenerate. Thus $C/\mathrm{rad}(C)$ is a 10-dimensional symplectic vector space over $\mathbb{F}_2$. This dimension is not introduced by pattern matching: it is the exact rank of the apartment Gram form. For the point–line incidence matrix one also has $N^T N = A^*$ over $\mathbb{F}_2$, with $\mathrm{rank}_{\mathbb{F}_2} N = 25$; the restricted dot product on that 25-dimensional incidence image therefore has a 15-dimensional radical. No physical qubit count or unrelated cyclotomic identification is inferred from these dimensions alone.

Evidence boundary. The identities above are finite combinatorial statements verified by the executable witnesses `analysis/w33_pass4461_line_signing_apartment_trace.py`, `analysis/w33_pass4462_apartment_walsh_null_model.py`, `analysis/w33_pass4463_apartment_parity_tomograph` and `analysis/w33_pass4464_apartment_code_symplectic_quotient.py`. They do not identify a physical gauge field, do not make a particular signing statistically special, do not assert physical measurement completeness, and do not promote the Artin–Ihara/2-lift analogy into a spacetime claim. They do show that the recent signing observable and the older 1620 apartment carrier are literally the same quartic finite-geometric statistic; within the line-signing model its full parity family loses only the global sign bit, and its nondegenerate binary core is an exact 10-dimensional symplectic quotient.

12 The last chromatic bit: an exact defect filter, not a search claim

The canonical frame graph has 540 vertices, 8,640 edges, degree 32, and

$$H + 4I = MM^{\mathsf{T}}, \qquad \operatorname{spec}(H) = 32^{1} \oplus 14^{44} \oplus 8^{15} \oplus 4^{81} \oplus 2^{84} \oplus (-4)^{315}.$$

The complete cover-link computation rules out nine colours, while a literal proper eleven-colouring is frozen. The exact frontier is therefore

$$\boxed{10 \le \chi(H) \le 11.}$$

No bounded heuristic or MILP non-solution is used to sharpen this interval.

Forty-five local A_4 blocks

The unique degree-one frame/octet relation partitions the frames into 45 blocks of size 12. Every induced block is

$$\boxed{K_{12} \setminus 3K_4.}$$

Thus one colour may occupy vertices in only one of the three independent four-cells. A ten-colouring of twelve local vertices must save at least two colours by repetition, giving the exact global local-pressure law

$$\boxed{\text{repeat savings} \ge 45 \cdot 2 = 90.}$$

Near-Hoffman energy

For an independent-set indicator x of size s, put

$$y = x - \frac{s}{540}\mathbf{1}.$$

Then

$$\boxed{y^{\mathsf{T}}(H + 4I)y = \frac{s(60 - s)}{15}.}$$

For a hypothetical ten-colouring let $d_i = 60 - s_i$. Since $\sum_i d_i = 60$,

$$\boxed{\sum_{i=1}^{10} y_i^{\mathsf{T}}(H + 4I)y_i = 240 - \frac{1}{15}\sum_i d_i^2 \le 216.}$$

The positive spectral gap away from E_{-4} is 6, hence

$$\boxed{\sum_i \|P_{E_{-4}^{\perp}} y_i\|^2 \le 36.}$$

Any ten-colouring must therefore lie close to the exact-cover/Hoffman eigenspace.

A ten-by-ten proof quotient

Let e_{ij} be the number of edges between colour classes i and j, and define

$$G = X^{\mathsf{T}}(H + 4I)X - \frac{1}{15}ss^{\mathsf{T}}, \qquad K = 15G.$$

Every ten-colouring must satisfy

$$K \succeq 0, \qquad K\mathbf{1} = 0, \qquad \operatorname{rank} K \leq 9,$$

with

$$K_{ii} = s_i(60 - s_i), \qquad K_{ij} = 15e_{ij} - s_i s_j.$$

In particular,

$$\boxed{K \equiv -ss^{\mathsf{T}} \pmod{15},}$$

so every 2×2 minor of K is divisible by 15. This arithmetic-semidefinite quotient and the 45 local blocks are exact necessary-condition filters; they do not yet decide whether the tenth colour exists.

Evidence type. All graph counts, block decompositions, identities, and the frozen eleven-colouring are finite machine-verified results. The remaining choice $\chi(H) = 10$ versus 11 is open. The equality-case language is consistent with A. Abiad, W. Bosma, and T. van Veluw, *Hoffman colorings of graphs*, Linear Algebra Appl. 710 (2025), 129–150; the W33 finite computations are independent project certificates.

13 The final chromatic bit as a finite port problem

The exact frame-graph frontier remains

$$\boxed{10 \leq \chi(H) \leq 11}.$$

The next reduction is not another bounded search claim. It is an exact factorisation of the 540 frames through 45 block supports, 135 local four-cells, and 240 W33 edges.

The 45×240 support incidence. Let N record which W33 edges occur in each canonical twelve-frame block. Every row of N has weight 16, every column has weight 3, and

$$\boxed{NN^{\mathsf{T}} = 16I + A_{45}},$$

where A_{45} is the adjacency matrix of $\mathrm{SRG}(45, 32, 22, 24)$. Each W33 edge labels a triangle of this block graph, and the 720 block-graph edges decompose uniquely into the 240 resulting triangles.

Three exact covers and sixteen ports per block. The three independent K_4 cells inside a block each cover the same sixteen W33 edges exactly once. Each support edge therefore chooses one frame from each cell. The sixteen resulting triples form

$$\boxed{\mathrm{OA}(16, 3, 4, 2)},$$

and every port is used by exactly two neighboring blocks. Two blocks are either frame-disconnected or share one support edge; in the latter case their cross graph is exactly $K_{3,3}$.

Equivalently, H is the line graph of the four-uniform linear hypergraph whose 240 vertices are W33 edges and whose 540 hyperedges are frames. Every hypergraph vertex has degree nine. Thus a ten-colouring would assign nine distinct colours around every W33 edge and leave a unique missing colour there.

Exact quotient and association algebra. Writing $d_i = 60 - s_i$ for the ten class deficits, there are exactly 195,490 sorted profiles with $\sum_i d_i = 60$. The defect-Gram trace is

$$\operatorname{tr} K = 3600 - \sum_i d_i^2,$$

with a unique maximum at $d_1 = \cdots = d_{10} = 6$. This exhausts the diagonal quotient, not the off-diagonal Gram entries.

The 135 local cells form a symmetric rank-four association scheme with valencies $(1, 2, 96, 36)$ and multiplicities $(1, 24, 20, 90)$. One eigenmatrix is

$$P = \begin{pmatrix} 1 & 2 & 96 & 36 \\ 1 & 2 & 6 & -9 \\ 1 & 2 & -12 & 9 \\ 1 & -1 & 0 & 0 \end{pmatrix}.$$

Its ordinary ratio bounds stop at nine. Therefore an improvement to eleven must use the split port or triangle data rather than only the commutative Bose–Mesner layer.

Arithmetic and uncertainty corrections. The Smith form of N is

$$\boxed{1^{44} \oplus 3}.$$

There is one 3-primary factor and no 5-primary torsion. Moreover, deleting any d frames from a frozen exact cover gives a binary integral row-space witness of weight $4d$. Hence linear 3-adic and 5-adic defect tests are vacuous for every possible deficit; any arithmetic obstruction must include nonlinear matching and port compatibility.

The frame-space localization spectrum of $E_{-4} = \ker M^{\mathsf{T}}$ on every block is

$$\frac{2}{9}, \quad \left(\frac{43}{81}\right)^9, \quad 1^2,$$

so two Hoffman directions localize perfectly inside each block. In contrast, the edge-kernel localization spectrum on a sixteen-edge support is

$$0^{10} \oplus \left(\frac{1}{6}\right)^6.$$

Thus the naive frame-delocalization obstruction fails, while the cut-code edge kernel is strongly delocalized.

Proof surface and boundary. A deterministic strengthened ten-colour DIMACS instance has 7,800 variables and 146,289 clauses. It exposes both frame colours and the unique missing colour at each W33 edge; its SHA-256 is `6c0c3daa...9c6b7cd5`. No SAT model and no checked UNSAT proof is claimed. The semantic exact certificate is `68e93f6b...db21d19`. Time-bounded MILP and local-search failures remain diagnostics only.

13.1 Exact-cover signature Fourier law and the one-bit symmetry overhead

The complete exact-cover census gives forty-five anchor octets. Relative to an anchor, the three independent four-cells of the induced $K_{4,4,4}$ carry one of

$$(2,2,2), \qquad (0,3,3), \qquad (1,2,3), \qquad (0,2,4).$$

Permuting the three cells produces orbit sizes $1,3,6,6$. Thus the local signature alphabet is the sixteen-state S_3-set

$$\Omega \cong 1 \sqcup S_3/C_2 \sqcup S_3 \sqcup S_3, \qquad 45|\Omega| = 720.$$

Its permutation character on the identity, transposition, and three-cycle classes is

$$\chi_\Omega = (16, 2, 1),$$

and therefore

$$\mathbb{Q}[\Omega] \cong 4\mathbf{1} \oplus 2\,\mathrm{sgn} \oplus 5V_{\mathrm{std}}.$$

Consequently

$$\dim \mathrm{End}_{S_3}(\mathbb{Q}[\Omega]) = 4^2 + 2^2 + 5^2 = 45,$$

with rational commutant

$$M_4(\mathbb{Q}) \oplus M_2(\mathbb{Q}) \oplus M_5(\mathbb{Q}).$$

Direct orbital enumeration gives forty-five relations on $\Omega \times \Omega$, with size profile $1^1 3^3 6^{41}$. Hence

$$720 = 45 \cdot 16 = \dim \mathrm{End}_{S_3}(\mathbb{Q}[\Omega])\,|\Omega|.$$

This rank equality does not itself identify the forty-five anchor octets with the forty-five orbitals.

Although $|\Omega| = 16$, its exact S_3 action cannot be affine on four binary bits. The unique fixed state makes every affine realization translation-conjugate to a linear one. An exhaustive classification of all 2800 embedded S_3 subgroups of $GL(4,2)$ finds only the orbit profiles

$$(1,1,2,3,3,6), \qquad (1,1,1,1,3,3,3,3), \qquad (1,3,3,3,6),$$

never $(1,3,6,6)$. The obstruction is sharp: on

$$\mathbb{F}_2^5 = (\mathbb{F}_2^3)_{\mathrm{perm}} \oplus (\mathbb{F}_2^2)_{\mathrm{std}}$$

there is an explicit invariant sixteen-state subset with the required orbit profile and an exact equivariant encoding of all four signature classes. Therefore the minimal affine binary register has dimension five:

$$\boxed{4 \text{ information bits} + 1 \text{ symmetry bit} = 5 \text{ affine-equivariant bits.}}$$

A four-bit implementation remains possible only with nonlinear lookup/permutation logic. In particular, equal cardinality does not justify identifying this signature alphabet with the $\mathrm{OA}(16,3,4,2)$ port alphabet without a separate intertwiner.

13.2 Signature–port obstruction and the minimal common controller

The sixteen exact-cover signature states and the sixteen natural V_4 orthogonal-array ports are not the same S_3-set. Their orbit profiles are

$$\Omega_{\mathrm{sig}} : 1+3+6+6, \qquad \Omega_{\mathrm{port}} : 1+3+3+3+6,$$

so no full S_3-equivariant bijection exists. Restriction to the orientation-preserving subgroup C_3 gives

$$1+3+3+3+3+3$$

on both sides, with exactly

$$5!\,3^5 = 29160$$

equivariant bijections. The reflection restrictions differ:

$$\Omega_{\mathrm{sig}}|_{C_2} : 1^2\,2^7, \qquad \Omega_{\mathrm{port}}|_{C_2} : 1^4\,2^6.$$

Thus the obstruction is reflection-sensitive.

The permutation characters are

$$\chi_{\mathrm{sig}} = (16,2,1), \qquad \chi_{\mathrm{port}} = (16,4,1),$$

and hence

$$\mathbb{Q}[\Omega_{\mathrm{sig}}] \cong 4\mathbf{1} \oplus 2\,\mathrm{sgn} \oplus 5V_{\mathrm{std}},$$
$$\mathbb{Q}[\Omega_{\mathrm{port}}] \cong 5\mathbf{1} \oplus \mathrm{sgn} \oplus 5V_{\mathrm{std}}.$$

The exact representation-ring defect is

$$[\mathbb{Q}\Omega_{\mathrm{port}}] - [\mathbb{Q}\Omega_{\mathrm{sig}}] = [\mathbf{1}] - [\mathrm{sgn}],$$

or stably

$$\mathbb{Q}[\Omega_{\mathrm{sig}}] \oplus \mathbf{1} \cong \mathbb{Q}[\Omega_{\mathrm{port}}] \oplus \mathrm{sgn}.$$

It vanishes on C_3, where the sign character becomes trivial.

The signature commutant has dimension

$$4^2 + 2^2 + 5^2 = 45,$$

whereas the natural port commutant has dimension

$$5^2 + 1^2 + 5^2 = 51.$$

Therefore the existing equality between forty-five anchor octets and forty-five signature orbitals cannot be lifted through the natural port action without treating the one-dimensional orientation defect.

At the set level, the orbit multiplicities are

$$\Omega_{\mathrm{sig}} : 1^1\,3^1\,6^2, \qquad \Omega_{\mathrm{port}} : 1^1\,3^3\,6^1.$$

Their minimal common S_3-envelope has profile

$$1^1\,3^3\,6^2$$

and therefore size

$$\boxed{22}.$$

The maximum equivariant overlap is

$$\boxed{10}, \qquad 16 + 16 - 10 = 22.$$

Both alphabets are embedded explicitly into the same linear S_3-action on $\mathbb{F}_2^5$. The twenty-two valid words consist of ten shared states, six signature-only states, and six port-only states; the other ten ambient words are guards.

A four-bit nonlinear signature ROM and a five-bit shared linear controller are supplied. The fixed four-bit encoding has algebraic degree three and twenty-seven ANF terms; the five-bit generator cores each use one XOR plus wire permutations before multiplexing. Source-level equivalence is exact. Observed synthesis, placement, manuscript-PDF evidence, and the unresolved chromatic decision remain separately gated. In particular,

$$10 \le \chi(H) \le 11$$

is unchanged. The new chromatic filter is that a full local S_3 signature/port quotient is invalid, whereas a C_3-only quotient is locally compatible.

13.3 Knight-hypercube gauge closure and the typed common controller

The local signature and natural-port alphabets become isomorphic after restriction to the orientation subgroup C_3, but the choice is highly noncanonical. The filled port complex has $\pi_1 \cong F_{436}$. After freezing the pairing of the five three-cycles, its phase group is $A = C_3^5$, and therefore

$$H^1(X; A) \cong A^{436} \cong \mathbb{F}_3^{2180}.$$

Without freezing orbit pairing, the local intertwiner group is $W = C_3 \wr S_5$ of order $3^5 5! = 29160$. Burnside enumeration over the 108 wreath-product conjugacy types gives a 1943-digit number of flat W-connections modulo switching. A trivial coboundary gauge exists, but the geometry does not select one canonically.

The minimal common envelope is the 22-state S_3-set

$$\Omega_{\mathrm{env}} \cong 1 \sqcup 3(S_3/C_2) \sqcup 2S_3.$$

Its character and rational module are

$$\chi_{\mathrm{env}} = (22, 4, 1), \qquad \mathbb{Q}[\Omega_{\mathrm{env}}] \cong 6\mathbf{1} \oplus 2\,\mathrm{sgn} \oplus 7V_{\mathrm{std}}.$$

Consequently

$$\dim \mathrm{End}_{S_3} \mathbb{Q}[\Omega_{\mathrm{env}}] = 6^2 + 2^2 + 7^2 = 89.$$

Direct enumeration gives orbital profile $1^1 3^{15} 6^{73}$. Algebra closure over two independent large prime fields gives the basepoint-dependent Terwilliger dimensions

$$\dim T_x = \begin{cases} 89, & x \text{ fixed}, \\ 222, & x \text{ in a three-state orbit}, \\ 484 = 22^2, & x \text{ in a regular six-state orbit}. \end{cases}$$

Thus a regular signature basepoint generates the full matrix algebra and admits no further exact algebraic compression.

The ten unused five-bit words form

$$\Omega_{\mathrm{guard}} \cong 1 \sqcup 3(S_3/C_2), \qquad \mathbb{Q}[\Omega_{\mathrm{guard}}] \cong 4\mathbf{1} \oplus 3V_{\mathrm{std}}.$$

In particular the guard shell contains no sign constituent. Its coherent algebra has rank 25, and its Terwilliger dimensions are 25 and 58 on the two orbit types. As an induced Q_5 network it has seven internal edges, thirty-six boundary edges, and component sizes $7, 1, 1, 1$; this is a typed detection shell, not a fault-tolerant memory.

The repository's 4×4 toroidal knight graph is exactly Q_4, and the frozen knight tour is a four-bit Gray Hamilton cycle. The nonlinear signature controller contains seven transpositions and five three-cycles. The transpositions contribute at least fourteen directed hops. Since Q_4 is bipartite, each embedded three-cycle has metric perimeter at least four, so

$$\text{total routing work} \geq 14 + 5 \cdot 4 = 34.$$

An exhaustive componentwise placement census attains the bound:

$$\boxed{\text{minimum work} = 34, \quad \text{average} = \frac{17}{16}, \quad \text{minimum dilation} = 2.}$$

There are 1105920 minimum-work labeled embeddings. After fixing translation and quotienting coordinate permutations, all 2880 representatives were routed exhaustively. No minimum-work embedding has shortest-path link congestion below three, and congestion three is attained.

The five-bit affine lift has the network decomposition

$$Q_5 = Q_4 \square K_2,$$

so it is two toroidal-knight boards joined by a sixteen-edge perfect matching. For both S_3 generators the binary column-weight profile is

$$(1, 1, 1, 1, 2).$$

Four basis directions remain one-hop routes; only the added symmetry direction is dilated to two. This turns the one-bit symmetry overhead into a literal double-board interconnect theorem.

Finally, the 45 signature orbitals are not intrinsically individually labelled. The order-72 automorphism group of the signature S_3-set acts on them with only thirteen orbits, of sizes

$$1^5\, 2^3\, 4^1\, 6^3\, 12^1.$$

Hence the equality between forty-five anchor octets and forty-five signature orbitals does not define a canonical correspondence from local data alone; any such lift needs extra global $PSp(4, 3)$-equivariant structure.

A complete canonical C_3 coboundary-gauge manifest is emitted for all 45 blocks, 720 block edges and 240 filled triangles. It is an exact bijective relabelling with transported interfaces, not a reduction or decision of the current ten-colour instance. The live boundary remains

$$\boxed{10 \leq \chi(H) \leq 11}.$$

14 Global cover closure and the three hypercube roles

The complete exact-cover census contains 3,547,800 covers in 327 $PSp(4,3)$-orbits. The closed ternary-Hamming switch component contributes 1,574,640 covers in 135 orbits, leaving the exact exterior complement

$$1{,}973{,}160 \text{ covers in } 192 \text{ orbit classes},$$

with stabilizer-order distribution $2^{120}4^{57}8^{15}$. The numerical equality with the 192 tomotope flags is not promoted to an identification: the exterior classes carry this nontrivial stabilizer partition and no equivariant map has been supplied.

For the rational chromatic-dual batch, deficit-profile stabilizers reduce the exact search surface from 204,287,050 to 98,191,335 rational block coordinates. This is an exact compiler reduction, not an eleven-colour certificate; the live boundary remains $10 \le \chi(H) \le 11$.

The ternary cover cube admits an exact binary host. Under the block-one-hot encoding $0 \mapsto 100$, $1 \mapsto 010$, $2 \mapsto 001$,

$$d_{Q_{15}}(\operatorname{enc} x, \operatorname{enc} y) = 2d_{H(5,3)}(x, y).$$

Hence $H(5,3)$ is the distance-two graph on 243 constant-weight-five words in Q_{15}. It is not a subgraph of an ordinary hypercube because it contains triangles. This Q_{15} host is distinct from both the toroidal-knight controller Q_4 and the secondary complement-codec Q_4; raw Levi complement adjacency remains $4K_4$.

The affine involution acts as a coordinate permutation of the 15 one-hot bits. Its traces on the six ternary Fourier grades are $(1,2,4,8,4,8)$, yielding invariant multiplicities $(1,6,22,44,42,20)$ and the exact 135-state quotient. For the reversible quotient chain $P = W/10$, the Szegedy walk has eigenphases $\exp(\pm 2i \arccos\lambda)$ for $\lambda \in \{1, 7/10, 2/5, 1/10, -1/5, -1/2\}$. This is a finite spectral compiler, not a physical speedup claim.

15 Minimum gauge defects, fault-aware hypercubes, and Clebsch recovery

The filled 45-block port complex has minimum nontrivial flat C_3^5 cochain support

$$d_{\text{gauge}} = 2.$$

Every minimum support is two edges of one filled triangle. The 720 geometric supports form one $PSp(4,3)$ orbit; for each fixed nonzero coefficient vector the orbit has size 720 and stabilizer order 36. There are 242 labeled coefficient orbits, or 121 projective directions after $v \sim -v$. Each minimum defect produces nonzero holonomy on exactly 42 unfilled triangles.

The optimal nonlinear signature routing on Q_4 has work 34 and dilation two. Mirroring it in

$$Q_5 = Q_4 \square K_2$$

preserves the same work and dilation under every one of the 32 single-vertex and 80 single-edge failures. Among two-vertex failures, loss is possible exactly for the 16 interlayer replica pairs. Under static one-cycle failover, 32 physical state slots are both necessary and sufficient.

The actual 45-anchor action has order 25,920, is transitive, and is perfect. The intrinsic signature automorphism group has derived series $72 \to 18 \to 9 \to 1$. Therefore no nontrivial action induced through the intrinsic signature coherent configuration can be equivariant with the anchor action; the identity orbital is fixed while the anchors are transitive.

At a regular envelope basepoint the local algebra is $M_{22}(\mathbb{Q})$. Nevertheless every separable positive lift $A_{45} \otimes K$, $K \succeq 0$, has extreme eigenvalues $32\lambda_{\max}(K)$ and $-4\lambda_{\max}(K)$, so its Hoffman bound remains exactly nine. Any improvement must use nonseparable, profile-sensitive cross-block orientation data. The exact chromatic boundary remains $10 \le \chi(H) \le 11$.

Validity alone detects 36/110 one-bit and 70/220 two-bit envelope faults. Exact confusability-graph colourings require 7, 11, and 16 trusted symbols to correct one bit, correct one/detect two, and correct two bits, respectively. The optimal four-bit two-error tag is the antipodal-axis label of Q_5. The quotient $Q_5/\{x \sim \bar{x}\}$ is the Clebsch graph $SRG(16, 5, 0, 2)$. Six axes contain two valid states and ten contain one valid state with its guard antipode. The decoder exhausts all 352 error patterns of weight at most two, conditional on a trusted tag.

These are exact finite and source-level digital results. They do not assert physical fault probabilities, observed FPGA timing, fault-tolerant quantum memory, a chromatic decision, or laboratory performance.

16 Minimum gauge defects generate the full flat connection space

The filled port complex has 45 vertices, 720 edges, and 240 edge-disjoint filled triangles, with coefficient module $A = C_3^5 \cong \mathbb{F}_3^5$. On one oriented triangle the scalar flat plane is

$$\{(a, b, c) \in \mathbb{F}_3^3 : a + b + c = 0\},$$

which has rank two and is spanned by its six nonzero weight-two vectors. Since the filled triangles partition all graph edges, these local planes sum directly. Consequently

$$\dim Z^1(X; \mathbb{F}_3) = 240 \cdot 2 = 480, \qquad \boxed{\dim Z^1(X; \mathbb{F}_3^5) = 2400}.$$

The block graph is connected, so

$$\dim B^1(X; \mathbb{F}_3^5) = (45 - 1) \cdot 5 = 220,$$

and therefore

$$\boxed{\dim H^1(X; \mathbb{F}_3^5) = 2400 - 220 = 2180}.$$

Thus the weight-two minimum defects do not merely witness the minimum nontrivial class: they span every flat C_3^5 connection, and every switching class has a representative assembled from minimum defects. This is a generation theorem, not a unique-decoding or multi-fault-correction claim.

Passes 3364–3375: Clebsch–Petersen resilient closure

The folded five-cube checksum graph is the Clebsch graph, SRG$(16, 5, 0, 2)$, with rooted shell decomposition $1 + 5 + 10$. The ten distance-two vertices induce $KG(5, 2)$, the Petersen graph. Its Cayley form on $\mathbb{F}_2^4$ has five circuit directions and automorphism group $2^4{:}S_5$ of order 1920.

Preserving the five raw envelope bits systematically, exhaustive search proves that seven parity bits are necessary and sufficient for a 22-word code of minimum distance five. Thus a self-protecting two-error-correcting envelope word requires 12 total bits. The mirrored Q_5 placement has exactly 16 catastrophic two-vertex sets and 480 catastrophic three-vertex sets, precisely those containing a complete replica pair.

The full block-distance-invariant nonseparable local-algebra lift reduces exactly to the three PSD cones

$$K_0 + 32K_1 + 12K_2 \succeq 0, \quad K_0 + 2K_1 - 3K_2 \succeq 0, \quad K_0 - 4K_1 + 3K_2 \succeq 0.$$

This compiler does not decide the ten-colour problem; the live boundary remains $10 \leq \chi(H) \leq 11$.

Minimum gauge defects obey a local fusion law: same omitted-edge types add coefficientwise and annihilate for opposite coefficients; distinct types in one filled face remain minimum exactly when their shared-edge coefficients cancel; distinct filled faces are edge-disjoint. Projectively, the 87,120 minimum defects contain 29,040 local three-state fusion triples.

The Clebsch graph also supplies a nested checksum geometry: one reference axis, five singleton fault directions, and ten pair channels forming a Petersen graph. A degree-four del Pezzo/Segre quartic supplies a separate 16-line incidence realization of the same graph, retained only as a mathematical dictionary and not as a physical hardware identification.

17 The hidden torus as a finite d'Alembertian

For the hidden 27-state signed-torus block,

$$D = A(C_3)_3 - A(C_3)_1 - A(C_3)_2.$$

Since $\Delta_i = 2I - A(C_3)_i$, one has the exact identity

$$\boxed{D + 2I = \Delta_1 + \Delta_2 - \Delta_3.}$$

Thus the shifted hidden block is a finite discrete d'Alembertian on C_3^3, with two positive Laplacian factors and one negative factor. At Fourier frequency $k \in \mathbb{F}_3^3$,

$$\lambda(k) = 3\big([k_1 \neq 0] + [k_2 \neq 0] - [k_3 \neq 0]\big),$$

so its spectrum is

$$\boxed{6^4,\ 3^{12},\ 0^9,\ (-3)^2}.$$

The rank is 18 and the nullity is 9. The null modes consist of the constant character together with four frequencies satisfying $k_1 = 0$, $k_2, k_3 \neq 0$, and four satisfying $k_2 = 0$, $k_1, k_3 \neq 0$. Hence the exact null profile is $1 + 4 + 4$. This is a finite signed-graph identity only; no physical spacetime, Lorentzian continuum, causal cone, or laboratory claim is made.

18 Minimum-defect normal forms and the hidden signed ternary torus

The flat C_3^5 port connections admit an exact minimum-defect word metric. On one filled triangle there are 1 states of length zero, 726 states of length one, and 58,322 states of length two, so the local enumerator is

$$1 + 726z + 58{,}322z^2.$$

Because the 240 filled faces partition all 720 edges, the global flat-space enumerator is its 240th power and the exact flat-space diameter is 480. A sphere-counting argument against the 3^{2180} switching classes gives the certified quotient bound

$$\boxed{389 \leq \operatorname{diam} H^1 \leq 480}.$$

The upper endpoint is the universal minimum-defect normal form; the exact quotient covering radius inside this interval remains open.

The minimum defects also give a canonical $PSp(4,3)$-equivariant presentation. For scalar coefficients,

$$0 \longrightarrow \mathbb{F}_3[240 \text{ faces}] \longrightarrow \mathbb{F}_3[720 \text{ supports}] \longrightarrow Z^1 \longrightarrow H^1 \longrightarrow 0,$$

with dimensions $240, 720, 480, 436$ after quotienting the 44-dimensional coboundary space. Tensoring by the externally labelled five-dimensional coefficient module gives 3600 generators, 1200 local face relations, 220 coboundary relations, and

$$3600 - 1200 - 220 = \boxed{2180}$$

logical dimensions. Thus the full logical sector is presented by minimum defects with exactly 1420 independent relations.

For the affine involution

$$\tau(x_1, x_2, x_3, x_4, x_5) = (-x_4, 1 - x_3, 1 - x_2, -x_1, x_5)$$

on $\mathbb{F}_3^5$, the 135 orbit species have only 108 distinct block-one-hot Q_{15} barycentres. Their fibre profile is

$$81 \text{ singletons} + 27 \text{ double fibres}.$$

The 27 double fibres occur exactly at ternary displacement four. Taking the coordinatewise missing symbols maps their barycentres bijectively to the 27 fixed points of τ. The two orbit species above each such centre are distinguished by the invariant binary correlation

$$h = (x_1 + x_4)(x_2 + x_3 - 1) \in \{1, 2\}.$$

Consequently the 54 ambiguous species form a canonical two-sheeted cover of the fixed affine flat $\mathbb{F}_3^3$.

More strongly, barycentric aggregation is exactly lumpable for the weighted Hamming-orbifold walk. Its 135-state operator splits as

$$\boxed{W_{135} \cong B_{108} \oplus D_{27}}.$$

The barycentric block has spectrum

$$10^1,\ 7^6,\ 4^{18},\ 1^{32},\ (-2)^{33},\ (-5)^{18},$$

and itself has the exact three-shell quotient

$$\begin{pmatrix} 2 & 8 & 0 \\ 2 & 4 & 4 \\ 0 & 4 & 6 \end{pmatrix}$$

on shells of sizes $27, 54, 27$, with spectrum $10, 4, -2$.

Orienting each double fibre by $h = 1$ versus $h = 2$ identifies the hidden block with the signed Cayley operator on $\mathbb{F}_3^3$

$$\boxed{D_{27} = C_3^{(3)} - C_3^{(1)} - C_3^{(2)}}.$$

Equivalently it has weight $+1$ on the two $\pm e_3$ steps and weight -1 on the four $\pm e_1, \pm e_2$ steps. Its exact spectrum is

$$4^4,\ 1^{12},\ (-2)^9,\ (-5)^2.$$

This is a finite signed-torus theorem, not a spacetime-signature claim.

Finally, a single minimum defect used as a C_3^5 voltage assignment generates only the subgroup $\langle v \rangle \cong C_3$. The full 10,935-vertex derived graph therefore splits into

$$\boxed{\text{81 connected components of 135 vertices each}}.$$

Each component is 32-regular with 2,160 edges and 15,714 triangles. Fourier decomposition across the C_3 fibre gives one untwisted 45-state block and two conjugate magnetic blocks. Their exact moments satisfy

$$\operatorname{tr} M^2 = 1440, \qquad \operatorname{tr} M^3 = 31{,}302,$$

whereas the untwisted cubic trace is 31,680. The $378 = 42 \cdot 9$ deficit proves that this is a genuine nonseparable cohomological weighting. It is a candidate chromatic-dual surface, not yet a certificate improving the bound nine. Its cardinality match with the 135 Hamming-orbit species is also not an isomorphism: the voltage component has degree 32, while the Hamming-orbifold walk has degree 10.

19 Minimum-defect radius, the finite null conic, and a matrix-valued ternary torus (Passes 3404–3417)

The minimum-defect word metric on the switching quotient admits the sharper exact interval

$$\boxed{389 \le D_{H^1} \le 436}.$$

The lower bound is the existing sphere-count obstruction. For the upper bound, the scalar cohomology has dimension 436 and is generated by minimum-support defects, so one may select 436 such supports as a basis. After tensoring with $\mathbb{F}_3^5$, an arbitrary nonzero coefficient vector on one selected support is still one minimum defect; hence every switching class uses at most 436 basis defects.

The nine-dimensional kernel of the shifted hidden operator is the zero mode together with the eight nonzero vectors satisfying

$$k_1^2 + k_2^2 - k_3^2 = 0 \qquad \text{in } \mathbb{F}_3.$$

Projectivization identifies the eight lifts in opposite pairs and produces a nondegenerate four-point conic in $PG(2,3)$. Its projective stabilizer has order 24 and acts as the full S_4 on the four conic points.

The four projective null directions form the columns of a ternary MDS code

$$\boxed{[4,3,2]_3},$$

with weight enumerator $1 + 12z^2 + 8z^3 + 6z^4$ and dual the signed repetition code generated by $(1,1,2,2)$, of parameters $[4,1,4]_3$.

More strongly, the 108 barycentric states admit an exact factorization

$$\boxed{108 = 27 \cdot 4 = |\mathbb{F}_3^3|\,|\mathbb{F}_2^2|}.$$

For every center in the fixed affine flat there are exactly four barycentric channels: one fixed channel, two distance-two channels, and one ambiguous channel. The adjacency is translation invariant in

the center coordinate, so it is a 4×4 matrix-valued Cayley operator with six nonzero kernels at $\pm e_1, \pm e_2, \pm e_3$. Three qutrit Fourier transforms reproduce the full barycentric spectrum from 27 four-dimensional symbols.

Adding the one-dimensional hidden signed channel gives

$$\boxed{135 = 27 \cdot 5},$$

so the complete walk reduces to 27 internal symbols of size 5. This yields an exact mixed-radix compilation contract: three qutrit center registers, one five-level internal register, and two Szegedy reflections per walk step. Uniform state preparation over ten neighbours and synthesis of controlled 5×5 symbols still require an approximation tolerance before any Clifford+T count can be certified.

The isolated magnetic-defect search closes negatively. The ternary phase family has

$$\chi_\omega(x) = (x-2)^{22}(x+4)^{18}\big(x^5 - 28x^4 - 140x^3 + 478x^2 + 1448x - 1328\big),$$

with generalized Hoffman ratio approximately $7.2835002808 < 8$. The real signed family has residual quintic

$$x^5 - 28x^4 - 140x^3 + 520x^2 + 1568x - 1088$$

and ratio approximately $7.0613187294 < 8$. Rational root isolation certifies both inequalities. Thus one profile-sensitive minimum defect cannot improve the live chromatic lower bound.

The literal 720-edge $PSp(4,3)$ permutation-character decomposition remains evidence-gated until its GAP-generated JSON is frozen. The live chromatic boundary remains

$$\boxed{10 \le \chi(H) \le 11},$$

and the finite quadratic form above is not identified with physical spacetime or Lorentz symmetry.

19.1 The 720-edge ordinary degree atlas (Pass 3408)

The minimum-support carrier is the transitive action of

$$PSU(4,2) \cong PSp(4,3)$$

on the 720 non-collinear point pairs of $H(3,4) = GQ(4,2)$. A point stabilizer has order 36 and subdegrees

$$1, 2, 3, 6, 9, 9, 12^5, 18^{11}, 36^{12},$$

so the orbital rank is 34.

Deterministic generic elements of the exact orbital commutant give the complex isotypic dimensions

$$1, 15, 15, 20, 20, 24, 24, 24, 30, 30, 45, 45, 60, 60, 64, 81, 81, 81.$$

The ordinary degree/multiplicity profile is therefore

$$\boxed{1 + 15_a + 15_b + 2 \cdot 20 + 3 \cdot 24 + 30_a + 30_b + 45_a + 45_b + 2 \cdot 60 + 64 + 3 \cdot 81.}$$

It closes both the carrier dimension,

$$1 + 30 + 40 + 72 + 60 + 90 + 120 + 64 + 243 = 720,$$

and the character norm, equal to the orbital rank 34.

The group, orbit, stabilizer, subdegrees, relations, and commutant matrices are exact. The isotypic dimensions are recovered from deterministic well-separated numerical eigenspaces and constrained by the exact dimension and rank identities. GAP/CTblLib remains an independent row-label check, especially for naming the selected conjugate degree-30 pair.

20 Passes 3418–3429: supplemental Clebsch–D_5 closure

The executable source wrappers retain a provisional build tag only for hash continuity after a namespace collision. Building on the parallel Clebsch–Petersen packet without replacing it, the source-complete verifier reports **PASS 11/11**. All graph, code, orbit, fusion, routing, and fault counts in this section are exact. The magnetic spectral family below is an explicitly marked high-margin numerical audit rather than a rational SDP certificate. The chromatic boundary remains

$$\boxed{10 \le \chi(H) \le 11}.$$

20.1 Edge-dependent magnetic phases do not improve the bound

For a flat C_3 edge cochain z, set

$$M(z)_{ab} = \omega^{z_{ab}}, \qquad M(z)_{ba} = \overline{M(z)_{ab}}.$$

The search exhausts the 24 $PSp(4,3)$-orbits of unordered pairs of the 720 minimum-defect supports and both relative coefficient signs. Among all 48 one/two-defect representatives, the best nonzero spectral value is

$$\lambda_{\min} \simeq -5.073280337457312, \quad \lambda_{\max} \simeq 31.877958425086288, \quad h \simeq 7.283500280818951 < 9.$$

Thus edge-dependent phases alone are insufficient; an improved dual must also retain nonseparable profile-sensitive amplitudes.

20.2 Self-protecting state codes

For arbitrary systematic encoding of the 22-state envelope, exhaustive search proves that seven parity bits are necessary and sufficient for distance five:

$$\boxed{(n, M, d) = (12, 22, 5)}.$$

The exhaustive radius-two decoder surface contains $22(1 + 12 + \binom{12}{2}) = 1738$ received words. In the linear systematic case, every five-bit difference occurs, so the problem is a binary $[5 + r, 5, 5]$ code. All 26,334 six-parity candidates and all 7,624,512 seven-parity candidates fail; eight parity bits succeed:

$$\boxed{[13, 5, 5]}, \qquad (c_0, \dots, c_4) = (15, 51, 85, 106, 150).$$

The 12-bit code is information-theoretically smaller; the 13-bit code is XOR-linear over all 32 words.

20.3 Six-spare dynamic recovery

Static state-availability mirroring uses 32 physical slots. Under an explicit protected-symbolic-state/recompilation contract, allowing bounded state remapping while preserving every original transition distance changes the frontier. Every one of the 6,884 fixed spare banks of size at most five fails. At size six there are exactly 96 solutions; the first is

$$\boxed{\{0, 1, 2, 3, 4, 5\}}.$$

Therefore 22 physical slots are necessary and sufficient for post-fault symbolic remapping at the original work 34 and dilation two.

20.4 Gauge fusion and the local A_2 root plane

The 720 minimum supports have 24 unordered-pair orbits. Their local fusion laws include annihilation, coefficient reversal, third-root completion, and a three-edge filled-face state. On one filled triangle the six weight-two flat cochains are precisely the six nonzero roots of an A_2 plane over $\mathbb{F}_3$. Consequently

$$Z^1(X;\mathbb{F}_3^5) \cong \big(A_2(\mathbb{F}_3)\otimes \mathbb{F}_3^5\big)^{\oplus 240}, \qquad \dim Z^1 = 2400,$$

with the 220-dimensional switching subspace leaving $\dim H^1 = 2180$.

20.5 Triple faults and the Q_6 boundary

The mirrored Q_5 census is

faults	cases	catastrophic	worst work	worst dilation
EEE	82160	0	40	3
VEE	101120	0	42	4
VVE	39680	1280	45	4
VVV	4960	480	46	4

Three Q_4 layers, or 48 slots, are cardinality-minimal for arbitrary two-vertex loss. Four layers give $Q_6 = Q_4 \square Q_2$, use 64 slots, and are necessary and sufficient in the untouched-layer model for preserving work 34 and dilation two after any three layer-local faults.

20.6 The Clebsch checksum is a repetition-code coset graph

The four-bit tag

$$t(x) = x_{3:0} \oplus x_4(1111)_2$$

is a parity-check syndrome for the binary repetition code $\mathrm{Rep}(5) = [5,1,5]$. Hence

$$\boxed{Q_5/\,\mathrm{Rep}(5) = \mathrm{Clebsch} = \mathrm{SRG}(16,5,0,2)}.$$

Every local checksum chart has distance shells

$$\boxed{1+5+10}.$$

The five one-error neighbors are independent, while the ten two-error symbols induce the Petersen graph $KG(5,2)$: two double-error syndromes are adjacent exactly when their error-position pairs are disjoint.

The 16 closed neighborhoods form a symmetric biplane

$$\boxed{2-(16,6,2)}, \qquad BB^{\mathsf{T}} = 4I + 2J.$$

Exact automorphism enumeration gives $|\,\mathrm{Aut}(\mathrm{Clebsch})| = 1920 = 2^4 \cdot 5!$. In the even-sign model the complement is the 5-demicube skeleton and the Clebsch edges are the opposition relation on one 16-weight D_5 half-spin orbit. The controller's valid/guard coloring leaves only an elementary Abelian stabilizer C_2^3.

20.7 Equivariance versus correction radius

The repetition kernel is not controller invariant: its generator has orbit

$$\{11111_2, 01111_2, 10111_2\}$$

of weights $5, 4, 4$. The unique common invariant line is generated by 00111_2 and has distance three. Therefore no fixed one-dimensional controller-equivariant quotient gives uniform two-bit correction. One must re-encode the Clebsch syndrome, transport a moving quotient chart, or use the self-protecting 12/13-bit code.

Boundary. No ten-colour decision, exact rational magnetic certificate, recovery of destroyed uncheckpointed state data, measured fault rate, observed FPGA timing, successful fresh PDF, physical D_5 or Spin(10) identification, quantum speedup, laboratory operation, or spacetime claim is inferred from this finite packet.

21 Generalized defect radius, modular cohomology, and the five-channel crossed algebra (Passes 3444–3457)

Let $E = \mathbb{F}_3^{720}$ be the minimum-support permutation module. If R is the filled-face relation map and N the unsigned vertex–edge incidence map, exact row reduction gives

$$\operatorname{rank} R = 240, \qquad \operatorname{rank} N = 45, \qquad \operatorname{rank}[R\ N] = 284,$$

with $\operatorname{im} R \cap \operatorname{im} N = \langle \mathbf{1}_E \rangle$. Hence the scalar cohomology has the objectwise presentation

$$0 \longrightarrow \mathbf{1} \longrightarrow \mathbb{F}_3[240 \text{ faces}] \oplus \mathbb{F}_3[45 \text{ vertices}] \longrightarrow \mathbb{F}_3[720 \text{ supports}] \longrightarrow H^1 \longrightarrow 0,$$

and therefore

$$\boxed{\dim_{\mathbb{F}_3} H^1 = 436}.$$

Dually, $(H^1)^*$ is the 436-dimensional edge code whose coordinate sum vanishes on every filled face and at every vertex.

After an arbitrary $\mathbb{F}_3$-linear identification $\mathbb{F}_3^5 \cong \mathbb{F}_{243}$, the labelled minimum-defect diameter is the fifth generalized covering radius of the ternary code

$$K = \operatorname{im}[R\ N],$$

equivalently the ordinary covering radius of its scalar extension to $\mathbb{F}_{243}$. One filled face contributes the three-direction Latin-square Cayley graph

$$\mathrm{SRG}(59049, 726, 243, 6),$$

with spectrum $726^1, 240^{726}, (-3)^{58322}$ and local length enumerator $1 + 726z + 58322z^2$. The relation-aware sphere obstruction remains stronger than the ordinary 243-ary Hamming count and yields

$$\boxed{389 \le R_{\mathrm{defect}} \le 436}.$$

The exact endpoint inside this interval remains open.

The four-channel barycentric Fourier symbol factors through the equitable $1+2$ quotient of K_3,

$$M = \begin{pmatrix} 0 & 2 \\ 1 & 1 \end{pmatrix},$$

as

$$B(k) = c(k_1)(I_2 \otimes M) + c(k_2)(M \otimes I_2) + c(k_3)I_4, \qquad c(t) = \begin{cases} 2, & t = 0, \\ -1, & t \neq 0. \end{cases}$$

The hidden channel is $d(k) = c(k_3) - c(k_1) - c(k_2)$. Thus only eight zero/nonzero masks are required, rather than 27 unrelated five-dimensional symbols.

The torus amplitudes alone generate a four-dimensional commutative algebra. Adding the coordinate swap S raises the algebra dimension to six, while adding the null-conic dual sign

$$D = \operatorname{diag}(1, 1, -1, -1)$$

raises it to eight. Together,

$$\boxed{\langle I_2 \otimes M, M \otimes I_2, S, D \rangle = M_4(\mathbb{Q})}.$$

This supplies an explicit noncommuting amplitude extension beyond the exhausted phase-only magnetic families, but it is not yet a chromatic certificate; the live boundary remains $10 \leq \chi(H) \leq 11$.

Modulo three, $2 \equiv -1$, so all 27 momentum symbols collapse to one matrix J. Writing $\mathcal{N} = J - I$, exact ranks give

$$\operatorname{rank} \mathcal{N} = 2, \qquad \operatorname{rank} \mathcal{N}^2 = 1, \qquad \mathcal{N}^3 = 0,$$

so J has Jordan type $J_3(1) \oplus J_1(1) \oplus J_1(1)$ and

$$\boxed{J^3 = I}.$$

The accompanying RTL exhausts all 200 integer-symbol entries modulo three and all $8 \cdot 3^5 = 1944$ mask/state triples.

Finally, after choosing one Fano point and one D_5 coordinate, three degree-four sets carry the same faithful S_4 action: the four projective null-conic directions, the four Fano lines avoiding the selected point, and the four residual D_5 coordinates. The choices are essential, so this is an equivariant chart bridge rather than a canonical ambient-geometric identification.

The local A_2 code $[3, 2, 2]_3$ tensored with the null-conic code $[4, 3, 2]_3$ gives the additional exact construction

$$\boxed{[3, 2, 2]_3 \otimes [4, 3, 2]_3 = [12, 6, 4]_3},$$

with visible $S_3 \times S_4$ coordinate action and dual parameters $[12, 6, 3]_3$. Its length agrees with the tomotope edge count, but no tomotope incidence realization is asserted without an explicit map.

21.1 The filled-face tower, modular descent, and the tomotope boundary

The selected orbit of 240 filled triangles carries a canonical $PSp(4, 3)$-equivariant antipodal involution. Its quotient has 120 states and a symmetric rank-five association scheme with valencies

$$1, 36, 27, 2, 54.$$

The valency-two relation is $40K_3$. Quotienting its forty components recovers the original graph

$$\mathrm{SRG}(40, 12, 2, 4) = W(3, 3).$$

Consequently the filled-face carrier has the exact tower

$$\boxed{240 \longrightarrow 120 \longrightarrow 40}.$$

Each W33 point supports six filled faces, arranged as three antipodal pairs. Its stabilizer has order $648 = 3^3 \cdot 24$ and induces the full S_4 action on the six edges of a tetrahedron; the induced action on the three antipodal pairs is S_3 with kernel V_4.

Across a W33 edge, one pair-scheme relation is the complete 3-by-3 block. Across a W33 nonedge, a second relation is a permutation matrix and its companion is the complementary block. The resulting matching connection has

$$1080 \text{ identity triangle loops}, \qquad 2160 \text{ transposition loops},$$

and no three-cycle loops on the triangles of the W33 complement. This is an objectwise nontrivial transport bundle, unlike the exhausted scalar phase-only families.

In characteristic three, all five ordinary characters of the 120-state association scheme reduce to $(1, 0, 0, 2, 0)$. Its endomorphism algebra is local, with radical tower

$$\dim J = 4, \qquad \dim J^2 = 1, \qquad J^3 = 0,$$

so the 120-dimensional pair module is indecomposable. The antisymmetric antipodal summand decomposes as

$$M_- = M_{81} \oplus M_{39},$$

where the 39-dimensional summand has endomorphism ring $\mathbb{F}_3[\varepsilon]/(\varepsilon^2)$ and glues the ordinary 15- and 24-dimensional sectors. The 81-dimensional summand is retained as a brick pending an independent MeatAxe composition-series calculation. This face-permutation result is complementary to the later edge-module filtration

$$0 < R_{240} < Z^1_{480} < E_{720},$$

which produces the distinct 196-dimensional quotient $Z^1/(R + B^1)$.

The six local face tokens map to the six transposition matrices in the four-dimensional tetrahedral permutation representation. Their group algebra image has dimension ten. Adjoining the null-conic dual sign $\mathrm{diag}(1, 1, -1, -1)$ generates all of $M_4(\mathbb{Q})$. Thus scalar phases, the later finite dyadic amplitude grid, and a trivial untwisted M_4 fibre are all insufficient, while the face tower supplies the first explicit objectwise noncommuting transport extension. This is a compiler surface, not yet a chromatic certificate; the live boundary remains

$$10 \le \chi(H) \le 11.$$

For the generalized covering-radius front, the transitive fractional/Delsarte relaxation reaches the quotient size first at radius 389, so level zero cannot improve the lower bound. The exact rank-ten face coherent configuration, rank-five antipodal scheme, eigenmatrix, and intersection tensor provide the symmetry-reduced input for a higher semidefinite hierarchy. The later certified 247-circuit basis-exchange theorem improves the upper bound to 435, and a dependency verifier binds this insert to that frozen certificate. The live interval is

$$\boxed{389 \le R_{\mathrm{defect}} \le 435}.$$

Finally, the ternary $[12, 6, 4]$ A_2–conic product code does not realize the tomotope faces. Exhaustion of all 1760 weight-three ambient vectors shows that a dual-code coset contains at most four projective triple supports, whereas the tomotope requires sixteen triangular faces. Nevertheless the same 3×4 coordinate grid has a positive incidence interpretation: matching rows and vertex columns identify the coordinates with the twelve oriented tetrahedron edges. Four outgoing stars, four incoming stars, and eight directed three-cycles form an exact $12_4\,16_3$ Reye-style incidence surface. The archived negative flag search remains decisive: this skeleton alone does not determine the missing cell/orientation cocycle needed for the true 192-flag tomotope monodromy.

21.2 Radius, amplitude, modular, and five-channel closure

An exact basis-exchange certificate in the minimum-defect Cayley system produces a 247-term circuit with 246 nonzero basis coordinates. Since the coefficient alphabet has only $3^5 - 1 = 242$ nonzero vectors, a nonzero circuit shift cancels at least two basis coefficients while adding one extra generator. The covering-radius interval therefore improves to

$$\boxed{389 \le D_{H^1} \le 435}.$$

The exact radius remains open.

A five-channel amplitude-bearing magnetic family was then screened on a 63,869-point dyadic grid. Its best member has weights

$$\left(-\frac{21}{32}, \frac{43}{32}, -\frac{27}{32}, -\frac{15}{16}, 1\right)$$

and generalized Hoffman ratio approximately 8.9024605237. After scaling by 32, its exact characteristic polynomial contains $(x + 128)^{17}(x - 64)^{21}$ and a seven-dimensional residual whose roots all lie strictly in $(-128, 1024)$. Consequently the unscaled matrix has $\lambda_{\min} = -4$ and $\lambda_{\max} < 32$, proving that this winner remains strictly below nine. This is a finite-grid no-go, not an optimization of the unrestricted real cone.

Over $\mathbb{F}_3$, the 240 face boundaries form a totally isotropic subspace of the 480-dimensional flat edge space. They are disjoint from the 44-dimensional coboundary space, giving the exact filtration

$$0 < R_{240} < Z^1_{480} < \mathbb{F}_3^{720}, \qquad \dim Z^1/(R + B^1) = 196.$$

No modular irreducible name is assigned without a composition-series certificate.

The full 135-state quotient admits an executable Fourier organization

$$135 = 27 \times 5.$$

For $c(0) = 2$ and $c(1) = c(2) = -1$, the four barycentric channels have symbol $c(k_1)K_x + c(k_2)K_y + c(k_3)I_4$, while the hidden channel is $-c(k_1) - c(k_2) + c(k_3)$. Exhausting all 675 symbol entries recovers

$$10^1,\ 7^6,\ 4^{22},\ 1^{44},\ (-2)^{42},\ (-5)^{20}.$$

The finite geometry itself forms a stabilizer chain

$$5 \xrightarrow{\text{hinge}} 4 \xrightarrow{\text{pairing}} 3.$$

Choosing one of the five Clebsch/D_5 coordinate directions leaves the S_4 action on the four points of the $PG(2, 3)$ null conic. The three perfect matchings of those four points carry the quotient

$S_4/V_4 \cong S_3$ and match the three projective $A_2(\mathbb{F}_3)$ root directions and the far/middle/active Fano gauges. This is a finite permutation correspondence, not a physical Spin(10) claim.

Finally, the fixed linear $[13, 5, 5]$ controller encoder has a unique minimum coordinate-orbit completion of length 28. The completed code is

$$\boxed{[28, 5, 11]},$$

so fifteen added coordinates are necessary and sufficient for coordinate-permutation S_3 equivariance of that encoder. The Clebsch closed-neighborhood matrix is the incidence matrix of a symmetric 2-$(16, 6, 2)$ biplane, with Smith form $1^6 2^4 4^5 12$ and the modular identity $B^2 = I - J$ over $\mathbb{F}_3$. Its zero and single-point syndromes have minimum distance six.

22 Triangle-free strongly regular graphs and the missing-Moore firewall

Exact fixed-μ ladder. For a strongly regular graph with

$$\mu = 4 \qquad \text{and restricted eigenvalue} \qquad r = 2,$$

the remaining data are forced by the SRG identities:

$$s = \lambda - 6, \qquad k = 16 - 2\lambda, \qquad v = \frac{(\lambda - 7)(3\lambda - 22)}{2},$$

with multiplicities

$$f_r = \frac{(\lambda - 5)(3\lambda - 22)}{2}, \qquad f_s = -3(\lambda - 7).$$

For $\lambda = 0, 1, 2, 3, 4$ this gives

$$\boxed{(77, 16, 0, 4) \longrightarrow (57, 14, 1, 4) \longrightarrow (40, 12, 2, 4) \longrightarrow (26, 10, 3, 4) \longrightarrow (15, 8, 4, 4).}$$

These are respectively the M_{22} graph, the nonexistent Wilbrink–Brouwer parameter set, the $W(3, 3)$ parameter class, the Paulus parameter class, and the triangular graph $T(6)$. Thus there is an exact 57-vertex spectral hole between M_{22} and $W(3, 3)$. It is not the hypothetical degree-57 Moore graph, whose parameters would be $(3250, 57, 0, 1)$.

$W(3, 3)$–Gewirtz restricted kernel. The $W(3, 3)$ and Gewirtz adjacency spectra are

$$12^1, 2^{24}, (-4)^{15} \qquad \text{and} \qquad 10^1, 2^{35}, (-4)^{20}.$$

After removing the constant line, both operators therefore obey

$$\boxed{(A - 2I)(A + 4I) = 0.}$$

Their complement operators have restricted eigenvalues ± 3, so their centered complement squares equal $9I$ on augmentation. This is a shared quadratic functional calculus, not a canonical objectwise intertwiner; the multiplicities and incidence geometries differ.

Necessary edge chart for a hypothetical M_{57}. Assume temporarily that a Moore graph with parameters $(3250, 57, 0, 1)$ exists and fix an edge $a \sim b$. The punctured neighborhoods

$$A = N(a) \setminus \{b\}, \qquad B = N(b) \setminus \{a\}$$

have size 56, and the remaining $3136 = 56^2$ vertices are forced bijectively onto $A \times B$. Every residual vertex has one neighbor in A, one in B, and 55 residual neighbors. No residual edge lies inside a row or column; hence every pair of distinct rows, and every pair of distinct columns, is joined by a perfect matching. If $\sigma_{ij} \in S_{56}$ denotes the matching from row i to row j, then necessarily

$$\sigma_{ji} = \sigma_{ij}^{-1}, \qquad \sigma_{ij} \text{ is fixed-point-free,}$$

and for distinct i, j, k the product

$$\sigma_{ki}\sigma_{jk}\sigma_{ij}$$

is fixed-point-free. These are necessary, not sufficient, constraints. Crucially, relabelling rows and columns is coordinate gauge, not an automorphism of one fixed completed graph; and

$$\frac{3250 \cdot 57}{2} = 92{,}625$$

is the edge count, not the automorphism-group order.

The four-way 57 firewall. Four different objects must remain separate:

object	meaning
M_{57}	3250 vertices, degree 57, existence open
$(57, 14, 1, 4)$	57 vertices, proved nonexistent
Perkel graph	57 vertices, degree 6
regular 57-cell	57 cells, $PSL(2, 19)$ symmetry

A June 2026 preprint claims that a hypothetical M_{57} has no involutory automorphisms. If that result survives review, then its automorphism group has odd order, whereas

$$|PSL(2, 19)| = 3420$$

is even; consequently the 57-cell/Perkel symmetry cannot embed into $\mathrm{Aut}(M_{57})$. This conditional firewall is not a proof of nonexistence.

Machine certificate. The standard-library verifier `analysis/bt3500_3505_triangle_free_srg_m57_bridge.` reconstructs all parameter, spectrum, multiplicity, edge-chart, and order identities above. Its frozen semantic digest is

`e308364dd480970803061b90ab27bf86afa2ae4946399b656292f02682c17fd9`.

The evidence boundary is explicit: no existence decision for the missing Moore graph, no Perkel/57-cell/Moore identification, and no canonical $W(3, 3)$–Gewirtz intertwiner are asserted.

23 Passes 3506–3512: exact descendants, Moore permutation curvature, and the scheme-blind 57-hole

Certified seven-front packet

The standard-library verifier reports

`PASS_7_FRONTS`

with semantic SHA-256

`15ab9b21e744e755917e0b4c40ec806b43c5463b8a11cfbfac7bdbb4a9c8dfe7`.

The packet supplies an executable Moore-57 permutation CSP, literal descendant constructions among five standard triangle-free strongly regular graphs, the complete rank-three Krein census of the fixed $\mu = 4, r = 2$ ladder, a W33/Gewirtz polynomial-transplant compiler, a sharpened 57-cell symmetry firewall, and two explicitly fenced high-risk constructions.

23.1 The Moore chart becomes a gauge-reduced permutation CSP

For a fixed edge of a hypothetical $\mathrm{SRG}(3250, 57, 0, 1)$, write $p_{ij}(a)$ for the destination column in row j of the residual neighbor of (i, a). The independent matching data contain

$$\binom{56}{2}56 = 86\,240$$

entries. The literal CP-SAT exporter uses 172 480 directed integer variables with explicit inverse channels, rather than 4 743 200 nonfixed one-hot Boolean variables. Before lazy cuts it has 1 540 row-pair permutation constraints, 1 540 inverse channels, 3 136 vertex-star constraints, and 55 gauge equalities:

$$p_{0j}(0) = j, \qquad 1 \le j \le 55.$$

Triangle fixed points are separated over the

$$\binom{56}{3} = 27\,720$$

row triples. This is a source-complete model, not a solved instance.

23.2 Two literal descendant chains

The Clebsch graph is reconstructed on the even-weight vectors of $\mathbb{F}_2^5$, with adjacency at Hamming distance four. Its second subconstituent at zero consists of the ten weight-two words and is exactly $KG(5, 2)$, the Petersen graph.

Independently, a cyclic generator produces the extended binary Golay code with weight distribution

$$1 + 759z^8 + 2576z^{12} + 759z^{16} + z^{24}.$$

Fixing two coordinates in the octads yields the 77 blocks of $S(3, 6, 22)$. Hexad disjointness gives M_{22}; avoiding one point gives Gewirtz; adjoining the 22 points and infinity gives Higman–Sims. Thus

$$\boxed{\mathrm{HS} \longrightarrow M_{22} \longrightarrow \mathrm{Gewirtz}}$$

and

$$\boxed{\text{Clebsch} \longrightarrow \text{Petersen}}$$

are now objectwise executable.

23.3 The nonexistent 57-vertex rung is invisible to rank-three feasibility

For every member of the fixed

$$\mu = 4, \qquad r = 2$$

ladder, the verifier computes the complete primitive-idempotent Krein products and both standard absolute bounds. Every test passes, including for the nonexistent parameter set $\mathrm{SRG}(57, 14, 1, 4)$. Its nontrivial Krein rows are

$$q_{11} = \left(38, \frac{1273}{49}, \frac{1140}{49}\right), \quad q_{12} = \left(0, \frac{540}{49}, \frac{722}{49}\right), \quad q_{22} = \left(18, \frac{342}{49}, \frac{111}{49}\right).$$

Hence its obstruction is not visible in the ordinary rank-three Bose–Mesner algebra:

$$\boxed{\text{the } \lambda = 1 \text{ hole is scheme-blind.}}$$

Finer local, Terwilliger, or star-complement compatibility is required.

23.4 A two-channel W33/Gewirtz transplant algebra

On augmentation, W33 and Gewirtz both satisfy

$$A^2 + 2A - 8I = 0.$$

Consequently every adjacency polynomial reduces uniquely to

$$f(A) = aA + bI$$

in $\mathbb{Q}[x]/(x^2 + 2x - 8)$. Moreover

$$U = \frac{-I - A}{3}$$

obeys

$$U^2 = I, \qquad P_{\pm} = \frac{I \pm U}{2}.$$

Polynomial identities transport automatically. Traces and projector ranks depend on the different multiplicities, while incidence, codes, automorphism groups, and descendant maps remain geometry-sensitive.

23.5 The 57-cell firewall and its surviving odd shadow

The Perkel/57-cell group has order

$$|PSL(2, 19)| = 3420.$$

Peer-reviewed results bound an odd hypothetical M57 automorphism group by 375 and an even one by 110. Conditional on the June 2026 no-involution preprint, $\mathrm{Aut}(M57)$ is odd and hence solvable; there can be no common A_5 or full $PSL(2, 19)$ automorphism action. However, the odd Borel subgroup

$$C_{19} \rtimes C_9, \qquad |C_{19} \rtimes C_9| = 171,$$

is not excluded by parity and the order bound alone. The next exact target is the restriction of the Perkel -3 twenty-plane to this 19:9 shadow.

23.6 Bonkers front: non-Abelian Moore curvature

The row matchings form an S_{d-1}-valued connection. Triangle holonomy

$$H_{ijk} = \sigma_{ki}\sigma_{jk}\sigma_{ij}$$

changes by conjugacy under gauge, so cycle type is invariant. In an exact edge-rooted chart of the Hoffman–Singleton graph, all 15 row-pair matchings and all 20 triangle holonomies have cycle type

$$2^3.$$

This motivates a non-necessary M57 search branch in which all matchings and triangle holonomies have type 2^{28}. It is a solver ansatz, not an M57 theorem.

23.7 Bonkers front: one Golay puncture/avoidance functor

The chain

$$[23, 12, 7] \to [24, 12, 8] \to S(3, 6, 22) \to M_{22} \to \text{Gewirtz}$$

together with the incidence extension to Higman–Sims is one executable information-losing pipeline. Its comparison with the W33 face tower $240 \to 120 \to 40$ is structural only: no category equivalence or group identification is asserted.

Evidence boundary. No M57 existence decision, complete CP-SAT run, necessity of involutive curvature, actual M57 19:9 action, canonical W33–Gewirtz intertwiner, or peer-reviewed status for the June 2026 preprint is claimed.

24 Multi-circuit, Reed–Muller, compound-biplane, and A_5 closure

The minimum-defect interval remains

$$389 \le D_{H^1} \le 435,$$

but the single-circuit method is now closed exactly. A deterministic basis exchange produces a certified 260-term circuit. Since a rank-436 fundamental circuit contains at most 436 basis coordinates while the nonzero coefficient alphabet has size $3^5 - 1 = 242$, one circuit can force at most two cancellations while adding one support. Hence no single-circuit pigeonhole argument can improve the universal upper bound below 435.

A five-channel continuous amplitude search gives a numerical candidate with ratio approximately 8.9062301931. The nearby exact tuple

$$\frac{1}{256}(122, 346, 220, -240, 256)$$

has a rational-polynomial certificate proving

$$8.905 < h < 9.$$

Thus it improves the earlier finite-grid witness but does not reach the live chromatic lower bound.

The complete binary coordinate-permutation S_3-equivariant dimension-five code frontier was exhausted through length forty. In particular,

$$[13, 5, 5], \qquad [16, 5, 8], \qquad [24, 5, 11], \qquad [28, 5, 14]$$

are length-minimal at the displayed target distances. The sixteen columns of the $[16, 5, 8]$ code are exactly the affine hyperplane

$$\{c \in \mathbb{F}_2^5 : \langle 00111, c\rangle = 1\},$$

so the controller code is objectwise $RM(1, 4)$ with weight enumerator $1 + 30z^8 + z^{16}$.

The Clebsch biplane has thirty fourfold collision classes among its 120 weight-two faults. A canonical exhaustive search proves that three additional bits are necessary and sufficient to separate all of them. The resulting nineteen-bit readout uniquely locates all

$$1 + 16 + \binom{16}{2} = 137$$

fault patterns of weight at most two. The minimal companion map is cubic in the four-bit Clebsch-axis coordinate.

Finally, an objectwise A_5 character computation separates the two tempting rank-twenty sectors. The Perkel -3 sector restricts as

$$1 \oplus 3 \oplus 3' \oplus 2 \cdot 4 \oplus 5,$$

whereas the W33 block -4 sector restricts as

$$3 \cdot 1 \oplus 3 \cdot 4 \oplus 5.$$

Consequently no A_5-equivariant rank-twenty intertwiner exists. The live chromatic boundary remains $10 \le \chi(H) \le 11$.

25 Borel Fourier anatomy, star complements, and typed Moore searches

Passes 3528–3534 execute the five graph-theoretic continuations after reconciling the complete-switch and common-A_5 packets. The exact standard-library verifier reports

`PASS_7_FRONTS`

with semantic digest

`1ec126887cd1f09b8cdc074872567dd4962c2a399c1b14db8b035a8ea50dc591`.

The degree-57 Moore graph remains open; no 56-fibre SAT or UNSAT result is claimed.

25.1 The Perkel twenty-plane restricted to the odd Borel subgroup

On the explicit Perkel model $(i, j) \in \mathbb{Z}_3 \times \mathbb{F}_{19}$, the maps

$$(b, m) : (i, j) \longmapsto (i + m, 4^m j + b)$$

realize all 171 elements of

$$B = C_{19} \rtimes C_9.$$

Every map is checked objectwise against the edge set. The -3 spectral projector is evaluated integrally through

$$171E_{-3} = -A^3 + 9A^2 - 19A + 6I.$$

The restricted character has value distribution

$$20^1, \qquad 1^{18}, \qquad 2^{38}, \qquad (-1)^{114},$$

and fixed dimensions

$$\dim V^{C_{19}} = 2, \quad \dim V^{C_9} = 2, \quad \dim V^{C_3} = 8, \quad \dim V^B = 0.$$

Over $\mathbb{Q}$ the twenty-plane is

$$\boxed{V_{-3}\downarrow_B \cong V_{18} \oplus V_2,}$$

where V_{18} is the conductor-19 rational constituent and V_2 is the conductor-3 constituent. This closes the surviving 19:9 comparison on the Perkel side only; it does not construct that subgroup in a hypothetical Moore graph.

25.2 The 57-vertex star-complement firewall

For the nonexistent parameter set

$$\mathrm{SRG}(57, 14, 1, 4),$$

the eigenvalue 2 has multiplicity 38, so a star complement has order 19. An independent heavy enumeration from the canonical windmill seed gives stage counts

$$22, \quad 784, \quad 157{,}349,$$

and exactly

$$\boxed{3{,}720}$$

spectral survivors. Their canonical ledger hash is

`c1e0cb753fbdeab4d8ecf8059896b6ff1eb1fcc75c663022ab7040ceea012219`.

The published compatibility-graph census has maximum clique 31, whereas reconstruction requires a 38-clique. Therefore

$$\boxed{31 < 38}$$

reproves nonexistence, with margin seven. The 3,720 candidate census is independently regenerated here; the complete maximum-clique histogram remains source-locked to the published Cliquer computation and is not presented as a fresh independent rerun.

25.3 Two typed Moore-57 solver tracks

For fibre size $n = d - 1$, a diameter-two Moore graph has parameters

$$(d^2 + 1, d, 0, 1)$$

and restricted polynomial

$$x^2 + x - (d - 1).$$

The exact global gate leaves only

$$\boxed{n \in \{1, 2, 6, 56\}},$$

corresponding to C_5, Petersen, Hoffman–Singleton, and the open degree-57 case. Every even stage $n = 8, 10, \ldots, 54$ fails spectrum or multiplicity integrality before a local CSP is built.

The unrestricted $n = 56$ model retains 172,480 directed integer variables, 6,271 structural constraints, and lazy triangle and common-neighbour separators. A second high-risk branch imposes

$$\sigma_{ij}^2 = 1$$

on every fixed-point-free row matching and separates triangle holonomies by cycle type 2^{28}. This adds 86,240 source-level element-involution constraints. Neither branch has an $n = 56$ verdict.

25.4 The two descendant towers are typed differently

The W33 face tower

$$240 \longrightarrow 120 \longrightarrow 40$$

is a pair of uniform quotients with fibre sizes two and three. The Golay–Witt chain

$$100 \longrightarrow 77 \longrightarrow 56$$

uses induced restriction and point avoidance. Since

$$100/77 \notin \mathbb{Z}, \qquad 77/56 \notin \mathbb{Z},$$

there is no common uniform-fibre quotient functor. The correct shared language requires distinct morphism types: uniform quotient, induced restriction, point avoidance, and incidence extension.

25.5 Fail-closed W33–Gewirtz transplantation

Automatic transfer is permitted only for statements reducible in

$$\mathbb{Q}[x]/(x^2 + 2x - 8).$$

Thus every adjacency polynomial reduces to $aA + bI$, and

$$U = \frac{-I - A}{3}, \qquad U^2 = I$$

is common on augmentation. Traces, determinants, ranks, multiplicities, Smith data, and p-ranks require new evidence. Lines, incidence, codes, automorphism groups, descendant maps, and objectwise intertwiners are denied automatic transfer. A repository scanner now fails closed on any explicit unsafe `AUTO_PORT` annotation.

25.6 Two outside-box consequences

The complete Perkel vertex module has the rational Borel decomposition

$$\boxed{\mathbb{Q}^{57} \cong \mathbf{1} \oplus 3V_{18} \oplus V_2.}$$

Its combined golden eigenspace is $2V_{18}$, while the -3 twenty-plane is $V_{18} \oplus V_2$. The whole graph is therefore one constant channel, three conductor-19 channels, and one conductor-3 phase channel.

Inside the involutive Moore branch, the vertex-star all-different law implies that the $n - 1$ matchings issuing from each source row form a 1-factorization of K_n. Hoffman–Singleton becomes six coupled non-group 1-factorization pencils of K_6. The $n = 56$ branch becomes

$$\boxed{\text{56 reciprocity-coupled 1-factorizations of } K_{56},}$$

with 55 perfect matchings and $55 \cdot 28 = 1540$ edges covered once in every pencil. Pair-matching involution is coordinate dependent; holonomy cycle type is gauge invariant, and the theorem applies only to the declared involutive branch.

26 Star-clique recertification, Borel–M57 archetypes, and nonseparable Moore factorization

The executable Passes 3535–3541 report

`PASS_7_FRONTS  34ea459ab6acea3a2b5624ba6523016cfb914ffb54220ed64230f74f78a1fb6b.`

The degree-57 Moore graph remains open; all statements below are finite theorems or explicitly conditional necessary conditions.

26.1 Independent star-complement clique source

For each of the 3720 independently regenerated 19-vertex star complements with adjacency matrix C, the companion source constructs

$$M = 2I - C$$

exactly, enumerates every admissible binary reconstruction column b satisfying

$$b^{\mathsf{T}} M^{-1} b = 2,$$

and joins two columns when their exact inner product is -1 or 0 and the corresponding $(\lambda, \mu) = (1, 4)$ common-neighbour bound is respected. A deterministic bitset maximum-clique engine emits a witness and proof digest for every instance. The complete heavy job fails closed unless it reproduces the published clique histogram and compatibility-graph order range 4 through 265. No fresh all-3720 result is promoted before its artifact is observed.

26.2 Prime fixed sets and the surviving Borel action

Let an automorphism of prime order p act on a hypothetical

$$\mathrm{SRG}(3250, 57, 0, 1).$$

A nontrivial fixed set is closed under unique common neighbours, and if it has more than one vertex its induced graph is itself a Moore graph, with fixed degree congruent to 57 modulo p. Consequently an order-19 element fixes exactly one vertex, whereas an order-3 element fixes either one vertex or a Petersen graph.

Assume conditionally that

$$B = C_{19} \rtimes C_9$$

acts. Orbit arithmetic leaves precisely

$$P_{19} : \ 1 + 9 \cdot 19 + 18 \cdot 171, \qquad P_{57} : \ 1 + 3 \cdot 57 + 18 \cdot 171.$$

The adjacency trace on an order-19 element first permits

$$g \in \{57, 342, 627, 912, 1197\},$$

where g counts vertices mapped to neighbours. Girth and equal displacement for nontrivial powers leave only

$$\boxed{g \in \{57, 342\}}.$$

Thus exactly four conditional action archetypes survive: low/high versions of P_{19} and P_{57}. They are necessary forms, not constructions or a contradiction.

26.3 Exact Perkel Fourier projectors

Let A be the Perkel adjacency matrix, J the all-ones matrix, and B_{19} the block diagonal matrix with three J_{19} blocks. Put

$$N = -A^3 + 9A^2 - 19A + 6I.$$

The integer projector numerators

$$P_1 = 3J, \quad P_2 = 9B_{19} - 3J, \quad P_{18} = N - 9B_{19} + 3J, \quad P_{36} = 171I - 3J - N$$

have ranks

$$1, 2, 18, 36$$

and satisfy

$$P_i P_j = 171\delta_{ij} P_i, \qquad \sum_i P_i = 171I.$$

The conductor-19 projector is

$$\boxed{P_{54} = 171I - 9B_{19} = P_{18} + P_{36}},$$

and

$$(A^3 - 8A + 3I)P_{54} = 0.$$

Hence every Perkel adjacency polynomial reduces to a constant channel, a ternary V_2 channel, and a degree-two normal form on the conductor-19 sector modulo $x^3 - 8x + 3$.

26.4 The one-factorization field

Inside the involutive edge-chart branch, each row pencil is a one-factorization. The exact Hoffman–Singleton control has 15 perfect matchings and exactly six labelled one-factorizations of K_6. Its six residual rows realize all six factorizations exactly once. Moreover, all $5! = 120$ globally separable colour identifications fail all 20 row triangles: every one of the 2400 holonomies has two fixed points. The actual Hoffman–Singleton holonomies all have cycle type 2^3.

Therefore a hypothetical involutive $n = 56$ branch cannot reuse one global factorization. It requires 56 genuinely row-dependent, reciprocity-coupled one-factorizations of K_{56}, each containing 55 perfect matchings and covering all 1540 symbol pairs.

26.5 Typed W33–Gewirtz polynomial port

Both exact graphs satisfy the common restricted relation

$$(A - 2I)(A + 4I) = 0$$

on augmentation. With $P = J/v$ and $Q = I - P$, the full identity is

$$(A - 2I)(A + 4I) = (k - 2)(k + 4)P.$$

The reflection

$$R = \frac{(k+1)P - I - A}{3}$$

satisfies $R^2 = Q$, and

$$E_2 = \frac{Q - R}{2}, \qquad E_{-4} = \frac{Q + R}{2}.$$

If $p(x) \equiv ax + b \pmod{x^2 + 2x - 8}$, then

$$\boxed{p(A) = p(k)P + (aA + bI)Q.}$$

This ports every adjacency-polynomial and functional-calculus theorem. Trace, determinant, and rank formulas require the typed multiplicities $(24, 15)$ for W33 and $(35, 20)$ for Gewirtz. Incidence, codes, automorphisms, Smith forms, descendants, and intertwiners remain geometry-sensitive and require independent evidence.

Boundary. No M57 existence verdict, unobserved full clique rerun, W33–Gewirtz objectwise equivalence, hardware result, or physical interpretation is asserted.

27 Cyclic Borel quotients, the Perkel commutant, and the outer-S_6 Moore chart

Passes 3542–3548 continue the degree-57 Moore and Perkel program with exact finite certificates. The corresponding verifier reports

`PASS_7_FRONTS a98621cc2f2378eaed09b8f747022f419a16fbb33433336eeb8f2414f4273f1a`

The missing Moore graph remains open.

The C_{19} quotient becomes three exact branches. Assume $B = C_{19} \rtimes C_9$ acts on a hypothetical SRG$(3250, 57, 0, 1)$. The normal C_{19} fixes one vertex and has 171 nonfixed orbit cells. Exactly three cells lie in the fixed vertex's neighbourhood. Writing $S_{ij} \subseteq \mathbb{Z}_{19}$ for the cyclic shifts between cells and $T_i = S_{ii}$, the unique-common-neighbour law forces the three neighbour cells to be independent, every connection leaving them to have size at most one, and their orbit-neighbour sets to be disjoint. Hence the remaining 168 cells split exactly as

$$168 = 56 + 56 + 56.$$

For a nonneighbour cell,

$$\sum_j |S_{ij}|(|S_{ij}| - 1) = 18 - |T_i|, \qquad |T_i| \in \{0, 2, 4\}.$$

C_9 or C_3 stabilizer invariance forbids nonempty T_i inside Borel orbits of size 19 or 57, so internal edges occur only in the eighteen size-171 Borel orbits. If a of those have internal degree two and b have internal degree four, the two displacement levels reduce to

$$a + 2b = 3 \quad \text{or} \quad a + 2b = 18.$$

Together with the two orbit profiles P_{19} and P_{57}, the four Borel archetypes reduce to exactly twenty-four aggregate cyclic-difference signatures. This is a finite CSP frontier, not a construction or contradiction.

The complete Perkel Borel commutant. For the explicit Perkel action $(i, j) \mapsto (i+m, 4^m j + b)$, the point stabilizer is C_3 with three singleton orbits and eighteen orbits of size three. The orbital algebra therefore has rank 21. The rational module

$$\mathbb{Q}^{57} = \mathbf{1} \oplus 3V_{18} \oplus V_2$$

gives projected algebra dimensions $1, 2, 18$, and hence

$$\mathrm{End}_B(\mathbb{Q}^{57}) \cong \mathbb{Q} \oplus M_3\big(\mathbb{Q}(\sqrt{-19})\big) \oplus \mathbb{Q}(\sqrt{-3}).$$

Let P_{54} and P_2 be the conductor-19 and conductor-3 projector numerators. The block-diagonal Paley tournament matrix D_{19} and the oriented three-layer all-one operator C_3 obey

$$9D_{19}^2 = -P_{54}, \qquad 3C_3^2 = -19P_2,$$

and commute with all twenty-one orbital matrices. The commutative adjacency layer has exact span

$$\mathbb{Q}[A, B_{19}] \cong \mathbb{Q} \times \mathbb{Q} \times \mathbb{Q} \times \mathbb{Q}(\sqrt{5}),$$

with basis $I, A, A^2, B_{19}, AB_{19}$.

Proof-carrying maximum cliques. The star-complement pipeline now has an independently checkable upper-bound proof language. A colour leaf proves $\omega(P) \le K$ by a proper K-colouring of the current candidate set. A branch node on v proves the include subproblem at $K-1$ and the exclude subproblem at K. The checker reconstructs all subproblems, verifies colour classes and references, and separately checks the clique witness. Thirty-one deterministic controls pass. A complete 3720-instance proof archive remains a heavy workflow boundary.

A factorization-field Moore compiler. Let n be even and suppose $F_0, \dots, F_{n-1}$ are one-factorizations of K_n satisfying $|F_i \cap F_j| = 1$. Let m_{ij} be the shared perfect matching. The vertex set

$$\{x, y\} \cup \{r_i\} \cup \{c_a\} \cup \{z_{i,a}\}$$

with edges

$$x \sim y, r_i, \qquad y \sim c_a, \qquad z_{i,a} \sim r_i, c_a, z_{j,m_{ij}(a)}$$

has $(n+1)^2 + 1$ vertices and degree $n+1$. If every simple three-row and four-row holonomy is fixed-point-free, the graph has girth at least five and meets the Moore bound exactly. For $n = 56$ this becomes a 3250-vertex, degree-57 construction surface with 27720 triangle checks and 1101870 simple four-cycle checks. Pairwise unique intersection is a sufficient high-risk branch, not a proved necessity.

Hoffman–Singleton as the outer automorphism of S_6. The fifteen duads, fifteen synthemes, and six pentads are respectively the edges, perfect matchings, and one-factorizations of K_6. Exact enumeration shows that every pair of pentads shares exactly one syntheme, every triangle holonomy has cycle type 2^3, and every simple four-row holonomy has cycle type 3^2. The induced action of S_6 on the six pentads is faithful of order 720; a point transposition of type $2\,1^4$ maps to type 2^3, certifying the outer action. Feeding the shared synthemes into the factorization-field compiler reconstructs

$$\mathrm{SRG}(50, 7, 0, 1),$$

the Hoffman–Singleton graph.

Analytic W33–Gewirtz ports. For either graph,

$$f(A) = f(k)P + f(2)E_2 + f(-4)E_{-4}$$

for every analytic f. In particular the heat kernel and resolvent port exactly, while the Ihara–Bass factors retain the graph-specific degree and multiplicities. No incidence, code, automorphism, hardware, or physical claim is inferred from this spectral compiler.

28 Passes 3549–3555: Borel orbit models, exact commutants, octad curvature, and quantum walks

Twenty-four exact Borel models. For a conditional $B = C_{19} \rtimes C_9$ action on a degree-57 Moore graph, the two orbit profiles and the equations $a + 2b = 3, 18$ produce exactly 24 aggregate signatures. Burnside gives 30,915 undirected edge-orbit variables and 61,858 ordered-pair orbitals for P_{19}, versus 30,885 and 61,792 for P_{57}. Every model imposes the exact lazy relation

$$\sum_w e_{uw}e_{vw} = 0 \text{ if } e_{uv} = 1, \qquad \sum_w e_{uw}e_{vw} = 1 \text{ if } e_{uv} = 0.$$

These are complete finite model surfaces, not SAT or UNSAT verdicts.

Complete Perkel orbital algebra. The 19:9 action has 21 orbitals, with size profile $57^3\,171^{18}$ and valencies $1^3\,3^{18}$. The exact multiplication table contains 1,035 nonzero integral structure constants, all at most three, and has five-dimensional center:

$$\mathrm{End}_{19:9}(\mathbb{Q}^{57}) \cong \mathbb{Q} \oplus M_3(\mathbb{Q}(\sqrt{-19})) \oplus \mathbb{Q}(\sqrt{-3}).$$

Transpose splits the algebra into 11 symmetric and 10 skew channels. Thus every real symmetric equivariant kernel lies in an eleven-dimensional space corresponding, after the imaginary-quadratic embeddings, to

$$\mathbb{R} \oplus \mathrm{Herm}_3(\mathbb{C}) \oplus \mathbb{R}.$$

Generalized pentads and an octad falsifier. The exact labelled one-factorization counts for K_4, K_6, K_8 are $1, 6, 6240$. A family of eight K_8 one-factorizations was found in which every pair shares exactly one perfect matching; its setwise S_8-stabilizer is trivial. However only 34/56 triangle holonomies and 163/210 simple four-row holonomies are derangements. The compiled graph is 9-regular on 82 vertices, has diameter three, 60 triangles, and 422 four-cycles. Hence pairwise factor intersection is the static design condition, while holonomy is the curvature condition deciding the Moore property.

Proof archive and analytic dynamics. The 3,720 star-complement proof DAGs are assigned to 64 deterministic shards, eight of size 59 and 56 of size 58, with an ordered Merkle aggregate. The archive protocol is complete, but the full payload remains evidence-gated. For either W33 or Gewirtz,

$$e^{-itA} = e^{-ikt}P + e^{-2it}E_2 + e^{4it}E_{-4}.$$

For W33, distinct-vertex amplitudes obey

$$|U_{xy}(t)| \le \frac{1}{4} \quad (x \sim y), \qquad |U_{xy}(t)| \le \frac{2}{15} \quad (x \nsim y),$$

and for Gewirtz

$$|U_{xy}(t)| \le \frac{2}{7} \quad (x \sim y), \qquad |U_{xy}(t)| \le \frac{1}{12} \quad (x \nsim y).$$

Thus neither graph permits perfect continuous-time state transfer between distinct vertices. The exact infinite-time average probabilities and nonbacktracking poles are emitted by the verifier.

> **Boundary.** The degree-57 Moore graph remains open. No Borel signature has a solver verdict, the full proof archive is not yet promoted, the K_8 graph is a falsifier rather than a Moore construction, and the quantum-walk formulas are mathematical dynamics rather than laboratory measurements.

29 Relation planes, magnetic conductors, code duality, and the pentagonal bridge

The live cohomology and chromatic boundaries remain

$$389 \le D_{H^1} \le 435, \qquad 10 \le \chi(H) \le 11.$$

A new exact fundamental cohomology relation has weight 263. In a deterministically extended fundamental basis, all $\binom{284}{2} = 40186$ nonbasis-column pairs were exhausted. Their rows occupy at most three of the four directions of $PG(1,3)$, the maximum union support is 319, and the adversarial cancellation-cap histogram is

$$\{2 : 34119,\ 3 : 5277,\ 4 : 790\}.$$

Thus this pure two-circuit direction method cannot establish $D_{H^1} \le 433$; 790 pairs remain label-sensitive candidates for 434. An exact pilot on all $\binom{64}{3} = 41664$ triples of the 64 heaviest columns reaches union support 360 and six occupied directions of $PG(2,3)$.

The five-channel Hermitian algebra has channel sizes

$$2, 1, 30, 60, 627$$

and exact characteristic factorization

$$(x + 4w_4)^{17}(x - 2w_4)^{21} q_2(x) q_5(x),$$

where

$$q_2(x) = x^2 + (w_1 + w_4)x + w_1 w_4 - 9w_3^2$$

and q_5 is quintic. The dyadic tuple

$$\frac{1}{32768}(-15576, 44300, -28135, -30786, 32768)$$

has an exact rational-root certificate proving

$$8.90622 < h < 8.90623.$$

A degree-eighteen elimination polynomial isolates a stationary candidate near $h = 8.90623076116309$, but global unrestricted optimality remains open.

The complete duality atlas of the four binary equivariant frontier codes gives

$[n,5,d]$	$d^\perp$	$\dim(C\cap C^\perp)$	$\lvert\operatorname{Aut}(C)\rvert$
$[13,5,5]$	3	2	48
$[16,5,8]$	4	5	322560
$[24,5,11]$	3	0	72
$[28,5,14]$	3	3	64512

with generalized weights computed exactly. The length-sixteen code is $RM(1,4)$ with automorphism group $AGL(4,2)$, while the length-twenty-eight code is the binary simplex code punctured on one projective line.

For compound Clebsch readout, three added bits cannot even force distance two, four cannot force distance three, and five bits attain distance three. Therefore five companion bits are necessary and sufficient to locate every zero-, single-, and double-device fault while correcting one corrupted readout bit. The resulting code has length twenty-one and 137 protected patterns.

Finally, the Perkel and W33 rank-twenty modules, although inequivalent over A_5, become fully isomorphic on the common pentagonal subgroup:

$$P_{20}\downarrow_{C_5}\cong W_{20}\downarrow_{C_5}\cong 4\mathbf{1}\oplus 4\mathbb{Q}(\zeta_5).$$

The rational intertwiner space has dimension 80. No canonical objectwise intertwiner is asserted.

A second objectwise closure identifies the 240 W33 edges with the 240 filled triangles of the 45-octet port graph: every W33 edge belongs to exactly three canonical $K_{4,4}$ octets, and the resulting triangles partition all 720 block-graph edges.

30 Maximal cyclic rank-twenty bridge and a gate-minimal fault locator

The rational C_5 restrictions of the Perkel and W33 rank-twenty modules are

$$P_{20}\downarrow_{C_5}\cong W_{20}\downarrow_{C_5}\cong 4\mathbf{1}\oplus 4\mathbb{Q}(\zeta_5).$$

Consequently their rational intertwiner algebra is

$$M_4(\mathbb{Q})\oplus M_4(\mathbb{Q}(\zeta_5)),$$

of dimension 80. Thus C_5 symmetry alone does not select a preferred objectwise map.

The full sixteen-dimensional cyclotomic moving sector extends to the dihedral normalizer D_{10}. The only obstruction lies in the four-dimensional C_5-fixed sector:

$$P_{20}\downarrow_{D_{10}}\cong 2\mathbf{1}\oplus 2\varepsilon\oplus 4V_{\mathrm{cyc}},$$

$$W_{20}\downarrow_{D_{10}}\cong 4\mathbf{1}\oplus 4V_{\mathrm{cyc}}.$$

Hence the maximum rank of a D_{10}-equivariant map is 18, and the minimal stable repair is

$$\boxed{P_{20}\oplus 2\mathbf{1}\cong W_{20}\oplus 2\varepsilon},$$

of dimension 22. At the full A_5 level the maximum common rank is 14, and the minimal stable repair is

$$\boxed{P_{20}\oplus 2\mathbf{1}\oplus 4\cong W_{20}\oplus(3\oplus 3')},$$

of dimension 26. Thus the unstabilized common-rank ladder is

$$20 \longrightarrow 18 \longrightarrow 14,$$

while the minimal invertible stable dimensions are $20, 22, 26$.

The Perkel Borel group has order

$$171 = 3^2 \cdot 19,$$

so it contains no element of order five. Its eleven-observable/ten-phase orbital algebra therefore supplies neither a C_5 generator nor its dihedral normalizer; it is not automatically a canonical C_5 selector.

The five-bit compound-fault locator admits the exact quadratic Boolean form

$$\begin{aligned} y_0 &= x_0x_2 + x_0x_3 + x_1x_3, \\ y_1 &= x_2 + x_0x_2 + x_1x_2 + x_0x_3, \\ y_2 &= x_2 + x_0x_2 + x_1x_2 + x_1x_3, \\ y_3 &= x_2 + x_1x_2 + x_0x_3 + x_1x_3, \\ y_4 &= x_2 + x_1x_2 + x_0x_3 + x_2x_3. \end{aligned}$$

Its five homogeneous quadratic parts have rank five. Since each AND gate can add at most one independent quadratic form, every XOR–AND realization needs at least five AND gates. The products

$$x_0x_2,\ x_0x_3,\ x_1x_2,\ x_1x_3,\ x_2x_3$$

attain the bound, proving multiplicative complexity exactly five. A shared network uses eight XOR gates. Exhaustive RTL equivalence preserves all 137 compound fault words and minimum distance three.

31 The Petersen spine, constructive Perkel matrices, and octad curvature

Passes 3577–3583 replace three previously broad search fronts by exact finite interfaces. First, the double-coset subdegrees of the hypothetical Borel action force the order-3 or order-9 fixed graph to be the Petersen graph in both surviving orbit profiles. After all variables controlled by this thin spine are fixed, both profiles leave exactly

$$30870$$

residual binary edge-orbit variables, despite starting from the different Burnside counts 30915 and 30885.

Second, the conductor-19 component of the Perkel orbital algebra is represented explicitly as

$$M_3\big(\mathbb{Q}(\sqrt{-19})\big)\,.$$

A primitive rank-18 idempotent produces a six-dimensional rational right ideal, the central Paley operator supplies the relation $D^2 = -19$, and all 441 orbital products are verified in the resulting 3×3 matrices. The frozen matrix-table digest is `366405ad8400779a79eb6b92437b6d354ad3019eb16e9b5a81b99c5adc`

Third, the 6240 labelled one-factorizations of K_8 contain at least two inequivalent eight-object pairwise-one-intersection phases. A common-core sunflower has trivial S_8 stabilizer, while a mixed core-free phase has stabilizer four. The sunflower compiles to a 9-regular graph on

$$82 = 1 + 9 + 9 \cdot 8$$

vertices. It is triangle-free but has diameter three and 3024 four-cycles, with characteristic polynomial

$$(x-9)(x-8)^3(x-1)^{32}(x+1)^{24}(x+8)^4(x^2+x-8)^9.$$

It therefore saturates the numerical Moore order while failing the uniform common-neighbour curvature.

A real star-complement canary also executes the proof-carrying clique pipeline: the canonical stages 22,784 are regenerated, a genuine third-stage spectral survivor produces a 52-vertex compatibility graph, and an independently checked proof DAG certifies maximum clique 11.

Finally, every SRG resolvent has the form

$$(zI-A)^{-1} = a(z)I + b(z)A + c(z)J.$$

For a marked set S, the principal resolvent $aI + bA[S] + cJ$ recovers the induced edge count from the second determinant coefficient. A four-site W33 line marker therefore detects the six edges of a K_4, which no four-set in the triangle-free Gewirtz graph can reproduce. This is an exact geometry-sensitive port beyond unmarked adjacency dynamics.

Boundary. The missing degree-57 Moore graph remains open. No complete Borel solver verdict, all-octad S_8 census, or all-3720 proof archive is claimed.

31.1 Cubic dependency projector and chained incidence closures

> **Correction from Passes 3649–3662.** The original Passes 3600–3613 source reported zero eight-cell double covers for the oriented $12_4\,16_3$ surface. That count is withdrawn: the increasing-index backtracker was incomplete. Complete enumeration finds exactly three simple covers among all $\binom{12}{8} = 495$ subsets and six solutions among all 75,582 eight-cell multisets. Section 34.1 gives the replacement theorem.

The retained theorem constructs the 5,040-triple dependency deck on 240 filled faces. Its weighted overlap operator has ordinary multiplicity fingerprint

$$1, 15, 15, 20, 24, 24, 60, 81,$$

and over $\mathbb{F}_3$,

$$D^4 = -D^3, \qquad E_{81} = -D^3, \qquad E_{81}^2 = E_{81}, \qquad \operatorname{rank} E_{81} = 81.$$

The deterministic 364-class transported-M_4 scalar screen, exact five-operation ternary datapath, induced $1+16+40$ decomposition obstruction, and W33–Clebsch spectral completion remain valid. Passes 3649–3662 subsequently prove that the explicit 81-space is simple and projective, close the positive-gauge transported dual at nine, and construct a concrete integral 56-object weighted Gewirtz bridge.

The historical certificate `a08844aa7ec3a6be578dece00e455c1868ad8b4c833d912ebe02b7f014077f17` remains the record for the original packet, with its tomotope field superseded by `067047bbf3fe04301fcb26bf484a3`
The live intervals remain $389 \le R_{\mathrm{defect}} \le 435$ and $10 \le \chi(H) \le 11$.

32 Monster $U_4(2)$, the Steinberg register, and two exact falsifiers

The structural program uses the genuine subgroup direction

$$PSp(4,3) \cong U_4(2) \longrightarrow \mathbb{M},$$

while keeping character fusion and generator-level embedding distinct. A GAP companion filters class fusions by the documented $5B$-type constraints

$$2 \mapsto 2B, \qquad 3 \mapsto 3B, \qquad 5 \mapsto 5B,$$

and decomposes the restriction of the degree-196883 Monster character.

The protected module has the sharper local interpretation

$$81 = 3^4 = |\operatorname{Syl}_3(U_4(2))|.$$

The unique degree-81 Steinberg character vanishes on every nonidentity 3-power class, so it restricts regularly to a Sylow 3-subgroup.

For

$$N = (12I - A)(A + 4I)$$

the exact W33 computation gives

$$N^2 = 60N, \qquad \operatorname{rank} N = 24, \qquad N_{xx} = 36, \qquad N_{xy} \in \{6, -4\}.$$

Uniform normalization to squared norm four yields off-diagonal products $2/3$ and $-4/9$, so the raw forty-vector frame is not directly an integral Leech subconfiguration.

Also every three-eigenmode W33 adjacency sequence satisfies

$$s_{n+3} = 10s_{n+2} + 32s_{n+1} - 96s_n,$$

while the first $1A$ moonshine coefficients violate this recurrence. Any surviving bridge must therefore be graded, induced, glued, or ambient rather than a raw adjacency-moment identification.

Majorana boundary. For the documented $5B$-type embedding, subgroup involutions fuse to Monster $2B$, whereas standard Monster Majorana axes correspond to $2A$. A direct subgroup-involution-to-axis assignment is blocked.

Evidence boundary. Character-table fusion is not a concrete `mmgroup` embedding. Promotion requires serialized Monster generators, exact relations, class fusion, and an independent image-order certificate 25920.

33 Octad pattern census, Borel core/bridge reduction, and marked tomography

The pair-intersection multiplicities of eight abstract one-factorization rows are exactly edge-disjoint clique packings of K_8. Canonical augmentation gives

$$\boxed{69}$$

S_8-orbits of abstract multiplicity patterns, with orbit counts

$$1, 6, 10, 10, 13, 14, 8, 6, 1$$

by the number of nontrivial blocks. This is a complete abstract pattern census, not yet the complete realization census inside the 6,240 labelled one-factorizations of K_8.

The two surviving 19:9 Moore-action profiles possess a literal common binary core. Its variable classes have sizes

$$18 \cdot 85 = 1530, \qquad \binom{18}{2} \cdot 171 = 26163, \qquad 9 \cdot 18 \cdot 19 = 3 \cdot 18 \cdot 57 = 3078,$$

so the shared core has

$$\boxed{30771}$$

variables. The P_{19} profile is exactly this core after presolve, while P_{57} adds eighteen nonneighbor bridge variables:

$$\boxed{30789 = 30771 + 18}.$$

No SAT or UNSAT verdict is inferred.

The conductor-19 component of the Perkel orbital algebra is realized by explicit matrix units in

$$M_3\big(\mathbb{Q}(\sqrt{-19})\big)\,.$$

Writing $s^2 = -19$, the units obey

$$E_{ij}E_{kl} = \delta_{jk}E_{il}, \qquad (sE_{ij})(sE_{kl}) = -19\delta_{jk}E_{il}.$$

The transpose involution is represented by the positive Hermitian form

$$H = \begin{pmatrix} 1 & 2s/19 & -2s/19 \\ -2s/19 & 1 & 2s/19 \\ 2s/19 & -2s/19 & 1 \end{pmatrix},$$

whose two-by-two principal minors equal $15/19$ and whose determinant is $7/19$.

A real proof-carrying archive of sixteen genuine star-complement compatibility graphs is frozen with clique histogram

$$8^1, 9^1, 10^1, 11^3, 12^1, 13^2, 16^2, 31^5$$

and ordered Merkle root

$$\texttt{c176539c7b944274fb64965275ce3f900852fe4b26f67923b2ca6a2f06e256a4}.$$

Every upper-bound DAG is independently checked from its frozen adjacency bitsets. The complete 3,720-instance archive remains resource-gated.

Finally, the minimum marked-resolvent rank that distinguishes W33 from Gewirtz is three. Rank one is common to both graphs, and rank two sees only edges versus nonedges. At rank three, W33 has a triangle while Gewirtz is triangle-free. Every W33 triangle reconstructs a unique K_4 line because an adjacent pair has exactly two common neighbors.

Evidence boundary. The degree-57 Moore graph, realized K_8 octad orbit census, Borel solver verdicts, complete proof archive, PDF evidence, and physical interpretation all remain open unless separately executed and observed.

34 Passes 3635–3648: exact $U_4(2)$ completion and rank-24 modular closure

The W33 projective action now has a compact exact certificate. Four order-three symplectic transvections generate a group of order

$$25{,}920 = |PSp(4,3)| = |U_4(2)|,$$

with element-order census

$$1^1,\ 2^{315},\ 3^{800},\ 4^{3780},\ 5^{5184},\ 6^{5760},\ 9^{5760},\ 12^{4320}.$$

Every three-transvection face has order 648 and fixes one W33 point, while an explicit pair has orders $(2,5,12)$ and generates the whole group.

The rank-24 projector carrier is bilinearly complete. Its symmetric tensors have rank

$$300 = \dim \mathrm{Sym}^2(\mathbf{Q}^{24}),$$

and its alternating tensors have rank

$$276 = \dim \Lambda^2(\mathbf{Q}^{24}).$$

Thus the carrier spans all $24^2 = 576$ matrix directions. This is a full linear operator envelope, not yet a Griess or VOA product certificate.

The integral projector Gram form has Smith profile

$$2^1, \qquad 10^9, \qquad 30^6, \qquad 60^8,$$

and discriminant valuation

$$2^{32}3^{14}5^{23}.$$

The odd 5-adic exponent survives every rational scalar rescaling in rank 24, so no scalar-rescaled copy can possess a unimodular overlattice. Any Leech route must use non-scalar coupling, quotienting, or a multi-lattice extension.

The exact graded completion is

$$\left(E_4^3 - 720\Delta\right)\prod_{n\geq 1}(1-q^n)^{-24},$$

whose initial shifted coefficients are

$$1,\ 24,\ 196884,\ 21493760,\ 864299970,\ 20245856256.$$

This identifies the minimum machinery missing from raw W33 adjacency moments: a rootless rank-24 modular numerator and a 24-oscillator denominator.

Two additional chamber structures emerge. The full group contains 432 copies of A_5 in two orbits of 216. Their D_{10}-sharing graph is

$$36K_{6,6},$$

with 1296 edges; every edge generates A_6, and each chamber has normalizer of order 720, hence S_6. Separately, the four transvections form a tetrahedral amalgam whose four faces are order-648 point stabilizers.

Evidence boundary. The exact Python certificate proves the abstract $U_4(2)$ carrier, the complete $A_5/A_6/S_6$ census, both tensor-span ranks, the scalar glue obstruction, and the modular coefficients. A companion GAP job enumerates compatible $5B$-containing class fusions and the possible multiplicities of the degree-81 constituent. No serialized Monster-word embedding, unique class fusion, observed degree-81 multiplicity, Leech embedding, Griess product, or physical result is promoted before its dedicated certificate is observed.

34.1 Cubic integrality, Steinberg closure, and the corrected tomotope lift

For the cubic dependency incidence matrix $T \in \{0,1\}^{240\times 5040}$, the uniform primal and dual witnesses have value 80:

$$x = \tfrac{1}{3}\mathbf{1}_{240}, \qquad y = \tfrac{1}{63}\mathbf{1}_{5040}.$$

Thus the fractional transversal number is 80. An integral 80-set would make every covering constraint tight, $T^T x = \mathbf{1}$. Since $TT^T = 63I + D$ has minimum eigenvalue 45 and full rank 240, the unique real solution is $x = \frac{1}{3}\mathbf{1}$, impossible for a binary vector. Hence

$$\boxed{\tau \geq 81}, \qquad \tau/\tau^* \geq 81/80.$$

This is a cubic integrality theorem, not a covering-radius endpoint; $389 \leq R_{\text{defect}} \leq 435$ remains live.

The ten orbital matrices of the 240-face action restrict on $E_{81} = -D^3$ to a one-dimensional algebra over $\mathbb{F}_3$, so

$$\mathrm{End}_{PSp(4,3)}(E_{81}) = \mathbb{F}_3.$$

A deterministic Sylow-three subgroup of order 81 acts regularly on this space. Therefore E_{81} is projective; the scalar endomorphism ring forces simplicity, and the explicit image realizes the defining-characteristic Steinberg module. The complementary filtration has dimensions $159 \supset 44 \supset 14 \supset 0$.

For the fourfold 45-anchor blowup, the 27 lifted independent 20-sets, each point occurring three times, give $\chi_f = 9$. The unrestricted positive-gauge weighted-Hoffman dual is therefore exactly nine, attained by $A_{45} \otimes I_4$ with spectrum $32^4, 2^{96}, (-4)^{80}$. Arbitrary signed complex Hermitian weights remain open.

Correction to Passes 3600–3613. The earlier zero count for eight-cell covers is withdrawn: its increasing-index backtracker skipped valid subsets. Complete enumeration of all $\binom{12}{8} = 495$ simple subsets finds exactly three covers, one orbit under the visible order-48 group, with stabilizer 16 and induced action S_3. Each cover has cell adjacency $K_{4,4}$. With

$$A = \{0,3,8,11\}, \quad B = \{1,5,6,10\}, \quad C = \{2,4,7,9\},$$

the covers are $A \cup B, A \cup C, B \cup C$; exhaustive enumeration of all 75,582 multisets adds precisely $2A, 2B, 2C$. This establishes the eight-cell incidence layer, but not yet the full rank-four polytope isomorphism.

A concrete objectwise W33–Clebsch bridge is supplied by the integral matrix

$$Q = \begin{pmatrix} 56A_W - 6J_{40} & 8J_{40,16} \\ 8J_{16,40} & \frac{7}{2}(-3A_C^2 + 18A_C + 17I) + 8J_{16} \end{pmatrix}.$$

It has constant row sum 560 and obeys

$$(Q - 560I)(Q - 112I)(Q + 224I) = 0,$$

so $Q/56$ has Gewirtz spectrum $10^1, 2^{35}, (-4)^{20}$. This is an integral weighted spectral bridge, not a 0/1 graph embedding.

Finally, $C = I + D + E_{81}$ has order three over $\mathbb{F}_3$, with $(C - I)$-power ranks $44, 14, 0$ and Jordan type $J_3(1)^{14} \oplus J_2(1)^{16} \oplus J_1(1)^{166}$. The three corrected tomotope covers form a second exact S_3-selector register. Neither construction is promoted as physical dynamics.

The frozen semantic SHA-256 is `067047bbf3fe04301fcb26bf484a3d151bf6db4ab762fa6bf31f527889d09a89`. No remote CI, PDF, FPGA, laboratory, Monster embedding, radius endpoint, or ten-colour result is asserted here.

34.2 The canonical A_6-chamber/spread bridge and the exceptional S_6 double-six

The preceding Monster-facing packet constructs all 432 subgroups isomorphic to A_5, their 36 $K_{6,6}$ components under the D_{10}-sharing relation, and one A_6 chamber per component. Earlier exact work independently identifies the rank-three action of $PSp(4,3)$ on the 36 spreads of $W(3,3)$. The following result supplies the missing objectwise map; it is not an inference from equal cardinalities or strongly regular graph parameters.

Theorem 34.1 (Canonical chamber/spread bridge)**.** *Let $G = PSp(4,3) \cong U_4(2)$ act on $W(3,3)$, and let $H \cong A_6$ be one of the 36 chambers. Then*

$$|N_G(H)| = 720, \qquad [N_G(H), N_G(H)] = H.$$

The normalizer fixes exactly one spread Σ_H, and

$$N_G(H) = \mathrm{Stab}_G(\Sigma_H).$$

Consequently

$$\boxed{G/N_G(A_6) \longleftrightarrow \{W(3,3) \text{ spreads}\}, \qquad H \longmapsto \Sigma_H,}$$

is a canonical G-equivariant bijection of two 36-element sets.

For distinct chambers H and K, the complete intersection dictionary is

$$\boxed{|H \cap K| = 18 \iff |\Sigma_H \cap \Sigma_K| = 1} \qquad (360 \text{ unordered pairs}),$$

and

$$\boxed{|H \cap K| = 12 \iff |\Sigma_H \cap \Sigma_K| = 4} \qquad (270 \text{ unordered pairs}).$$

The order-12 relation is therefore

$$\mathrm{SRG}(36, 15, 6, 6), \qquad \mathrm{spec} = 15^1 \oplus 3^{15} \oplus (-3)^{20},$$

while the complementary order-18 relation is

$$\mathrm{SRG}(36, 20, 10, 12), \qquad \mathrm{spec} = 20^1 \oplus 2^{20} \oplus (-4)^{15}.$$

The graph identification is carried by the explicit equivariant bijection, not by the parameter tuple alone.

Each chamber contains twelve A_5 subgroups, split by the two global A_5 classes as $6 + 6$. Two members of the same six-set intersect in A_4; every cross-pair intersects in D_{10}. Thus the cross-intersection graph is exactly $K_{6,6}$. The normalizer S_6 acts faithfully on both six-sets, and the exact cycle-type census verifies that the two actions are exchanged by the exceptional outer automorphism:

$$(2,1,1,1,1) \longleftrightarrow (2,2,2), \qquad (3,1,1,1) \longleftrightarrow (3,3), \qquad (6) \longleftrightarrow (3,2,1).$$

Their directed multiplicities are respectively 15, 40, and 120 in each direction.

Monster-facing boundary. Any future concrete $5B$-containing $U_4(2)$ embedding in the Monster transports this complete 36-spread/36-chamber carrier and every local double-six chart. The certificate does not provide Monster words, a unique class fusion, a verified multiplicity of the 81-dimensional constituent, or a Griess/VOA/photonic multiplication law. In particular, this rank-three spread carrier is not identified with the distinct 36-ray magic-state orthogonality graph, which is not strongly regular.

35 The chamber–tomotope central lift and thick amalgamation boundary

Passes 3663–3669 established the canonical equivariant identification of the thirty-six A_6 chambers with the thirty-six spreads of $W(3,3)$. The present packet retains that carrier and moves one level upward. The valency-15 chamber relation is

$$\mathrm{SRG}(36,15,6,6), \qquad 15^1 \oplus 3^{15} \oplus (-3)^{20},$$

and contains exactly 135 maximal K_4 subgraphs. Every chamber belongs to fifteen of them, giving

$$36 \cdot 15 = 135 \cdot 4 = 540$$

chamber–K_4 incidences.

The stabilizer of a maximal K_4 has order 192 and centre of order two. Its central quotient has order census

$$1^1\, 2^{27}\, 3^{32}\, 4^{36},$$

and an explicit four-generator word transport identifies it, as a marked group, with the automorphism group of the tomotope. The extension is not split: the stabilizer census

$$1^1\, 2^{43}\, 3^{32}\, 4^{84}\, 6^{32}$$

differs from the census of $C_2 \times \mathrm{Aut}(T)$. This supplies a third exact 192 mechanism: a non-split central tomotope lift, distinct from both the tomotope's 192 flags and the split order-192 universal group.

Let P_i be the four order-648 three-generator parabolics supplied by the explicit $U_4(2)$ transvections. Their pair-intersection multiset is

$$\{24, 24, 24, 24, 24, 54\},$$

every triple intersection has order three, and the total core is trivial. The associated coset geometry has forty objects of each type and $25,920$ chambers, but every panel has thickness three. Its natural panel motion is therefore C_3, not an exchange involution. The construction is an exact thick chamber system rather than an abstract polytope: it fails the diamond condition at the final local step.

For the rank-24 integral projector Gram matrix G, the non-scalar block coupling

$$\mathcal{G} = \begin{pmatrix} G & I \\ I & 0 \end{pmatrix}$$

is even, has determinant one, and has signature $(24,24)$. Thus the scalar discriminant obstruction can be cancelled exactly, but the canonical closure is the indefinite lattice $II_{24,24}$ rather than a positive-definite Leech lattice.

If V denotes the rank-24 $U_4(2)$ module, exact character inner products give

$$\dim \mathrm{Hom}_{U_4(2)}(\mathrm{Sym}^2 V, V) = 2, \qquad \dim \mathrm{Hom}_{U_4(2)}(\Lambda^2 V, V) = 1.$$

Projected coordinatewise multiplication and projected W33 triangle-neighbour multiplication form a basis of the commutative envelope; both are Frobenius. Their complete associator ideal becomes the unit ideal modulo $1,000,003$, so no nonzero rational member of this envelope is associative. This classifies the available equivariant commutative products without promoting any of them to a Griess or VOA multiplication.

Finally, the prime support $\{2,3,5\}$ of $U_4(2)$ selects the six exact McKay–Thompson targets $2A/2B$, $3A/3B$, and $5A/5B$. With $r = 24/(p-1)$,

$$T_{pB} = \left(\frac{\eta(\tau)}{\eta(p\tau)}\right)^r + r, \qquad T_{pA} = T_{pB} + p^{r/2}\left(\frac{\eta(p\tau)}{\eta(\tau)}\right)^r.$$

These channels refine the scalar $J+24$ target but do not by themselves construct a Monster module.

A final spectral firewall is exact. The W33 (-4) eigenspace and the chamber-complement (-4) eigenspace are both irreducible and fifteen-dimensional, yet their $U_4(2)$ characters have inner product zero. They are inequivalent modules; matching dimension and graph eigenvalue do not supply an equivariant intertwiner.

The concrete Monster embedding remains fail-closed. The new harness requires four serialized Monster elements of order three, pair-product orders $3,6,6,6,6,6$, four order-648 triple closures, full closure order $25,920$, and an independently hashed class-fusion certificate before promotion.

35.1 Realized octads, the exact Borel bridge, and architecture-level firewalls

The abstract K_8 octad-pattern deck has 69 S_8-orbits. Exact certificates now realize 59 of them inside the $6,240$ labelled one-factorizations; ten sharply identified patterns remain open. The 18 additional thick variables of the P_{57} Borel profile collapse under the Moore common-neighbour screen to only

$$1 + 18 + 36 = 55$$

locally admissible masks, all of weight at most two. Their compatibility graph is $3K_{2,2,2}$.

The real symmetric Perkel commutant has the complete positive-cone model

$$\mathbb{R}_+ \times \mathrm{Herm}_3^+(\mathbb{C}) \times \mathbb{R}_+.$$

It has two scalar extreme rays plus the rank-one rays zz^* parametrized by $\mathbb{CP}^2$, sixteen rank strata, algebraic boundary $\alpha\beta \det Q = 0$, and Carathéodory number five. The proof archive now contains 32 content-addressed, independently checkable clique proof DAGs. Exhaustive marked-resolvent tomography through rank five gives W33-exclusive signature counts $0,0,1,3,10$, while Gewirtz has no exclusive signature in that range.

Two architecture-level corrections are more consequential. An exactly-one-photon carrier has only M dimensions in M orthogonal modes, so representing n independent qutrits requires $M \geq 3^n$. Moreover the total-loss Knill–Laflamme products satisfy $a_i^\dagger a_j = |i\rangle\langle j|$ and span the full matrix algebra. Their compression can all be scalar only on a one-dimensional code. Thus no nontrivial logical code confined to exactly one photon corrects arbitrary total photon loss. The abstract $[[240,81,4]]_3$ code therefore requires an explicit multi-photon, bosonic, teleportation/cluster, or quantum-memory realization before it can be called loss tolerant.

Conversely, independently addressable local phases and real edge couplers on any connected d-mode graph generate $\mathfrak{u}(d)$. W33, a path, and a cycle on forty modes all yield dimension $40^2 = 1,600$

under that idealized control model. Bare one-photon universality is therefore generic rather than W33-specific. The geometry's architectural claim must be tested through fault-tolerant overhead, routing, calibration, noise, code, or component advantages.

Evidence boundary

Fifty-nine octad patterns are realized, not all sixty-nine. The Borel result is a local presolve, not a Moore-graph verdict. Thirty-two proof DAGs are frozen, not all 3,720. The loss and controllability results are exact conditional architecture theorems; laboratory performance remains unmeasured.

35.2 The spread ETF and its canonical Norton algebra (Passes 3694–3700)

Let A be the graph on the 36 spreads of $W(3,3)$, adjacent when two spreads share four lines. Its rational primitive idempotents are

$$E_{15} = \tfrac{1}{2}I + \tfrac{1}{6}A - \tfrac{1}{12}J, \qquad E_{20} = \tfrac{1}{2}I - \tfrac{1}{6}A + \tfrac{1}{18}J.$$

If B is the 40×36 line–spread incidence matrix and $C = B - \tfrac{1}{4}J_{40\times 36}$, then

$$\boxed{C^{\mathsf{T}}C = 18E_{15}}$$

shows that the normalized columns form a real ETF$(15, 36)$. Their mutual inner products are $+1/5$ for a four-line intersection and $-1/5$ for a one-line intersection, saturating the Welch bound. The Seidel matrix $S = I + 2A - J$ obeys $S^2 - 2S - 35I = 0$ and has spectrum $7^{15} \oplus (-5)^{21}$.

The complementary projector $I - E_{15}$ has rank 21. Thus an exact passive unitary dilation of the 36-mode frame analysis requires a 21-dimensional guard sector; this is a dimension certificate, not an experimental claim.

On $V = \operatorname{im} E_{15}$ define the Norton product $x \star y = E_{15}(x \circ y)$ and axes $a_i = 6E_{15}e_i$. The 36 axes are primitive idempotents. Each axis has multiplication spectrum

$$1^1 \oplus (-\tfrac{1}{2})^5 \oplus (\tfrac{1}{6})^9,$$

with the exact $\mathbb{Z}_2$-graded fusion law

$$(-\tfrac{1}{2}) \star (-\tfrac{1}{2}) \subseteq 1 \oplus \tfrac{1}{6}, \quad (-\tfrac{1}{2}) \star \tfrac{1}{6} \subseteq -\tfrac{1}{2}, \quad \tfrac{1}{6} \star \tfrac{1}{6} \subseteq 1 \oplus \tfrac{1}{6}.$$

This is a positive Frobenius axial algebra but not a Monster/Majorana algebra. For adjacent axes, $a_i \star a_j = (a_i + a_j)/6$. Every nonadjacent pair has a unique third axis a_k satisfying

$$a_i \star a_j = -\frac{a_i + a_j}{6} + \frac{a_k}{3}.$$

These products define 120 triples. Each triple consists of three spreads sharing one W33 line; for every W33 line, its nine containing spreads split into three disjoint triples.

The 36 Witting-ray orthogonality graph is a different object: it is 11-regular with spectrum $11^1 \oplus 2^{20} \oplus (-1)^3 \oplus (-4)^{12}$, whereas the spread graph is 15-regular with spectrum $15^1 \oplus 3^{15} \oplus (-3)^{20}$. Finally, the ternary panels of the four-parabolic chamber system cannot be changed to binary panels by an unbranched type-preserving cover, because such covers are locally bijective on rank-one residues.

35.3 Passes 3701–3714: the D_4/F_4 triality carrier and the 45-axis firewall

The 135 maximal four-cliques of the 36-chamber graph admit an exact three-to-one quotient. The stabilizer of each four-clique acts on the forty W33 points with an eight-point orbit; precisely three pairwise-disjoint four-cliques determine the same octad. Hence

$$135 = 45 \cdot 3.$$

Two octads meet in zero or two points, and octad disjointness is

$$\mathrm{SRG}(45, 12, 3, 3), \qquad \mathrm{spec} = 12^1 \oplus 3^{20} \oplus (-3)^{24}.$$

The centered octad vectors, with entries 48 on the octad and -12 off it, have norm 23040, off-diagonal products -5760 or 1440, and Gram spectrum

$$43200^{24} \oplus 0^{21}.$$

Thus they form a rank-24 two-distance tight frame.

The 135 four-cliques are exactly the 135 Lagrangian three-spaces of $W(5, 2)$, restricted to the 36 anisotropic points of a minus quadratic form. Their binary incidence matrix has rank 29, and its dual is the affine restriction code

$$[36, 7, 16]_2, \qquad W(z) = 1 + 63z^{16} + 63z^{20} + z^{36}.$$

A frame stabilizer is

$$C_2^3 \rtimes S_4 \cong W(D_4), \qquad |W(D_4)| = 192.$$

It has an explicit S_4 complement. Its central quotient is non-split: the section cocycle system has coefficient rank 95 and augmented rank 96. The common normalizer of the three frames over one octad has order 576, while the stabilizer in the outer extension $U_4(2){:}2$ has order 1152. A colored-orbital conjugacy on a faithful 24-point orbit identifies the latter with the short-root action of $W(F_4)$. Therefore

$$W(D_4)\ (192) < W(F_4)_{\text{even frame}}\ (576) < W(F_4)\ (1152).$$

The ternary panels do not admit a string-Coxeter resolution preserving the exact four-generator target. Each generator has 108 inverting outer involutions, but no outer involution inverts all four. In every two-involution-per-colour factorization, each pair of colours contributes at least two cross-colour noncommutations. The resulting minimum is 16 noncommuting edges, whereas a rank-eight string diagram has only seven.

For the 45 canonical octad axes, the two basis products of the complete equivariant commutative Frobenius plane satisfy

$$m_0(u, u) = 36u, \qquad m_1(u, u) = -216u.$$

The simultaneous left-eigenpairs are

$$(36, -216)^1, \quad (28, 152)^6, \quad (-12, -168)^8, \quad (-12, 72)^9.$$

No rational parameter gives the Monster $2A$ Majorana non-axis spectrum $\{0, 1/4, 1/32\}$.

Finally, for

$$\mathcal{G} = \begin{pmatrix} G & I \\ I & 0 \end{pmatrix},$$

the graph of an integral matrix B has Gram matrix $G+B+B^{\mathsf{T}}$. Every even integral rank-24 Gram matrix occurs in this way; E_8^3 is an explicit positive unimodular child. The standard existence theorem for the Leech lattice therefore gives a noncanonical rootless graph section, but no explicit Leech basis is frozen here. Equivariance is impossible: irreducibility forces $B = mI$, and no such scalar section is simultaneously positive definite and unimodular.

Concrete Monster words, a regular thin polytope cover, an explicit canonical Leech section, and a Majorana/Griess/VOA realization remain certificate-gated.

36 Passes 3715–3721: carrier replacement and control-plane architecture

The literal exactly-one-photon register is replaced by an explicit qutrit erasure carrier. The code

$$|i_L\rangle = 3^{-1/2} \sum_{j \in \mathbf{F}_3} |j, j+i, j+2i\rangle$$

satisfies all Knill–Laflamme conditions for one known physical-qutrit erasure and realizes $[[3,1,2]]_3$. Eighty-one logical qutrits therefore require 243 physical qutrits; under one-photon triple-rail encoding this is 243 photons in 729 modes. For independent transmissivity η, the all-block success condition

$$[\eta^3 + 3(1-\eta)\eta^2]^{81} \geq 2/3$$

gives $\eta \geq 0.958628272258342$.

An exhaustive degree-matched tournament checks all $\binom{19}{6} = 27,132$ twelve-regular circulants on forty vertices. W33 and the best route circulants share diameter two and average distance 22/13, but W33 alone has exactly four common neighbours for every nonedge and zero redundancy variance; its spectral gap is 10, above the best circulant value found, approximately 9.280621379.

The proposed temporal loop is formalized as a causal qutrit process tensor: a qutrit SWAP stores the past state, a middle causal break replaces the exposed system, and a second SWAP retrieves the past. This is non-Markovian memory without future-to-past signalling. Its memory bond dimension is three for one qutrit and at least 3^{81} for an arbitrary eighty-one-qutrit state.

At 1550 nm the minimum energy in the 243-photon carrier is 3.1142×10^{-17} J per shot. A 162-bit erasure record has a 300-K Landauer floor 4.6510×10^{-19} J per cycle. At group index four, feedforward delays of 1, 10, and 100 ns require approximately 7.49 cm, 74.95 cm, and 7.49 m of passive delay.

A complete forty-mode intensity-interference identification uses 1600 input settings. A familywise Hoeffding bound with $\epsilon = \delta = 0.01$ requires 81,825 shots per setting, or 130,920,000 shots total. The device must recover the SRG identity, forty lines, 160 line triangles, and the frozen marked-resolvent atlas against degree-matched controls.

Two control-plane theorems change the architectural interpretation. First, the 160 point-line incidences decompose into four perfect matchings, giving an optimal four-tick collision-free syndrome schedule. Second, the order-25,920 symplectic group has exactly three ordered-pair orbits, so automorphism twirling compresses a generic 1600-parameter Hermitian calibration model to

$$aI + bA + c(J - I - A).$$

Thus W33 need not be the literal protected Hilbert-space carrier to remain operationally distinguished: it can serve as an optimal syndrome scheduler and a rank-three calibration/noise compressor. These are exact finite results; hardware cost, executed tomography, wall-plug power, and fault-tolerant thresholds remain evidence-gated.

37 Fischer closure, a Hadamard Naimark transform, and the six-bit orthogonal core

The thirty-six primitive Norton axes from the spread ETF carry canonical Miyamoto involutions. The exact pair census is

$$270 \text{ commuting pairs} + 360 \text{ pairs whose product has order } 3.$$

For every noncommuting pair, conjugation produces the unique third axis in its Norton triple. Consequently the 120 Norton triples are exactly the Fischer lines of a three-transposition space. Seven involutions generate a group of order 51,840, while the subgroup generated by even products has order 25,920 and the previously certified $U_4(2)$ element-order census. Thus the internal action is

$$O_6^-(2) \cong U_4(2){:}2, \qquad \Omega_6^-(2) \cong U_4(2).$$

This is an abstract finite-group identification, not a serialized Monster embedding.

Let A be the adjacency matrix of the spread graph $\mathrm{SRG}(36, 15, 6, 6)$. The matrix

$$K = 2A - J$$

is a symmetric regular Hadamard matrix:

$$KK^{\mathsf{T}} = 36I, \qquad K\mathbf{1} = -6\mathbf{1}.$$

Hence $H = K/6$ is an exact rational orthogonal involution and

$$E_{15} = \frac{I + H}{2}, \qquad E_{21} = \frac{I - H}{2}.$$

The rank-15 signal and rank-21 guard sectors therefore arise from one explicit uniform-amplitude two-phase thirty-six-port transform. This is a transfer-matrix certificate, not a laboratory claim.

The associative algebra generated by the fifteen-dimensional left-multiplication operators has dimension 225 modulo 1,000,003, while the derivation equations have rank 225. Therefore the rational Norton algebra is simple and

$$\mathrm{Der}(V) = 0.$$

Adjacent pairs generate a two-dimensional algebra with idempotents $0, a, b, \frac{3}{4}(a + b)$; nonadjacent pairs generate a three-dimensional algebra containing the unique third Fischer axis c, with idempotents $0, a, b, c, a + b + c$. The fusion spectrum remains non-Majorana and non-Griess.

If D is the 36×120 axis–Fischer-line incidence matrix, then its binary left kernel is a $[36, 6]$ code with weight enumerator

$$1 + 27z^{16} + 36z^{20}.$$

The quadratic form $q(x) = \mathrm{wt}(x)/4 \pmod 2$ is nondegenerate of minus type. Its 27 nonzero singular vectors recover $\mathrm{SRG}(27, 10, 1, 5)$, while its 36 nonsingular vectors are exactly the Miyamoto supports and recover the spread graph. Thus the 27- and 36-object carriers are the two nonzero sectors of one explicit six-bit orthogonal space.

Finally, the intersection graph of the 120 Fischer lines has degree 27, spectrum

$$27^1 \oplus 9^{20} \oplus 3^{15} \oplus (-3)^{84},$$

and distance distribution $1 + 27 + 90 + 2$ from every vertex. Its forty antipodal fibers are the three triples through each W33 line, and its quotient is $\mathrm{SRG}(40, 27, 18, 18)$. The lift is a connected three-cover with full S_3 holonomy and trivial deck group; it is not a regular C_3 cover.

37.1 Cubic-transversal closure, tomotope completion square, and website restoration

The long-form public site was restored byte-for-byte from the final intact blob `41a8d733f42da18282fa276f5d2fa82` the compact replacement was preserved separately at `docs/source-derived-architecture-landing-2026-08-05`.

For the 240×5040 cubic dependency incidence matrix T, put $D = TT^{\mathsf{T}} - 63I$. If a transversal has size m and $P = \sum_t \binom{h_t}{2} = \frac{1}{2}x^{\mathsf{T}}Dx$, then the minimum eigenvalue -18 of D gives

$$P \geq \frac{3}{10}m^2 - 9m,$$

while $h_t \in \{1, 2, 3\}$ gives

$$P \leq \frac{3}{2}(63m - 5040).$$

Hence $(m - 105)(m - 240) \leq 0$. Equality at $m = 105$ would make the integer P equal to $4725/2$, so $m \geq 106$. An explicit 62-face cap gives a 178-face transversal, and therefore

$$\boxed{106 \leq \tau_{\text{cubic}} \leq 178}.$$

The covering-radius interval remains $389 \leq R \leq 435$.

The 45-anchor graph has independence number five and fractional chromatic number nine. The generalized weighted-Hoffman optimum over arbitrary edge-supported Hermitian matrices is therefore exactly nine, attained by $A_{45} \otimes I_4$. This does not change $10 \leq \chi(H) \leq 11$.

The corrected edge–face layer admits three vertex-structure orbits and three cell covers. All nine pairings are connected rank-four incidence geometries with f-vector $(4, 12, 16, 8)$, 192 flags, and all diamond intervals of size two. Their automorphism-order matrix is

$$\begin{pmatrix} 96 & 96 & 192 \\ 192 & 96 & 96 \\ 96 & 192 & 96 \end{pmatrix}.$$

Thus six completions are two-flag-orbit tomotopes with automorphism order 96, while a perfect matching of three completions gives regular non-split central lifts of order 192.

The characteristic-three complement has filtration

$$159 \supset 44 \supset 14 \supset 0.$$

The bottom 14-space is absolutely irreducible. The middle quotient satisfies the non-split exact sequence

$$0 \longrightarrow 1 \oplus 5 \oplus 10 \longrightarrow M_{30} \longrightarrow 14 \longrightarrow 0.$$

The top 115-quotient has fixed-socle dimension two and trivial-head multiplicity one; its remaining factors are not labelled here.

Finally, all 32 full-orbit binary roundings of the integral weighted W33–Clebsch bridge were exhausted. None is 10-regular and none satisfies the Gewirtz identity $A^2 = 8I - 2A + 2J$. Asymmetric rounding remains open.

Two further constructions follow. The 3×3 tomotope completion square has six order-96 entries and a perfect matching of three order-192 entries. The explicit 62-cap has trivial stabilizer in $U_4(2)$, producing a free orbit of 25,920 cap witnesses.

The frozen semantic SHA-256 is `c6e5e73fb5a18d9add4c1643d52df31413280b0e5cd157294ca686f8df32a299`. No remote CI, PDF, hardware, laboratory, or physical claim is promoted here.

38 Symmetry operating system, space–time decoding, and falsifiable architecture

Passes 3743–3750 convert the W33 machine from an abstract universal single-particle carrier into an explicitly testable control-plane architecture. The executable certificate has semantic digest

`67ce2d0ab105d8809dd6ae1af60381e1181d9a08c9032ce1dad1130f7bb8ff62`

and is reproduced by the focused regression suite.

Symmetry operating system. Four projective symplectic transvections generate the full order-25,920 point action. Their Cayley compiler has word diameter 11 and mean word length 8.17507716049; a complete exact group sweep uses 211,898 generator macros. This is an exact permutation compiler, not yet a calibrated optical pulse compiler.

Correlated space–time decoding. For the declared two-state hidden-Markov benchmark, eight consecutive observations have exact MAP error $1.1395646255 \times 10^{-3}$, whereas observations separated by the four-tick incidence schedule have error $6.3819353522 \times 10^{-5}$. Thus the interleaved error is 0.0560032771 of the consecutive value. The result is model-specific and does not promote an empirical device threshold.

Hybrid resource factory. The protected resource graph contains forty point registers, forty line-check registers, and one frame/clock register, with $160 + 80 = 240$ logical links. Under the verified $[[3, 1, 2]]_3$ block carrier this requires 243 physical qutrits in 729 triple-rail modes. Exhaustive search over 3^9 bilinear couplings proves that each logical controlled phase needs at least three physical phase terms, so all logical links require at least 720 such terms. A single frame bus has serial-depth lower bound 80.

Grand matched-geometry tournament. All 167,356 degree-twelve Cayley generator sets on $\mathbb{Z}_2^3 \times \mathbb{Z}_5$ were enumerated; 165,984 are connected. Their largest spectral gap is $9.527864045 < 10$, the exact W33 gap. A competitor attains minimum four common neighbours on nonedges, but with histogram $4^{18}6^8 12^1$ rather than W33's uniform 4^{270}. Frozen layout witnesses also show that W33 does not minimize the tested Manhattan wirelength proxy.

Preregistered hardware challenge. A prospective three-device comparison locks structural, transport, twirl, and scheduling endpoints before data. W33 is falsified if its recovered support violates $A^2 = 8I - 2A + 4J$, if it fails to beat both matched controls by 2×10^{-4} on the locked worst-nonedge task, if the twirled residual exceeds ten percent, or if the four-tick schedule hides serialization or unreported resources.

Three outside-lane results. The relative permutations of the four incidence matchings generate the full symmetric group S_{40}, so the schedule is a universal classical permutation microcode, not a coherent quantum gate set. Exact unweighted automorphism twirling requires a sample count divisible by $\operatorname{lcm}(40, 480, 1080) = 4320$; this lower bound is not sufficient, and the known exact sweep uses all 25,920 automorphisms. Finally, passive fixed-adjacency dynamics lie in $\operatorname{span}\{I, A, J\}$, while zero forcing gives the certified control-port interval

$$24 \le Z(W33) \le 29.$$

Thus symmetry provides compression only when accompanied by an explicit symmetry-breaking control layer.

Evidence boundary. No optical pulse calibration, measured correlated-noise law, complete fault-tolerance threshold, minimum physical layout, coherent S_{40} universality, exact minimum twirl design, or exact zero-forcing number is claimed by these computations.

39 The six-bit quadratic parent, the rooted code lattice, and the Fischer holonomy frame

The thirty-six spreads and their 120 Norton triples admit a further exact closure. The Miyamoto involutions generate

$$O_6^-(2) \cong U_4(2){:}2, \qquad \Omega_6^-(2) \cong U_4(2),$$

and the compressed standard pairs can be supplemented by complete cycle and class-size fingerprints on both the thirty-six axes and the 120 Fischer lines. These are abstract finite-group search filters; no serialized Monster words are asserted.

Let D be the 36×120 axis–triple incidence matrix. Its binary left kernel is the doubly-even self-orthogonal code

$$C = [36, 6, 16], \qquad W_C(z) = 1 + 27z^{16} + 36z^{20}.$$

The associated Construction-A lattice

$$L(C) = 2^{-1/2}\{z \in \mathbb{Z}^{36} : z \bmod 2 \in C\}$$

is even, has minimum norm two, and satisfies

$$\mathrm{SNF}(G) = 1^{12}2^{24}, \qquad L(C)^*/L(C) \cong (\mathbb{Z}/2\mathbb{Z})^{24}.$$

Its root system is A_1^{36}, so the lattice is explicitly rooted and non-unimodular rather than Leech-like.

If A is the spread graph adjacency matrix, then

$$K = 2A - J, \qquad H = K/6$$

is the symmetric rational Hadamard involution of the previous section. There exist twenty-one pairwise orthogonal primitive vectors $v_i \in \mathbb{Z}^{36}$ such that the commuting Householder reflections

$$R_i = I - 2\frac{v_i v_i^{\mathsf{T}}}{v_i^{\mathsf{T}} v_i}$$

satisfy the exact factorization

$$H = R_1 R_2 \cdots R_{21}.$$

This is a transfer-matrix factorization and not a fabricated optical-device claim.

The same code identifies a six-dimensional minus-type quadratic space. Its thirty-six nonsingular vectors form a $(64, 36, 20)$ Hadamard difference set. For the full bilinear Walsh matrix W_{64} and its nonsingular principal minor W_N,

$$W_{64}W_{64}^{\mathsf{T}} = 64I, \qquad K = W_N - 2I.$$

Thus the thirty-six-port transform is a diagonal shift of a quadratic-Walsh principal minor.

Integrally, the triple incidence has

$$\mathrm{SNF}(D) = 1^{30}2^{5}6, \qquad \operatorname{coker}(D) \cong (\mathbb{Z}/2\mathbb{Z})^{5} \times \mathbb{Z}/6\mathbb{Z}.$$

The order 192 is not promoted to a tomotope identification without an objectwise map.

Finally, the 120-vertex Fischer-line graph is not distance regular: distance-two pairs split into two intersection profiles. Its exact symmetry group is $U_4(2){:}2$, a vertex stabilizer has subdegrees $1, 2, 27, 36, 54$, and the Terwilliger algebra has dimension 55 modulo three independent large primes. Projecting the three-point fibers to their standard S_3 sectors produces a rank-twenty tight-frame projector

$$E_{20} = \frac{FAF + 9F}{108}, \qquad (FAF + 9F)^2 = 108(FAF + 9F),$$

whose 120 vectors have normalized inner products in

$$\left\{-\frac{1}{2}, -\frac{1}{6}, 0, \frac{1}{3}\right\}.$$

The Monster class-fusion computation is delegated to a self-reporting GAP/CTblLib workflow. No fusion count or degree-81 multiplicity is asserted until its committed execution artifact is observed.

39.1 Passes 3769–3786: the $GQ(4,2)$–Veldkamp–W33 closure

The six-dimensional minus quadratic space over $\mathbb{F}_2$ supplies 27 singular and 36 nonsingular nonzero vectors. Its singular points and totally singular lines form $GQ(2,4)$, with 27 points and 45 three-point lines; the dual $GQ(4,2)$ has 45 points and 27 five-point lines. The dual point graph is

$$\mathrm{srg}(45, 12, 3, 3), \qquad \mathrm{Spec}(A) = \{12^{1}, 3^{20}, (-3)^{24}\}.$$

Writing $A_0 = I$, $A_1 = A$, and $A_2 = J - I - A$, its Bose–Mesner multiplication is

$$A_1^2 = 12A_0 + 3A_1 + 3A_2, \quad A_1A_2 = 8A_1 + 9A_2, \quad A_2^2 = 32A_0 + 24A_1 + 22A_2.$$

The primitive-idempotent ranks are $1, 20, 24$. The Terwilliger algebra at a point has dimension 16, center dimension 5, and standard-module central block multiplicities $2, 3, 8, 14, 18$, hence semisimple type

$$M_3 \oplus M_2 \oplus \mathbb{C}^3.$$

All 651 projective lines of $PG(5,2)$ split by quadratic type as

$$45 + 216 + 270 + 120.$$

The final 120 lines consist of three nonsingular vectors and coincide exactly with the Norton–Fischer triples of the preceding spread algebra. Thus that triple system is the type-IV line class of the Veldkamp space $V(GQ(2,4))$.

An exact-cover enumeration finds 200 ovoids of $GQ(4,2)$, in automorphism orbits $40 + 160$. On the 40 plane ovoids, declare two objects adjacent when they share three quadrangle lines. The resulting graph is

$$\mathrm{srg}(40, 12, 2, 4)$$

and is explicitly isomorphic to the independently reconstructed W33 point graph. If M is the 40×45 plane-ovoid incidence matrix, then

$$MM^{\mathsf{T}} = 8I + 2A_{W33} + J, \qquad \mathrm{Spec}(MM^{\mathsf{T}}) = \{72^{1}, 12^{24}, 0^{15}\}.$$

The recurring count $135 = 45 \cdot 3$ supports two inequivalent $U_4(2)$ actions. The Lagrangian-frame stabilizer has order census

$$1^1\,2^{43}\,3^{32}\,4^{84}\,6^{32},$$

whereas an ordinary $GQ(4,2)$ flag stabilizer has

$$1^1\,2^{27}\,3^{32}\,4^{36}\,6^{96}.$$

The corresponding permutation-character norms are 9 and 8, with cross-inner product 4.

The rank-24 primitive projector is

$$P = (A - 12I)(A - 3I) = 90E_{-3},$$

with entries 48 on the diagonal, -12 on adjacent pairs, and 3 on nonadjacent pairs. On $\operatorname{im} P$ define

$$x \star y = E_{-3}(x \circ y), \qquad a_i = Pe_i/21.$$

Then the 45 vectors a_i are idempotent axes with Peirce spectrum

$$1^1, \qquad (1/7)^{14}, \qquad (-1/3)^9.$$

For collinear axes,

$$a_i \star a_j = -\frac{1}{3}(a_i + a_j),$$

and the five axes on every quadrangle line sum to zero. For noncollinear i, j with common neighbors c_1, c_2, c_3,

$$a_i \star a_j = \frac{1}{7}(a_i + a_j) + \frac{5}{42}(a_{c_1} + a_{c_2} + a_{c_3}).$$

The algebra is positive Frobenius; its multiplication operators span all M_{24} modulo 1000003, so it is simple, and its derivation algebra is zero because $1/2$ is absent from every axis spectrum. Its fusion law is not nontrivially $\mathbb{Z}_2$-graded, so this is not a Monster-$2A$ Majorana algebra.

For a representative $W(D_4)$ frame stabilizer, the invariant alternating forms modulo two have dimension seven and rank distribution

$$0^1, 4^3, 6^4, 8^{12}, 10^{12}, 14^{40}, 16^{56}.$$

No invariant form has rank 24; consequently no $W(D_4)$-invariant even unimodular rank-24 child exists. A deterministic trace-eight involution nevertheless permits an integral determinant--1 basis change that pulls back E_8^3 to an even unimodular positive child whose exact surviving $U_4(2)$ stabilizer is C_2. This child has roots and is not promoted as a Leech realization.

The finite-group embedding front remains fail-closed. A future candidate must reproduce the complete 36/45/27/120/135/40 fingerprint, independent order 51840, class correspondence, and content-addressed incidence digests before any Monster embedding is asserted.

39.2 Exact twirl estimation, Floquet cancellation, distributed clocking, and control closure (Passes 3787–3794)

The W33 control architecture now has exact finite resource contracts beyond the preceding symmetry-operating-system packet. The results below distinguish algebraic control statements from physical pulse and device claims.

Minimum exact observable twirl. The ordered-pair action has orbit sizes 40, 480, and 1080. Exact unweighted estimation of the diagonal, oriented-edge, and oriented-nonedge averages therefore needs at least

$$40 + 480 + 1080 = 1600$$

settings, and one shortest automorphism word per target attains the bound. The total compiled cost is 8934 generator macros, versus 211898 for the complete group sweep. This closes observable/orbit estimation, not the stronger active conjugation-channel twirl, whose unweighted divisibility lower bound remains 4320.

Floquet cancellation. The four incidence matchings induce relative cycle types $(20, 20)$, (40), and (40) and generate S_{40}. For either relative forty-cycle C and any diagonal error Hamiltonian D,

$$\frac{1}{40}\sum_{t=0}^{39} C^{-t} D C^{t} = \frac{\operatorname{tr} D}{40} I.$$

Hence all traceless static diagonal disorder cancels exactly over one orbit. This is not a general coherent-error or loss theorem.

Optimal distributed clock. On the eighty-node point–line incidence network, one matching per tick gives the exact informed-node census

$$1, 2, 4, 8, 16, 30, 54, 80.$$

All nodes receive the frame in seven ticks. The information-doubling lower bound $\lceil \log_2 80 \rceil = 7$ proves optimality in the declared store-and-forward model, replacing the prior eighty-step central-bus serialization.

Exact control-port count. A complete automorphism-orbit enumeration of reverse zero-forcing sequences has orbit counts

$$1, 1, 2, 5, 16, 43, 191, 769, 3024, 9772, 24852, 34890$$

through depth eleven. Every depth-eleven orbit is terminal and depth twelve is empty. Therefore

$$\boxed{Z(W33) = 29}.$$

An explicit minimum set and eleven-step force chain are frozen in the executable certificate. The graph-control consequence retains the standard Hamiltonian assumptions and is not a pulse-robustness result.

Dynamic W33/local phase. An explicit relabelling of the degree-twelve local ring and W33 shares 128 of their 240 couplers. The reconfigurable union therefore uses

$$240 + 240 - 128 = 352$$

couplers, a 26.67% reduction from disjoint hardware. The cross-phase two-step operator has pairwise minimum two, while the complete two-phase walk has minimum four. The witness is not claimed globally optimal.

Three further mechanisms. First, the exact zero-forcing chain virtualizes eleven unactuated calibration channels behind twenty-nine physical phase actuators in the ideal graph-linear model. Second, the same forty-cycle provides a forty-setting Fourier spectrometer that reconstructs all thirty-nine traceless diagonal modes while its zero character performs common-mode averaging. Third, reversing the optimal broadcast tree gives a seven-tick qutrit gather and a fourteen-tick collision-free all-reduce.

Evidence boundary. The frozen semantic certificate is

`aa3daf462320badd607a1720479f083df159044f24242e7f46810de30bc2e0d8`.

The results certify finite group words, orbit-estimation cost, static diagonal cancellation, broadcast depth, zero forcing, a dynamic-topology witness, and three algebraic communication/calibration mechanisms. They do not certify an optimal active twirl, a complete Floquet quantum code, noisy actuator virtualization, minimum physical layout, or laboratory performance.

39.3 Exact plane-ovoid transport, the 200-ovoid scheme, and a rootless axial Leech polarization

Passes 3795–3812 replace the prior existential plane-ovoid isomorphism by a canonical objectwise dictionary. The full $O_6^-(2)$ torsor contains 51,840 graph isomorphisms, and its lexicographically minimal representative transports all forty points, all forty four-point lines, and all thirty-six ten-line spreads of $W(3,3)$ onto the forty plane ovoids of $GQ(4,2)$.

The action on all $200 = 40{+}160$ ovoids has nineteen ordered-pair orbitals. Their orbital matrices form a nineteen-dimensional coherent algebra; the complete $19 \times 19 \times 19$ intersection tensor has 405 nonzero entries and center dimension five modulo 1,000,003. Two self-paired valency-three relations on the 160 tripods each split into forty disjoint copies of K_4. If B is the 40×40 intersection matrix of the two block systems, then

$$BB^{\mathsf{T}} = 4I + A_{W(3,3)},$$

so the tripods are precisely the 160 flags between two dual forty-object systems and reconstruct the strongly regular graph $(40, 12, 2, 4)$.

Using the standard degree-24 M_{24} generators and a base octad, the verifier regenerates the binary Golay code with weight distribution

$$A_0 = 1, \quad A_8 = 759, \quad A_{12} = 2576, \quad A_{16} = 759, \quad A_{24} = 1.$$

Its integral coordinate construction gives a positive-definite even unimodular rank-24 Gram matrix. Exact short-vector enumeration finds only the zero vector at norm at most two and exhibits norm four, hence the lattice is rootless with minimum four and is therefore the Leech lattice. A determinant-one integral transport places this Gram matrix on the rank-24 axial carrier. Exhaustive testing of all 25,920 elements of the axial $U_4(2)$ action gives

$$\mathrm{Stab}_{U_4(2)}(\Lambda_{\mathrm{axial}}) \cong C_2.$$

Seven explicit degree-45 permutations generate $O_6^-(2) = U_4(2){:}2$ of order 51,840, with index-two subgroup $U_4(2)$ of order 25,920. This is an abstract finite descent only: serialized Monster or `mmgroup` words and an executed Monster class fusion remain absent.

Finally, the forty-five axes span dimension twenty-four. The twenty-seven five-axis line sums have rank twenty-one and generate the complete linear kernel. Collinear pairs generate dimension two, noncollinear pairs dimension four, and the six triple orbits have generated dimensions

$$4,\ 10,\ 24,\ 10,\ 5,\ 3$$

for orbit sizes $240, 2160, 2880, 6480, 2160, 270$, respectively. Thus one orbit of 2,880 triples generates the entire algebra, although no pair does. The algebra is simple, nonunital, and has zero derivations. The exact semantic certificate is

`be5ee56a84141a7bbc896b4cef0e8eda32167a00749dbb17f10d24d0505bdd41`.

No Monster/Majorana/Griess/VOA, remote-PDF, hardware, laboratory, or physical claim is promoted by this computation.

40 Quadratic Parent, Discriminant Chain, Multiport Compiler, and Holonomy Scheme

The thirty-six nonsingular vectors of the minus-type quadratic space $(\mathbf{F}_2^6, q)$ are one subconstituent of the Cayley graph $x \sim y \Leftrightarrow q(x+y) = 1$. Its adjacency matrix obeys

$$A_{64}^2 = 16I + 20J,$$

so the parent is $\mathrm{SRG}(64, 36, 20, 20)$. The neighborhood of zero induces the complement of $\mathrm{SRG}(36, 15, 6, 6)$, while the twenty-seven nonzero nonneighbors induce the Schlaefli graph, the complement of $\mathrm{SRG}(27, 10, 1, 5)$.

For the binary character code

$$C = \{(\beta(a, x))_{x \in N} : a \in \mathbf{F}_2^6\} = [36, 6, 16],$$

the Construction–A discriminant module is

$$L(C)^*/L(C) \cong C^\perp/C \cong (\mathbf{Z}/2)^{24}, \qquad q_L(c + C) = \mathrm{wt}(c)/2 \pmod{2\mathbf{Z}}.$$

An explicit rank-eleven totally isotropic chain yields a maximal doubly-even $[36, 17, 8]$ extension and an even overlattice of determinant four. Rank twelve is impossible because it would produce an even unimodular lattice of rank thirty-six. The residual two-dimensional quotient gives three singly-even self-dual code extensions and hence three odd unimodular Construction–A neighbors, in two distinct weight-enumerator types.

The exact involution

$$H = (2A_{36} - J)/6$$

admits a proof-carrying compilation through twenty-one primitive integer Householder directions. Balanced exact Givens trees require 944 two-mode rotations, twenty-one single-mode π phases, and sequential depth 221. A deterministic adjacent elimination reduces the candidate mesh to 512 rotations in sixty-nine layers. Full support gives the unconditional light-cone bound $d \geq \lceil \log_2 36 \rceil = 6$.

The 120 Fischer triples carry a four-angle rank-twenty frame whose five Gram relations close to a commutative association scheme. Its valencies and multiplicities are

$$(1, 2, 54, 36, 27), \qquad (1, 20, 24, 60, 15),$$

and its first eigenmatrix is

$$\begin{pmatrix} 1 & 2 & 54 & 36 & 27 \\ 1 & -1 & -9 & 0 & 9 \\ 1 & 2 & -6 & 6 & -3 \\ 1 & -1 & 3 & 0 & -3 \\ 1 & 2 & 6 & -12 & 3 \end{pmatrix}.$$

The forty antipodal fibers quotient to $W(3,3)$. On quotient nonedges the $1/3$ relation is a perfect matching and defines an S_3 connection. Of the 3240 base triangles, 1080 are flat and 2160 have transposition holonomy; three- cycle holonomy first appears on four-cycles, so the full holonomy group is S_3.

Finally, if F and T denote port–frame and port–triple incidence, then

$$FF^{\mathsf{T}} = 15I + 3A, \qquad TT^{\mathsf{T}} = 9I + J - A,$$

and therefore

$$\boxed{FF^{\mathsf{T}} + 3TT^{\mathsf{T}} = 42I + 3J}.$$

After removing the all-ones channel, the weighted frame–triple carrier is an exact tight resolution of the thirty-five-dimensional contrast space.

All statements in this section are finite exact certificates. They do not supply Monster words, a Leech identification, an optimal optical circuit, a hardware result, or a physical gauge interpretation.

41 Maximal-code census, exact adjacent mesh, holonomy closure, and the ovoid flag completion

The six-bit minus-type quadratic parent supports a complete exact refinement of the code, multiport, Fischer-holonomy, finite-group, and ovoid fronts. The frozen component certificate has semantic digest

`b141dd0f82e4a6b1ee62d1c57f0e92bdfc9f58d3b32515f9521a0175fdca88a1`.

41.1 Maximal doubly-even extensions

Let $C = [36, 6, 16]$ be the binary character code on the nonsingular vectors. Its discriminant module is the minus-type quadratic space $O_{24}^{-}(2)$ of Witt index eleven. Hence the exact number of maximal doubly-even extensions is

$$N = \prod_{i=2}^{12} (2^i + 1) = 2401379053872797858681 25.$$

Since $|U_4(2){:}2| = 51840$, there are at least

$$46322898415756134 40$$

orbits. Thus the exact classification is necessarily a census and orbit-explosion theorem rather than a literal representative list. An explicit maximal extension $D = [36, 17, 8]$ has enumerator

$$1 + 225z^8 + 9555z^{12} + 55755z^{16} + 55755z^{20} + 9555z^{24} + 225z^{28} + z^{36},$$

and trivial stabilizer in $U_4(2){:}2$.

41.2 An exact 418-gate adjacent mesh

For

$$H = (2A_{36} - J)/6,$$

an exact symbolic adjacent Givens elimination gives 418 nontrivial rotations in 69 layers, 212 exact zero skips, and one terminal π phase. Every gate has

$$c = \operatorname{sgn}(c)\sqrt{c^2}, \qquad s = \operatorname{sgn}(s)\sqrt{s^2}, \qquad c^2 + s^2 = 1,$$

with rational squared parameters. The exact parameter digest is

`5c933cc2e6d2484e97894f3ca1f71627214238e41a68cd59b7527993d2b06b6b`.

The certified bounds are

$$35 \le g \le 418, \qquad 6 \le d \le 69.$$

No global optimality claim is made.

41.3 The rank-five holonomy scheme

The 120 Fischer triples carry five Gram relations with valencies

$$1, 2, 54, 36, 27$$

and primitive multiplicities

$$1, 20, 24, 60, 15.$$

All Krein parameters are exact. There is no Q-polynomial ordering, and exactly four fusion schemes survive: the full scheme, the fusion $(2, 4)$, the fusion $(2, 3, 4)$, and the complete rank-two fusion. The full automorphism group is $U_4(2)$:2. At a point,

$$\dim_{\mathbf{Q}} T = 79, \qquad \dim_{\mathbf{Q}} Z(T) = 10.$$

The certificate proves exact closure using 79 word matrices and all 83 point-stabilizer orbitals.

41.4 Complete abstract standard-pair census

Inside $U_4(2)$, fix an involution a in the class of size 45. Exactly 1152 order-five elements b satisfy

$$|ab| = 9, \qquad |[a, b]| = 3.$$

The centralizer $C(a)$ has order 576 and splits those elements into two orbits of size 576. Each orbit representative generates all 25920 elements. Therefore the complete ordered standard-pair census is

$$45 \cdot 1152 = 51840.$$

No serialized Monster words or Monster character restriction is asserted.

41.5 Ovoids as W33 points and flags

All 200 ovoids of $GQ(4,2)$ split into 40 plane ovoids and 160 tripods. Objectwise,

$$40 \text{ plane ovoids} = 40 \text{ W33 points},$$

$$160 \text{ tripods} = 160 \text{ incident W33 point-line flags}.$$

The 160 tripod port columns collapse four-to-one onto the 40 W33 line-versus-spread incidence columns. Finally the five fibers

$$1 \mid 27 \mid 36 \mid 40 \mid 160$$

form one $O_6^-(2)$ orbital coherent configuration of rank 48.

Boundary. The packet does not materialize billions of orbit representatives, prove global circuit optimality, produce Monster words or class fusion, identify a rootless lattice, or certify hardware, laboratory, remote-CI, or PDF results.

42 Adaptive geometry, virtual topology, autonomous attraction, and thermodynamic inversion

Passes 3829–3836 recast the W33 machine as a dynamically selected control architecture rather than a single permanently active graph. The exact certificate is generated by `analysis/w33_pass3829_3836_adaptive_` and has semantic digest `d924764ba5d64326fbdc8d7a6bbd8bcdff2fd08fb2a4c6560f29c53a71c29fe4`.

Adaptive hypervisor. A declared four-state, five-action discounted control model selects the local ring in the clean regime, the forty-cycle Floquet mode under diagonal drift, W33 under burst loss, and spectroscopy or direct 29-port control under crosstalk. Its frozen adaptive score is 36.5799750262, compared with 66.3616366758 for the best static policy. These are benchmark-model scores, not measured logical-error rates.

Virtual topology. The 240 W33 edges admit an explicit decomposition into twelve perfect matchings. Because every vertex has degree twelve and one edge token per vertex can be consumed in one round, twelve rounds are both necessary and sufficient. Thus a measurement- or teleportation-mediated realization can instantiate the complete W33 interaction epoch using twenty heralded edge tokens per round and no permanently fabricated W33 couplers, before source, fusion, memory, and feedforward overheads are counted.

Autonomous attraction. Let Π_{W33} average a symmetric forty-mode matrix over its diagonal, adjacent, and nonadjacent entries. Then Π_{W33} is an idempotent projector with image

$$\operatorname{span}\{I, A, J - I - A\}.$$

The ideal reservoir step

$$\Phi(X) = \tfrac{1}{2}\big(X + \Pi_{W33}(X)\big)$$

contracts every symmetry-breaking component by exactly one half. Twenty steps therefore suppress the deviation by 2^{-20}. This is an algebraic reservoir target, not an implemented Lindbladian.

Thermodynamic crossover. For independent heralded edge success p, the worst-nonedge route probabilities are

$$q_{W33} = 1 - (1 - p^2)^4, \qquad q_2 = 1 - (1 - p^2)^2.$$

Using frozen wirelength proxies 1064 and 938, the retry-energy crossover is

$$p_* = \sqrt{1 - \sqrt{63/469}} \approx 0.795921897507.$$

Below p_*, W33's four-route redundancy outweighs its longer layout proxy; above p_*, the local two-route control is cheaper in this declared model. No wall-plug energy claim follows.

Substrate inversion. One complete interaction epoch has the exact primitive-count alternatives

$$C_{\text{native}} = 240a + 12g + 240d, \quad C_{\text{virtual}} = 240b + 12g + 240d,$$

$$C_{\text{mesh}} \in 67a + [12, 870]g + 870d, \quad C_{\text{bus}} = a + 240g + 240d,$$

where a, b, g, d price static links, consumable edge tokens, rounds, and routing hops. No substrate class is coefficient-independently optimal.

Three additional mechanisms. First, the exact strongly regular identity

$$A^2 + 2A - 8I - 4J = 0$$

acts as a digital-twin checksum. Every single edge deletion produces a rank-four residual with squared Frobenius norm 54 and support 48; every single insertion produces rank four, norm squared 58, and support 52. The two corrupted endpoints are the unique residual rows of support thirteen or fourteen, respectively.

Second, independent heralded links can be distilled geometrically. For nonadjacent vertices,

$$P_{\text{route}} = 1 - (1 - p^2)^4,$$

while an adjacent pair can use its direct edge and two triangle detours,

$$P_{\text{route}} = 1 - (1 - p)(1 - p^2)^2.$$

At target reliability 0.999, the corresponding edge-success thresholds are approximately 0.906737 and 0.935615.

Third, the four transvections and their inverses define an eight-jump symmetry bath on the forty points. Its second eigenvalue is 0.9367092858522434, its spectral gap is 0.0632907141477566, and the standard spectral bound gives 89 jumps for one-percent mixing from a localized point defect. This is an ideal Markov process, not a physical dissipation-rate theorem.

Evidence boundary. The finite graph identities, matching decomposition, defect signatures, projector law, routing formulas, and primitive counts are exact. The adaptive cost model, ideal reservoir, retry-energy proxy, substrate coefficients, independent-link model, and symmetry-bath implementation remain explicit architectural hypotheses rather than laboratory evidence.

43 Ovoid Wedderburn Algebra, Leech Transport, and Triality Incidence

The complete $40 + 160$ ovoid coherent algebra has dimension 19 and centre dimension 5 over $\mathbf{Q}$. Exact rational primitive central idempotents and minimal-left-ideal ranks give the split decomposition

$$\mathcal{A} \cong M_2(\mathbf{Q}) \oplus \mathbf{Q} \oplus M_2(\mathbf{Q}) \oplus \mathbf{Q} \oplus M_3(\mathbf{Q}).$$

On the 200-point permutation module,

$$\mathbf{Q}^{200} \cong 1^{\oplus 2} \oplus 15_a^{\oplus 2} \oplus 15_b \oplus 24^{\oplus 3} \oplus 81.$$

The canonical W33–plane-ovoid dictionary transports all 240 edges, 160 triangles, 40 lines, and 36 spreads. The oriented ternary check matrices satisfy

$$\operatorname{rank} H_X = 39, \qquad \operatorname{rank} H_Z = 120, \qquad H_X H_Z^{\mathsf{T}} = 0,$$

with $d_X = 3$ and $d_Z = 4$, hence the edge code is $[[240, 81, 3]]_3$.

Under the explicit determinant-one Leech transport, exactly three integral axial numerator vectors have norm four:

$$a_3, \quad a_{33}, \quad a_{36}.$$

The surviving involution fixes a_3, swaps a_{33} and a_{36}, and the three carriers lift to nine D_4 frames.

The 45 marked axes admit a universal rational presentation by the 27 five-axis line sums and the two exact pair-product laws. The line relations have rank 21, so the quotient has dimension 24. An independent rooted graph computation gives

$$|\operatorname{Aut}_{\text{marked}}| = 45 \cdot 1152 = 51840 \cong |O_6^-(2)|.$$

The 148995 four-axis subsets form 20 orbits, with generated-dimension census

$$4^{135},\ 5^{720},\ 6^{1080},\ 10^{16740},\ 14^{27000},\ 24^{103320}.$$

The two 40-block tripod fibrations produce a 40×40 incidence matrix whose row and column Gram graphs both have parameters $(40, 12, 2, 4)$ but are nonisomorphic. The full bipartition-preserving automorphism group has order 51840, and no side swap exists. The smallest tripod–Norton relation has size 480, rank 40, and bipartite graph

$$40K_{4,3}.$$

Although this equals the number of directed W33 edges, the two permutation characters have norms 23 and 24 with cross inner product 18, so the two 480-actions are inequivalent.

The semantic certificate is `ede91cc799f9093209c589fb0b73c88fca4159bedcc8e1e7cd6680c5f0c778fd`. Serialized Monster words, Monster class fusion, the full unmarked linear automorphism group, remote CI/PDF success, and physical claims remain outside the promoted boundary.

43.1 Cubic tightening, tomotope outer extension, and complete modular descent

The dependency hypergraph on the 240 filled faces admits an explicit 63-face cap. Its complement is a 177-face transversal, improving the live exact interval to

$$106 \le \tau_{\text{cubic}} \le 177.$$

The witness has triple-hit profile $1^{876}2^{2217}3^{1947}$ and is locally optimal against every exchange removing at most two selected faces. No nonexistence theorem for a 64-cap is claimed, and the independent covering-radius boundary remains $389 \le R \le 435$.

The three exceptional entries in the 3×3 tomotope-completion square require a correction. Their automorphism groups have order 192 but trivial centre. Each has a unique normal elementary abelian subgroup 2^4, ordinary index-two subgroup $2^4{:}S_3$, and quotient D_{12}. Hence the exceptional group is the split, centreless outer extension

$$2^4{:}D_{12},$$

not a non-split central double cover.

The previously unresolved 115-dimensional characteristic-three quotient has composition factors

$$1^3 \oplus 5^3 \oplus 10^3 \oplus 14^3 \oplus 25.$$

An explicit 13-step series has successive dimensions

$$10, 14, 5, 10, 25, 5, 1, 14, 5, 10, 1, 14, 1,$$

and every factor generates its full matrix algebra over $\mathbb{F}_3$.

The exact Golay–Witt Gewirtz graph admits a canonical 16+40 split under a second fixed point. Its unique two-point-stabilizer-invariant degree-12 residual graph is not W33; it is the independent fourfold blow-up of Petersen, with spectrum $12^1 4^5 0^{30} (-8)^4$.

Three associated constructions are exact: the free 63-cap orbit is a binary constant-weight code of length 240, size 25,920, weight 63, and minimum distance 62; the residual graph has ten twin classes of size four and Petersen quotient; and the cap's forty W33-fibre occupancies form a free orbit with spectral energies 3969/40, 157/5, and 163/8 on the 12, 2, and -4 channels.

The authoritative website remains pinned to Git blob `41a8d733f42da18282fa276f5d2fa82bac7516f6`. A fail-closed migration validator requires literal owner authorization binding old blob, new blob, and an exact archive before replacement. No migration, remote CI/PDF result, hardware result, laboratory result, Monster embedding, or physical interpretation is asserted.

43.2 Unmarked axial symmetry, explicit rational modules, and the order-192 barcode

Passes 3887–3904 have semantic certificate `6ef2f6c4a0fa7e52da9f4abff6d899d0250eeabde1a601d53c40052a841`. They also correct the four-axis generated-dimension census of Passes 3837–3854, whose unreduced three-factor `int64` contraction overflowed before modular reduction.

Let $E = (A - 12I)(A - 3I)/90$ and let $V = \operatorname{im} E$ carry $x \star y = E(x \circ y)$. Exact rational multiplication matrices satisfy

$$\operatorname{tr}(L_x L_y) = \frac{7}{30}\langle x, y\rangle.$$

Thus the Euclidean form is intrinsic to multiplication. If $y \neq 0$ is an idempotent and m is its largest coordinate, the three quadrangle lines through a maximizing point give $N \ge 3m^2/4$ on its twelve neighbours, while its thirty-two nonneighbours give $Q \ge m^2/8$. Together with

$$m = \frac{8}{15}m^2 - \frac{2}{15}N + \frac{1}{30}Q$$

and $\|y\|^2 = \sum_i y_i^3$, this proves

$$\|y\|^2 \ge \frac{480}{49}.$$

Equality holds exactly for the 45 known axes. Hence every unmarked algebra automorphism permutes them, and

$$\boxed{\mathrm{Aut}(V,\star) \cong O_6^-(2) \cong U_4(2):2, \qquad |\,\mathrm{Aut}\,| = 51{,}840.}$$

The 19-dimensional orbital algebra has explicit split rational model

$$M_2(\mathbb{Q}) \oplus \mathbb{Q} \oplus M_2(\mathbb{Q}) \oplus \mathbb{Q} \oplus M_3(\mathbb{Q}).$$

Primitive rational projectors produce irreducible modules of dimensions $1, 15, 15, 24, 81$, and

$$\mathbb{Q}^{200} \cong 1^{\oplus 2} \oplus 15_a^{\oplus 2} \oplus 15_b \oplus 24^{\oplus 3} \oplus 81.$$

All five character inner products were evaluated on the complete order-51,840 group and form the identity matrix.

The 480-element $40K_{4,3}$ incidence action has character norm 23 and decomposes on the five known constituents as

$$\chi_{480} = 1 + 2 \cdot 81 + 2 \cdot 15_a + 15_b + 3 \cdot 24 + \rho_{200},$$

where ρ_{200} has degree 200, norm 4, and is orthogonal to all five known characters. The explicit Monster-subgroup database contains portable maximal-overgroup seeds but no direct $U_4(2):2$ key; no Monster words or class fusion are promoted.

The corrected four-axis calculation reduces after each contraction stage and is stable over six primes. Its weighted generated-dimension census is

$$4^{135}5^{720}6^{1080}10^{16740}12^{5040}14^{27000}16^{14040}24^{84240}.$$

The twenty generating-set orbits collapse to eight simple nonunital subalgebra species of dimensions

$$\boxed{4, 5, 6, 10, 12, 14, 16, 24.}$$

Every species has zero annihilator and nucleus, full square span and trace rank, full associator ideal, and multiplication envelope M_d.

Finally, four order-192 mechanisms are separated. The ordered incident-pair/frame stabilizer is $W(D_4)$ with center 2 and derived subgroup 96; a distinguished involution centralizer is $D_8 \times S_4$ with derived subgroup 24; the archived octonion axis-line stabilizer is centerless and has 48 elements of order 8; and the corrected exceptional tomotope completion is the centerless split group $2^4 : D_{12}$. Equality of order or carrier size is therefore not an identification.

No portable Monster words, executed Monster class fusion, complete decomposition of ρ_{200}, complete tensor-product table, SmallGroup identification of the octonion stabilizer, remote CI/PDF success, hardware result, laboratory result, thermodynamic result, or physical mechanism is asserted without separate evidence.

43.3 Terwilliger sieve, improved adjacent mesh, code strata, and rank-48 overlap

The rank-five holonomy Terwilliger algebra has exact dimensions

$$\dim_{\mathbf{Q}} T = 79, \qquad \dim_{\mathbf{Q}} Z(T) = 10.$$

Assuming split semisimplicity over $\mathbf{Q}$, exhaustive integer arithmetic leaves exactly fourteen possible nondecreasing matrix-degree multisets satisfying $\sum_i n_i^2 = 79$; the largest block degree lies between four and eight. Primitive central idempotents are still required to select the actual multiset.

For the 36-port involution $H = (2A - J)/6$, a new symmetry-adapted ordering lowers the adjacent elimination candidate from 418 to

$$398 \text{ rotations in } 69 \text{ layers},$$

with one terminal π phase. The zero pattern is numerically stable and all nontrivial rotations admit rational-square parameter recovery, but a complete exact-radical replay remains required before the circuit is promoted as an exact identity.

Maximal doubly-even $[36, 17]$ extensions containing the character code obey an exact one-parameter enumerator law. Writing $t = A_4$,

$$A_8 = 225 + 11t, \qquad A_{12} = 9555 - 39t, \qquad A_{16} = 55755 + 27t,$$

with symmetry about weight 18. A deterministic 258-code sample realizes $t = 0, 1, 2, 3, 4, 5$ and 184 distinct weight-eight coordinate-degree profiles, demonstrating that the enumerator is a coarse orbit invariant.

Finally, the 64-point quadratic carrier, 200-ovoid carrier, and combined 264-object carrier have orbital ranks 15, 19, and 48. Therefore their cross-Hom dimension is seven. Six dimensions are forced by the three-versus-two trivial constituents, leaving exactly one shared nontrivial 15-dimensional constituent. The 64-module consequently has form

$$1^3 \oplus 15_b \oplus X^2 \oplus Y, \qquad 2\dim X + \dim Y = 46,$$

where X and Y do not occur in the 200-ovoid carrier. No Monster embedding, class fusion, exact-radical mesh proof, global mesh optimum, exhaustive code-orbit ledger, hardware result, laboratory result, or physical interpretation is claimed.

44 Passes 3913–3920: multi-defect immunity, symmetry dissipation, process control, and dual scheduling

The W33 control architecture now has a bounded multi-defect decoder, an explicit random-unitary symmetry Lindbladian, a partially observed controller, a correlated-fusion threshold, and a joint substrate/topology phase diagram. Three additional constructions compress the graph into a finite-field seed, extend the interaction schedule to an optimal all-to-all epoch, and compress the two-defect sensor.

Bounded topology immune system. For a measured adjacency matrix B, define

$$R(B) = B^2 + 2B - 8I - 4J.$$

The exhaustive ledger contains all

$$\binom{780}{2} = 303{,}810$$

two-edge insertion/deletion mixtures, and every complete residual is distinct. It also contains all

$$\binom{240}{3} = 2{,}275{,}280$$

three-edge deletions, again without a repeated residual. General mixed weight-three cases remain open.

Symmetry Lindbladian. Let U_g denote the four generating transvections and their inverses. The random-unitary generator

$$\mathcal{L}(X) = \frac{1}{8}\sum_g (U_g X U_g^\dagger - X)$$

has fixed algebra

$$\mathrm{Fix}(\mathcal{L}) = \mathrm{span}\{I, A, J - I - A\}.$$

Its unit-rate gap is

$$0.06329071414775411.$$

Every transvection consists of nine disjoint three-cycles and thirteen fixed points, yielding a 72 three-mode-cycle compilation target for the eight directed jumps. A sparse local physical realization with the same fixed algebra is not yet proved.

Partially observed geometry control. A six-step four-regime hidden-Markov benchmark with 85-percent regime readout and five geometry/control modes has exact belief-state optimum

$$23.115384313076735.$$

The best static policy costs 30.176036574158424, while full regime information gives the lower bound 16.514150252446512. These are declared benchmark values, not learned process-tensor measurements.

Correlated fusion compiler. A twenty-edge matching is accumulated by a 21-state Markov chain with stored-edge survival 0.995, common outage probability 0.05, and five attempts. Requiring a complete twelve-matching epoch to succeed with probability at least 0.99 gives

$$p \geq 0.9158993399430635.$$

The corresponding independent no-decay threshold is 0.8668344006872047.

Architecture phase diagram. A 500-point declared-cost grid compares native W33, virtual W33, a local ring, a routed mesh, and a shared bus. The winner counts are respectively

$$54, \quad 84, \quad 37, \quad 15, \quad 310.$$

Every implementation wins somewhere; no architecture is coefficient-independently optimal.

Topology DNA. Four four-trit transvection generators and one ordered edge generate the order-25,920 group and the complete 480-element oriented-edge orbit. The graph seed therefore uses eighteen finite-field coordinate symbols rather than 960 explicit oriented-edge endpoint symbols.

Dual-geometry all-to-all epoch. The twelve W33 perfect matchings and twenty-seven complement perfect matchings partition $E(K_{40})$. Hence

$$A + (J - I - A) = J - I$$

and the complete all-to-all one-port schedule has optimal depth

$$12 + 27 = 39.$$

Compressed two-defect sensor. A fixed set of 192 residual entries distinguishes all 303,810 two-edge syndromes, reducing the complete 40×40 residual readout by a factor $1600/192 = 25/3$. Minimality and noise robustness remain open.

Evidence boundary. The executable semantic certificate is `019183d46768ff68a5f57676540d8aefd8530106145` The packet does not establish general mixed weight-three decoding, a local Lindbladian implementation, measured process control, microscopic fusion correlations, measured platform costs, minimum topology memory, simultaneous all-to-all coupling, minimum sensing, hardware performance, or laboratory validation.

45 Hidden character, local-algebra poset, and null-processor boundary

The 480-element $40K_{4,3}$ incidence character decomposes exactly as

$$\chi_{480} = 1 + 2(15_a) + 15_b + 3(24) + 2(81) + 20 + 30 + 60 + 90.$$

Hence the previously unresolved residual is

$$\rho_{200} = 20 \oplus 30 \oplus 60 \oplus 90.$$

The eight simple nonunital local-algebra species have dimensions

$$4, 5, 6, 10, 12, 14, 16, 24.$$

Their Hasse covers are

$$4 \prec 16, \quad 5 \prec 6, \quad 5 \prec 10, \quad 6 \prec 14, \quad 10 \prec 14, \quad 10 \prec 16, \quad 12 \prec 24, \quad 14 \prec 24, \quad 16 \prec 24.$$

The undirected Hasse graph is connected and bipartite with first Betti number two.

For a projected-coordinate algebra $x \star y = E(x \circ y)$, if the scaled columns of E are exactly the minimum-norm nonzero idempotents and pair invariants recover adjacency, every algebra automorphism preserves the recovered graph. In the 45-axis $GQ(4,2)$ instance,

$$\operatorname{tr}(L_x L_y) = \frac{7}{30}\langle x, y\rangle, \qquad \min_{e^2=e,\ e\neq 0} \|e\|^2 = \frac{480}{49},$$

with equality precisely on the 45 axes. Thus

$$\operatorname{Aut}(V, \star) \cong O_6^-(2) \cong U_4(2) : 2.$$

A speculative photon-node model is admitted only in the Lorentz-compatible fixed-product form. If N effective nodes of pitch a are traversed in observer-frame period $T = 1/\nu$, then

$$v_{\text{eff}} = \frac{Na}{\sigma T}.$$

Vacuum null propagation requires $Na = \lambda$, $\lambda\nu = c$, and unit routing stretch. Consequently

$$c = \frac{Na}{T},$$

and a self-similar refinement $N \mapsto bN$, $a \mapsto a/b$ leaves c invariant. This is a falsifiable information-transport model, not evidence for literal photon substructure or variable vacuum light speed.

45.1 Exact selector algebra, radical multiport, code strata, and photon-capacity boundary

The fourteen-case arithmetic sieve for the 79-dimensional selector Terwilliger algebra is superseded by the exact characteristic-zero result already certified in Passes 1365–1369:

$$T(x) \cong \mathbb{Q}^3 \oplus M_2(\mathbb{Q})^2 \oplus M_3(\mathbb{Q})^3 \oplus M_4(\mathbb{Q}) \oplus M_5(\mathbb{Q}).$$

Its simple degrees are

$$1, 1, 1, 2, 2, 3, 3, 3, 4, 5,$$

with standard-module multiplicities

$$3, 12, 14, 1, 2, 4, 4, 8, 8, 1.$$

For the spread-graph multiport

$$H = \frac{2A_{36} - J}{6},$$

an exact sparse multiquadratic replay now proves the previously numerical adjacent-mode candidate. The complete transform uses

$$398$$

nontrivial adjacent Givens rotations in 69 layers, skips 232 eliminations because their entries are exactly zero, and terminates at

$$\mathrm{diag}(1^{35}, -1).$$

Every intermediate entry is a single rational radical. There are 75 distinct values of c^2, the largest denominator is 441, and the ordered parameter digest is

`2c3be7815b8346cd90be108faad4cc68866ad453f13b76bbdd4a9988a4569555`.

No global gate-count or depth optimality is claimed.

The binary character code $C = [36, 6, 16]$ admits an explicit maximal doubly-even extension

$$D = [36, 17, 4]$$

with

$$\begin{aligned} W_D(z) = 1 &+ 57z^4 + 852z^8 + 7332z^{12} + 57294z^{16} \\ &+ 57294z^{20} + 7332z^{24} + 852z^{28} + 57z^{32} + z^{36}. \end{aligned}$$

The intersection-two graph on its 57 weight-four words splits as

$$\boxed{\mathrm{SRG}(45, 16, 8, 4) \sqcup K_{2,2,2} \sqcup K_{2,2,2}.}$$

The coordinate-degree profile is $9^{20}3^{16}$. This proves an exact $A_4 = 57$ stratum, not its global maximality.

The five-fiber carrier $1|27|36|40|160$ has rational permutation decomposition

$$\mathbb{Q}^{264} \cong 1^5 \oplus 6 \oplus 15_a^2 \oplus 15_b^2 \oplus 20^2 \oplus 24^3 \oplus 81,$$

and hence

$$\boxed{\mathrm{End}_G(\mathbb{Q}^{264}) \cong \mathbb{Q}^2 \oplus M_2(\mathbb{Q})^3 \oplus M_3(\mathbb{Q}) \oplus M_5(\mathbb{Q}).}$$

The algebra dimension is 48, its centre has dimension seven, and the cross-carrier Hom space has dimension

$$7 = 3 \cdot 2 + 1,$$

consisting of six trivial channels and one shared 15_b channel.

Photon node-packing boundary. For optical frequency ν,

$$T = \nu^{-1}, \qquad \lambda = c/\nu.$$

If N internal update sites refine one wavelength and one period together,

$$a_N = \lambda/N, \qquad \tau_N = T/N,$$

then

$$\boxed{\frac{a_N}{\tau_N} = c.}$$

Thus node density can refine internal state space and update throughput while leaving vacuum c invariant. In the ideal tensor-factor bookkeeping,

$$R = N\nu \log_2 d, \qquad \rho = N/\lambda, \qquad \frac{R}{\rho \log_2 d} = c.$$

A single photon distributed over N alternatives with a d-state label generally has direct-sum dimension Nd, however, so its accessible classical information is bounded by $\log_2(Nd)$ rather than $N \log_2 d$ unless physically independent tensor factors exist.

The Margolus–Levitin rate for one photon of energy $E = h\nu$ gives

$$\Gamma_\perp \le \frac{2E}{\pi\hbar} = 4\nu, \qquad \Gamma_\perp T \le 4.$$

Consequently forty W33 nodes cannot mean forty sequential mutually orthogonal transitions within one optical period of an isolated photon. They must represent parallel or nonorthogonal modes, multiple periods, or externally driven evolution. This is a falsifier for one literal interpretation, not a rejection of high-dimensional single-photon processing.

The Monster descent remains fail-closed: no portable serialized Monster words or executed character-fusion artifact are present, and no embedding is promoted. No literal photon-node ontology, variable-c mechanism, hardware result, laboratory result, remote-CI success, or PDF success is claimed.

45.2 Topology-code firewall, optimal 24-port control, autonomous boot, and photon causal density

The W33 polynomial residual

$$R(B) = B^2 + 2B - 8I - 4J$$

separates all 79,092,651 edge-toggle patterns of weight at most three: one zero pattern, 780 single toggles, 303,810 double toggles, and 78,788,060 triple toggles. A zero residual has balanced insertion and deletion degree at every vertex. Exhaustion of all 27,000 alternating weight-four supports and 2,769,952 alternating simple weight-six supports finds no undetectable pattern. A nonadjacent vertex transposition gives an explicit undetectable weight-32 relabelling, so

$$8 \le d_0 \le 32.$$

The exact distance remains open.

The desired symmetry dissipator cannot be made from independent strictly two- or three-mode permutation jumps. Every nontrivial W33 automorphism moves at least 27 points, and every transvection has cycle structure $1^{13}3^9$. Four transvections are necessary and sufficient to generate

the full order-25,920 group; each global jump is compilable into nine disjoint three-mode cycles, but those cycles must remain one macro if the fixed algebra

$$\operatorname{span}\{I, A, J - I - A\}$$

is to be preserved.

Writing $B = J - I - A = (A^2 - 2A - 12I)/4$, the complement adds no passive drift algebra. The largest adjacency multiplicity forces at least 24 independent diagonal controls. For one explicit 24-port set, the commutant constraint has modular rank 279 on 280 coordinates over three primes, leaving scalars only. Therefore the ideal controlled $*$-algebra has dimension

$$40^2 = 1600,$$

and 24 ports are necessary and sufficient algebraically.

The topology can boot from four transvection vectors and one ordered edge, an 18-trit seed. Its ordered-edge orbit has 480 elements and BFS diameter 9; a deterministic factorization then supplies 12 collision-free W33 matching rounds. The declared boot sequence—seed verification, orbit expansion, schedule compilation, a 192-entry residual measurement, bounded repair, and symmetry activation—has a 221-round network-action upper bound before source, detector, classical, memory, and settling overhead.

The user-proposed relation between photon computation and light speed survives in a constrained form. If serial node spacing is ℓ and local update time is τ, Lorentz-compatible propagation requires $\ell/\tau = c$. Combining a one-photon energy $E = h\nu$ with the Margolus–Levitin speed limit gives

$$N_{\text{serial}} \le \frac{4EL}{hc} = \frac{4L}{\lambda}.$$

Increasing serial node count at fixed length therefore requires faster internal updates; it does not change invariant vacuum c. Parallel photonic modes enlarge capacity—an ideal M-mode alphabet carries $\log_2 M$ bits—without representing M serial state transitions per optical cycle. Any literal node-count dependence of vacuum speed would predict encoding- or frequency-dependent front arrival and is retained only as a falsifiable, presently unsupported hypothesis.

Two additional exact constructions follow. Since A and its complement commute,

$$e^{-itA}e^{-itB} = e^{-it(J-I)}, \qquad e^{-itA}e^{+itB} = e^{-it(A-B)},$$

giving common-mode and W33-contrast interferometric channels. For the Cartesian hierarchy $W33^{\square m}$,

$$|V| = 40^m, \quad k = 12m, \quad \text{diam} = 2m, \quad |E| = 6m40^m,$$

with absolute spectral gap 10 and ideal causal-density requirement $L/\lambda \ge m/2$. Self-similarity yields logarithmic routing depth but does not compress the exponential physical mode requirement.

No exact topology distance, independently local Lindbladian, robust pulse theorem, learned process tensor, autonomous physical boot, hidden photon-node ontology, variable speed of light, hardware result, or laboratory validation is claimed.

Passes 3973–3980: extremal-code geometry, mesh locality, and photon resource separation

Exact 57-code geometry. For the deterministic maximal doubly-even code $D = [36, 17, 4]$, join two weight-four words when their supports meet in two coordinates. The resulting graph is not

merely a $45 + 6 + 6$ census: an explicit maximal-clique reconstruction gives

$$\boxed{G_{57} \cong T(10) \sqcup T(4) \sqcup T(4) = L(K_{10}) \sqcup L(K_4) \sqcup L(K_4).}$$

Thus

$$57 = \binom{10}{2} + 2\binom{4}{2}.$$

If $t = A_4$, MacWilliams symmetry forces

$$A_8 = 11t + 225, \qquad A_{12} = 9555 - 39t, \qquad A_{16} = 55755 + 27t,$$

and, on the dual side,

$$B_4 = t, \quad B_6 = 6(t + 7), \quad B_{12} = 39(245 - t).$$

Nonnegativity gives only $t \leq 245$. Hence $t = 57$ is exact and geometrically rigid here, but global A_4-extremality is not claimed.

Exact radius-one mesh optimum. The established 36-port factorization uses 398 nontrivial exact multiquadratic Givens rotations, 232 exact zero eliminations, and 69 layers. All $\binom{36}{2} = 630$ single transpositions of the port order were replayed exactly. None improves 398, 22 tie it, and every neighbor has depth 69. Therefore the order is an exact radius-one local optimum in permutation space; global rotation and depth optimality remain open.

One-photon slope/intercept falsifier. The physically conservative null is

$$t(M, L) = a(M) + L/c,$$

where M is the orthogonal-mode alphabet and $a(M)$ absorbs encoder, decoder, detector, and pulse-shape latency. Randomly interleaving fixed-spectrum alphabets $M \in \{2, 4, 8, 16, 40\}$ at two or more free-space lengths permits the fit

$$t(M, L) = a(M) + b(M)L.$$

A mode-dependent intercept is ordinary device latency; only a reproducible mode-dependent slope, surviving encoder swaps and length scaling, challenges the invariant-front null. Capacity must be reported separately from timing. For a symmetric M-ary channel with total error probability ϵ,

$$I(M, \epsilon) = \log_2 M + (1 - \epsilon)\log_2(1 - \epsilon) + \epsilon \log_2\left(\frac{\epsilon}{M - 1}\right).$$

At $M = 40$, this is 5.32193 ideal bits per use, about 5.18828 bits at one-percent symmetric error, and 4.77126 bits at five-percent error.

Literal rank-48 multiplication tensor. The split centralizer algebra

$$\boxed{\mathbb{Q}^2 \oplus M_2(\mathbb{Q})^3 \oplus M_3(\mathbb{Q}) \oplus M_5(\mathbb{Q})}$$

has dimension 48 and center dimension seven. Its matrix-unit multiplication table contains

$$1^3 + 1^3 + 3 \cdot 2^3 + 3^3 + 5^3 = 178$$

nonzero products. The later content-addressed verifier also reconstructs the complete literal orbital tensor:

$$\boxed{48 \text{ relations}, \qquad 904 \text{ nonzero intersection constants.}}$$

Its tensor SHA-256 is

`a17a375552c102d281e3ba79b602b67aa54a426fd68b1878293763ea65395ff9`.

Thus both the split Wedderburn tensor and the geometric orbital-relation tensor are closed exactly.

Photon resource trilemma. A one-photon direct-sum alphabet of M orthogonal alternatives carries at most $\log_2 M$ ideal classical bits per use. A tensor-product claim $N \log_2 d$ requires N physically independent factors. Mutually orthogonal serial updates obey a separate energy–time bound. Temporal packing additionally satisfies the engineering estimate $M \sim 2WT$ for half-bandwidth W and duration T. Larger internal alphabets can therefore increase capacity and spacetime support without changing vacuum c.

For the Cartesian power $W(3,3)^{\square m}$,

$$|V| = 40^m, \qquad \operatorname{diam} = 2m,$$

so the self-similar address density is

$$\boxed{\frac{\log_2 |V|}{\operatorname{diam}} = \frac{\log_2 40}{2} \approx 2.660964.}$$

This is an addressing/routing invariant, not a variable-light-speed law.

Monster gate and evidence boundary. The required observable Monster class-fusion artifact remains absent, so no Monster embedding is promoted. Exact results in this insert are the code geometry, enumerator identities, all-630 mesh audit, split and literal rank-48 tensors, and algebraic resource formulas. The timing sensitivity and time-bandwidth examples are models; the photon experiment, global code extremality, global mesh optimum, Monster fusion, remote CI/PDF success, hardware, and laboratory validation remain open.

46 Extremal code, active multiport, photon mode tests, and rank-48 tensor

Exact certificate. Passes 3973–3980 are reproduced by the content-addressed verifier and frozen certificate with semantic digest `03c37b821bb9b6f875a8bd4edde8dc96fe36a43d6d8dc24144d8dbd5e3aa5104`. Monster execution, laboratory photonics, and remote PDF evidence remain outside the promoted boundary.

Theorem 46.1 (Extremal $A_4 = 57$ extension)**.** *Let $C = [36, 6, 16]$ be the binary character code on the nonsingular vectors of the six-dimensional minus-type quadratic space. Among doubly-even self-orthogonal extensions of C,*

$$\boxed{A_4 \le 57}.$$

The bound is attained by an explicit $[36, 17, 4]$ code. Its 57 weight-four words have intersection-two graph

$$\mathrm{SRG}(45, 16, 8, 4) \sqcup K_{2,2,2} \sqcup K_{2,2,2},$$

and coordinate stabilizer of order 192, with element-order census

$$1^1 2^{59} 3^8 4^{68} 6^{40} 12^{16}.$$

Proof certificate. The 945 admissible weight-four words form a degree-624 compatibility graph with two $O_6^-(2)$ vertex orbits of sizes 135 and 810. Exact colored bitset branch-and-bound gives orbit maxima 15 and 54. Transitivity reduces any clique meeting the 135-orbit to one fixed representative; its exact neighborhood search has maximum 57.

Theorem 46.2 (Active-mixer and fixed-order cut bounds)**.** *The exact* 36*-port involution* $H = (2A_{36} - J)/6$ *admits an adjacent factorization*

$$401 = 296 \text{ genuine mixers} + 105 \text{ signed swaps}$$

in 69 *layers, with zero exact residual. The prior common-order compiler has* $398 = 302+96$ *factors. Thus six active mixing elements are removed when input and output relabeling may differ. For the original common order, the sum of the exact off-diagonal cut ranks is*

$$\boxed{253},$$

so every adjacent factorization respecting that order uses at least 253 *factors.*

Theorem 46.3 (Literal rank-48 coherent tensor)**.** *The five fibers*

$$1 \mid 27 \mid 36 \mid 40 \mid 160$$

carry exactly 48 *orbitals under* $O_6^-(2)$*. Their source–target relation count matrix is*

$$\begin{pmatrix} 1 & 1 & 1 & 1 & 1 \\ 1 & 3 & 2 & 1 & 1 \\ 1 & 2 & 3 & 1 & 2 \\ 1 & 1 & 1 & 3 & 4 \\ 1 & 1 & 2 & 4 & 8 \end{pmatrix}.$$

Exactly 904 *of the* 48^3 *intersection constants are nonzero. The complete sparse tensor has digest* `a17a375552c102d281e3ba79b602b67aa54a426fd68b1878293763ea65395ff9`*.*

Photon competing-model protocol. The photon hypothesis is separated into six models: invariant-front direct-sum capacity; transverse-structure axial delay; a falsifiable hidden-node variable-speed alternative; an engineered W33 graph-kinetic model; independent hyperentangled tensor factors; and self-similar coupling efficiency. For the engineered graph model, $L_{W33} = 12I - A$ has sectors

$$\boxed{0, 10, 16},$$

giving a declared 0:10:16 delay-spectroscopy target. The experiment varies mode count at fixed spectrum and transverse momentum, varies transverse momentum at fixed alphabet, compares equal-dimension factorisations, and keeps causal-front arrival distinct from pulse-peak or group delay. No hidden nodes, variable vacuum light speed, achieved capacity, or measured delay are claimed.

Monster firewall. The exact internal queue contains 51,840 ordered standard pairs in two centralizer orbits of 576, but no portable serialized `mmgroup` words or executed class-fusion artifact are present. The result therefore remains `PENDING_EXPLICIT_MM_WORDS_AND_CLASS_FUSION`.

47 Passes 3981–3988: global mesh bound and photon spectral processor

The stronger reconciled Passes 3973–3980 certificate already proves that the fixed-parent weight-four compatibility graph has maximum clique size 57, hence the selected $[36, 17, 4]$ doubly-even extension is globally extremal within that parent-extension problem. It also reconstructs the literal five-fiber orbital algebra with 48 relations and 904 nonzero intersection constants. The present packet retains those exact results and advances the open physical and compiler boundaries.

47.1 An ordering-independent adjacent-factor lower bound

Let $K = 2A_{36} - J$ be the symmetric 36-port Hadamard transfer matrix, so $K^2 = 36I$. For an arbitrary port ordering and a prefix cut of size k, write

$$K = \begin{pmatrix} A_k & B_k \\ B_k^T & D_k \end{pmatrix}.$$

Then

$$B_k B_k^T = 36I - A_k^2.$$

Thus the cross-cut rank defect is the multiplicity of the eigenvalues ± 6 of A_k. Using

$$\operatorname{tr} A_k = -k, \qquad \operatorname{tr} A_k^2 = k^2,$$

and Cauchy–Schwarz gives the ordering-independent half-sequence

$$1, 2, 3, 4, 5, 5, 6, 7, 7, 8, 8, 8, 9, 9, 9, 9, 10, 9.$$

Reflection symmetry therefore forces

$$\boxed{N_{\text{adjacent}} \geq 229.}$$

The published ordering has cut-rank sum 253. A deterministic exact ordering search found a second ordering with sum 251. The number 251 is a stronger order-specific target, not yet an implemented factorization or a proof of global optimality.

47.2 Nuisance-complete photon timing tomography

A mode-count timing test must separate propagation slope from encoder, detector, spatial, spectral, and pulse-shape delays. The declared model contains the target regressor

$$\gamma \frac{L}{c} \log M$$

alongside mode intercepts, encoder and detector swaps, measured transverse-momentum and spectral covariates, pulse width, intensity, detector walk, and drift. The frozen design has 48 randomized cells and 16 parameters with full normalized rank 16.

For the declared synthetic benchmark of 20 ps single-event jitter and 10^6 events per cell,

$$\sigma_\gamma \simeq 2.19 \times 10^{-9}.$$

Omitting the measured spatial and spectral covariates creates a false

$$\widehat{\gamma} \simeq 1.1243 \times 10^{-9},$$

whereas the complete noiseless model returns zero to numerical precision. This explicitly demonstrates why structured-mode group delay is not, by itself, evidence for a mode-dependent vacuum front velocity.

47.3 Three exact photon constructions

For the W33 Laplacian $L = 12I - A$,

$$\mathrm{Spec}(L) = 0^1, 10^{24}, 16^{15}.$$

A localized mode has $\langle L \rangle = 12$ and $\mathrm{Var}(L) = 12$, so its ideal pure-state quantum Fisher information is

$$F_Q = 48.$$

The optimal extremal-sector superposition has $F_Q = 256$.

For the complement $B = J - I - A$,

$$A + B : (39, -1, -1), \qquad A - B : (-15, 5, -7).$$

The sum arm is geometry-blind on the 39-dimensional nonuniform sector, while the difference arm resolves the two protected sectors. Its full ideal spectral-range QFI is 400, with protected nonuniform value 144.

Most importantly, half a W33 Laplacian period gives the exact global reflection

$$\boxed{U = e^{-i\pi L/2} = I - 2E_{10} = -\frac{1}{3}(I + A) + \frac{2}{15}J.}$$

Each row has amplitude $-1/5$ on the point and its 12 neighbors and amplitude $2/15$ on its 27 nonneighbors, and

$$U^2 = I.$$

Thus one engineered analog evolution can implement a global 40-mode operation in parallel; it need not be interpreted as forty sequential orthogonal updates inside one optical period.

For a genuine tensor carrier,

$$\mathrm{mult}(m, r) = \binom{m}{r} 13^{m-r} 27^r, \qquad \mathrm{amp}(m, r) = \left(-\frac{1}{5}\right)^{m-r} \left(\frac{2}{15}\right)^r.$$

The 40^m-entry tensor kernel therefore has only $m + 1$ amplitude-shell types. This is exact control-description compression, not Hilbert-space compression or a variable-c mechanism.

47.4 Monster and evidence firewall

A GAP/CTblLib class-fusion sieve and an `mmgroup` canonical-integer engine test have been materialized upstream of the strict Monster gate. The repository still lacks four explicit portable Monster words realizing the target $U_4(2)$ subgroup. Therefore the promoted status remains

`PENDING_EXPLICIT_MM_WORDS_AND_CLASS_FUSION_EXECUTION.`

No Monster embedding, laboratory photon result, hidden photon-node ontology, mode-dependent vacuum c, global circuit optimum, or unobserved remote CI/PDF result is claimed.

48 Passes 3989–3996: physical incidence photon processor

The W33 point graph admits an exact sparse physical lift. Let N be the 40×40 point–line incidence matrix of $W(3,3)$. Exact enumeration gives

$$NN^T = 4I + A_{W33}.$$

Hence a dense twelve-neighbour point Hamiltonian may be generated from an eighty-mode bipartite point–line device with 160 couplings, degree four, and girth eight. Its spectrum is

$$-4^1, -\sqrt{6}^{24}, 0^{30}, \sqrt{6}^{24}, 4^1.$$

With point–line coupling g and bus detuning Δ,

$$H_{\text{eff}} = -\frac{g^2}{\Delta}(A + 4I) + O(g^4/\Delta^3),$$

and $t = \pi\Delta/(2g^2)$ approaches the exact W33 half-period reflection on the point sector. This is an analytic architecture, not a fabricated device.

Let $B = J - I - A$ and $D = A - B$. Then $A + B = J - I$ is geometry-blind on the nonuniform sector, while

$$\operatorname{Spec}(D) = -15^1, 5^{24}, -7^{15}.$$

The spectral projectors are

$$E_{-15} = \frac{(D-5I)(D+7I)}{160} = \frac{J}{40}, \quad E_5 = \frac{(D+15I)(D+7I)}{240}, \quad E_{-7} = -\frac{(D+15I)(D-5I)}{96}.$$

Consequently $\langle D\rangle$ and $\langle D^2\rangle$ determine all three sector populations. If identical commuting error C enters both arms, then

$$e^{-it(A+C)}e^{+it(B+C)} = e^{-it(A-B)},$$

so the dual-geometry echo cancels it exactly.

The maximum-code census is also complete. The 945-vertex fixed-parent compatibility graph contains exactly 945 maximum 57-cliques, split into three parent-group orbits

$$\boxed{945 = 540 + 270 + 135}$$

with stabilizer orders

$$\boxed{96, 192, 384}.$$

Thus maximum-code uniqueness is false in the fixed-parent problem. This corrects the earlier division by an order-192 full coordinate stabilizer without first checking parent preservation.

The seven primitive central blocks of the literal 48-orbital algebra have simple degrees

$$1, 1, 2, 2, 2, 3, 5.$$

Their complete central coarse-graining lattice contains

$$B_7 = 877$$

partitions. Quotienting equal-degree relabelings by $S_2 \times S_3$ leaves exactly

$$\boxed{198}$$

inequivalent central types. These are exact central subalgebras, not automatically combinatorial fusions of the 48 orbital relations.

Three further photon constructions follow from the incidence lift. First, $\operatorname{rank} N = 25$, so the bipartite processor contains thirty exact dark modes. Second, for $L = 12I - A$,

$$V = e^{-i\pi L/4} = I - (1+i)E_{10}, \qquad V^2 = U, \qquad V^4 = I,$$

which gives an exact four-phase internal graph clock. Third, for a genuine m-fold tensor carrier,

$$\operatorname{rank}(N^{\otimes m}) = 25^m, \qquad \dim\ker(N^{\otimes m}) = 40^m - 25^m,$$

so the one-side dark fraction is

$$\boxed{1 - (5/8)^m}.$$

Only $m+1$ nonzero singular shells occur, with multiplicity $\binom{m}{r}24^r$ and squared singular value $16^{m-r}6^r$.

The Monster acquisition gate now composes $U_4(2) \to H \to \mathbb{M}$ class fusions through maximal-subgroup tables and searches only compatible published explicit `mmgroup` overgroups. The promoted status remains

$$\boxed{\texttt{PENDING_EXPLICIT_MONSTER_U42_WORDS}}$$

until four portable words pass the exact pair, triple, order-25,920, object-action, and class-fusion firewalls. No variable vacuum c, literal hidden photon nodes, fabricated hardware, laboratory result, or unobserved remote build is claimed.

Passes 3989–3996 supplement: direct W33 flight and causal memory

Exact forty-mode analog flight. Let A be the adjacency matrix of $W(3,3)$. A forty-mode equal-edge coupled-mode array obeying

$$i\frac{d\psi}{dz} = \kappa A\psi$$

implements, at $\kappa z = \pi/2$,

$$\boxed{e^{-i\pi A/2} = -\frac{I+A}{3} + \frac{2J}{15}.}$$

This is an exact symmetric involution with row amplitudes $-1/5$ on a point and its twelve neighbours and $2/15$ on its twenty-seven nonneighbours. For uniform fractional interaction error ϵ,

$$F_{\mathrm{pro}} = 1 - 3\pi^2\epsilon^2 + O(\epsilon^3), \qquad F_{\mathrm{avg}} = 1 - \frac{120}{41}\pi^2\epsilon^2 + O(\epsilon^3).$$

The linear average-fidelity term vanishes because $\operatorname{Tr} A = 0$.

Wigner–Smith time as operational memory. For a frequency-dependent W33 scattering unitary

$$S(\omega) = e^{i\theta(\omega)L_{W33}},$$

the Wigner–Smith operator is exactly

$$\boxed{Q(\omega) = -iS^\dagger\frac{dS}{d\omega} = \theta'(\omega)L_{W33}.}$$

Hence the proper-delay sectors are

$$0^1, \qquad (10\theta')^{24}, \qquad (16\theta')^{15},$$

with mean $12\theta'$, variance $12(\theta')^2$, and total trace $480\theta'$. This gives a measurable meaning to internal history: dwell-time and stored-energy sensitivity, not a changed vacuum causal speed.

For m independent W33 factors, the exact delay-shell polynomial is

$$\boxed{(1 + 24z^{10} + 15z^{16})^m.}$$

The address space has 40^m modes and

$$\langle\tau\rangle = 12m\theta', \qquad \mathrm{Var}(\tau) = 12m(\theta')^2.$$

Consequently

$$\boxed{\frac{\log_2(40^m)}{\langle\tau\rangle} = \frac{\log_2 40}{12\theta'}}$$

is independent of self-similar depth, while the relative delay width is $1/\sqrt{12m}$.

Causal-refinement boundary. A local-interaction causal cone has schematic physical velocity

$$v_{\mathrm{int}} \lesssim aC_{LR}(\Delta)J/\hbar.$$

Self-similar refinement preserves the cone only when aJ remains fixed. More serial nodes without stronger coupling slow the internal cone; node density alone neither determines nor raises vacuum c. Fabrication, measured Wigner–Smith delays, literal hidden photon nodes, variable vacuum c, and laboratory performance remain unclaimed.

49 Photon layout, delay tomography, orbital closure, and code stabilizers

The direct forty-mode W33 coupler and the eighty-mode point–line incidence lift both admit exact one-factorizations. Their resource vectors

$$(\mathrm{modes}, \mathrm{links}, \mathrm{degree}, \mathrm{layers})$$

are

$$(40, 240, 12, 12), \qquad (80, 160, 4, 4).$$

For linear cost $C = \alpha M + \beta E + \gamma R$,

$$C_{40} - C_{80} = -40\alpha + 80\beta + 8\gamma,$$

so the direct device wins exactly when

$$\boxed{5\alpha > 10\beta + \gamma}.$$

For $S(\omega) = e^{i\theta(\omega)L}$, the Wigner–Smith operator is $Q = \theta' L$. The three sector populations obey

$$p_{16} = \frac{m_2 - 10m_1}{96}, \qquad p_{10} = \frac{16m_1 - m_2}{60}, \qquad p_0 = 1 - p_{10} - p_{16}.$$

The executed central-difference reconstruction converges quadratically. Removing common delay gives the stronger identity

$$\boxed{Q - \frac{\operatorname{Tr} Q}{40} I = -\theta' A_{W33}},$$

so the complete W33 adjacency relation is recovered from the off-diagonal delay kernel.

The three fixed-parent maximum-code stabilizers are identified exactly:

$$G_{540} \cong S_4 \times V_4,$$

$$G_{270} \cong D_8 \rtimes_{\mathrm{sgn},\alpha} S_4, \qquad \alpha(r) = r^{-1}, \quad \alpha(s) = r^2 s,$$

and

$$\boxed{G_{135} \cong C_2 \wr S_4 = 2^4 : S_4 = W(B_4).}$$

The last group acts faithfully on eight coordinates preserving four opposite pairs, giving an exact four-bit hypercube/cross-polytope bridge.

For the oriented vertex–edge incidence matrix D,

$$\operatorname{Spec}(D^T D) = 0^{201} + 10^{24} + 16^{15},$$

and therefore

$$\boxed{e^{-i\pi D^T D/2} = I - 2E_{10}}.$$

The 201-dimensional kernel is raw cycle-space memory, not the 81-dimensional Hodge/CSS logical sector.

Finally, pure-state delay metrology satisfies $F_Q = 4 \operatorname{Var}(Q)$. Thus

$$F_Q^{\mathrm{vertex}} = 48(\theta')^2, \qquad F_Q^{\mathrm{opt}} = 256(\theta')^2.$$

The literal orbital Fourier/relation-fusion and Monster overgroup workflows are executable but their generated outputs remain pending. No fabricated device, measured delay, variable vacuum c, Monster embedding, remote CI/PDF success, or laboratory result is claimed.

50 Exact finite-detuning photon revival and coherent delay memory

Exact non-dispersive incidence revival. Let N be the 40×40 point–line incidence matrix of $W(3,3)$, so that $NN^{\mathsf{T}} = 4I + A$. For the full point–bus Hamiltonian

$$H = g \begin{pmatrix} 0 & N \\ N^{\mathsf{T}} & (\Delta/g) I \end{pmatrix},$$

the finite values

$$\boxed{\Delta/g = 2\sqrt{2}}, \qquad \boxed{gt = \pi/\sqrt{2}}$$

produce an exact zero-leakage revival. The half-angle windings of the singular-value-4, singular-value-$\sqrt{6}$, and bus-dark sectors are 3π, 2π, and π, respectively. Hence the point action is

$$\boxed{U_P = E_{16} - E_6 + E_0 = I - 2E_6 = -\frac{I + A}{3} + \frac{2J}{15}},$$

and the line action is $U_L = F_{16} - F_6 + F_0$. Direct exponentiation of the full eighty-mode matrix gives operator error below 6.6×10^{-15} and off-block leakage below 2.9×10^{-15}. This is not a dispersive approximation.

Quadratic-form Wigner–Smith tomography. For $\tau(v) = v^\dagger Q v$,

$$Q_{ii} = \tau(e_i),$$
$$\Re Q_{ij} = \tau\left(\frac{e_i + e_j}{\sqrt{2}}\right) - \frac{Q_{ii} + Q_{jj}}{2},$$
$$\Im Q_{ij} = \frac{Q_{ii} + Q_{jj}}{2} - \tau\left(\frac{e_i + i e_j}{\sqrt{2}}\right).$$

Thus a general Hermitian forty-mode delay matrix requires exactly $40^2 = 1600$ expectation probes, reduced to $40 + \binom{40}{2} = 820$ under reciprocal real symmetry. The exact synthetic reconstruction recovered all 240 W33 edges with maximum matrix error below 2.6×10^{-15}. For a three-frequency central difference and a linear phase law,

$$Q_h = \frac{\sin(h\theta' L)}{h} = Q - \frac{h^2}{6}(\theta')^3 L^3 + O(h^4),$$

and Richardson extrapolation removes the leading error. A separate precursor/front measurement remains mandatory before testing any mode-count-dependent causal-front slope.

Exact bright-sector write–hold–read gate. Define

$$T = N^{\mathsf{T}}\left(\frac{E_{16}}{4} + \frac{E_6}{\sqrt{6}}\right), \qquad X = \begin{pmatrix} 0 & T^{\mathsf{T}} \\ T & 0 \end{pmatrix}.$$

Then

$$T^{\mathsf{T}} T = E_{16} + E_6, \qquad T T^{\mathsf{T}} = F_{16} + F_6,$$

and

$$\boxed{W = e^{-i\pi X/2}}$$

swaps the twenty-five-dimensional point-bright sector into the line-bright sector while fixing both fifteen-dimensional dark sectors. A diagonal bus hold phase followed by $W^\dagger$ returns

$$\boxed{e^{-i\phi_0} E_0 + e^{-i\phi_6} E_6 + e^{-i\phi_{16}} E_{16}}$$

on the point modes. An arbitrary three-phase test had operator error below 2.7×10^{-15} and leakage below 3.1×10^{-15}. This is an exact controlled-Hamiltonian synthesis, not a fabricated-memory claim.

Three further photon constructions. Exact zero-leakage reflection revivals satisfy the integer quadric

$$\boxed{3n_{16}^2 - 8n_6^2 + 5k^2 = 0},$$

with $n_{16} + k$ even and $n_6 + k$ odd. The parameter map is

$$\frac{\Delta}{g} = k\sqrt{\frac{24}{n_6^2 - k^2}}, \qquad gt = 2\pi\sqrt{\frac{n_6^2 - k^2}{24}}.$$

The shortest positive primitive solution is $(n_{16}, n_6, k) = (3, 2, 1)$, which yields the revival above.

Writing $\tau = \operatorname{Tr} Q/480$, an ideal W33 delay matrix obeys the basis-free checksum

$$\boxed{Q(Q-10\tau I)(Q-16\tau I)=0},$$

and the geometry is recovered self-calibratingly by

$$\boxed{A=-\frac{Q-(\operatorname{Tr} Q/40)I}{\tau}}.$$

For m commuting physical copies, all factors revive at the same gate time $gt=\pi/\sqrt{2}$. The point action is $U_P^{\otimes m}$, with

$$\boxed{m_+=\frac{40^m+(-8)^m}{2},\qquad m_-=\frac{40^m-(-8)^m}{2}}.$$

This is a synchronization theorem, not a hardware-compression theorem.

Algebra and evidence boundary. The literal 48-relation Fourier/fusion calculation and the GAP/mmgroup Monster maximal-overgroup search are exposed through an artifact-producing execution workflow. No relation-fusion rank, Monster words, or embedding is promoted until the generated artifacts are inspected. Fabricated hardware, measured delay matrices, literal hidden photon nodes, variable vacuum light speed, remote CI, and PDF evidence likewise remain unclaimed.

51 Physical incidence-link H_1 memory and exact projector gates

The lower-degree point–line incidence architecture has 80 modes and 160 physical couplers. Let $D\in\{-1,0,1\}^{80\times160}$ be its oriented vertex–edge boundary matrix and put $K=D^TD$. The exact spectrum is

$$0^{81},\quad 8^{1},\quad 4^{30},\quad (4-\sqrt{6})^{24},\quad (4+\sqrt{6})^{24}.$$

Therefore

$$\boxed{320P_{H_1}=(K-8I)(K-4I)\big((K-4I)^2-6I\big)}$$

is an exact integral numerator for the rank-81 Hodge/Kirchhoff cycle projector. Indeed $DP_{H_1}=0$, $\operatorname{rank} D=79$, and $\operatorname{rank} P_{H_1}=81$, so its image is exactly the boundaryless link-current space. Every physical coupler has diagonal projector weight $81/160$.

The corresponding exact memory reflection is

$$\boxed{R_{H_1}=I-2P_{H_1}},\qquad \operatorname{Tr} R_{H_1}=79-81=-2.$$

It is $+1$ on the cut space and -1 on the protected cycle-memory space.

A separate polynomial dynamics exists on the 80 mode coordinates. The raw Levi adjacency has spectrum

$$-4^{1},\ (-\sqrt{6})^{24},\ 0^{30},\ (+\sqrt{6})^{24},\ 4^{1}$$

and is not globally periodic. Its sign fold $H_2=A_L^2$ has spectrum $0^{30}+6^{48}+16^2$, giving

$$e^{-i\pi H_2}=I,\qquad e^{-i\pi H_2/2}=I-2E_6,\qquad e^{-i\pi H_2/4}=I+(i-1)E_6.$$

This polynomial revival is distinct from the finite-detuning block Hamiltonian of Pass 4005, although both use the same incidence matrix.

The five signed Levi sectors are recovered from four moments. With $a = p_{+4} + p_{-4}$, $b = p_{+\sqrt{6}} + p_{-\sqrt{6}}$, $d = p_{+4} - p_{-4}$, and $e = p_{+\sqrt{6}} - p_{-\sqrt{6}}$,

$$a = \frac{m_4 - 6m_2}{160}, \qquad b = \frac{16m_2 - m_4}{60},$$

$$d = \frac{m_3 - 6m_1}{40}, \qquad e = \frac{16m_1 - m_3}{10\sqrt{6}}.$$

Finally, in the ideal delay model $Q = \tau I + \theta' A_L$,

$$\boxed{Q - \frac{\operatorname{Tr} Q}{80} I = \theta' A_L},$$

so the centered delay kernel recovers all 160 point–line incidences.

The mode decomposition $30 + 48 + 2$ and the link-current decomposition $79 + 81$ are distinct vector spaces. No fabricated coupler network, measured delay, loss tolerance, variable vacuum c, literal hidden photon nodes, Monster embedding, or laboratory performance is claimed.

52 The protected H_1 sector as an exact photonic flat band

BT548 already identified the protected Levi cycle projector with the -2 eigenspace of the Levi line graph. The new step is the explicit coupler-as-site physical model and its apartment-frame and perturbation refinement.

Promote the 160 incidence links of the 80-vertex Levi graph L to the sites of

$$X = \operatorname{LineGraph}(L).$$

Then X has 160 sites, 480 links, and degree 6. For the oriented Levi boundary matrix D,

$$\boxed{A_X = D^T D - 2I.}$$

Hence

$$\boxed{\ker D = E_{-2}(A_X)},$$

and the protected $H_1 = 81$ sector is exactly the -2 flat band of X. Its spectrum is

$$6^1 + (2 + \sqrt{6})^{24} + 2^{30} + (2 - \sqrt{6})^{24} + (-2)^{81}.$$

Let $C \in \{-1, 0, 1\}^{160 \times 1620}$ have one signed alternating column for each Levi octagon. Every such apartment column c has support 8 and satisfies

$$A_X c = -2c.$$

The 1620 compact apartment states span the full flat band, and

$$P_{H_1} = \frac{1}{160} CC^T,$$

$$CC^T = \frac{1}{2}(A_X - 6I)(A_X - 2I)(A_X^2 - 4A_X - 2I).$$

After normalizing each column by $\sqrt{8}$, they form a unit-norm tight frame:

$$\boxed{\left(\frac{C}{\sqrt{8}}\right)\left(\frac{C}{\sqrt{8}}\right)^{T} = 20P_{H_1}}, \qquad \frac{1620}{81} = 20.$$

Each secondary site belongs to exactly 81 apartments,

$$\boxed{160 \cdot 81 = 1620 \cdot 8 = 12960.}$$

The perturbation boundary is exact. A uniform onsite shift δI moves the band without splitting it, whereas

$$P_{H_1}|e\rangle\langle e|P_{H_1}$$

has rank one and nonzero eigenvalue $81/160$. More generally,

$$\mathrm{Tr}(P_{H_1}\,\mathrm{diag}\,v) = \frac{81}{160}\sum_{e} v_e.$$

Thus the symmetric model has an exact flat band, but generic nonuniform onsite or coupling disorder is not proved harmless.

This 160-site line-graph Hamiltonian, the primary 80-mode incidence Hamiltonian, and the passive 160-dimensional link-current coordinates are related but distinct physical models. No fabricated secondary lattice, measured localization, disorder tolerance, local coupling synthesis, variable vacuum c, hidden-node ontology, or laboratory performance is claimed.

53 Physics-first audit of the W33 universal-computer hypothesis

Exact revival error tensor. For $d = \Delta/g$, $\tau = gt$, and the target $d_0 = 2\sqrt{2}$, $\tau_0 = \pi/\sqrt{2}$, write $\delta d = d - d_0$ and $\delta\tau = \tau - \tau_0$. The coherent target overlap and average point–bus leakage obey

$$1 - F_e = \frac{1}{2}\left[\frac{323\pi^2}{5184}(\delta d)^2 + 2\frac{17\pi}{36}\delta d\,\delta\tau + 8(\delta\tau)^2\right] + O(\delta^3),$$

$$P_{\mathrm{leak}} = \frac{1}{2}\left[\frac{149\pi^2}{5184}(\delta d)^2 + 2\frac{17\pi}{36}\delta d\,\delta\tau + 8(\delta\tau)^2\right] + O(\delta^3).$$

The locally optimal retiming law is

$$\boxed{\delta\tau = -\frac{17\pi}{288}\delta d},$$

for which

$$1 - F_e = \frac{119\pi^2}{6912}(\delta d)^2 + O(\delta^3), \qquad P_{\mathrm{leak}} = \frac{\pi^2}{2304}(\delta d)^2 + O(\delta^3).$$

Cubic physical compiler. Let

$$H_L = \begin{pmatrix} 0 & N \\ N^{\mathsf{T}} & 0 \end{pmatrix}.$$

The polar bright-sector operator is the exact cubic transform

$$\boxed{\mathrm{sign}(H_L) = \alpha H_L + \beta H_L^3},$$

with

$$\alpha = -\frac{3}{20} + \frac{4\sqrt{6}}{15}, \qquad \beta = \frac{1}{40} - \frac{\sqrt{6}}{60}.$$

Hence its point–line block is

$$\boxed{T = N^{\mathsf{T}}(\alpha I + \beta N N^{\mathsf{T}})}.$$

The dense polar coupling is therefore an exact sparse incidence traversal plus a three-hop spectral correction. A passive finite-depth hardware synthesis remains open.

Protected-memory accessibility theorem. For the oriented Levi boundary D,

$$\mathbb{R}^{160} = \operatorname{im} D^{\mathsf{T}} \oplus \ker D, \qquad \dim \operatorname{im} D^{\mathsf{T}} = 79, \quad \dim \ker D = 81.$$

The algebra generated by $D, D^{\mathsf{T}}, DD^{\mathsf{T}}$ and $D^{\mathsf{T}}D$ preserves this decomposition. Thus incidence-only linear dynamics cannot write cut/mode information into the protected H_1 memory. For one controlled link detuning,

$$V_e = P_{H_1}|e\rangle\langle e|P_{\mathrm{cut}}$$

has rank one and

$$\boxed{\sigma(V_e) = \frac{\sqrt{81 \cdot 79}}{160}}.$$

A uniform pulse has zero cross-sector matrix element. Controlled local symmetry breaking is therefore the physical write/read port rather than merely an imperfection.

Common-delay-invariant geometry tomography. For

$$Q = cI + \theta(12I - A_{W33}) + E,$$

define

$$C = Q - \frac{\operatorname{Tr} Q}{40} I.$$

Then $C = -\theta A_{W33} + E_c$, and the ideal scale and adjacency are

$$\boxed{\widehat{\theta} = \frac{\|C\|_F}{\sqrt{480}}}, \qquad \boxed{\widehat{A} = -\frac{C}{\widehat{\theta}}}.$$

The scalar common delay cancels exactly. The centered checksum is

$$\boxed{(C + 12\theta I)(C + 2\theta I)(C - 4\theta I) = 0}.$$

If $\|E_c\|_{\max} < \theta/4$ and $\|E_c\|_F/\sqrt{480} < \theta/4$, thresholding at $\widehat{\theta}/2$ recovers every labeled edge exactly. If $\|E_c\|_2 < 3\theta$, all three spectral clusters remain disjoint.

Causality and speed boundary. The diameters of the W33 graph, Levi graph, and Levi line graph are $2, 4, 4$. A fixed cell therefore supplies microscopic graph locality but not a macroscopic light cone. Any Lieb–Robinson-type physical speed has the form

$$v_{\mathrm{LR}} \lesssim C_{\mathrm{graph}} \frac{aJ}{\hbar},$$

so node count alone cannot determine the vacuum speed of light. For the exact finite-detuning gate,

$$t_{\mathrm{gate}} = \frac{\pi}{\sqrt{2}g},$$

while a localized point state has $\Delta E = 2\hbar g$ and $E - E_0 = 2\sqrt{2}\hbar g$. The gate is $2\sqrt{2}$ times the orthogonal Mandelstam–Tamm time and four times the Margolus–Levitin time.

Spectral-dimension falsifier. The W33 heat trace is

$$Z(t) = 1 + 24e^{-10t} + 15e^{-16t}.$$

Its running spectral dimension has maximum approximately 3.71848244 and returns to zero in both ultraviolet and infrared limits. The Levi line-graph maximum is approximately 3.47298414. Thus neither fixed finite graph has a four-dimensional Weyl plateau. A spacetime claim requires a refinement or RG family with $Z(t) \sim t^{-2}$ over a stable scale window and Lorentzian causal observables.

Thermodynamic and holographic capacity. The H_1 flat band has dimension 81. Its 1620 apartment states form an overcomplete tight frame of redundancy 20, not 1620 orthogonal messages. A single photon restricted to this sector has orthogonal capacity at most

$$\boxed{\log_2 81 \simeq 6.33985000 \text{ bits}},$$

and erasure obeys

$$\boxed{Q_{\mathrm{erase}} \geq k_B T \ln 81}.$$

A Bekenstein or covariant-entropy comparison remains undefined until physical energy, size or area, species content, and encoder/decoder restrictions are fixed.

Claim boundary. The finite architecture now has exact protected memory, controlled spectral unitaries, entangling protocols, error tensors, write ports, and tomography. It does not yet have a proved fault-tolerant non-Clifford injection, scalable local continuum, Standard Model representation functor, gravitational entropy–energy dictionary, dimensional scale derivation, fabricated device, or laboratory performance. "THE universal computer" and "the theory of everything" therefore remain explicit hypotheses with pass/fail obligations, not promoted conclusions.

53.1 Full harmonic compiler, projected controls, and finite-network electrodynamics (Passes 4033–4040)

The completed physics-first audit is supplemented by a deterministic construction on the same W33 point–line Levi graph. Let

$$D \in \{-1, 0, 1\}^{80\times 160}, \qquad C \in \{-1, 0, 1\}^{160\times 1620}, \qquad P_{H_1} = \frac{1}{160} CC^T,$$

with $\operatorname{rank} D = 79$, $\operatorname{rank} C = 81$, and $DC = 0$.

Exact write/read compiler. The first 81 canonically ordered apartment columns form an integer basis B of H_1. With

$$W = B(B^T B)^{-1/2},$$

one has

$$W^T W = I_{81}, \qquad W W^T = P_{H_1}.$$

Hence

$$H_{\mathrm{swap}} = \begin{pmatrix} 0 & W^T \\ W & 0 \end{pmatrix}$$

performs a complete input–H_1 swap at time $\pi/2$, up to phase. The dimension mismatch is physical: all 81 harmonic channels require the 80 incidence modes plus one ancilla.

Projected disorder and control. The 160 projected onsite operators

$$A_e = P_{H_1} |e\rangle\langle e| P_{H_1}$$

are linearly independent. The 480 nearest-neighbour projected couplings span 320 dimensions, and the onsite span lies inside that coupling span through

$$A_e = -\frac{1}{4} \sum_{f \sim e} P_{H_1} \big(|e\rangle\langle f| + |f\rangle\langle e| \big) P_{H_1}.$$

All projected site rays are pairwise nonorthogonal, so their commutant on H_1 is scalar. Their associative closure is $M_{81}(\mathbb{C})$; with the uniform identity control the ideal Hamiltonian Lie closure is $\mathfrak{u}(81)$. Thus uncalibrated local detuning is a splitting mechanism, whereas calibrated detuning is a universal control alphabet.

Compressed tomography and fabrication contract. The three-sector H_2 populations require two nontrivial scalar probes. Each five-sector signed-Levi or line-graph population vector requires four. Affinely scaled Chebyshev probes have condition number below two in all three cases. The secondary flat-band realization requires 160 sites, 480 degree-six couplings, and only uniform real hopping. Its exact flat-band gap is

$$\Delta_{\mathrm{fb}} = (4 - \sqrt{6})J.$$

A sufficient static cluster-separation condition is $\|V\|_2 < \Delta_{\mathrm{fb}}/2$. This is a design theorem, not a fabrication claim.

Three physics constructions. First, the Lindblad jump map

$$L_v = \sum_e D_{ve} a_e$$

has dark space $\ker D = H_1$ and dissipative gap $4 - \sqrt{6}$. Second, the local projected controls generate $\mathfrak{u}(81)$ in the ideal protected model. Third, interpreting $\rho = DE$ as a discrete Gauss law gives an exact Levi effective-resistance law

$$R_1 = \frac{79}{160}, \qquad R_2 = \frac{13}{20}, \qquad R_3 = \frac{111}{160}, \qquad R_4 = \frac{7}{10}.$$

This is finite-network electrodynamics, not a continuum Maxwell or gravity derivation.

Execution boundary. The literal 48-relation fusion and Monster jobs still have no generated engine outputs. No relation-fusion rank, Monster word, class fusion, or embedding is promoted. The exact certificate is `data/PART_4033_4040_PHYSICS_CONTINUATION.json`.

54 Eight-physics expansion: holonomies, interacting flat-band matter, cooling, spectroscopy, refinement, and three outside-box constructions

Passes 4041–4048 extend the exact W33/Levi H_1 architecture along five requested physics fronts and three independent finite-model constructions. All claims below are finite-dimensional and machine checked; none is a fabricated-device, continuum-gravity, Standard-Model, or laboratory-performance claim.

54.1 Non-Abelian holonomic control in the harmonic memory

Choose an orthonormal logical pair in the 81-dimensional harmonic space, a third harmonic helper, and one excited ancilla. The ideal tripod spectrum is $\{-\Omega, 0, 0, +\Omega\}$ and the dark space has rank two. In a real tripod chart,

$$A_\phi = \cos\theta \begin{pmatrix} 0 & -1 \\ 1 & 0 \end{pmatrix}, \qquad A_\theta = 0.$$

The closed loop through $\theta = \arccos(1/4)$ yields

$$U_X = \begin{pmatrix} 0 & 1 \\ -1 & 0 \end{pmatrix},$$

while a phase loop at $\theta = \pi/6$ yields $U_Z = \mathrm{diag}(-i, 1)$. Their commutator obeys

$$\|[U_X, U_Z]\|_F^2 = 4,$$

so the exact geometric gates are non-Abelian. Varying the loop latitudes gives continuous rotations about two nonparallel axes and therefore ideal $SU(2)$ control. This does not certify finite-speed adiabatic fidelity or a laboratory pulse sequence.

54.2 Projected two-photon contact spectrum

For onsite interaction projected into the flat band,

$$V = U \sum_{e=1}^{160} |Pe, Pe\rangle\langle Pe, Pe|,$$

we have $\dim \mathrm{Sym}^2(H_1) = 3321$. The contact map has rank 160, leaving an exact contact-dark pair space of dimension

$$\boxed{3161}.$$

The complete nonzero spectrum of V/U is

$$\left(\frac{81}{160}\right)^1, \left(\frac{252+27\sqrt{6}}{800}\right)^{24}, \left(\frac{117}{400}\right)^{30}, \left(\frac{252-27\sqrt{6}}{800}\right)^{24}, \left(\frac{41}{200}\right)^{81}.$$

No bound-pair transport or many-body phase follows without additional dynamics.

54.3 Number-conserving one-shot Hodge cooling

On the charge-zero vertex sector let

$$Q = D^T (DD^T)^{-1/2}.$$

Then $Q^T Q = I_{79}$ and $QQ^T = P_{\mathrm{cut}}$. Coupling 160 system links to 79 reservoir modes through

$$H_{\mathrm{cool}} = g \begin{pmatrix} 0 & Q \\ Q^T & 0 \end{pmatrix}$$

produces at $t = \pi/(2g)$ the exact passive swap

$$|\psi\rangle_{\mathrm{sys}} |0\rangle_{\mathrm{res}} \longmapsto P_{H_1} |\psi\rangle_{\mathrm{sys}} - iQ^T |\psi\rangle_{\mathrm{res}}.$$

Thus all cut-space excitation leaves the system while the harmonic memory remains. The polar coupler is generally dense, and reservoir reset and finite-depth synthesis remain engineering obligations.

54.4 Synthetic Coulomb spectroscopy

For opposite drive at Levi vertices separated by distance d, define $s = (i\omega C + \gamma)/J$. The shell responses are

$$Z_1(s) = \frac{2(s^3 + 15s^2 + 66s + 79)}{(s+4)(s+8)(s^2 + 8s + 10)},$$

$$Z_2(s) = \frac{2(s^2 + 8s + 13)}{(s+4)(s^2 + 8s + 10)},$$

$$Z_3(s) = \frac{2(s^3 + 16s^2 + 78s + 111)}{(s+4)(s+8)(s^2 + 8s + 10)},$$

$$Z_4(s) = \frac{2(s^2 + 8s + 14)}{(s+4)(s^2 + 8s + 10)}.$$

Their DC limits are

$$\boxed{79/160,\ 13/20,\ 111/160,\ 7/10}.$$

The minimum shell gap is $1/160$, so absolute error below $1/320$ in units of $1/J$ is sufficient for nearest-shell identification.

54.5 Causal refinement tower and dimensional boundary

For a periodic d-dimensional array of cells,

$$\lambda(k) = 2\kappa \sum_{\mu=1}^{d} (1 - \cos k_\mu) = \kappa |k|^2 + O(k^4),$$

and the wave equation gives

$$\omega(k) = \sqrt{\kappa}|k| + O(k^3), \qquad c_{\mathrm{cell}} = a\sqrt{\kappa}.$$

At $N = 64$ and $\kappa/J = 0.05$, the one-dimensional tower has a stable $d_s \simeq 1$ heat-kernel window, while a four-dimensional torus has a stable $d_s \simeq 4$ window. The conclusion is a boundary rather than an emergence claim: four macroscopic dimensions occur only when four external lattice directions are explicitly supplied.

54.6 Three outside-box exact constructions

First, the discrete supercharge

$$\mathcal{Q} = \begin{pmatrix} 0 & D \\ D^T & 0 \end{pmatrix}$$

has 82 zero modes, one uniform vertex mode and 81 harmonic edge modes. With vertex-positive and edge-negative grading, the Witten index is

$$\boxed{1 - 81 = -80}.$$

Every nonzero eigenvalue occurs in an exact $\pm$ pair. This is incidence-complex supersymmetry, not particle-physics supersymmetry.

Second, one local site reflection composed with the Hodge reflection,

$$U_F = (I - 2|e\rangle\langle e|)(I - 2P_{H_1}),$$

has spectrum $(+1)^{78} + (-1)^{80} + e^{\pm i\phi}$ with

$$\boxed{\cos\phi = 1/80}.$$

Niven's theorem excludes rational ϕ/π, so the Floquet rotor has infinite order. This is not a many-body time crystal.

Third, the normalized protected site states satisfy

$$\langle u_e|u_f\rangle = -1/3,\ 1/9,\ -1/27,\ 1/81$$

for line-graph distances $1, 2, 3, 4$. Under the two-defect Hamiltonian

$$H_{ef} = P|e\rangle\langle e|P + P|f\rangle\langle f|P,$$

unit-fidelity transfer occurs at

$$\boxed{t/\pi = 80/27,\ 80/9,\ 80/3,\ 80}.$$

This is perfect transfer between nonorthogonal projected modes in an ideal protected model, not superluminal signaling or a spacetime wormhole.

Evidence firewall. The frozen semantic certificate is `08414977d5198aa43ea25127bbe7fa0e6529f56471dabe974`
The exact verifier and focused regression are `analysis/w33_pass4041_4048_eight_physics_expansion.py` and `tests/test_w33_pass4041_4048_eight_physics_expansion.py`.

55 Minimal spectral compiler, protected pulse alphabet, scaling family, and magic reduction

Minimal bounded QSVT compiler. With $X = H_L/4$, the relevant spectrum is

$$\{-1, -\sqrt{6}/4, 0, \sqrt{6}/4, 1\}.$$

The unique exact odd cubic sign interpolant exceeds one on $[-1,1]$, reaching approximately 1.09215935, and is therefore not directly QSVT-admissible. The minimal bounded odd polynomial is the quintic

$$p_5(x) = \left(\frac{9}{25} + \frac{24\sqrt{6}}{25}\right)x + \left(-\frac{48}{25} - \frac{152\sqrt{6}}{225}\right)x^3 + \left(\frac{64}{25} - \frac{64\sqrt{6}}{225}\right)x^5.$$

It has the exact certificate

$$1 - p_5(x)^2 = \frac{4096(29-6\sqrt{6})}{16875}(1-x^2)\left(x^2 - \frac{3}{8}\right)^2 q_+(x)q_-(x),$$

where

$$q_\pm(x) = x^2 \pm \left(1 + \frac{\sqrt{6}}{2}\right)x + \frac{9+\sqrt{6}}{8} > 0.$$

Thus $|p_5(x)| \le 1$ on $[-1,1]$, and the exact polar sign transform admits a degree-five, six-phase QSVT realization once a block encoding of $H_L/4$ is provided. Degree five is minimal because the unique degree-three interpolant violates boundedness.

Protected local phase pulses. For $P = P_{H_1}$ and

$$|u_e\rangle = \sqrt{160/81}\, P|e\rangle,$$

the normalized off-diagonal overlap alphabet is

$$-\frac{1}{3}, \quad \frac{1}{9}, \quad -\frac{1}{27}, \quad \frac{1}{81},$$

with respective per-site multiplicities $6, 18, 54, 81$. A calibrated local detuning produces

$$A_e = P|e\rangle\langle e|P = \frac{81}{160}|u_e\rangle\langle u_e|.$$

Holding amplitude δ_e for

$$t_\phi = \frac{160\phi}{81\delta_e}$$

implements

$$U_e(\phi) = I + (e^{-i\phi} - 1)|u_e\rangle\langle u_e|.$$

At $\phi = \pi$ this is a Householder reflection. Two-reflection rotations have angle alphabet

$$2\arccos(1/3), \quad 2\arccos(1/9), \quad 2\arccos(1/27), \quad 2\arccos(1/81).$$

Together with the Pass 4034 Lie-closure theorem, these are exact pulse-level generators of $\mathfrak{u}(81)$ on the protected memory.

A local four-dimensional W33-fiber family. Define

$$G_n = W33 \square C_n \square C_n \square C_n \square C_n.$$

Then $|V(G_n)| = 40n^4$ and $\deg G_n = 20$. For physical side length L and internal scale M, use

$$\mathcal{L}_n = M^2 L_{W33} \otimes I + I \otimes \left(\frac{n}{L}\right)^2 \sum_{\mu=1}^{4} L_{C_n}^{(\mu)}.$$

The heat trace factors into the W33 internal trace and four identical discrete circle traces. In the window

$$M^{-2} \ll t \ll L^2, \qquad (L/n)^2 \ll t,$$

the internal excitations freeze while the rescaled discrete torus converges to a real four-torus, giving $d_s \to 4$. This is a controlled four-dimensional base with W33 internal fiber; it does not derive dimension four from W33.

Exact one-copy M36 magic reduction. For

$$|m\rangle = (0, 1, -1, 1)/\sqrt{3},$$

measure the first qubit in the X basis and retain the plus result. With probability $5/6$, the remaining qubit is

$$(-|0\rangle + 2|1\rangle)/\sqrt{5}.$$

After the Clifford $R_x(\pi/2)$ this becomes

$$|A_\phi\rangle = (|0\rangle + e^{i\phi}|1\rangle)/\sqrt{2}, \qquad e^{i\phi} = (-4 + 3i)/5.$$

Since $\cos\phi = -4/5$, the rational-cosine theorem implies $\phi/\pi \notin \mathbb{Q}$. A CNOT from data to this resource followed by a computational-basis resource measurement applies $\mathrm{diag}(1, e^{i\phi})$ on one outcome and its inverse on the other. Postselecting the desired outcome succeeds with total probability

$$\boxed{5/12}.$$

The irrational z-rotation, Clifford conjugates, and an entangling Clifford gate give ideal postselected universal quantum computation. Deterministic correction, logical encoding, distillation, and a fault-tolerance threshold remain open.

Finite-to-observable quadratic functor. On

$$\mathcal{H}_n = \ell^2((C_n)^4) \otimes \mathbb{C}^{40},$$

define

$$K_n = \left(\frac{n}{L}\right)^2 L_{(C_n)^4} \otimes I + I \otimes [m_0^2 I + g(12I - A_{W33})].$$

Full W33 automorphism invariance restricts the internal quadratic algebra to $\mathrm{span}\{I, A, J\}$. The resulting free species have squared masses

$$m_0^2, \qquad m_0^2 + 10g, \qquad m_0^2 + 16g$$

with multiplicities $1, 24, 15$. This is an explicit free-field observable dictionary and selection rule, not a Standard Model construction.

Outside-box shell splitter. For a localized point state, the exact reflection gives amplitude $-1/5$ on the closed neighbourhood of size 13 and $2/15$ on the far shell of size 27:

$$U|v\rangle = -\frac{\sqrt{13}}{5}|N_v\rangle + \frac{2\sqrt{3}}{5}|F_v\rangle.$$

The shell probabilities are $13/25$ and $12/25$, yielding $H_2(13/25) \simeq 0.998845536$ bits of single-photon mode-partition entanglement. Since $U^2 = I$, the shell split recombines exactly.

Outside-box apartment projective code. The 1620 normalized apartment states in dimension 81 have absolute inner products

$$0, \quad 1/8, \quad 1/4, \quad 3/8, \quad 1/2, \quad 1.$$

Their fourth-power frame potential is

$$F_2 = 79785/16,$$

whereas a real projective 2-design would have $97200/83$. The exact defect ratio is $16351/3840$. Thus the apartment frame is a five-angle tight projective code but not a projective 2-design; tightness does not imply Haar isotropy or maximal scrambling.

Outside-box spectral calorimeter. The finite W33 spectrum $0^1 + 10^{24} + 16^{15}$ has partition function

$$Z(\beta) = 1 + 24e^{-10\beta} + 15e^{-16\beta}.$$

Its Schottky heat-capacity peak occurs at

$$\beta_* \simeq 0.4127094288, \qquad k_B T_*/J \simeq 2.4225277564,$$

with

$$C_{\max}/k_B \simeq 3.8006256108.$$

This is an exact single-particle spectral fingerprint, not a measured or interacting thermodynamic response.

Boundary. The results establish an exact minimal bounded spectral compiler, pulse-level protected controls, a convergent W33-fibered four-dimensional family, ideal postselected non-Clifford universality, and a free quadratic observable functor. They do not establish a fabricated block encoding, extracted phase list, deterministic fault-tolerant injection, Lorentzian spacetime, Standard Model, gravity, measured calorimetry, or a theory of everything.

55.1 Transitionless holonomies, dark-pair characters, local Hodge cooling, and finite-graph physics

Passes 4057–4064 close five physics targets and three independent outside-box probes on the exact Levi–H_1 substrate. All statements in this subsection are finite graph, representation-theoretic, spectral, lattice, Floquet, or canonical-ensemble statements; none is evidence for fabricated hardware, measured gate fidelity, a chiral Standard Model, quantized pumping, gravity, cosmology, or a theory of everything.

For the two non-Abelian tripod loops, the Kato counterdiabatic term

$$H_{\mathrm{CD}} = i[\dot{P}_D, P_D]$$

produces exact finite-time parallel transport in the ideal dark bundle. Their Fubini–Study actions are

$$L_X = 2\arccos(1/4) + \frac{\pi\sqrt{15}}{2} = 8.719900157\ldots, \qquad L_Z = \frac{\pi}{3} + \frac{\pi\sqrt{3}}{2} = 3.767896598\ldots.$$

Thus a constant-speed duration T requires peak counterdiabatic norm L/T, while uniform loss gives no-jump survival $e^{-\kappa T}$.

The 3161-dimensional two-boson contact-dark module was decomposed by generating $PSp(4,3)$ as a 25,920-element permutation group, reconstructing its twenty conjugacy classes and class algebra, and diagonalizing the center. Grouped by equal ordinary-character degree, its multiplicities are

d	1	5	6	10	15	20	24	30	40	45	60	64	81
m	0	$(1,1)$	2	$(1,1)$	$(1,3)$	5	2	$(3,6,6)$	$(4,4)$	$(4,4)$	9	8	9.

The weighted dimension is exactly 3161, and there is no trivial constituent. The bright rank-160 contact sector is an equivariant incidence-edge permutation module, so

$$P_{\mathrm{dark}} V_{\mathrm{contact}} P_{\mathrm{dark}} = 0;$$

contact-only first-order pair motion inside the dark sector is forbidden.

Because the nonzero Levi Laplacian spectrum is $\{4-\sqrt{6}, 4, 4+\sqrt{6}, 8\}$, the inverse square root is represented exactly on the physical spectrum by a cubic Lagrange polynomial p_3. Consequently

$$Q = D^T p_3(DD^T), \qquad Q^T Q = I - J/80, \qquad QQ^T = P_{\mathrm{cut}}.$$

The polar cooler can therefore be compiled from three nearest-neighbour Levi-Laplacian queries and one incidence query, together with the bounded degree-five sign compiler of Pass 4049. The collapsed matrix remains dense; this is exact circuit/query locality, not a one-layer sparse Hamiltonian.

On the explicit four-dimensional refinement tower, the gauge-covariant Wilson–Dirac operator

$$H(k) = \sum_{\mu=1}^{4} \gamma_\mu \sin k_\mu + \gamma_5 \left[m + r \sum_{\mu} (1 - \cos k_\mu) \right]$$

is nearest-neighbour and may be tensored with I_{81} on the harmonic fiber. At $m = 0$, the naive operator has sixteen corner zeros, whereas $r = 1$ leaves only the origin and gives the other corners Wilson masses $2, 4, 6, 8$. The price is explicit breaking of exact lattice chirality; the construction is vectorlike and does not evade the Nielsen–Ninomiya boundary.

Feeding the irrational Floquet phase $\cos\phi = 1/80$ into a static Coulomb port yields $V_n = Z_d(s) I_n$. The static linear network preserves the input quasifrequencies and

$$\frac{1}{N} \sum_{n<N} e^{in\phi} \longrightarrow 0, \qquad \left| \sum_{n=0}^{N-1} e^{in\phi} \right| \le \frac{2}{|1 - e^{i\phi}|}.$$

Hence there is no DC pump and no integer topological transport from one irrational phase alone; a second independently cycled parameter and a maintained gap are required.

Three outside-box consequences are exact. First, two projected Householder reflections convert graph distance into quasienergy through

$$|\langle u_e, u_f\rangle| = 3^{-d}, \qquad \theta_d = 2\arccos(3^{-d}),$$

giving four infinite-order distance clocks. Second, the repulsive two-boson contact model has residual entropy $k_B \log 3161$ and infinite-temperature dark probability $3161/3321$. Third, the Levi graph has edge connectivity four, so any $r \le 3$ missing couplers leave

$$\dim H_1 = 81 - r, \qquad \mathcal{I}_W = -80 + r,$$

providing a topological fault odometer up to the four-edge connectivity threshold.

The executable certificate is `data/PART_4057_4064_ADVANCED_PHYSICS.json`, with semantic SHA-256 `131ba5f89474a0283eedd0ae1ec5e5e6618b6d3e2bd6eeb8654fd4df8abbcd72`.

56 Explicit QSP, adaptive irrational magic, Lorentzian Dirac dynamics, and exact physical obstructions

Six-phase QSP compiler. In the W_x convention

$$W(x) = \begin{pmatrix} x & i\sqrt{1-x^2} \\ i\sqrt{1-x^2} & x \end{pmatrix}, \quad U_{\boldsymbol{\phi}}(x) = e^{i\phi_0 Z} \prod_{j=1}^{5} [W(x) e^{i\phi_j Z}],$$

the bounded quintic sign compiler is realized by

$$\boldsymbol{\phi} = (-2.8067951015434964, -2.042810210594929, -2.419664116537273, 2.419664116537273, -1.098782442994863$$

On a 20,001-point grid the top-left polynomial residual is below 1.19×10^{-15}. The sequence uses five signal queries and six phase gates. A telescoping perturbation bound is

$$\|\delta U\| \le 6\delta_\phi + 5\eta_W.$$

Adaptive irrational-magic correction. For $e^{i\phi} = (-4 + 3i)/5$, an undesired $-\phi$ injection branch is corrected with 2ϕ, then 4ϕ, and so forth. After K correction levels,

$$p_{\text{fail}} = 2^{-(K+1)}, \qquad \|\mathcal{E}_K - \mathcal{U}_\phi\|_\diamond \le 2^{-K}.$$

If doubled-angle states are directly available, fewer than two are injected on average. If each is recursively produced from the original state by parity doubling, the expected raw cost is

$$N_{\text{raw}} = 2^{K+1} - 1.$$

No finite doubling tree is exactly deterministic because the final residual differs from the target by $2^{K+1}\phi$, and ϕ/π is irrational.

Causal W33-fibered Dirac walk. Let

$$\beta = Z \otimes I, \qquad \alpha_j = X \otimes \sigma_j, \qquad m_r = \sqrt{m_0^2 + g\lambda_r},$$

where $\lambda_r \in \{0, 10, 16\}$ with multiplicities $1, 24, 15$. The exact three-spatial-dimensional local walk is

$$U_a(p, r) = e^{-iam_r\beta} e^{-iap_1\alpha_1} e^{-iap_2\alpha_2} e^{-iap_3\alpha_3}.$$

Each factor is a conditional nearest-neighbour shift, and

$$\frac{U_a - I}{-ia} = m_r\beta + \sum_{j=1}^{3} p_j\alpha_j + O(a).$$

Thus discrete time plus three spatial directions supplies a controlled $3+1$-dimensional Dirac limit carrying the three W33 mass sectors.

SK1-protected H1 pulse. For common fractional amplitude error ϵ,

$$U_{\mathrm{SK1}} = R_{-\chi}(2\pi(1+\epsilon))R_{\chi}(2\pi(1+\epsilon))R_x(\theta(1+\epsilon)), \quad \chi = \arccos\left(-\frac{\theta}{4\pi}\right).$$

The linear error vanishes. For $\theta = \pi$,

$$R_x(\pi)^{\dagger}U_{\mathrm{SK1}} = I - i\frac{\sqrt{15}\pi^2}{8}\epsilon^2 Z + O(\epsilon^3),$$

so the entanglement infidelity begins at $15\pi^4\epsilon^4/64$.

Gauge-commutant obstruction. The W33 permutation module decomposes as

$$\mathbb{C}^{40} = \mathbf{1} \oplus V_{24} \oplus V_{15},$$

and its full automorphism commutant is

$$\mathrm{span}\{E_{12}, E_2, E_{-4}\} = \mathrm{span}\{I, A, J\}.$$

This algebra is commutative, so its unitary gauge group is exactly

$$\boxed{U(1)^3}.$$

Unbroken W33 symmetry alone cannot generate non-Abelian $SU(2)$ or $SU(3)$ gauge bosons or mix the three sectors. A non-Abelian gauge theory requires symmetry breaking, multiplicity spaces, or a larger noncommutative algebra.

Three outside-box exact results. First, the reflection $U = I - 2E_6$ obeys $U^2 = I$, so repeated reflection has orbit dimension at most two and pure-state time-averaged entropy at most one bit. A localized vertex gives $H_2(3/5) = 0.97095059445$ bits; the reflection alone cannot thermalize or generate a Page curve.

Second, local H1 defect sensing satisfies

$$F_e^{\max} = \left(\frac{81}{160}\right)^2 t^2, \qquad \sum_e F_e \le 2t^2.$$

The total bound is attained by an equal-magnitude divergence-free Eulerian flow, giving uniform-prior average QFI $t^2/80$.

Third, the matrix-tree theorem gives

$$\tau(W33) = 2^{81}5^{23}, \qquad \tau(L_{\mathrm{Levi}}) = 2^{83}5^{23}, \qquad \frac{\tau(L_{\mathrm{Levi}})}{\tau(W33)} = 4.$$

The incidence lift changes Kirchhoff complexity by exactly two bits.

Boundary. These are exact algebraic or deterministic numerical statements in explicitly specified models. No fabricated block encoding, finite-cost exact deterministic irrational injection, fault-tolerance threshold, Standard Model, gravity, cosmology, or theory of everything is established.

56.1 Passes 4073–4080: engineering closures and outside-box physics probes

Exact four-router block encoding. The 4-regular Levi graph admits a one-factorization $A_L = P_0 + P_1 + P_2 + P_3$ into four involutory perfect-matching permutations. Consequently a balanced four-path selector and the controlled router $U_{\mathrm{sel}} = \sum_j |j\rangle\langle j| \otimes P_j$ obey

$$(\langle 00|B^\dagger \otimes I)U_{\mathrm{sel}}(B|00\rangle \otimes I) = \frac{A_L}{4}.$$

This is an exact abstract block encoding with two selector bits or paths; loss, crosstalk, and fabrication are not included.

Finite phase reference. Compressing K copies of $|A_\phi\rangle = (|0\rangle + e^{i\phi}|1\rangle)/\sqrt{2}$ into the symmetric Hamming-weight basis and applying a controlled cyclic lowering produces coherence multiplier

$$z_K = e^{i\phi}S_K + 2^{-K}e^{-iK\phi}, \qquad S_K = 2^{-K}\sum_{n=1}^{K}\sqrt{\binom{K}{n-1}\binom{K}{n}}.$$

The one-use channel error is at most $1 - S_K + 2^{-K}$, with $1 - S_K \sim (2K)^{-1}$. This removes the doubled-angle hierarchy but is only approximately catalytic.

Minimal non-Abelian multiplicities. The multiplicity extension $(m_1, m_{24}, m_{15}) = (3, 1, 2)$ has dimension 57 and commutant

$$M_3(\mathbb{C}) \oplus \mathbb{C} \oplus M_2(\mathbb{C}).$$

After freezing the spectator $U(1)$, its determinant-one subgroup has global form $S(U(3)\times U(2)) \cong (SU(3)\times SU(2)\times U(1))/\mathbb{Z}_6$ and central charge ratio $-1/3 : 1/2$. The present Dirac matter remains vectorlike; chirality and the observed matter representation are not derived.

Four-gap leakage notch. For the bright gaps $\Delta/J \in \{4-\sqrt{6}, 4, 4+\sqrt{6}, 8\}$, choose

$$f = \frac{h^{(8)} + 124h^{(6)} + 4644h^{(4)} + 53056h'' + 102400h}{102400},$$

with h and its first seven derivatives vanishing at the pulse endpoints. Then

$$F(\omega) = H(\omega)\frac{\prod_r(\Delta_r^2 - \omega^2)}{102400},$$

so all first-order H_1-to-bright transition amplitudes vanish while $\int f = \int h$. Leakage probability therefore begins at fourth order in the perturbative control strength.

Independent falsifiers and outside-box correspondences. The packet freezes six laboratory null tests. It also identifies P_{H_1} with the Maxwell–Calladine state-of-self-stress projector of an 80-node, 160-spring scalar network, giving one uniform mechanism and 81 self-stress states. A sudden quench of $H(g) = gL_{W33}$ has an exact three-line work distribution and obeys $\langle e^{-\beta W}\rangle = Z_1/Z_0$. Finally, the normalized Sakaguchi–Kuramoto linearization has decay rates $(5/6)K\cos\alpha$ with multiplicity 24 and $(4/3)K\cos\alpha$ with multiplicity 15, fixing the relaxation-time ratio to 8/5.

Boundary. These are exact finite or perturbative ideal-model statements. They do not certify a fabricated interferometer, an exact finite reusable irrational-phase catalyst, a fault-tolerance threshold, a chiral Standard Model, a mechanical prototype, a global nonlinear synchronization theorem, gravity, cosmology, or a theory of everything.

56.2 Canonical dark sectors, mobile pairs, overlap chirality, and operational geometry

The rank-3161 contact-dark two-photon module has now been resolved into all ordinary $PSp(4,3)$ irreducibles. The twenty conjugacy classes were mapped to ATLAS order

$$1A, 2A, 2B, 3A, 3B, 3C, 3D, 4A, 4B, 5A, 6A, 6B, 6C, 6D, 6E, 6F, 9A, 9B, 12A, 12B,$$

and every character fingerprint was frozen exactly in $\mathbb{Q}(\sqrt{-3})$. The central idempotents are

$$e_\chi = \frac{\chi(1)}{25920}\sum_C \overline{\chi(C)}K_C.$$

The dark module contains no trivial constituent; its nineteen nonzero isotypic dimensions sum to 3161.

After introducing an explicit same-cell dark-pair binding energy $-\Delta$ and symmetry-preserving one-photon hopping t, second-order Schrieffer–Wolff reduction gives

$$J_{\mathrm{pair}} = \frac{2t^2}{\Delta}, \qquad E(k) = -\Delta - \frac{4t^2}{\Delta} - \frac{4t^2}{\Delta}\cos k,$$

with bandwidth $8t^2/\Delta$ and $m^* = \Delta/(4t^2a^2)$ for $\hbar = 1$. All nineteen dark isotypic sectors share this clean dispersion and do not mix. This mobility requires the added binding scale; bare repulsive contact darkness alone is not a bound mobile phase.

A two-parameter dimerization cycle

$$J_{1,2} = J \pm R\cos\theta, \qquad m = 2R\sin\theta,$$

produces a pair-center Rice–Mele Hamiltonian whose lower band has $C = +1$ and minimum gap $4R$. At clean filled-band occupancy it pumps one composite pair, hence two photons, per cycle.

On the four-dimensional external tower, the overlap operator

$$D_{\mathrm{ov}} = a^{-1}\big[I + \gamma_5\,\mathrm{sign}(H_W)\big]$$

obeys the exact Ginsparg–Wilson relation

$$\gamma_5 D + D\gamma_5 = aD\gamma_5 D.$$

For $0 < m_0 < 2r$ one light external species survives per harmonic fibre, so the rank-81 fibre carries 81 light vectorlike Dirac species. This does not construct anomaly-free chiral gauge matter.

Marking a single incidence edge reduces the symmetry to a stabilizer of order 162. The restricted harmonic module has commutant dimension 45; a six-dimensional stabilizer irrep occurs with multiplicity three, giving an exact $U(3)$ block, while several three-dimensional irreps occur with multiplicity two, giving exact $U(2)$ blocks. Thus one marked edge is minimal in mark count for exposing $SU(3)$ and $SU(2)$ control subalgebras; these are commutant algebras, not identified Standard Model gauge bosons.

Three independent finite-physics consequences follow. First, one ideal Levi vertex port has local resolvent

$$G_{00}(s) = \frac{s^4 + 16s^3 + 78s^2 + 112s + 4}{s(s+4)(s+8)(s^2+8s+10)},$$

so its poles and residues recover the complete Levi spectrum and multiplicities. Second, erasing a maximally mixed dark state costs at least

$$k_B T \ln 3161 = 8.058643712215618\, k_B T.$$

Resolving and retaining the irrep label lowers the conditional data cost by $2.3278663282163152\, k_B T$, but erasing that label restores the same Landauer bound. Third, for $H = JA_{\text{line}}$ the order of the first nonzero short-time derivative of $\langle u|e^{-iHt}|v\rangle$ equals graph distance exactly. The four nontrivial shells have sizes $6, 18, 54, 81$ and first geodesic multiplicities $1, 1, 1, 2$.

These are exact finite group, band, operator, resolvent, thermodynamic, and graph-propagation statements. They establish neither fabricated hardware, measured quantization, chiral Standard Model matter, gravity, cosmology, nor a theory of everything.

57 Passes 4089–4096: implementation closure and outside-box probes

Theorem 57.1 (Router layout, optimal phase reference, anomaly bridge, and four-notch control)**.** *The* 80*-vertex Levi adjacency admits a deterministic decomposition* $A_L = P_0 + P_1 + P_2 + P_3$ *into four involutory perfect-matching permutations. Hence a balanced four-path selector gives an exact block encoding* $A_L/4$*. The frozen* 160*-swap route table is* `data/w33_pass4089_four_router_layout.json`*.*

For a finite phase reference on weights $0, \dots, K$*, the maximum nearest-neighbour coherence is*

$$\max \sum_{n=1}^{K} c_{n-1} c_n = \cos \frac{\pi}{K+2},$$

attained by $c_n = \sqrt{2/(K+2)}\sin((n+1)\pi/(K+2))$*. The resulting one-use error is* $O(K^{-2})$*.*

The exterior representation ring generated by the multiplicity spaces $\mathbb{C}^3$ *and* $\mathbb{C}^2$*, with determinant-one central charges* $(-1/3, 1/2)$*, contains*

$$(3,2)_{1/6},\ (\bar{3},1)_{-2/3},\ (\bar{3},1)_{1/3},\ (1,2)_{-1/2},\ (1,1)_1,$$

and all perturbative gauge, mixed gravitational, cubic Abelian, and mod-two $SU(2)$ *anomalies cancel exactly. This is a representation-ring identity, not a particle derivation.*

Finally, the compact envelope $h = 218790 T^{-1} x^8 (1-x)^8$ *and*

$$f = \frac{h^{(8)} + 124h^{(6)} + 4644h^{(4)} + 53056h'' + 102400h}{102400}$$

annihilate all four H_1*-to-bright first-order amplitudes. A full* 160*-mode simulation gives leakage exponents* 2.0191 *for a square pulse and* 4.0191 *for the notched pulse.*

Corollary 57.2 (Mechanical, coding, pattern, and circuit consequences)**.** *The scalar mechanical dual has* 81 *states of self stress and remains spectrally resolvable under the sufficient worst-case spring tolerance*

$$\epsilon < \frac{4-\sqrt{6}}{16} = 0.0969068911.$$

Its real cycle code has exact sparse parameters $[160, 81, 8]$*, detecting seven and uniquely correcting three noiseless sparse bond errors. Two explicit reaction–diffusion Jacobians select respectively the* 24- *and* 15*-dimensional W33 Laplacian sectors as the unique linearly unstable pattern spaces. The unit-resistor W33 network has only two effective resistances,*

$$R_{\mathrm{adj}} = \frac{13}{80}, \qquad R_{\mathrm{nonadj}} = \frac{7}{40},$$

with Kirchhoff index $267/2$*.*

Evidence boundary. No fabricated router, finite exact reusable irrational reference, dynamically derived Standard Model, measured pulse, mechanical prototype, nonlinear pattern experiment, gravity, cosmology, or theory of everything is asserted.

58 Passes 4097–4104: interacting pumping, quantum links, horizon falsifier, and spectral renormalization

Exact fractional many-composite pump. On the nine-cell, three-pair hard-core ring

$$H_0/U = \sum_i (n_i + n_{i+1} + n_{i+2} - 1)^2,$$

the fixed-filling spectrum is

$$0^3 + 2^{18} + 4^{36} + 6^{18} + 10^9.$$

The exact ground patterns 100100100, 010010010, and 001001001 have Resta polarizations $0, 1/3, 2/3$ and gap $2U$. With twisted holonomy

$$W(\phi) = e^{i\phi/3} T_3,$$

we have $\det W = e^{i\phi}$, so the rank-three ground bundle has Chern number one while one branch transports one third of a composite-pair charge per cycle. Three cycles pump one pair, or two photons.

Finite $SU(3)$ quantum-link sector. For link Hilbert space $\mathbf{1} \oplus (\mathbf{3} \otimes \bar{\mathbf{3}})$, the 81-dimensional one-link endpoint sector has a one-dimensional exact Gauss-law kernel,

$$|\mathrm{string}\rangle = \frac{1}{3} \sum_{a,b} |\bar{a}\rangle |a, \bar{b}\rangle |b\rangle.$$

Since $C_2(\mathbf{3}) = 4/3$, the electric string energy is

$$E_{\mathrm{string}}(R) = \frac{2g^2 R}{3}, \qquad \sigma = \frac{2g^2}{3a}.$$

The minimal vacuum/loop plaquette block is

$$H_\square = \begin{pmatrix} 0 & -J \\ -J & 8g^2/3 \end{pmatrix},$$

with gap $2\sqrt{16g^4/9 + J^2}$.

Passive-horizon no-go. For a reciprocal number-conserving chain with real hopping profile J_n, all open-chain hopping signs are removable by local phases. Moreover $U(t) = e^{-iht}$ is symmetric and its Nambu evolution is $\mathrm{diag}(U, U^*)$, so the Bogoliubov creation block vanishes exactly:

$$\beta = 0, \qquad \langle N \rangle_{\mathrm{vacuum}} = 0.$$

A static reciprocal $J(x)$ profile alone therefore creates neither a one-way horizon nor spontaneous Hawking radiation. Directed Floquet/background flow and particle–hole mixing are additional necessary ingredients.

Discrete-scale spectral fixed cycle. At hierarchy level n, retain one zero mode and modes

$$\lambda_\alpha b^{-2(n-1-j)}$$

with multiplicity $m_\alpha 80^j$, where

$$(\lambda_\alpha, m_\alpha) = (4 - \sqrt{6}, 24), (4, 30), (4 + \sqrt{6}, 24), (8, 1).$$

The total dimension is 80^n, and the log-period-average spectral dimension is

$$\bar{d}_s = \frac{\log 80}{\log b}.$$

For $b = 80^{1/4}$, $\bar{d}_s = 4$. At $n = 14$ the computed central-window mean is 3.99987084247, with persistent log-periodic oscillations between 2.97765560 and 5.14402331. Thus the construction is a discrete-scale fixed cycle, not a smooth continuum fixed point; the value four depends on the supplied rescaling.

Topological information engine. For the 19 dark isotypic dimensions n_j, with $p_j = n_j/3161$,

$$H(J) = 2.327866328216315, \qquad \sum_j p_j \log n_j = 5.730777383999302,$$

and

$$H(J) + \sum_j p_j \log n_j = \log 3161.$$

A reversible expansion extracts $k_B T \log 3161$, while conditional erasure and label erasure cost exactly the same total. Irrep-controlled Chern pumps can robustly route one pair per cycle, but the maximum closed-cycle net work remains zero.

Three outside-box constructions. First, the invariant CDW clock subspace with

$$H_{\mathrm{scar}} = \Omega(T_3 + T_3^\dagger)$$

has eigenvalues $-\Omega, -\Omega, 2\Omega$ and exact return probability

$$P_A(t) = \frac{5 + 4\cos(3\Omega t)}{9},$$

with perfect revival at $2\pi/(3\Omega)$. Second, the qutrit-cat probe over the three fractional-pump branches has

$$F_Q = \frac{8N_p^2}{3}$$

for a pair-position phase and $32N_p^2/3$ for the corresponding photon-gradient phase. Third, the canonical Fisher length of the projected contact spectrum from $\beta = 0$ to ∞ is 0.4530018812338062, while the Fisher–Rao endpoint geodesic is 0.4425945899021065, an excess of only 2.3514% because 3161/3321 of the Hilbert space is already dark.

Evidence boundary. These are exact finite strong-coupling, Gauss-law, passive-Bogoliubov, hierarchical-spectrum, information-thermodynamic, invariant-subspace, and Fisher-geometry statements. They do not establish a fractional-pump experiment, continuum QCD, Hawking observation, physical four-dimensional spacetime, positive-work engine, generic scar phase, gravity, cosmology, or a theory of everything.

Passes 4105–4112: carrier audit, correlated reference, implementation contracts, and three outside-box probes

The candidate module

$$(\mathbb{C}^6 \otimes V_1) \oplus (\mathbb{C}^3 \otimes V_{15}) \oplus (\mathbb{C}^2 \otimes V_{24})$$

has dimension 99 and commutant $M_6 \oplus M_3 \oplus M_2$, but it contains only one independent anti-triplet and no independent charged singlet. Under the sector assignment $Q, e^c \mapsto V_1$, $u^c, d^c \mapsto V_{15}$, and $L \mapsto V_{24}$, the minimum direct carrier is therefore

$$(\mathbb{C}^7 \otimes V_1) \oplus (\mathbb{C}^6 \otimes V_{15}) \oplus (\mathbb{C}^2 \otimes V_{24}), \qquad \dim = 145.$$

This carries the anomaly-free one-generation representation as a representation architecture, not as a derived particle model.

For the sine phase reference $c_n = \sqrt{2/(K+2)}\sin((n+1)\theta)$, $\theta = \pi/(K+2)$, sequential use gives a collective channel

$$\mathcal{E}_N(|x\rangle\langle y|) = z_{|x|-|y|}|x\rangle\langle y|,$$

with exact bulk overlap

$$C_m = \frac{(K+1-m)\cos(m\theta) + \sin((m+1)\theta)/\sin\theta}{K+2}.$$

Equal-Hamming-weight coherences are decoherence-free and the fixed-N error is $O(N^2/K^2)$.

The four-router signal unitary compiles to four coherent 80-mode branches with 40 parallel swaps per branch. A recirculating five-query realization uses 160 swap cells, six selector/recombiner couplers, six phase shifters, and five coherent passes; an unrolled realization uses 800 swap cells.

For noisy self-stress syndrome data $y = De + n$, exhaustive support-three decoding obeys

$$\|\widehat{e} - e\|_2 \le \frac{2\|n\|_2}{2\sin(\pi/14)},$$

because every union of two support-three candidates is a forest and the worst six-edge restricted singular value is $2\sin(\pi/14)$. Cubically saturated reaction–diffusion simulations converge with unit numerical modal purity into the intended 24- and 15-dimensional eigenspaces.

Finally,

$$\frac{J}{40} = I - \frac{13}{80}L + \frac{1}{160}L^2$$

gives exact two-round average consensus; simple random walk has adjacent and nonadjacent hitting times 39 and 42 with Kemeny constant 801/20; and the abstract Hückel model has a 50-electron closed shell with gap $6|\beta|$ and a 40-electron open-shell determinant count $\binom{48}{10} = 6{,}540{,}715{,}896$.

58.1 Passes 4113–4120: gauge-string pumping, active horizons, dynamic dimension, local scar compilation, and thermodynamic curvature

The exact evidence bundle for this subsection is `data/PART_4113_4120_GAUGE_HORIZON_DIMENSION_SCAR_CURVATU` with semantic SHA-256 `28391f98e03ec20cc688cc8692579ff0cf352930d085b2d33d979de7ef9a3e2a`. All statements below are finite-model statements; continuum QCD, observed Hawking radiation, physical spacetime emergence, a static local scar Hamiltonian, thermodynamic singularities, and non-Abelian anyons remain outside the evidence boundary.

Gauge-string fractional pump. Tensoring the three one-third-filled CDW branches with the unique finite $SU(3)$ Gauss singlet

$$|\mathcal{M}\rangle = \frac{1}{3}\sum_{a,b=1}^{3} |\bar{a}\rangle|a,\bar{b}\rangle|b\rangle$$

gives a one-dimensional simultaneous left/right Gauss-law kernel in the 81-dimensional endpoint–link–endpoint space. A branch cycle transports one third of a gauge-invariant composite and its attached fundamental–antifundamental flux support. After three cycles one complete singlet composite crosses a cut, but the net transported color charge is zero. In the zero-flux sector the three-cycle Wilson holonomy is the identity; a prescribed $\mathbb{Z}_3$ center flux contributes only $e^{2\pi ik/3}I$. Non-Abelian Wilson mixing therefore requires a degenerate color multiplet or nontrivial plaquette background.

Active Floquet–Bogoliubov horizon. The passive reciprocal no-go is evaded by combining directed walk dispersion

$$\Omega(k) = \frac{2}{\tau}\arcsin\left[v\sin\left(\frac{ka}{2}\right)\right]$$

with a local two-mode squeezer. At a horizon $u(x_H) = c_{\text{eff}}$,

$$\kappa = |\partial_x(u - c_{\text{eff}})|_{x_H}, \qquad T_H = \frac{\kappa}{2\pi},$$

and

$$\tanh r = e^{-\pi\omega/\kappa}, \qquad n_\omega = \sinh^2 r = \frac{1}{e^{2\pi\omega/\kappa} - 1}.$$

A greybody beam splitter of transmission Γ gives $n_{\text{out}} = \Gamma n_\omega$. The full six-channel Nambu map is paraunitary with residual $2.282836126979115 \times 10^{-16}$ in the frozen demonstration. For $\kappa = 0.4$, $\omega = 0.3$, and $\Gamma = 0.7$, $T_H = 0.06366197723675814$, $n_\omega = 0.009064722057396675$, $n_{\text{out}} = 0.006345305440177674$, and the post-greybody logarithmic negativity is 0.15624263179344325. The lattice ultraviolet correction begins at cubic order,

$$\Omega(k) = \frac{va}{\tau}k + \frac{v^3 - v}{24}\frac{a^3}{\tau}k^3 + O(k^5a^5).$$

Dynamically selected spectral dimension. Let $s = \ln b$, use the exact branch count $B = 80$ and exact Levi edge connectivity $\chi = 4$, and define

$$\Phi(s) = \frac{1}{2}[\ln 80 - 4s]^2, \qquad \dot{s} = \gamma[\ln 80 - 4s].$$

Then

$$\dot{\Phi} = -4\gamma[\ln 80 - 4s]^2 \le 0,$$

so

$$s_* = \frac{\ln 80}{4}, \qquad b_* = 80^{1/4} = 2.9906975624424406$$

is globally stable, with linear exponent -4γ. The selected spectral dimension is

$$d_s = \frac{\ln 80}{\ln b_*} = 4.$$

This is an explicit four-channel information-balance law, not an independent derivation of physical spacetime.

Local scar compilation and static no-go. The three CDW words 100100100, 010010010, and 001001001 have pairwise Hamming distance six. Any operator supported on fewer than six sites therefore has zero direct matrix element between distinct branches. If their bare span is exactly invariant, a strictly finite-range static Hamiltonian cannot realize the nontrivial branch cycle. An exact local Floquet realization nevertheless exists: apply the eight adjacent swaps $(0,1),(1,2),\ldots,(7,8)$ sequentially, each generated for time τ by

$$H_i = \frac{\pi}{2\tau}(I - \mathrm{SWAP}_{i,i+1}).$$

One compiled shift takes $T_{\mathrm{shift}} = 8\tau$, cycles the three CDW branches, and obeys

$$U_{\mathrm{shift}}^3 = I, \qquad T_{\mathrm{rev}} = 24\tau.$$

The Floquet quasienergies are 0 and $\pm 2\pi/(3T_{\mathrm{shift}})$.

Thermodynamic curvature. Assign each dark isotypic block of dimension n_j the splitting charge $q_j = \ln n_j$, while the five bright groups retain their exact contact energies and have $q = 0$. Then

$$Z(\beta,h) = \sum_{j\in\mathrm{dark}} n_j e^{-h\ln n_j} + \sum_{a\in\mathrm{bright}} g_a e^{-\beta E_a}, \qquad g_{ab} = \mathrm{Cov}(T_a,T_b), \quad T = (-E,-q).$$

The two-dimensional Hessian scalar curvature satisfies

$$R(0,0) = -0.6460278596846867,$$

crosses zero at $\beta U = 14.579166757087052$, and reaches $R(20,0) = 0.20080335722980544$. Because Z is a finite positive exponential sum, this is a finite information-geometric crossover rather than a thermodynamic singularity.

Three outside-box consequences. First, the branch shift X and branch twist Z satisfy

$$ZX = \omega XZ, \qquad \omega = e^{2\pi i/3},$$

with residual $2.482534153247273 \times 10^{-16}$, yielding the qutrit Heisenberg–Weyl logical algebra and projective commutator ωI; this is projective holonomy, not anyon braiding. Second, the principal

logarithm of X has phases $0, \pm 2\pi/3$, so any generator with $\|H - cI\| \le \Lambda$ obeys the exact unitary-geodesic limit

$$T \ge \frac{2\pi}{3\Lambda}.$$

Third, at $b_* = 80^{1/4}$ the hierarchy obeys

$$\lambda_{n+m} = \lambda_n b_*^{-2m}, \qquad \omega_{n+m} = \omega_n b_*^{-m}, \qquad 1 + z_m = b_*^m = 80^{m/4}.$$

For $m = 1, 2, 3, 4$, the spectral redshifts are 1.9906975624424406, 7.944271909999156, 25.749612199056866, and 79. This is discrete spectral scaling, not gravitational or cosmological redshift.

58.2 Passes 4121–4128: explicit gauge audit, relational phase coding, decoding, foundry feasibility, attractors, and outside-box probes

The explicit 145-dimensional carrier

$$(\mathbb{C}^7 \otimes V_1) \oplus (\mathbb{C}^6 \otimes V_{15}) \oplus (\mathbb{C}^2 \otimes V_{24})$$

was equipped with concrete $SU(3) \times SU(2) \times U(1)$ generators. This calculation corrects the earlier multiplicity-space reading: the complete carrier has W33 weights $(q, u, d, l, e) = (1, 15, 15, 24, 1)$ and is anomalous,

$$\mathcal{A}_{3^3} = -28, \quad \mathcal{A}_{3^2Y} = -\frac{7}{3}, \quad \mathcal{A}_{2^2Y} = -\frac{23}{4}, \quad \mathcal{A}_{\mathrm{grav}^2Y} = -37, \quad \mathcal{A}_{Y^3} = -\frac{599}{36}.$$

The weak-doublet count is 27. Without exotic representations, the anomaly equations force equal W33 weights $q = u = d = l = e$. Exact repair architectures therefore require either a rank-one PSp-breaking generation inside the 145 states, a 225-dimensional V_{15} generation, a 360-dimensional V_{24} generation, or 600 dimensions containing one complete generation in each of V_1, V_{15}, V_{24}. Gauge symmetry permits three Yukawa tensors, but a W33-singlet Higgs permits none; the up, down, and lepton couplings require mediators in V_{15}, V_{15}, V_{24}.

For the optimal sine phase reference, a single fixed-weight subspace is an exact decoherence-free space but supports only a global phase. Pairing $\mathcal{H}_r$ and $\mathcal{H}_{r+1}$ for $N = 2r + 1$ instead gives

$$\mathbb{C}^2_{\mathrm{clock}} \otimes \mathbb{C}^{\binom{N}{r}}_{\mathrm{payload}}.$$

The reference noise and desired phase act only on the clock; all payload coherences are exact. At $K = 256$ and $N = 31$, one clock plus 28 payload qubits has error $7.3646628264 \times 10^{-5}$, versus $5.5087125884 \times 10^{-2}$ for direct 29-qubit injection.

The three-error self-stress decoder was reduced from 682641 global supports to at most

$$1 + 20 + \binom{20}{2} + \binom{20}{3} = 1351$$

local candidates. The candidate graph is formed from all Levi paths of length at most three between threshold vertices; an exhaustive audit proves the 20-edge bound. Stability remains controlled by

$$\sigma_6 = 2\sin(\pi/14), \qquad \|\widehat{e} - e\|_2 \le 2\epsilon/\sigma_6.$$

A CORNERSTONE 340 nm SOI floorplan audit gives 1934 crossings, at most 21 on one path, 480 selector/recombiner MMIs, and 480 phase shifters for a spatial 80-mode realization. Under

conservative public platform inputs, five signal uses incur a conditional pre-MMI path loss of 27.43 dB. Thus the exact logical router is not tapeout-ready in naive spatial SOI; low-loss passive routing with an active phase layer, or time/frequency serialization, is required.

A 64-seed nonlinear census produced 25 observed orbit classes for the nominal 24-mode selector and 9 for the nominal 15-mode selector. Pure bivalent stabilizers include $V_4, S_3, D_8, C_6 \times C_2, D_{10}, S_5$, and A_5, while mixed-sector attractors show that cubic saturation does not globally remain in one Laplacian eigenspace.

Three outside-box consequences were certified. First, the A_5 sign vector satisfies $As = -4s$ and attains the exact MaxCut value 160, hence the antiferromagnetic ground energy is $-80J$. Second, the continuous-time walk at $t = \pi/(2J)$ is the exact Householder mirror

$$U = I - 2P_2 = \frac{A^2 - 8A - 18I}{30} = -\frac{I + A}{3} + \frac{2}{15} J_{40},$$

which flips precisely the 24-dimensional eigenvalue-two sector. Third, pairing the 15 eigenvalue-minus-four modes with 15 eigenvalue-two modes yields fifteen simultaneous EP_2 blocks at $\gamma = g$; the paired 30-dimensional operator has square zero and rank 15.

All statements above are finite algebraic, combinatorial, or explicitly labelled numerical results. No derived Standard Model, fabricated chip, measured decoder or pattern, physical magnet, graph-walk processor, exceptional-point sensor, gravity, cosmology, or theory of everything is claimed.

58.3 Passes 4129–4136: anomaly optimization, relational gates, seven-fault decoding, hybrid routing, and exact pure-orbit catalogues

Let the signed W33 multiplicities of Q, u^c, d^c, L, e^c be (q, u, d, ℓ, e). The independent integer anomaly map is

$$M = \begin{pmatrix} 2 & -1 & -1 & 0 & 0 \\ 1 & -2 & 1 & 0 & 0 \\ 1 & 0 & 0 & -1 & 0 \\ 1 & -2 & 1 & -1 & 1 \end{pmatrix},$$

with kernel $\mathbb{Z}(1,1,1,1,1)$ and Smith diagonal $(1,1,1,3)$. For the anomalous $(1, 15, 15, 24, 1)$ carrier, vectorlike pairs alone cannot repair the anomalies. The minimum standard-charge signed repair adds $14Q + 14e^c + 9\bar{L}$, giving dimension 261 but breaking the W33 module assignment. Exact representation-ring optimization gives total dimensions $291, 335, 554, 600$ for common target modules $V_1, V_{15}, V_{24}, V_1 \oplus V_{15} \oplus V_{24}$ respectively; 335 is the smallest repair with nontrivial $PSp(4,3)$ action on the net chiral generation.

For $N = 31$, $r = 15$, adding one reservoir mode gives the fixed-number code

$$|0, S\rangle_L = |S\rangle|1\rangle_R, \qquad |1, S\rangle_L = |\bar{S}\rangle|0\rangle_R,$$

with total number 16 and dimension $2\binom{31}{15} = 601080390$. The clock operators $Z_c = \Pi_{15} - \Pi_{16}$, the paired complement X_c, $H_c = (X_c + Z_c)/\sqrt{2}$, paired payload unitaries, and clock-controlled payload unitaries all preserve total number. The reference channel factors as $\mathcal{E}_{z_1}^{\mathrm{clock}} \otimes I_{\mathrm{payload}}$; at $K = 256$, $|z_1| = 0.9999263606710866$, corresponding after known-phase correction to dephasing probability $3.6819664457 \times 10^{-5}$.

The Levi incidence syndrome has spark eight, so four-error uniqueness is impossible: opposite halves of an apartment cycle collide. The first three generalized cycle-support weights are $8, 12, 16$. Adding

$$m_3(x) = \sum_{e=1}^{160} e^3 x_e, \qquad m_5(x) = \sum_{e=1}^{160} e^5 x_e$$

raises the stacked spark to at least fifteen. This follows from exhaustive audits of 386964 simple cycles through length fourteen and 133920 rank-two theta cores. Hence every seven-sparse error is uniquely identifiable in the noiseless model.

The four router permutations decompose into $8, 8, 9, 8$ planar increasing-subsequence layers. A hybrid architecture with passive SiN permutation banks and a shared active SOI selector/phase layer uses 160 passive routes, six selector/recombiner MZIs, 24 common phase plates, 30 active controls, and no same-plane crossings. Under the stated design targets its provisional five-pass internal budget is 9.12 dB and its all-π heater envelope is 0.48 W. This is an architecture contract, not a fabricated device.

The pure $\lambda = 16$ binary system $(A + 4I)x = 8\mathbf{1}$ has exactly 432 signs, or 216 maximum cuts modulo reversal, in one A_5-stabilized orbit. The pure $\lambda = 10$ system $(A - 2I)x = 5\mathbf{1}$ has exactly 33264 signs in seven $PSp(4, 3) \times \{\pm 1\}$ orbit classes of sizes

$$6480, 8640, 6480, 6480, 2160, 2592, 432.$$

Thus all pure bivalent nonlinear branches and all maximum cuts are catalogued; mixed-amplitude attractors remain open.

Three further exact constructions are recorded. First, the anomaly cokernel contains genuine $\mathbb{Z}/3\mathbb{Z}$ torsion, yielding $a_{SU(3)^3} + a_{6SU(3)^2U(1)} \equiv 0 \pmod 3$. Second, the distributed projectors

$$P_{12} = J/40, \quad P_2 = \tfrac{2}{3}I + \tfrac{1}{6}A - \tfrac{1}{15}J, \quad P_{-4} = \tfrac{1}{3}I - \tfrac{1}{6}A + \tfrac{1}{24}J$$

provide exact two-round network tomography. Third,

$$G_8 = e^{-i\pi L/8}, \qquad G_5 = e^{-i\pi L/5}$$

have orders eight and five and generate $\mathbb{Z}_{40}$ on the nonuniform spectral sectors. This is a finite reversible spectral clock, not emergent physical time.

59 Passes 4137–4144: matrix Wilson pumping, extended horizons, microscopic scale flow, and autonomous history dynamics

The exact certificate for this packet is `d16f8ab7ce51f2953cfd4866e7a716e31a271b3337a05b6105b367736bcecb6c`
All statements in this section concern finite group, Gaussian, Markov, clock, transfer-matrix, circuit, or band-topology models.

Matrix-valued gauge-singlet holonomy. The color space $(\mathbf{3} \otimes \bar{\mathbf{3}})^{\otimes 3}$ contains six independent contraction singlets, with Gram spectrum

$$\left\{\frac{2}{9}, \left(\frac{8}{9}\right)^4, \frac{20}{9}\right\}.$$

Three orthonormal singlet channels support a tripod Hamiltonian whose rank-two dark bundle has two exact Wilson loops

$$U_y = \begin{pmatrix} -\frac{1}{2} & -\frac{\sqrt{3}}{2} \\ \frac{\sqrt{3}}{2} & -\frac{1}{2} \end{pmatrix}, \qquad U_z = \operatorname{diag}(e^{-2\pi i/3}, e^{2\pi i/3}).$$

Their group commutator has trace $-1/4$, so the adiabatic Wilson response is genuinely matrix-valued rather than a center phase.

Extended active horizon lattice. Nine localized squeezing cells act on one outgoing, nine partner, and nine environment modes. The resulting 38×38 Nambu map has paraunitary residual 1.11×10^{-15}. At $\omega = 0.3$ the outgoing occupation is 0.01195894, the greybody ratio is 0.48573560, and the outgoing/partner logarithmic negativity is 0.20853530. The partner profile is centered at cell 4.0048 with RMS width 1.1977 cells. The inside-flow lattice dispersion has two ultraviolet roots with opposite group velocities, giving explicit mode conversion without promoting the finite analogue model to gravitational Hawking radiation.

Microscopic channel-balance flow. Four independent local Markov channels sum to

$$ds = \gamma(\ln 80 - 4s)dt + \sqrt{2D}\, dW.$$

The stationary law is Gaussian around $s_* = \ln 80/4$, the Fokker–Planck gap is 4γ, and the deterministic spectral dimension is exactly

$$d_s = \frac{\ln 80}{s_*} = 4.$$

For $D = 0.01$ and $\gamma = 1$, the mean noisy value is 4.00838502 and relative entropy to stationarity decreases monotonically.

Autonomous history-state scar gadget. Three repetitions of the eight adjacent-SWAP branch compiler define a 24-gate program. The static engineered history Hamiltonian

$$H = \Omega \sum_{t=0}^{23} \sqrt{(t+1)(24-t)}\, (|t+1\rangle\langle t| \otimes U_{t+1} + \text{h.c.})$$

has a 25-state clock, an equally spaced spectrum from -24Ω to 24Ω, perfect endpoint transfer at $\pi/(2\Omega)$, and full history revival at π/Ω. The endpoint data operation is $U_{\text{shift}}^3 = I$.

Curvature scaling. For N independent dark-reservoir cells, $Z_N = Z_1^N$, $g_N = N g_1$, and the scalar curvature satisfies

$$R_N = \frac{R_1}{N}.$$

The sign change remains at $\beta U = 14.5791667571$, but its magnitude vanishes in the thermodynamic limit. A positive 2×2 transfer matrix for a weakly coupled one-dimensional dark/bright hierarchy is analytic for finite coupling and has correlation length 0.14340675 cells in the frozen demonstration, excluding a finite-temperature singularity in this class.

Outside-box probes. Ordering $U_y U_z$ versus $U_z U_y$ yields output fidelity 7/16, furnishing a geometric phase-order transistor. Levi edge connectivity four and the $2 \ln 3$ entropy-change bound per two-qutrit cut gate imply a throughput ceiling of $8 \ln 3$ nats per layer and at least 74 layers for 80 maximally mixed dark cells. Finally, a spin-one Qi–Wu–Zhang control Hamiltonian on three singlet channels has band Chern numbers $(-2, 0, 2)$ and realizes a charge-two synthetic control-space monopole.

Boundary. No continuum QCD, fabricated non-Abelian pump, observed Hawking radiation, derivation of physical spacetime, thermodynamic phase transition, non-Abelian anyon, physical monopole, gravity, cosmology, or theory of everything follows from these finite exact results.

59.1 The 200-cover orbital dictionary and Gram reconstruction

The 200 nine-tritangent covers split canonically as 40 point-covers and 160 flag-covers. Exact cover overlap is constant on the 19 point/flag orbitals. The point fiber has overlap values 9, 3, 1 on identity, collinear, and noncollinear pairs, while the eight flag relative positions have overlaps 9, 3, 0, 0, 0, 3, 4, 1. The full integer cover Gram reconstructs the two fibers, W33 collinearity, the 40 maximal four-point lines, and every incident point-line flag. Its cross-fiber level 6 is the previously certified 480-incidence cover graph. After integer centering, the 40 point-covers and 160 flag-covers are separately tight frames for the same tritangent degree-24 constituent, with frame operators 300 P24 and 1200 P24 respectively. These are finite incidence statements only.

Passes 5056–5057: $q = 4$ theta code and the local cut-space law

A direct construction of $W(3,4)$ gives 85 points, 85 lines, 425 flags and 13,600 apartments. The binary apartment cycles have rank $256 = 4^4$. The point- and line-side theta construction gives 54,400 weight-three relations of rank $13{,}344 = 13{,}600 - 256$, so at $q = 4$ the theta relations generate the full dual. The exact minimum support is 256, hence

$$\boxed{C_4 = [13600, 256, 256]_2}.$$

Together with Pass 5051, the family is therefore exact at $q = 2, 3, 4$.

For arbitrary q, fix an opposite same-type pair. Its $q+1$ geodesics form the vertices of K_{q+1}; apartments are edges and theta relations are triangles. If x_{ij} satisfies every triangle relation, then

$$x_{ij} = x_{0i} + x_{0j} = a_i + a_j.$$

Thus the local theta kernel is exactly the cut space of K_{q+1}, has dimension q, and every nonzero local word has weight $s(q+1-s) \geq q$.

Every apartment belongs to four opposite-pair charts, so

$$4\,\mathrm{wt}(x) = \sum_O \mathrm{wt}(x|_O) \geq qA(x).$$

Consequently the still-open family distance theorem reduces to one statement:

$$\boxed{A(x) \geq 4q^3 \Longrightarrow d = q^4}.$$

At $q = 4$ the chamber-star witness has $A = 128_{\text{point}} + 128_{\text{line}} = 256 = 4q^3$ and saturates the bound. Arbitrary-q full-dual generation and the active-chart inequality remain open; no stronger claim is promoted here.

59.2 Bounded exotic repair, local relational gates, conditioned seven-fault sensing, and exact finite probes

Within the bounded family $R_3 \in \{1, 3, \bar{3}\}$, $\dim R_2 \in \{1, 2\}$, and $Y = n/6$ with $0 < |n| \leq 6$, exact mixed-integer optimization repairs the explicit 145-state carrier with 107 added states. The resulting 252-state signed spectrum is optimal in that family and uses an odd number of added weak doublets.

The compressed relational clock has a sharp one-shot locality obstruction: paired words differ on all 32 occupation modes. A 58-mode dual-rail lift instead carries one clock and 28 payload

qubits at fixed total particle number 29. Logical H, S, CNOT, clock exchange, and clock-controlled payload operations are generated by Hamiltonians supported on at most three modes, while the shared reference acts only on the clock.

Two centered integer moment rows obtained modulo 24001 have maximum magnitude 11992. Exhaustive audits of all 386964 simple Levi cycles of length at most fourteen and all 133920 relevant theta cores prove stacked spark at least fifteen and exact noiseless recovery of every seven-sparse edge error. The coefficient envelope is reduced by more than 8.7×10^6 relative to the e^5 row.

The four exact router permutations decompose into $8, 8, 9, 8$ noncrossing layers. The 33-layer SiN schedule uses zero same-plane crossings and 30 active controls, but static nine-slot delay equalization requires 1280 route-slot units. At a 5 ps slot and group index two, the added five-use delay loss is 1.5 dB; sub-1 dB delay loss requires slots below 3.34 ps.

Full Newton refinement gives 18 stable mixed classes for the nominal 24-sector selector in the 64-seed corpus. In an enlarged 200-seed corpus, the nominal 15-sector selector has four stable mixed roots and one weak index-one saddle; the earlier finite-time count of eight mixed classes collapses to five actual roots. The two nonzero root-stabilizer quotient branches are saddles of Morse indices 23 and 14.

Three further finite constructions are exact. The eight-regular bipartite maximum-cut graph has 56260624960 perfect matchings, but a one-bit feedback engine obeys the exact Landauer balance $p\Delta - kTh(p) = -kT\ln(1 + e^{-\beta\Delta}) < 0$. The signed Levi incidence supercharge has 82 zero modes and Witten index $1 - 81 = -80 = V - E$. Finally, $H_- = 12I - A$ and $H_+ = 4I + A$ satisfy $H_- + H_+ = 16I$, so $e^{-i\tau H_+}e^{-i\tau H_-} = e^{-i16\tau}I$, with an exact identity echo at $\tau = \pi/8$.

Evidence boundary. These are finite algebraic, combinatorial, optimization, modular-audit, and Newton-refined corpus results. They do not establish a derived Standard Model, a fabricated photonic stack, a globally complete mixed-attractor theorem, a perpetual-motion engine, physical supersymmetry, a measured time crystal, gravity, cosmology, or a theory of everything.

60 Passes 4153–4160: second-Chern pumping, disorder, Lindblad scale flow, and graph thermodynamics

Second-Chern singlet pump. Let Γ_a be five Hermitian 4×4 Clifford generators with $\{\Gamma_a, \Gamma_b\} = 2\delta_{ab}$ and $\Gamma_1\Gamma_2\Gamma_3\Gamma_4\Gamma_5 = -I_4$. For $H(n) = \sum_a n_a\Gamma_a$ on S^4, the negative-energy projector $P = (I - H)/2$ has rank two and

$$\mathrm{Tr}[P(dP)^4] = \frac{1}{8}\epsilon_{abcde}n_a\, dn_b \wedge dn_c \wedge dn_d \wedge dn_e.$$

Consequently

$$C_2 = \frac{1}{8\pi^2}\int_{S^4}\mathrm{Tr}[P(dP)^4] = 1, \qquad C_1 = 0.$$

This is an exact Yang-monopole bundle embedded in the finite singlet-contraction space; it is not a fabricated four-dimensional pump.

Disordered Hawking chain. All 512 binary patterns $r_j \mapsto r_j(1 + 0.5s_j)$ and $\Gamma_j \mapsto \Gamma_j + 0.05s_j$ were audited in the nine-cell, 38-dimensional Nambu chain. The minimum logarithmic negativity is 0.0920180870833, the largest minimum partially-transposed symplectic eigenvalue is $0.456044326186 < 1/2$, and the maximum paraunitary residual is 1.82×10^{-15}. Every audited realization remains entangled.

Lindblad scale oscillator. For $s_* = \ln(80)/4$, define

$$L_- = \sqrt{8\gamma(\bar{n}+1)}\, b, \qquad L_+ = \sqrt{8\gamma\bar{n}}\, b^\dagger, \qquad s = s_* + \sigma(b + b^\dagger),$$

with $\sigma^2 = D/[4\gamma(2\bar{n}+1)]$. Then

$$\frac{d\langle s\rangle}{dt} = -4\gamma(\langle s\rangle - s_*), \qquad \mathrm{gap}(\mathcal{L}) = 4\gamma, \qquad d_s = \frac{\ln 80}{s_*} = 4.$$

The stationary state is thermal and unique. This is an explicit open-system scale model, not a spacetime derivation.

Compressed autonomous clock. The 25 legal history states require at least five qubits. The reflected Gray encoding $g_t = t \oplus (t \gg 1)$ reaches this lower bound and has unit Hamming distance between successive legal words. The engineered history Hamiltonian retains spectrum $-24\Omega, -22\Omega, \ldots, 24\Omega$, perfect transfer at $\pi/(2\Omega)$, and full revival at π/Ω. The exact tradeoff is five-local clock conditioning and seven-local clock–SWAP propagation terms.

Levi-cover thermodynamics. For dark/bright degeneracies $g_D = 3161$ and $g_B = 160$, the entropic coexistence field is

$$H_c(T) = -\frac{T}{2}\ln\frac{3161}{160}.$$

The six-regular Levi universal cover has nonbacktracking branching five, so the cavity instability satisfies

$$5\tanh(\beta_c J) = 1, \qquad \beta_c J = \operatorname{atanh}(1/5) = 0.202732554054.$$

The finite 160-vertex graph remains analytic, whereas large-girth six-regular covers possess a genuine Bethe ordering singularity on the coexistence line.

Outside-box probes. Repeated partner-vacuum projections after M fractional squeezing steps give $P_M = \mathrm{sech}^{2M}(r/M)$ and suppress conditional pair production as r^2/M; this is a Zeno effect, not a firewall. Pauli-twirl purity spectroscopy distinguishes the active rank-two bundle from the full six-dimensional singlet space. Finally, a four-state clock ring with π loop flux has spectrum $\pm\sqrt{2}\Omega$ and exact projective echo $U(\pi/(\sqrt{2}\Omega)) = -I_4$.

Evidence boundary. The frozen semantic certificate is `0e9080801a2cfcca3b7b39afd807835d7bdc6b1a483cd68`
All statements are finite Clifford, Gaussian, Lindblad, clock, Bethe, measurement, purity, or flux-ring results. No observed Hawking radiation, physical firewall, anyonic quantum dimension, spacetime torsion, gravity, cosmology, or theory of everything is established.

60.1 Passes 4161–4168: broader anomaly repair, local hardware, noisy decoding, storage, global basin push, and three exact probes

The bounded representation search was enlarged to $SU(3)$ irreps $1, 3, \bar{3}, 6, \bar{6}, 8$, weak dimensions $1, 2, 3$, and $Y = n/6$ with $|n| \le 6$. Exact mixed-integer optimization lowers the anomaly-free carrier from 252 to **213 states** inside this finite family, while a second exact optimization proves an added color Dynkin load of at least 11, giving a one-loop $SU(3)$ asymptotic-freedom obstruction for this embedding. The 58-mode relational lift admits a 139-coupler hardware graph of maximum degree seven, arbitrary payload CNOT depth at most 15, and 28-qubit GHZ depth five. For

lattice-amplitude errors, the two conditioned integer moment rows give deterministic seven-fault correction under componentwise noise $< \Delta/2$ after rounding; a modulo-24001 accumulator needs 15 residue bits. A low-loss tapped delay bank reduces the five-use storage propagation comparison to < 0.15 dB, while an unreshaped 5-ps pulse obeys a sharp single-pole resonator time–bandwidth no-go. A macroscopic 64-seed selector-24 corpus finds 24 mixed classes, including 20 absent from the perturbative corpus, 19 of them stable.

Three independent exact probes accompany the implementation results. The W33 uniform projector is $P_0 = (A^2 + 2A - 8I)/160$, so the Grover diffusion reflection is a quadratic adjacency polynomial and four oracle calls reach success 3920137321/4000000000. The Laplacian pseudoinverse is $L^+ = (7/80)I + (1/160)A - (13/3200)J$, giving resistance distances 13/80 and 7/40 and Kirchhoff index 267/2. Finally, every diameter-four Levi interval has layer profile $(1, 4, 4, 4, 1)$ and exactly four geodesics, hence finite geodesic entropy $\log 4 = \log|\text{waist}|$. These are finite graph/control statements only: they do not establish physical quantum speedup, inertia, spacetime entropy, gravity, cosmology, or a theory of everything. The frozen semantic certificate is `db91cd6c70138d44917ba4274a7d087927caec691be5d49efd83528e7f8d4bd5`.

61 Passes 4169–4176: discrete C_2, Hawking disorder, backreaction, Gray locality, Levi-cover correction, Casimir and axion reduction

Pass 4169: discrete second-Chern compiler. For the four-dimensional Wilson–Dirac control

$$d(k) = (\sin k_1, \sin k_2, \sin k_3, \sin k_4, -3 + \textstyle\sum_i \cos k_i), \qquad H = \widehat{d} \cdot \Gamma,$$

the sixteen high-symmetry masses group as $1, -1, -3, -5, -7$ with multiplicities $1, 4, 6, 4, 1$. The oriented Dirac count gives

$$C_2 = \frac{1}{2} \sum_{N=0}^{4} \binom{4}{N} (-1)^N \operatorname{sgn}(-3 + 4 - 2N) = 1.$$

Thus sixteen calibration points certify the topological sector. A uniform central-difference response integral converges much more slowly: among the audited meshes, $N = 29$ per control axis is the first below five-percent error, with $C_2^{(29)} = 0.9504670029565596$ on $29^4 = 707281$ nodes.

Pass 4170: continuous Hawking disorder. For 512 correlated-Gaussian samples with $C_{ij} = e^{-|i-j|/2}$, $r_j \mapsto r_j e^{0.35 x_j}$, and $\Gamma_j \mapsto \text{logistic}(\text{logit}\,\Gamma_j + 0.25 x_j)$, the logarithmic negativity remains in

$$0.0822919174978226 \le E_N \le 0.5298852171115666.$$

A 721-phase quasiperiodic scan with $\alpha = (\sqrt{5}-1)/2$ and amplitude 0.7 gives $0.24211601793444767 \le E_N \le 0.27238456666720445$. With thermal occupation n_{th}, the PPT mobility edge is defined by $\widetilde{\nu}_-(\omega_c, n_{\text{th}}) = 1/2$; for $n_{\text{th}} = 0.01$, $\omega_c = 0.5783917254706858$, while at $\omega = 0.3$ the thermal threshold is $n_{\text{th}} = 0.11593620709206182$.

Pass 4171: scale–geometry backreaction. For the minimal occupied-mode feedback

$$\dot{s} = \gamma \left[\ln 80 - 4s + g\, n_B(2e^{-s}) \right],$$

$g = 1$ has a stable root $s = 1.5949469860997991$ and an unstable root $s = 2.5062250949365414$. They annihilate at the saddle node

$$(s_c, g_c) = (1.9679175210441553, 1.1252773999853873).$$

Thus this minimal positive backreaction shifts the spectral dimension away from four and ultimately destroys the stationary scale; it does not create two stable geometric branches without an additional saturation mechanism.

Pass 4172: exact locality reduction of the Gray clock. A five-qubit reflected-Gray transition flips one clock bit conditioned on four spectator literals and accompanies a two-site data SWAP, hence is directly seven-local. Three binary AND ancillas per transition encode the four spectators using the exact two-local penalty

$$P_{\mathrm{AND}}(x, y, z) = xy - 2xz - 2yz + 3z,$$

reducing each propagation term to the four-local form $f_t X_{c_t}\mathrm{SWAP}$. For twenty-four transitions this requires seventy-two static ancillas. The legal clock block is unchanged exactly, preserving spacing 2Ω, perfect transfer at $\pi/(2\Omega)$, and full revival at π/Ω.

Pass 4173: Levi-cover correction and obstruction. The committed $W(3, 3)$ geometry has forty points, forty lines, and $40(3 + 1) = 160$ flags. Hence its point–line Levi graph has eighty vertices, degree four, 160 edges, and girth eight. This supersedes the degree-six premise used in Pass 4157. The graph contains exactly 1620 simple eight-cycles. Requiring every one to acquire odd sign parity in a signed two-lift produces a 1620×160 binary system whose coefficient rank is 81 and augmented rank is 82, so the system is inconsistent. Therefore no signed two-lift can double all base eight-cycles. The correct degree-four Bethe comparison has

$$3\tanh(\beta_c J) = 1, \qquad \beta_c J = \operatorname{atanh}(1/3) = \frac{\ln 2}{2} = 0.34657359027997264.$$

Simple iterated two-lifts remain girth eight and therefore do not provide the previously assumed large-girth sequence.

Pass 4174: Hawking erasure-channel threshold. Interpreting the greybody stage as an effective pure-loss channel with $\eta_{\mathrm{eff}} = n_{\mathrm{out}}/n_{\mathrm{out}}^{\mathrm{lossless}}$, the baseline value is $0.485735597242 < 1/2$, hence the unassisted pure-loss quantum capacity is zero. Across the 512 binary disorder patterns, η_{eff} spans 0.3109129598611626 to 0.7282862738005136: 251 patterns lie in the antidegradable half and 261 above the capacity threshold. The largest effective capacity in that ensemble is 1.4224182063347266 bits per use.

Pass 4175: exact graph-spectral Casimir attraction. For the massive Levi operator $K = L + I = 5I - A$, $G = K^{-1}$ has exact distance data

$$G_{uu} = \frac{211}{855}, \quad G_1 = \frac{10}{171}, \quad G_2 = \frac{13}{855}, \quad G_3 = \frac{1}{171}, \quad G_4 = \frac{4}{855}.$$

Two unit-strength pinning defects therefore interact through

$$E_{\mathrm{int}}(u, v) = \frac{1}{2}\ln\left[1 - \frac{G_{uv}^2}{(1 + G_{uu})(1 + G_{vv})}\right] < 0,$$

with values $-1.1012191859481348 \times 10^{-3}$, $-7.436602973476341 \times 10^{-5}$, $-1.1000194923920593 \times 10^{-5}$, and $-7.04009687184613 \times 10^{-6}$ at graph distances one through four.

Pass 4176: dimensional reduction. For the parent bundle with $C_2 = 1$, the three-dimensional Chern–Simons descendant satisfies

$$\Delta\theta = 2\pi C_2 = 2\pi.$$

The closed bulk returns to the same θ mod 2π sector, while a gapped boundary Chern–Simons level shifts by one, corresponding in electronic normalization to one e^2/h Hall-sheet unit.

Evidence boundary. These are finite Wilson–Dirac, Gaussian, one-mode backreaction, clock-gadget, graph-cover, pure-loss-channel, Green-function determinant, and dimensional-reduction statements. In particular, Pass 4173 is an explicit erratum to the degree-six assumption in Pass 4157 for the $W(3,3)$ point–line Levi graph. No fabricated four-dimensional pump, observed Hawking radiation, physical spacetime backreaction, hardware-optimal clock, experimental criticality, black-hole communication result, measured Casimir force, axion detection, gravity, cosmology, or theory of everything is established.

Passes 4177–4184: fixed-carrier AF obstruction, two-mode relational compilation, Hodge decoding, PDK delay materialization, and three exact probes

The fixed 145-state carrier has SU(3) Dynkin load 16 and nonzero cubic color anomaly, so every add-only anomaly repair must add colored matter. Since every nontrivial finite-dimensional SU(3) irrep has Dynkin index at least 1/2, strict one-loop $b_0^{SU(3)} > 0$ is impossible; even the marginal $b_0 = 0$ budget cannot cancel the cubic anomaly magnitude 28. The 58-mode relational architecture admits a strict two-mode implementation with pairwise exchange plus cross-Kerr interactions on an 84-coupler, degree-four graph. For the Levi incidence matrix D, augmenting by an orthonormal basis Z of $\ker D$ gives $M = [D; Z]$ with $\sigma_{\min}(M) = 1$ and condition number $2\sqrt{2}$, yielding a globally stable arbitrary-real-amplitude decoder. The exact noncrossing delay schedule needs 919 rather than 1280 slot-units, corresponding to 0.688773172255 m aggregate passive delay at 5 ps slots and assumed group index two; current public LIGENTEC TFLN/SiN loss data imply a longest-path five-use propagation contribution below 0.015 dB, before tap/coupler and DRC effects. On the nonlinear side, interval/Krawczyk analysis proves exactly three equilibria in each selector's $1 + 12 + 27$ point-stabilizer quotient, while edge and nonedge stabilizer strata are now explicitly mapped for subsequent exhaustive work. Outside-box constructions give an exact three-channel unitary scattering polynomial, the rooted-forest partition $\det(I + tL) = (1 + 10t)^{24}(1 + 16t)^{15}$, and the signed sector lens $K = P_2 - P_{-4}$ with $K^2 = I - J/40$. No fabricated hardware, global nonlinear completeness theorem, Standard Model derivation, gravity, cosmology, or theory of everything is claimed.

Passes 4185–4192: adaptive C_2, Hawking criticality, hysteresis, exact three-local clocks, and high-girth covers

Adaptive second-Chern compilation. For the Wilson–Dirac map $d = (\sin k_1, \ldots, \sin k_4, -3 + \sum_i \cos k_i)$, the sixteen high-symmetry corners still give the exact integer certificate $C_2 = 1$. Phase-centered midpoint cubature reaches the correct rounded integer already at $7^4 = 2401$ samples and falls below five-percent response error at $9^4 = 6561$ samples, a $107.8008\times$ reduction from the prior 707281-node response mesh. This is a deterministic response-compiler improvement, not a proof of global sample minimality.

Hawking critical surfaces. For a symmetric two-mode squeezed thermal core with $r(\omega) = \operatorname{atanh}(e^{-\pi\omega/\kappa})$ and one-sided attenuation η, the finite Gaussian thresholds are

$$n_{\mathrm{ent}} = \frac{e^{2r}-1}{2}, \qquad n_{B\to A} = \sinh^2 r,$$

$$n_{A\to B} = (2\eta-1)\sinh^2 r \quad (\eta > 1/2), \qquad Q_{\text{pure loss}} = \max\left\{0, \log_2 \frac{\eta}{1-\eta}\right\}.$$

At $\omega = 0.3$ one has $r = 0.09506557725$, $n_{\mathrm{ent}} = 0.1047041033$, and $n_{B\to A} = 0.009064722057$. The analytic core is tied to the previously frozen correlated-disorder envelope but is not promoted to an arbitrary continuous five-dimensional channel theorem.

Saturating backreaction and hysteresis. The nonlinear scale flow

$$\dot{s} = \gamma\left[\ln 80 - 4s + g n_B(2e^{-s}) - 0.004\, n_B(2e^{-s})^2\right]$$

has a three-fixed-point window

$$0.4815579549 < g < 1.1377609143.$$

At $g = 0.5$, the stable branches are $s = 1.2568469367$ and $s = 4.9471634287$, separated by the unstable branch $s = 4.2806819287$. This supplies a finite scale-memory hysteresis model, not physical spacetime hysteresis.

Exact three-local autonomous clock. Each of the 24 Gray-clock transitions is split into a conditioned clock-update/transition-flag substep and a transition-flag-controlled two-site SWAP substep. With 72 static AND ancillas and 24 one-hot transition ancillas, every propagation and legality term is at most three-local. The resulting 49-state legal history chain has spectrum

$$-48\Omega, -46\Omega, \ldots, +48\Omega,$$

legal gap 2Ω, perfect transfer time $\pi/(2\Omega)$, and full revival time π/Ω.

High-girth Levi covers. The corrected degree-four $W(3,3)$ point–line Levi graph has cycle counts $N_8 = 1620$, $N_{10} = 5184$, and $N_{12} = 43200$, and free fundamental-group rank 81. A deterministic $\mathbb{Z}_{65537}$ voltage assignment has nonzero voltage on every audited simple cycle of lengths 8, 10, and 12, producing a 5,242,960-vertex cyclic cover with certified girth at least 14. Since the base fundamental group is the residually finite free group F_{81}, finite regular covers with girth tending to infinity exist abstractly.

Three outside-box closures. The two noncommuting order-three Wilczek–Zee loops from Pass 4137 have commutator trace $-1/4$, hence eigenphase cosine $-1/8$ and infinite commutator order; closed-subgroup classification then gives dense closure $SU(2)$, so they form a universal single-qubit holonomic gate set. The corrected Levi graph is bipartite Ramanujan and has exact Ihara factorization

$$\zeta^{-1}(u) = (1-u^2)^{81}(1-9u^2)(1+9u^4)^{24}(1+3u^2)^{30}.$$

Finally its exact heat trace gives a maximum diffusion spectral dimension only

$$d_s^{\max} = 3.47143073390 < 4,$$

so bare Levi diffusion does not reproduce the separate channel-balance $d_s = 4$ model.

Boundary. These are finite Wilson–Dirac, Gaussian, nonlinear mean-field, clock-gadget, graph-cover, holonomy-group, Ihara-zeta, and heat-kernel statements only. No fabricated four-dimensional pump, observed Hawking radiation, physical spacetime hysteresis, laboratory three-local processor, fabricated high-girth network, experimental holonomic universality, gravity, cosmology, or theory of everything is established.

62 Passes 4205–4212: carrier surgery, native dual rail, compressed Hodge sensing, and interval strata

The fixed 145-state carrier cannot retain its original full $PSp(4,3)$-commuting standard-charge embedding while becoming a nonzero anomaly-free generation sector. If charge labels are allowed to be surgically reassigned, the largest complete-generation sector keeping both nonabelian Weyl-matter one-loop coefficients positive has five generations: 75 gauge-charged states and 70 singlets, with $b_0^{SU(3)} = 13/3$ and $b_0^{SU(2)} = 2/3$. On the hardware side, the 58 occupation modes map to 29 logical dual-rail qubits, 87 transmons including one erasure ancilla per logical qubit, and 28 inter-logical tunable couplers on a degree-three logical tree; this is a topology map, not a fabricated 28-payload-qubit processor.

The 81-dimensional Levi harmonic readout can be compressed to ten deterministic whitened cycle channels in the audited nested family while retaining nonzero cycle/theta gains through 14-edge nullspaces; a conservative restricted singular lower bound for the resulting 90-row stacked sensor is 0.0138377. The populated photonic delay schedule contains 919 slot-units and 0.688773 m of aggregate passive delay. The point-, edge-, and nonedge-pair stabilizer fixed spaces are now interval-audited: edge fixed spaces contain five and three roots for selectors 24 and 15, while nonedge fixed spaces contain thirteen and nine.

Three finite exact probes accompany the implementation work. Critical coupling to the rank-24 $+2$ adjacency sector produces $S = I - P_2$, absorbing 3/5 of a vertex input. Any nonzero vector supported on s vertices and contained in a central W33 spectral subspace of rank d obeys $sd \geq 40$. Finally, the Levi harmonic quadratic form $E_H(x) = \frac{1}{2}x^T P_H x$ is invariant under $x \mapsto x + D^T\phi$ and has 81 independent cycle modes; the "battery" terminology is only a graph-Hodge analogy.

Passes 4214–4221: smaller covers, two-bundle holonomy, hysteretic memory, compressed clocks, and full Gaussian horizon diagnostics. The corrected degree-four $W(3,3)$ point–line Levi graph admits an explicit cyclic $\mathbb{Z}_{359}$ voltage cover in which every simple base cycle of lengths $8, 10, 12$ has nonzero voltage. Hence the cover has 28,720 vertices, 57,440 edges, and certified girth at least 14, a factor $65537/359 = 182.5543\ldots$ smaller in sheet count than the earlier construction. No global minimality is claimed.

On two rank-two singlet bundles, the dense local $SU(2)$ holonomies of Pass 4190 together with one auxiliary bright level produce a geometric controlled phase: a solid-angle 2π loop in $\mathrm{span}\{|11\rangle, |a\rangle\}$ gives Berry phase π and hence $\mathrm{CZ} = \mathrm{diag}(1,1,1,-1)$. The Pauli commutator closure has dimension 15, so dense local $SU(2) \times SU(2)$ plus this entangler is dense in $SU(4)$.

For the saturated scale flow $\dot{s} = \gamma[\ln 80 - 4s + g n_B(2e^{-s}) - 0.004 n_B(2e^{-s})^2]$, equal-well coexistence occurs at $g = 0.5700939873$. The minima $s_L = 1.2870434725$ and $s_R = 5.3097911844$ are separated by $s_B = 3.8542873087$ with barrier 4.4597412117; the dimensionless $M = 1$ instanton action is 7.7881701215. This supports a two-state quantum-memory reduction but not a physical spacetime-memory claim.

An exact MILP shares the Gray-clock spectator logic: 13 pair conjunctions, 24 final conditions, and 24 transition flags require 61 auxiliaries instead of 96, retaining exact three-local propagation,

legal gap 2Ω, perfect transfer at $\pi/(2\Omega)$, and full revival at π/Ω.

For the complete 19-mode Gaussian horizon chain, uniform thermal loading removes outside-to-partner steering at $n_{\mathrm{th}} = 0.0042826995$, positive coherent information at 0.0079250582, reverse steering at 0.0117448238, and PPT entanglement only at 0.1159362071. In the frozen 512-sample correlated-disorder ensemble at $n_{\mathrm{th}} = 0.005$, all 512 remain entangled while the stronger witnesses survive in 228, 415, and 482 samples respectively.

Three independent probes sharpen the finite boundary. The Levi spectrum $\{0, \pm 4, \pm\sqrt{6}\}$ forbids exact nonzero global CTQW revival, but the Pell solution $11760^2 - 6(4801)^2 = -6$ gives an operator near-echo error 4.0071334×10^{-4}. For $K = 5I - A_{\mathrm{Levi}}$, point–line harmonic-vacuum entropy is 2.4552973872 nats with logarithmic negativity 6.9804187391 nats. Finally, the degree-four tree radial band $E(q) = 2\sqrt{3}J\cos q$ gives $v_{\max} = 2\sqrt{3}J$ while shell capacity grows as 3^r; this graph velocity is not identified with physical c.

Renumbering and boundary. Glue-track commit 84db6db5c reserved Pass 4213 before the original physics-block reservation; the canonical physics range is therefore 4214–4221. These are finite graph-cover, holonomic, stochastic/semiclassical, clock-gadget, Gaussian-channel, recurrence, harmonic-network, and tree-band results, not fabricated hardware, observed Hawking radiation, physical spacetime memory, a speed-of-light derivation, gravity, cosmology, or a theory of everything.

Passes 4245–4252: residual symmetry, GHZ resource model, minimum Hodge sensing, routed delay geometry, and quotient closure

The five-generation carrier surgery admits a natural anchor-level residual-symmetry target: the 658008 five-subsets of the 40-point W33 action form 43 $PSp(4,3)$ orbits, and the unique largest setwise stabilizer has order 72. A representative induces $K_{1,4}$; the stabilizer fixes the center, acts as A_4 on the four leaves, and has central pointwise kernel C_6. This is an anchor scaffold, not yet a full branching theorem for the charged 75-state subspace.

On the 28-payload binary tree, physically disjoint two-qubit gates require seven entangling rounds for the 27 tree edges. At the published dual-rail operating point $F_{\mathrm{CNOT}} = 0.981$ and erasure probability 0.13, whole-circuit postselection accepts only $0.87^{27} \simeq 0.02328$ of runs, whereas heralded modular-fusion resource models reduce the expected entangler count per accepted construction from roughly 1160 to between 31.0 and 47.9, depending on restart locality. The conditional product $0.981^{27} \simeq 0.596$ remains the fidelity bottleneck.

For arbitrary real edge errors of support at most seven, exactly two global scalar measurements beyond the oriented Levi incidence matrix are information-theoretically necessary and sufficient. One row cannot be injective on a two-dimensional theta circulation space supported on at most fourteen edges; the two deterministic Pass-4147 rows give stacked spark at least 15. Thus the exact noiseless minimum is $m = 2$. The ten-channel Hodge construction remains a conditioning, rather than an injectivity, result.

The 919 delay units are now tied to explicit route centerlines. Each 5-ps slot is a rounded four-quarter-bend dogleg of radius 0.05 mm and vertical excursion 0.3176609398 mm, satisfying $2h + (2\pi - 4)r = 0.749481145$ mm. The route generator consumes the frozen Pass-4148 four-branch schedule and emits all 160 point-line identities and cell coordinates; the design remains a public-PDK centerline contract rather than proprietary DRC signoff.

The next setwise-subset rank of the nonlinear stabilizer lattice has exactly five three-vertex orbit types, with stabilizer orders $162, 72, 12, 9, 6$. Interval/Krawczyk exhaustion closes the two smallest quotient systems: the triangle stratum has $(9, 3)$ roots for selectors $(24, 15)$ and the maximally

symmetric independent-triple stratum has $(9, 9)$ roots. Three larger triple quotients and trivial-stabilizer equilibria remain open.

Three independent finite constructions accompany the implementation work. First, W33 adjacency phase sensing has $F_Q^{\max} = 256$, while a vertex probe has $F_Q = 48$, an exact ratio $16/3$ before resource/noise accounting. Second, the Levi edge Hodge split gives 81 harmonic and 79 gradient Gaussian modes; reversible entropy-conserving equalization obeys $T_* = T_H^{81/160} T_G^{79/160}$ and $W_{\max} = \frac{k_B}{2}(81T_H + 79T_G - 160T_*)$. Third, the point $\to$ ordered-edge $\to$ ordered-triangle pointwise-stabilizer chain yields quotient dimensions $3 \to 6 \to 8$ with exact refinement intertwiners $Q_6 R_{63} = R_{63} Q_3$ and $Q_8 R_{86} = R_{86} Q_6$; componentwise cubing also commutes with each refinement lift, so the cubic nonlinear vector field closes exactly along this finite coarse-to-fine hierarchy.

Passes 4253–4260: retracted cover, surviving finite models, and channel bounds

4253 (retracted by Pass 4329). The stored $\mathbb{Z}_{2731}$ voltage assignment has one zero-voltage base eight-cycle, with signed sum $1328 - 542 + 801 - 1587 = 0 \pmod{2731}$. Its 218480-vertex lift therefore has girth exactly 8, not at least 16. The historical vector is retained as a falsifier, not a cover certificate.

4254. Oppositely oriented latitude loops at $\theta = \pi/3$ and $2\pi/3$ implement the geometric controlled phase π. A common polar offset δ gives $\phi(\delta) = \pi \cos \delta$, so the first-order calibration error cancels. At $\omega/\Omega = 0.02$ the two exact nonadiabatic leakage probabilities are 3.05824×10^{-4} and 2.93842×10^{-4}.

4255. At the saturated coexistence point and $D = 0.25$, a detailed-balance finite-volume Fokker–Planck discretization converges to metastable gap 4.37527×10^{-8}, with the next rate 2.93047. The unit-prefactor two-state Lindblad demo crosses from underdamped to overdamped at $\gamma_\phi = 2\Delta = 8.29222 \times 10^{-4}$.

4256. The 24 data gates are three repeats of eight adjacent SWAP supports, so the exact three-local clock needs only eight reusable dynamic flags. Together with the frozen 13 shared pair conjunctions and 24 final conditions this gives 45 auxiliaries, preserving gap 2Ω, perfect transfer at $\pi/(2\Omega)$ and revival at π/Ω.

4257. The complete 19-mode horizon induces a baseline effective signal attenuator with $\tau = 0.2830095941$ and $\bar{n}_{\mathrm{env}} = 0.0166793553$. In the frozen 512-sample correlated-disorder ensemble, 510 samples have $\tau \le 1/2$, two have $\tau > 1/2$, and none is entanglement breaking. At $n_{\mathrm{th}} = 0.005$ the generated outside–partner state remains PPT-entangled in all 512 samples, demonstrating that state entanglement and signal-channel capacity are distinct resources.

4258–4260. The exact Levi spectral form factor has infinite-time plateau $2054/6400 = 0.3209375$, 25.675 times a nondegenerate 80-level reference, falsifying a bare random-matrix scrambling interpretation. The point–line harmonic modular spectrum has only two finite entanglement energies, 2.63391579385 and 4.03202440074, with multiplicities 1 and 24 plus 15 exact spectators. In the conditional degree-four tree model, $v_{\mathrm{rad}}^{\max} = 2\sqrt{3}J$ while $B(r) = 2\,3^r - 1$. Its 4373-vertex radius-seven ball is not realized by the retracted Pass 4253 cover.

Boundary. These are finite graph-cover, holonomic, stochastic/Lindblad, clock-compilation, Gaussian-channel, spectral, modular and tree-band statements. They do not establish fabricated devices, observed Hawking radiation, physical spacetime memory, a derivation of c, gravity, cosmology, or a theory of everything.

Passes 4261–4268: girth 18, dynamically corrected holonomy, full-coordinate metastability, clock-37, and finite outside-box probes

A cyclic voltage assignment in $\mathbb{Z}_{750019}$ makes every radius-eight sheet-zero ball above each of the 80 Levi base vertices a collision-free 4-regular tree of 13,121 vertices. Deck translation therefore excludes every lifted cycle of length at most 16 and certifies girth at least 18. The resulting 60,001,520-vertex cover is an explicit upper bound rather than a compact solution: the desired sub-10,000-sheet girth-18 construction remains open.

For the two-bundle holonomic controlled phase, choose $\cos\theta = 1/4$ and execute latitude loops at $\theta, \pi - \theta$, followed by the same pair on the opposite adiabatic eigenbranch with reversed physical orientations. The geometric phase is $-\pi\cos\delta$ under a common polar offset δ, so the first derivative vanishes at the operating point, while repeatable static loop-dependent dynamical phases cancel by echo. Adding $H_{\mathrm{CD}} = \frac{1}{2}(\mathbf{n}\times\dot{\mathbf{n}})\cdot\boldsymbol{\sigma}$ gives exact transitionless driving in the modeled two-level control. At $\omega/\Omega = 0.1$, a one-percent CD-amplitude error gives a four-loop leakage union bound 2.004×10^{-6}.

The saturated scale coordinate was then quantized directly as $H = p^2/(2M) + U(s)$ with $U' = -F$, $M = 16$, and coupled through the full coordinate operator to an Ohmic Davies bath at $T = 0.25$. On a 180-point grid the retained-basis population gap converges from 1.06×10^{-11} at $K = 14$ to 1.87223×10^{-11} at $K = 20$, corresponding to a dimensionless metastable lifetime 5.34×10^{10}. This is a finite-coordinate open-system model, not a physical spacetime-memory lifetime.

An exact local-dimension trade replaces the five binary Gray clock digits by five qutrit digits $\{0, 1, *\}$, using $*$ as the intermediate transition state. The eight explicit dynamic flags disappear, leaving 13 shared pair ancillas plus 24 final spectator-condition ancillas, hence 37 auxiliaries. The legal 49-state history, maximum locality three, gap 2Ω, perfect-transfer time $\pi/(2\Omega)$, and full revival π/Ω are unchanged.

The two previously unresolved thermal attenuator samples, $\tau = 0.5039652$ and 0.5113024, were attacked with low-Fock non-Gaussian inputs: all optimized two-Fock mixtures through $n = 8$, 2,000 random three-Fock mixtures per channel, and 5,000 random coherent rank-two states in $\{|0\rangle, \ldots, |4\rangle\}$ per channel. No positive coherent information was found. Pure inputs attain exactly zero in the purified-environment Stinespring picture, so the tested family maximum is zero; unrestricted multi-use non-Gaussian capacity remains open.

Three independent finite probes accompany the main work. The Levi distance partition $[1, 4, 12, 36, 27]$ reduces marked-vertex continuous-time search to an exact five-shell Hamiltonian and yields a concrete 73.016% success operating point. A rank-one onsite defect $V = 4$ creates a unique eigenmode above the spectral edge at $E = 4.9600853$ with 76.202% weight on the defect. Finally, the point-line harmonic thermal state has two distinct PPT death temperatures: $T_c = 0.9947197$ for the 24 $\sqrt{6}$ channels and $T_c = 1.2027283$ for the unique singular-value-4 collective channel, producing a two-stage loss of bipartite entanglement.

Passes 4269–4276: carrier branching, heralded fusion, minimum Hodge sensing, corrected GDS geometry, and finite outside-box probes

4269. The order-72 five-anchor stabilizer is $C_3 \times SL(2,3)$. Restricting the W33 eigenspaces gives an explicit 21-character branching of V_{15} and V_{24} and hence of $H_{145} = 7V_1 + 6V_{15} + 2V_{24}$. A species-wise 75-state five-generation charge partition can commute with this group, while an identical five-dimensional generation factor repeated over all 15 gauge-internal states cannot.

4270. A nondestructive GHZ-block fusion uses two anchor-to-ancilla CNOTs, one Z parity readout, and a tracked block-X frame. Under the frozen 1.3×10^{-1} erasure model, the optimized 28-qubit modular construction uses 33 accepted-path CNOTs and 94.2734 expected CNOT attempts, a 12.30× reduction versus whole-run restart; its independent conditional process factor remains only 0.53098.

4271. Two extra global measurements are both necessary and sufficient for noiseless arbitrary-real seven-sparse Levi-edge recovery. A deterministic $\mathbf{F}_{65537}$ search yields a signed-16 pair with normalized worst theta gain 1.33507×10^{-5}, 1.805× the prior pair, while preserving the exhaustive spark-15 cycle/theta certificate.

4272. The previous 0.12-mm rounded dogleg cell is geometrically impossible for four 50 μm quarter bends, and the true excursion is $h + 2r$, not h. The corrected pure-Python GDSII compiler uses 0.205-mm cells, 0.45-mm lanes and sixteen ten-lane banks, producing an 11.04 mm × 14.85 mm keepout-inclusive preliminary layout with 919 doglegs and 361 straight cells.

4273. The order-12 and order-9 triple quotients have locally certified saturated deterministic catalogues 57/27 for the two selectors, whereas the order-6 edge-plus-isolated quotient already contains at least 2376/246 locally certified roots. Among the 16 four-subset orbits, one has trivial stabilizer, so global nonlinear completion must leave the nontrivial-symmetry-stratum strategy.

4274–4276. The W33 graph state is exactly five-uniform with 240 weight-six stabilizers supported on pairs of disjoint triangles. Non-lazy Ollivier curvature is $+1/6$ on W33 edges but -1 on Levi edges. The $81 + 79$ Hodge decomposition also gives an exact two-temperature Ornstein–Uhlenbeck fluctuation–dissipation splitting.

Boundary. These are finite mathematical and engineering statements. They do not establish fabricated devices, phenomenological particle physics, continuum spacetime curvature, gravity, cosmology, or a theory of everything.

Passes 4324–4334: the chamber Hecke machine and an exact frontier correction

4324: two native chamber switches. On the 160 incident point–line chambers, let P change the line while holding the point fixed and let L change the point while holding the line fixed. Each is forty disjoint copies of the K_4 adjacency operator, and GAP proves

$$P^2 = 2P + 3I, \qquad L^2 = 2L + 3I, \qquad PLPL = LPLP.$$

The eight standard type-C_2 words are linearly independent. Thus this chamber carrier realizes the full eight-dimensional $q = 3$ Iwahori–Hecke image. Its exact module ledger is

$$1\chi_{3,3} + 15\chi_{3,-1} + 15\chi_{-1,3} + 81\chi_{-1,-1} + 24V_2,$$

which explains the long-standing flag-scheme dimensions $1 + 30 + 48 + 81 = 160$.

4325–4326: the Hashimoto turn and its chirality. With the 320 oriented Levi edges ordered by orientation,

$$B_{\mathrm{Levi}} = \begin{pmatrix} 0 & L \\ P & 0 \end{pmatrix}, \qquad B_{\mathrm{Levi}}^2 = \mathrm{diag}(LP, PL).$$

The two products are disjoint binary 9-out halves of the chamber distance-two shell. For $K = LP$,

$$\chi_K(x) = (x-9)(x-1)^{81}(x+3)^{30}(x^2+9)^{24}.$$

The antisymmetric turn $\Omega = LP - PL$ has

$$\chi_\Omega(x) = x^{112}(x^2+60)^{24}, \quad \Pi_{48} = -\Omega^2/60, \quad \operatorname{rank}\Pi_{48} = 48.$$

Consequently $\Omega/\sqrt{60}$ is a canonical complex structure on the conjugate $24 + 24$ chamber channel. This is a finite operator theorem, not a $W(G_2)$ action.

4327: exact folded-propagator normal form. Let $C = P + L$, $X = (C - 2I)\Pi_{48}$, and let F be the old folded cubic point-Hashimoto operator compressed to Π_{48}. In the four-dimensional packet algebra $\{\Pi_{48}, X, \Omega, X\Omega\}$,

$$F = -68\Pi_{48} - 31X - \frac{21}{2}\Omega + \frac{2}{3}X\Omega, \qquad (F + 68\Pi_{48})^2 = -689\Pi_{48}.$$

The old numerical -6455 is now explained exactly by the square of the off-diagonal part. No continuum propagator, particle, mass, or coupling identification follows.

4334: the $24+24$ count becomes an object-level carrier split. Let E_p, E_ℓ be the eigenvalue-2 projectors of the W33 point graph and its dual line graph, and pull them to the chamber space as orthogonal rank-24 projectors Q_p, Q_ℓ. GAP proves

$$\operatorname{im}\Pi_{48} = \operatorname{im} Q_p \oplus \operatorname{im} Q_\ell, \qquad Q_pQ_\ell Q_p = \frac{3}{8}Q_p, \quad Q_\ell Q_pQ_\ell = \frac{3}{8}Q_\ell.$$

Thus the two natural summands meet only in zero but are uniformly nonorthogonal: all 24 principal angles have cosine $\sqrt{6}/4$. With $Q = Q_p + Q_\ell$,

$$\Pi_{48} = \frac{8}{5}(2Q - Q^2) = -\frac{\Omega^2}{60}.$$

The conjugate channel is therefore literally the joined point/line eigenvalue-2 carriers, not just a multiplicity ledger.

4328: the irregular Ihara boundary corrected. Bass's determinant formula already applies to general finite graphs with $D - I$. The Kotani–Sunada theorem bounds non-real poles by

$$(d_{\max} - 1)^{-1/2} \le |u| \le (d_{\min} - 1)^{-1/2},$$

not by the same expression without square roots, and it does not put every nontrivial root in that annulus. For the shipped degree-2–8 frame graph the reciprocal-root form is $1 \le |\lambda| \le \sqrt{7}$ for the corresponding non-real roots. The old "band filling" and "closest irregular Ramanujan" metric is withdrawn.

4329: a cover certificate retracted by one cycle. The stored $\mathbb{Z}_{2731}$ voltage vector from Pass 4253 has the base eight-cycle

$$(3, 52, 4, 48, 8, 66, 18, 53)$$

with signed voltage sum $1328 - 542 + 801 - 1587 = 0 \pmod{2731}$. The lifted cover therefore has girth exactly 8, not at least 16. Pass 4260's 4373-vertex radius-seven tree ball remains a correct conditional tree count but is not realized by that cover. The valid cover ladder is the earlier $\mathbb{Z}_{359}$ girth-at-least-14 cover followed by the much larger $\mathbb{Z}_{750019}$ girth-at-least-18 cover.

4330–4331: what symmetry and fault detection actually survive. Under the literal pair swap $S(x_0, x_1, x_2, x_3) = (x_2, x_3, x_0, x_1)$, machines A/B/C/D are invariant in the pattern false/true/-false/true. Machine D therefore removes both the directed time arrow and the point/frequency structural asymmetry. Its 0.460435 peak is symmetric localization, not residual point/frequency bias. Affine translations act on the 81 frames but descend to neither projective 40-carrier, so they do not force a point-side load port.

Pass 4331's linear-opcode mismatch census tests incidence after two rails choose among three selected linear panel opcodes. It detects $1656/1920 = 69/80$ differential single-rail opcode substitutions and $0/960$ shared-control substitutions. This is narrower than the Pass 4367/4374 intrinsic flag-register comparator, which detects $36/39 = 12/13$ arbitrary one-register substitutions at $q = 3$. The earlier 95.71% number compared each faulty rail with a golden run and was not a dual-rail comparator.

4332–4333: one arithmetic component, and an honest rank. The irreducible degree-33 factor of the instruction Hashimoto pencil has exactly one real root in $(5.74, 5.75)$ and one in $(3.349, 3.350)$ by an exact Sturm certificate. Thus the global nonbacktracking growth root and the reported slow real mode are Galois conjugates in one rational primary component. The rational projector and a basis-independent localization theorem remain open.

Finally, the complete universal-set census by sizes 4 through 10 is

$$24,\ 80,\ 114,\ 90,\ 41,\ 10,\ 1,$$

totalling 360. The shipped ISA is not strictly "12th": only six sets have lower ρ at the stated tolerance, while six isomorphic sets share its numerical value and occupy positions 7–12. Size is a coarse correlate whose bands overlap, not an explanation of that tie.

Evidence boundary. The three GAP witnesses replay 31/31, 28/28, and 17/17 exact checks. The panel operators are three-way relations, not yet a deterministic opcode selector or synthesized B/D RTL. The exact finite algebra and the retractions above should therefore be read separately from hardware, continuum, thermodynamic, and phenomenological interpretations.

63 Passes 4801–4808: exact H10 radius and the local-Golay/global-homology triangle code

The 45-point $GQ(4, 2)$ triangle carrier from Passes 4795–4800 supports a sharper local-to-global code decomposition, while the binary H_{10} covering-radius problem also closes exactly.

Exact covering radius. Pass 4794 had proved $14 \le \rho(H_{10}) \le 15$ and exhibited a distance-14 coset. A distance-15 coset would contain a leader x of weight exactly 15. For each $c \in H_{10}$,

$$d(x, c) = 15 + \mathrm{wt}(c) - 2|\operatorname{supp}(x) \cap \operatorname{supp}(c)|,$$

so a weight-15 leader is exactly a 40-variable cardinality-feasibility problem. Coordinate transitivity fixes one selected coordinate. Its intersection with the corresponding weight-12 neighborhood codeword has size $a \in \{1, \dots, 6\}$. The order-648 point stabilizer has respectively

$$1, 2, 3, 6, 6, 7$$

orbits on those neighbor subsets. Exhaustive exact propagation over the resulting 25 symmetry representatives rejects every case. Hence

$$\boxed{\rho(H_{10}) = 14.}$$

The independent PySAT producer `w33_pass4801_h10_covering_radius_sat.py` encodes the same finite decision directly.

Complete weight-four logical shell. Let B be the 45×270 point–triangle incidence matrix and $C = \mathrm{row}_{\mathbb{F}_3}(B) = [270, 44, 18]_3$. For the CSS code $H_X = H_Z = B$, all projective weight-four words of $C^\perp$ were enumerated exactly. There are

$$810 = 135 + 270 + 405$$

projective minimum logicals, or 1620 including nonzero scalar multiples, and every one is supported inside exactly one of the 27 maximal K_5 fibers. Per fiber the split is $5 + 10 + 15$.

Decoder and optimal interaction schedule. The 270 columns of B are distinct weight-three vectors. Consequently the ordered X/Z syndrome pair uniquely identifies all

$$270(3^2 - 1) = 2160$$

nontrivial single-qutrit Pauli errors. The combined X/Z Tanner graph has 90 real checks of degree 18 and 270 data vertices of degree 6. An exact regular completion and one-factorization yields 18 conflict-free layers, each containing all 90 checks on 90 distinct data qutrits. The check weight gives the matching lower bound, so 18 layers are optimal in this interaction model.

Equivariant F_4/E_6 bridge and extension firewall. The Pass-4797 dependency-cube/F4 quotient crosswalk upgrades projectively to a $PSp(4, 3)$-equivariant identification of the degree-45 simple-group images,

$$U_4(2) \cong PSp(4, 3), \qquad |U_4(2)| = 25920.$$

The two order-51840 extensions remain distinct: the central double cover $Sp(4, 3) = 2.U_4(2)$ has degree-45 image 25920 with kernel 2, whereas the outer projective extension has 51840 distinct permutations. No central/outer extension identification is made.

$q = 9$ **minimum shell.** The general odd-q theorem from Pass 4754 identifies the minimum line-kernel words with BLT sets. For $q = 9$ the code has length 820 and minimum distance 10. Transferring Betten's complete BLT classification gives three full projective-semilinear orthogonal classes: Linear, K1, and Fi/Mondello, with class sizes

$$239112, \qquad 1195560, \qquad 17216064,$$

for a total shell of 18650736. This is a transfer of prior-art BLT classification; no finer $PSp(4, 9)$ orbit splitting is asserted.

Local punctured ternary Golay. The ten triangle coordinates inside one K_5 carry a local kernel

$$G_{10} = [10, 6, 4]_3$$

with enumerator

$$1 + 60z^4 + 144z^5 + 60z^6 + 240z^7 + 180z^8 + 20z^9 + 24z^{10}.$$

This is not identified from parameters alone. Exhausting all linear one-coordinate extensions gives exactly two projective extension directions to the perfect ternary Golay

$$G_{11} = [11, 6, 5]_3.$$

Adjoining both directions gives the self-dual extended ternary Golay

$$G_{12} = [12, 6, 6]_3,$$

with enumerator $1 + 264z^6 + 440z^9 + 24z^{12}$. Hence every K_5 fiber is explicitly a punctured ternary-Golay block.

Canonical local-to-global filtration. Let

$$L = G_{10}^{\oplus 27}.$$

Exact ranks and orthogonality give

$$C = [270, 44, 18]_3 \subset L = [270, 162, 4]_3 \subset C^\perp = [270, 226, 4]_3.$$

The $GQ(4, 2)$ Levi graph has $45 + 27 = 72$ vertices and 135 edges, hence

$$\dim_{\mathbb{F}_3} H_1 = 135 - 72 + 1 = 64.$$

The line-local point-sum incidence map has kernel exactly L and induces the canonical quotient isomorphism

$$\boxed{C^\perp/L \cong H_1(\mathrm{Levi}(GQ(4, 2)); \mathbb{F}_3).}$$

Thus the 182-dimensional logical space fits into the canonical exact sequence

$$0 \longrightarrow L/C \longrightarrow C^\perp/C \longrightarrow H_1(\mathrm{Levi}; \mathbb{F}_3) \longrightarrow 0,$$

with dimensions 118, 182, and 64. No canonical direct-sum splitting is asserted.

First nonlocal logical sector. Modulo L, each K_5 block has 81 possible point-sum syndromes with minimum lift costs distributed as 1 state of cost 0, 20 of cost 1, and 60 of cost 2. An exact symmetry-broken MILP excludes every nonzero global homology class of triangle-lift weight at most 5. Weight 6 is attained by induced $K_{3,3}$ subgraphs of the 27-line intersection graph: opposite signs are assigned to the two three-line parts, and each line contributes the triangle of its three intersections with the opposite part. There are exactly 360 induced $K_{3,3}$ subgraphs, furnishing a canonical projective witness family. Therefore

$$\boxed{d_{\mathrm{lift}}(C^{\perp}/L) = 6.}$$

The 360 witnesses are not claimed to exhaust the full weight-six quotient shell.

Interpretive boundary. The overall CSS distance 4 is therefore entirely local to the punctured-Golay fibers, while the first genuinely nonlocal/Levi-homological sector occurs at lift weight 6. This is an exact finite-code statement. It does not imply a fault-tolerance threshold, a microscopic Hamiltonian, or a physical energy scale.

64 Complete nonlocal Golay–Levi shell and decoder reconstruction

The local-to-global filtration of the intrinsic qutrit triangle code can be sharpened substantially. Write

$$C \subset L := G_{10}^{\oplus 27} \subset C^{\perp}, \qquad C^{\perp}/L \cong H_1(\mathrm{Levi}(GQ(4,2)); \mathbb{F}_3),$$

where $G_{10} = [10, 6, 4]_3$ is the punctured ternary Golay code on a single K_5 fibre.

Complete minimum nonlocal shell. The quotient has triangle-lift distance six. Exhausting all local cost patterns of total cost six shows that the previously exhibited 360 induced $K_{3,3}$ witnesses are complete: all mixed cost-one/cost-two patterns are empty. Thus there are exactly 360 projective minimum classes. They form one orbit under $PSp(4, 3)$, with stabilizer order 72, and one orbit under the full order-51840 outer action, with stabilizer order 144.

Exact hierarchical component decoder. A single ten-triangle fibre has exactly 81 point-syndrome states, whose minimum local lift costs occur with multiplicities

$$1 \times 0 + 20 \times 1 + 60 \times 2.$$

Consequently exact minimum-Hamming-weight decoding of one ternary X- or Z-error component reduces to choosing one of 81 states on each of the 27 fibres, minimizing the sum of their exact local costs, and imposing the 45 global point-sum constraints modulo three. The exact weight-two census is

$$145260 = 140400 + 3 \cdot 1620,$$

so every weight-two ambiguity is local Golay. At weight three the syndrome multiplicity census is

$$1^{23385600}, \quad 2^{7200}, \quad 3^{842400}, \quad 12^{2160}.$$

The 7200 twofold classes are precisely the first genuinely global ambiguity sector: they are the two complementary weight-three halves of the 720 nonzero scalar $K_{3,3}$ weight-six logicals. This statement concerns one ternary component; independent component decoding is not asserted to minimize joint qutrit Pauli support.

Global Golay extension chirality. The two projective one-coordinate extension directions $G_{10} \to G_{11}$ transform under the local S_5 by its sign character: every even permutation fixes both directions separately and every odd permutation exchanges them. Globally the resulting 54 directions form two 27-orbits under $PSp(4,3)$ but one transitive 54-orbit under the full order-51840 group. Choosing either inner sheet gives a monomially PSp-equivariant direct sum

$$G_{11}^{\oplus 27} = [297, 162, 5]_3,$$

while adjoining both directions gives the self-dual full-outer-equivariant

$$G_{12}^{\oplus 27} = [324, 162, 6]_3.$$

The full stabilizer of a base fibre has structure $2^4{:}S_5$ and order 1920; the direction stabilizer is the sign-kernel preimage $2^4{:}A_5$ of order 960. Hence the $54 \to 27$ map is the orientation cover

$$W(E_6)/(2^4{:}A_5) \longrightarrow W(E_6)/(2^4{:}S_5).$$

In particular this is not an untwisted disjoint union of two full-$W(E_6)$ invariant 27-sets; an identification with the 27 and dual-27 modules would require a representation-level intertwiner.

$q = 9$ minimum-shell splitting. Using the published $q = 9$ BLT stabilizers and evaluating their Frobenius and orthogonal/spinor outer bits, each of the three complete $P\Gamma O(5,9)$ classes already forms a single $PSp(4,9)$ orbit. The orbit/stabilizer pairs are

$$(239112, 7200), \qquad (1195560, 1440), \qquad (17216064, 100)$$

for the Linear, K1, and Fi/Mondello classes respectively. The BLT classification, names, completeness, and $P\Gamma O$ stabilizers are prior art; the additional result here is the outer-quotient evaluation and the consequent absence of further PSp splitting.

$K_{3,3}$ multidesign and intrinsic reconstruction. The complete 360-class minimum shell is simultaneously regular on three natural coordinate sets: its blocks contain six of the 27 line fibres, nine of the 45 GQ points, and six of the 270 physical triangle coordinates, with replication numbers 80, 72, and 8 respectively. Adjacent line pairs occur in 24 blocks and nonadjacent pairs in 10. Every one of the 720 independent triples in the 27-line graph is one side of a unique $K_{3,3}$, and every induced $K_{1,3}$ has a unique $K_{3,3}$ completion.

The decoder sees the same geometry intrinsically. For a projective signed $K_{3,3}$ logical, its two nonzero scalars and ten unordered $3+3$ support partitions produce exactly 20 twofold weight-three syndrome collisions. Therefore

$$360 \cdot 20 = 7200,$$

which equals the complete twofold collision census above. Subtracting the two colliding errors recovers the signed weight-six logical, so the twofold weight-three collision relation reconstructs the entire projective minimum nonlocal shell.

Complete H_{10} deep-hole census. The binary adjacency code H_{10} has exact covering radius 14, and its radius-14 cosets now admit a complete orbit classification:

82080 deep-hole cosets in 12 $PSp(4,3)$ orbits.

The inner orbit-size multiset is

$$1080^1, \quad 2160^2, \quad 3240^1, \quad 4320^2, \quad 6480^2, \quad 12960^4.$$

Each of these twelve orbit sets is preserved by the full order-51840 outer action, so there are also twelve full-group orbits and no outer fusions.

There are three coset-distribution species. Four inner orbits, 29160 cosets total, have 64 minimum leaders and distribution

$$64z^{14} + 128z^{16} + 192z^{18} + 256z^{20} + 192z^{22} + 128z^{24} + 64z^{26}.$$

Seven inner orbits, 39960 cosets total, have 96 minimum leaders and distribution

$$96z^{14} + 416z^{18} + 416z^{22} + 96z^{26}.$$

The remaining 12960-coset orbit has 56 minimum leaders and distribution

$$56z^{14} + 144z^{16} + 200z^{18} + 224z^{20} + 200z^{22} + 144z^{24} + 56z^{26}.$$

Hence there are exactly 6428160 weight-14 leaders.

Completeness is independently certified by symmetry. Fix one coordinate of a minimum leader. Its order-648 stabilizer acts on the twelve-coordinate neighborhood codeword; the allowed intersection sizes are $0, 1, \ldots, 6$, with respectively $1, 1, 2, 3, 6, 6, 7$ stabilizer orbits, only 26 representatives total. Exact branch search over the remaining 27 coordinates enforces the 511 complement-paired distance constraints and finds no leader whose 30-bit coset syndrome lies outside the twelve blocked orbit sets. The quotient-SAT orbit sieve remains an independent certificate path.

Passes 4817–4824: PGSp moduli, invariant outer codes, outage flow, and decoding

Finite S_3-moduli and the modular boundary (Passes 4817–4818). The selected three-sheet connection lives in two exact finite deformation modules: a 64-dimensional binary sign-cohomology quotient and a 225-dimensional sign-twisted $\mathbb{F}_3$ quotient. Executable generators for the full $\mathrm{PGSp}(4,3)$ action on both quotients are now installed; the selected binary sign sector is tested against the full group and the selected A_3 exponent class against its projective stabilizer. The complete astronomical orbit census is deliberately not inferred from dimensions or from the triangle rule. For the 5671-dimensional flag-graph $H^1(\mathbb{F}_2)$, GAP/CTblLib extraction of the exact characteristic-two decomposition matrix is wired to the frozen ordinary character. This determines the Brauer semisimplification once materialized, while the already exact module-level data remain: four-dimensional trivial socle, one-dimensional trivial head, all four fixed vectors in the augmentation image, and a nonsplit apartment deck line. A decomposition matrix is not promoted to a full Loewy ordering.

Complete invariant line-parity preimage family (Pass 4819). On the 27 quotient lines the even binary permutation module has the exact uniserial chain

$$0 < W_6 < W_{20} < E_{26}, \qquad \dim = (0, 6, 20, 26),$$

with irreducible successive factors of dimensions $6, 14, 6$ and both extensions nonsplit. Splitting off the all-one line leaves exactly eight PGSp-invariant outer codes of dimensions

$$0, 1, 6, 7, 20, 21, 26, 27$$

and minimum distances $\infty, 27, 12, 11, 4, 3, 2, 1$. Pullback through the canonical 27 line-parity map gives

$[2025, 378, 14], [2025, 379, 14], [2025, 384, 14], [2025, 385, 14], [2025, 398, 14], \boxed{[2025, 399, 14]}, [2025, 404, 8], [2025, 405,$

Thus 399 is the largest dimension in this complete invariant preimage family retaining distance 14.

Exact symmetry-broken fractional flow (Pass 4820). The six failure cases left bracketed in Pass 4773 are now solved exactly by stabilizer-orbit reduction plus a metric-dual cutting-plane calculation and matching rational primal certificates. At unit surviving-edge capacities and ordered all-pairs demand on surviving vertices,

$$\lambda_{\text{one hot}} = \frac{67}{5952}, \quad \lambda_{\text{two hot,adj}} = \frac{665}{59746}, \quad \lambda_{\text{two hot,nonadj}} = \frac{133}{11946},$$
$$\lambda_{\text{one fiber removed}} = \frac{189}{16538}, \quad \lambda_{\text{two fibers,adj}} = \frac{1767}{153094}, \quad \lambda_{\text{two fibers,nonadj}} = \frac{351}{30670}.$$

Each frozen certificate rechecks commodity conservation, edge capacities, dual normalization, exact rational shortest-path separation, and primal–dual equality.

Sparse decoder and optimal two-layer syndrome schedule (Pass 4821). The $[2025, 378, 14]_2$ code has an explicit rank-1647 parity-check matrix: 1485 local weight-two repetition rows, 135 local weight-four coupling rows, and 27 global weight-fifteen line rows. In the disjoint-support check model all 1647 checks schedule in exactly two layers $(945 + 702)$, and depth one is impossible. Each local $[15, 3, 7]_2$ cell has 4096 syndromes with eight representatives per syndrome and zero-syndrome weights $0, 7, 8, 15$. Consequently every arbitrary error pattern of weight at most six is decoded exactly by searching only the nonzero-local-syndrome cells, with raw bound at most 8^6, and the global 27 syndrome bits select the unique candidate.

Binary Levi cut/homology bridge (Pass 4822). The 27 global router checks are literally the pullback of the 27 line-vertex star vectors in the binary cut space of the 72-vertex, 135-edge Levi graph of $GQ(4, 2)$; they are not homology checks. The same Levi graph has binary H_1 dimension 64 and girth 8. Repeating a Levi cycle on the three sheet coordinates and applying the local physical generator map gives an exact

$$\boxed{[2025, 64, 96]_2}$$

homology subcode with $w_{\text{phys}} = 12 w_{\text{Levi}}$. The equal dimension 64 of the ternary Levi homology in Pass 4807 is not used to identify the two coefficient-field modules.

Selected-connection invariant and transfer falsifier (Passes 4823–4824). The selected A_3 exponent class is now represented explicitly in the 225-dimensional twisted $\mathbb{F}_3$ quotient; the certified producer computes its $PSp/PGSp$ fixed-space dimensions and tests whether its projective line is the unique PSp-invariant line rather than inferring uniqueness from the triangle condition. Independently, binary Levi homology has

$$\dim H_1^{PSp} = 0, \qquad \dim(H_1)_{PSp} = 0.$$

Hence

$$\mathrm{Hom}_{PSp}(\mathbf{1}, H_1) = \mathrm{Hom}_{PSp}(H_1, \mathbf{1}) = 0,$$

so none of the four characteristic-two trivial flag-H^1 socle lines transfers linearly and equivariantly into Levi homology. This closes the tempting same-characteristic bridge by an explicit module obstruction.

Evidence boundary. All promoted numerical statements above are exact finite graph, code, module, homology, decoder, or fractional-flow results. Pass 4817 deliberately leaves the complete orbit enumeration of 2^{64} sign sectors and $PG(224,3)$ points to the installed finite-action computation. Pass 4818 separates the Brauer semisimplification from the still-harder complete nontrivial Loewy extension ordering. No physical gauge field, measured hardware timing, or fault-tolerance threshold is inferred.

64.1 Passes 4825–4832: maximal distance-14 decoding, intrinsic dual shells, and Levi-cycle coding

The maximal member of the $PGSp(4,3)$-invariant line-parity preimage family from Pass 4819 is

$$[2025, 399, 14]_2.$$

Its outer code is $W_{20} + \langle \mathbf{1} \rangle = [27, 21, 3]_2$, whose dual is the six-dimensional $W_6 = [27, 6, 12]_2$. Consequently the physical parity-check rank is

$$1620 + 6 = 1626 :$$

the 1620 local K_6-cell checks of Pass 4821 plus six global W_6 checks. The local syndrome cosets are unchanged: there are 4096 local syndromes with eight representatives each, and no nonzero zero-local-syndrome word has weight below seven. Hence the same local-coset search, now filtered by six outer syndrome bits, uniquely corrects every arbitrary physical error of weight at most six. Any two distinct nonzero W_6 words intersect, so six separate global check layers are necessary; together with the two local layers this gives a certified eight-layer schedule upper bound. Global optimality of the combined eight layers is not asserted.

The dual shells of this $[2025, 399, 14]_2$ code recover the router geometry without importing the router labels. The 2025 generator columns form exactly 540 equivalence classes:

$$405 \times 4 \; + \; 135 \times 3.$$

The size-four classes are the cold $K_{2,2}$ blocks and the size-three classes are the Petersen-hot triples. The complete weight-two dual shell has 2835 words and spans dimension 1485. After quotienting this span, the residual dual has length 540, dimension 141, and minimum weight four. Its minimum shell consists of exactly 135 disjoint relations of class-size profile $(4, 4, 4, 3)$; these partition all 540 quotient coordinates and reconstruct the 135 physical K_6 cells. The six outer W_6 dual directions have quotient weights 180 or 240, so they cannot create additional weight-four relations.

The binary Levi-homology code of Pass 4822 also admits a sharper exact description. It is

$$0^{405} \oplus \mathrm{Rep}_{12}(H_1(\mathrm{Levi}(GQ(4,2)); \mathbb{F}_2)) \,,$$

so puncturing the forced-zero hot coordinates gives $[1620, 64, 96]_2$. The Levi graph has 72 vertices, 135 edges, cycle dimension 64, girth eight and 1080 eight-cycles; these 1080 cycles give exactly the minimum weight-96 physical words. A sparse dual basis has 405 hot singleton rows, 1485 repetition rows and 71 Levi-star rows, for rank 1961. Maximum-likelihood decoding reduces exactly to a minimum-weight T-join problem on the Levi graph after compressing each twelvefold repetition block, and $d = 96$ guarantees correction of every error of weight at most 47.

A tempting count coincidence is explicitly rejected. Pass 4812 has twelve $PSp(4,3)$ orbits of H_{10} deep holes, while the 270-residue action has rank twelve. Their homogeneous orbit-size and stabilizer multisets differ, so there is no componentwise PSp-equivariant identification of the two twelve-part decompositions.

Four heavier exact computations are installed but are not promoted here until their generated certificates materialize: the characteristic-two Brauer/Loewy closure of the 5671-dimensional flag H^1; the Burnside quotient of the 64-dimensional sign-cohomology module; arbitrary-ρ outage-flow phase diagrams; and the common-generator intertwiner test between the two independent 64-dimensional binary cohomology modules. This boundary is deliberate: installed producers are not theorem evidence until their outputs are frozen.

64.2 Passes 4833–4840: invariant Levi subcode, three-layer scheduling, and binary–ternary cycle incidence

The binary Levi repetition-cycle code sits strictly inside the maximal distance-14 line-parity preimage. On the common 2025-coordinate carrier one has the exact inclusions

$$C_{\mathrm{Levi}} \le C_{378} \le C_{399},$$

where

$$\dim C_{\mathrm{Levi}} = 64, \qquad \dim C_{378} = 378, \qquad \dim C_{399} = 399.$$

Thus $\dim(C_{399}/C_{\mathrm{Levi}}) = 335$. Moreover, puncturing the 405 hot coordinates is injective on C_{399}, so the ambient code retains dimension 399 on the 1620 cold coordinates. The Levi code is $PGSp(4,3)$-invariant, but no invariant complement or direct-summand interpretation is inferred.

The syndrome schedule of the $[2025, 399, 14]_2$ code admits a substantial correction and improvement. The earlier eight-layer construction treated the six global W_6 checks as fixed physical representatives. However, the fourfold cold repetition classes allow a global functional to be shifted by local dual checks among four equal physical coordinates. For the canonical sparse rank-1620 local basis, an exact finite search yields a W_6 basis of weights

$$12, 12, 16, 12, 12, 12$$

with maximum coordinate multiplicity four. Assigning active global occurrences injectively to the four repeated physical representatives puts all six global checks into a single third layer, while retaining the two local layers of sizes 945 and 675. Therefore

$$\boxed{\text{optimal sparse-check schedule depth} = 3}.$$

Two layers are impossible in this stated model: the connected bipartite local-cell conflict graph fixes the local two-colouring up to swap and leaves at most one globally usable representative in each logical repetition class. Six outer basis supports would then have to be disjoint on 27 outer coordinates, forcing total outer weight at most 27, whereas every W_6 basis has total weight at least $6 \cdot 12 = 72$. This theorem supersedes the previous eight-layer upper-bound paragraph and the first, overly rigid six-layer continuation argument; it is not a hardware clock-depth claim.

The low intrinsic dual shells do *not* by themselves recover the global router geometry. Pass 4832 gives 540 generator-column classes, namely 405 cold classes of size four and 135 hot classes of size three. The 135 minimum quotient relations, each of type $(4, 4, 4, 3)$, partition all 540 classes. Consequently the specified dual-shell design is simply 135 disconnected typed cells and has exact class-level automorphism group

$$\boxed{S_3^{135} : S_{135}}.$$

The physical-coordinate design has additional internal repetition-class symmetry containing $S_4^{405} \times S_3^{135}$. This is vastly larger than $PGSp(4,3)$ and proves that the weight-two shell plus minimum

quotient shell alone cannot reconstruct the 45 packets, 27 generalized-quadrangle lines, Petersen fibers, or global router action. Higher-shell/full-code relations are necessary to break the free S_{135} cell symmetry.

The complete minimum shell of the Levi code is also now classified. Its 1080 weight-96 words are exactly the twelvefold repetitions of Levi eight-cycles, equivalently the 1080 four-cycles of the 27-line graph $\mathrm{SRG}(27, 10, 1, 5)$. They form one $PSp(4, 3)$ orbit and one $PGSp(4, 3)$ orbit, with stabilizer orders

$$24 \qquad \text{and} \qquad 48,$$

respectively. Relative to any fixed minimum word, the other minima split by the number of shared Levi edges as

$$0^{759}, \qquad 1^{192}, \qquad 2^{88}, \qquad 3^{24}, \qquad 4^{16}.$$

Finally, the relation between these 1080 binary minima and the 360 induced-$K_{3,3}$ ternary homology witnesses is objectwise rather than numerical. A binary minimum four-cycle is incident with a ternary witness precisely when its four quotient-line vertices lie inside the six vertices of the induced $K_{3,3}$. The exact biregular law is

$$\boxed{1080_3 - 360_9},$$

that is, every binary cycle lies in exactly three induced $K_{3,3}$s and every induced $K_{3,3}$ contains exactly nine binary cycles. Hence

$$1080 \cdot 3 = 360 \cdot 9 = 3240.$$

The incidence graph is connected; its incidence-matrix ranks over $\mathbb{F}_2, \mathbb{F}_3, \mathbb{F}_5, \mathbb{F}_7$ are respectively

$$324, \qquad 359, \qquad 360, \qquad 360.$$

The coarse partition of pairs of binary minima only by shared-edge count is not itself an association scheme: already in the shared-one-edge relation the number of common same-relation neighbours takes the three values $30, 31, 36$.

The four heavy carryovers are now closed as well. The characteristic-two Brauer semisimplification of the 5671-dimensional invariant-flag cohomology is

$$71 \cdot 1 + 70 \cdot 4_a + 70 \cdot 4_b + 154 \cdot 6 + 70 \cdot 14 + 56 \cdot 20_a + 56 \cdot 20_b + 14 \cdot 64.$$

Together with the exact trivial socle dimension 4 and trivial head dimension 1, at least 66 trivial composition factors are forced into internal nonsplit layers, so the Loewy length is at least three; the full nontrivial Loewy ordering remains open. On the 64-dimensional binary sign-cohomology module, exact Burnside enumeration gives 711679993497112 PSp-orbits and 355840805040988 $PGSp$-orbits. The linear fixed space is zero for both groups, hence the canonical all-odd affine signing is the unique fully symmetric sign sector. Moreover, the sign-cohomology module and binary Levi homology are $PGSp$-isomorphic: the simultaneous intertwiner space has dimension one and its unique nonzero element has rank 64. Finally, all six failed-router capacity functions are now exact piecewise-rational lower envelopes in the hot/cold capacity ratio ρ; every failure type shifts the intact-router phase boundaries, while the value at $\rho = 1$ reproduces the independently frozen Pass 4820 optimum in each case.

64.3 Passes 4841–4848: orbital refinement, modular incidence codes, and the first cross-cell reconstruction threshold

The 1080 minimum words of the binary Levi code carry a substantially finer symmetry than their shared-edge census suggests. The stabilizer of one minimum word has order 24 in $PSp(4,3)$ and 48 in $PGSp(4,3)$, and exact stabilizer-orbit enumeration gives permutation ranks

$$\boxed{59 \quad \text{and} \quad 49},$$

respectively. The corresponding subdegree censuses are

$$1^1, 3^1, 4^2, 6^2, 12^{18}, 24^{35}$$

for PSp, and

$$1^1, 3^1, 4^2, 6^2, 12^{16}, 24^{18}, 48^9$$

for $PGSp$. Thus the outer involution fuses ten pairs of inner suborbits, and the coarse partition by the number of shared Levi edges is only a strong quotient of the true orbital algebra.

Let $M \in \{0,1\}^{1080\times 360}$ denote the incidence matrix from binary Levi minimum cycles to the 360 induced-$K_{3,3}$ ternary witnesses of Pass 4840. Its modular ranks are

$$\operatorname{rank}_{\mathbb{F}_2} M = 324, \qquad \operatorname{rank}_{\mathbb{F}_3} M = 359, \qquad \operatorname{rank}_{\mathbb{F}_5} M = \operatorname{rank}_{\mathbb{F}_7} M = 360.$$

The binary right kernel is an exact

$$\boxed{[360, 36, 20]_2}$$

code. Exact integer optimization proves distance twenty, and an exclusion certificate shows that its complete minimum shell contains exactly 36 words. Each such minimum word consists of all twenty induced $K_{3,3}$ witnesses contained in a twelve-line carrier

$$\boxed{K_{6,6} \setminus M_6}.$$

The 36 carriers form one PSp orbit and one $PGSp$ orbit, with stabilizer orders 720 and 1440. The 36 minimum words span dimension 35; every one of the 360 $K_{3,3}$ witnesses lies in exactly two minima, so the XOR of all 36 minimum words vanishes. The remaining one-dimensional quotient of the binary kernel by this minimum-word span is left unresolved.

Characteristic three collapses in a completely different way. Every binary cycle is incident with exactly three $K_{3,3}$ witnesses, so $M\mathbf{1} = 0$ modulo three. Since $\operatorname{rank}_{\mathbb{F}_3} M = 359$,

$$\boxed{\ker_{\mathbb{F}_3} M = \langle \mathbf{1} \rangle}.$$

Thus the complete ternary column relation is the single global sum of all 360 projective witnesses.

Over characteristic zero the columns are independent. In fact

$$M^T M = 9I + A,$$

where A is the connected 18-regular graph on the 360 $K_{3,3}$ witnesses obtained by joining two witnesses when they share a binary Levi cycle. It has 3240 edges, diameter four, uniform distance shells

$$1, 18, 108, 227, 6,$$

and exact adjacency spectrum

$$18^1,\ (-5)^{60},\ (-2)^{84},\ (-1)^{81},\ 4^{64},\ \left(\frac{13\pm\sqrt{97}}{2}\right)^{20},\ \left(\frac{1\pm\sqrt{73}}{2}\right)^{15}.$$

Hence the squared singular values of M are

$$27^1,\ 4^{60},\ 7^{84},\ 8^{81},\ 13^{64},\ \left(\frac{31\pm\sqrt{97}}{2}\right)^{20},\ \left(\frac{19\pm\sqrt{73}}{2}\right)^{15}.$$

The graph is not distance-regular, despite its uniform shell sizes. The rank defects in characteristics two and three are therefore genuinely modular.

The intrinsic-code reconstruction threshold can now be stated exactly. Pass 4832 gives a 141-dimensional dependency code on the 540 repetition classes. Its 135 disjoint local minimum relations are independent, so exactly six cross-cell dimensions remain. These are the global

$$W_6 = [27, 6, 12]_2$$

sector, with enumerator $1+36z^{12}+27z^{16}$. On the 540 class carrier this becomes the cross-cell shell

$$36z^{180} + 27z^{240}.$$

The six-dimensional residual generator has 135 zero columns, precisely the hot classes, and 27 distinct nonzero column types, each repeated on 15 cold classes. The three cold classes in every local cell therefore acquire three intrinsic quotient-line labels. Grouping the 135 cells by their unordered triple of such labels produces exactly 45 triples, each repeated on three sheets. Thus

$$\boxed{27 \text{ line types} + 45 \text{ line triples} = GQ(4,2)}$$

is recovered from the code shells themselves. This repairs the Pass 4839 falsifier: the local weight-two/minimum-weight-four shells alone are insufficient, but adjoining the first six-dimensional cross-cell shell is sufficient. At the quotient-class level the resulting shell-design automorphism group is

$$\boxed{S_3^{45} : \mathrm{Aut}(GQ(4,2))},$$

with $|\mathrm{Aut}(GQ(4,2))| = 51840$; the S_3^{45} kernel permutes the three indistinguishable sheet cells above each recovered point. This is not yet a theorem about the complete 2025-coordinate code automorphism group.

Finally, the quotient metric from the invariant inclusion $C_{\mathrm{Levi}} \le C_{399}$ is exact. One local $[15,3,7]_2$ cell has nonzero weights $7,7,7,8,8,8,15$, so an ambient word of weight fourteen consists of exactly two weight-seven singleton generators. Since the outer code has distance three, those generators must carry the same quotient-line label. Therefore the complete ambient weight-fourteen shell has

$$27\binom{15}{2} = 2835$$

words. As $d(C_{\mathrm{Levi}}) = 96$, all 2835 give distinct nonzero Levi cosets, and hence

$$\boxed{\dim(C_{399}/C_{\mathrm{Levi}}) = 335, \qquad d_{\mathrm{coset}} = 14}$$

with exactly 2835 minimum cosets. No $PGSp$-module splitting is inferred from this quotient-metric statement.

64.4 Passes 4849–4856: the E_6 switching code, orbital algebra, and oriented ternary lift

The one-dimensional gap left in Pass 4848 admits an exact geometric resolution. Let M be the 1080×360 binary incidence matrix between Levi eight-cycles and induced $K_{3,3}$ witnesses, and let

$$K = \ker_{\mathbb{F}_2} M = [360, 36, 20]_2.$$

Its 36 minimum words are exactly the twelve-line $K_{6,6}$-minus-matching carriers. Cross-certification with Pass 4659 identifies these carriers objectwise with the classical 36 cubic-surface double-sixes. Every $K_{3,3}$ lies in exactly two such carriers, so the 36×360 minimum-shell incidence matrix is the vertex–edge incidence matrix of

$$H_{36} = \mathrm{SRG}(36, 20, 10, 12),$$

whose complement is the previously certified $\mathrm{SRG}(36, 15, 6, 6)$ double-six overlap graph. Consequently the minimum shell spans the 35-dimensional binary cut code of H_{36}.

An independent construction from the E_6 Cartan matrix produces 72 roots and 36 projective root pairs. Their nonorthogonality graph $|\langle r, s\rangle| = 1$ is explicitly isomorphic to H_{36}, and under this isomorphism the full order-51840 action on the double-sixes is conjugate to the Weyl action $W(E_6)$ on projective roots. Choosing a positive root from each pair and recording the edges with negative root inner product gives a weight-120 vector $\sigma_{E_6} \in K$ with

$$K = \mathrm{Cut}(H_{36}) + \langle \sigma_{E_6} \rangle.$$

The corresponding signed adjacency matrix has spectrum $10^6 + (-2)^{30}$, and $2I + B$ is the rank-six projective-root Gram matrix with nonzero spectrum 12^6.

The nontrivial switching coset has exact minimum 120. If N_- is the number of negative nonorthogonal pairs among one representative from each projective root pair, then

$$\left\| \sum r \right\|^2 = 792 - 4N_-.$$

For a positive E_6 root system, $\sum r = 2\rho$ and $\|2\rho\|^2 = 312$, giving $N_- = 120$. Equality orientations are Weyl chambers; opposite chambers yield the same edge signing. Hence the complete coset-minimum shell has $51840/2 = 25920$ words. The full group is transitive on them with stabilizer two, while $PSp(4, 3)$ splits them into two orbits of 12960.

The characteristic-two extension

$$0 \longrightarrow \mathrm{Cut}(H_{36}) \longrightarrow K \longrightarrow \mathbb{F}_2 \longrightarrow 0$$

is nonsplit for both $PSp(4, 3)$ and its full outer extension. Both groups are transitive on the 360 coordinates, so the ambient fixed space is the all-one line; that vector is not in K because every defining incidence row has odd weight three. Thus the trivial quotient has no fixed lift. The dual code is

$$K^\perp = [360, 324, 3]_2,$$

and its 1080 minimum words are precisely the E_6-sign-even triangles of H_{36}, equivalently the binary Levi cycles. The exact low shell below weight 64 is

$$A_{20} = 36, \quad A_{38} = 360, \quad A_{40} = 270, \quad A_{54} = 1200, \quad A_{56} = 3240, \quad A_{58} = 2160, \quad A_{60} = 540.$$

The full coordinate automorphism group of K has order 51840 and is the certified $W(E_6) \cong PGSp(4,3)$ action on projective roots/double-sixes. Maximum-likelihood decoding reduces to two signed switching/MaxCut problems on H_{36}, one for each cut-code coset; $d = 20$ gives bounded-distance radius nine.

The 1080-point Levi-minimum orbital algebras can also be resolved exactly. For $PSp(4,3)$ the orbital algebra has dimension 59 and center dimension 15, with complex Wedderburn type

$$\mathbb{C}^7 \times M_2(\mathbb{C})^4 \times M_3(\mathbb{C})^4$$

and rational center

$$\mathbb{Q}^9 \times \mathbb{Q}(\sqrt{-3})^3.$$

For the full $PGSp$ action the corresponding values are dimension 49, center dimension 13, and

$$\mathbb{C}^6 \times M_2(\mathbb{C})^4 \times M_3(\mathbb{C})^3, \qquad Z(\mathcal{A}_{\mathbb{Q}}) \cong \mathbb{Q}^{13}.$$

Thus the outer involution fuses ten stabilizer orbitals and removes the three Eisenstein center factors. The $K_{3,3}$ incidence Gram operator is especially sparse in the full orbital basis,

$$MM^T = 3A_0 + A_1 + A_5,$$

but is not central; its commutant inside the 49-dimensional orbital algebra has dimension 27. Split-versus-division status of every noncommutative rational simple block is not asserted without explicit rational matrix units.

The residual three-sheet symmetry in the $[2025, 399, 14]_2$ code is likewise resolved, but as a falsifier of the earlier goal. The S_3^{45} action is a genuine automorphism subgroup of the complete classical code: the three sheet cells over every recovered $GQ(4,2)$ point are identical copies with the same outer labels. Together with arbitrary permutations inside equal generator-column classes, the full coordinate automorphism structure is

$$\left(S_4^{405} \times S_3^{135}\right) \rtimes \left(S_3^{45} \rtimes PGSp(4,3)\right).$$

No higher intrinsic codeword or dual shell can remove this sheet kernel; breaking it requires structure external to the binary code, such as fixed placement, timing, dynamics, or labels.

Finally, the binary cycle–$K_{3,3}$ incidence has a precise but twisted ternary lift. Pass 4807 gives

$$C^{\perp} / \bigoplus_{27} G_{10} \cong H_1(\mathrm{Levi}(GQ(4,2)); \mathbb{F}_3), \qquad \dim = 64.$$

The 1080 projective Levi eight-cycle lines span all 64 dimensions, while the 360 canonical projective $K_{3,3}$ weight-six witnesses span only 54, leaving a ten-dimensional quotient. The unweighted 1080×360 incidence matrix has ternary rank 359 and kernel $\langle \mathbf{1} \rangle$, but an exact sign-gauge feasibility test proves that no choice of projective $\pm$ orientations makes the signed sum of all 360 homology witnesses vanish. Hence the unweighted projective incidence quotient cannot factor linearly to the $K_{3,3}$ homology map.

The correct object is the oriented 720-object double cover: deck reversal acts by -1, and the anti-invariant map sending an oriented $K_{3,3}$ to its signed 18-edge Levi flow is $PGSp$-equivariant with rank 54 and kernel dimension 306. Via the Pass 4807 isomorphism this gives a canonical 54-dimensional subspace of the nonlocal ternary Golay/Levi logical quotient. The complementary ten dimensions are left unidentified pending an explicit module-theoretic construction.

All statements in this subsection are exact finite root, graph, code, group, and homology results. No physical E_6 field, particle assignment, hardware clock depth, or experimental threshold is inferred.

64.5 Passes 4857–4864: rational orbital splitting, the Steiner two-graph, and the ternary adjoint quotient

The rational ambiguity left by Pass 4850 can be closed completely. The full projective action is the already certified Weyl action $PGSp(4,3) \cong W(E_6)$. Combining the exact Pass 4850 center and complex block multiplicities with the classical Schur-index-one theorem for the exceptional Weyl groups gives

$$\mathcal{A}_{PGSp,\mathbb{Q}} \cong \mathbb{Q}^6 \times M_2(\mathbb{Q})^4 \times M_3(\mathbb{Q})^3.$$

Writing $K = \mathbb{Q}(\sqrt{-3})$, restriction to the index-two projective symplectic subgroup yields

$$\mathcal{A}_{PSp,\mathbb{Q}} \cong \mathbb{Q}^3 \times K^2 \times M_2(\mathbb{Q})^2 \times M_2(K) \times M_3(\mathbb{Q})^4.$$

Thus every noncommutative rational factor is split over its center. The Schur-index theorem itself is classical prior art; the statement here is its exact allocation to the explicitly reconstructed 1080-point orbital algebras.

The ten ternary homology dimensions left outside the canonical oriented $K_{3,3}$ span are also no longer anonymous. Exact induced matrices on

$$Q_{10} = H_1(\mathrm{Levi}(GQ(4,2)); \mathbb{F}_3)/\langle K_{3,3} \text{ witnesses} \rangle$$

have endomorphism ring exactly $\mathbb{F}_3$ for both PSp and $PGSp$; exhaustive cyclic-span testing of all 29524 projective nonzero vectors proves absolute irreducibility. Independently, in $PG(4,3)$ the standard five-dimensional orthogonal form has projective norm-class sizes

$$40, \quad 45, \quad 36.$$

The nonorthogonality graph on the 36 norm-two points is exactly the double-six graph $\mathrm{SRG}(36, 20, 10, 12)$. Using the same eight $PGSp$ generators, the 36-point action lifts to orthogonal 5×5 matrices, and their exterior squares give a ten-dimensional module. The simultaneous intertwiner space

$$\mathrm{Hom}_{PGSp}(Q_{10}, \Lambda^2 \mathbb{F}_3^5)$$

has dimension one and its nonzero map has rank ten. Hence

$$\boxed{Q_{10} \cong \Lambda^2(\mathbb{F}_3^5)}$$

equivariantly. Under the standard bivector-to-skew-endomorphism map this is $\mathfrak{so}_5(\mathbb{F}_3) \cong \mathfrak{sp}_4(\mathbb{F}_3)$. The transported commutator bracket has zero center and full ten-dimensional derived algebra, satisfies Jacobi exactly, and is preserved by all common $PGSp$ generators. This is a finite characteristic-three Lie-algebra theorem, not a continuum gauge-field claim.

The E_6 switching sign likewise admits a root-free definition. The 36 cubic-surface double-sixes have 1200 triangles in their overlap-six graph. Their triple intersections split exactly as

$$1080 \times 4 \quad \sqcup \quad 120 \times 0.$$

The 120 empty-triple-intersection triangles are precisely the independently reconstructed Steiner trihedral-pair triples. Let

$$\delta : \mathbb{F}_2^{360} \longrightarrow \mathbb{F}_2^{1200}$$

record triangle parity. Exact elimination gives $\operatorname{rank} \delta = 325$. If p_{St} is the characteristic vector of those 120 Steiner triangles, then the parity equation $\delta\sigma = p_{\mathrm{St}}$ is solvable and its full solution set

has dimension 35, exactly the graph cut-space dimension. Therefore the switching class is uniquely determined modulo cuts by Steiner incidence alone. The root-inner-product signing of Pass 4849 is an independent representative of that same class.

This yields the exact two-graph description

$$\boxed{K_{360} = \delta^{-1}(\langle p_{\mathrm{St}} \rangle)}.$$

Its kernel over the Steiner parity line is the 35-dimensional cut space. The 1080 non-Steiner/even-sign triangles span exactly 324 dimensions and are the binary Levi minimum checks, so

$$K_{360}^{\perp} = \langle \text{1080 even Steiner triangles} \rangle = [360, 324, 3]_2.$$

For the nontrivial switching coset of K_{360}, an exact rank-six E_6 root-sum dynamic program gives the complete 2^{35}-word enumerator on forty even weights from 120 through 198, beginning with the 25920 Weyl-chamber minima. The ordinary cut-space Ising polynomial does not collapse to that rank-six statistic and remains open. The covering radius is likewise not promoted as exact: a symmetric signed-graph witness together with an exact rational LDL certificate gives the lower bound 124, while orthogonal-array strength two from $d(K_{360}^{\perp}) = 3$ gives the universal upper bound 179:

$$\boxed{124 \le \rho(K_{360}) \le 179}.$$

Finally, Pass 4851 showed that the S_3^{45} sheet action in C_{399} is a genuine code symmetry. The minimal local datum that removes it is a full bijection between the three physical sheet cells above each recovered $GQ(4,2)$ point and its three incident quotient-line ports. There are six such bijections and the local S_3 action on them is simply transitive, so the stabilizer is trivial and the datum is minimal. A global system of these port matchings leaves a diagonal/cocycle copy of $PGSp(4,3)$; adjoining the previously certified global chirality choice reduces that stabilizer to $PSp(4,3)$. This removes compilation ambiguity without changing the abstract code parameters or decoder guarantee.

65 Intrinsic ternary filtration, Steiner clique homology, and the closed cut enumerator

This section records the exact finite results of Passes 4865–4867, 4869, 4871, and 4872. The evidence boundary is important: all statements below are finite graph, code, module, Lie-algebra, or compiler theorems. They do not by themselves identify a continuum gauge field, a particle multiplet, or a physical coupling. In particular, the covering radius of the binary $[360, 36, 20]_2$ code is *not* closed here; the exact bound from the prior packet remains $124 \le \rho \le 179$.

65.1 The 64-dimensional ternary Levi homology has a canonical radical

Let H_1 denote the 64-dimensional cycle space of the $GQ(4,2)$ Levi graph over $\mathbb{F}_3$, and let $K_{54} \subset H_1$ be the 54-dimensional module generated by the oriented local $K_{3,3}$ witnesses. Restrict the standard edge dot product to H_1. Its Gram matrix has rank 35, hence radical

$$R_{29} = \mathrm{rad}(H_1), \qquad \dim R_{29} = 29.$$

The exact reconstruction proves

$$R_{29} \subset K_{54}, \qquad \mathrm{rank}\langle\ ,\ \rangle|_{K_{54}} = 25.$$

Thus the previously observed $54 + 10$ quotient is controlled by a canonical bilinear-form defect rather than by an arbitrary choice of complement.

Under both $PSp(4,3)$ and $PGSp(4,3)$, the radical has the invariant diamond

$$0 < S_{14} < M_{19}, M_{24} < R_{29}, \qquad M_{19} \cap M_{24} = S_{14}, \qquad M_{19} + M_{24} = R_{29}.$$

The successive irreducible dimensions are

$$R_{29} : 14, 5, 10, \qquad K_{54} : 14, 5, 10, 25, \qquad H_1 : 14, 5, 10, 25, 10.$$

Exact splitting systems show that both

$$0 \longrightarrow R_{29} \longrightarrow K_{54} \longrightarrow Q_{25} \longrightarrow 0$$

and

$$0 \longrightarrow K_{54} \longrightarrow H_1 \longrightarrow Q_{10} \longrightarrow 0$$

are nonsplit for both PSp and $PGSp$. After quotienting by the radical, the pairing is nondegenerate and gives the canonical orthogonal decomposition

$$H_1/R_{29} \cong Q_{25} \perp Q_{10}.$$

The resulting 10-space is explicitly intertwined with the previously certified adjoint quotient.

65.2 The Steiner triples are exactly the maximal triangles

Let H_{36} be the double-six graph, $\mathrm{SRG}(36, 20, 10, 12)$. Its clique complex has

$$f = (36, 360, 1200, 1080, 216).$$

Its maximal cliques are exactly 216 copies of K_5 and 120 maximal triangles. Those 120 maximal triangles are precisely the Steiner trihedral pairs. Equivalently, a double-six triangle is Steiner exactly when it has no common neighbor. Every other triangle has exactly four common neighbors and lies in exactly two K_5's. This removes cubic-surface coordinates from the definition of the Steiner subset itself.

Over both $\mathbb{F}_2$ and $\mathbb{F}_3$, the boundary ranks are

$$(\operatorname{rank} d_1, \operatorname{rank} d_2, \operatorname{rank} d_3, \operatorname{rank} d_4) = (35, 325, 755, 216),$$

with Betti numbers

$$(1, 0, 120, 109, 0).$$

There is nevertheless a sharp characteristic boundary. The 1080 non-Steiner triangle boundaries span rank 324 over $\mathbb{F}_2$ but rank 325 over $\mathbb{F}_3$. Hence the one-dimensional even-triangle defect that defines the binary Steiner switching parity is genuinely characteristic two. Over $\mathbb{F}_3$, H_2 identifies with the 120-dimensional permutation module on the Steiner triangles, and exact common-generator calculations give

$$\mathrm{Hom}_{PSp}(H_2, Q_{10}) = 0, \qquad \mathrm{Hom}_{PSp}(Q_{10}, H_2) = 0.$$

Thus there is no linear PSp-equivariant Steiner-H_2/adjoint bridge. Any such bridge must use a nonlinear operation, a change of characteristic, or additional structure.

65.3 The ordinary cut polynomial and the complete binary enumerator

Marking one double-six exposes six opposite columns. The other 35 double-sixes become the 15 duads and 20 triads of this six-set. A cut, after fixing the marked vertex on one side, is therefore specified by 15 duad bits and 20 triad bits. The duad bits are precisely a labeled graph on six vertices. Quotienting them by S_6 leaves only the 156 unlabeled six-vertex graph classes. Exhausting the 2^{20} triad states for each class and restoring the exact orbit multiplicity gives the complete ordinary cut enumerator without enumerating all 2^{35} cuts individually.

The cut code has 82 occupied weights, minimum nonzero weight 20, maximum weight 216, and exactly 120 maximum cuts. Combining this enumerator with the already frozen nontrivial switching-coset enumerator closes the complete weight enumerator of

$$K = [360, 36, 20]_2, \qquad |K| = 2^{36}.$$

A MacWilliams transform gives

$$A_0^\perp = 1, \quad A_1^\perp = A_2^\perp = 0, \quad A_3^\perp = 1080,$$

recovering the 1080 even-triangle minimum checks independently.

65.4 A marked double-six produces a literal K_6 symplectic chart

For a marked double-six, its twelve lines canonically pair into six opposite columns. The 15 non-neighboring double-sixes are exactly the duads $\binom{[6]}{2}$, while the 20 neighboring double-sixes are the triads $\binom{[6]}{3}$. Writing the corresponding subsets as weight-2 and weight-3 vectors in $\mathbb{F}_2^6$, the entire 35-vertex residue adjacency is

$$x \sim y \quad \Longleftrightarrow \quad B(x,y) = x \cdot y + \mathrm{wt}(x)\,\mathrm{wt}(y) = 1 \pmod 2.$$

The matrix of B is $I_6 + J_6$, a nondegenerate alternating matrix of rank six. The residue automorphism group has order 1440 and is explicitly

$$S_6 \times C_2,$$

where S_6 permutes the six columns and the central C_2 fixes duads while complementing triads. In particular, the earlier 15-coordinate K_6-duad carrier is now incidence-derived once a double-six is marked. The marking is extra data, and the 35-shell is not being identified with the whole 63-point three-qubit symplectic polar space.

65.5 The adjoint bracket is forced by Levi incidence

The 10-dimensional quotient Q_{10} can be reconstructed using only the Levi cycle space and the oriented $K_{3,3}$ span. Solving directly for equivariant alternating products gives

$$\dim \mathrm{Hom}_{PSp}(\Lambda^2 Q_{10}, Q_{10}) = \dim \mathrm{Hom}_{PGSp}(\Lambda^2 Q_{10}, Q_{10}) = 1.$$

The unique nonzero map has rank 10, satisfies Jacobi on every basis triple, has zero center, and has full derived algebra. Therefore the finite Lie algebra structure

$$Q_{10} \cong \mathfrak{sp}_4(\mathbb{F}_3)$$

is determined by the Levi incidence action up to multiplication of the bracket by a nonzero scalar in $\mathbb{F}_3$. The earlier $O_5(3)$ exterior-square construction is consequently an independent cross-certificate, not a required definition of the bracket.

65.6 Exact qutrit-native compilation of the port-matching datum

The minimal local datum that removes the S_3^{45} sheet ambiguity is a bijection between three sheet cells and three incident line ports at each of 45 recovered points. Each local S_3 element has the exact affine form

$$i \longmapsto (-1)^b i + r \pmod 3, \qquad r \in \mathbb{F}_3,\ b \in \mathbb{F}_2.$$

Thus the native representation is one trit plus one bit per point. The full port table has 6^{45} states and information

$$45 \log_2 6 \approx 116.3233 \text{ bits},$$

so an arbitrary globally packed binary table requires at least 117 bits, whereas independent three-bit local words require 135 bits. Adding the already-certified global chirality bit raises the globally packed optimum to 118 bits. For logically irreversible reset, the information-theoretic Landauer lower bound is $45 k_B T \ln 6$ (plus $k_B T \ln 2$ for chirality); reversible routing itself need not dissipate this amount.

Evidence firewall. The executable producers and frozen JSON certificates for this section are `w33_pass4865_4866_ternary_filtration_steiner_clique.py`, `w33_pass4867_cut_ising_full_enumerator.p` `w33_pass4869_marked_double_six_k6_symplectic_residue.py`, `w33_pass4871_intrinsic_levi_adjoint_bra` and `w33_pass4872_port_matching_information_compiler.py` together with their `PART_W33_PASS...json` outputs. Count equalities are not promoted to identifications without an explicit equivariant map.

66 The Steiner-triangle three-cover of the $W(3,3)$ line action and the first nonlinear adjoint bridge

Prior-art and correction firewall. The bare partition of the 120 Steiner trihedral pairs into forty triads is classical cubic-surface geometry; it is not claimed here as a discovery of this project. In particular, Frame's finite-geometric treatment of the 27 lines already identifies forty triads of trihedral pairs. Pass 4870 correctly recovered that 40×3 partition as a particular $PSp(4,3)$ pair orbital and correctly computed the four pair-orbit refinement and the quadratic Hom space below. It originally made one additional inference that is now withdrawn: the forty-fiber quotient was called the standard symplectic $W(3,3)$ point graph merely after an intended graph-isomorphism check. Passes 4953–4955 rebuild both degree-40 actions independently and prove that the quotient is instead the *line-intersection graph* of $W(3,3)$, i.e. the point graph of the nonisomorphic odd-q dual generalized quadrangle $Q(4,3)$. The two graphs share $\mathrm{SRG}(40,12,2,4)$ parameters but are not isomorphic.

Pass 4866 proved two facts that appeared, at first, to pull in opposite directions: the 120 Steiner/maximal triangles form the full $H_2(-;\mathbb{F}_3)$ coordinate module of the double-six clique complex, but

$$\mathrm{Hom}_{PSp}(H_2, Q_{10}) = \mathrm{Hom}_{PSp}(Q_{10}, H_2) = 0.$$

The linear obstruction is exact. Pass 4870 determines the first nonlinear layer rather than bypassing that obstruction.

The action of $PSp(4,3)$ on unordered pairs of Steiner triangles has four orbits, of sizes

$$120, \qquad 1620, \qquad 2160, \qquad 3240,$$

with per-triangle degrees $2, 27, 36, 54$. Their intrinsic incidence types are, respectively,

$$(|T \cap T'|, e_\times) = (0,0), (1,6), (0,6), (0,4),$$

where $e_\times$ is the number of double-six-graph edges joining the two triangles.

The 120-pair relation is $40K_3$, recovering internally the classical forty triads. The 2160-pair relation is exactly the complete $K_{3,3}$ lift between adjacent fibers. Quotienting by the three-element fibers gives a graph with

$$v = 40, \qquad k = 12, \qquad \lambda = 2, \qquad \mu = 4.$$

Pass 4954 proves by explicit graph isomorphism that this quotient is the intersection graph of the forty $W(3,3)$ lines, equivalently the $Q(4,3)$ point graph. Its independent-triad common-neighbor census is $0^{1080}2^{2160}$ and it has no spread, whereas the standard $W(3,3)$ point graph has census $1^{2880}4^{360}$ and does have spreads. The induced projective symplectic action still has order 25920: this is the second, nonisomorphic degree-40 $PSp(4,3)$ action, not a second copy of the point action.

Because 2 is invertible in $\mathbb{F}_3$, equivariant homogeneous quadratic maps $H_2 \to Q_{10}$ are equivalent to equivariant symmetric bilinear maps, or

$$\mathrm{Hom}_{PSp}(\mathrm{Sym}^2 H_2, Q_{10}).$$

For a permutation module, $\mathrm{Sym}^2 H_2$ splits into the diagonal permutation module and the four unordered-pair orbit modules above. The stabilizer orders and Q_{10} fixed-space dimensions are

orbit	diagonal	120	1620	2160	3240
$\lvert G_x\rvert$	216	216	16	12	8
$\dim Q_{10}^{G_x}$	0	0	0	2	0.

Therefore

$$\boxed{\dim \mathrm{Hom}_{PSp}(\mathrm{Sym}^2 H_2, Q_{10}) = 2.}$$

Both dimensions are supported exclusively on the 2160-pair relation that lifts $Q(4,3)$ adjacency between the Steiner fibers. Since Q_{10} is irreducible, every nonzero linear map $\mathrm{Sym}^2 H_2 \to Q_{10}$ in this two-dimensional family is surjective.

This gives a precise characteristic-three answer to the preceding obstruction: the first equivariant Steiner-to-adjoint bridge is quadratic, not linear, and its orbital mediator is the recovered $Q(4,3)$ line-action quotient. Pass 4941 then removes the two-dimensional quadratic-channel ambiguity projectively by taking the intrinsic Lie bracket of the two quadratic channels, producing an outer-even quartic with full Q_{10} image.

Evidence firewall. The owner producer `analysis/w33_pass4870_steiner_w33_quadratic_bridge.py` now emits the corrected carrier directly. It recovers the forty W33 points as the maximal K_4 pencils of the line graph and verifies the Pass 4949 separator

$$\mathrm{rank}_{\mathbb{F}_3}(A_Q + I) = 15 \neq 11 = \mathrm{rank}_{\mathbb{F}_3}(A_W + I).$$

Independent correction producers are `analysis/w33_pass4954_steiner_quotient_is_q43_dual.py` and `analysis/w33_pass4955_maxcut_points_steiner_lines_incidence.py`. The classical forty-triad partition is prior art; the exact pair-orbit and quadratic-module calculations are repo-derived. The two-dimensional Hom space does not select a preferred normalization, physical coupling, or continuum field without extra structure.

67 Two order-1440 six-set extensions: a necessary non-isomorphism firewall

The marked-double-six chart of Pass 4869 and the earlier duad–syntheme transfer of Pass 1848 both expose symmetry scales of order 1440. They do *not* expose the same group.

For the marked double-six, the six opposite columns carry the direct product

$$G_{\mathrm{res}} \cong S_6 \times C_2,$$

where the central involution fixes all duads and complements every triad. Its exact element-order census is

$$1^1\,2^{151}\,3^{80}\,4^{360}\,5^{144}\,6^{560}\,10^{144}.$$

In particular $|Z(G_{\mathrm{res}})| = 2$ and there are no elements of order 8.

The frozen Pass 1848 duad-to-syntheme bijection instead reconstructs the exceptional outer automorphism class of S_6: a transposition of cycle type $(2,1,1,1,1)$ is carried to a triple transposition of type $(2,2,2)$. After an explicit inner adjustment one obtains an involutive representative of the outer class and hence

$$G_{\mathrm{out}} \cong \mathrm{Aut}(S_6) = S_6{:}\,\mathrm{Out}(S_6).$$

Its exact order census is

$$1^1\,2^{111}\,3^{80}\,4^{360}\,5^{144}\,6^{240}\,8^{360}\,10^{144}.$$

Thus $Z(G_{\mathrm{out}}) = 1$, it has only 111 involutions, and it contains 360 elements of order 8.

Therefore

$$\boxed{S_6 \times C_2 \ncong \mathrm{Aut}(S_6),}$$

despite the common order 1440. The first C_2 is a central triad-complement operation; the second is the exceptional outer-automorphism direction. Their numerical equality must not be used as an identification.

Evidence firewall. The producer is `analysis/w33_pass4873_two_order1440_extensions.py` and the frozen certificate is `data/PART_W33_PASS4873_TWO_ORDER1440_EXTENSIONS.json`. This is a finite group-extension distinction and does not decide which carrier, if either, is physically realized.

68 The Steiner three-cover is a four-class association-scheme refinement of the $W(3,3)$ line action

Pass 4870 identified forty intrinsic three-element fibers among the 120 Steiner triangles. Pass 4954 later corrected the degree-40 quotient label: it is the intersection graph of the forty $W(3,3)$ lines, equivalently the point graph of the nonisomorphic odd-q dual $Q(4,3)$, rather than the standard $W(3,3)$ point graph. Pass 4874 closes the full pair algebra on the 120-set. Besides the identity relation, the four symmetric relations have valencies

$$2, \qquad 27, \qquad 36, \qquad 54,$$

and unordered-pair counts

$$120, \qquad 1620, \qquad 2160, \qquad 3240.$$

They close under matrix multiplication to a commutative imprimitive four-class association scheme.

With relation order $(R_0, R_1, R_2, R_3, R_4)$ equal to identity, fiber, first nonedge refinement, $Q(4,3)$-adjacency lift, and second nonedge refinement, the first eigenmatrix is

$$P = \begin{pmatrix} 1 & 2 & 27 & 36 & 54 \\ 1 & 2 & -3 & 6 & -6 \\ 1 & 2 & 3 & -12 & 6 \\ 1 & -1 & 9 & 0 & -9 \\ 1 & -1 & -3 & 0 & 3 \end{pmatrix},$$

with primitive multiplicities

$$1, \qquad 24, \qquad 15, \qquad 20, \qquad 60.$$

The fiber-constant 40-space is exactly the first three primitive sectors. On it, the 2160-pair adjacency-lift relation has eigenvalues

$$36, \quad 6, \quad -12,$$

which are three times the common SRG eigenvalues $12, 2, -4$ of the $Q(4,3)$ line-intersection graph. The remaining 80 transverse directions split as $20 + 60$ over characteristic zero and are annihilated by the adjacency-lift relation.

The refinement is also exact over quotient nonedges. Every adjacent pair of three-element fibers contributes all nine cross pairs, i.e. a $K_{3,3}$. For each of the 540 nonedges of $Q(4,3)$—equivalently each pair of disjoint $W(3,3)$ lines—the nine cross pairs instead split canonically as

$$3 + 6,$$

where the three-pair relation is a perfect matching and the other relation is its six-edge complement. Thus the Steiner layer refines adjacency and disjointness of the W33 *line* carrier, not the W33 point graph.

Correction and evidence firewall. The owner producer `analysis/w33_pass4874_steiner_w33_association` now emits the corrected carrier itself, reconstructs the forty dual K_4 pencils, and verifies the characteristic-three ranks 15 on the line carrier and 11 on the point carrier. Its frozen certificate is `data/PART_W33_PASS4874_STEINER_W33_ASSOCIATION_SCHEME.json`. Pass 4949 is authoritative for the modular carrier separator. The four-class scheme, its eigenmatrix, multiplicities, and $3 + 6$ matching refinement remain unchanged. The $3 + 6$ matching relation is intrinsic; choosing labels inside an individual three-element fiber is still extra coordinate or gauge data.

69 The quadratic Steiner-to-adjoint bridge is odd under the outer $PGSp/PSp$ involution

Pass 4870 found

$$\dim \mathrm{Hom}_{PSp}(\mathrm{Sym}^2 H_2, Q_{10}) = 2,$$

with both dimensions supported on the 2160-pair relation lifting adjacency of the Steiner forty-fiber quotient. Pass 4954 identifies that quotient correctly as $Q(4,3)$, equivalently the $W(3,3)$ line-intersection graph, not the standard W33 point graph. Pass 4875 repeats the exact stabilizer-fixed-space calculation for the full $PGSp(4,3)$ action.

The four unordered-pair orbit sizes remain

$$120, \qquad 1620, \qquad 2160, \qquad 3240,$$

but each stabilizer doubles. For PSp the pairs

$$(|G_x|, \dim Q_{10}^{G_x})$$

are

$$(216, 0),\ (16, 0),\ (12, 2),\ (8, 0),$$

while for $PGSp$ they become

$$(432, 0),\ (32, 0),\ (24, 0),\ (16, 0).$$

The diagonal orbit contributes zero in both groups. Therefore

$$\boxed{\dim \mathrm{Hom}_{PGSp}(\mathrm{Sym}^2 H_2, Q_{10}) = 0.}$$

Since $PGSp/PSp \cong C_2$ and 2 is invertible in $\mathbb{F}_3$, the outer involution acts semisimply on the two-dimensional PSp Hom space. Its $+1$ eigenspace is exactly the $PGSp$-equivariant Hom space, hence is zero. Consequently the full two-dimensional space is the -1 eigenspace:

$$\boxed{\tau_{\mathrm{out}}|_{\mathrm{Hom}_{PSp}} = -I_2.}$$

Thus every nonzero quadratic map changes sign under the projective outer involution. No nonzero quadratic map is fully $PGSp$-equivariant. At the same time, multiplication by -1 fixes every one-dimensional projective line setwise, so this sign rule still does not select a preferred projective quadratic channel.

Evidence firewall. The producer is `analysis/w33_pass4875_pgsp_quadratic_chirality.py`, with frozen certificate `data/PART_W33_PASS4875_PGSP_QUADRATIC_CHIRALITY.json`. Pass 4954 changes only the geometric label of the 2160 support relation; the fixed-space and outer-action calculation is unchanged. Here "odd" refers only to the finite $PGSp/PSp$ outer involution; it is not being identified automatically with a spacetime parity or CP operation.

70 The two 120-object carriers are not the same $PGSp$ set

Pass 4867 found exactly 120 maximum cuts of weight 216 in the double-six graph, while the Steiner layer contains exactly 120 maximal/Steiner triangles. Pass 4877 tests the equality rather than promoting it.

A marked-double-six K_6 chart constructs a maximum cut with a Hamilton C_6 duad state and exactly two triad completions. Its full $PGSp(4, 3)$ orbit has size 120. Thus both the maximum-cut set and the Steiner-triangle set are transitive $PGSp$ sets with stabilizer order

$$51840/120 = 432.$$

The stabilizers are nevertheless nonconjugate. The maximum-cut stabilizer fixes no Steiner triangle and has element-order census

$$1^1\, 2^{45}\, 3^{26}\, 4^{54}\, 6^{90}\, 8^{108}\, 12^{108},$$

whereas a Steiner-triangle stabilizer fixes exactly its defining Steiner triangle and has census

$$1^1\,2^{87}\,3^{26}\,4^{72}\,6^{210}\,12^{36}.$$

In particular, the first stabilizer has 108 elements of order 8 and the second has none. Hence

$$\boxed{\{\text{maximum cuts}\} \not\cong_{PGSp} \{\text{Steiner triangles}\}.}$$

There is no $PGSp$-equivariant bijection between the two 120-sets. Their equal cardinalities and equal stabilizer orders are not an identification.

Evidence firewall. The producer is `analysis/w33_pass4877_maxcut_steiner_nonbijection.py`, with frozen certificate `data/PART_W33_PASS4877_MAXCUT_STEINER_NONBIJECTION.json`. An arbitrary coordinate-dependent bijection between two sets of size 120 is of course possible; the theorem excludes the canonical equivariant one.

70.1 Passes 4936–4937: exact chamber matrix units and a finite adjoint controller

The rank-48 chamber packet of Passes 4324 and 4334 now has literal rational matrix units. In the packet algebra

$$\mathcal{A}_{48} = \langle \Pi_{48}, X, \Omega, X\Omega \rangle_{\mathbb{Q}}, \qquad X^2 = 6\Pi_{48}, \quad \Omega^2 = -60\Pi_{48}, \quad X\Omega = -\Omega X,$$

the point and line carriers are

$$Q_p = \frac{1}{2}\Pi_{48} + \frac{1}{8}X + \frac{1}{48}X\Omega, \qquad Q_\ell = \frac{1}{2}\Pi_{48} + \frac{1}{8}X - \frac{1}{48}X\Omega.$$

Putting

$$e_{11} = Q_p, \quad e_{22} = \Pi_{48} - Q_p, \quad e_{21} = (\Pi_{48} - Q_p)Q_\ell Q_p, \quad e_{12} = \frac{64}{15}Q_p Q_\ell (\Pi_{48} - Q_p)$$

gives all sixteen relations

$$e_{ij}e_{k\ell} = \delta_{jk}e_{i\ell}.$$

Hence

$$\boxed{\mathcal{A}_{48} \cong M_2(\mathbb{Q})}$$

on the packet representation: one exact two-state multiplicity algebra repeated on 24 representation lanes. This is not a construction of 24 physical qubits.

The bridge to the checked-in chamber ISA is deliberately aggregate. If the three deterministic point-panel transitions are denoted HP_i and the three line-panel transitions HL_i, their chart-independent family sums are P and L. Their packet compressions

$$H_p = \frac{\Pi_{48}P\Pi_{48} - \Pi_{48}}{2} = 2Q_p - \Pi_{48}, \qquad H_\ell = \frac{\Pi_{48}L\Pi_{48} - \Pi_{48}}{2} = 2Q_\ell - \Pi_{48}$$

satisfy

$$H_p^2 = H_\ell^2 = \Pi_{48}, \qquad H_pH_\ell + H_\ell H_p = -\frac{1}{2}\Pi_{48}.$$

For $T = H_p H_\ell$ one has

$$2T^2 + T + 2\Pi_{48} = 0, \qquad \chi_T(t) = t^{112}\left(t^2 + \frac{1}{2}t + 1\right)^{24},$$

so the aggregate turn has infinite order on the packet. These identities certify the complete HP or HL family only; no individual selector is asserted to preserve the packet.

Pass 4864 identified the remaining ternary ten-space with $\mathfrak{sp}_4(\mathbb{F}_3)$, and Pass 4871 later proved that its bracket is already forced up to nonzero scalar by the Levi-incidence action. Pass 4861 showed that full local port matching leaves one global $PGSp(4,3)$, while Pass 4872 compiled each of the 45 local S_3 matchings as one trit plus one bit. Pass 4937 composes the ten-space and global frame into a different object: a ten-trit affine correction register. Over $R = \mathbb{F}_3[\epsilon]/(\epsilon^2)$ it verifies the split sequence

$$1 \longrightarrow \mathfrak{sp}_4(\mathbb{F}_3)^+ \longrightarrow Sp_4(R) \longrightarrow Sp_4(3) \longrightarrow 1,$$

whose elementary-abelian tangent kernel has order $3^{10} = 59049$. Port matching instead gives the faithful affine controller candidate

$$\mathbb{F}_3^{10} \rtimes PGSp(4,3), \qquad v \longmapsto vA_g + w, \qquad |\mathbb{F}_3^{10} \rtimes PGSp(4,3)| = 3{,}061{,}100{,}160.$$

The 59049 offsets form exactly 17 $PGSp(4,3)$-orbits. The dual-number group has the same order as this affine group but is not the same group: their centers have orders 2 and 1, respectively. Moreover, multiplication in the square-zero kernel is addition, so its group commutator is zero; the nonabelian Lie bracket is tangent data inherited from Pass 4864, not a hidden kernel commutator.

Evidence boundary. The two native GAP witnesses replay 20/20 and 30/30 exact checks and emit byte-stable certificates. Pass 4936 proves a finite rational packet algebra and a chart-independent selector-family checksum. Pass 4937 proves a finite characteristic-three tangent group, affine semidirect product, and orbit atlas. Neither pass implements an individual chamber selector, a HoloBox guest transition, a compiler lowering, an isolation or security guarantee, hardware timing, a continuum gauge field, or a particle, mass, or coupling.

71 Passes 4940–4947: exact radius witness, quartic adjoint bridge, and the Steiner–cut point/line reconstruction

This packet executes five queued fronts and three independent probes. Every claim below is finite and executable. Passes 4951–4958 subsequently sharpen the covering-radius ceiling and correct the degree-40 quotient labels: the Steiner fibers form the $Q(4,3)$ point graph, equivalently the $W(3,3)$ line-intersection graph, while the maximum-cut triples recover the actual $W(3,3)$ point action.

71.1 Pass 4940: the hard covering witness is exactly 134 away

Pass 4859 exhibited a received word $x \in \mathbb{F}_2^{360}$ with an exact automorphism g satisfying

$$g(x) = x + \sigma_{E_6},$$

so its distances to the ordinary cut class and to the switched class agree. Pass 4940 solves the remaining cut-class minimization by deterministic integer branch-and-bound on the 36 vertex bits.

Fixing the cut/complement symmetry at one vertex, the exhaustive search visits 8,242,747 nodes and certifies

$$\boxed{d(x, K) = 134.}$$

At the time this improved the interval to $134 \le \rho(K) \le 179$. Pass 4951 uses the exact dual values $A_1 = A_2 = 0$, $A_3 = 1080$ to control the third centered moment of every coset and rules out leaders ≥ 174, including the equality case by a $2^{36} \not\equiv 0 \pmod 7$ divisibility obstruction. The current rigorous interval is therefore

$$\boxed{134 \le \rho(K) \le 173.}$$

The exact covering radius remains open.

71.2 Pass 4941: the quadratic ambiguity cancels at degree four

Passes 4870 and 4875 give a two-dimensional PSp-equivariant quadratic Hom plane

$$\mathrm{Hom}_{PSp}(\mathrm{Sym}^2 H_2, Q_{10})$$

on which the outer $PGSp/PSp$ involution acts as $-I_2$. Pass 4871 supplies the unique intrinsic equivariant Lie bracket on Q_{10}. For any basis q_1, q_2 of the quadratic Hom plane define

$$\mathcal{F}(x) = [q_1(x), q_2(x)].$$

Then $\mathcal{F}$ is homogeneous of degree four, and under a basis change $A \in GL_2(\mathbb{F}_3)$ it scales only by $\det A$. Thus it defines a canonical projective quartic line. The two outer minus signs cancel, so the quartic is $PGSp$-even. Direct exact evaluation finds three-support inputs whose images span all ten dimensions of Q_{10}:

$$\boxed{\dim\langle \mathcal{F}(x) \rangle = 10.}$$

Every two-support input vanishes. Moreover each quadratic channel separately annihilates the entire 40-dimensional fiber-constant subspace, because the sum over every complete 3×3 lift of a quotient edge is zero in $\mathbb{F}_3$. Pass 4954 identifies that quotient edge relation correctly as $Q(4, 3)$ adjacency, not the standard $W(3, 3)$ point adjacency. Hence the quartic construction is genuinely carried by the non-semisimple three-fiber layer rather than by the quotient alone.

71.3 Pass 4942: the rational $20 + 60$ transverse split degenerates over $\mathbb{F}_3$

The rational Steiner association scheme has a 40-dimensional fiber-constant sector and an $80 = 20 + 60$ transverse sector. In defining characteristic the fiber-sum operator

$$N = I + R_1$$

has rank 40 and satisfies $N^2 = 0$. Therefore

$$\operatorname{im} N \subset \ker N, \qquad \dim \operatorname{im} N = 40, \qquad \dim \ker N = 80.$$

The nonedge-matching relation R_2 is nilpotent of index three with exact ranks

$$34 \longrightarrow 14 \longrightarrow 0,$$

and Jordan type

$$\boxed{3^{14}\, 2^6\, 1^{66}.}$$

The adjacency-lift relation R_3 has rank 39 and is square-zero. Thus the characteristic-zero $20+60$ eigensplitting is not a direct-sum decomposition in characteristic three. This direct 120×120 matrix calculation also serves as a guardrail: coincidence of rational eigenvalues modulo 3 does *not* by itself justify reducing the full modular Bose–Mesner algebra to "rank two." Pass 4948 is independently reserved for the broader modular Bose–Mesner correction audit.

71.4 Pass 4943: a literal common S_6 core, but two different extensions

After marking one double-six, both the Pass 4869 residue and the Pass 1848 duad–syntheme construction can be placed on the same six literal labels. Their adjacent-transposition generators then agree coordinate-for-coordinate on the same 15 duads. Hence the common order-720 S_6 carrier is an explicit intertwiner, not an order match.

The extra involutions remain different. In the marked-double-six shell it is central, fixes every duad, and complements every triad, yielding $S_6 \times C_2$. In the duad–syntheme carrier it is the exceptional outer automorphism swapping the two 15-sets, yielding $\mathrm{Aut}(S_6) = S_6{:}2$. The common S_6 crosswalk therefore does not extend to an identification of the order-1440 groups.

71.5 Pass 4944: the 45 local port matchings are literal RTL

The Pass 4872 local state

$$i \longmapsto (-1)^b i + r \pmod 3, \qquad r \in \mathbb{F}_3,\ b \in \mathbb{F}_2,$$

is implemented by `rtl/w33_pass4944_port_selector45.sv`. Exhaustive semantic evaluation checks all $6 \times 3 = 18$ valid selector/input cases and recovers all six permutations of three ports with zero local collisions. Forty-five selectors operate in one parallel combinational layer.

The physically local control representation uses 45 two-bit trit fields and 45 reflection bits, namely 135 binary wires. Against the information-only fixed-binary optimum of 117 bits from Pass 4872, this is an exact

$$\boxed{135 - 117 = 18\text{-bit locality premium.}}$$

Gate-level Yosys cell counts are kept separate until an actual synthesis run finishes; no timing, placement, optical-loss, or end-to-end scheduling claim is made by the functional RTL theorem.

71.6 Pass 4945: the Steiner-line disjointness matchings have full S_3 holonomy

Pass 4954 identifies the forty Steiner fibers with the forty lines of $W(3,3)$. Their quotient graph is therefore the line-intersection graph $Q(4,3)$; an edge of its complement is a pair of disjoint W33 lines. Each such pair carries the canonical perfect matching between its two three-element Steiner fibers. After arbitrary local fiber labels these become S_3 transports on the 540 disjoint-line edges. Gauge-fixing along a spanning tree leaves 501 fundamental cycles, whose transports generate all six permutations:

$$\boxed{\mathrm{Hol} = S_3.}$$

Therefore no global relabeling can make all matchings simultaneously trivial, and the connection does not globally reduce to C_3 or C_2. Only the local edge representatives depend on chosen labels; the holonomy-group conjugacy class is gauge invariant.

71.7 Pass 4946, corrected by Pass 4955: maximum cuts are points, Steiner fibers are lines

Pass 4877 proved that the 120 maximum cuts and 120 Steiner triangles are not equivariantly bijective. Define the cross-incidence matrix by

$$B(C,T)=1 \quad \Longleftrightarrow \quad \text{the maximum cut } C \text{ splits the Steiner triangle } T.$$

Every row and column has weight 108. Exactly forty classes of three rows are identical, and exactly forty classes of three columns are identical. On the 40×40 quotient, the complementary non-splitting relation $Z=1-B$ has row and column weight four.

Pass 4955 reconstructs both quotient sides against the standard symplectic model and proves the precise roles:

$$\boxed{120 \text{ maximum cuts } /3 \;= 40\; W(3,3) \textbf{ points}, \qquad 120 \text{ Steiner triangles } /3 \;= 40\; W(3,3) \textbf{ lines}.}$$

The matrix Z is literal W33 point–line incidence. Its row collinearity graph is the standard $W(3,3)$ point graph; its column collinearity graph is the nonisomorphic line-intersection graph $Q(4,3)$. Consequently

$$ZZ^T = 4I + A_W, \qquad Z^TZ = 4I + A_Q,$$

and Z has singular spectrum

$$\boxed{4^1, (\sqrt{6})^{24}, 0^{15}}$$

with rank 25. The failed $120 \leftrightarrow 120$ identification is thus replaced by the actual point/line incidence geometry.

71.8 Pass 4947, relabeled by Pass 4954: matching curvature detects $Q(4,3)$ triad type

The complement of the Steiner quotient has 3240 triangles, i.e. triples of pairwise noncollinear $Q(4,3)$ *points*, equivalently triples of pairwise disjoint W33 lines. Their matching transports split exactly as

$$1080 \text{ identity}, \qquad 2160 \text{ transposition}, \qquad 0 \text{ three-cycle}.$$

Their common-neighbor counts in the $Q(4,3)$ quotient are exactly

$$1080 \text{ with } 0 \text{ centers}, \qquad 2160 \text{ with } 2 \text{ centers}.$$

Thus

$$\boxed{\text{flat} \iff 0\text{-center}, \qquad \text{reflection} \iff 2\text{-center}.}$$

These counts must not be quoted as triad statistics of the standard W33 point graph. Pass 4953 proves that standard $W(3,3)$ instead has 2880 one-center and 360 four-center independent triads. The numerical $1080+2160$ curvature classification survives; only its original substrate label was wrong.

Executable evidence and boundaries. The owner producers are `analysis/w33_pass4940_exact_hardword_` `analysis/w33_pass4941_quartic_ambiguity_cancellation.py`, `analysis/w33_pass4942_transverse_char3_` `analysis/w33_pass4943_common_s6_carrier_crosswalk.py`, `analysis/w33_pass4944_port_selector_rtl_re` and `analysis/w33_pass4945_4947_steiner_connection_maxcut_duality.py`. The Pass 4870, 4874, 4941, 4942, and 4945–4947 owners now emit corrected point/line labels directly; Pass 4949 supplies their common exact separator $15 \neq 11$ in characteristic three. Independent duality/radius checks are `analysis/w33_pass4951_third_moment_radius_bound.py`, `analysis/w33_pass4953_correct_w33_t` `analysis/w33_pass4954_steiner_quotient_is_q43_dual.py`, and `analysis/w33_pass4955_maxcut_points_s` The covering radius remains open in $[134, 173]$; the quartic is projectively defined only up to nonzero scalar; and no finite control or holonomy statement here is a continuum gauge-field or microscopic-device derivation.

72 Passes 4951–4958: the radius drops to 173 and the Steiner quotient resolves into the dual $Q(4,3)$

The preceding Steiner packet exposed a tension that could not be dismissed as notation. Its forty-fiber quotient had the same strongly regular parameters as $W(3,3)$, but its triad-center census disagreed with the standard symplectic model. The resolution is exact and useful: the quotient is not the $W(3,3)$ point graph. It is the graph on the forty *lines* of $W(3,3)$, equivalently the point graph of the nonisomorphic odd-q dual $Q(4,3)$. Once that correction is made, the maximum-cut shell, the Steiner shell, point–line incidence, and the old spread carrier assemble into one coherent pair of complementary transceivers.

72.1 Pass 4951: a third-moment theorem gives $\rho(K) \leq 173$

Let $K = [360, 36, 20]_2$. Pass 4867 froze

$$A_1(K^\perp) = A_2(K^\perp) = 0, \qquad A_3(K^\perp) = 1080,$$

and Pass 4940 exhibited a word at exact distance 134 from K. For any coset, let W be the Hamming weight of a uniformly sampled word and set $X = W - 180$. Pairwise independence gives

$$\mathbb{E}X = 0, \qquad \mathbb{E}X^2 = 90.$$

The 1080 dual weight-three words give the exact character identity

$$\mu_3 := \mathbb{E}X^3 = -\frac{3}{4} \sum_{\substack{h \in K^\perp \\ |h|=3}} (-1)^{y \cdot h}, \qquad |\mu_3| \leq 810.$$

If a coset leader has weight δ and $a = 180 - \delta$, then $X \geq -a$. Positivity of $\mathbb{E}[(X + a)(X - t)^2]$, optimized at $t = 90/a$, yields

$$\mu_3 \geq 90 \left(\frac{90}{a} - a \right).$$

For $\delta \geq 175$ the right side is at least 1170, impossible. At $\delta = 174$, equality in the moment bound forces every coset word to have weight 174 or 195; the zero mean then forces population ratio $5 : 2$. But $|K| = 2^{36}$ is not divisible by 7. Hence

$$\boxed{134 \leq \rho(K) \leq 173.}$$

The lower endpoint is a certified hard word; the upper endpoint is universal. The exact radius remains open.

72.2 Passes 4953–4955: the two degree-40 actions are points and lines, not two copies of points

Construct the standard symplectic point graph on projective $\mathbb{F}_3^4$. Its 3240 independent triples have common-neighbor census

$$1^{2880}\,4^{360}.$$

The 360 four-center triples are exactly the three-subsets of the 90 nonisotropic projective lines of $PG(3,3)$.

Reconstructing the Steiner forty-fiber quotient from the double-six geometry gives the same parameter tuple $\mathrm{SRG}(40,12,2,4)$ but a different graph. Exact graph comparison proves

$$\boxed{\text{Steiner quotient} = W(3,3)\text{ line-intersection graph} = Q(4,3)_{\mathrm{pt}}},$$

while it is not isomorphic to the standard $W(3,3)$ point graph. Its independent-triad center census is

$$0^{1080}\,2^{2160},$$

and exhaustive search finds no spread, matching the odd-q duality criterion already recorded elsewhere in the repository.

The maximum-cut/Steiner cross-incidence then fixes the orientation of the duality. The 120 maximum cuts collapse into forty identical profile triples, and the 120 Steiner triangles do the same. On the quotient,

$$\boxed{\text{maximum-cut triples} = W(3,3)\text{ points}, \qquad \text{Steiner triples} = W(3,3)\text{ lines}.}$$

The non-splitting matrix Z is the literal 40×40 point–line incidence matrix.

72.3 Passes 4952 and 4956: incidence transmits $1 + 24$ and is blind to both 15-spaces

Let A_W be the standard W33 point graph and A_Q the $Q(4,3)$ line graph. The corrected incidence matrix satisfies

$$A_W Z = Z A_Q, \qquad Z Z^T = 4I + A_W, \qquad Z^T Z = 4I + A_Q.$$

Both degree-40 graphs have rational spectrum $12^1, 2^{24}, (-4)^{15}$, hence

$$\mathrm{Spec}(ZZ^T) = 16^1, 6^{24}, 0^{15}, \qquad \operatorname{rank} Z = 25.$$

Thus the two distinct 15-dimensional -4 constituents are exactly the left and right dark spaces of incidence. Conversely the 24-dimensional $+2$ constituents are canonically isomorphic:

$$\boxed{Z:\ V_{24}^{\mathrm{line}} \xrightarrow{\sim} V_{24}^{\mathrm{point}}, \qquad Z^{-1} = Z^T/6 \ \text{ on } V_{24}.}$$

Equivalently, with $P_2 = 60E_2$,

$$Z^T P_{2,W} Z = 6P_{2,Q}, \qquad Z P_{2,Q} Z^T = 6P_{2,W}.$$

This is the exact representation-theoretic content of the point/line incidence bridge.

72.4 Pass 4957: the 36 ovoids of $Q(4,3)$ are exactly the 36 W33 spreads

Under the corrected line interpretation, a ten-coclique of the $Q(4,3)$ quotient is a set of ten pairwise disjoint W33 lines, hence a spread. Exhaustive enumeration gives exactly

$$\boxed{\text{36 maximum cocliques of size } 10 = \text{36 W33 spreads.}}$$

The full maximal-coclique census is

$$5^{432}, \qquad 8^{135}, \qquad 10^{36},$$

and the 36 ovoids reproduce the independently frozen spread intersection law

$$\boxed{1^{360}\,4^{270}}.$$

Each W33 line lies in exactly nine spreads. This reconnects the corrected Steiner/Q43 quotient to the existing spread/MUB carrier without a count-based identification: the objects are literally the same line sets.

72.5 Pass 4958: point incidence and spread incidence are complementary complete readouts

This result combines two older exact ingredients with the corrected duality. Pass 173 studied the point–line transceiver Z. Part CXXVI established the line–spread incidence matrix $B \in \{0,1\}^{40\times 36}$ and its Morita spectrum. The latter obeys

$$BB^T = 9I + 3A_{\text{disjoint}}, \qquad \operatorname{Spec}(BB^T) = 90^1, 18^{15}, 0^{24}.$$

Thus Z transmits $1+24$ and kills 15, while B transmits $1+15$ and kills 24. Their only common nonzero constituent is the constant line. The new combined identity is

$$\boxed{18I_{40} = 3Z^TZ + BB^T - 3J_{40}.}$$

Therefore the stacked readout

$$\begin{bmatrix} Z \\ B^T \end{bmatrix} : \mathbb{Q}^{40}_{\text{lines}} \longrightarrow \mathbb{Q}^{76}$$

has full rank 40, and every line-coordinate vector is reconstructed exactly:

$$\boxed{x = \frac{1}{6}Z^T(Zx) + \frac{1}{18}B(B^Tx) - \frac{1}{6}Jx.}$$

The primitive projectors themselves can be read off from the two Gram operators,

$$E_{24} = \frac{5Z^TZ - 2J}{30}, \qquad E_{15} = \frac{4BB^T - 9J}{72}, \qquad E_0 = \frac{J}{40},$$

with fraction-free completeness certificate

$$9J + 12(5Z^TZ - 2J) + 5(4BB^T - 9J) = 360I.$$

The spectra of the two individual channels are prior repo results; their complementary full-line reconstruction is the new consequence of the corrected W33/$Q(4,3)$ identification.

Correction and evidence firewall. The old Pass 4870 certificate field `explicit_isomorphism_to_standard_W` is withdrawn and has been replaced by the corrected certificate. The authoritative producers for this packet are `analysis/w33_pass4951_third_moment_radius_bound.py`, `analysis/w33_pass4953_correct_w33_t` `analysis/w33_pass4954_steiner_quotient_is_q43_dual.py`, `analysis/w33_pass4955_maxcut_points_stei` `analysis/w33_pass4956_point_line_24d_intertwiner.py`, `analysis/w33_pass4957_q43_ovoids_are_w33_s` and `analysis/w33_pass4958_point_spread_complementary_transceiver.py`. The point–spread result explicitly credits Pass 173 and Part CXXVI for the individual incidence spectra. No finite incidence identity here implies a continuum gauge field or physical coupling normalization.

73 Passes 4960–4967: moment barrier, dark-15 obstruction, local S_3 curvature, Witting phase, and the double-six/spread transceiver

This packet executes five independent queued attacks and three additional outside-box probes. Two queued fronts close as exact negative structural results rather than forced positives: the degree-seven moment relaxation does not lower the covering-radius ceiling 173, and no ordinary equivariant point–line matrix can connect the two dark 15-dimensional constituents. The remaining fronts reveal a local curvature theorem, correct the Witting carrier, and produce a canonical bridge between the cubic-surface double-sixes and the W33 spreads.

73.1 Pass 4960: degree-seven moments hit a real relaxation barrier

For a coset of $K = [360, 36, 20]_2$, put $X = W - 180$ and

$$T_j(y) = \sum_{\substack{h \in K^\perp \\ |h|=j}} (-1)^{y \cdot h}.$$

Using the frozen dual coefficients through A_7, the centered moments through degree seven are exact affine functions of $T_3, \dots, T_7$. In particular

$$\begin{aligned}
m_3 &= -\tfrac{3}{4}T_3, \\
m_4 &= 24255 + \tfrac{3}{2}T_4, \\
m_5 &= -\tfrac{2685}{4}T_3 - \tfrac{15}{4}T_5, \\
m_6 &= 10874340 + 2010T_4 + \tfrac{45}{4}T_6, \\
m_7 &= -\tfrac{5037081}{8}T_3 - \tfrac{56175}{8}T_5 - \tfrac{315}{8}T_7.
\end{aligned}$$

At the still-allowed endpoint $\delta = 173$, hence $X \geq -7$, there is an exact truncated functional satisfying every independent bound $|T_j| \leq A_j$ and the required signed-sum parity:

$$(T_3, T_4, T_5, T_6, T_7) = (-1080, -1936, 75316, 830590, -37193040).$$

The ordinary degree-three moment matrix has leading principal minors

$$1, \quad 90, \quad 536490, \quad 2855774841174,$$

and the $(X + 7)$ localizing matrix has leading principal minors

$$7, \quad 1980, \quad 79022673, \quad 27807585328055790.$$

Both are positive definite. Therefore the shellwise degree-≤ 7 one-sided moment relaxation cannot improve

$$\boxed{134 \leq \rho(K) \leq 173}.$$

This does not construct a distance-173 coset. It proves that the next improvement must use correlations among the signed dual shells, additional coset identities, or stronger structure than their separate absolute bounds.

73.2 Pass 4961: the missing $15 \leftrightarrow 15$ bridge is linearly forbidden

Pass 4956 showed that point–line incidence carries the common 24 but kills the two inequivalent degree-15 constituents. The full $PSp(4,3)$ action on point–line pairs has exactly two orbits,

$$160 \text{ incident}, \qquad 1440 \text{ nonincident}.$$

Consequently every equivariant 40×40 point–line matrix is of the form

$$M = aZ + b(J - Z).$$

On either nonconstant module J vanishes, while on the line -4 eigenspace

$$Z^T Z = 4I + A_{\text{line}} = 0.$$

Hence

$$\boxed{\mathrm{Hom}_{PSp}(V_{15}^{\text{line}}, V_{15}^{\text{point}}) = 0, \qquad \mathrm{Hom}_{PSp}(V_{15}^{\text{point}}, V_{15}^{\text{line}}) = 0.}$$

Changing signs or orientations inside an ordinary equivariant incidence matrix cannot evade this obstruction. A nonzero dark-15 channel must introduce a twist, symmetry breaking, nonlinearity, or a different carrier.

73.3 Pass 4962: local triangle curvature already generates the full S_3 holonomy

The Pass 4945 matching connection lives on the 540 edges of the disjointness graph of the forty $Q(4,3)$ / W33-line fibers. Fill all 3240 graph triangles as 2-cells. Over $\mathbb{F}_2$, the triangle–edge boundary matrix has rank

$$501 = 540 - 40 + 1,$$

exactly the graph cycle rank. Since the vertex–edge boundary has rank 39,

$$\boxed{H^1(-; \mathbb{F}_2) = 0.}$$

The sign abelianization of the S_3 transport has curvature zero on 1080 triangles and one on 2160. Transporting every nonabelian triangle holonomy to a common root yields the identity together with all three transpositions. Those three reflections generate

$$\boxed{S_3}.$$

Thus the full holonomy is already generated by local triangle curvature; there is no residual flat C_2 topological sector after the triangle relations are imposed.

73.4 Pass 4963: the Witting rays are W33 points, and phase detects the 1/4 center law

The earlier Witting/Steiner proposal conflated the two nonisomorphic degree-40 actions because both have strongly regular parameters $(40, 12, 2, 4)$. Direct Eisenstein-integer reconstruction of the forty Witting rays gives an orthogonality graph with 240 edges and degree 12 which is isomorphic to the standard symplectic $W(3,3)$ *point* graph and is not isomorphic to the $Q(4,3)$ Steiner/W33-line graph.

The retired direct ray-to-$\mathbb{F}_3^4$ exponent encoder is also invalid: it maps forty rays to only nineteen tuples and maps eight rays to the zero tuple. Using exact Bargmann triple products instead, the 3240 nonorthogonal triples obey

W33 common centers	phase +	phase −	total
1	1440 $(\pi/6)$	1440 $(-\pi/6)$	2880
4	180 $(\pi/2)$	180 $(-\pi/2)$	360.

Therefore

$$\boxed{1 \text{ center} \iff |\phi_P| = \pi/6, \qquad 4 \text{ centers} \iff |\phi_P| = \pi/2.}$$

The old direct equality between the E_6 Steiner signing and Witting phase is withdrawn because those structures live on different forty-element G-sets.

73.5 Pass 4964: the 36 double-sixes and the 36 W33 spreads are the same full-group G-set

The full order-51840 $W(E_6) \cong PGSp(4,3)$ action on the cubic-surface double-sixes and on the W33 spreads has the same permutation character. More strongly, the stabilizer of one double-six, of order 1440, fixes exactly one spread. Propagating that fixed pair gives a unique equivariant bijection

$$\boxed{\{36 \text{ double-sixes}\} \cong \{36 \text{ W33 spreads}\}}.$$

It extends across the outer involution and transports the two pair relations as

$$|D_i \cap D_j| = 6 \iff |\Sigma_i \cap \Sigma_j| = 1 \quad (360 \text{ pairs}),$$

$$|D_i \cap D_j| = 4 \iff |\Sigma_i \cap \Sigma_j| = 4 \quad (270 \text{ pairs}).$$

Thus the double-six graph $\mathrm{SRG}(36, 20, 10, 12)$ is literally the one-overlap graph on the thirty-six W33 spreads.

73.6 Pass 4965: a canonical local $9 = 3 + 3 + 3$ spread chart at every W33 line

Transport each of the 120 Steiner triangles through the preceding bijection. Its three double-sixes become three spreads whose common intersection is exactly one W33 line. Every W33 line lies in nine spreads and supports exactly three Steiner triangles. Those triangles partition the nine spreads as

$$\boxed{9 = 3 + 3 + 3}.$$

Within one triple the corresponding spreads meet in one W33 line; between different triples they meet in four. Therefore the local four-overlap graph is

$$\boxed{K_{3,3,3}},$$

while the one-overlap graph is $3K_3$. This is a canonical finite incidence chart. Interpreting it as a hardware qutrit port decomposition requires a separate physical model.

73.7 Pass 4966: oriented Witting phase realizes the outer index-two sign

Transfer a generating $PSp(4,3)$ action through the exact Witting–W33 point graph isomorphism. Every generator preserves the oriented Bargmann phase on all 3240 nonorthogonal triples. The explicit similitude

$$M = \mathrm{diag}(1,2,1,2), \qquad M^T J M = -J \pmod 3,$$

extends the action to order 51840 and sends every phase to its negative:

$$\pi/6 \leftrightarrow -\pi/6, \qquad \pi/2 \leftrightarrow -\pi/2.$$

Hence the oriented phase carries the finite index-two character

$$\boxed{PGSp(4,3)/PSp(4,3) \cong C_2}.$$

This is a finite ray-level complex-conjugation rule; it is not automatically a spacetime parity or CP operation.

73.8 Pass 4967: point and cubic-surface double-six readouts reconstruct the full W33 line carrier

Via Pass 4964, line–spread incidence becomes a canonical 36×40 double-six/line matrix C. It has row weight 10, column weight 9, rank 16, and

$$CC^T = 4J + 6I - 3A_{\mathrm{DS}}.$$

On the W33-line side it transmits exactly $1 + 15$ and kills 24. Point–line incidence Z transmits $1 + 24$ and kills 15. Their stacked matrix has full rank 40 and obeys

$$\boxed{18 I_{40} = 3Z^T Z + C^T C - 3J_{40}}.$$

Thus every W33-line coordinate is reconstructed exactly from a point readout and a cubic-surface double-six readout. The individual spread-line spectrum is older Part CXXVI work, and Pass 4958 already established the anonymous point+spread complementarity. The new content is that the spread rows are now canonically and equivariantly named by the cubic-surface double-sixes.

Evidence firewall. The authoritative producers are `analysis/w33_pass4960_degree7_moment_radius_barri`
`analysis/w33_pass4961_dark15_point_line_hom_obstruction.py`, `analysis/w33_pass4962_q43_s3_curvatu`
`analysis/w33_pass4963_witting_pancharatnam_w33_reaudit.py`, `analysis/w33_pass4964_4965_4967_doub`
and `analysis/w33_pass4966_witting_phase_outer_character.py`. Each pass has a frozen JSON certificate. These are finite code, graph, group, cohomology, incidence, and ray-phase statements. No continuum gauge field, particle coupling, or microscopic device follows without additional physical input.

Passes 4976–4983: shell correlations, the 40+45 spread reader, and local gauge closure

Pass 4976: shell-three correlations. On the 360 edges of the double-six graph H_{36}, the Pass4859 switching cochain is even on exactly the 1080 non-Steiner triangles and odd on the

120 Steiner triangles. The 1080 even triangle vectors span all 324 dimensions of $K^{\perp}$. Hence the extremal signed-shell values are rigid:

$$T_3 = +1080 \Rightarrow T_j = A_j, \qquad T_3 = -1080 \Rightarrow T_j = (-1)^j A_j.$$

In particular, the Pass4960 truncated-moment witness with $T_3 = -1080$ and $T_4 = -1936$ is not a character of $K^{\perp}$: it would have to satisfy $T_4 = 10530$. This does not yet lower the rigorous covering-radius ceiling 173.

Pass 4977: the PGSp outer twist does not restore the dark 15. The point and line permutation modules both extend from $\mathrm{PSp}(4,3)$ to $\mathrm{PGSp}(4,3)$. Therefore conjugation by the multiplier-minus-one outer element fixes the isomorphism class of the unique 15-dimensional constituent in each module. The twisted point-line Hom spaces remain zero. A true point/line correlation, if used, requires structure outside these ordinary PGSp permutation extensions.

Pass 4978: Witting phase compensates the quadratic outer sign. The two-dimensional quadratic Hom multiplicity space of Pass4875 carries outer action $-I_2$, while the oriented Witting phase line of Pass4966 carries the same nontrivial quotient character. Tensoring them gives

$$H_{\mathrm{comp}} = H \otimes \varepsilon_W, \qquad (-I_2)(-1) = +I_2,$$

so the compensated quadratic multiplicity space is PGSp-even. Unlike the intrinsic quartic bracket of Pass4941, this cancellation does not select a preferred projective quadratic channel.

Pass 4979: the 45 tritangents read the missing $1+20$ spread sector. Let M be the 45×36 matrix with $M_{TD} = 1$ when the tritangent T meets the corresponding double-six in exactly two of its three cubic lines. Every row has weight 24, every column weight 30, and

$$\operatorname{rank} M = 21, \qquad M^{\mathsf{T}} M = 18J + 12I + 3A_{H_{36}}.$$

Thus M transmits the $1 + 20$ sector and kills the 15. The Pass4967 spread-line matrix C obeys $CC^{\mathsf{T}} = 4J + 6I - 3A_{H_{36}}$, hence

$$\boxed{18I_{36} = CC^{\mathsf{T}} + M^{\mathsf{T}} M - 22J_{36}}.$$

The stacked $40+45$ readout has rank 36: W33 lines plus cubic tritangents reconstruct the complete 36-spread/double-six carrier.

Passes 4980 and 4982: the local nine-spread gauge. At every W33 line, the nine incident spreads have the canonical Steiner partition $3 + 3 + 3$. The full line stabilizer has order 1296 and acts faithfully as the complete imprimitive wreath product $S_3 \wr S_3$. Therefore the block system is canonical but its labels are not. If the partition is treated as one parallel class of $\mathrm{AG}(2,3)$, there are exactly 12 affine-plane completions; the local wreath product acts transitively on all twelve, with completion stabilizer order 108. Thus a qutrit compiler must fix a finite gauge rather than inherit canonical affine coordinates.

Pass 4981: tetrahedral Bianchi closure. The disjointness graph of the forty Q43/W33-line fibers has 9450 four-cliques. Over $\mathbb{F}_2$, the triangle boundary has rank 501 and kernel dimension 2739, while the tetrahedron boundary has rank exactly 2739. Hence the clique 3-skeleton has $H^1 = H^2 = 0$ over $\mathbb{F}_2$. For the S_3 matching connection, the tetrahedra have respectively $0, 2, 4$ reflection-curvature faces in counts $270, 6480, 2700$, and all 9450 satisfy the nonabelian Bianchi identity

$$H_{abc}H_{acd}H_{adb} = P_{ab}H_{bcd}P_{ba}.$$

Pass 4983: the geometric meaning of $A_3(K^\perp) = 1080$. Among the 1200 triangles of the one-overlap graph on the 36 spreads, exactly 120 have one common W33 line and exactly 1080 have empty triple intersection. The former are the Steiner triangles; the latter are exactly the complete weight-three shell of $K^\perp$. Thus a pairwise one-overlap spread triple is a weight-three dual check precisely when its common W33-line intersection is empty.

Residual A_4, complementary readout, and local affine gauge (Passes 4984–4991)

The weight-four dual shell of the 36-dimensional switching code has the exact $W(E_6)$-orbit decomposition

$$A_4 = 10530 = 810 + 6480 + 3240,$$

where the three classes are the σ-even simple four-cycles of H_{36} with respectively zero, one, and two chords. The 9720 words generated by sums of two weight-three checks are precisely the one- and two-chord classes; the residual 810 is a single chordless orbit with stabilizer order 64. This does not yet improve the rigorous covering-radius interval $134 \le \rho \le 173$.

The residual orbit admits a second, cubic-surface description. Each residual square is unselected by exactly two tritangents. The resulting map has image the 270 intersecting tritangent pairs and fibre size three. For every such pair the six double-sixes missed by both induce the octahedral graph $K_{2,2,2}$, and the three residual checks are its three equatorial squares. Hence

$$810 = 270 \cdot 3$$

is an exact three-fold octahedral-equator bundle.

Let C be the 36×40 spread–line incidence reader and M the 45×36 tritangent selector. For the stacked readout $R = [C^T; M]$ one has

$$R^T R = 18I_{36} + 22J_{36}, \qquad R^\dagger = \left(\frac{1}{18}I - \frac{11}{7290}J\right)R^T.$$

Thus for measurements $y_L = C^T x$ and $y_T = Mx$,

$$x = \frac{1}{18}(Cy_L + M^T y_T) - \frac{11}{90}\left(\sum y_L\right)\mathbf{1}.$$

The nonconstant squared singular value is exactly 18. Thirty-six rows are minimal, and exact full-rank bases exist with compositions $15+21$ and $16+20$ line/tritangent rows. Centering the line rows by $1/4$ and tritangent rows by $2/3$ yields frame operators $18P_{15}$ and $18P_{20}$, so their union is an equal-bound tight frame $18P_{\mathbf{1}^\perp}$ on the 35-dimensional mean-zero spread carrier.

The point- and line-side dark fifteens remain inequivalent. Point–line incidence annihilates both; the 80-vertex Levi graph has exact nullspace $15_p \oplus 15_\ell$ of dimension 30. The point and line-intersection graphs have binary adjacency ranks 16 and 10, respectively, so there is no incidence-preserving point–line side swap at $q = 3$. Together with the negative PGSp outer-twist test,

the honest symmetry-preserving dark carrier is the twin 30-space rather than a hidden $15 \leftrightarrow 15$ operator.

Finally, the twelve local $AG(2,3)$ completions remain a single orbit even under the PSp index-two subgroup selected by Witting phase, so the finite outer sign does not choose a qutrit coordinate plane. Their ambiguity is nevertheless structured: the disjointness graph of completions is $4K_3$, and the four 3-packets are uniquely equivariantly indexed by the four points of the underlying W33 line. A distinguished line point reduces the ambiguity to a residual triple, but the bare incidence geometry does not select such a point.

Pass4985 also hardens the collided Pass4968–4972 repair: graph automorphisms preserve the 24- and 15-dimensional adjacency eigenspaces; the nontrivial Ihara root fields are $\mathbb{Q}(i\sqrt{10})$ and $\mathbb{Q}(i\sqrt{7})$; and the exact W33 critical group is $(\mathbb{Z}/10)^8 \oplus \mathbb{Z}/40 \oplus (\mathbb{Z}/160)^{14}$. Finite outer sign, critical-group numerology, and hardware coordinate labels are kept separate from physical identifications unless an independent mechanism is supplied.

Octahedral shell algebra and binary 30-layer (Passes 4992–4999; corrections through Pass5011)

The 270 octahedra organize the 1080 sigma-even weight-three checks and 810 residual weight-four equators. Their exact local product identities strengthen the shell constraints, while the rigorous covering-radius interval remains $134 \le \rho(K) \le 173$.

Reader corrections. The global complementary line–tritangent reader has erasure distance six. The line block has 240 support-six point-pencil-gradient relations. Pass5011 further supersedes the former pure-tritangent minimum claim: the tritangent block has exactly 120 support-six signed $K_{3,3}$ relations. The 135 support-eight $2K_4$ configurations from Pass4998 remain an exact secondary family, not the minimum. The first mixed relations occur at support 13, not at support eight or nine.

Over $\mathbb{F}_2$ the residual-square, triangle, and full cycle ranks are $294 < 324 < 325$. Shared-line projection yields the canonical nonsplit sequence $0 \to V_{20} \to Q_{30} \to Q_{10} \to 0$.

The 270×360 octahedron/edge frame has real rank 120 and binary rank 90. Pass5009 refines its real active decomposition to $1+20+15+60+24$. Pass5010 separately resolves the modular K_{60} by a canonical 14-dimensional submodule and 46-dimensional quotient; no real/binary 60-space identification is inferred from dimension alone.

Global character closure, modular extensions, and corrected readout (Passes 5000–5007)

The octahedral shell algebra of Pass4992 was pushed through an exact 270-cell sign ILP together with the degree-seven radial moment and localizing constraints. The resulting local relaxation remains feasible at the distance-173 frontier: one may assign all four even triangle signs in every octahedron to -1 and the three equator signs to $(-1,-1,+1)$, while retaining the Pass4960 radial tuple

$$(T_3, T_4, T_5, T_6, T_7) = (-1080, -1936, 75316, 830590, -37193040)$$

and positive moment/localizing matrices. This witness is not a global dual character. Since the 1080 weight-three checks span $K^{\perp}$, the condition $T_3 = -A_3$ forces $\chi(h) = (-1)^{\mathrm{wt}(h)}$ on all of $K^{\perp}$, hence $T_4 = +A_4 = 10530$, contradicting the local witness. Thus octahedron-local cells plus independent shell complements cannot lower the current theorem

$$134 \le \rho(K) \le 173;$$

the next radius model must encode global cross-octahedron character closure.

The binary 30-layer from Pass4997 is now resolved equivariantly. Let Q_{30} denote the triangle-span modulo residual-square-span carrier and let Q_{10} be its canonical ten-dimensional Q43 target. The kernel has dimension 20. Solving the complete PSp generator intertwining equations between this kernel and the binary rank-20 tritangent-selector code gives a one-dimensional Hom space whose unique nonzero map has rank 20; the same map commutes with the outer PGSp generator. Therefore

$$0 \longrightarrow V_{20}^{\mathrm{trit}} \longrightarrow Q_{30} \longrightarrow Q_{10} \longrightarrow 0$$

is a full-group exact sequence over $\mathbb{F}_2$. The complete affine section equations have no solution, so this extension is nonsplit already over PSp.

Corrected readout boundary. The global 85-channel line-plus-tritangent reader has erasure distance six, not eight. Every W33 point gives a centered relation among its four incident line sensors. If p and q are collinear points, their pencils share one line, and subtracting the two four-line relations cancels that common coordinate and leaves a raw six-line dependency. The 240 collinear point pairs give 240 distinct support-six failures, and exact rank checks find no raw line or tritangent dependency of support at most five. Consequently

$$\boxed{d_{\mathrm{erasure}}(R) = 6},$$

so arbitrary erasure of at most five sensors is guaranteed safe. The centered line and tritangent sensor spaces are orthogonal; a mixed dependency must contain a nonzero centered dependency in both blocks, of support at least four and five respectively, hence there is no mixed support-eight cocircuit. The 135 $2K_4$ tritangent supports of Pass4998 remain the exact pure-tritangent support-eight family.

The 240 minimum line failures have additional structure. With Z the W33 point–line incidence matrix, define $D_{pq} = Z_p - Z_q$ for each W33 point-graph edge $\{p, q\}$. Then D is 240×40, has rank 24, spans the complete left nullspace of the line reader, and

$$D^T D \sim 60^{(24)} \oplus 0^{(16)}.$$

Thus, after scaling by $1/\sqrt{60}$, the minimum six-line failure modes form a Parseval frame for the entire 24-dimensional line-reader null sector.

The real 270-octahedron edge frame is also resolved more precisely. Its share-three graph has spectrum

$$32^{(1)}, \quad 14^{(20)}, \quad 8^{(15)}, \quad 2^{(84)}, \quad (-4)^{(150)},$$

and the rank-120 active space is exactly

$$1 \oplus 20 \oplus 15 \oplus 84.$$

The natural 270×36 incidence recording the six double-sixes missed by each tritangent pair has image exactly $1 \oplus 20 \oplus 15$, while the natural tritangent-endpoint incidence projects with rank 20 onto the active 20-sector. Hence the remaining active block is 84-dimensional. In particular the real rank-120 octahedron carrier is not the coexact $30 \oplus 90$ module: the former contains a trivial constituent and the latter does not. Likewise its binary rank 90 is modular rather than a real degree-90 constituent.

Modulo two, the octahedron frame has a second exact geometric resolution. Shared-line projection maps its 270 rows onto the 270 overlap-four spread-intersection vectors, whose span is the 30-dimensional orthogonal complement of the Q43 adjacency code. Therefore

$$0 \longrightarrow K_{60} \longrightarrow O_{90} \longrightarrow C_{Q43}^{\perp}(30) \longrightarrow 0.$$

No identification of K_{60} with an unrelated real carrier is made without an intertwiner.

Finally, the residual affine triple is a genuine torsor rather than a secretly labeled qutrit. After choosing one of the four base-line points, the PSp line-and-point stabilizer has order 162 and acts regularly through C_3 on the three completions, with kernel 54. The full PGSp stabilizer has order 324 and acts through S_3, again with kernel 54. Therefore no intrinsic PSp- or PGSp-equivariant choice of origin exists. The Witting outer sign supplies only the reflection parity $S_3/C_3 \cong C_2$. A physical compiler that names the states $0, 1, 2$ must carry an external phase, time-bin, OAM, or equivalent C_3-breaking reference.

Passes 5008–5015 current frontier

Exact results and boundaries are frozen in `analysis/PASS5008_5015_EXECUTED_OUTCOMES.md` and the associated JSON certificates.

Projective-plane closure, opposite 60-extensions, and the cover-cube realization of H_1^{81} (Passes 5016–5023)

The post-octahedral character-closure deficit admits a sharper exact factorization. Among the 1080 sigma-even A_3 triangle checks, all 1080 K_4 subgraphs of H_{36} have four even triangular faces. Their tetrahedral boundary relations form one $\mathrm{PGSp}(4,3)$ orbit and have binary rank 755. Since the triangle-check span has rank 324, its full relation space has dimension $1080 - 324 = 756$. The remaining one-dimensional class has an explicit closed 18-triangle representative on 10 vertices and 27 edges, with every edge occurring twice, every vertex link a cycle, and Euler characteristic one. It is therefore a triangulated $\mathbb{RP}^2$ class mod two and is not a tetrahedral boundary. Together with the 270 independent octahedral equations, the complete low-shell closure factors as

$$1566 = 755 + 1 + 270 + 540,$$

so the previous 1296 post-local deficit is precisely $756+540$. This reorganizes the exact distance-173 decision problem but does not change the rigorous bound

$$134 \le \rho(K) \le 173.$$

The real and binary sixty-dimensional octahedron sectors are now related explicitly across characteristic two. Let

$$L_{60} = \ker(X - 2I) \cap \ker(B_{\mathrm{end}}^{T}) \subset \mathbb{Q}^{270}.$$

A primitive integral basis of this real sector reduces with rank 60 mod two, even though the full defining equation kernel jumps to dimension 174 in characteristic two. Comparing the resulting full-PGSp module with the binary K_{60} gives one-dimensional Hom spaces in both directions. The unique maps have ranks 14 and 46, respectively, their two compositions vanish, and both endomorphism rings are scalar. The rank-14 image is exactly the Pass5010 S_{14}. Hence the two modules are not isomorphic; instead they are opposite nonsplit extensions,

$$0 \to S_{14} \to K_{60} \to Q_{46} \to 0, \qquad 0 \to Q_{46} \to L_{60} \to S_{14} \to 0.$$

The 200 nine-tritangent exact covers form a two-fiber Schurian coherent configuration rather than one transitive association scheme. Its fibers are the 40 W33 point-covers and 160 incident point-line flag-covers, and its ordered orbital rank is

$$3 + 4 + 4 + 8 = 19.$$

If U is the 200×45 cover/tritangent incidence matrix and A_T is the tritangent intersection graph $\mathrm{srg}(45, 12, 3, 3)$, then

$$U^T U = 30I - 10A_T + 10J,$$

so $\operatorname{rank} U = 25$ and the nonzero squared singular spectrum is $360^{(1)} + 60^{(24)}$. Thus the cover rows carry exactly $1 \oplus V_{24}$.

The corrected 120 signed $K_{3,3}$ minimum circuits give a second canonical realization of the same tritangent sector. Their signed 120×45 matrix S has rank 24 over $\mathbb{Q}$, $\mathbb{F}_2$, and $\mathbb{F}_3$, has Smith invariants 1^{24}, and obeys

$$S^T S = 15I - 5A_T + J = 30P_{24}.$$

Its binary and ternary row codes are both $[45, 24, 6]$, with 120 binary minimum words and 240 ternary minimum words, respectively. Centering the cover rows by $U_c = U - \frac{1}{5}J$ gives the exact frame identity

$$U_c^T U_c = 60P_{24} = 2S^T S.$$

Thus exact covers and minimum Steiner circuits are two tight frames for the same V_{24}.

Finally, the three Steiner circuits over each W33 line produce an intrinsic eight-cover cube Q_3. The forty line-cubes are edge-disjoint and glue into a connected bipartite graph on 40 point-covers and 160 flag-covers with 480 edges. The edge

$$(p, q) \ -- \ r \qquad (r \in q,\ r \neq p)$$

is canonically the directed W33 edge $p \to r$. Filling the six square faces of each cube gives a finite cell complex

$$C_2^{240} \longrightarrow C_1^{480} \longrightarrow C_0^{200}$$

with boundary ranks 200 and 199, hence

$$(H_0, H_1, H_2) = (1, 81, 40).$$

Topologically it is a wedge of 81 circles and 40 two-spheres. The 240 square faces are canonically indexed by the 240 undirected W33 edges.

This 81 is now connected to the prior Hodge carrier by an explicit chain map. Map a point-cover r to point r, a flag-cover (p, q) to point p, and the cube edge $(p, q) - -r$ to the W33 edge $\{p, r\}$. Every cube square maps to a four-cycle in one W33 K_4 line and hence to the W33 triangle-boundary span. The induced map on H_1 has rank 81 over both $\mathbb{F}_2$ and $\mathbb{F}_3$. Therefore the cover-cube H_1 is canonically isomorphic to the previously audited W33 line-triangle homology sector, rather than merely sharing its dimension.

Passes 5024–5027: exact-cover Levi bridge

The tritangent-cover carrier has an exact graph-theoretic bridge to the W33 Levi graph. The cover/line support graph has 240 vertices and 320 edges; its 160 one-line cover vertices are pendant, so its 2-core is exactly the 80-vertex point–line Levi graph and its cycle rank is 81. A second

canonical graph uses the 160 incident point–line covers as edge subdivisions of that Levi graph, again giving cycle rank 81 and sending each Levi octagon to a 16-cycle.

For the cover–line incidence matrix H, one has $H^T H = 8I + A_{\text{line}}$. The later certified Levi spectrum also corrects the historical Pass74 spanning-tree arithmetic to $2^{83}5^{23}$. These are finite graph consequences only; no new physical inference is made from the repeated value 81. **COVER-CHAMBER PROJECTOR AND APARTMENT FRAME (Passes 5028–5035).** The 160 incident point–line covers are the chambers of the C_2 building of $W(3,3)$. If $\ell(f,g)$ is gallery distance, define

$$R_{fg} = (-1)^{\ell(f,g)} 3^{4-\ell(f,g)}.$$

Its five values are $81, -27, 9, -3, 1$, and exact multiplication gives $R^2 = 160R$ with zero panel sums and trace $160 \cdot 81$. Thus $P_{\text{St}} = R/160$ is the rank-81 chamber-cycle projector. Together with Pass 5023 this is the canonical W33 Hodge H_1 carrier, now realized inside the flag–flag coherent-algebra corner.

For the signed chamber-by-apartment matrix X and unsigned apartment-by-cover matrix Y,

$$XX^\top = 160P_{\text{St}}, \qquad \operatorname{rank} X = 81,$$

so the 1620 apartments form a tight frame for the protected 81-space. Also $\operatorname{rank} Y = 160$ and

$$\operatorname{spec}(Y^\top Y) = 0^{40} \oplus 40^{81} \oplus 72^{15} \oplus 144^{15} \oplus (243 - 9\sqrt{409})^{24} \oplus (243 + 9\sqrt{409})^{24} \oplus 1296^{1}.$$

Hence the same 81 is already the eigenvalue-40 block on the full 200-cover carrier.

The 1620 apartments form one $PSp(4,3)$ orbit, with setwise stabilizer orders 16 in PSp and 32 in $PGSp$. Their line-incidence matrix obeys

$$B^\top B = 156I + 21A_{\text{line}} + 6J.$$

The Levi graph and pendant-cover support graph have critical group

$$(\mathbb{Z}/4)^6 \oplus (\mathbb{Z}/40)^{22} \oplus \mathbb{Z}/160,$$

while full edge subdivision gives

$$(\mathbb{Z}/2)^{52} \oplus (\mathbb{Z}/8)^6 \oplus (\mathbb{Z}/80)^{22} \oplus \mathbb{Z}/320.$$

Finally the cube-complex rational homology representation is

$$H_0 = \mathbf{1}, \qquad H_1 = \text{St}_{81}, \qquad H_2 = \mathbf{1} \oplus V_{24} \oplus V_{15}.$$

The separate 240-object constructions remain distinct unless an explicit action-preserving map is supplied.

Passes 5036–5043: apartment transport, Jacobian, and the q^4 building law

The exact-cover apartment transform now extends through the labeled cubic-surface tritangent carrier. If U is the canonical 200×45 cover/tritangent matrix, Y the 1620×200 apartment/cover matrix, and $Z = YU$, then

$$\operatorname{rank} Z = 25, \qquad Z^\mathsf{T} Z = 3132I - 1044A_{\text{trit}} + 9540J,$$

with squared singular spectrum $419904^1 + 6264^{24} + 0^{20}$. Thus the apartment transport again selects $\mathbf{1} \oplus V_{24}$ and annihilates V_{20}.

On the 160 chamber/flag covers, the eight flag–flag orbitals are the eight type-C_2 Bruhat cells, with lengths $0,1,1,2,2,3,3,4$ and subdegrees $1,3,3,9,9,27,27,81$. The Steinberg kernel has coefficients

$$81,-27,-27,9,9,-3,-3,1, \qquad R_w=(-1)^{\ell(w)}3^{4-\ell(w)},$$

so $P_{\mathrm{St}}=R/160$ is the same protected rank-81 projector.

The all-edge subdivision also carries this sector arithmetically. Modulo two its reduced Laplacian kernel is canonically the Levi binary cycle space:

$$K(\mathrm{SubLevi})/2K(\mathrm{SubLevi})\cong H_1(\mathrm{Levi};\mathbb{F}_2)\cong\mathbb{F}_2^{81}.$$

The 1620 signed apartment cycles generate $H_1(\mathrm{Levi};\mathbb{Z})$ integrally: an explicit 81-apartment minor in fundamental-cycle coordinates has determinant ±1. Modulo two the Levi cycle space is therefore a $[160,81,8]_2$ code whose complete minimum-weight shell is exactly the apartment orbit.

The apartment frame obeys $XX^{\mathsf{T}}=160P_{\mathrm{St}}$. Its absolute off-diagonal correlation census from every apartment is $4^{16},3^{32},2^{96},1^{288},0^{1187}$. This certifies reconstruction after any at most 46 apartment removals; removing all 81 apartments through one chamber gives an explicit rank-80 failure example.

Finally, the mechanism is the $q=3$ member of the symplectic rank-two family. For $W(3,q)$ the Levi cycle rank is q^4, each chamber lies in q^4 apartments, and

$$N_{\mathrm{apt}}=\frac{q^4(q+1)^2(q^2+1)}{8}, \qquad R_{fg}=(-1)^{\ell(f,g)}q^{4-\ell(f,g)}.$$

The full matrix identities are reconstructed directly at $q=2$ and $q=3$. For odd q, the subdivided-Levi mod-two Jacobian quotient has dimension q^4. These are finite building/module statements; no continuum dynamics is inferred from them.

Passes 5044–5051: exact apartment erasure, local V_{24} compiler, and theta relations

The signed apartment frame now has an exact erasure distance. Modulo two its apartment-evaluation code has parameters

$$[1620,81,81]_2.$$

Its dual has dimension 1539 and minimum weight three. There are exactly 4320 weight-three checks, each apartment occurring in eight of them, and those checks span the complete dual. The corresponding exact even-set optimization has optimum 81; hence every set of at most 80 apartment erasures preserves the protected rank 81, while deleting the 81 apartments through one chamber lowers the rank to 80.

The all-edge subdivision Jacobian refines this same sector 2-adically. Its 2-primary elementary divisors are

$$2^{52}, \qquad 8^{6}, \qquad 16^{22}, \qquad 64,$$

so the successive height dimensions are $81,29,29,23,1,1$. The first layer is $H_1(\mathrm{Levi};\mathbb{F}_2)$; the final one-dimensional layer is necessarily trivial in characteristic two.

The labeled cubic-surface transport also admits a sharply local implementation. If $Z=YU$ and the DC component is removed by $Z_{24}=5Z-12J$, then $\operatorname{rank}Z_{24}=24$. The 162 apartments through any fixed W33 point already have rank 24, as do the corresponding fixed-line stars. In particular, an explicit basis of only 24 apartments through one W33 point carries the full nontrivial V_{24} transport.

The q-family formulas now follow symbolically from the type-C_2 building and its Hecke sign idempotent. The Weyl lengths occur with multiplicities $1, 2, 2, 2, 1$, Bruhat cells have sizes q^ℓ, and

$$R_{fg} = (-1)^{\ell(f,g)} q^{4-\ell(f,g)}, \qquad R^2 = |\mathrm{Ch}| R,$$

with $|\mathrm{Ch}| = (q+1)^2(q^2+1)$. Consequently the Levi cycle rank and the number of apartments through a chamber are both q^4, while

$$N_{\mathrm{apt}} = \frac{q^4(q+1)^2(q^2+1)}{8}.$$

Finally, the unsigned 1620-apartment permutation action has orbital rank 131 and contains five copies of the degree-81 Steinberg constituent. The signed apartment-cycle transform therefore selects one canonical Steinberg copy from a five-copy ambient permutation carrier. The 4320 minimum dual checks have a geometric description: an opposite same-type Levi pair has four internally disjoint length-four geodesics, and choosing any three gives a theta graph whose three pairwise path-unions are apartments summing to zero over $\mathbb{F}_2$. The resulting apartment orbit contains 4320 projective binary lines but no complete seven-point projective plane. For general q the theta count is $q^3(q+1)(q^2+1)\binom{q+1}{3}$ and each apartment lies in $4(q-1)$ such triples; full-dual generation and distance q^4 beyond the verified $q = 2, 3$ anchors remain a stated conjectural frontier.

Passes 5142–5149: cubic q=5 leader barrier and root-direction mean-value calculus

The q=5 minimum-distance search now has a genuinely third-order obstruction rather than only a pairwise relaxation. If an apartment contains r selected chamber stars, then $0 \le r \le 8$ and the pointwise inequality

$$7\,\mathbf{1}_{r \bmod 7} \ge 7r - 14\binom{r}{2} + 6\binom{r}{3}$$

holds. Summing apartment-by-apartment and inserting the all-q triple-star law of Pass 5140 gives a cubic lower bound in terms of selected-chamber gallery data. In particular, a selected chamber triple with sorted gallery signature $(1, 1, 2)$ contributes exactly q^2 common apartments.

For a cut-minimal selected Levi subgraph, let m be its number of selected chamber edges and let n_1 be the number of adjacent selected chamber pairs. Its selected-chamber line graph satisfies

$$N_{112} = \sum_v \binom{d_v}{2} - 3\tau,$$

where N_{112} counts $(1, 1, 2)$ triples and τ is the number of line-graph triangles, equivalently the number of degree-three selected Levi stars. Combining this identity with exact deletion bounds and the chamber-scheme Delsarte relaxation closes q=5 chamber leaders 18, 19, and 20. The resulting strict-counterexample barrier is

$$\boxed{\mathrm{leader}_{\mathrm{chamber}}(y) \ge 21 \quad \text{for every q=5 codeword with } \mathrm{wt}(y) < 625.}$$

The leader-20 uniform lower bound is 711. At leader 21, every sector with $n_1 \le 32$ is also excluded; the sole remaining cubic wall is the sharp $n_1 = 33$ sector. There the guaranteed $(1, 1, 2)$ contribution gives triple mass 1200, while mass 1242 would suffice to reach weight 625. Thus the present leader-21 frontier is concentrated into an exact residual target of only 42 common-apartment incidences. This is not yet a q=5 distance theorem.

The abstract sharp $m = 18, n_1 = 27$ leader is also realized inside the actual $W(3,5)$ Levi graph. One opposite-line/transversal family has $4^6 = 4096$ pendant gauges with apartment weights

$$5832^4,\ 5848^{180},\ 5856^{480},\ 5864^{1260},\ 5872^{1440},\ 5880^{732},$$

and an independent $K_{3,3}$ point-collinearity carrier gives weight 5832. These witnesses show that the sharp local adjacency profile is geometric, while also illustrating how far representative sharp leaders can lie above the 625 target. They are witnesses, not an orbit-complete classification.

The root-direction controller also admits a complete mean-value formulation. Let $U(q)$ be the maximal unipotent chamber controller and let $H_0, \dots, H_3$ be its four positive-root subgroups. If P_i denotes averaging on right H_i-cosets, then

$$\boxed{A_\theta = q(P_0 + P_1 + P_2 + P_3) - 4I}, \qquad \boxed{L_\theta = q(4I - P_0 - P_1 - P_2 - P_3)}.$$

Consequently

$$\langle f, L_\theta f\rangle = q \sum_{i=0}^{3} \|(I - P_i)f\|^2,$$

and for an indicator 1_S this is the exact theta-edge boundary $|\delta_\theta S|$. The open uniform spectral-gap-q statement is therefore equivalent, on mean-zero functions, to the single projection inequality

$$\sum_{i=0}^{3} \|P_i f\|^2 \le 3\|f\|^2.$$

Pass 5137 proves equality in the linear-character sector; the nonlinear all-q inequality remains open.

If H is the element-versus-root-coset incidence matrix, the same geometry gives the integral Gram identity

$$\boxed{HH^T = 4I + A_\theta}.$$

Thus over characteristic zero the free root-coset defect is precisely the -4 theta eigenspace. At q=3 this recovers rank 69 and the free 12-space, while the known $\mathbb{Z}/3$ Smith defect remains genuinely arithmetic torsion. At q=5 the exact theta spectrum fixes rational rank 405 and free defect dimension 220 before any integral Smith analysis.

Finally, the root-direction word metric is now symbolic rather than merely interpolated. Over finite fields of characteristic greater than three, after normalizing states with $a, b \neq 0$ by

$$u = \frac{c}{ab}, \qquad v = \frac{d}{a^2 b},$$

all states reachable in at most three root moves lie on the eight curves

$$u = 0, \quad u = -1, \quad v = 0, \quad v = 1, \quad v = -u, \quad v = -2u, \quad v = -2u - 1, \quad v = u^2.$$

Their complement contains $(q-4)^2$ normalized pairs. Hence the exact distance shells are

$$\boxed{1, \quad 4(q-1), \quad 8(q-1)^2, \quad (q-1)^2(10q-21), \quad (q-1)^2(q-4)^2}$$

for characteristics greater than three. Characteristics two and three have additional curve collisions and retain their separately certified small-field profiles.

Evidence boundary. The q=5 apartment-code theorem $d = 625$ is still open: strict counterexamples are now forced to chamber leader at least 21, and the leader-21 cubic method has one sharp $n_1 = 33$ sector left. The root-coset Gram and Dirichlet identities are exact finite group/graph statements, not hardware-performance claims. The projection reformulation does not itself prove the all-q nonlinear theta gap. The embedded sharp-leader census is diagnostic and not a classification theorem.

Passes 5158–5165: path-enhanced q=5 barrier, fourth-order apartment law, decoder hub pruning, and odd-characteristic root metric

The q=5 strict-counterexample barrier advances four chamber-leader shells beyond the Pass 5149 frontier. Pass 5148 had reduced leader $m = 21$ to the single sharp sector $N_1 = 33$, with pairwise contribution -439, forced $(1, 1, 2)$ triple count at least 48, and a residual need for only 42 more common-apartment incidences. That residual is forced by selected four-edge Levi paths. Every such path of chamber edges e_0, e_1, e_2, e_3 injects the two distinct chamber triples $\{e_0, e_1, e_3\}$ and $\{e_0, e_2, e_3\}$ of gallery signature $(1, 2, 3)$; Levi girth eight makes their intervening geodesic unique. Pass 5140 assigns five common apartments to each such triple at q=5. The degree equations in the sharp $m = 21, N_1 = 33$ sector force at least six selected four-edge paths, hence at least twelve $(1, 2, 3)$ triples and sixty additional triple-intersection incidences. The cubic parity minorant therefore gives

$$-439 + \frac{6}{7}(25 \cdot 48 + 5 \cdot 12) = 641 > 625,$$

closing leader 21.

The same path count can be optimized by a small local degree-type relaxation. For each selected Levi vertex, its contribution to the number of four-edge paths centered there is

$$\sum_{\{u,w\} \subset N(v)} (d(u) - 1)(d(w) - 1).$$

Balancing degree-class stubs while imposing the deletion-derived endpoint-degree constraints gives rigorous lower bounds because the relaxation omits, rather than adds, simplicity and girth restrictions. At leader 22 the sharp adjacency sectors $N_1 = 34, 35$ force respectively $P_4 \geq 56, 68$ and apartment-weight bounds $972, 900$; the weakest sector is $N_1 = 33$ at 668. At leader 23, the sectors $N_1 = 34, \ldots, 38$ force

$$P_4 \geq 44, 54, 64, 76, 94$$

and corresponding weight bounds

$$1151, 1040, 854, 781, 760.$$

Thus leaders 22 and 23 are excluded as strict sub-625 counterexamples.

Leader 24 has one final local-relaxation equality wall at $N_1 = 40$. The degree-type relaxation has profiles

$$(n_1, n_2, n_3) = (1, 7, 11), (4, 4, 12), (7, 1, 13)$$

with P_4 lower bounds $100, 96, 96$. The two $P_4 = 96$ cases are incompatible with Levi girth eight. In the $(4, 4, 12)$ case, equality forces the induced degree-three graph to be a C_{12} and the four degree-two vertices to be antipodal two-edge chords. Their four antipodal classes would have to form an independent set of size four in the quotient C_6, impossible because $\alpha(C_6) = 3$. In the $(7, 1, 13)$ case equality forces the degree-three induced bipartite degree split

$$(3, 2, 2, 2, 2, 2, 2) \mid (3, 3, 3, 2, 2, 2),$$

for which exact backtracking finds no simple C_4/C_6-free realization. Hence actual $P_4 \geq 97$ and the final cubic lower bound is 629. Consequently

$$\boxed{\mathrm{wt}(y) < 625 \Longrightarrow \mathrm{leader}_{\mathrm{chamber}}(y) \geq 25 \qquad (q = 5).}$$

This is still a strict-counterexample barrier, not the full q=5 distance theorem.

The fourth-order chamber-star coefficient is now explicit for all finite q. Four distinct chamber edges can lie in an apartment C_8 in exactly seven dihedral six-distance patterns. The consecutive-four-edge pattern satisfies

$$(1, 1, 1, 2, 2, 3) \longmapsto q$$

common apartments, while

$$(1, 1, 2, 2, 3, 4),\ (1, 1, 2, 3, 3, 4),\ (1, 1, 3, 3, 4, 4),\ (1, 2, 2, 3, 3, 3),\ (1, 2, 2, 3, 3, 4),\ (2, 2, 2, 2, 4, 4)$$

each determine a unique apartment; every other six-distance signature gives zero. Complete rooted censuses at $q = 2, 3, 4, 5$, including $\mathbb{F}_4$, have no signature splitting. Through one base chamber the consecutive pattern occurs in $4q^3$ quadruples and each of the other six multiplicities is respectively $8q^4, 8q^4, 2q^4, 4q^4, 8q^4, q^4$.

The requested q=5 equality-shell attack also acquires a fourth local moment, although it does not yet eliminate the exotic shell. In a local K_6 cut of weights $5, 8, 9$, the selected line graph contains respectively $5, 2, 0$ four-cliques. Hence for one point/line chart type

$$Q_{4,\mathrm{type}} = 5(A - h_8 - h_9) + 2h_8 = 1250 - 6h_8 - 9h_9.$$

The minimal exotic coarea profile $(h_8, h_9) = (2, 1)$ therefore has $Q_{4,\mathrm{type}} = 1229$, a fourth-moment defect 21 from the chamber-star value 1250, in addition to the previously established triangle defect 28. No global invariant equating this fourth moment to the star value has been proved, so the exotic equality profile is not declared impossible.

The q=3 decoder obstruction admits a symmetry-preserving repair. Retain the original local syndrome ROM and global maximum-vote set, but among tied maximum-vote candidates correct only those having minimum induced degree in the apartment chart-sharing graph. Exhaustion of all connected representatives through a base apartment at weights 1 through 5—counts $1, 20, 490, 13269, 381480$—shows the modified rule preserves monotone radius-five correction and the three-sweep bound. The complete centered $2 + 2 + 2$ weight-six false-center family has 32 representatives through a fixed center, and all 32 clear monotonically. For the original witness $\{1, 2, 3, 6, 27, 54\}$, false center 0 has tie-degree 6 while each true error has tie-degree 2, so the corrected set is exactly the six true errors. Non-centered connected weight-six types have not yet been orbit-completely classified, so a global radius-six theorem is not claimed.

The chamber-dependency cut code also has a uniform second shell. Its second nonzero weight is

$$\boxed{2q},$$

and the weight-$2q$ words are exactly cuts of adjacent point-line Levi vertex pairs, one for each chamber, giving $(q + 1)^2(q^2 + 1)$ words. Girth eight proves the small-shore statement and the Levi spectral gap $q + 1 - \sqrt{2q}$ excludes larger shores.

Finally, the root-direction Cayley metric is now symbolic in every odd characteristic. Pass 5143 handles characteristic greater than three. In characteristic three the normalized three-move curves become

$$u = 0, \quad u = -1, \qquad v \in \{0, 1, -u, u, u - 1, u^2\}.$$

For $u \notin \{0, -1, 1\}$ these six values are distinct; at $u = 1$ only three remain. For every $q = 3^f$ this yields exact shells

$$\boxed{1, \quad 4(q-1), \quad 8(q-1)^2, \quad 10(q-2)(q-1)^2, \quad (q-1)^2(q-3)(q-5)}.$$

At q=3 the last shell vanishes and the exact profile is $1, 8, 32, 40$. Characteristic two remains the sole unsolved uniform root-metric family.

Evidence boundary. The q=5/all-q apartment-code minimum-distance theorem remains open for chamber leaders at least 25, and the weight-625 exotic equality shell remains unclassified. The all-q nonlinear theta spectral-gap target $\sum_i \|P_i f\|^2 \le 3\|f\|^2$ is not duplicated here because the collision-reserved Passes 5150–5157 own the centered/theta spectral continuation; no theorem from that packet had landed at the time of this insertion. The hub-pruned decoder has a certified radius-five guarantee and repairs the full centered minimal weight-six obstruction family, but global radius six remains open. Controller and metric statements are finite algebraic geometry, not hardware-performance claims.

Passes 5170–5173: q=5 geodesic injections, incidence coupling, and the leader-31 wall

The q=5 apartment-code distance program now has two additional intrinsic geodesic constraints. A cut-minimal chamber leader is a bipartite subcubic Levi subgraph of girth at least eight. In such a graph, selected three-edge paths inject into opposite-part nonedges: two different paths with the same endpoints would create a 4- or 6-cycle. A leaf reaches at most four vertices of the opposite part by such a path, giving a complementary unreached-nonedge defect. At leader size 28 these facts rule out the only dangerous adjacent-pair layers $N_1 = 49, 50$; the surviving layer $N_1 \le 48$ has cubic lower bound

$$\mathrm{wt} \ge 651.$$

Hence every strict q=5 counterexample has chamber leader at least 29.

There is a second geodesic injection. A selected four-edge Levi path is uniquely determined by its two outer chamber edges, so

$$P_4 \le N_3,$$

where N_3 is the gallery-distance-three coordinate of the chamber association scheme. Coupling this inequality directly into the exact Delsarte optimization closes leader size 29: the two surviving dense degree types have lower bounds 715 and 630. Thus the strict-counterexample wall rises to leader at least 30.

A separate all-q matrix identity couples the gallery-distance-two coordinate to the point–line incidence geometry. If Y is any selected chamber set, x and y are its selected point and line degree vectors, $m = |Y|$, N_1 is its adjacent-pair count, and N is the point–line incidence matrix, then

$$\boxed{N_2 = x^{\mathsf{T}} N y - (m + 2N_1).}$$

For $W(3, q)$,

$$NN^{\mathsf{T}} = (q+1)I + A_{\mathrm{point}}$$

has eigenvalues $(q+1)^2, 2q, 0$. Writing $W_P + W_L = N_1$ and $v = (q+1)(q^2+1)$ therefore gives the exact spectral upper bound

$$N_2 \le \frac{m^2}{q^2+1} + \sqrt{2q\left(m + 2W_P - \frac{m^2}{v}\right)\left(m + 2W_L - \frac{m^2}{v}\right)} - (m + 2N_1).$$

This removes N_2 as a free Delsarte coordinate once the point/line wedge split is known.

Finally, the five-edge-path extension admits a sharper universal form. If t_d is the number of endpoints of selected four-edge paths that lie at selected degree d, then

$$P_5 = 2P_4 - t_1 - \frac{t_2}{2}.$$

A degree-one endpoint terminates at most 8 four-edge paths and a degree-two endpoint at most 16, so

$$\boxed{P_5 \geq \max(0, 2P_4 - 8n_1 - 8n_2).}$$

With the $P_4 \leq N_3$ coupling, this closes every leader-30 sector: pairwise Delsarte already gives 776 through $N_1 = 40$, the strengthened cubic bounds give 827 at $N_1 = 50$, and the two densest layers satisfy

$$N_1 = 51 : \ \text{wt} \geq 794, \qquad N_1 = 52 : \ \text{wt} \geq 760.$$

The raw $N_1 = 53$ layer is impossible by edge-deletion degree constraints. Therefore

$$\boxed{\text{every q=5 word of weight } < 625 \text{ has chamber leader } \geq 31.}$$

Evidence boundary. This is a strict-counterexample barrier, not the q=5 minimum-distance theorem. Leaders ≥ 31 and the weight-625 equality shell remain open. The incidence and geodesic statements are finite generalized-quadrangle/code theorems; no hardware timing, noise threshold, or physical-particle interpretation is inferred.

Passes 5174–5181: all-q theta gap, global q=3 radius six, complete finite-field root metric, quartic parity, and point/line tensor asymmetry

The root-coset theta spectral frontier closes uniformly. Write the maximal-unipotent chamber controller in canonical coordinates

$$u(a, b, c, d) = x_0(a)x_1(b)x_2(c)x_3(d),$$

for which direct multiplication gives

$$(a, b, c, d)(A, B, C, D) = (a + A,\ b + B,\ c + C - Ab,\ d + D - 2Ac + A^2b).$$

Right multiplication by H_1, H_2, H_3 is therefore literal translation in b, c, d, respectively. Let P_i be the four root-subgroup averaging projections from Pass 5147 and let

$$\mathcal{L} = \{f(a, b, c, d) = g(a, b)\}, \qquad \dim \mathcal{L} = q^2,$$

be the linear-character sector. Fourier transform in (b, c, d) diagonalizes $P_1 + P_2 + P_3$. On $\mathcal{L}^\perp$ at least one of the c, d frequencies is nonzero, so

$$P_1 + P_2 + P_3 \leq 2I.$$

Since $0 \leq P_0 \leq I$,

$$\boxed{\sum_{i=0}^{3} P_i \leq 3I \quad \text{on } \mathcal{L}^\perp.}$$

Together with $A_\theta = q\sum_i P_i - 4I$ and the already proved linear-sector eigenvalue $3q-4$, this yields the exact all-finite-field result

$$\boxed{\lambda_2(A_\theta) = 3q-4, \qquad \operatorname{gap}(A_\theta) = q.}$$

No nonlinear irreducible-representation classification is needed.

The four-root Cayley word metric is now classified in every characteristic. In characteristic two the $(0,2)$ two-root ordering collision removes one two-move family, and for $a, b \neq 0$ the normalized three-move locus is

$$u = 0, \quad u = 1, \qquad \text{or} \qquad v \in \{0, 1, u, u^2\}.$$

Thus for $q = 2^f$ the exact shells are

$$\boxed{1, \quad 4(q-1), \quad 7(q-1)^2, \quad 4(q-1)^2(2q-3), \quad (q-1)^2(q-2)(q-4).}$$

Combined with Pass 5143 (characteristic > 3) and Pass 5165 (characteristic three), this completes the symbolic root-direction metric over all finite fields.

The q=3 hard-decision decoder also advances from radius five to radius six, but only after falsifying the first proposed repair. Pure max-vote plus minimum tie-graph degree fails on the connected weight-six set

$$\{0, 219, 492, 493, 526, 527\},$$

whose nine maximum-vote candidates form a 4-regular tie graph containing three false candidates. Vote provenance separates them: false candidates have no singleton local-mask vote source. The refined deterministic rule is

$$\text{maximum vote} \longrightarrow \text{maximum singleton-source count} \longrightarrow \text{minimum tie-graph degree}.$$

An exact connected census contains 11,401,011 weight-six sets through a fixed apartment. Every one has a nonempty first correction contained in the true error set. The refined rule also replays all connected weights one through five with no failure and maximum three sweeps. Component separation then gives the global theorem

$$\boxed{\text{every q=3 error pattern of weight at most six clears in at most four sweeps.}}$$

This is a theorem for the stated finite hard-decision rule, not an ML decoder or noise-threshold claim.

The q=5 equality-shell analysis acquires a new factorized coordinate system on the P/opposite-point side. The P chart-intersection graph decomposes into

$$\frac{q^2(q^2+1)}{2}$$

components, each $K_{m,m}$ with $m = \binom{q+1}{2}$, and the theta restriction code on each component is

$$C_q \otimes C_q, \qquad C_q = \operatorname{Cut}(K_{q+1}),$$

with parameters $[m^2, q^2, q^2]_2$. Every minimum component word is a simple tensor of two vertex-star cuts, so the component minimum shell has exactly $(q+1)^2$ words. At q=5 this is the $[225, 25, 25]$ code with exactly 36 minimum words.

Exhausting all $2^{25} = 33{,}554{,}432$ states of one q=5 P component gives 140 distinct $(\mathrm{wt}, h_8, h_9, A)$ profiles. Under $h_8 \le 2, h_9 \le 1$, the only states are

$$(0,0,0,0), \qquad (25,0,0,10), \qquad (48,2,0,18).$$

In particular the old P-side candidate $(h_8, h_9) = (2,1)$ is impossible. A weight-625 P-side knapsack has minimum positive coarea cost

$$3h_8 + 4h_9 = 50,$$

so if a weight-625 word is P-heavy then

$$\boxed{A_P \le 240.}$$

The old conditional deficit 2 becomes at least 10 on the P side.

The minimum P atoms themselves have a panel interpretation. Every chamber star restricts to exactly q^2 nonzero P components, each restriction a weight-q^2 atom. Across the exact q=2,3,4,5 anchors these restrictions exhaust the complete tensor minimum shell. Every P atom lies in exactly two chamber stars sharing a line panel; every such chamber pair owns exactly q atoms. Thus a chamber star is the disjoint union of q^2 atoms, namely all q copies over each of its q same-line panel neighbours. At q=5 a P-heavy-free weight-625 candidate is therefore exactly a union of 25 disjoint P atoms, while a chamber star is one distinguished 25-atom incidence pattern.

A crucial point/line firewall accompanies this tensorization. For even q, the classical symplectic quadrangle $W_3(q)$ is self-dual, so point-line duality transfers the complete P tensor decomposition to L/opposite-line charts. For odd q, the classical dual is $Q_4(q)$ rather than $W_3(q)$; there is no same-geometry duality authorizing that transfer. The repo anchors show precisely this parity split: at q=2,4 both P and L graphs decompose into the same $K_{m,m}$ components, whereas at q=3,5 the P graph remains factorized and the L chart-intersection graph is connected. Hence the remaining odd-q equality-shell problem is a factorized-P/connected-L gluing problem, not two copies of the same tensor knapsack.

Finally, the fourth-order apartment parity coefficient is now usable directly. For apartment occupancy $0 \le r \le 8$,

$$\mathbf{1}_{r \text{ odd}} = r - 2\binom{r}{2} + 4\binom{r}{3} - 8\binom{r}{4} + R_5(r),$$

with

$$R_5(0), \ldots, R_5(8) = 0,0,0,0,0,16,64,176,384.$$

Thus every chamber leader satisfies

$$\boxed{\mathrm{wt} \ge S_1 - 2S_2 + 4S_3 - 8S_4 + 16N_{r\ge 5},}$$

where S_3 is supplied by the triple-star law and S_4 by the seven-signature four-chamber law. If no apartment contains five selected leader chambers, the quartic formula is exact. This is deliberately packaged as a collision-safe tool for the parallel q=5 leader frontier rather than duplicating its reserved passes.

Evidence boundary. The all-q theta gap and the finite-field root metric are closed mathematical theorems. The q=3 radius-six result applies only to the explicitly stated deterministic hard-decision decoder. The tensor and atom theorems are P-side statements for odd q; an L-heavy-only q=5 equality candidate is not eliminated here. The q=5/all-q apartment-code minimum-distance theorem remains separate from the strict-leader frontier being advanced in the collision-owned Passes 5182–5189.

Passes 5182–5189: q=5 leader 33, full cut geometry, and the dual-grid incidence layer

The q=5 strict-counterexample recursion advances two more leader sizes. The sharpened path law from Pass 5173 closes every $m = 31$ layer through the deletion cap $N_1 = 55$; the weakest layer is $N_1 = 54$ with apartment-weight lower bound 673. Hence a q=5 word below 625 has chamber leader at least 32.

For $m = 32$, the remaining obstruction is removed by a new gallery-distance-four coupling. A selected five-edge Levi path has opposite outer chamber edges. Such a chamber pair lies in one apartment and has exactly two shortest galleries in its C_8, so

$$P_5 \le 2N_4.$$

The sole dangerous layer $N_1 = 56$ has $P_4 \ge 160$ and $P_5 \ge 256$, hence $N_3 \ge 160$ and $N_4 \ge 128$. The conditioned distance distribution is $(56, 152, 160, 128)$ and gives

$$\mathrm{wt} \ge 631.$$

Thus every strict q=5 counterexample has chamber leader at least 33.

Two exact all-q identities now connect the chamber distance scheme back to the Levi and point geometries. If x, y are the selected point and line degree vectors, then

$$N_2 = x^{\mathsf{T}} N y - (m + 2N_1),$$

and

$$\frac{x^{\mathsf{T}} A_P x + y^{\mathsf{T}} A_L y}{2} = N_1 + 2N_2 + N_3.$$

The point and line graphs are $\mathrm{SRG}((q+1)(q^2+1), q(q+1), q-1, q+1)$, so the second identity carries an exact quadratic-form spectral bound. At q=5 and $m = 33$ the defect is quantized in $3/2 + 2\mathbb{Z}_{\ge 0}$, giving the integer cap $N_1 + 2N_2 + N_3 \le 312 + 4N_1$.

The full cut-space theorem from Pass 5110 also admits a useful global form. A minimum chamber representative Y satisfies, for every Levi vertex set S,

$$2|Y \cap \delta(S)| \le |\delta(S)|,$$

or equivalently

$$2e_\Gamma(S) \le 4e_Y(S) + \sum_{v \in S} (q + 1 - 2d_Y(v)).$$

For q=5 this forces every host incidence between selected-degree-three vertices to be selected and every host 3–2–3 path to contain a selected edge. This is strictly stronger than the singleton degree cap used in the earlier recursion.

The P-component tensor decomposition now has a geometric identification. The chamber-star P-component footprints are indexed by W-points. Every P component is indexed by an unordered polar pair $\{H, H^\perp\}$ of non-isotropic projective lines; its point carrier

$$H \sqcup H^\perp$$

is a dual grid inducing $K_{q+1,q+1}$, and its $(q+1)^2$ minimum tensor atoms are exactly the edges of that complete bipartite graph. For distinct W-points, their component footprints meet in q components when the points are collinear and one component otherwise.

If B is point-by-P-component incidence and N is ordinary point-line incidence, then

$$BB^{\mathsf{T}} = (q^2-1)I + (q-1)A + J = (q-1)NN^{\mathsf{T}} + J.$$

Every W-line meets every dual grid in zero or two points, hence $N^{\mathsf{T}}B = 0$ over $\mathbb{F}_2$. At q=5, $\operatorname{rank}_2 N = 91$ and $\operatorname{rank}_2 B = 65$, so

$$\operatorname{im}_{\mathbb{F}_2} B = \ker_{\mathbb{F}_2} N^{\mathsf{T}}$$

and the incidence-dual code is

$$\boxed{[156, 65, 12]_2}.$$

Its 325 minimum words are exactly the 325 P-component dual grids. More generally, for every q the binary W-line dual has minimum distance $2(q+1)$ and its complete minimum shell is precisely the $q^2(q^2+1)/2$ dual grids.

Evidence boundary. The q=5 minimum-distance theorem remains open at leaders ≥ 33, and the weight-625 equality shell still requires the connected L-side gluing. The dual-grid minimum-shell theorem does not imply that minimum dual-grid words span the full incidence dual for even q. All promoted statements are finite geometry/code statements; no physical timing or noise claim is inferred.

73.9 Full-apartment cubic correction and the P-footprint quotient

The chamber-leader recursion at $q = 5$ can be sharpened without assuming a fourth-order apartment-intersection classification. For an apartment containing $r \in \{0, \dots, 8\}$ selected chambers one has the pointwise inequality

$$\mathbf{1}_{\{r \text{ odd}\}} \geq r - 2\binom{r}{2} + \frac{36}{35}\binom{r}{3} - \frac{48}{5}\binom{r}{8}.$$

Thus the cubic coefficient may be raised from 6/7 to 36/35 provided fully selected apartments are charged explicitly. If A_8 denotes their number and P_5 the number of selected five-edge Levi paths, then every full apartment contains eight such windows, whereas a selected five-edge path has a unique apartment completion. Hence

$$8A_8 \leq P_5.$$

A central selected edge of selected endpoint degrees (i, j) supports at most $4(i-1)(j-1)$ such paths. Therefore, writing e_{ij} for the selected edge-type counts,

$$P_5 \leq \sum_{i,j} 4(i-1)(j-1)e_{ij}, \qquad A_8 \leq \left\lfloor \frac{P_5}{8} \right\rfloor.$$

Combined with the existing pairwise Delsarte, P_4, P_5, N_3, and N_4 constraints, this closes chamber leaders 33, 34, and 35. The respective new strict barriers are

$$\boxed{m_{\min} \geq 34}, \qquad \boxed{m_{\min} \geq 35}, \qquad \boxed{m_{\min} \geq 36}.$$

At leader 35 the sharpest surviving relaxed layer is $N_1 = 57$, with certified integer lower bound 627, only two units above the target $5^4 = 625$. Consequently this method is near its natural limit; no claim for leaders $m \geq 36$ is made here.

A separate exact quotient emerges from the opposite-point (P) tensor components. Let F be the binary incidence matrix between the $W(3, 5)$ points and the 325 P-component point blocks.

Each point lies in 25 blocks and each component block consists of 12 points inducing $K_{6,6}$. Direct projective-polarity reconstruction gives

$$\operatorname{rank}_{\mathbb{F}_2} F = 65, \qquad \dim \ker F^T = 91.$$

Every $W(3,5)$ line incidence vector lies in $\ker F^T$, and the binary line incidence code also has rank 91. Hence

$$\boxed{\ker F^T = \langle W(3,5) \text{ line incidences} \rangle_{\mathbb{F}_2}}.$$

The same rank complement is verified independently at $q = 3$ and $q = 7$. For odd q, the parity of each P-component restriction is therefore a genuine cut-gauge invariant; at $q = 5$, a zero component-parity vector admits a gauge-equivalent representative with zero point-parity vector. This normal-form statement does *not* assert preservation of minimum chamber-leader size.

The P-component blocks themselves carry a strongly regular intersection graph. In general its parameters are

$$\mathrm{SRG}\left(\frac{q^2(q^2+1)}{2}, (q+1)(q^2-1), 3q^2-q-2, 2q(q+1)\right).$$

At $q = 5$ this is

$$\mathrm{SRG}(325, 144, 68, 60)$$

with nontrivial eigenvalues 14 and -6. The 25 components in a fixed W-point footprint form a clique, and the Delsarte bound $1 - 144/(-6) = 25$ proves that these footprints are maximum cliques. Every block-graph edge lies in exactly two distinguished point-footprint cliques. The resulting binary footprint code has parameters $[325, 65]$ at the level of length and dimension and contains weight-25 point-footprint words. Its minimum distance is *not* promoted here: the exact exclusion of nonzero weights below 25, and the residual zero-parity apartment sector, remain open.

Evidence firewall. Passes 5198–5200 prove only the strict-counterexample barrier $m_{\min} \geq 36$ at $q = 5$; they do not prove $d = 625$ or classify the weight-625 equality shell. Passes 5201–5203 are P-side quotient and block-geometry theorems and preserve the established odd-q P/L asymmetry. No L-side tensor decomposition is inferred from them.

Passes 5206–5213: leader-36 obstruction, footprint hull, orthogonal graph, and dual code

The current strict q=5 distance barrier is leader at least 36. Applying the first global-cut consequences of Pass 5185 to the Pass 5205 leader-36 wall gives an exact negative diagnostic: the degree-class aggregation bounds

$$x^{\mathsf{T}} N y \leq 16n_1 + 34n_2 + 45n_3.$$

Across the open $N_1 = 54, \ldots, 64$ sectors this only gives $N_2 \leq 381, \ldots, 405$, while the dangerous Delsarte extremizers use $N_2 = 164, \ldots, 175$. Hence the two-vertex/3–2–3 consequences are redundant; any successful cut proof must retain correlated larger-shore host incidences or an independent quotient constraint.

The remaining q=5 weight-625 equality problem reduces sharply to the P-footprint code $C_F = \operatorname{im}_{\mathbb{F}_2} F^{\mathsf{T}} \subseteq \mathbb{F}_2^{325}$. The P-component parity vector of every weight-625 apartment word is nonzero. If such a word is P-heavy, one component costs more than the minimum 25, so if t is the footprint weight,

$$625 \geq 26 + 25(t-1), \qquad t \leq 24.$$

Thus any exotic P-heavy equality word would produce a nonzero footprint-code word of weight at most 24. Since point footprints have weight 25, proving $d(C_F) = 25$ would, together with Pass 5191, classify the complete q=5 weight-625 shell as chamber stars.

The footprint code has additional exact structure. Pass 5202 gives $\dim C_F = 65$, and for q=5 the Gram relation is $FF^{\mathsf{T}} = J$ over $\mathbb{F}_2$. Its hull has dimension 64. Every hull word has weight 0 (mod 4) and every word in the other coset has weight 1 (mod 4). The 156 point rows have weight 25; sums of two point rows have weight 40 for collinear points and 48 otherwise. Hence a hypothetical word below 25 is restricted to

$$\{4, 8, 12, 16, 20, 24\} \quad \text{or} \quad \{1, 5, 9, 13, 17, 21\}.$$

For odd q, the conjecture that dual grids span the complete W-line incidence dual is exactly the binary rank statement

$$\operatorname{rank}_2 F = \frac{q(q^2+1)}{2}.$$

This holds at q=3, 5, 7, 11 and is a theorem at q=5, but no all-odd-q proof is promoted here; even characteristic is genuinely different.

The controller and footprint geometries are representations of the same Borel symmetry. The four U(q) coordinates have C2 positive-root weights $\alpha, \beta, \alpha+\beta, 2\alpha+\beta$, giving the Pass 5192 torus action

$$(a, b, c, d) \mapsto (ra, sb, rsc, r^2sd).$$

Since W-points and hyperbolic polar-pair dual grids are canonical $PSp_4(q)$ sets,

$$P_{\text{pts}}(g)F = FP_{\text{grid}}(g),$$

so the root controller acts by automorphisms of the footprint code and P-component block graph.

For odd q, the latter graph has a classical orthogonal identification. On $\Lambda^2(\mathbb{F}_q^4)/\langle\omega\rangle$, the exceptional action $PSp_4(q) \cong P\Omega_5(q)$ sends a polar hyperbolic-line pair $\{H, H^\perp\}$ to one plus-type nonisotropic projective point. Therefore the P-component graph is

$$\boxed{NO_5^+(q)}.$$

At q=5 this is SRG(325, 144, 68, 60).

Two additional q=5 structures occur. First, there is an explicit set of 13 pairwise disjoint dual grids partitioning all 156 W-points. They form a Hoffman-optimal coclique in $NO_5^+(5)$ and meet every distinguished point-footprint 25-clique exactly once. Second, the dual footprint code is exactly

$$\boxed{C_F^\perp = [325, 260, 8]_2}.$$

The lower bound follows from even point degrees: for a t-block dual word the induced block-graph edge count satisfies $E \geq 3t$, hence $t \geq 7$. The weight-seven equality configuration is excluded by an exact 265-node canonical backtrack, and an explicit weight-eight support exists; its eight grids cover 48 W-points twice and induce K_8 minus a perfect matching.

Evidence boundary. Leader 36 remains open. The primal footprint distance 25 remains open, so the P-heavy equality shell is not yet closed by this packet. The odd-q spanning theorem is reduced to a rank formula but remains unproved in general. The orthogonal-graph and dual-code statements are finite geometry/code theorems, not physical performance claims.

Passes 5214–5221: connected-L atom gluing, radius seven, and the P-atom/L-syndrome presentation

The q=5 point-footprint equality problem can now be solved exactly on its P-heavy-free slice. Fix a W-point p. Its footprint consists of 25 P-components, and a P-heavy-free word of weight 625 chooses one weight-25 minimum P-atom in each component. Restrict the 97,500 fundamental L-chart triangle checks to these 25 atom groups. Exactly 17,250 nontrivial checks are unary and 7,500 are binary; no higher-arity condition occurs. The unary conditions leave precisely six atoms per group, naturally labelled by the six W-lines through p. Every one of the $\binom{25}{2} = 300$ pairs of groups is constrained, and its binary relation is exactly equality of line labels. Hence all 25 groups choose one common line and there are exactly six solutions, the six chamber stars based at p.

The q=3 provenance-refined hard-decision decoder also advances by one exact radius. The projective collineation stabilizer of a fixed apartment has order 16. Connected-set orbit counts through the fixed apartment are

$$1,\ 5,\ 57,\ 1043,\ 25929,\ 734414$$

for weights one through six. Every connected seven-set has a connected six-set parent, so all weight-seven stabilizer orbits occur among one-vertex extensions of these 734,414 representatives. An exact 64,439,500-extension census shows that after maximum-vote and maximum-singleton-source filtering, before tie-degree pruning, the candidate set is always nonempty and contained in the true errors. Component separation then gives a global guaranteed radius seven; the first correction leaves weight at most six, so Pass 5176 yields a global five-sweep bound.

For odd q the L/opposite-line chart graph is connected rather than P-tensor-disconnected. Exact q=3 and q=5 spectra are now frozen by integer annihilators and closed-walk traces. At q=3 the graph is 6-regular on 540 vertices, with rational sectors

$$6^1, 3^{60}, 2^{84}, 1^{81}, (-1)^{120}, (-3)^{116},$$

plus the roots of $x^2 - 2x - 9$ with multiplicity 24 each and $x^2 + x - 18$ with multiplicity 15 each. At q=5 it is 15-regular on 9750 vertices, with rational sectors

$$15^1, 6^{130}, 5^{1235}, 3^{520}, 1^{1899}, 0^{520}, (-2)^{520}, (-3)^{625}, (-4)^{520}, (-5)^{1534},$$

plus quadratic factors $x^2 - 3x - 50$, $x^2 + 2x - 75$, $x^2 + 2x - 30$ of multiplicities 90,65,104 per root, and the three roots of $x^3 - 4x^2 - 12x + 40$ with multiplicity 576 each. Both graphs are triangle-free.

The q=5 root-controller/equality-coordinate bridge is objectwise. On the canonical $U(5)$ chamber carrier, state coordinates (a, b, c, d) project to the 25 P-atoms by

$$(a, b, c, d) \longmapsto (a, c).$$

Each atom fixes (a, c) and contains all 25 (b, d) choices. The 16 distance-four root states $(a, b, 2ab, 2a^2b)$, $a, b \neq 0$, occupy exactly the 4×4 torus $(a, c) \in (\mathbb{F}_5^*)^2$; the remaining nine star atoms form the coordinate cross $a = 0$ or $c = 0$. The 400-apartment torus and 225-apartment cross have different L local-weight profiles but exactly the same fundamental L syndrome of weight 664, which cancels in their chamber-star XOR.

The P-atoms in fact give an all-q presentation. One P component is $C_q = \mathrm{Cut}(K_{q+1}) \otimes \mathrm{Cut}(K_{q+1})$, dimension q^2, and its $(q+1)^2$ minimum atoms span it, leaving $2q+1$ internal atom relations. Over all $q^2(q^2+1)/2$ P components, the P-side theta kernel has dimension

$$\frac{q^4(q^2+1)}{2}.$$

Intersecting with the L-theta kernel leaves the q^4-dimensional apartment code, so the independent L compatibility rank on the P-side space is exactly

$$\boxed{\frac{q^4(q^2-1)}{2}}.$$

At q=5: 11,700 atom coefficients modulo 3,575 internal relations give 8,125 P-side dimensions; 7,500 independent L conditions leave 625 code dimensions.

The characteristic-two shadow of the connected L graph is also nonsemisimple. Direct binary elimination gives q=3 ranks $\operatorname{rank} A = 440$, $\operatorname{rank}(A+I) = 360$ and q=5 ranks $7074, 6891$, with nullities $100, 180$ and $2676, 2859$ respectively. These are modular modules, not parity reductions of the real eigenspaces.

Finally, the exact four-chamber law has been applied to the live q=5 leader-36 wall in the complete scalar quartic family

$$\mathbf{1}_{r \text{ odd}} \geq r - 2\binom{r}{2} + a\binom{r}{3} + b\binom{r}{4} - c\binom{r}{8}, \qquad 0 \leq r \leq 8,$$

with $a, b, c \geq 0$. Its feasible coefficient polytope has five vertices. Using all presently certified aggregate data, including $S_4 \geq 5P_4$, every critical $N_1 = 54, \ldots, 64$ profile is optimized at $b = 0$, reproducing exactly the two cubic bounds already used by Pass 5205. Thus scalar quartic tuning is rigorously redundant: leader 36 requires configuration-resolved fourth-order data, correlated larger-shore cut information, or an independent quotient/residual argument.

Evidence boundary. The q=5 strict sub-625 frontier remains chamber leader at least 36 and leader 36 is open. The primal footprint-code distance 25 remains open, so the complete weight-625 equality shell is not yet globally classified; the fixed point-footprint P-heavy-free slice is classified exactly. The radius-seven theorem concerns the stated deterministic q=3 hard-decision decoder only. The L spectra and modular ranks are exact finite q=3/q=5 statements unless explicitly labelled all-q, and the controller/atom bridge is finite algebraic geometry rather than a physical-performance claim.

Pass5230–5237: the q=5 footprint dual shell exposes a rank-4 scheme. Let F be the 156×325 point–dual-grid incidence matrix from Passes 5201–5203 and let $C_F = \operatorname{im}(F^T)$. The dual remains $C_F^\perp = [325, 260, 8]_2$ (Pass 5213), but the complete minimum shell is now rigidly classified. There are exactly 24375 weight-8 dual words, forming a single orbit under the generated symplectic transvections. Every support covers exactly 48 points twice and induces K_8 minus a perfect matching in the $NO_5^+(5)$ block graph. The shell span has dimension 259.

An explicit odd dual word of weight 9, on coordinates

$$\{15, 20, 38, 44, 139, 164, 197, 278, 311\},$$

therefore supplies the missing parity direction. Consequently C_F has an exact sparse parity-check presentation with 259 independent weight-8 checks and one weight-9 check. Since the dual minimum is 8, this also gives odd-dual minimum 9.

The weight-8 shell refines the old strongly regular relation. For two distinct P components, let R_1 denote block adjacency, R_2 nonadjacency with weight-8 pair-codegree 5, and R_3 nonadjacency with pair-codegree 0. Their valencies are

$$(k_1, k_2, k_3) = (144, 120, 60),$$

and they close to a three-class association scheme. Selected intersection-number rows are

	R_0	R_1	R_2	R_3
R_1R_1	144	68	60	60
R_1R_2	0	50	54	60
R_1R_3	0	25	30	24
R_2R_2	120	45	45	40
R_2R_3	0	25	20	20
R_3R_3	60	10	10	15

with primitive multiplicities $1, 90, 104, 130$ and eigenvalue rows

$$R_1 : (144, 14, -6, -6), \qquad R_2 : (120, -10, -5, 10), \qquad R_3 : (60, -5, 10, -5).$$

Thus the weight-8 Tanner shell sees strictly more geometry than the SRG parameters alone.

The Pass5212 Hoffman 13-coclique is also a systematic quotient: each W-point lies in exactly one of its 13 blocks, the restriction of F to those columns has binary rank 13, and puncturing those columns leaves rank 65. Hence

$$0 \longrightarrow C_{\text{short}} \longrightarrow C_F \longrightarrow \mathbb{F}_2^{13} \longrightarrow 0, \qquad \dim C_{\text{short}} = 52.$$

Firewall. These results do not yet prove $d(C_F) = 25$. A symmetry-broken sparse-check MILP for a nonzero word of weight at most 24 did not finish with either feasibility or infeasibility in the bounded diagnostic run. Therefore the q=5 P-heavy equality obstruction remains open, as does chamber leader 36 and the full q=5 distance-625 theorem. The odd-q $NO_5^+(q)$ rank formula also remains a target rather than a promoted theorem.

73.10 Footprint distance closure and the residual zero-P strict sector

The minimum-shell orbit of the $q = 5$ footprint dual code now closes the previously open primal distance problem. Let $\mathcal{B}_8$ be the complete orbit of 24,375 dual words of weight eight. Every footprint coordinate occurs in 600 members of $\mathcal{B}_8$, while a pair of coordinates occurs in 25, 5, or 0 members according to the three nontrivial relations R_1, R_2, R_3 of the Pass5232 rank-four scheme. If S is the support of a primal word, $w = |S|$, and $t_B = |S \cap B|$, then t_B is even. Therefore

$$\sum_{B \in \mathcal{B}_8} \binom{t_B}{2} \geq \frac{1}{2} \sum_B t_B = 300w,$$

whereas

$$\sum_{B \in \mathcal{B}_8} \binom{t_B}{2} = 25e_1 + 5e_2 \leq 25\binom{w}{2}.$$

Hence $w \geq 25$. Since every point footprint has weight 25,

$$\boxed{C_F(q = 5) = [325, 65, 25]_2}.$$

Equality forces $e_2 = e_3 = 0$ and all dual-check intersections to have size zero or two. An exact maximum-clique census gives precisely 156 cliques of size 25, exactly the 156 point footprints. Thus the minimum shell is also classified.

This settles the formerly open equality branch of the apartment code. Pass5207 shows that any P-heavy exotic word of apartment weight 625 would induce a nonzero footprint word of weight at

most 24, now impossible. Pass5191 already classifies the P-heavy-free equality case. Consequently every $q = 5$ apartment-code word of weight 625 is one of the 936 chamber stars. This is an equality-shell theorem, not yet the strict minimum-distance theorem.

The same distance theorem sharply reduces the strict side. For any apartment word of weight below 625, its P-component parity vector s lies in C_F. If $s \neq 0$, then $\mathrm{wt}(s) \geq 25$, while every parity-odd P component is nonzero in the local $[225, 25, 25]_2$ tensor code and therefore contributes at least 25 apartments. This would already cost 625. Hence every strict counterexample has

$$\boxed{s = 0}.$$

Moreover the even subcode of $\mathrm{Cut}(K_6) \otimes \mathrm{Cut}(K_6)$ has minimum distance 40. Indeed $d_1(\mathrm{Cut}(K_6)) = 5$ and $d_2 = 9$: a rank-one tensor has smallest even product $5 \cdot 8 = 40$, while tensor rank at least two has at least nine nonzero rows of weight at least five. Therefore any word below 625 can activate at most $\lfloor 624/40 \rfloor = 15$ of the 325 P components. The remaining strict problem is thus a zero-P-parity, block-sparse connected-L obstruction problem; leader 36 is not claimed closed here.

A useful general principle emerged. If an automorphism-invariant family of dual checks has coordinate replication r and maximum distinct-pair codegree λ, then even primal/check intersections imply

$$w \geq 1 + \frac{r}{\lambda}.$$

The exact anchors are

$$(q, r, \lambda, d) = (3, 24, 3, 9), \quad (5, 600, 25, 25), \quad (7, 18816, 392, 49).$$

For $q = 7$ an exact finite computation gives $\mathrm{rank}_2 F = 175$, excludes dual weights $9, 10, 11$, and exhibits a weight-12 dual word whose symplectic orbit has 1,920,800 checks. Its maximum pair codegree is 392, so the same moment argument proves

$$\boxed{C_F(q = 7) = [1225, 175, 49]_2}.$$

Thus the footprint distance law $d = q^2$ is now certified by the same mechanism at $q = 3, 5, 7$. An all-odd-q theorem would follow from an appropriate dual-check orbit with $r/\lambda = q^2 - 1$; that family construction remains open.

Finally, the P-component action itself refines with q: exact generated $\mathrm{PSp}_4(q)$ pair orbitals have ranks $3, 4, 5$ for $q = 3, 5, 7$ respectively. At $q = 7$ the nonadjacent valencies are $336, 336, 168$ in addition to adjacency valency 384. These are finite anchors only; no all-odd-q orbital formula is promoted without a separate proof.

Passes 5254–5261: radius-eight echo, modular L-Jordan form, and the zero-footprint residual

The authoritative Passes 5238–5245 close the $q = 5$ footprint distance and the complete apartment-code equality shell:

$$C_F = [325, 65, 25]_2, \qquad \{c : \mathrm{wt}(c) = 625\} = \{936 \text{ chamber stars}\}.$$

The results below were developed concurrently under colliding draft filenames and are authoritatively renumbered 5254–5261; the original filenames are retained only as provenance.

The $q = 3$ decoder at weight eight. The provenance-refined hard-decision decoder has a complete structured first-correction obstruction family at weight eight. Every apartment center belongs to four local charts, and in each incident chart there are exactly two two-error masks on the other coordinates whose unique local leader is the center. Independent choice in the four charts gives $2^4 = 16$ configurations per center and therefore

$$1620 \cdot 16 = 25920$$

distinct weight-eight errors. For every one, maximum vote followed by maximum singleton provenance selects the false center alone. Nevertheless the full deterministic decoder self-heals in exactly three sweeps,

$$8 \longrightarrow 9 \longrightarrow 1 \longrightarrow 0.$$

Thus the true-only/monotone first-correction guarantee is sharp at radius seven. These configurations do not disprove eventual radius eight; an orbit-complete census of all weight-eight errors remains open.

Exact modular Jordan structure of the connected L chart graph. The large binary radicals found previously are not semisimple reductions of the characteristic-zero spectrum. At $q = 3$,

$$\chi_A(x) \bmod 2 = x^{100}(x+1)^{440},$$

with zero-primary blocks J_1^{100} and one-primary blocks

$$J_1^{70} \oplus J_2^{22} \oplus J_3^{26} \oplus J_4^{62}.$$

At $q = 5$,

$$\chi_A(x) \bmod 2 = x^{3716}(x+1)^{6034},$$

with

$$\ker(x\text{-primary}) \sim J_1^{2156} \oplus J_3^{520},$$

and

$$(x+1)\text{-primary} \sim J_1^{804} \oplus J_2^{1471} \oplus J_3^{48} \oplus J_4^{536}.$$

These are exact finite GF(2) Jordan decompositions at $q = 3, 5$.

Two-root quotient and the outer root shell. In canonical unipotent coordinates (a, b, c, d) the commuting subgroup generated by the second and fourth positive-root directions has order q^2 and its right cosets are exactly the fixed-(a, c) fibers. Hence the quotient is coordinatized by $\mathbb{F}_q^2$. In every characteristic greater than three, the distance-four root-Cayley shell projects exactly onto

$$(\mathbb{F}_q^*)^2,$$

and every nonzero (a, c) fiber contains precisely $(q-4)^2$ distance-four states. Therefore

$$|S_4| = (q-1)^2(q-4)^2.$$

At $q = 5$ these fibers are objectwise the 25 P atoms of a chamber star, so the shell occupies the 4×4 nonzero atom torus and misses the nine-atom coordinate cross.

The complete minimum dual shell as a real frame. Let H_8 be the 24375×325 incidence matrix of all weight-eight dual footprint words. The rank-four pair scheme gives

$$H_8^T H_8 = 600I + 25R_1 + 5R_2,$$

with real spectrum

$$4800^1 \oplus 900^{90} \oplus 425^{104} \oplus 500^{130}.$$

Thus H_8 has full real column rank. Over $\mathbb{F}_2$ its rank is 259, and the exact binary kernel is

$$\boxed{\ker_{\mathbb{F}_2} H_8 = C_F \oplus \langle \mathbf{1} \rangle.}$$

The complete minimum dual shell therefore misses exactly one binary bit, global parity; one independent odd weight-nine dual check removes precisely that mode.

Hoffman-13 shortened residual. The Hoffman 13-cover gives 13 systematic footprint coordinates. Its shortening kernel has dimension 52, and because the cover carriers partition all 156 W-points, vanishing on those coordinates forces even point-input parity. Hence the shortening lies in the doubly-even hull and has

$$[312, 52, d_{\mathrm{sh}}]_2, \qquad 28 \le d_{\mathrm{sh}} \le 40,$$

with $d_{\mathrm{sh}} \in \{28, 32, 36, 40\}$. Sums of two collinear point footprints in one cover carrier furnish weight-40 shortened words. The exact shortened minimum remains open.

Strict $q = 5$ sector: a 560-dimensional zero-footprint block code. A local P component is

$$C_0 = \mathrm{Cut}(K_6) \otimes \mathrm{Cut}(K_6) = [225, 25, 25]_2.$$

Exhaustion of all 2^{25} local states gives minimum nonzero even weight 40, with exactly 180 such words. Every weight-40 word is a simple tensor of factor weights 5×8 or 8×5:

$$180 = 6 \cdot 15 \cdot 2.$$

Since every strict q5 apartment word has zero P parity, each active P block is even and costs at least 40 apartments. Hence any word below 625 has at most

$$\left\lfloor \frac{624}{40} \right\rfloor = 15$$

active P components.

This reduction fits into an exact parity/syndrome sequence. The full P-side space has dimension 8125; its even-block subspace has dimension 7800. The connected-L map has ranks 7500 and 7240 on these two spaces respectively. The apartment code has dimension 625 and its footprint image has dimension 65, so the zero-footprint residual has dimension

$$\boxed{560}.$$

Moreover

$$0 \longrightarrow C_F \longrightarrow \mathbb{F}_2^{325} \longrightarrow \mathrm{Im}(L|V_P)/\,\mathrm{Im}(L|E) \longrightarrow 0,$$

where the final quotient has dimension 260 and dual $C_F^{\perp}$. Thus the complete strict q5 problem can now be replaced by one finite block-code target:

$$\boxed{d_{\mathrm{block}}(K_0) \ge 16.}$$

Such a theorem would eliminate every strict sub-625 word. It is not proved here, so the full q5 distance theorem remains open on the strict side.

Minimum-shell two-distance frame. The 156 exact weight-25 footprint minimum words are the $\mathrm{W}(3,5)$ point footprints. Their incidence Gram is

$$FF^T = 24I + 4A_W + J,$$

with spectrum $300^1 \oplus 40^{90} \oplus 0^{65}$. Every coordinate lies in 12 minimum words, hence the centroid is $(1/13)\mathbf{1}_{325}$. After centering the Gram spectrum is $40^{90} \oplus 0^{66}$. Consequently the 156 centered vectors form an equal-norm tight frame for $\mathbb{R}^{90}$ with frame bound 40. After unit normalization the two off-diagonal inner products are

$$\boxed{\frac{2}{15} \quad \text{(collinear W-points)}, \qquad -\frac{1}{25} \quad \text{(noncollinear W-points)}.}$$

Thus the exact binary minimum shell recovers $\mathrm{W}(3,5)$ collinearity as a real two-distance tight frame.

Evidence firewall. The q5 weight-625 equality shell is closed, but $d = 625$ is not yet a theorem because the 560-dimensional zero-footprint strict residual may in principle contain a word below 625. The block-distance-16 statement is a sufficient target, not a proved fact. The q3 decoder has guaranteed radius seven; the 25920 weight-eight echo configurations self-heal, but global eventual radius eight remains open. The modular L-Jordan statements are exact only for q3 and q5, and the geometric P-atom interpretation of the two-root quotient is objectwise certified at q5.

73.11 The $q = 5$ apartment code has distance 625

Pass 5262 closes the remaining strict $q = 5$ sector. Let K_0 be the 560-dimensional zero-P-parity residual inside the product of the 325 local even P-component spaces. On a minimum weight-eight footprint-dual support D, the projection of K_0 has rank 134, and deleting any one block of D leaves rank 134. Hence a nonzero K_0 word cannot meet D in exactly one active P block. Since the complete 24,375-word weight-eight dual shell is one symplectic orbit, this no-singleton property holds for every shell check. If S is a nonzero P-block support of size w, the shell replication 600 and maximum pair codegree 25 give

$$300w \le \sum_D \binom{|S \cap D|}{2} \le 25\binom{w}{2},$$

so $w \ge 25$. Every hypothetical apartment word of weight below 625 had already been reduced to at most 15 active even P blocks, a contradiction. Therefore

$$\boxed{C_A(q=5) = [73125, 625, 625]_2}.$$

Together with the Pass 5238 equality-shell theorem, the 936 chamber stars are exactly the minimum words. This is a finite $q = 5$ theorem, not an all-q q^4 distance theorem.

Residual structure. Pass 5265 records the complete block-polymatroid rank profile on a weight-eight dual support. Pass 5268 identifies every local even minimum word of $\mathrm{Cut}(K_6) \otimes \mathrm{Cut}(K_6)$ as a pair of adjacent edges in its $K_{6,6}$ atom graph. Pass 5269 proves that every block-minimum support of K_0 is one of the 156 W-point footprints. Pass 5266 also rules out the naive channelwise connected-L Jordan lift $A_L \otimes I_{10}$: the correct modular-Jordan object must include nontrivial transport of the ten local triangle channels.

Independent decoder advance. Pass 5263 proves, by finite MILP and exhaustive local completion certificates, that the deterministic $q = 3$ provenance decoder has global eventual guaranteed radius eight. The monotone true-only radius remains seven; the only false-first- correction weight-eight family consists of the 25,920 poison-pair echoes, all of which self-heal by $8 \to 9 \to 1 \to 0$.

73.12 Post-distance shell geometry and the odd-q footprint quotient

Pass 5284 completes the minimum-word shell of the $q = 5$ zero-P residual K_0. On any one of the 156 W-point block-minimum supports, the $25 \times 24 = 600$ local even variables have connected-L syndrome rank 596, leaving a four-dimensional restricted kernel. Its 15 nonzero words are exactly the $\binom{6}{2} = 15$ differences of the six chamber stars based at that point. Consequently the complete K_0 block-minimum shell has

$$156 \cdot 15 = 2340$$

words, all of apartment weight $25 \cdot 40 = 1000$.

The six chamber-star coefficients at a fixed point give a canonical fiber

$$U_p = E_6/\langle 111111 \rangle \cong \mathbb{F}_2^4,$$

where E_6 is the even-weight subspace of $\mathbb{F}_2^6$. Thus the 15 nonzero minimum words over a point are naturally the 15 points of $PG(3, 2)$, equivalently the unordered pairs of the six W-lines through the point (Pass 5289). Under the Pass 5217 controller chart, the common 25 P blocks are indexed by $(a, c) \in \mathbb{F}_5^2$, and this four-dimensional fiber embeds diagonally as a constant section over the full 5×5 sheet (Pass 5290). Every local fiber code is a five-fold replicated binary simplex $[75, 4, 40]_2$ plus 150 zero coordinates; globally the effective code is the 125-fold simplex $[1875, 4, 1000]_2$ plus 3750 zero coordinates in the 5625-coordinate footprint region (Pass 5291). These are finite code-coordinate statements, not physical dynamics claims.

Hoffman shortening. For the fixed Hoffman 13-cover, the 312 non-cover coordinates split by their (R_1, R_2, R_3) relation counts to the cover as

$$(6, 5, 2)^{144}, \quad (6, 6, 1)^{96}, \quad (6, 3, 4)^{48}, \quad (6, 1, 6)^{24}.$$

The complete weight-eight dual shell meets the cover in $0, 1, 2$ coordinates with counts $16815, 7320, 240$. These exact four types sharpen the shortening problem, but the minimum of the $[312, 52]$ shortened code remains one of $28, 32, 36, 40$; no $d = 40$ theorem is promoted.

$q = 9$ anchor and all-odd rank reduction. Over $GF(9) = \mathbb{F}_3[t]/(t^2+1)$ the point/P-component incidence matrix has 820 rows and 3321 columns, point-row weight 81, and exact binary rank

$$\operatorname{rank}_2 F = 369 = \frac{9(9^2 + 1)}{2}.$$

An explicit weight-16 dual dependence has carrier degree profile $2^{160}0^{660}$; its selected block graph is 10-regular on 16 vertices, and its complement has two 8-vertex components, each $K_8 \setminus C_8$. This does not yet prove the $q = 9$ primal distance 81.

For every odd q, every totally isotropic W-line L meets a P-carrier $H \cup H^\perp$ in 0 or 2 points, because $L = L^\perp$ implies $\dim(L \cap H) = \dim(L \cap H^\perp)$. Hence the binary W-line code lies in $\ker F^T$. Using the odd-q W-line-code dimension gives the universal upper bound

$$\operatorname{rank}_2 F \le g = \frac{q(q^2 + 1)}{2}.$$

The exact anchors $q = 3, 5, 7, 9$ all saturate this bound. The remaining all-odd rank theorem is therefore precisely injectivity of the induced footprint map on the g-dimensional quotient of the point module by the W-line code.

Pass5292–5299: q=9 footprint distance and the post-distance odd-q structure. The $q = 9$ point/P-component footprint code is now exact:

$$C_F(9) = [3321, 369, 81]_2.$$

An explicit dual word of weight 16 has setwise stabilizer 128 in $PSp_4(9)$, hence an orbit of 13,450,050 dual checks. The orbit has coordinate replication $r = 64{,}800$ and maximum pair codegree $\lambda = 810$, so the even-intersection moment inequality gives

$$\mathrm{wt}(x) \geq 1 + \frac{r}{\lambda} = 81,$$

with equality attained by the point footprints. Thus the footprint-distance law $d = q^2$ is exact at $q = 3, 5, 7, 9$.

For odd q, write $g = q(q^2+1)/2$ and let D_q be the apartment-code subspace generated by differences of two chamber stars based at the same W-point. Using the full Levi cut-space dependency theorem and the odd-q incidence nullity $\dim\ker N = g$, the direct sum of local point fibers has dimension $q^4 - 1$, its relation module is canonically $\ker N/\langle \mathbf{1} \rangle$ of dimension $g - 1$, and hence

$$\dim D_q = q^4 - g.$$

Since D_q lies in the zero-P-parity residual K_0 and $\dim K_0 = q^4 - \mathrm{rank}_2 F$, one obtains the exact equivalence

$$\mathrm{rank}_2 F = g \quad \Longleftrightarrow \quad K_0 = D_q.$$

The rank equality is now computationally exact at $q = 3, 5, 7, 9, 11$, with the new $q = 11$ anchor $\mathrm{rank}_2 F = 671$. The all-odd generation statement $K_0 = D_q$ remains open.

For the Hoffman-13 shortening at $q = 5$, the cover stabilizer has order 576 and has six orbits on triples of cells, with span ranks $25, 28, 28, 30, 30, 30$. Exact Gray-code enumeration of one representative of every orbit gives minimum 40 in all six triple spans. Therefore any shortened word of weight 28, 32, or 36 must involve at least four cover cells. The exact shortened distance is not yet promoted beyond $d \in \{28, 32, 36, 40\}$.

The low dual supports at $q = 5, 7, 9$ share a finite two-factor skeleton

$$K_{q-1,q-1} + F_A + F_B,$$

with $(F_A, F_B) = (C_4, C_4)$, $(C_6, C_3 \sqcup C_3)$, and (C_8, C_8) respectively. At $q = 9$ the support graph is the Cayley graph on $\mathbb{Z}_8 \times \mathbb{Z}_2$ obtained from all eight cross-layer generators together with $(\pm 1, 0)$; its graph automorphism group has order 512, while only a 128-element subgroup extends to the ambient symplectic geometry.

Finally, the $q = 5$ block-minimum residual shell has exactly 2340 words of apartment weight 1000 and GF(2) span rank $560 = \dim K_0$. Over each W-point the 15 words form the nonzero vectors of $PG(3, 2)$, and the point stabilizer acts as $PSL_2(5) \cong A_5$. Its action on the 35 projective lines has orbit sizes $5, 10, 10, 10$; the size-5 orbit is a spread partitioning all 15 fiber points. These are finite code-geometry statements and are not interpreted as physical transport.

Evidence boundary. The $q = 5$ apartment code remains the exact $[73125, 625, 625]_2$ code with 936 chamber-star minimum words. Pass5292 closes only the $q = 9$ footprint distance. The all-odd footprint-rank equality, an all-odd dual-shell construction, and the exact Hoffman-shortened distance remain open at the boundaries stated above.

73.13 Passes 5300–5307: the exact 576 bridge and the post-$q = 9$ frontier

The numerical coincidence $576 = 576$ between the Hoffman-cover stabilizer and the number of order-four Latin squares admits a precise refinement. Let H be the setwise stabilizer of the thirteen-cell Hoffman cover in $\mathrm{PSp}_4(5)$. Then

$$|H| = 576, \qquad Z(H) \cong C_2,$$

and the computation identifies

$$H \cong 2^{1+4}_{+} : (S_3 \times C_3).$$

The full autoparatopy group of the Klein V_4 Latin square also has order 576, but it is a different group,

$$\mathrm{AutPar}(L_{V_4}) \cong 2^4 : (S_3 \times S_3).$$

Their centers, derived subgroup orders, and element-order distributions differ. The genuine bridge appears one level down: if L^+ denotes the index-two subgroup of even parastrophes, then an explicit $\mathrm{GL}_4(2)$ change of basis gives

$$\boxed{H/Z(H) \cong L^+ \cong 2^4 : (S_3 \times C_3).}$$

Thus the Hoffman order-576 group is a central double lift of the same affine $\mathbb{F}_2^4$ symmetry carried by the orientation-even half of the Klein Latin chart; equality of the integers alone is not used as evidence.

This exposes an exact connection with the earlier toroidal-knight construction. The sixteen cells of the Klein 4×4 chart are

$$\mathbb{F}_2^2 \times \mathbb{F}_2^2 \cong \mathbb{F}_2^4,$$

the same sixteen-point substrate on which the toroidal knight graph was proved to be Q_4. The Latin affine-plane completion partitions the fifteen nonzero translation directions into five $PG(3, 2)$ lines: row, column, symbol, and two additional orthogonal-mate directions. The Hoffman/Latin-even linear quotient has direction orbits $9 + 6$, exactly three of these spread lines plus two spread lines. In contrast, Q_4 uses only four basis directions, two from the row line and two from the column line. The order-288 affine quotient does not preserve that four-direction set, so the shared theorem is the common $\mathbb{F}_2^4$ substrate, not an equality of edge graphs.

The order-four Latin census itself is

$$576 = 144 + 432,$$

with a 144-element Klein-V_4 isotopy class and a 432-element cyclic-C_4 class. The complete three-MOLS(4) geometry of the Klein chart is a five-line spread of $PG(3, 2)$. There are exactly 56 such spreads; $\mathrm{GL}_4(2)$ is transitive on them and a spread stabilizer has order 360. Hence the A_5-invariant five-line spread independently found in every $q = 5$ K_0 fiber is $\mathrm{GL}_4(2)$-conjugate to a complete-MOLS(4) spread. A canonical objectwise identification of the particular labels remains open.

The Hoffman shortening frontier also contracts. The 715 four-subsets of the thirteen cover cells form only ten stabilizer orbits, with orbit-size/rank pairs

$$(3,33),(12,33),(16,35),(144,35),(96,38),(144,38),(36,39),(48,40),(72,40),(144,40).$$

Pass 5294 already proves every span involving at most three cells has minimum forty. Therefore the first unresolved layer has ten four-cell representatives. Bounded exact searches find weight-forty words but do not certify the absence of weights $28, 32, 36$; accordingly the shortened distance remains

$$d_{\mathrm{sh}} \in \{28, 32, 36, 40\}.$$

On the all-odd footprint side, the exact rank formula gains a new finite anchor: for $q = 13$ the point/P-component incidence matrix has 2380 rows, 14365 columns, point-footprint weight 169, and

$$\operatorname{rank}_2 F = 1105 = \frac{13(13^2+1)}{2}.$$

Together with $q = 3, 5, 7, 9, 11$, this gives six exact anchors. The general theorem remains equivalent to the same-point generation statement $K_0 = D_q$.

At $q = 11$, every P-carrier has size 24 and any two distinct carriers intersect in zero or two W-points. Hence a hypothetical dual word supported on twenty carriers has, writing d_p for point multiplicities and e for selected carrier-graph edges,

$$2e = \sum_p \binom{d_p}{2}, \qquad \sum_p d_p = 480, \qquad d_p \equiv 0 \pmod 2,$$

so

$$\boxed{e \geq 120}.$$

Equality holds precisely when 240 W-points are covered twice, in which case the selected graph is 12-regular. The conjectural $K_{10,10}$ plus two-factor support saturates this lower bound. Symmetry-broken bounded MILPs produced no incumbent but no infeasibility certificate, so neither a weight-twenty dual shell nor $d(C_F) = 121$ is promoted here.

Finally, the complete 2340-word $q = 5$ minimum K_0 shell has a finer symmetry than its six Hamming distances reveal. The transitive $\mathrm{PSp}_4(5)$ action has point stabilizer order 2000 and orbital rank

$$\boxed{21},$$

with subdegree histogram $1^3, 4^3, 50^9, 125^3, 500^3$. Thus the Hamming-distance partition is a fusion of a rank-21 coherent configuration. In a separate negative theorem, the two previously noted 64-dimensional modules are not isomorphic: a symplectic transvection fixes dimension 4 on $\ker_2 N/\langle \mathbf{1} \rangle$ but dimension 24 on the footprint hull. Hence there is no $\mathrm{PSp}_4(5)$-equivariant invertible 64×64 intertwiner between them.

Evidence boundary. The $q = 5$ apartment distance 625 and the $q = 9$ footprint distance 81 remain closed theorems. Passes 5300–5307 do not prove the general odd-q generation statement $K_0 = D_q$, do not prove a $q = 11$ weight-twenty dual shell or footprint distance 121, and do not promote the Hoffman-shortened distance to 40. The Latin/Hoffman/toroidal statements are finite group and affine-geometry identifications; no physical dynamics are inferred from them.

73.14 The Hoffman 576 stabilizer, D_4 triality, and the tomotope quotient

The order-576 setwise stabilizer H of the 13-cell Hoffman cover has a canonical characteristic subgroup

$$N = \langle h \in H : \ |h| \text{ is a power of } 2 \rangle, \qquad |N| = 192.$$

Machine reconstruction gives

$$N \cong 2^3{:}S_4 \cong W(D_4), \qquad Z(N) \cong C_2, \qquad H/N \cong C_3.$$

Moreover N contains exactly three normal elementary-abelian 2^3 subgroups, and an element representing the quotient C_3 cyclically permutes these three subgroups. Thus the factor $576/192 = 3$ is an explicit D_4 triality action, not merely a numerical factorization.

The action of N on the 13 Hoffman cover cells has orbit structure

$$1 + 12,$$

and its kernel is exactly $Z(N)$. On the 12 moving cells the induced order-96 permutation group is, after the explicit relabeling

$$(0, 1, \ldots, 11) \mapsto (0, 3, 9, 5, 6, 10, 1, 4, 11, 2, 8, 7),$$

identical to the group generated by the four published tomotope permutations. Consequently

$$\boxed{W(D_4)/Z(W(D_4)) \cong \Gamma(T)}$$

not only abstractly, but as the displayed degree-12 permutation action. Here

$$|\Gamma(T)| = 96, \qquad \Gamma(T) \cong 2^4{:}S_3.$$

The thirteenth fixed Hoffman cell is not identified with a tomotope face by this argument.

The tesseract order-192 near miss. The full signed-permutation symmetry group of the 4-cube has order 384 and contains two natural index-two subgroups of order 192. The determinant-+1 subgroup R is the orientation-preserving tesseract group, while the even-sign subgroup is $W(D_4)$. They are not isomorphic: their element-order censuses are

$$R: \quad 1^1\, 2^{43}\, 3^{32}\, 4^{36}\, 6^{32}\, 8^{48},$$

$$W(D_4): \quad 1^1\, 2^{43}\, 3^{32}\, 4^{84}\, 6^{32}.$$

In particular, R has 48 elements of order 8 and $W(D_4)$ has none. Nevertheless both centers have order two and both central quotients are isomorphic to

$$2^4{:}S_3 \cong \Gamma(T).$$

Thus the tomotope is a common order-96 central quotient of two distinct order-192 double covers. The Hoffman stabilizer selects the $W(D_4)$ cover, not the tesseract rotation cover.

Latin and toroidal-Q_4 refinement. For the fixed 4×4 toroidal-knight graph used in this project, which is isomorphic to Q_4, enumerate all 576 Latin squares of order four and count the knight edges whose endpoints carry the same symbol. The exact census is

$$\boxed{576 = 96 + 192 + 288},$$

where the three classes have respectively 0, 8, and 16 same-symbol knight edges. Under the common board symmetry preserving both the row/column grid and this fixed Q_4 edge set, together with independent symbol relabeling, the 576 squares split further into orbit sizes

$$48,\ 48,\ 96,\ 192,\ 192.$$

This is an exact object-level statistic on the shared 16-cell substrate. The coincidence of the class sizes $96, 192, 288$ with the tomotope, D_4/tesseract, and Hoffman-central-quotient scales is recorded as a structural target, not as a group-isomorphism theorem.

Finally, the Pass 5300 affine-module isomorphism

$$H/Z(H) \cong L_+$$

with the even Klein-Latin parastrophe group L_+ sends the distinguished normal index-three subgroup $W(D_4)/Z$ to the Klein autotopy subgroup of order 96. The corresponding quotient C_3 is therefore D_4 triality on the Hoffman side and cyclic row/column/symbol parastrophe on the Latin side. This is an affine-module statement: the natural degree-12 Hoffman and Latin label actions have nonisomorphic point stabilizers and are not permutation-equivalent.

73.15 Affine Latin colorings, D_4 triality, and the tomotope square-face action

Fix the explicit toroidal-knight–to–Q_4 labeling used by the router certificate, and encode the four Latin symbols by $\mathbb{F}_2^2$. Pulling an order-four Latin square back to $\mathbb{F}_2^4$, define the four first differences

$$\Delta_i L(x) = L(x + e_i) + L(x) \in \mathbb{F}_2^2.$$

An exhaustive census of all 576 labeled Latin squares gives a sharp affine criterion. The 144 Klein-V_4 squares are exactly those for which all four $\Delta_i L$ are constant, equivalently the symbol map $L : \mathbb{F}_2^4 \to \mathbb{F}_2^2$ is affine. None of the 432 cyclic-C_4 squares is affine: 192 have exactly one constant derivative (48 for each of the four Q_4 directions) and 240 have none. This refines the fixed knight-edge census of Pass5311; it is a coloring/code statement, not a symmetry group identification.

For the Hoffman 13-cell cover, let H be the order-576 stabilizer and let $N \cong W(D_4)$ be the canonical order-192 normal subgroup of Pass5308, so $H/N \cong C_3$. The ten H-orbits on four-cell subsets from Pass5302 refine to exactly 22 N-orbits. Four H-orbits remain transitive under N and six split into triples of equal N-orbits. Thus the outer C_3 acts literally as a triality fusion on the first open four-cell shortening layer. This orbit refinement does not determine the shortened minimum distance.

Under the Pass5300 affine isomorphism

$$H/Z(H) \cong L_+,$$

where L_+ is the order-288 even-parastrophe group of the Klein Latin square, the characteristic order-96 subgroup corresponding to $N/Z(N)$ fixes the row, column, and symbol lines of the five-line $PG(3,2)$ spread individually and swaps the two orthogonal-mate lines. The quotient C_3 is represented by cyclic parastrophe,

$$\text{row} \longmapsto \text{column} \longmapsto \text{symbol} \longmapsto \text{row},$$

while fixing both mate lines. This is the Latin-square realization of the outer D_4 triality factor; it is distinct from the inner S_3 quotient of the tomotope group.

There is also a natural tesseract realization of the tomotope action. The *tesseract* has 24 square faces, hence 12 antipodal square-face pairs. The even-sign signed-permutation group $W(D_4)$ acts on those 12 objects, and its central antipode is exactly the kernel. The induced order-96 action is permutation-conjugate to the published Monson–Pellicer–Williams tomotope action; an explicit conjugating relabeling is

$$(0, 1, 4, 5, 8, 9, 11, 10, 7, 6, 3, 2).$$

Consequently

$$W(D_4)/\langle -I\rangle \curvearrowright \{\text{12 antipodal square-face pairs}\} \cong \Gamma(\mathcal{T})$$

as degree-12 permutation representations.

The three small non-diagonal orbitals of this action are perfect matchings. Their union is $3K_4$. The three K_4 components are exactly the three complementary $2+2$ partitions of the four tesseract coordinate axes,

$$01 \mid 23, \qquad 02 \mid 13, \qquad 03 \mid 12.$$

The kernel of the induced action on these three components is elementary abelian of order 16, while the component action is S_3. Hence the natural square-face action realizes the semidirect product directly:

$$\Gamma(\mathcal{T}) \cong (C_2)^4 : S_3.$$

Finally, the orientation-preserving tesseract group R and $W(D_4)$ remain distinct order-192 double covers. On the same 12 antipodal square-face pairs, $W(D_4)/Z$ has orbital rank 5 (three separate perfect-matching relations), whereas R/Z has orbital rank 4: it preserves one matching and fuses the other two into a degree-two relation. Both share the same uncolored $3K_4$ skeleton, but the natural degree-12 representations are not permutation-conjugate. No physical identification is inferred from these finite symmetry correspondences.

73.16 The $q = 5$ K_0 minimum shell: a noncommutative rank-21 orbital algebra

The complete 2340-word minimum shell of the zero-P residual carries a transitive $PSp_4(5)$ action of orbital rank 21. Computing the full orbital intersection tensor shows that this object is not a commutative association scheme: eleven orbitals are symmetric and the remaining ten form five transpose pairs. Its complex adjacency algebra has

$$\dim Z = 7, \qquad \dim[\mathcal{A}, \mathcal{A}] = 14,$$

and Wedderburn decomposition

$$\boxed{\mathcal{A}_{\mathbb{C}} \cong \mathbb{C}^4 \oplus M_2(\mathbb{C})^2 \oplus M_3(\mathbb{C}).}$$

The resulting permutation-module decomposition is

$$\boxed{2340 = 1 + 104 + 65_a + 520 + 3 \cdot 90 + 2 \cdot 65_b + 2 \cdot 625.}$$

Here the subscripts on the two equal-dimensional 65-constituents are labels for nonisomorphic central blocks; equality of dimensions is not an identification.

The shell projects 15-to-1 onto the 156 points of $W(3, 5)$. For the generic central element used in the orbital calculation, the induced operator on the base-point space is exactly

$$Q = 476I - 87A_W + 77J,$$

with spectrum

$$9878^{1} \oplus 128^{90} \oplus 998^{65}.$$

Thus the multiplicity-one block 65_a is the characteristic-zero $-(q+1) = -6$ point constituent. This statement is deliberately separated from the binary footprint code: the point–carrier incidence matrix has characteristic-zero rank 91 but binary rank 65, so a dimension match does not supply a characteristic-2 intertwiner.

73.17 Characteristic-rank complement and the binary kernel target

For every odd q, the real footprint Gram law

$$FF^{\mathsf{T}} = (q^2-1)I + (q-1)A_W + J$$

gives

$$\operatorname{rank}_{\mathbb{Q}} F = 1 + f, \qquad \operatorname{null}_{\mathbb{Q}} F = g,$$

where

$$f = \frac{q(q+1)^2}{2}, \qquad g = \frac{q(q^2+1)}{2}, \qquad v = 1 + f + g.$$

The binary rank theorem already gives $\operatorname{rank}_2 F \le g$, and equality is equivalent to $K_0 = D_q$. Hence the all-odd target can be written as the characteristic-complement swap

$$\boxed{\operatorname{rank}_2 F = \operatorname{null}_{\mathbb{Q}} F = g, \qquad \operatorname{null}_2 F = \operatorname{rank}_{\mathbb{Q}} F = 1 + f.}$$

It is verified at $q = 3, 5, 7, 9, 11, 13$, but remains open for arbitrary odd q. At those six anchors the already-proved inclusion of the binary W-line code in the footprint kernel is therefore equality:

$$\boxed{\ker_2(F^{\mathsf{T}}) = C_W.}$$

73.18 Local A_5/V_4 fiber and exact induced branching

Fixing a base point, the six incident W-lines carry the $A_5 \cong PSL_2(5)$ action of the point stabilizer. A minimum-shell fiber is the set of unordered pairs of those six lines, hence the homogeneous 15-point space A_5/V_4. Its orbital algebra is itself noncommutative, of rank six, with

$$\mathbb{C}^2 \oplus M_2(\mathbb{C}), \qquad \mathbb{C}[A_5/V_4] \cong 1 \oplus 4 \oplus 2 \cdot 5.$$

In particular the local augmentation module is $14 = 4 + 5 + 5$; no G_2 adjoint interpretation is inferred from the integer 14.

The exact stabilizer tower is

$$H_{\text{shell}}(2000) < P_{\text{point}}(30000) < PSp_4(5)(4680000),$$

with indices 15 and 156. Thus

$$G/H \longrightarrow G/P$$

is a homogeneous bundle with fiber $P/H \cong A_5/V_4$. Induction transitivity, together with the global Wedderburn decomposition, forces

$$\boxed{\operatorname{Ind}_P^G(1) = 1 + 90 + 65_a,}$$

$$\boxed{\mathrm{Ind}_P^G(4) = 104 + 520,}$$

$$\boxed{\mathrm{Ind}_P^G(5) = 90 + 65_b + 625.}$$

Consequently the $2184 = 156 \cdot 14$ vertical fiber module is

$$104 + 520 + 2 \cdot 90 + 2 \cdot 65_b + 2 \cdot 625.$$

This separates the two global 65-dimensional irreducibles by their local branch source while preserving the characteristic-2 firewall above.

73.19 The $q = 11$ footprint distance closes at 121

Pass 5304 showed that a weight-20 footprint-dual word at $q = 11$ must induce at least 120 intersection-two edges among its selected P-carriers, with equality precisely when 240 W-points are covered twice. The congruence pattern from $q = 5, 7, 9$ singles out the $q \equiv 3 \pmod 4$ two-factor shape

$$K_{10,10} + C_{10} + (C_5 + C_5).$$

Pass 5354 constructs such a support explicitly from the order-10 symplectic map

$$T = \mathrm{diag}(1, 2, 1, 6) \in \mathrm{Sp}_4(11).$$

The two ten-carrier orbits have internal two-factors C_{10} and $C_5 + C_5$; every cross pair meets in two W-points, and the XOR of all twenty carrier incidence vectors is zero. Thus a genuine dual word of weight 20 exists and saturates the 120-edge lower bound.

For the orbit moment closure, attach to each polar-pair carrier A the involution S_A acting as $+1$ on one nondegenerate summand and -1 on its polar mate. A fixed carrier has stabilizer suborbits

$$1, 660, 1320, 1320, 1320, 1320, 1440,$$

separated by $\mathrm{tr}(S_A S_B)^2 \in \{0, 1, 3, 4, 5, 9\}$. On the dual-20 seed the six nontrivial pair counts are

$$10, 30, 10, 5, 120, 15,$$

so the replication-to-pair-codegree ratios are

$$660, 440, 1320, 2640, 120, 880.$$

The worst ratio is exactly 120. Since every dual intersection with a primal support is even, the standard first/second-moment inequality gives

$$w_{\mathrm{primal}} \geq 1 + 120 = 121.$$

Point footprints attain 121, while Pass 5376 supplies rank 671. Therefore

$$\boxed{C_F(q = 11) = [7381, 671, 121]_2.}$$

Consequently the exact footprint-distance law $d = q^2$ is now verified at $q = 3, 5, 7, 9, 11$; no all-odd distance theorem beyond these anchors is asserted.

73.20 The odd-q footprint matrix is a binary two-periodic complex

The integral Gram identity of Pass 5267 reduces for odd q to

$$\boxed{FF^{\mathsf{T}} = J \pmod 2}.$$

Hence $\langle F^{\mathsf{T}}x, F^{\mathsf{T}}y\rangle$ is simply the product of the parities of x and y; in particular $\ker F^{\mathsf{T}}$ is contained in the even point module and the induced bilinear form on the footprint image has rank one.

There is a complementary identity. Two carriers are $C_H = \mathrm{PG}(H) \cup \mathrm{PG}(H^{\perp})$ and $C_K = \mathrm{PG}(K) \cup \mathrm{PG}(K^{\perp})$. Orthogonal complementation pairs $H \cap K$ with $H^{\perp} \cap K^{\perp}$ and pairs $H \cap K^{\perp}$ with $H^{\perp} \cap K$; their projective point counts therefore occur twice. Thus every two carrier columns have even intersection and

$$\boxed{F^{\mathsf{T}}F = 0 \pmod 2}.$$

Writing V_0 for the even point module and U for the carrier module gives the binary two-periodic complex

$$U \xrightarrow{F} V_0 \xrightarrow{F^{\mathsf{T}}} U.$$

Pass 5376 closes $\operatorname{im} F = C_W^{\perp}$, $\ker F^{\mathsf{T}} = C_W$, and $\operatorname{rank} F = g = q(q^2+1)/2$. Since the restriction $F^{\mathsf{T}}|_{V_0}$ has rank $g-1$, the point-side homology is canonically

$$\boxed{H_V = C_W/C_W^{\perp}, \qquad \dim H_V = q^2 + 1.}$$

This is exactly the logical quotient of the binary CSS family in Pass 5379, so its logical dimension has a canonical chain-homology realization rather than being only a rank subtraction.

73.21 The Hoffman extraspecial lift is a real two-qubit Pauli group

The normal order-32 subgroup of the Hoffman-cover stabilizer found in Pass 5300 is 2_+^{1+4}. Passes 5351–5352 choose explicit involutions X_1, Z_1, X_2, Z_2 and the central involution z satisfying

$$X_i^2 = Z_i^2 = z^2 = 1, \qquad [X_1, Z_1] = [X_2, Z_2] = z,$$

with all cross-pair commutators trivial; the 32 normal forms $z^e X_1^a Z_1^b X_2^c Z_2^d$ are distinct. This is an explicit presentation of the real two-qubit Pauli extraspecial group.

Transporting its commutator symplectic form through the Pass 5300 $\mathbb{F}_2^4$ Latin/Hoffman conjugacy explains the previous $9+6$ direction split exactly. In the five-line $\mathrm{PG}(3,2)$ spread carried by the complete order-4 MOLS geometry,

$$\boxed{\text{row, column, symbol are isotropic/commuting}},$$

whereas

$$\boxed{\text{the two orthogonal-mate triples are nonisotropic and pairwise anticommuting}}.$$

Thus $9+6$ is literally three isotropic projective lines plus two nonisotropic triples. This is finite group/code geometry only; no physical two-qubit identification is inferred.

73.22 Seven spherical shadows of the 2340-word K_0 shell

Applying the seven primitive central idempotents of the Pass 5332 rank-21 orbital algebra to the 2340 minimum K_0 words gives seven exact unit-norm tight-frame embeddings, with isotypic ranks

$$1, 104, 65, 520, 270, 130, 1250.$$

The multiplicity-one 65-block is especially rigid: the fifteen local shell words over each $W(3,5)$ point collapse to one vector, leaving exactly 156 distinct unit vectors. Their off-fiber inner products are

$$-\frac{1}{5} \quad \text{and} \quad \frac{1}{25},$$

recovering the negative two-distance spherical embedding of $W(3,5)$. The 104- and 520-blocks instead collapse the shell in triples to 780 distinct vectors, while the multiplicity-2 and multiplicity-3 blocks retain all 2340 vectors and produce new six-distance spherical configurations.

73.23 The $q = 5$ footprint hull is the $NO_5^+(5)$ adjacency code

Join two of the 325 $q = 5$ polar-pair carriers when their W-supports meet in two points. This is the rank-three graph

$$\mathrm{srg}(325, 144, 68, 60) = NO_5^+(5).$$

The binary row span of its adjacency matrix has rank 64. Independently the q5 footprint hull has rank 64, and the combined span still has rank 64. Hence

$$\boxed{\mathrm{Hull}(C_F) = \mathrm{Row}_{\mathbb{F}_2}(A_{NO_5^+(5)}).}$$

Because $144, 68, 60$ are all even, the SRG identity gives $A^2 = 0$ over $\mathbb{F}_2$, so this graph code is self-orthogonal. By Pass 5243 every Hoffman 13-cover shortened word lies in this 64-dimensional graph code. Exact XOR-SAT models have been committed both for the full $[312, 52, d]$ shortening and, after coordinate-transitivity symmetry breaking, for the ambient hull. Their clean replay remains the final certificate needed to promote $d = 40$; until that replay completes the established Hoffman status remains $d \in \{28, 32, 36, 40\}$.

Evidence boundary. The $q = 11$ $[7381, 671, 121]_2$ theorem, the binary chain complex and CSS logical homology, the extraspecial/Pauli presentation, the Latin $3 + 2$ commutator split, the seven K_0 tight frames, and the $NO_5^+(5)$ graph-code identity are exact. The Hoffman shortening distance is not promoted here without the queued UNSAT certificate. No physical quantum hardware, topological phase, or all-odd footprint-distance theorem beyond the stated finite anchors is claimed.

73.24 Canonical two-line pair space and the all-odd Steinberg-square law

The local fifteen-point fiber isolated at $q = 5$ in Pass 5336 is not an isolated representation-theoretic object. For every odd prime power q, the $q + 1$ lines through a point of $W(3, q)$ carry the natural projective $\mathrm{PSL}_2(q)$ action, and their unordered pairs form the canonical homogeneous space

$$\Lambda_q = \binom{\mathbf{P}^1(q)}{2} \cong \mathrm{PSL}_2(q)/N(T_{\mathrm{split}}), \qquad |\Lambda_q| = \frac{q(q+1)}{2}, \qquad |N(T_{\mathrm{split}})| = q - 1.$$

At $q = 5$, Λ_5 is exactly the A_5/V_4 fiber of Pass 5336. For general q we use only the canonical incident-line pair space; we do *not* assume that an arbitrary minimum K_0 shell has this fiber.

Let St_q denote the q-dimensional complex Steinberg module of $\mathrm{PSL}_2(q)$. Since

$$\mathbb{C}[\mathbf{P}^1(q)] \cong \mathbf{1} \oplus \mathrm{St}_q,$$

and the symmetric square of the point-permutation module splits into its diagonal monomials and its off-diagonal monomials, Pass 5356 gives the exact characteristic-zero identity

$$\boxed{\mathbb{C}[\Lambda_q] \cong \mathrm{Sym}^2(\mathrm{St}_q).}$$

The direct elementwise character check

$$\chi_{\Lambda_q}(g) = \frac{\chi_{\mathrm{St}}(g)^2 + \chi_{\mathrm{St}}(g^2)}{2}$$

was replayed for $q = 3, 5, 7, 11, 13$. In particular, the $q = 5$ decomposition

$$15 = 1 + 4 + 2 \cdot 5$$

is the first nontrivial member of an all-odd Steinberg-square family.

Orbital rank. Write $m = (q-1)/2$. The pair stabilizer is a dihedral group of order $2m$. A Burnside count of its orbits on Λ_q gives

$$\boxed{r(q) = \dim \mathrm{End}_{\mathrm{PSL}_2(q)} \mathbb{C}[\Lambda_q] = \begin{cases} (3q+9)/4, & q \equiv 1 \pmod 4, \\ (3q+7)/4, & q \equiv 3 \pmod 4. \end{cases}}$$

The identity contributes $|\Lambda_q|$ fixed pairs; each nonidentity split rotation fixes the base pair, the unique rotational involution contributes an additional m pairs when m is even, and each of the m reflections fixes $m+1$ pairs. Thus the rank-six algebra at $q = 5$ is not uniform in q.

73.25 All-odd complex Wedderburn theorem for the pair Hecke algebra

The exact permutation-character decomposition of $\mathrm{PSL}_2(q)$ on two-subsets, as computed by Daraf-sheh and Pournaki, shows that every irreducible constituent occurs with multiplicity one or two. More precisely, for $q \equiv 1 \pmod 4$ the multiplicity-two terms are the Steinberg character together with the relevant principal-series characters indexed by $i \equiv 0 \pmod 4$, while for $q \equiv 3 \pmod 4$ they are the discrete-series terms indexed by $j \equiv 2 \pmod 4$. Counting them gives

$$d(q) = \left\lfloor \frac{q+3}{8} \right\rfloor.$$

Consequently Pass 5360 upgrades the finite Pass 5359 intersection-tensor census to the all-odd theorem

$$\boxed{\mathcal{A}_q := \mathrm{End}_{\mathrm{PSL}_2(q)} \mathbb{C}[\Lambda_q] \cong \mathbb{C}^{\,s(q)} \oplus M_2(\mathbb{C})^{\,d(q)},}$$

where

$$s(q) = r(q) - 4d(q).$$

Hence

$$\boxed{\dim Z(\mathcal{A}_q) = r(q) - 3d(q), \qquad \dim[\mathcal{A}_q, \mathcal{A}_q] = 3d(q).}$$

The direct intersection tensors at $q = 3, 5, 7, 11, 13, 17, 19, 23$ agree exactly. The first values are

q	$r(q)$	$\mathcal{A}_q$
3	4	$\mathbb{C}^4$
5	6	$\mathbb{C}^2 \oplus M_2(\mathbb{C})$
7	7	$\mathbb{C}^3 \oplus M_2(\mathbb{C})$
11	10	$\mathbb{C}^6 \oplus M_2(\mathbb{C})$
13	12	$\mathbb{C}^4 \oplus M_2(\mathbb{C})^2$.

This is a theorem about the complex canonical pair space. It does not identify the characteristic-two footprint module.

73.26 Characteristic-two firewall and the $q \bmod 8$ Klein clock

The characteristic-zero cancellation used above cannot simply be reduced modulo two. Put

$$V_2 = \mathbb{F}_2[\mathbf{P}^1(q)], \qquad \mathbf{j} = \sum_x e_x, \qquad \varepsilon\colon V_2 \to \mathbb{F}_2.$$

Because $q + 1$ is even,

$$\varepsilon(\mathbf{j}) = 0.$$

Transitivity gives $\dim \mathrm{Hom}_{\mathrm{PSL}_2(q)}(V_2, \mathbf{1}) = 1$, generated by augmentation. Therefore every equivariant map $V_2 \to \mathbf{1}$ kills $\mathbf{j}$, so no equivariant projection onto $\langle \mathbf{j} \rangle$ exists. Thus the trivial submodule does not split off in characteristic two. This is the explicit firewall preventing the Steinberg-square theorem from being misused as a proof of the still-open all-odd binary footprint-rank law.

There is, however, an exact arithmetic compatibility. The complex pair character contains its exceptional conjugate pair precisely for $q \equiv 1, 3 \pmod 8$, while the characteristic-two Weil pair from the rank-three point module descends to $\mathbb{F}_2$ precisely for $q \equiv 1, 7 \pmod 8$ (and otherwise requires $\mathbb{F}_4$). These are the two quadratic characters

$$\chi_{-2}(q), \qquad \chi_2(q),$$

and

$$\chi_{-2}(q)\chi_2(q) = \chi_{-1}(q).$$

Equivalently,

$$\boxed{(\mathbb{Z}/8\mathbb{Z})^\times \longrightarrow \{\pm 1\}^2, \qquad q \longmapsto (\chi_{-2}(q), \chi_2(q))}$$

is the full Klein-four character clock. The two bits come from independent characteristic-zero and characteristic-two constructions; no isomorphism between their exceptional constituents is asserted.

Evidence boundary. The all-odd statements proved in Passes 5356–5361 concern the canonical $\mathrm{PSL}_2(q)$ pair space and its complex centralizer algebra, plus the elementary characteristic-two nonsplitting statement and the arithmetic q mod 8 clock. The general equality

$$\mathrm{rank}_2\, F = \frac{q(q^2+1)}{2} \quad \Longleftrightarrow \quad \ker_2(F^T) = C_W$$

remains open beyond the verified anchors. Likewise the $q = 11$ dual weight-20 existence/distance problem and the Hoffman shortened-code minimum distance remain unchanged.

73.27 Publication-DAG integrity: recursive frontier reachability

The shared live theorem frontier is now audited as a directed acyclic include graph rather than as a flat list. This matters because `analysis/W33_CURRENT_FRONTIER_MANIFEST.tex` is a wrapper around the preserved pre-Pass4865 manifest together with later theorem inserts. The older flat-list auditor therefore no longer described the object it was checking.

The recursive audit exposed one concrete publication defect: the insert `BT4137_BT4144_matrix_horizon_rg_sc` was reachable once through the preserved pre-Pass4865 manifest and a second time through a direct edge in the live wrapper. The redundant edge has been removed; the theorem source itself is unchanged.

A second source-level drift surface was then eliminated. The three canonical wrappers each carried the same ordered block of 28 post-manifest theorem inputs. Those 84 manually repeated edges have been replaced by one shared source, `analysis/W33_SHARED_FRONTIER_TAIL.tex`, referenced exactly once after the current-frontier root by each manuscript. This preserves the historical publication order while reducing the common post-frontier routing surface from 84 wrapper edges to three. Manuscript-specific earlier inserts remain untouched.

The active source contract is now `data/w33_publication_frontier_contract_v2.json`. It records the nested frontier root, the shared wrapper tail, all three front doors, the public index, and the later public-section extension. The old v1 ordered list is retained as archival must-remain-reachable data rather than being mistaken for the current direct-child list.

The publication guard now checks the following fail-closed conditions:

1. the nested manifest graph is acyclic;
2. every referenced TeX source exists;
3. every reachable theorem leaf has exactly one incoming publication path;
4. the 28-leaf shared tail is internally unique and disjoint from the frontier root;
5. each of `w33_paper.tex`, `photonic_holonet.tex`, and `holonet_machine_blueprint.tex` enters the shared frontier and shared tail exactly once, in that order;
6. no front-door wrapper directly re-includes a leaf already reachable through either shared source; and
7. configured public-index sections, including extension-ledger sections, have unique tokens and source files and materialize exactly once when the public audit is enabled.

This is a publication-integrity theorem, not a mathematical or physical theorem. It changes no finite-geometry result, code parameter, hardware claim, or evidence tier; it only makes the source reachability of the three canonical manuscripts explicit and machine-checkable.

73.28 The all-odd binary footprint theorem is closed

Let $C_W \subseteq \mathbb{F}_2^{\mathcal{P}}$ be the binary code spanned by the lines of $W(3,q)$ on the point set $\mathcal{P}$, and let F be the point-versus-P-component footprint matrix whose columns are the indicators of polar pairs $H \cup H^{\perp}$ of non-isotropic projective lines. Passes 5201 and 5288 already give

$$\operatorname{im}_2 F \subseteq C_W^{\perp},$$

because every footprint block meets every W-line in zero or two points. Moreover, every point belongs to exactly q^2 footprint blocks, so for odd q the sum of all columns of F is the all-one vector $\mathbf{1}$. Since a single footprint column has weight $2(q+1) < |\mathcal{P}|$, we have the strict containment

$$\langle \mathbf{1} \rangle < \operatorname{im}_2 F \leq C_W^{\perp}.$$

The missing step is supplied by the complete characteristic-two point-module lattice of Lataille–Sin–Tiep. Their incidence map $\eta_{2,1}$ is exactly the line-to-point incidence map of $W(3,q)$, so their code $C = \operatorname{im} \eta_{2,1}$ is C_W. They prove $C^{\perp} = U'$ and, because $m = 2$ is even, the bottom interval is uniserial:

$$\boxed{U' > \langle \mathbf{1} \rangle > 0.}$$

Their field-of-definition remark carries this submodule interval to $\mathbb{F}_2$. Hence $C_W^{\perp}/\langle \mathbf{1} \rangle$ is simple. The strict submodule sandwich above therefore forces

$$\boxed{\operatorname{im}_2 F = C_W^{\perp}.}$$

Using

$$\dim C_W = 1 + \frac{q(q+1)^2}{2}$$

then gives, for every odd prime power q,

$$\boxed{\operatorname{rank}_2 F = \frac{q(q^2+1)}{2}, \qquad \ker_2(F^T) = C_W.}$$

This is the formerly open all-odd footprint-rank theorem, not a finite-anchor extrapolation.

73.29 Rank complement and zero-footprint generation

Write

$$f = \frac{q(q+1)^2}{2}, \qquad g = \frac{q(q^2+1)}{2}.$$

Together with the characteristic-zero frame theorem of Pass 5267, the complete rank complement is now exact:

$$\boxed{\operatorname{rank}_{\mathbb{Q}} F = 1 + f = \operatorname{null}_2 F, \qquad \operatorname{null}_{\mathbb{Q}} F = g = \operatorname{rank}_2 F.}$$

Pass 5299 had already constructed the same-point difference code D_q and proved

$$D_q \subseteq K_0, \qquad \dim D_q = q^4 - g, \qquad \dim K_0 = q^4 - \operatorname{rank}_2 F.$$

Therefore Pass 5376 closes the last dimension gap and yields

$$\boxed{K_0 = D_q}$$

for every odd prime power q. Thus the three formerly equivalent conjectures

$$\operatorname{rank}_2 F = g, \qquad \ker_2(F^T) = C_W, \qquad K_0 = D_q$$

are now three equivalent theorems.

73.30 The footprint image is generated by its complete minimum shell

Pass 5189 already proved, for every prime power q, that $C_W^{\perp}$ has minimum distance

$$d(C_W^{\perp}) = 2(q+1),$$

and that its complete minimum shell consists exactly of the dual grids

$$H \cup H^{\perp},$$

one for each polar pair of non-isotropic projective lines. There are

$$\frac{q^2(q^2+1)}{2}$$

such words. These are exactly the columns of F. The new equality $\mathrm{im}_2 F = C_W^{\perp}$ therefore upgrades the old minimum-shell classification to the all-odd spanning theorem

$$\boxed{C_W^{\perp} = \left\langle H \cup H^{\perp} : \ H \text{ non-isotropic} \right\rangle_{\mathbb{F}_2}.}$$

Equivalently the footprint image is the classical binary code

$$\boxed{\left[(q+1)(q^2+1),\ \frac{q(q^2+1)}{2},\ 2(q+1)\right]_2}$$

generated by a single $\mathrm{PSp}_4(q)$-orbit consisting of *all* of its minimum words.

73.31 Binary point-code CSS corollary

The same Lataille–Sin–Tiep lattice gives

$$C_W^{\perp} \subset C_W.$$

Hence the footprint code $C_F = C_W^{\perp}$ is self-orthogonal and may be used as both the X- and Z-check space of a binary CSS stabilizer code. The length and check rank are

$$n = (q+1)(q^2+1), \qquad \operatorname{rank} H_X = \operatorname{rank} H_Z = g,$$

so

$$k = n - 2g = q^2 + 1.$$

For regular generalized quadrangles the binary line code C_W has minimum weight $q+1$, attained by line incidence vectors. A W-line does not lie in $C_W^{\perp}$: any intersecting W-line has inner product one with it. Therefore both logical distances are exactly $q+1$, and we obtain the all-odd family

$$\boxed{\left[\!\left[(q+1)(q^2+1),\ q^2+1,\ q+1\right]\!\right]_2.}$$

The first examples are

$$[[40, 10, 4]]_2, \qquad [[156, 26, 6]]_2, \qquad [[400, 50, 8]]_2, \qquad [[820, 82, 10]]_2.$$

This is a binary *point-code* CSS family. It is distinct from the project's ternary edge code $[[240, 81, 3]]_3$; no equivalence between the two is claimed.

73.32 The logical module carries the same $q \bmod 8$ Weil clock

The logical vector space is not only dimensionally simple:

$$\mathcal{L}_q = C_W / C_W^{\perp}, \qquad \dim \mathcal{L}_q = q^2 + 1.$$

The proof of the Lataille–Sin–Tiep point-module theorem gives the composition factors of this quotient over an algebraic closure of $\mathbb{F}_2$ as

$$\boxed{\mathcal{L}_q : \quad \mathbf{1},\ \mathbf{1},\ W_1,\ W_2, \qquad \dim W_1 = \dim W_2 = \frac{q^2-1}{2}.}$$

Their field-of-definition theorem then makes the arithmetic clock explicit on the logical sector itself. If $q \equiv \pm 1 \pmod 8$, the two Weil factors are individually defined over $\mathbb{F}_2$. If $q \equiv \pm 3 \pmod 8$, their smallest field is $\mathbb{F}_4$, so over $\mathbb{F}_2$ the middle pair is one irreducible Galois-fused module of dimension $q^2 - 1$. Thus the same mod-8 Weil bit from Pass 5361 now controls the binary logical-channel decomposition.

This is a composition-factor and field-of-definition theorem. In particular, we do not infer that the two trivial factors split as direct summands of $\mathcal{L}_q$.

Evidence boundary. Passes 5376–5379 and 5406 close the all-odd binary footprint rank, kernel, same-point K_0 generation, complete minimum-shell spanning, the abstract CSS parameters, and the logical Weil descent clock above. They do *not* close the $q = 11$ dual weight-20 existence/$d = 121$ problem, the Hoffman shortened-code distance $d \in \{28, 32, 36, 40\}$, any fault-tolerant threshold, or a hardware realization of the binary CSS family.

Pass5380–5387 frontier: filtered code tower, radius nine, and modular projectors

At $q = 5$ the apartment code, its zero-footprint kernel, and the point-footprint quotient form the exact sequence

$$0 \longrightarrow K_0 \longrightarrow C_A \longrightarrow C_F \longrightarrow 0$$

with

$$C_A = [73125, 625, 625]_2, \qquad K_0 = [73125, 560, 1000]_2, \qquad C_F = [325, 65, 25]_2.$$

Their complete minimum shells have 936, 2340, and 156 words, respectively. Thus every apartment-code word of weight below 1000 has nonzero point footprint. This statement synthesizes the previously proved q5 distance, zero-footprint block-distance, and minimum-shell certificates; it is not a new all-q distance claim.

For the deterministic qutrit-building hard-decision decoder at $q = 3$, the eventual guaranteed radius is now nine. Fixing a false candidate by apartment transitivity, the false-vote sectors satisfy: $V = 1$ and $V = 2$ are excluded by exact mixed-integer feasibility tests; the $V = 3$ sector leaves exactly 32 rooted candidates, all clearing as

$$9 \to 10 \to 1 \to 0;$$

and all 25648 rooted $V = 4$ configurations clear as well. Therefore every weight-nine error either makes a nonempty true-only first correction and enters the certified radius-eight basin, or lies in one of these finite false-survivor families and self-heals. The monotone true-only guarantee remains radius seven, because the known weight-eight echo family intentionally makes a false first correction.

The connected opposite-line chart graph at $q = 5$ also admits exact characteristic-two primary projectors. Its binary adjacency operator A_L has minimal polynomial

$$x^3(x+1)^4.$$

Since $(x+1)^4 = x^4 + 1$ over $\mathbb{F}_2$, the generalized one- and zero-primary projectors are simply

$$P_1 = A_L^4, \qquad P_0 = I + A_L^4,$$

with ranks 6034 and 3716. These scalar projectors do not undo the previously certified failure of the naive ten-channel lift $A_L \otimes I_{10}$; rather, any correct twisted channel transport must be compatible with this primary decomposition after channel coordinates are forgotten.

The parallel all-odd footprint theorem now upgrades the parity bridge to the exact sequence

$$0 \longrightarrow D_q = K_0 \longrightarrow C_A \longrightarrow C_F \longrightarrow 0$$

for every odd prime power q, with

$$\dim C_A = q^4, \qquad \dim C_F = \frac{q(q^2+1)}{2}, \qquad \dim D_q = \frac{q(q-1)(2q^2+q+1)}{2}.$$

Consequently the remaining all-odd apartment-distance problem is no longer a footprint-rank problem: it is a Hamming-weight problem inside D_q and its nonzero footprint cosets.

Three further structural consequences emerge. First, the multiplicity-one 65_a central idempotent of the q5 K_0 minimum-shell orbital algebra reconstructs the base geometry internally: quotienting the 2340 shell words by their 15-fold duplicate relation leaves 156 vectors, with 30 vectors at inner product $-1/5$ and 125 at $+1/25$ from each vector. Declaring the $-1/5$ relation adjacent recovers exactly $\mathrm{SRG}(156, 30, 4, 6) = W(3, 5)$.

Second, if $c_1, \ldots, c_k$ are k consecutive chambers of an apartment, then for $1 \le k \le 5$

$$\left| \bigcap_{i=1}^{k} \mathrm{Star}(c_i) \right| = q^{5-k},$$

so the exact consecutive-gallery tower is

$$q^4,\ q^3,\ q^2,\ q,\ 1.$$

The $k = 5$ step follows directly from the generalized-quadrangle projection axiom, which uniquely closes the remaining two apartment edges. This is the rigorous power-drop structure behind the earlier derivative analogy; the calculus coefficients themselves are not part of the theorem.

Third, on each q5 point footprint the restricted zero-footprint kernel is $\mathbb{F}_2^4$. Translating the six chamber-star restrictions by one chosen star gives a six-element set whose fifteen unordered pair differences are all fifteen nonzero vectors. Hence every point fiber carries a $(16, 6, 2)$ difference set and therefore a symmetric 2-$(16, 6, 2)$ development.

Open solver boundary. The Hoffman-13 shortened code remains $[312, 52, d]_2$ with $d \in \{28, 32, 36, 40\}$ until the exact full-code XOR–SAT replay terminates. Pass5383 encodes an injective 52-bit generator, all 312 coordinate XOR equations, a nonzero-message condition, and Hamming weight at most 39. UNSAT would prove $d = 40$; SAT must instead be frozen as an explicit verified sub-40 witness. No $d = 40$ claim is made before that solver evidence exists.

73.33 All-q Levi flag distance scheme and Hodge cycle projector

Let $\mathcal{S}$ be a finite generalized quadrangle of order (q,q), $q>1$, let Γ be its point–line incidence graph, and let

$$X = L(\Gamma)$$

be the line graph of Γ. Thus the vertices of X are exactly the flags (p,L) of $\mathcal{S}$, and two flags are adjacent when they share their point or their line.

There is an important prior-art boundary. Colangelo, Monzillo, and Siciliano, *Discrete Mathematics* **347** (2024), 114054 (arXiv:2406.03942), already construct and characterize the symmetric primitive four-class fusion of the flag association scheme. In the equal-parameter case its nontrivial valencies are

$$2q, \qquad 2q^2, \qquad 2q^3, \qquad q^4.$$

The result below does not claim priority for that association scheme. The new bridge here is to the Levi Hodge/cycle projector used throughout the $W(3,3)$ architecture.

Direct generalized-quadrangle counting identifies the four fusion relations with the four distance shells of X, giving the intersection array

$$\boxed{\{2q,q,q,q;\ 1,1,1,2\}.}$$

Hence every flag has distance profile

$$\boxed{1,\ 2q,\ 2q^2,\ 2q^3,\ q^4,}$$

and

$$|V(X)| = (q+1)^2(q^2+1).$$

The corresponding distance-quotient characteristic polynomial factors exactly as

$$\boxed{(x-2q)(x+2)(x-q+1)\big((x-q+1)^2-2q\big).}$$

Thus the adjacency spectrum of X is

$$2q, \qquad q-1+\sqrt{2q}, \qquad q-1, \qquad q-1-\sqrt{2q}, \qquad -2,$$

with multiplicities

$$\boxed{1, \quad \frac{q(q+1)^2}{2}, \quad q(q^2+1), \quad \frac{q(q+1)^2}{2}, \quad q^4.}$$

The multiplicity q^4 has a direct topological meaning. The Levi graph has

$$|V(\Gamma)| = 2(q+1)(q^2+1), \qquad |E(\Gamma)| = (q+1)^2(q^2+1),$$

so, because Γ is connected,

$$\boxed{\beta_1(\Gamma) = |E| - |V| + 1 = q^4.}$$

Orient every Levi edge from its point endpoint to its line endpoint and let D be the oriented incidence matrix. Two distinct oriented columns have inner product one precisely when the corresponding Levi edges meet, hence

$$\boxed{D^{\mathsf{T}}D = 2I + A_X.}$$

Consequently

$$\boxed{\ker D = E_{-2}(A_X),}$$

so the terminal primitive eigenspace of the flag distance scheme is *exactly* the Levi cycle space. Its dimension is q^4.

Let $A_0, \dots, A_4$ be the distance matrices of X. The standard sequence for the eigenvalue -2 is

$$1, -\frac{1}{q}, \frac{1}{q^2}, -\frac{1}{q^3}, \frac{1}{q^4}.$$

Multiplying by the distance valencies gives the q-independent terminal first-eigenmatrix row

$$\boxed{(1, -2, 2, -2, 1),}$$

while multiplying by the multiplicity q^4 gives the terminal second-eigenmatrix column

$$\boxed{(q^4, -q^3, q^2, -q, 1).}$$

Therefore the orthogonal Hodge projector onto the Levi cycle space is the radial Bose–Mesner idempotent

$$\boxed{P_{\mathrm{cyc}} = E_{-2} = \frac{q^4 A_0 - q^3 A_1 + q^2 A_2 - q A_3 + A_4}{(q+1)^2(q^2+1)}.}$$

At $q = 3$, this becomes

$$|V(X)| = 160, \qquad (1, 6, 18, 54, 81), \qquad \beta_1(\Gamma) = 81,$$

and

$$\boxed{E_{-2} = \frac{81A_0 - 27A_1 + 9A_2 - 3A_3 + A_4}{160}.}$$

This is exactly the BT545–BT551 W33 Levi Hodge/Kirchhoff projector and explains the previously observed coefficient column $(81, -27, 9, -3, 1)$ as the $q = 3$ specialization of the universal $(-1/q)^d$ radial law.

Evidence boundary. This theorem identifies an exact graph-theoretic/Hodge sector. It does not by itself prove a quantum-code distance, a fault-tolerance threshold, or a laboratory protection mechanism.

73.34 All-q Levi apartments form the Hodge cycle tight frame

Continue with a generalized quadrangle $\mathcal{S}$ of order (q, q), its Levi graph Γ, and its flag line graph $X = L(\Gamma)$. An apartment of the rank-two building is a simple 8-cycle in Γ. Let

$$C \in \{-1, 0, 1\}^{N \times M}, \qquad N = (q+1)^2(q^2+1),$$

be the signed flag-edge/apartment incidence matrix: every Levi edge is oriented from its point endpoint to its line endpoint, and every apartment column is given either cyclic orientation. Reversing an apartment reverses its entire column and therefore leaves CC^{T} unchanged.

The apartment counts follow directly from the generalized-quadrangle axiom. A nonbacktracking Levi path of five edges has endpoints consisting of a point and a nonincident line. The unique projection of that point to that line supplies the unique three-edge return path, hence

$$\boxed{\text{every nonbacktracking five-edge Levi path lies in a unique apartment.}}$$

For a shorter fixed nonbacktracking path, the terminal vertex has q legal continuations after excluding the edge just traversed. Each apartment containing the shorter path chooses exactly one of them. Iterating therefore gives

$$\boxed{\#\{\text{apartments containing flag edges } e, f\} = q^{4-d_X(e,f)}.}$$

In particular every flag edge lies in q^4 apartments. Since every apartment contains eight flag edges,

$$\boxed{M = \frac{Nq^4}{8} = \frac{(q+1)^2(q^2+1)q^4}{8}.}$$

The fixed point-to-line orientation alternates signs around an apartment. Thus two flag edges at line-graph distance d contribute relative sign $(-1)^d$, and the full overlap kernel is

$$\boxed{CC^{\mathsf{T}} = q^4A_0 - q^3A_1 + q^2A_2 - qA_3 + A_4.}$$

Passes 5388–5395 identified the right-hand side as NE_{-2}. Therefore

$$\boxed{CC^{\mathsf{T}} = NE_{-2} = NP_{\mathrm{cyc}}.}$$

Consequently the complete apartment family spans the entire Levi cycle space,

$$\boxed{\operatorname{rank} C = q^4,}$$

and its nonzero frame-operator eigenvalue is N.

Each apartment column has squared norm 8. After dividing every column by $\sqrt{8}$, the $M = Nq^4/8$ apartment vectors form a unit-norm tight frame for the q^4-dimensional cycle space, with frame bound

$$\boxed{N/8.}$$

This is an exact all-q extension of the W33 cycle-frame theorem, not an analogy.

At $q = 3$,

$$N = 160, \qquad q^4 = 81, \qquad M = \frac{160 \cdot 81}{8} = 1620,$$

and

$$\boxed{CC^{\mathsf{T}} = 81A_0 - 27A_1 + 9A_2 - 3A_3 + A_4 = 160E_{-2}.}$$

Thus the former BT545–BT549 identities

$$160 \cdot 81 = 1620 \cdot 8 = 12960, \qquad \operatorname{spec}(CC^{\mathsf{T}}) = 160^{81} \oplus 0^{79},$$

are the $q = 3$ specialization of the general apartment tight-frame law.

Prior-art and evidence boundary. The flag association scheme and its symmetric four-class fusion are existing literature; targeted literature search also finds other tight-frame constructions built from generalized quadrangles. No priority claim is made here for generalized-quadrangle tight frames in the broad sense. The theorem asserted here is the explicit full-apartment cycle-incidence identity above and its Hodge specialization. It does not assert tightness for arbitrary apartment subsets and does not by itself imply a code distance or physical fault-tolerance threshold.

73.35 Unsigned apartment visibility: the full flag space before Hodge signing

Let $B = |C|$ be the unsigned flag-edge/apartment incidence matrix from the preceding apartment theorem. The distance-d pair count is q^{4-d}, so

$$\boxed{BB^{\mathsf{T}} = q^4 A_0 + q^3 A_1 + q^2 A_2 + q A_3 + A_4.}$$

This is the unsigned companion to

$$CC^{\mathsf{T}} = q^4 A_0 - q^3 A_1 + q^2 A_2 - q A_3 + A_4.$$

The sign change is not cosmetic: it changes the rank from the protected cycle sector to the entire flag space.

Evaluating the unsigned radial kernel on the five adjacency eigenspaces of the flag distance scheme gives

$$\boxed{\begin{aligned} \lambda_0 &= 8q^4, \\ \lambda_+ &= 2q^2(q-1)\big(q+1+\sqrt{2q}\big), \\ \lambda_m &= 2q^2(q-1)^2, \\ \lambda_- &= 2q^2(q-1)\big(q+1-\sqrt{2q}\big), \\ \lambda_c &= (q-1)^2(q^2+1), \end{aligned}}$$

with multiplicities

$$\boxed{1, \quad \frac{q(q+1)^2}{2}, \quad q(q^2+1), \quad \frac{q(q+1)^2}{2}, \quad q^4.}$$

For $q > 1$, every eigenvalue is positive. In particular,

$$\boxed{\operatorname{rank} B = N = (q+1)^2(q^2+1).}$$

The complete unsigned apartment family therefore spans the full real flag space.

By contrast, the signed matrix satisfies

$$\operatorname{rank} C = q^4.$$

The missing dimensions are exactly

$$\boxed{N - q^4 = 2(q+1)(q^2+1) - 1 = \operatorname{rank} D,}$$

where D is the oriented incidence matrix of the connected Levi graph. Thus the alternating point-to-line cycle signs remove precisely the Kirchhoff cut-space sector and retain precisely the cycle-space sector:

$$\boxed{\text{unsigned visibility} = \text{cycle} \oplus \text{cut}, \qquad \text{signed visibility} = \text{cycle}.}$$

This supplies an all-q explanation of the q=3 rank complement $160 = 81 + 79$.

At $q = 3$, the unsigned spectrum becomes

$$\boxed{648^{1} \oplus (144 + 36\sqrt{6})^{24} \oplus 72^{30} \oplus (144 - 36\sqrt{6})^{24} \oplus 40^{81},}$$

exactly the BT546 unsigned Levi edge/apartment spectrum. The signed matrix has rank 81, while the removed cut sector has rank 79, exactly as in BT549. Hence the old 3-adic visibility kernel and the old cycle/cut tight-frame decomposition are both specializations of the same all-q orientation-sign mechanism.

Evidence boundary. This is a combinatorial spectral theorem about the full unsigned apartment-incidence Gram matrix and its relation to the signed Hodge matrix. It is not a contextuality-degree theorem, a quantum-code minimum-distance theorem, or a physical noise-tolerance result.

Passes 5420–5427: complementary Hodge frames, apartment intersections, footprint bicycles, and the discrete q^4 derivative

Let Γ be the Levi graph of a generalized quadrangle $\mathrm{GQ}(q, q)$, let $X = L(\Gamma)$ be its flag line graph, and write

$$N = (q+1)^2(q^2+1), \qquad h = q^4, \qquad r = N - q^4 = 2(q+1)(q^2+1) - 1.$$

Passes 5388–5409 identified the terminal flag idempotent

$$E = \frac{q^4 A_0 - q^3 A_1 + q^2 A_2 - q A_3 + A_4}{N}$$

as the orthogonal projector onto the h-dimensional Levi cycle space.

Pass 5420: the all-q complementary cut frame. The normalized rows of E form a unit-norm tight frame with Gram matrix

$$G_{\mathrm{cyc}} = \frac{N}{q^4} E, \qquad \langle x_e, x_f \rangle = \left(-\frac{1}{q}\right)^{d_X(e,f)}.$$

The Naimark-complement projector $I - E$ has constant diagonal r/N, so its normalized rows form a second unit-norm tight frame,

$$G_{\mathrm{cut}} = \frac{N}{r}(I - E).$$

For distinct flags at distance $d = 1, 2, 3, 4$,

$$\boxed{\langle y_e, y_f \rangle = \frac{(-1)^{d+1} q^{4-d}}{r}}.$$

The pair satisfies the exact weighted complement identity

$$\boxed{\frac{q^4}{N} G_{\mathrm{cyc}} + \frac{r}{N} G_{\mathrm{cut}} = I_N}.$$

At $q = 3$ this recovers the frozen BT549 cut-frame inner products

$$1, \quad \frac{27}{79}, \quad -\frac{9}{79}, \quad \frac{3}{79}, \quad -\frac{1}{79}.$$

The Naimark-complement language is standard frame theory; the statement here is the exact generalized-quadrangle Hodge specialization.

Pass 5421: the canonical H_1–footprint exact sequence. Pass5066 gives the apartment/-theta presentation

$$0 \longrightarrow \Theta \longrightarrow \mathbb{F}_2^{\mathcal{A}} \xrightarrow{\partial} H_1(\Gamma;\mathbb{F}_2) \longrightarrow 0.$$

Since the binary apartment code is $C_A = \Theta^{\perp}$, dualizing identifies it canonically and equivariantly with $H_1(\Gamma;\mathbb{F}_2)^*$. For odd prime powers, Pass5384 gives

$$0 \longrightarrow D_q \longrightarrow C_A \longrightarrow C_F \longrightarrow 0,$$

where $\dim C_F = g = q(q^2+1)/2$. Hence

$$\boxed{0 \longrightarrow D_q \longrightarrow H_1^* \longrightarrow C_F \longrightarrow 0},$$

and dualizing once more gives

$$\boxed{0 \longrightarrow C_F^* \longrightarrow H_1 \longrightarrow D_q^* \longrightarrow 0}.$$

Thus the all-odd footprint quotient is a canonical quotient of the dual Levi cycle module, and its dual is a canonical submodule of Levi H_1. No unproved self-duality identification of C_F with C_F^* is used here.

Pass 5422: the all-q apartment-intersection profile. Two distinct apartments cannot meet in two disconnected edge intervals: otherwise their symmetric difference would contain at least two cycles whose total length is < 16, contradicting Levi girth eight. Thus every nonempty proper intersection is one path. If the common path had at least five edges, the two complementary paths would form a cycle of length at most six. Therefore a proper nonempty apartment intersection is exactly one consecutive flag-edge path of length $j \in \{1,2,3,4\}$.

Let $T_j = q^{5-j}$ be the Pass5386 number of apartments through a fixed consecutive j-edge path, and let a_j be the number of other apartments whose exact intersection with a fixed apartment is a specified j-edge path. Since a fixed j-path is contained in exactly $k-j+1$ of the k-paths of the base apartment,

$$T_j = 1 + \sum_{k=j}^{4} (k-j+1)a_k.$$

Back-substitution yields

$$a_4 = q-1, \qquad a_3 = (q-1)^2, \qquad a_2 = q(q-1)^2, \qquad a_1 = q^2(q-1)^2.$$

There are eight cyclic paths of each length, so for a fixed apartment the numbers of distinct partners meeting it in j edges are

$$\boxed{n_4 = 8(q-1), \quad n_3 = 8(q-1)^2, \quad n_2 = 8q(q-1)^2, \quad n_1 = 8q^2(q-1)^2},$$

with $n_0 = Nq^4/8 - 1 - n_1 - n_2 - n_3 - n_4$. Independent projective-polarity enumerations at $q = 2, 3, 5$ give respectively

$$(n_0, n_1, n_2, n_3, n_4) = (25, 32, 16, 8, 8),$$

$$(1187, 288, 96, 32, 16),$$

and

$$(69124, 3200, 640, 128, 32).$$

The middle line is exactly the frozen BT546 W33 census.

For oriented apartment columns c_A, the sign products are constant along a common path, hence

$$|\langle c_A, c_B\rangle| = |A \cap B|.$$

After unit normalization by $\|c_A\| = \sqrt{8}$, the full apartment frame has absolute inner products

$$0,\ \frac{1}{8},\ \frac{1}{4},\ \frac{3}{8},\ \frac{1}{2},$$

so its coherence is exactly $1/2$, independently of q.

Pass 5423: exact unsigned visibility conditioning. For the unsigned apartment-incidence matrix B, Pass5404 gives five positive eigenvalues of BB^T. The maximum is

$$\lambda_{\max} = 8q^4,$$

and the minimum is the terminal value

$$\boxed{\lambda_{\min} = (q-1)^2(q^2+1)}.$$

The only nontrivial comparison is against $2q^2(q-1)(q+1-\sqrt{2q})$. After isolating the radical, squaring leaves

$$(q^2+1)(q^4-2q^3+6q^2-2q+1) > 0,$$

whose quartic equals $q^2(q-1)^2 + 5q^2 - 2q + 1 > 0$ for $q > 1$. Consequently

$$\boxed{\kappa(BB^T) = \frac{8q^4}{(q-1)^2(q^2+1)} \longrightarrow 8},$$

while the singular-value condition number is

$$\boxed{\kappa_2(B) = \frac{\sqrt{8}\,q^2}{(q-1)\sqrt{q^2+1}} \longrightarrow \sqrt{8}}.$$

At $q = 3$, $\kappa(BB^T) = 81/5$. This statement concerns the full incidence operator, not arbitrary sparse hardware submatrices.

Pass 5425, outside box: the derivative resemblance becomes an exact finite difference. The gallery tower from Pass5386 is

$$I_1 = q^4, \quad I_2 = q^3, \quad I_3 = q^2, \quad I_4 = q, \quad I_5 = 1.$$

Therefore the user's observation that $4q^3$ resembles $d(q^4)/dq$ is the leading term of the exact identity

$$\boxed{(q+1)^4 - q^4 = 4I_2 + 6I_3 + 4I_4 + I_5} = 4q^3 + 6q^2 + 4q + 1.$$

The binomial coefficients $(4, 6, 4, 1)$ weight successive gallery-intersection levels. This is a discrete-combinatorial identity, not a differential equation in the field-size parameter.

Pass 5426, outside box: the footprint code is the point half of the Levi bicycle space. Now assume q odd and let M be the binary point–line incidence matrix. Write D for the binary vertex–flag incidence matrix of the Levi graph. Since every Levi vertex has even degree $q+1$,

$$DD^T = \begin{pmatrix} 0 & M \\ M^T & 0 \end{pmatrix} \pmod 2.$$

For $x \in \ker M^T = C_W^\perp = C_F$, define the flag vector

$$(\iota_P x)_{(p,L)} = x_p.$$

It is a cut because it is the coboundary of the point-supported vertex function x, and it is a cycle because $M^T x = 0$ while $(q+1)x_p = 0$ in characteristic two. Thus

$$\boxed{C_F \hookrightarrow \operatorname{im} D^T \cap \ker D}$$

is the canonical point-half bicycle embedding. Dually, $\ker M$ gives a line-supported kernel copy; this is only an incidence-dual copy and is not promoted as an L-footprint tensor.

Both kernels have dimension $g = q(q^2+1)/2$. Their flag images meet in the all-ones flag vector J, because the only kernel of D^T on the connected Levi vertex space is the global all-ones vertex vector. Hence

$$\boxed{\text{Bike} = P_g + L_g, \qquad P_g \cap L_g = \langle J \rangle, \qquad \dim \text{Bike} = 2g - 1 = q(q^2+1) - 1}.$$

At $q = 3$ this gives P_{15} and Bike_{29} exactly, identifying the Pass5068 point half with the already-proved $[40, 15, 8]_2$ footprint code. At $q = 5$ it predicts the exact bicycle dimension 129 from two 65-dimensional halves meeting in J.

Pass 5427, outside box: an orthogonal two-design decomposition of the regular simplex. Let $P_0 = J/N$, $P_{\text{cyc}} = E$, and

$$P_{\text{cut},0} = I - P_0 - P_{\text{cyc}}.$$

These are mutually orthogonal projectors of ranks

$$1, \qquad q^4, \qquad r-1,$$

and $q^4 + (r-1) = N - 1$. Both nonconstant projectors have constant diagonal. Their normalized row projections are centered unit-norm tight frames, hence spherical 2-designs. If $G_{\text{cut},0}$ is the centered-cut unit Gram and $G_{\text{simplex}} = \frac{N}{N-1}(I - J/N)$ is the unit regular-simplex Gram, then

$$\boxed{\frac{q^4}{N-1} G_{\text{cyc}} + \frac{r-1}{N-1} G_{\text{cut},0} = G_{\text{simplex}}}.$$

Thus the flag regular simplex splits orthogonally into its Hodge-cycle design and its nonconstant cut design. At $q = 3$, the 160 simplex vertices decompose into dimensions 81 and 78.

Evidence and prior-art firewall. The flag association scheme itself is prior art, and Naimark complements and spherical-design consequences of centered tight frames are standard frame theory. Generalized-quadrangle tight-frame constructions also exist in the literature. The claims promoted here are the exact all-q Hodge-complement formulas, the apartment-intersection census, the conditioning theorem, the all-odd footprint/bicycle identification, and their exact W33 regressions. No new optimal spherical-code, contextuality-degree, apartment-code-distance, or physical-noise theorem is inferred.

73.36 Canonical apartment tomography and the orientation Hodge filter

Let C denote the signed flag–apartment incidence matrix of a generalized quadrangle $GQ(q,q)$, with every Levi edge oriented from point to line, and put

$$N=(q+1)^2(q^2+1).$$

Pass 5396 gives $CC^{\mathsf T}=NE_{\mathrm{cyc}}$, where E_{cyc} is the orthogonal projector onto the q^4-dimensional Levi cycle space. Consequently all nonzero singular values of C equal $\sqrt{N}$, and the Moore–Penrose inverse on the cycle image is

$$\boxed{C^{+}=\frac{1}{N}C^{\mathsf T}.}$$

Thus every real cycle flow z has the canonical minimum-ℓ_2 apartment reconstruction

$$a_{\min}=\frac{1}{N}C^{\mathsf T}z,\qquad z=Ca_{\min},\qquad \|a_{\min}\|^2=\frac{\|z\|^2}{N}.$$

Equivalently, $\sum_A\langle c_A,z\rangle^2=N\|z\|^2$. Since each apartment column has squared norm eight, the normalized apartments form a unit-norm tight frame of bound $N/8$.

For the unsigned matrix $B=|C|$, Pass 5404 gives a positive five-sector Gram spectrum. Its largest eigenvalue is $8q^4$ and its smallest is $(q-1)^2(q^2+1)$ for every $q>1$, so

$$\boxed{\kappa(BB^{\mathsf T})=\frac{8q^4}{(q-1)^2(q^2+1)}.}$$

The exact inverse is the primitive-idempotent spectral sum and $B^{+}=B^{\mathsf T}(BB^{\mathsf T})^{-1}$. Changing only the odd-distance shell signs sends the full-rank unsigned kernel

$$q^4A_0+q^3A_1+q^2A_2+qA_3+A_4$$

to

$$q^4A_0-q^3A_1+q^2A_2-qA_3+A_4=NE_{\mathrm{cyc}}.$$

Hence orientation is an exact algebraic Hodge spectral filter: it removes the Levi cut-space dimensions while preserving the diagonal trace. This terminology is purely spectral and carries no thermodynamic claim.

73.37 Integral unsigned spectrum and exact Gram volume

The conjugate eigenvalues

$$\lambda_{\pm}=2q^2(q-1)(q+1\pm\sqrt{2q})$$

are the roots of

$$Q_q(x)=x^2-4q^2(q-1)(q+1)x+4q^4(q-1)^2(q^2+1).$$

With $f=q(q+1)^2/2$ and $g=q(q^2+1)/2$, the complete characteristic polynomial is

$$\boxed{(x-8q^4)Q_q(x)^f(x-2q^2(q-1)^2)^{2g}(x-(q-1)^2(q^2+1))^{q^4}.}$$

In particular the radicals cancel in the global determinant. Writing $P=(q+1)(q^2+1)$,

$$\boxed{\det(BB^{\mathsf T})=2^{2P+1}q^{4P}(q-1)^{2f+4g+2q^4}(q^2+1)^{f+q^4}.}$$

At $q=3$ this is $2^{456}3^{160}5^{105}$.

73.38 Characteristic-two radical quotient and the $q = 5$ post-minimum gap

Pass 5376 already closes the all-odd binary footprint theorem:

$$\operatorname{rank}_2 F = g = \frac{q(q^2+1)}{2}, \qquad \ker(F^{\mathsf{T}}) = C_W$$

for every odd prime power q. Pass 5350 independently identifies, for the even-weight point module M_0,

$$\operatorname{Rad}(\operatorname{im} F^{\mathsf{T}}) = F^{\mathsf{T}}(M_0).$$

The general exact sequence

$$0 \longrightarrow X_q := \ker(F^{\mathsf{T}})/C_W \longrightarrow M_0/C_W \longrightarrow \operatorname{Rad}(\operatorname{im} F^{\mathsf{T}}) \longrightarrow 0$$

therefore collapses by Pass 5376 to $X_q = 0$, giving the canonical all-odd isomorphism

$$\boxed{M_0/C_W \cong \operatorname{Rad}(\operatorname{im} F^{\mathsf{T}}),} \qquad \dim = g - 1.$$

This X_q is only the transient extra point-kernel quotient and is distinct from Pass 5421's nonzero apartment-to-footprint kernel D_q in $0 \to D_q \to H_1^* \to C_F \to 0$, where $\dim D_q = q^4 - g$. No splitting of $\mathbb{F}_2[P^1(q)]$ is used.

At $q = 5$, $K_0 = [73125, 560, 1000]_2$. Pass 5284 classifies every block-minimum word: there are 2340, all of weight 1000. Every other word has at least 26 active P-components, each nonzero local even component having weight at least 40. Therefore

$$\boxed{d_2(K_0) \geq 1040,}$$

so weights $1001, \ldots, 1039$ are absent. No weight-1040 witness is asserted.

73.39 The $q = 3$ provenance decoder reaches eventual radius ten

Pass 5381 closes eventual radius nine. At weight ten, fix a false candidate by apartment transitivity and write V for its vote. The four incident charts are disjoint away from the candidate, so $V \leq 4$. For $V = 1$, an exact fixed-coordinate stopping-set MILP is infeasible. For $V = 2$, an exact MILP enforcing two local false votes and at least three spoiled charts at every true error is infeasible.

For $V = 3$, the local false-center weights $6, 7, 8, 9, 10$ occur with counts

$$32,\ 256,\ 832,\ 1536,\ 1856.$$

A single outsider supplies at most two new local chart directions. The exact local direction deficits are already too large for weights seven through ten, so only weight six plus four outsiders survives the necessary spoiled-chart test. Its complete completion census contains $\boxed{1296}$ rooted candidates, and every one clears under the actual deterministic decoder.

For $V = 4$, the raw rooted count is

$$16\binom{1599}{2} + 64 \cdot 1599 + 96 = 20{,}544{,}048.$$

An outsider must share a chart with another true error or singleton provenance eliminates the false center. This exact prune leaves

$$341{,}664 + 7{,}808 + 96 = \boxed{349{,}568}$$

necessary survivors, and all 349,568 clear under the actual decoder. Hence

$$\boxed{r_{\text{eventual}} = 10.}$$

The monotone true-only guarantee remains sharply seven because the radius-eight echo family still makes false first corrections. Radius eleven remains open.

Passes 5436–5443: bicycle filtration, apartment orbitals, Tanner fusion, and minimum apartment bases

For odd q, Pass5426 identifies the Levi bicycle space as the amalgam

$$\mathrm{Bike} = P_g + L_g, \qquad P_g \cap L_g = \langle J \rangle, \qquad \dim \mathrm{Bike} = 2g - 1 = q(q^2+1) - 1.$$

At $q = 3$, combine this with the characteristic-two filtration from Pass5068: $\dim P_{15} = 15$, $J < L_9 < L_{15}$ with dimensions $1 < 9 < 15$, and $W_{23} = P_{15} + L_9$. Since $P_{15} \cap L_{15} = J$, also $P_{15} \cap L_9 = J$, and therefore the previously separate pieces lock into the exact filtration

$$\boxed{0 < J < P_{15} < W_{23} < \mathrm{Bike}_{29}}$$

with dimensions $0, 1, 15, 23, 29$. Its successive quotient dimensions are

$$\boxed{1,\ 14,\ 8,\ 6},$$

namely P_{15}/J has dimension 14, $W_{23}/P_{15} \cong L_9/J$ has dimension 8, and $\mathrm{Bike}_{29}/W_{23} \cong L_{15}/L_9$ has dimension 6. These are quotient-dimension statements; no new irreducibility assertion is made.

The apartment-overlap fusion from Pass5422 is not itself an association scheme. A direct construction of $PSp(4,3)$ from symplectic transvections gives order 25920, acting transitively on the 1620 apartments with stabilizer H of order 16. The H-orbits on apartments give the exact Schurian orbital coherent configuration. Its rank is

$$\boxed{131},$$

with orbital-size census

$$1^2, \qquad 2^3, \qquad 4^{17}, \qquad 8^{25}, \qquad 16^{84}.$$

There are 25 self-transpose orbitals and 53 directed transpose pairs. The five proper overlap sizes split as follows: overlap 4 refines into three orbitals of sizes $4, 4, 8$; overlap 3 into two size-16 orbitals; overlap 2 into nine orbitals with sizes $4^2, 8^3, 16^4$; overlap 1 into eighteen size-16 orbitals; and the disjoint relation into ninety-eight orbitals with sizes $1, 2^3, 4^{13}, 8^{21}, 16^{60}$. The complete intersection tensor has 159065 nonzero structure constants; its canonical sparse encoding has SHA-256 `868ffd6ea89ab41b95557cdd97b4ffca6198771238a0bb0f8c006974c7885b19`. The resulting 131-dimensional orbital algebra has exact center dimension

$$\boxed{17}$$

and center codimension 114. Thus a five-class Bose–Mesner eigenmatrix is not the correct object here; the exact refinement is noncommutative and rank 131.

The overlap-4 fusion nevertheless has a clean all-q graph theorem. Let $\mathcal{G}_4$ have the apartments of a finite $GQ(q,q)$ as vertices, joining two apartments when their intersection is a four-edge

geodesic. Pass5422 gives regular degree $8(q-1)$. Pass5079 already proves that the apartment/-theta Tanner graph has $T(q)(q-2)$ six-cycles. Combining the two statements yields an edge-regular decomposition: every edge of $\mathcal{G}_4$ lies in exactly

$$\boxed{q-1}$$

triangles, consisting of one theta-check triangle and $q-2$ common-root/Tanner triangles. Hence

$$\#\triangle(\mathcal{G}_4) = T(q)(q-1).$$

At $q=3$ this gives a 16-regular graph on 1620 apartments, two triangles through every edge, 4320 theta triangles, 4320 root/Tanner triangles, and 8640 triangles total. The 131-orbital refinement above shows why this edge-regular graph must not be promoted to a strongly regular graph.

There is also an exact cardinality-optimal sparse apartment basis for every $GQ(q,q)$. Root the Levi graph and choose a BFS geodesic spanning tree. Its diameter is four and its girth is eight. For every cotree edge, the fundamental cycle has length at most eight; since it is nonzero, girth forces its length to be exactly eight. Thus every cotree fundamental cycle is an apartment. The number of cotree edges is the Levi cycle rank

$$E-(V-1) = q^4,$$

so these apartments form a basis of H_1:

$$\boxed{\text{a minimum apartment basis has exactly } q^4 \text{ apartments.}}$$

At $q=3$ this compresses the full 1620-apartment frame to an exact 81-apartment basis.

The same basis exposes the critical group. If F is any integral fundamental cycle matrix, Cauchy–Binet gives

$$\det(F^{\mathsf{T}}F) = \tau(\Gamma),$$

because its nonzero maximal minors are ± 1 and are indexed by complements of spanning trees. For the Levi graph of $GQ(q,q)$, writing

$$f = \frac{q(q+1)^2}{2}, \qquad g = \frac{q(q^2+1)}{2},$$

the Levi Laplacian spectrum gives

$$\boxed{\tau(\Gamma) = (q^2+1)^{f-1}(q+1)^{2g}}.$$

At $q=3$ this is $2^{83}5^{23}$, exactly the tree order already frozen in Pass5031. For the deterministic root-0 BFS basis used in the exact replay, the 81×81 Gram characteristic polynomial factors as

$$\boxed{(x-160)(x-40)^4(x-4)^{12}(x-1)^{28}(x^2-17x+40)^{12}(x^2-8x+10)^6}.$$

Thus that literal basis has smallest Gram eigenvalue 1, largest 160, and singular condition number $\sqrt{160}$, while its Gram determinant again equals $2^{83}5^{23}$.

Finally, the order-16 apartment stabilizer has a sharp fixed-apartment fingerprint. Besides the identity fixing all 1620 apartments, three involutions fix 108 apartments each, four involutions fix 24 each, four order-4 elements fix 12 each, and four order-4 elements fix only two each. Burnside therefore gives

$$1620 + 3(108) + 4(24) + 4(12) + 4(2) = 2096 = 16\cdot 131,$$

independently recovering the 131 stabilizer orbits.

Evidence firewall. Pass5079, not this packet, owns the all-q Tanner-six-cycle theorem. This packet supplies the overlap-4 edge-regular corollary and an independent geometric reconciliation. The five overlap sizes are explicitly not claimed to form an association scheme. No physical threshold, code-distance, strong-regularity, irreducibility, optimal conditioning, or broad priority claim follows from these finite calculations. Remote workflow success is reported only when a completed GitHub Actions run is actually observed.

73.40 The apartment tight frame carries an exact basis-volume budget

Put $r = q^4$ and $N = (q+1)^2(q^2+1)$. For the signed flag–apartment matrix C, Pass 5396 gives $CC^{\mathsf{T}} = NE_{\mathrm{cyc}}$. If Q is any orthonormal basis of the Levi cycle space and $D = Q^{\mathsf{T}}C$, then $DD^{\mathsf{T}} = NI_r$. Cauchy–Binet therefore yields

$$\boxed{\sum_{|S|=r} \det(C_S^{\mathsf{T}} C_S) = N^r,}$$

where dependent r-subsets contribute zero. Thus the full apartment family has an exact coordinate-free squared-volume budget.

Passes 5439 and 5441 give a cardinality-minimal fundamental apartment basis and the Levi tree number

$$\tau(L) = (q^2+1)^{f-1}(q+1)^{2g}, \quad f = \frac{q(q+1)^2}{2}, \quad g = \frac{q(q^2+1)}{2}.$$

Let $\Lambda = Z_1(L;\mathbb{Z})$. For any independent r-apartment set S, its columns generate a finite-index sublattice $\Lambda_S \le \Lambda$, so

$$\boxed{\det(C_S^{\mathsf{T}} C_S) = \tau(L)\,[\Lambda : \Lambda_S]^2.}$$

Consequently the real Cauchy–Binet identity refines to the integral sum-of-squares law

$$\boxed{\sum_{|S|=r} m_S^2 = \frac{N^r}{\tau(L)}, \qquad m_S = [\Lambda : \Lambda_S],}$$

with $m_S = 0$ for dependent sets. At $q = 3$ the right side is $2^{322}5^{58}$.

At $q = 3$, the full 1620-apartment signed frame has redundancy 20 and condition number one on its 81-dimensional image. The deterministic 81-apartment BFS basis of Pass 5443 has Gram minimum/maximum eigenvalues 1 and 160, hence singular condition number $\sqrt{160}$. Its inverse norm is therefore worse than the full-frame Moore–Penrose inverse norm by exactly $\sqrt{160}$. This compares that specific BFS basis with the full frame; no optimal-conditioning claim over all 81-apartment bases is made.

73.41 The two binary footprint kernels live at different stages

For odd prime powers, Pass 5376 gives

$$\ker(F^{\mathsf{T}}) = C_W, \qquad \operatorname{rank}_2 F = g, \qquad C_F = \operatorname{im} F = C_W^{\perp}.$$

Hence F^{T} induces

$$M/C_W \cong \operatorname{im} F^{\mathsf{T}}.$$

Pass 5350 identifies the radical, giving

$$\boxed{0 \to M_0/C_W \to \operatorname{im} F^{\mathsf{T}} \to \langle \mathbf{1} \rangle \to 0,}$$

with dimensions $0 \to (g-1) \to g \to 1 \to 0$. This is the point/transposed stage. By contrast, Passes 5421 and 5377 give the apartment stage

$$\boxed{0 \to D_{\mathrm{ap}} = K_0 \to H_1(L)^* \to C_F \to 0,}$$

with dimensions $0 \to (q^4 - g) \to q^4 \to g \to 0$. Thus the all-odd point-kernel closure does not kill the nonzero apartment residual.

73.42 The $q = 5$ weight-1040 support is forced into an exotic corner

A weight-1040 word of K_0 would have exactly 26 active P-components, each a local even minimum of weight 40. Let (a, b, c) count its internal block pairs in the three Pass 5232 relations R_1, R_2, R_3, whose weight-eight-shell pair codegrees are $25, 5, 0$. The no-singleton shell law gives

$$4a - c \geq 1235.$$

Delsarte positivity in the rank-four block association scheme gives

$$\frac{a}{10} - \frac{39}{5} \geq 0, \quad \frac{2c}{15} - \frac{26}{75} \geq 0, \quad \frac{481}{15} - \frac{a}{10} - \frac{2c}{15} \geq 0.$$

Together with $a + b + c = 325$, only 21 integer pair profiles remain; all satisfy $310 \leq a \leq 316$, so only 9–15 of the 325 block pairs lie outside R_1. Moreover, exhaustive extension of every one of the 156 known 25-block point footprints by every one of its 300 outside blocks gives zero no-singleton survivors. Hence any weight-1040 word, if it exists, has an exotic 26-block support. Nonexistence is not claimed.

73.43 The $q = 3$ radius-eleven decoder frontier

Pass 5430 proves global eventual radius ten. At weight eleven, exact MILPs rule out false-center sectors $V = 1$ and $V = 2$. For $V = 3$, local weights 6 through 11 occur with counts

$$32,\ 256,\ 832,\ 1536,\ 1856,\ 1536.$$

The two-new-direction cap per outsider eliminates all local weights at least 8. Only weight six plus five outsiders and weight seven plus four outsiders remain; exact MILPs exhibit necessary survivors in both branches, and the sampled witnesses self-heal.

For $V = 4$, the raw rooted space has

$$\boxed{10{,}963{,}673{,}616}$$

cases. Requiring every outsider to share a chart with the local core or another outsider leaves exactly

$$\boxed{35{,}218{,}336}$$

necessary cases. A necessary-survivor witness again self-heals, but the remaining census has not been exhaustively decoded. Thus radius eleven remains open.

73.44 A negative-Pell square clock for the unsigned Gram determinant

Pass 5434 implies that for odd q the square class of $\det(BB^{\mathsf{T}})$ is

$$\boxed{\frac{q^2+1}{2}}.$$

Therefore the determinant is a perfect integer square exactly when

$$\boxed{q^2 - 2m^2 = -1.}$$

The first nontrivial Pell q-coordinates are $7, 41, 239, 1393, 8119, \ldots$; only prime-power coordinates are admissible generalized-quadrangle parameters. For even q, the square class is 10 at $q = 2$ and 2 for $q \geq 4$, so the unsigned Gram determinant is never square.

Reducing the negative-Pell equation modulo 16 forces $q \equiv \pm 1 \pmod 8$. Passes 5361 and 5406 independently identify exactly this congruence class as the branch where the two binary logical Weil factors are individually defined over $\mathbb{F}_2$. Hence

$$\boxed{\det(BB^{\mathsf{T}}) \text{ square at odd } q \Longrightarrow q \equiv \pm 1 \pmod 8 \Longrightarrow \text{split } \mathbb{F}_2 \text{ Weil branch.}}$$

The converse fails, e.g. $q = 9$.

73.45 The Reye/tomotope family as a projectivity-graph incidence design

The incidence family isolated in Passes 5488–5495 admits a structural identification which explains its parameters without an integer coincidence. For odd prime q, write

$$X(x) = \begin{pmatrix} x_0 & x_2 \\ -x_3 & x_1 \end{pmatrix}, \qquad Q(x) = x_0x_1 + x_2x_3.$$

Then $\det X(x) = Q(x)$, so the hyperbolic quadric $Q^+(3,q)$ is the projectivized rank-one locus. Writing $X = uv^T$ gives the Segre grid

$$\boxed{Q^+(3,q) \cong \mathbf{P}^1(q) \times \mathbf{P}^1(q)}$$

with $(q+1)^2$ points.

For a nonsingular point $p = (a,b,c,d)$ define

$$T_p = \begin{pmatrix} c & -a \\ -b & -d \end{pmatrix}.$$

If

$$s(u,v) = (u_0v_0, u_1v_1, u_0v_1, -u_1v_0)$$

is the corresponding singular point, direct expansion of the symplectic form B gives

$$\boxed{B(p, s(u,v)) = 0 \iff u \sim T_pv.}$$

Moreover $\det T_p = -Q(p)$. Hence a fixed nonsingular quadratic-value class is one of the two determinant-square cosets of $\mathrm{PGL}_2(q)$, and after translating by one fixed projectivity if necessary the incidence structure is exactly the permutation-graph design of

$$G = \mathrm{PSL}_2(q) \curvearrowright \mathbf{P}^1(q).$$

Its rows are $g \in G$, its columns are grid cells (x, y), and

$$M_{g,(x,y)} = 1 \iff y = g(x).$$

Thus

$$|G| = \frac{q(q^2-1)}{2}, \qquad |\text{columns}| = (q+1)^2,$$

with row weight $q+1$ and column weight $q(q-1)/2$. In particular the $q = 3, 5, 7$ members are precisely

$$12_4\, 16_3, \qquad 60_6\, 36_{10}, \qquad 168_8\, 64_{21}.$$

The first is the Reye configuration/tomotope medial layer already identified in Pass 5490; the new statement is the projectivity-graph mechanism for the whole tested family.

Rook-complement Gram theorem. Let A be the adjacency matrix of the complement of the $(q+1) \times (q+1)$ rook graph. Two distinct cells can lie on one projectivity graph precisely when both coordinates differ; 2-transitivity then leaves a two-point stabilizer of size $(q-1)/2$. Therefore

$$\boxed{M^T M = \frac{q-1}{2}(qI + A).}$$

Since A is the tensor graph $K_{q+1} \times K_{q+1}$ with spectrum

$$q^{2\,1} \oplus 1^{q^2} \oplus (-q)^{2q},$$

one obtains

$$\boxed{\operatorname{spec}(M^T M) = \left(\frac{q(q^2-1)}{2}\right)^1 \oplus \left(\frac{q^2-1}{2}\right)^{q^2} \oplus 0^{2q},}$$

and hence

$$\boxed{\operatorname{rank}_{\mathbf{Q}} M = q^2 + 1.}$$

The executable certificate independently reaches this rank modulo 1000003 for $q = 3, 5, 7, 11, 13$.

Centered tight frame. Every row has mean $1/(q+1)$ and centered squared norm q. Distinct projectivities agree at $t \in \{0, 1, 2\}$ points, so after unit normalization the centered inner products lie in

$$\boxed{\left\{-\frac{1}{q}, 0, \frac{1}{q}\right\}.}$$

Removing the constant eigenline leaves one nonzero Gram eigenvalue, so the $|\mathrm{PSL}_2(q)|$ centered rows form a unit-norm tight frame in $\mathbf{R}^{q^2}$ with frame bound

$$\boxed{\frac{q^2-1}{2q}.}$$

At $q = 3$ only $-1/3$ and 0 occur, giving a two-distance specialization.

The order-576 Reye symmetry becomes explicit. At $q = 3$, $\mathrm{PSL}_2(3) \cong A_4$ on four letters. The Reye incidence is

$$g \sim (x, y) \iff y = g(x), \qquad g \in A_4, \quad (x, y) \in [4]^2.$$

Every pair $(a, b) \in S_4^2$ with equal parity acts by

$$(x, y) \mapsto (ax, by), \qquad g \mapsto bga^{-1},$$

giving $24^2/2 = 288$ automorphisms. Adjoining $(x, y) \leftrightarrow (y, x)$ and $g \leftrightarrow g^{-1}$ doubles this to

$$\boxed{576}$$

with abstract shape

$$\boxed{\{(a, b) \in S_4^2 : \mathrm{sgn}(a) = \mathrm{sgn}(b)\} \rtimes C_2 \cong ((A_4 \times A_4) : C_2) : C_2.}$$

This is the same abstract group shape that Pass 5516 obtained by GAP for the Klein-V_4 Latin-square autoparatopy/13-cover image. This observation explains why the Reye object naturally carries that 576-group; it does *not* identify the underlying acted-on objects.

Characteristic-two firewall. The measured binary ranks are

$$8, 18, 32, 72, 98 \qquad (q = 3, 5, 7, 11, 13),$$

which equal $(q + 1)^2/2$ in every tested case. We record

$$\mathrm{rank}_2\, M \stackrel{?}{=} \frac{(q + 1)^2}{2}$$

as a conjecture, not an all-q theorem. The characteristic-two nonsplitting warning of Passes 5356–5361 applies directly; a proof must analyze the image algebra of the modular projective-line permutation representation rather than reduce the characteristic-zero Gram decomposition.

Evidence boundary. The coordinate incidence identity, rook-complement Gram factorization, and $q = 3$ order-576 subgroup are exact. The committed verifier replays the construction for the five odd primes $3, 5, 7, 11, 13$. The prime-power extension, the binary-rank law beyond these anchors, and any polytope realization for $q > 3$ remain open. No physical claim follows from this finite incidence identification.

73.46 Characteristic-two closure: the projectivity-frame rank is $(q + 1)^2/2$

The binary-rank pattern left explicitly conjectural at the end of Pass 5585 can be closed for every odd prime power q. The important point is that this is a theorem about the projectivity-graph design of Section 73.45; it is *not* the separate $\mathrm{W}(3, q)$ footprint-rank conjecture firewalled in Passes 5358 and 5376.

Let $V = \mathbf{F}_2[\mathbf{P}^1(q)]$ be the natural permutation module for $G = \mathrm{PSL}_2(q)$ and let

$$\mathcal{A} = \mathrm{span}_{\mathbf{F}_2}\{\rho(g) : g \in G\} \subseteq \mathrm{End}_{\mathbf{F}_2}(V).$$

Vectorizing matrices identifies the rows of the Pass 5580 incidence matrix with the permutation matrices of one $\mathrm{PGL}_2(q)/\mathrm{PSL}_2(q)$ coset. Left multiplication by one fixed coset representative is invertible, so

$$\operatorname{rank}_2 M = \dim_{\mathbf{F}_2} \mathcal{A}.$$

The needed modular module structure is classical. Zavarnitsine's Lemma 7 (*Subextensions for a permutation* $\mathrm{PSL}_2(q)$*-module*, 2013), refined in Revin–Zavarnitsine (2021), gives the Loewy shape after scalar extension to $k = \overline{\mathbf{F}}_2$:

$$\boxed{\mathbf{1} \;\big|\; (U_+ \oplus U_-) \;\big|\; \mathbf{1}, \qquad \dim U_+ = \dim U_- = a := \frac{q-1}{2}.}$$

The bottom trivial module is the all-one vector, the unique maximal submodule is the augmentation kernel, and the quotient is again trivial. For $q \equiv \pm 1 \pmod 8$ the two middle constituents are already absolutely irreducible over $\mathbf{F}_2$; for $q \equiv \pm 3 \pmod 8$ the $(q-1)$-dimensional middle constituent splits into $U_+ \oplus U_-$ after extending scalars to $\mathbf{F}_4$ (and hence to k).

Let $J = \operatorname{rad}(\mathcal{A} \otimes k)$. Faithfulness of V for the image algebra and the three simple composition types give

$$\boxed{(\mathcal{A} \otimes k)/J \cong k \oplus M_a(k) \oplus M_a(k),}$$

so

$$\dim((\mathcal{A} \otimes k)/J) = 1 + 2a^2.$$

The Loewy filtration gives an immediate upper bound on the radical. Every element of J kills the one-dimensional socle, maps the $2a$-dimensional middle layer into the socle, and maps the one-dimensional top into the middle layer plus socle. Hence

$$\dim J \le 2a + (2a+1) = 4a + 1.$$

For the reverse inequality, the two middle simples occur in $\operatorname{rad} V/\operatorname{rad}^2 V$. Therefore the two distinct Pierce components of J/J^2 from the trivial top to U_+ and U_- are nonzero and contribute at least $a + a$ dimensions. Transposition preserves the permutation matrix algebra and its radical and supplies the two reverse Pierce components, contributing another $a+a$. Finally $\operatorname{rad}^2 V = \operatorname{soc} V \neq 0$, so $J^2 \neq 0$. Thus

$$\dim J \ge 4a + 1,$$

and equality holds.

Consequently

$$\begin{aligned} \operatorname{rank}_2 M &= \dim \mathcal{A} \\ &= 1 + 2a^2 + 4a + 1 \\ &= 2(a+1)^2 \\ &= \boxed{\frac{(q+1)^2}{2}}. \end{aligned}$$

This proves the all-odd prime-power law. The previously measured anchors

$$q = 3, 5, 7, 11, 13 \quad \longmapsto \quad 8, 18, 32, 72, 98$$

are exact instances rather than evidence for an open formula.

Evidence boundary. The theorem closes only the characteristic-two rank of the $\mathrm{PSL}_2(q)$ projectivity-graph incidence family. It does not prove the independent all-odd $\mathrm{W}(3,q)$ footprint-rank law, and it supplies no $q > 3$ polytope or physical identification. The older Pass 5358 warning remains essential: the proof uses the nonsplit modular Loewy structure itself, not an invalid reduction of the characteristic-zero decomposition.

73.47 Projectivity-frame closure: automorphisms, extension fields, codes, and kinematic firewalls

The projectivity-graph design of Passes 5588–5594 admits several further structural closures. Write $X = \mathbf{P}^1(q)$ and $G = \mathrm{PSL}_2(q)$, with rows $g \in G$, columns $(x, y) \in X^2$, and incidence $y = g(x)$.

Pass 5595: full incidence automorphism mechanism. The number of common row-neighbours of two distinct columns vanishes exactly when the two grid cells share one coordinate. Thus the incidence structure recovers the square rook graph on X^2. Every incidence automorphism therefore acts on columns through $(S_{q+1} \times S_{q+1}) \rtimes C_2$. Without swapping the two rulings, $(x, y) \mapsto (ax, by)$ preserves the graph-row set exactly when $bGa^{-1} = G$. Hence $ba^{-1} \in G$ and $a \in N_{S_{q+1}}(G)$, and conversely these conditions suffice. Using the standard natural-action normalizer

$$N_{S_{q+1}}(\mathrm{PSL}_2(q)) = \mathrm{P\Gamma L}_2(q),$$

for $q = p^f$ odd gives

$$\boxed{|\mathrm{Aut}(D_q)| = 4f\,|\mathrm{PSL}_2(q)|^2.}$$

The executable verifier enumerates the complete natural action at $q = 3, 5$, giving 576 and 14,400. Thus the Reye 576 is the first member of an all-q normalizer law, rather than an isolated order coincidence.

Pass 5596: the Reye and Klein-V_4 Latin degree-12 actions are permutation-isomorphic. Write $A_4 = V_4 \rtimes \langle r \rangle$ with $r = (0\ 2\ 3\ 1)$. The Reye rows are vr^k. The Klein-V_4 Latin autoparatopy action is the affine symmetry of $x + y + z = 0$ on three labelled copies of $V_4 \cong \mathbf{F}_2^2$. The explicit bijection

$$\boxed{\Phi(vr^k) = \big(k, r^k(v(0))\big)}$$

conjugates the entire 576-element Reye row action onto the entire 576-element Latin 12-symbol action. Their non-diagonal orbital sizes are 36 and 96, and the 36-orbital is exactly $3K_4$. The existing 13-cover certificate records an abstractly isomorphic image with orbits $1 + 12$ but does not retain explicit S_{13} generators, so this pass does not silently claim that final action-level intertwiner.

Pass 5597: genuine extension-field replay. Explicit quadratic-field arithmetic over $\mathbf{F}_9 = \mathbf{F}_3[w]/(w^2 - 2)$ and $\mathbf{F}_{25} = \mathbf{F}_5[w]/(w^2 - 2)$ reproduces the complete Segre grid, one nonsingular determinant class, and every symplectic/projectivity incidence. The non-prime anchors are

q	$\lvert\mathrm{PSL}_2(q)\rvert$	$(q+1)^2$	$\mathrm{rank}_2\, M$
9	360	100	50
25	7800	676	338

so the all-prime-power binary theorem now has direct extension-field replay.

Pass 5598: the frame code projects from the footprint kernel. Let C_W be the binary W-line incidence code. Pass 5376 proved $C_W = \ker(F^T)$ for the footprint matrix F. For a nonsingular-class point p, let $N(p)$ be its full symplectic-neighbour indicator. Modulo two the sum of the $q+1$ W-lines through p cancels p and leaves its neighbours once, so $N(p) \in C_W$. Restricting coordinates to the singular Segre sheet S gives precisely the projectivity row M_p. Therefore

$$\boxed{\operatorname{row}(M) = \pi_S \operatorname{span}\{N(p) : p \in C_+\} \subseteq \pi_S(C_W) = \pi_S \ker(F^T).}$$

This is a bridge to the footprint *kernel*, not an identification with the footprint image. At $q = 3, 5, 7$ the restricted line-code ranks are $15, 34, 61$ while the projectivity-code ranks are $8, 18, 32$, so equality with the full restricted line code is false.

Pass 5599: fixed-point fusion and the exceptional $q = 3$ collapse. For $g, h \in G$, classify $g^{-1}h$ by $t = 0, 1, 2$ fixed points on X. The three observed valencies are

$$\boxed{k_0 = \frac{q(q-1)^2}{4}}, \qquad \boxed{k_1 = q^2 - 1}, \qquad \boxed{k_2 = \frac{q(q+1)(q-3)}{4}}.$$

Full intersection-number constancy is verified at $q = 3, 5, 7, 9$, and one uniform set of polynomial intersection matrices is replayed at $q = 11, 13, 25$. We keep the all-odd fusion theorem itself open until a symbolic counting or character proof replaces finite interpolation. At $q = 3$, however, $k_2 = 0$ exactly and the fusion collapses to

$$\boxed{R_0 = 3K_4, \qquad R_1 = K_{4,4,4}.}$$

The three K_4 blocks are the three cosets of $V_4 \triangleleft A_4$, exactly the 3×4 block system exposed by the Reye–Latin intertwiner.

Pass 5600: a finite null-coordinate kinematic primitive, not a spacetime derivation. The Segre sheet $Q^+(3, q) = \mathbf{P}^1(q) \times \mathbf{P}^1(q)$ has two canonical rulings. Every projectivity graph $y = g(x)$ meets every member of each ruling exactly once, so it is a perfect matching/transversal between the two coordinate families. Two such transversals meet in $0, 1, 2$ events. This supports a useful finite two-null-coordinate kinematic picture for the Holonet. It does *not* derive a Lorentz metric, causal order, continuum limit, $3+1$ dimensions, a mass shell, or the physical speed of light.

Pass 5601: determinant chirality gives an exact isodual binary code. Let C_+ be the binary span of vectorized permutation matrices from $\mathrm{PSL}_2(q)$ and C_- the span of the opposite determinant coset in $\mathrm{PGL}_2(q)$. A cross dot product is the number of fixed points of a relative nonsquare-determinant projectivity modulo two. Such an element cannot be one-fixed-point/unipotent, since a repeated eigenvalue has square determinant class; it has 0 or 2 fixed points. Hence $C_- \subseteq C_+^\perp$. The binary rank theorem gives both dimensions $(q+1)^2/2$, because multiplying by a fixed opposite-coset projectivity only permutes grid coordinates. Therefore

$$\boxed{C_- = C_+^\perp,} \qquad \boxed{C_+ \text{ is isodual } [(q+1)^2, (q+1)^2/2].}$$

At $q = 3$ its measured weight enumerator is $1 + 12z^4 + 64z^6 + 102z^8 + 64z^{10} + 12z^{12} + z^{16}$; at $q = 5$ the measured minimum distance is 6. No all-q minimum-distance claim is made here.

Pass 5602: spectral-action firewall. After subtracting the constant row mean, the projectivity frame has only one nonzero frame eigenvalue:

$$\boxed{\operatorname{spec}(M_c^T M_c) = \left(\frac{q^2-1}{2}\right)^{q^2} \oplus 0^*.}$$

Thus the nonzero spectrum is perfectly flat. The associated heat trace has only one nonzero exponential scale and cannot furnish a Weyl-law spectral ladder for a local continuum dimension. The frame Gram is therefore a projector/tight-frame observable, *not* a credible standalone spacetime Laplacian. Any physical dynamics must live in a richer operator (for example the Hodge, Hashimoto, transport, or holonomy operators already present in the repository) and must pass a separate scaling test.

Evidence boundary. These passes establish or replay finite group, incidence, code, and frame statements. The three Theory-of-Everything probes are intentionally firewalled: one supplies a candidate finite kinematic primitive, one an exact information duality, and one rules out a tempting dynamics interpretation. No gravity, Standard-Model, cosmological, or laboratory claim follows from this packet by itself.

Pass 5596 addendum: the same degree-12 action lives on short F_4 root pairs. An independent root-system verifier builds all 48 roots of F_4, generates $W(F_4)$ of order 1152 from four simple reflections, and lets it act on the 12 antipodal pairs of its 24 short roots. The central antipodal involution is the kernel, so the image has order 576. Its orbital sizes are

$$\boxed{12, 36, 96},$$

and the 36-orbital is again $3K_4$. A block-respecting search finds an explicit conjugating permutation in S_{12} from this short-root-pair action to the independently constructed Klein-V_4 Latin autoparatopy action. Consequently

$$\boxed{W(F_4)/\{\pm 1\} \curvearrowright \{12 \text{ antipodal short-root pairs}\} \cong \mathrm{AutPar}(V_4) \curvearrowright 12 \cong \mathrm{Aut}(\mathrm{Reye}) \curvearrowright 12.}$$

This is an action-level bridge, not an order match. Pass 5468 already identifies the selected 13-cover's setwise stabilizer with $W(F_4)$ and its 13-point image with $W(F_4)/\{\pm 1\}$; the separate GAP replay in this packet tests whether the cover's particular moving 12-orbit is conjugate to this same short-root/Latin/Reye action.

73.48 Projectivity fusion, exact distance, and the phase-sensitive dynamical frontier

Pass 5603: the fixed-point fusion is an all-odd Bose–Mesner algebra. For odd prime powers $q > 3$, fuse pairs $g, h \in \mathrm{PSL}_2(q)$ according to the number $0, 1, 2$ of fixed points of $g^{-1}h$ on $\mathbf{P}^1(q)$. With

$$k_0 = \frac{q(q-1)^2}{4}, \qquad k_1 = q^2 - 1, \qquad k_2 = \frac{q(q+1)(q-3)}{4},$$

the first eigenmatrix and multiplicities are

$$\boxed{P = \begin{pmatrix} 1 & k_0 & k_1 & k_2 \\ 1 & 0 & q-1 & -q \\ 1 & -(q-1)^2/4 & 0 & (q-3)(q+1)/4 \\ 1 & q & -(q+1) & 0 \end{pmatrix},}$$

$$\boxed{m = \left(1, \frac{(q-3)(q+1)^2}{4}, q^2, \frac{(q-1)^3}{4}\right).}$$

The symbolic certificate verifies $P^{\mathsf{T}} \operatorname{diag}(m) P = |\mathrm{PSL}_2(q)| \operatorname{diag}(1, k_0, k_1, k_2)$ and reconstructs all Pass 5599 intersection polynomials from the standard character formula for p_{ij}^k. At $q = 3$ both

$$\boxed{k_2 = 0, \qquad m_1 = 0,}$$

so the exceptional Reye/Latin member is an actual degeneration of the generic Bose–Mesner algebra: one relation and one primitive idempotent disappear. The character-table background is the standard projective-line treatment in Long–Plaza–Sin–Xiang, arXiv:1608.07304.

Pass 5604: exact all-odd minimum distance. Let C_+ and C_- be the square- and nonsquare-determinant binary projectivity spans from Pass 5601, so $C_- = C_+^{\perp}$. Through a fixed grid cell pass $r = q(q-1)/2$ opposite-coset projectivity graphs, while a compatible pair lies on $\lambda = (q-1)/2$ of them. If a nonzero support S of size $s \le q$ contained a cell c, then at least

$$r - (s-1)\lambda = \frac{q-1}{2}(q - s + 1) > 0$$

dual generators would meet S exactly once, contradicting orthogonality. A generator has weight $q+1$, hence

$$\boxed{d(C_+) = d(C_-) = q + 1}$$

for every odd prime power q, with parameters

$$\boxed{[(q+1)^2, (q+1)^2/2, q+1]_2.}$$

Independent exact MILPs give $d = 8$ at $q = 7$ and $d = 10$ at $q = 9$.

Pass 5605: maximally symmetric Hodge and Hashimoto scaling is atomic. The all-q Levi flag Hodge spectrum is

$$0^{q^4}, \quad (q+1-\sqrt{2q})^{q(q+1)^2/2}, \quad (q+1)^{q(q^2+1)}, \quad (q+1+\sqrt{2q})^{q(q+1)^2/2}, \quad (2q+2)^1.$$

The full normalized spectral measure tends δ_0; after deleting the cycle kernel and scaling by $q+1$, the nonzero measure tends δ_1. Likewise, for every k-regular graph the nonbacktracking matrix is locally permutation-equivalent to $J_k - I_k$, so its singular values are only $k-1$ and 1. The $W(3,q)$ Ihara–Bass roots also have a finite atomic normalized limit. Thus these maximally symmetric families do not supply a Weyl-law continuum spectrum without further phase, refinement, defects, or symmetry breaking.

Pass 5606: the selected 13-cover object map has passed its gate. The fail-closed GAP gate rebuilds the exact Pass 5417 325-vertex substrate and selected 13-cover, restricts its $1 + 12$ action to the moving twelve points, and asks for an explicit conjugator to the independently constructed Klein-V_4 Latin S_{12} action. It has now returned true: the action is $T_{12,165}$ and the one-based conjugator is

$$[1, 9, 4, 8, 12, 7, 10, 2, 5, 3, 6, 11].$$

A companion script has composed that witness with the already proved F_4 short-root-pair–Latin conjugator and emitted the twelve-row object map. Passes 5667–5674 subsequently reconstruct the Reye configuration intrinsically from the zero-containment triples of the same $q = 5$ multidesign.

Pass 5607: full projective symmetry forbids a dispersive Segre wave operator. On $X = \mathbf{P}^1(q) \times \mathbf{P}^1(q)$, 2-transitivity gives $\mathrm{End}_{\mathrm{PSL}_2(q)}\,\mathbb{R}[\mathbf{P}^1(q)] = \mathrm{span}\{I, J\}$, hence the product commutant is four-dimensional. For $n = q + 1$ the canonical indefinite ruling operator

$$\boxed{\Box_q = (nI - J) \otimes I - I \otimes (nI - J)}$$

has spectrum

$$\boxed{0^{q^2+1} \oplus (+n)^q \oplus (-n)^q.}$$

Thus exact independent projective symmetry is too restrictive for a dispersive continuum d'Alembertian; additional phase/holonomy, directed transport, chart order, or symmetry breaking is mathematically necessary.

Pass 5608: the older `s12` Golay twelve is not the Reye twelve. The old ternary-Golay projectivization has weight split $132 + 220 + 12$. Transporting the natural ATLAS M_{12} generators into the repo Golay coordinates, including the required monomial sign lifts, shows that the twelve projective weight-12 lines carry the natural degree-12 Mathieu action:

$$\boxed{|M_{12}| = 95040, \qquad \text{orbitals } 12, 132.}$$

This is not the rank-3 order-576 Reye/Latin/F_4 action with orbitals $12, 36, 96$. The distinction is structural.

Pass 5609: the old `s12` Heisenberg phase breaks the flat event spectrum. For the $q = 3$ Segre carrier, let two events be adjacent when both ruling coordinates differ. The untwisted adjacency has only $9^1 \oplus 1^9 \oplus (-3)^6$. Weight an allowed edge $s \to t$ by $\omega^{B(s,t)}$, where $\omega^3 = 1$ and

$$B(x, y) = x_0y_1 - x_1y_0 + x_2y_3 - x_3y_2 \pmod 3.$$

The matrix is Hermitian. Exact arithmetic in $\mathbb{Z}[\omega]$ gives

$$\chi(x) = (x+2)^2\big(x^{14}-4x^{13}-60x^{12}+244x^{11}+1292x^{10}-5517x^9-12212x^8+58256x^7+46617x^6-296670x^5-16992x^4+66$$

It has 15 distinct real eigenvalues numerically, and 60 of the 96 event triangles carry nonzero $\mathbb{Z}_3$ Wilson flux. The phase is therefore not gauge-trivial: it supplies genuine holonomy and removes nearly all of the untwisted spectral degeneracy.

Pass 5610: explicit but noncanonical embedding into the old `s12` phase space. The old $728/2 = 364$ Golay/Klein calculation is an exact cardinality statement, but it does not by itself construct a canonical Pluecker isometry or select a canonical 40-point $W(3, 3)$ slice. One compatible phase bridge can be made explicit. Embed $\mathbb{F}_3^4$ into the old three-qutrit $\mathbb{F}_3^6 = (p_1, p_2, p_3, q_1, q_2, q_3)$ phase space by

$$\boxed{E(x_0, x_1, x_2, x_3) = (x_0, x_2, 0, -x_1, -x_3, 0).}$$

For the old convention $\langle (p, q), (p', q') \rangle = q \cdot p' - p \cdot q'$, all 6561 ordered pairs satisfy

$$\boxed{\langle E(x), E(y) \rangle = B(x, y).}$$

Hence the Pass 5609 magnetic phase is literally the restriction of the old `s12` Weyl–Heisenberg cocycle. The embedding is, however, a chosen gauge/subspace; a physical uniqueness principle remains open.

Physical boundary. The packet closes finite-group, coding, and spectral statements and identifies a concrete phase mechanism that defeats the simplest spectral-flatness no-go. It does not yet derive a Lorentzian continuum, gravity, Standard-Model parameters, a speed of light, or laboratory dynamics. The next dynamical test is whether a phase-twisted transport tower has a controlled multiscale heat-kernel/dispersion limit and whether the required phase embedding can be selected rather than chosen.

73.49 Heisenberg magnetic bulk, intrinsic vector lift, and finite gauge dynamics

The projectivity-frame programme now admits a sharper separation between finite kinematics, phase data, and candidate dynamics. On the affine bulk $V = \mathbb{F}_q^2$, define

$$A_q((x,y),(u,v)) = \mathbf{1}_{x\neq u,\, y\neq v}\, \chi(xv - uy),$$

where χ is a nontrivial additive character. Writing K for the full symplectic Fourier kernel and R, C for the same-coordinate kernels gives

$$A = K - R - C + I,$$

with

$$K^2 = q^2 I, \qquad R^2 = qR, \qquad C^2 = qC,$$
$$KR = RK = qR, \qquad KC = CK = qC, \qquad RCR = qR, \qquad CRC = qC.$$

Hence the exact affine magnetic spectrum is

$$\boxed{-(q-1)^{q(q-1)/2} \oplus (q+1)^{q(q-3)/2} \oplus (1-\sqrt{q})^q \oplus (1+\sqrt{q})^q.}$$

After division by q, its empirical spectral measure converges to

$$\boxed{\tfrac{1}{2}\delta_{-1} + \tfrac{1}{2}\delta_{+1}.}$$

Thus the Heisenberg phase removes substantial finite degeneracy but, at maximal all-q regularity, still does not generate a Weyl-law continuum.

The minimum-word theorem of the determinant-isodual code also sharpens. If S is a weight-$(q+1)$ word, parity against the opposite determinant coset and the counts

$$a = \frac{q(q-1)}{2}, \qquad b = \frac{q-1}{2}$$

of opposite projectivities through one cell and through two compatible cells force equality in $\binom{m}{2} \geq m/2$ for every even intersection size m. Consequently S has one cell in every row and column, and every opposite projectivity meets it in 0 or 2 cells. Thus minimum words are permutation graphs preserving the two $\mathrm{PSL}_2(q)$ colours of ordered triples. The standard projective switching automorphism group is $\mathrm{P\Sigma}L_2(q)$, so field automorphisms occur as genuine minimum histories over extension fields. Exhaustive prime-field checks give $12, 60, 168$ minimum histories at $q = 3, 5, 7$, while at $q = 9$ the Frobenius map $x \mapsto x^3$ is a minimum word although it is not a projectivity.

A correction is required for the previous sixteen-event magnetic operator. The spectrum computed there is exact for the chosen normalized projective representatives, but the phase $\omega^{B(s,t)}$ is not projectively intrinsic: changing one representative $s \mapsto -s$ changes $\operatorname{tr} A^4$ from 2256 to 2400. This is structural rather than a numerical defect. The central element $-I \in \mathrm{Sp}(4,3)$ fixes every

projective point but exchanges its two nonzero vector lifts, so no $\mathrm{Sp}(4,3)$-equivariant section of projectivization exists.

The intrinsic $q=3$ replacement is the vector lift of the 16 Segre events to all 32 vectors $\pm v$, carrying the alternating Heisenberg cocycle

$$\psi(v,w)=\tfrac{1}{2}B(v,w)=2B(v,w)\pmod 3.$$

Its Hermitian magnetic spectrum is

$$\boxed{-6^6\oplus(-3)^7\oplus(-1)^3\oplus 2^6\oplus 3^5\oplus 6^4\oplus 9^1.}$$

The projective-to-vector fiber has $q-1$ nonzero lifts, so it is literally a two-sheeted sign cover precisely at $q=3$ among odd q. This supplies a spin/frame-like structural selector, not yet a derivation of physical spin statistics.

This selector is independent of the fixed-point Bose–Mesner degeneration

$$k_2=\frac{q(q+1)(q-3)}{4},\qquad m_1=\frac{(q-3)(q+1)^2}{4},$$

where both a relation and a primitive idempotent disappear at $q=3$. The repo's existing mixing dictionary also has defect

$$\sin^2\theta_{23}-\sin^2\theta_W-\sin^2\theta_{12}=\frac{q(q-3)}{q^2+q+1},$$

but that third statement remains explicitly model-dependent. The older all-q Ollivier curvature extrapolation is not used as a theorem here; only its exhaustive $q=3$ value is certified in the older script.

The qutrit/E_6 connection gives a concrete finite gauge sector. The previously derived $AG(2,3)$ connection satisfies

$$F(d_1,d_2)=-\det(d_1,d_2)\pmod 3,$$

so magnetic translations obey the qutrit Heisenberg relation $ZX=\omega XZ$. The minimal Harper operator

$$H_{\mathrm{H}}=X+X^\dagger+Z+Z^\dagger$$

has exact spectrum

$$\boxed{-2,\ 1-\sqrt{3},\ 1+\sqrt{3}.}$$

With the declared finite Wilson normalization $\sum_p(1-\Re\omega^{F_p})$, the 54 point/direction-class plaquettes give 81; this normalization-dependent number is not a physical coupling prediction.

Finally, couple the intrinsic magnetic operator H_{mag} to the existing causal Clifford Dirac walk by

$$H(p)=\sum_{j=1}^{3}p_j\alpha_j\otimes I+\beta\otimes(m_0I+gH_{\mathrm{mag}}).$$

Clifford anticommutation yields the exact identity

$$\boxed{H(p)^2=|p|^2I+I\otimes(m_0I+gH_{\mathrm{mag}})^2,}$$

and therefore

$$\boxed{E_{h,\pm}(p)=\pm\sqrt{|p|^2+(m_0+gh)^2}.}$$

This is an exact relativistic-form dispersion in lattice units. The parameters m_0, g, physical c, particle assignments, and curved-spacetime dynamics remain open.

A useful matter-sector falsifier also emerges. Every allowed E_6 cubic lift has $(t_0, t_1, t_2) = (k, k+\lambda, k+2\lambda)$ and hence total $\mathbb{Z}_3$ charge zero, but each forbidden firewall fiber $(0, 1, 2)$ is neutral as well. Thus simple $\mathbb{Z}_3$ charge conservation cannot explain the 36/9 cubic selection. The selector must involve richer incidence, holonomy, L_∞, CE2/metaplectic, or chirality data.

Cover/F_4 boundary. The selected 13-cover still has exact stabilizer data $1152 \to 576$ with kernel 2 and orbit split $1 + 12$. The direct GAP program now requests an explicit moving-12 conjugator and the committed consumer will compose it with the frozen Latin–F_4 short-root-pair map. No cover-to-root object dictionary is asserted until that queued action-level witness is emitted.

Evidence boundary. The finite algebra, code, spectrum, gauge-curvature, and Dirac identities above are kept separate from physical semantics. They do not yet derive the Standard Model spectrum, physical masses, the speed of light, a gauge coupling, gravity, or a continuum spacetime.

73.50 Deck parity, gauge transversality, magnetic composition, and causal boundaries

The intrinsic $q = 3$ vector lift admits an exact deck decomposition

$$\mathcal{H}_{32} = \mathcal{H}_+ \oplus \mathcal{H}_-, \qquad \dim \mathcal{H}_+ = \dim \mathcal{H}_- = 16,$$

with

$$\operatorname{spec} H_- = -6^4 \oplus -3^4 \oplus 3^4 \oplus 6^4.$$

This signed 16-space is not identified with a D_5 half-spin module. Indeed, the standard two-qutrit Weil realization sends the central symplectic $-I$ to parity with spectrum $+1^5 \oplus (-1)^4$, not scalar -1, while the previously proved outer-controller no-go continues to exchange the two D_5 chiralities.

The E_6 firewall has an exact gauge-invariant bundle interpretation. The thirty-six allowed cubic triads are horizontal/covariantly affine lifts of the twelve lines of $AG(2, 3)$, three lifts per line, whereas the nine forbidden cubics are precisely the complete vertical $\mathbb{Z}_3$ fibers over the nine base points. Hence projection/transversality, not total $\mathbb{Z}_3$ charge, separates the $36 + 9$ partition.

For the deck-odd cell,

$$\phi(t) = \frac{1}{2}(\cos 3t + \cos 6t), \qquad \sigma^2 = \frac{45}{2}, \qquad \gamma_2 = -\frac{41}{25}.$$

Consequently the normalized N-cell tensor-sum converges in empirical spectral distribution to a standard Gaussian and has excess kurtosis $-41/(25N)$. This is a genuine continuous many-body spectral limit, but not a spacetime Weyl law.

Complex conjugation obeys $KH_-K^{-1} = -H_-$. If the internal mass operator $M = m_0 I + gH_-$ is required to preserve this particle-hole-type symmetry, then $m_0 = 0$ and the two absolute internal levels are $3|g|$ and $6|g|$, giving the conditional scale-free ratio

$$\frac{m_{\text{heavy}}}{m_{\text{light}}} = 2.$$

The overall dimensionful scale $|g|$ remains undetermined.

The split-step Dirac walk has exact one-macrostep support $|\Delta x_j| \le \ell$, hence $|\Delta x|_2 \le \sqrt{3}\ell$, and its long-wave generator gives $E^2 = p^2 + m^2$ with $|v_g| \le 1$ in natural units. The physical

speed conversion remains $c \sim \ell/\tau$; W33 node counts do not determine its SI value. Finite-step quasienergies retain lattice artifacts.

Finally, the finite spectral-asymmetry diagram of $rI + H_{\mathrm{mag}}$ has walls

$$r \in \{-9, -6, -3, -2, 1, 3, 6\}$$

and a balanced chamber $-2 < r < 1$; the deck-odd block has balanced chamber $-3 < r < 3$. These replace, rather than revive, the repository's quarantined legacy anomaly-polynomial claims.

The selected 13-cover remains a $q = 5$ branch. Its $1 + 12$ action gives one invariant line in the centered simplex module, $12e_{\mathrm{fixed}} - \sum e_{\mathrm{moving}}$, but the balanced 2-design makes the fixed point locally indistinguishable. No $q = 3$ vacuum identification is claimed, and the explicit moving-$12 \leftrightarrow F_4$ object dictionary remains fail-closed until the direct GAP conjugator is replayed.

Evidence boundary. These are finite algebraic, spectral, bundle, cover, and quantum-walk results. They do not prove physical spin-statistics, a Standard-Model mass assignment, an SI value of c, continuum anomaly cancellation, a physical vacuum, or a spacetime Weyl law.

73.51 Carrier-spinorial symmetry, gauge-action obstruction, and finite sheet dressing

The intrinsic deck-odd 16 is a genuine central-sign representation, but only of the vector stabilizer of the Segre carrier. Direct generation gives

$$|\mathrm{PSp}(4,3)| = 25920, \qquad |G^{\mathrm{proj}}_{\mathrm{Segre}}| = 48, \qquad |\mathrm{Sp}(4,3)| = 51840, \qquad |\widetilde{G}_{\mathrm{Segre}}| = 96,$$

and the central $-I \in \mathrm{Sp}(4,3)$ acts on the signed space as $-I_{16}$. Consequently this representation cannot descend to an ordinary $\mathrm{PSp}(4,3)$ module and is not either of the previously constructed D_5 half-spin 16-modules. Under $\widetilde{G}_{\mathrm{Segre}}$ it decomposes over $\mathbb{C}$ as

$$V_{16} \cong 2A \oplus 2\overline{A}, \qquad \dim A = 4,$$

with magnetic eigenspace pattern

$$-6 : A, \qquad -3 : \overline{A}, \qquad 3 : A, \qquad 6 : \overline{A}.$$

The equivariant complex commutant has dimension eight. Its real symmetric and skew parts both have dimension four, so the K-odd Hermitian Hamiltonians compatible with the full carrier stabilizer form a four-real-dimensional space. An explicit equivariant particle-hole-compatible perturbation moves the unperturbed $6/3 = 2$ level ratio. Thus that ratio is an exact feature of the chosen magnetic operator, not a symmetry-protected mass prediction.

The E_6 bundle selector also sharpens negatively. Local $\mathbb{Z}_3$ gauge covariance preserves both the horizontal thirty-six-term cubic sum and the nine vertical full-fiber cubics, hence gauge symmetry permits

$$S_{\mathrm{cubic}} = g_H \sum_{T \in H_{36}} C_T + g_V \sum_{b=1}^{9} V_b.$$

Therefore gauge invariance and total $\mathbb{Z}_3$ neutrality do not force $g_V = 0$. Suppression of the vertical nine requires an additional horizontality/locality, L_∞/Jacobi, representation-theoretic, or dynamical principle. Moreover the affine base has nine sites and complete one-skeleton K_9 with thirty-six links; its incidence rank is eight and cycle-space dimension twenty-eight. The bad nine naturally

occupy site/C^0 degree rather than link/C^1 connection degree, obstructing their identification with propagating gauge bosons by count alone.

The simplest cover-based continuum iteration fails exactly. The connected 270-vertex Pass4719 carrier is already the bipartite double cover $G \times K_2$, and

$$(G \times K_2) \times K_2 = G \times (K_2 \times K_2) = 2(G \times K_2).$$

Hence the next naive C_2 lift has two connected components and duplicates the existing spectral support rather than generating a new scale. A connected refinement tower must use a new nontrivial voltage/cohomology class at each level.

The signed block has the Majorana/BdG algebraic form $H = iS$ with S real skew and $KHK^{-1} = -H$, $K^2 = 1$. Searching for a second carrier-equivariant antiunitary $T = UK$ commuting with H gives the simultaneous linear equations $UR_g = R_g U$ and $UH + HU = 0$, whose solution space has dimension zero. Thus the carrier supplies no equivariant Kramers $T^2 = -1$ symmetry; in tenfold-way vocabulary its finite algebraic pattern is class-D-like rather than DIII-like. This does not constitute a relativistic spin-statistics theorem.

For the $q = 5$ selected cover, every $1 + 12$ permutation action satisfies the module identity

$$\text{centered}(1 \oplus \text{Perm}_{12}) \cong \text{Perm}_{12}\,.$$

Under such an intertwiner the invariant direction $12e_{\text{fixed}} - \sum e_i$ maps to the constant vector $\sum e_i$ on the moving orbit. Therefore, even if the still-pending direct moving-12 GAP conjugator closes the Latin/F_4 action gate, the $q = 5$ distinguished direction can map only to a collective $q = 3$ orbit-average singlet, not to a distinguished $q = 3$ point; the two isomorphic $q = 3$ twelve-orbits also leave the target nonunique.

Finally, ordering the intrinsic vector lift by its two sheets gives

$$H_{32} = \begin{pmatrix} A & B \\ B & A \end{pmatrix}, \qquad H_+ = A + B, \qquad H_- = A - B.$$

Up to the $\omega \leftrightarrow \omega^2$ convention, A is precisely the old section-dependent sixteen-state magnetic operator. It therefore has a precise new role as a bare one-sheet block rather than an intrinsic projective observable. Eliminating the opposite sheet gives the exact Feshbach operator

$$\boxed{H_{\text{eff}}(E) = A + B(E - A)^{-1}B}.$$

Since $[A, B] \neq 0$, the self-energy is not a scalar renormalization of A and has poles at its fifteen distinct one-sheet energies. This is an exact finite energy-dependent dressing/decimation flow, not yet a Wilsonian spacetime RG.

Evidence boundary. These statements are finite group-action, representation, bundle-gauge, graph-cover, cochain, BdG-algebra, and resolvent results. They do not prove physical spin-statistics, a Standard-Model mass prediction, physical gauge bosons, a continuum Weyl law, a Wilsonian fixed point, or a $q = 5$ physical vacuum identification.

73.52 The q=5 zero shell reconstructs Reye and opens the natural seven-side to S_{12}

The fail-closed Pass 5606 action gate has now executed. The setwise stabilizer of the selected thirteen-vertex cover in the exact $q = 5$ substrate has orbit split $1 + 12$; on the moving twelve its

image has order 576, point stabilizer $C_2 \times S_4$, subdegrees $1, 3, 8$, and

$$\text{TransitiveIdentification}(G) = 165.$$

It is explicitly conjugate to the independent Klein-V_4 Latin action by the one-based permutation

$$\boxed{[1, 9, 4, 8, 12, 7, 10, 2, 5, 3, 6, 11]}.$$

Composing with the already certified Latin–F_4 map gives a literal table from the twelve moving cover vertices to the twelve antipodal short-root pairs of F_4. This executes the old gate; it does not reassign its ownership.

The stronger new structure is internal to the $q = 5$ design. For each of the 312 vertices outside the cover, record its six neighbors in the cover. With multiplicity these rows form a 2-$(13, 6, 60)$ design with point replication 144. Its triple-containment spectrum is

$$\boxed{0^{16} \oplus 16^{30} \oplus 24^{240}}.$$

The sixteen zero-containment triples avoid the unique fixed cover vertex and, on the moving twelve, form a $12_4, 16_3$ configuration. Their Levi graph has 48 edges and automorphism group of order 576; its two faithful actions are

$$\boxed{T_{12,165} \quad \text{on points}, \qquad T_{16,1034} \quad \text{on lines.}}$$

Thus the Reye configuration is reconstructed by an intrinsic third-order predicate of the $q = 5$ multidesign, rather than imported through an order match.

The two carriers also detect different orientation characters. The twelve-point action is not contained in A_{12}, and its sign kernel is

$$\boxed{\text{SmallGroup}(288, 1025) \cong 2^4 : (C_3 \times S_3).}$$

The explicit cover-to-Latin conjugator transports this kernel to the even-Latin group which Pass 5300 already identifies with the Hoffman stabilizer quotient. By contrast, the entire sixteen-line action lies in A_{16}. Orientation is therefore a carrier-dependent character, not an invariant of the abstract order-576 group alone.

The former "order 4032" seven-side frontier sharpens drastically on the natural twelve-symbol carrier. Embed the natural degree-seven action of $PSL(2, 7)$ in S_{12} with five fixed points. Exhaustive GAP enumeration of all 23,760 conjugate embeddings gives

$$\boxed{\langle T_{12,165}, PSL(2, 7)^g \rangle = S_{12} \quad \text{for every such } g.}$$

For comparison, every placement with $T_{12,161}$ or $T_{12,163}$ closes only to A_{12}. The distinction is exactly parity: classes 161 and 163 are even, while class 165 is not. This is scoped to the natural $7 + 1^5$ permutation representation and does not classify arbitrary common overgroups.

Finally, the 312 rows have only 132 distinct supports:

$$312 = 120 \cdot 2 + 12 \cdot 6.$$

The twelve multiplicity-six supports carry a second $T_{12,165}$ action. Their stabilizers and the moving-point stabilizers both have type SmallGroup$(48, 48)$ but are not conjugate in the source group. Hence the two twelve-carriers are permutation-isomorphic only after an outer twist; there is no

source-equivariant or canonical point–support bijection. The twist lifts to a source automorphism whose displayed representative has order eight and square inner. Exactly 48 inner re-gaugings yield genuine outer involutions; the frozen order-two witness exchanges the two nonconjugate stabilizer classes.

This outer carrier involution is not the point-side sign twist. Write π_P, π_H, π_L for the point, heavy-support, and line permutation characters. Exact enumeration over all 576 source elements gives

$$\langle \pi_P, \pi_P \rangle = \langle \pi_H, \pi_H \rangle = \langle \pi_L, \pi_L \rangle = 3, \qquad \langle \pi_P, \pi_H \rangle = \langle \pi_P, \pi_L \rangle = \langle \pi_H, \pi_L \rangle = 2.$$

If ε_P is the sign character of the point action, however, then

$$\boxed{\langle \varepsilon_P \pi_P, \pi_H \rangle = 0, \qquad \langle \varepsilon_P \pi_P, \pi_L \rangle = 0.}$$

Hence the sign-twisted point module is disjoint from both the heavy and line modules: the sign twist is neither the source outer involution nor the even line carrier.

Evidence boundary. All statements above are reproduced by a native GAP/GRAPE witness with 56/56 checks and a byte-exact focused regression. Classical Reye parameters, its order-576 Levi automorphism group, the GAP transitive-group catalogue, and the $W(F_4)$ action are prior art. No continuum, dynamics, particle, gauge-force, or physical-unification statement is inferred.

73.53 Equivariant BdG moduli, fiber locality, and connected voltage refinement

The signed deck-odd carrier admits a complete stabilizer-equivariant normal form. With

$$V_{16} \cong 2A \oplus 2\overline{A}, \qquad \dim_{\mathbb{C}} A = 4,$$

every Hermitian Hamiltonian compatible with the carrier stabilizer and ordinary conjugation particle-hole symmetry is, after choosing multiplicity coordinates,

$$\boxed{H_X = (I_A \otimes X) \oplus (I_{\overline{A}} \otimes -\overline{X}), \qquad X = X^\dagger \in M_2(\mathbb{C}).}$$

If the eigenvalues of X are λ_1, λ_2, then

$$\operatorname{spec} H_X = \lambda_1^4 \oplus \lambda_2^4 \oplus (-\lambda_1)^4 \oplus (-\lambda_2)^4,$$

and

$$H^4 - (\lambda_1^2 + \lambda_2^2) H^2 + \lambda_1^2 \lambda_2^2 I = 0.$$

Thus, after quotienting by equivariant basis changes and one nonzero overall energy scale, one continuous dimensionless level ratio remains. The intrinsic magnetic operator is the special point with absolute levels $3, 6$ and $H^4 - 45H^2 + 324I = 0$; the ratio 2 is not symmetry protected.

The E_6 horizontal/vertical split admits an exact gauge-invariant separator once an additional fiber-locality principle is supplied. For a cubic support T, let $n_b(T)$ count its vertices over base site $b \in AG(2,3)$ and define

$$\mathcal{C}(T) = \sum_b \binom{n_b(T)}{2} = \frac{\|n(T)\|^2 - 3}{2}.$$

Every one of the thirty-six horizontal lifts has occupancy $1+1+1$ and $\mathcal{C} = 0$, whereas each of the nine vertical full fibers has occupancy 3 and $\mathcal{C} = 3$. Hence on the forty-five cubic supports,

$$\boxed{C_{45} = 0^{36} \oplus 3^9, \qquad P_H = I - C_{45}/3, \qquad P_V = C_{45}/3.}$$

The operator depends only on the bundle projection and therefore commutes with independent $\mathbb{Z}_3$ translations in every fiber. A hard-core rule allowing at most one field insertion per fiber projects exactly onto the horizontal thirty-six. Gauge covariance alone still does not impose this rule. Indeed the 9×12 affine point-line incidence matrix satisfies $BB^T = 3I_9 + J_9$ and has rank nine, so no linear base-site projector can preserve all horizontal line occupancies while killing all vertical site vectors.

The failure of the naive repeated C_2 cover is also sharpened. The W33 point-line Levi graph has

$$|V| = 80, \qquad |E| = 160, \qquad \beta_1 = 81, \qquad d = 4.$$

A $\mathbb{Z}_2$ voltage cover is connected when its cycle voltages generate the deck group. Choosing at each level a spanning tree and a fresh non-tree chord, with voltage one on that chord and zero elsewhere, gives a connected lift at every stage. Repeating the construction on the newly obtained graph produces

$$\boxed{|V(L_n)| = 80\,2^n, \qquad |E(L_n)| = 160\,2^n, \qquad \beta_1(L_n) = 1 + 80\,2^n, \qquad d = 4.}$$

Thus the earlier disconnection obstruction concerned reuse of one pulled-back cohomology class, not connected binary refinement in general.

For every such two-lift, sheet parity gives the exact spectral decomposition

$$A_{\mathrm{lift}} \simeq A_{\mathrm{base}} \oplus A_\sigma.$$

The deterministic single-chord tower has verified distinct-adjacency-eigenvalue counts $5, 13, 29, 61, 125$ through depth four, so fresh classes do create new spectral scales. However one negative chord produces only two cross-sheet edges. For a four-regular N-vertex base the sheet cut has conductance at most $1/(2N)$, and the next combinatorial Laplacian gap obeys

$$\boxed{\lambda_1 \le 4/N.}$$

The tower is therefore connected but increasingly bottlenecked, not an isotropic continuum. A viable continuum search requires balanced voltage signatures with controlled new spectrum.

The old one-section magnetic matrix also receives a complete intrinsic reading. In sheet coordinates the exact identity is

$$\boxed{H_{32} = \begin{pmatrix} A & \overline{A} \\ \overline{A} & A \end{pmatrix}, \qquad H_+ = 2\,\mathrm{Re}\,A, \qquad H_- = 2i\,\mathrm{Im}\,A.}$$

Thus the section matrix is a complex parent coordinate whose real and imaginary parts become the two intrinsic deck-parity sectors after the conjugate sheet is restored. The exact one-sheet Schur operator is

$$H_{\mathrm{eff}}(E) = A + \overline{A}(E - A)^{-1}\overline{A},$$

and its fifteen bare section poles cancel in the full determinant

$$\det(E - H_{32}) = \det(E - A)\det(E - H_{\mathrm{eff}}(E));$$

they are decimation poles rather than physical eigenlevels.

Two especially tempting physical identifications fail further exact tests. For the class-D-like odd block $H = iS$, stabilizer symmetry forces fourfold level multiplicities, so

$$|\,\mathrm{Pf}\,S| = |\lambda_1\lambda_2|^4.$$

Positive-definite, indefinite, and negative-definite multiplicity representatives all have the same Pfaffian sign in the canonical deck ordering; at the magnetic point

$$\operatorname{Pf} S_{\mathrm{mag}} = -(3 \cdot 6)^4 = -104976.$$

Hence the finite zero-dimensional class-D $\mathbb{Z}_2$ bit is trivial on the whole stabilizer-equivariant gapped cone.

Likewise the nine vertical fibers do give a genuine affine representation hierarchy. Since $AGL(2,3)$ acts doubly transitively on the nine base sites,

$$\mathbb{C}^9 = \mathbf{1} \oplus V_8$$

with V_8 irreducible, and the complete K_9 cycle module is

$$Z_1(K_9) \cong \Lambda^2 V_8, \qquad \dim Z_1 = 28.$$

But character theory gives

$$\boxed{\dim \operatorname{Hom}_{AGL(2,3)}(\Lambda^2 V_8, V_8) = 0.}$$

There is no affine-equivariant alternating bracket $V_8 \times V_8 \to V_8$; therefore the structural dimension-eight sector cannot be identified with the $SU(3)$ adjoint/eight gluons while retaining the full affine symmetry.

Finally, graph covering preserves the local causal statement of a nearest-neighbor propagator: at every level, graph distance changes by at most one edge per tick. If one edge has physical length ℓ_n and one tick duration τ_n, the physical conversion is

$$\boxed{c_n = \ell_n/\tau_n.}$$

The cover topology fixes neither quantity. If a fixed d-dimensional physical volume is separately assumed, then $N_n = 2^n N_0$ implies $\ell_n/\ell_0 = 2^{-n/d}$, and constant nonzero c requires the same scaling for τ_n. Neither d nor the absolute calibration ℓ_0/τ_0 follows from the cover counts.

Evidence boundary. These are finite representation, bundle-projection, graph-cover, spectral, Pfaffian, cochain, and causal-scaling results. They do not derive Standard Model masses, an $SU(3)$ gauge theory, an interacting topological phase, a continuum spectral dimension, Lorentz invariance, the SI speed of light, or a unique physical voltage-refinement tower.

73.54 Ramanujan refinement, affine orientation, and the vertical eight

The W33 point–line Levi graph is four-regular and bipartite with exact spectrum

$$\pm 4^1 \oplus \pm\sqrt{6}^{24} \oplus 0^{30}.$$

Since $\sqrt{6} < 2\sqrt{3}$, it is Ramanujan. The bipartite Ramanujan 2-lift theorem of Marcus–Spielman–Srivastava therefore yields an existential infinite four-regular Ramanujan 2-lift tower rooted at this Levi graph, with all nontrivial adjacency eigenvalues bounded by $2\sqrt{3}$ and hence Laplacian gap at least $4 - 2\sqrt{3}$. An explicit first signing with eighty negative incidences and negative degree two at every Levi vertex has signed spectral radius $3.283768875\ldots < 2\sqrt{3}$, so its 160-vertex lift is connected and Ramanujan. This replaces the sparse single-chord bottleneck by a genuine uniform-gap refinement theorem, while leaving the subsequent signings noncanonical.

For the E_6 cubic split, the same-fiber collision observable

$$C(T) = \sum_b \binom{n_b(T)}{2}$$

satisfies $C = 0$ on all thirty-six horizontal affine lifts and $C = 3$ on all nine vertical full fibers. Thus the normalized observable is exactly the old firewall deletion mask,

$$\delta_{\mathrm{fw}}(T) = C(T)/3, \qquad l_{2,\mathrm{fw}} = l_{2,\mathrm{other}} + (I - C/3)l_{2,\mathrm{cubic}}.$$

The support projector is therefore identical to the support shadow of the L_∞ firewall deformation. The full Jacobiator is not simply C, because nested l_2 compositions generate retained/deleted cross terms.

The stabilizer-equivariant deck-odd Hamiltonian cone remains four-real-dimensional before geometric constraints. Requiring the exact intrinsic magnetic zero pattern reduces it to dimension two; additionally requiring equal absolute magnitude on all sixty surviving bonds leaves exactly two real projective rays. Both have fourfold spectrum

$$-2a,\ -a,\ a,\ 2a,$$

and therefore

$$\boxed{|\lambda_{\mathrm{high}}/\lambda_{\mathrm{low}}| = 2}.$$

Thus the ratio two is not fixed by carrier symmetry alone, but it is fixed by carrier symmetry together with magnetic locality and flat bond magnitude. A discrete two-ray sign/chirality ambiguity remains, and no physical particle assignment or energy scale is inferred.

The nine vertical fibers carry the affine site permutation module

$$\mathbb{C}^9 = \mathbf{1} \oplus V_8.$$

For the full affine group $AGL(2,3)$ one has

$$\mathrm{Hom}_{AGL(2,3)}(\Lambda^2 V_8, V_8) = 0.$$

However, the unique index-two orientation-preserving affine subgroup

$$ASL(2,3) = \mathbb{F}_3^2 {:} SL(2,3), \qquad |ASL(2,3)| = 216,$$

has

$$\dim \mathrm{Hom}_{ASL(2,3)}(\Lambda^2 V_8, V_8) = 1.$$

Writing

$$\phi(x,y,z) = \mathrm{sgn}_3 \det(y - x, z - x),$$

the bracket defined on the zero-sum site module by

$$\langle [f,g], h\rangle = \sum_{x,y,z} \phi(x,y,z) f(x) g(y) h(z)$$

is $ASL(2,3)$-equivariant. Integer verification gives exact Jacobi identity and Killing form

$$\boxed{K = -54 I_8}.$$

Hence, up to overall bracket scale, this is the compact A_2 algebra

$$\boxed{V_8 \cong \mathfrak{su}(3)}.$$

Determinant-reversing affine transformations reverse the bracket sign. The statement is therefore conditional on choosing affine orientation/chirality; it does not by itself derive QCD, a Yang–Mills action, or a gauge coupling.

The Ramanujan tower also sharpens the spacetime boundary. If $N_n = N_0 2^n$ cells are assumed to refine a fixed d-dimensional physical volume, preserving one causal conversion $c = \ell/\tau$ requires

$$\ell_{n+1}/\ell_n = \tau_{n+1}/\tau_n = 2^{-1/d}.$$

But a Ramanujan tower is a uniform expander, so its raw graph metric has nonvanishing macroscopic conductance rather than the shrinking boundary/volume behavior of a local fixed-dimensional manifold refinement. The cover tower is therefore naturally an internal routing/state refinement unless an additional local embedding metric is supplied.

Two further boundaries are exact. Ordinary fermionic antisymmetry on the full twenty-seven resolved fiber modes does not kill a vertical support, since

$$e_{b,0} \wedge e_{b,1} \wedge e_{b,2} \neq 0;$$

only the additional one-occupancy-per-fiber hard-core quotient makes it vanish. Finally, normalized traceless multiplicity Hamiltonians form a synthetic Bloch sphere. The full negative-energy rank-eight deck bundle has

$$\boxed{|c_1| = 8},$$

a Berry invariant of the Hamiltonian-parameter sphere rather than a momentum-space Chern phase or particle-count statement.

Evidence boundary. The promoted statements are finite graph-spectrum, representation, Lie-bracket, support-projector, exterior-algebra, Berry-bundle, and conditional metric/clock-scaling results. General Ramanujan 2-lift theory, expander theory, compact Lie-algebra classification, and historical Hessian/$SU(3)$ finite-group structure are prior art. No Standard-Model mass assignment, physical gluon identification, Yang–Mills coupling, absolute energy scale, Lorentz-invariant spacetime limit, physical value of c, dynamical orientation selector, or canonical explicit infinite signing sequence is claimed.

73.55 Passes 5691–5698: finite Yang–Mills candidate, duality, and Ramanujan depth

This recovered publication insert is reconstructed from the frozen Pass5691–5698 Markdown and JSON summary; it restores a manifest edge that was referenced historically but never committed.

On the nine affine sites, the 36 links have cycle-space dimension 28. The 54 translation parallelograms span rank 24 over $\mathbb{R}$, leaving $\dim H_1 = 4$; adjoining the twelve affine-line triangle boundaries raises the real face rank to 28. Over $\mathbb{F}_3$ the combined face rank is 26, leaving a two-dimensional modular quotient. The compact $\mathfrak{su}(3)$ Killing form is -54 times the Euclidean metric on the zero-sum eight, fixing the invariant quadratic form up to scale but not the physical coupling or the dynamical face set.

The two quantized flat-bond sign carriers are related exactly by $H_2 = -DH_1D$ for the recorded diagonal involution D, and particle-hole conjugation completes the antiunitary duality. The W33

Levi lift has explicit connected Ramanujan levels through 640 vertices under the corrected complement-gauge convention; later Pass5701 supplies exact PSD spectral certificates.

For the bracket firewall, the exact identity

$$J(b - D) = J(b) - B(b, D) - B(D, b) + J(D)$$

survives, but the former $l_1 = 0$ "l_3 repairs Jacobi" reading is superseded by Pass5707: with $l_1 = 0$, the ordinary uncurved L_∞ arity-three identity forces l_2 Jacobi strictly.

In the tensor-separated model $H_{\text{tot}} = H_D \otimes I + I \otimes H_{\text{int}}$, internal routing capacity can grow without changing the Dirac group velocity or split-step causal support. Twisting the affine action by the determinant character restores all 432 elements of $AGL(2, 3)$ as automorphisms of the finite $\mathfrak{su}(3)$ bracket. The Ramanujan adjoint Laplacian has the finite dimensionless lower gap $4 - 2\sqrt{3}$, explicitly not a Yang–Mills mass-gap claim.

Finally, the vertical Z_3 Fourier sectors are inequivalent gauge charges, not three identical generations: after retaining the Z_3 action the six $ASL(2, 3) \times Z_3$ constituents are multiplicity one and the joint commutant is $\mathbb{C}^6$, rather than an M_3 generation-mixing algebra.

Evidence boundary. These are finite graph, cochain, Lie-algebra, centralizer, tensor-product, representation, and spectrum results. No QCD/Yang–Mills derivation, confinement theorem, physical gauge coupling, Standard Model mass assignment, physical mass gap, spacetime-continuum derivation, value of c, or three-generation derivation is claimed.

Frozen sources: `analysis/PASS5691_5698_physics_ym_duality_ramanujan_frontier.md` and `data/PART_W33_PASS5691_5698_PHYSICS_YM_DUALITY_RAMANUJAN_FRONTIER_SUMMARY.json`.

Passes 5704–5711: finite Wilson transport, magnetic group bridge, Ramanujan depth, and generation-symmetry boundary

The affine 8-dimensional compact Lie algebra from the preceding frontier can be exponentiated in its adjoint representation. On the nine affine sites the complete link space has 36 edges and real cycle-space dimension 28. The twelve affine-line triangles selected by the 36 allowed E_6 cubics have boundary rank 12, while the 54 translation parallelograms have rank 24; together they have rank 28. Thus the E_6 cubic incidence canonically selects the line faces, translation geometry supplies a second face family, and only the combined 66-face complex kills the real harmonic one-sector. Finite transporters $U_e = \exp(\mathrm{ad}_{a_e})$ and nontrivial adjoint Wilson commutators are explicit, but neither the relative face weights nor a physical Yang–Mills coupling is selected.

The signed Segre stabilizer G_{96} has centre C_2 and derived subgroup

$$G'_{96} \cong Q_8 : C_3 \cong \mathrm{SL}(2, 3).$$

Quotienting the central sheet sign gives exactly

$$G_{96}/\langle -1 \rangle \cong C_2 \times S_4,$$

the cube/frame controller. The magnetic involution D centralizes G_{96} and is external to it, hence

$$\langle G_{96}, D \rangle \cong G_{96} \times C_2$$

has order 192. This is a quotient/direct-product bridge and not an order-based identification with the tomotope group or $W(D_4)$.

The W33-rooted Ramanujan two-lift tower was also made reproducible. Complementary signings are switching-equivalent on a bipartite graph, so the matching choices occur in three classes

$$01 \sim 23, \qquad 02 \sim 13, \qquad 03 \sim 12.$$

Fixing canonical representatives before the next labelled factorization removes a hidden floating-point gauge ambiguity. The selected signed radii for parents of sizes $160, 320, 640, 1280$ are approximately

$$3.423202804, \quad 3.396072581, \quad 3.453933214, \quad 3.446782416,$$

all below $2\sqrt{3}$. Hence an explicit connected Ramanujan chain now reaches

$$80 \to 160 \to 320 \to 640 \to 1280 \to 2560.$$

The raw matching-colour sequence is not intrinsic because S_4 permutes the three $2+2$ partitions transitively; an automorphism-canonical recursive signing law remains open.

A higher-algebra correction is required. The existing firewall builder states $l_1 = 0$ while using a non-Jacobi l_2 and presenting l_3 as the Jacobi repair. In an ordinary uncurved L_∞ algebra the arity-three identity contains

$$l_1 l_3 + \sum_{\text{cyc}} l_2 l_2 + \sum_{\text{cyc}} l_3 l_1 = 0.$$

Therefore $l_1 = 0$ forces strict Jacobi for l_2 and removes l_3 from this identity. The finite firewall Jacobiator and collision-support computations survive, but the previous minimal $l_1 = 0$ L_∞ interpretation does not. A genuine homotopy repair must introduce a nonzero differential on an extended degree, deform l_2 by a Chevalley–Eilenberg coboundary, or specify another higher structure with its identities checked directly.

Finally, the standard $E_8 \supset E_6 \times SU(3)$ branching

$$248 = (78, 1) + (1, 8) + (27, 3) + (\overline{27}, \overline{3})$$

does contain a real three-dimensional multiplicity space relative to E_6 alone:

$$\mathrm{End}_{E_6}(27 \otimes \mathbb{C}^3) \cong M_3(\mathbb{C}).$$

A central Z_3 acting as ωI_3 leaves this commutant unchanged, a generic family torus reduces it to $\mathbb{C}^3$, and the full irreducible family $SU(3)$ reduces it to scalars. Consequently exact unbroken family $SU(3)$ permits only a generation operator mI_3 and forces degeneracy. A physical hierarchy therefore requires a family-symmetry reduction/breaking datum. No explicit intertwiner yet identifies the new affine $\mathfrak{su}(3)$ with the $(1, 8)$ factor of this branching.

Two additional finite diagnostics sharpen these boundaries. The old affine Z_3 curvature may be embedded abstractly as centre flux $\omega^h I_3 \in Z(SU(3))$, but every such flux is invisible in the adjoint representation, so a nonzero-triality matter representation is required to observe it. And for the two magnetic flat-bond rays, $S_2 = -DS_1D$ with $\det D = 1$ gives equal Pfaffian parity; D neither commutes nor anticommutes with one ray, so DK is a duality between the rays rather than a symmetry producing a distinct protected topological sector.

Boundary. These are finite Lie-algebra, graph, group, cochain, representation and Pfaffian statements. They do not derive QCD, confinement, the Yang–Mills mass gap, a physical coupling, observed fermion masses or mixing, a physical BdG phase, or a spacetime continuum.

Passes 5720–5724: the affine gauge face complex has exact 3-torsion

Pass 5691 found an arithmetically exceptional rank drop for the nine-site affine gauge complex: the 54 translation plaquettes together with the 12 affine-line faces span the full 28-dimensional cycle space over characteristic zero, but have rank only 26 over $\mathbb{F}_3$. The integral calculation now resolves the defect exactly.

Choose the star spanning tree of K_9. Its 28 chords form an integral basis of the cycle lattice. In that basis the translation-plaquette boundary lattice has Smith invariants

$$1^{24},$$

whereas the full 66-face lattice has

$$\boxed{1^{26} \oplus 3^2.}$$

Hence, for the full affine face complex X,

$$\boxed{H_0(X;\mathbb{Z}) = \mathbb{Z}, \qquad H_1(X;\mathbb{Z}) \cong (\mathbb{Z}/3)^2, \qquad H_2(X;\mathbb{Z}) \cong \mathbb{Z}^{38}.}$$

The plaquette-only complex instead has

$$H_1(X_P;\mathbb{Z}) \cong \mathbb{Z}^4, \qquad H_2(X_P;\mathbb{Z}) \cong \mathbb{Z}^{30},$$

and the 12 affine-line attachments induce Smith invariants

$$\boxed{1, 1, 3, 3}$$

on this four-dimensional integral homology lattice. Thus the line faces kill all four real plaquette modes but leave an index-9 residue, producing two order-three classes.

The universal-coefficient consequence is

$$H^1(X;\mathbb{Z}) = 0, \qquad \boxed{H^2(X;\mathbb{Z}) \cong \mathbb{Z}^{38} \oplus (\mathbb{Z}/3)^2.}$$

Accordingly the two mod-3 one-homology/one-cohomology modes are torsion/Bockstein modes, not hidden real harmonic modes.

The symmetry is equally rigid. All 432 elements of

$$\mathrm{AGL}(2,3) = \mathbb{F}_3^2 \rtimes GL(2,3)$$

preserve the face set. On $H_1(X;\mathbb{F}_3) \cong \mathbb{F}_3^2$ the kernel is exactly the order-9 translation subgroup and the image is the full order-48 group $GL(2,3)$. In the explicit quotient basis used by the certificate,

$$Q(M,b) = P^{-1}\big(\det(M)M^T\big)P, \qquad P = \begin{pmatrix} 0 & 1 \\ 1 & 1 \end{pmatrix},$$

so the action is independent of the affine translation and carries an essential determinant twist.

Separation and physics firewall. This $(\mathbb{Z}/3)^2$ belongs to the nine-vertex/36-edge affine face complex. It is not Pass 5121's distinct one-dimensional $\mathbb{Z}/3$ saturation quotient on an 81×108 incidence carrier; no chain map between them is asserted. Nor does this torsion fix the Yang–Mills coupling, repair the adjoint-trivial vertical $\mathbb{Z}_3$ connection, prove confinement or a mass gap, choose matter, or supply a continuum limit. It is an exact finite homology and symmetry theorem.

74 Passes 5725–5732: torsion-center pairing, 234-dimensional Jacobi defect, and the finite Heisenberg family bridge

Passes 5720–5724 left an exact integral torsion doublet

$$H_1(X;\mathbb{Z}) \cong (\mathbb{Z}/3)^2$$

carrying the residual $GL(2,3)$ action. The first result of the present packet is a sharp observability boundary. The eight nonzero covectors of H^* form one $GL(2,3)$-orbit, the only fixed covector is zero, and every nonzero torsion class is detected by exactly six nonzero covectors. Thus

$$W_{t,\ell}(h) = \omega^{t\ell(h)}, \qquad t \in \{1,2\},$$

provides a nontrivial center character after a charge ℓ is chosen, but there is no nonzero full-affine-equivariant scalar map $H \to Z_3$. The canonical object is the contragredient evaluation pairing $H^* \times H \to \mathbb{F}_3$.

The firewall higher-algebra obstruction is now exact. All

$$\binom{248}{3} = 2{,}511{,}496$$

unordered basis triples were enumerated for the filtered E8 binary bracket; 32,400 have nonzero Jacobiator. The integer Jacobiator matrix has modular rank 234 over each of $\mathbb{F}_{1,000,003}$ and $\mathbb{F}_{1,000,033}$, while exactly 234 output basis coordinates occur. Therefore

$$\boxed{\operatorname{rank}_{\mathbb{Q}} J = 234}.$$

In fact $\operatorname{im} J$ is the full coordinate subspace on those 234 occupied coordinates, leaving a 14-dimensional untouched coordinate complement. Any two-term arity-three repair

$$l_1 : Y \to \mathfrak{g}, \qquad l_1(l_3) = -J$$

must have

$$\boxed{\dim Y \geq 234}.$$

The lower bound is attained at arity three by $Y = \operatorname{im} J$, l_1 the inclusion, and $l_3 = -J$; in this minimal model the lift is unique because l_1 is injective. Arity four and all higher L_∞ identities remain separate open equations. Hence the old small l_3-repair picture is ruled out for the actual firewall defect.

A finite family bridge also closes, with an important correction to Pass5708. The matrices used there,

$$Z = \operatorname{diag}(1,\omega,\omega^2), \qquad X = (012),$$

do not generate full $SU(3)$; they generate the order-27 qutrit Heisenberg group H_3. The old scalar-commutant conclusion nevertheless survives because its three-dimensional Schrödinger representation is irreducible. Moreover

$$\boxed{H_3/Z(H_3) \cong \mathbb{F}_3^2 \cong H_1(X;\mathbb{Z})}.$$

After a torsion-basis choice, $e_1 \mapsto [X]$ and $e_2 \mapsto [Z]$ therefore give an explicit projective torsion action on the same $\mathbb{C}^3$ multiplicity factor appearing in the E8 $(27,3)$ branch. This is an exact

finite-module intertwiner, not an identification of the affine Lie $\mathfrak{su}(3)$ with the E8 family $SU(3)$ Lie algebra.

The normalizer sharpens the bridge. Qutrit Fourier and quadratic-phase gates implement determinant-+1 symplectic transformations, while complex conjugation sends $X \mapsto X$, $Z \mapsto Z^{-1}$. Thus the exact determinant character

$$\det : GL(2,3) \longrightarrow \mathbb{F}_3^\times \cong C_2$$

separates the unitary Clifford $SL(2,3)$ sector from the determinant-reversing antiunitary extended-Clifford coset. The same bit records preservation versus reversal of the torsion alternating form.

The family-symmetry breaking lattice on Herm(3) is

G	1	Z_3^{scalar}	$\langle X\rangle$	$\langle Z\rangle$	C_2	S_3	H_3
$\dim_{\mathbb{R}} \mathrm{Herm}(3)^G$	9	9	3	3	5	2	1.

A single cyclic C_3 can therefore support a generic nondegenerate three-level operator, whereas S_3 forces a doublet and the irreducible Heisenberg action forces exact degeneracy. The X- and Z-cyclic axes are Fourier conjugate with overlap magnitude $1/\sqrt{3}$; nontrivial finite mixing is consequently a relative mismatch between independently chosen residual axes, not a property of one cyclic sector alone. No observed mass or CKM/PMNS value is inferred.

On the Ramanujan tower, complementary 2-of-4 matching signings form three switching classes. Signed spectral radius is switching- and automorphism-invariant, and at parent sizes $160, 320, 640, 1280$ the three candidate radii are strictly ordered. Hence $\arg\min \rho$ gives a unique label-independent choice on each known transported candidate triple and removes the raw three-colour naming gauge. The candidate triple itself still depends on the chosen perfect-matching factorization, so an all-level automorphism-canonical recursion is not yet proved.

Two outside-box mixed-sector tests close negatively. For trivial action,

$$H^2(C_3, C_2) = H^2(C_2, C_3) = 0,$$

so adjoining the ternary torsion label to the deck/class-D Z_2 label creates no new mixed central extension; $C_3 \times C_2 \cong C_6$ splits. A noncentral $C_3 : C_2 \cong S_3$ route exists only if deck conjugation is independently identified with the qutrit antiunitary inversion. Likewise

$$\mathrm{Hom}(C_2, C_3) = \mathrm{Hom}(C_3, C_2) = 0,$$

so Chinese-remainder packaging alone does not couple the binary and ternary cohomology sectors. The determinant map above is the exact cross-prime orientation hinge, but no canonical map from the binary Ramanujan switching state into that hinge is presently known.

All claims in this section are finite algebraic or graph-theoretic statements. They do not derive QCD color, confinement, physical generations, observed masses, a continuum anomaly, spacetime, or laboratory performance.

74.1 A fixed quadratic code with 234 selectable symplectic W33 overlays

The characteristic-3 non-collinearity matrix of $W(3,3)$ provides an explicit coordinate bridge to a classical code rather than a new code family. Write the forty points as the projective points of $PG(3,3)$ and let

$$V(x) = (x_0^2, x_0x_1, x_0x_2, x_0x_3, x_1^2, x_1x_2, x_1x_3, x_2^2, x_2x_3, x_3^2) \in \mathbb{F}_3^{10}$$

be the quadratic Veronese feature map. If J is a nondegenerate alternating form, then

$$C_J(x, y) = (x^T J y)^2$$

is exactly the 0/1 non-collinearity matrix, because every nonzero element of $\mathbb{F}_3$ has square one. Exact replay gives

$$\operatorname{rowspan}_{\mathbb{F}_3} C_J = \operatorname{rowspan}_{\mathbb{F}_3} V^T, \qquad \operatorname{rank} C_J = 10.$$

Thus the W33 characteristic-3 module is the known quadratic Veronese code $[40, 10, 18]_3$. Its replayed weight distribution is

$$0^1, \quad 18^{1560}, \quad 24^{21060}, \quad 27^{18800}, \quad 30^{16848}, \quad 36^{780}.$$

The parameters themselves are prior art and are not promoted here as novel.

For the standard polarity the bridge factors exactly as

$$\boxed{C_J = V B_J V^T \pmod 3},$$

where B_J is a symmetric involution with only ten nonzero entries. The direct 40×40 matrix contains 1080 nonzero coefficients, whereas the two Veronese legs and the core contain $216 + 10 + 216 = 442$. This is a finite-field structural factorization, not a hardware-speedup claim.

The same matrix satisfies

$$\boxed{C_J^2 = 0 \pmod 3},$$

so its row space is self-orthogonal. The dual has distance four. Its 130 projective minimum supports are exactly the 130 projective lines of $PG(3, 3)$, with two nonzero scalar multiples per support, giving the known 260 weight-four dual words. The standard qutrit CSS construction therefore has parameters

$$\boxed{[[40, 20, 4]]_3},$$

recorded as a standard consequence of the classical code rather than a new coding family.

Let H be the 130×40 all-one projective-line incidence matrix. Exact replay finds

$$\operatorname{rank}_{\mathbb{F}_3} H = 30,$$

so the line rows span the full classical dual. Every line gives the local parity law

$$\sum_{p \in L} x_p = 0,$$

and hence any coordinate is recovered from the other three points on the line. Every point belongs to thirteen such repair groups. Relative to one selected W33 polarity the split is

$$\boxed{13 = 4_{\text{isotropic}} + 9_{\text{nonisotropic}}}.$$

The four isotropic groups are the native W33 lines through that point; the other nine belong only to the ambient projective geometry.

The projective minimum-dual rays have dot-product graph equal to the line-intersection Grassmann graph

$$\boxed{J_3(4, 2) = \mathrm{SRG}(130, 48, 20, 16)}.$$

The forty lines isotropic for the chosen polarity induce

$$\boxed{\mathrm{SRG}(40, 12, 2, 4)},$$

while the ninety non-isotropic lines have induced degree 32. Cross-incidence is biregular with degrees 36 and 16.

The architecture-level result is the polarity census. A projective alternating form on $\mathbb{F}_3^4$ has six coefficients. Exhausting the nondegenerate forms modulo nonzero scalar gives

$$\boxed{234}$$

distinct symplectic polarity classes. Equivalently,

$$[PGL(4,3) : PGSp(4,3)] = \frac{12{,}130{,}560}{51{,}840} = 234.$$

For every one of these 234 forms, the exact matrix $C_J = (x^T Jy)^2$ is different, but its row space is the same fixed ten-dimensional quadratic code. Each overlay selects forty W33-isotropic lines from the same 130 ambient projective lines, and every ambient line is selected in exactly seventy-two overlays:

$$234 \cdot 40 = 130 \cdot 72 = 9360.$$

Consequently the finite architecture admits the exact separation

$$\boxed{\text{fixed quadratic code space} \times \text{234-way symplectic selector} \longrightarrow \text{selectable W33 routing overlay.}}$$

The code state therefore need not be re-encoded merely to change which symplectic polarity supplies the native W33 incidence fabric. This is a finite reconfiguration theorem only; no physical gauge-field, spacetime, coupling, or laboratory interpretation is asserted.

The executable witness is `analysis/w33_pass5744_5751_quadratic_code_overlays.py`; its frozen certificate and focused regression are stored under `data/` and `tests/`.

74.2 The q=5 Reye and heavy shells share one rank-nine Latin core

The Pass 5667–5674 q=5 multidesign certificate contains two apparently different incidence systems on the same moving twelve cover cells: the twelve multiplicity-six heavy supports and the sixteen zero-containment triples forming Reye's $12_4, 16_3$ configuration. Let

$$H \in \{0,1\}^{12\times 12} \qquad \text{and} \qquad R \in \{0,1\}^{12\times 16}$$

be their point–block incidence matrices. Exact arithmetic gives the stronger identity

$$\boxed{HH^T - 3J_{12} = RR^T - J_{12} =: K_9,}$$

with

$$\boxed{K_9^2 = 4K_9}, \qquad \boxed{\mathrm{rank}_{\mathbb{Q}}\, K_9 = 9}.$$

Thus

$$\boxed{P_9 = \frac{1}{4}K_9}$$

is a rational orthogonal projector canonically extracted from either shell.

The same matrix reconstructs an intrinsic imprimitivity system. The matrix

$$A_{\mathrm{blk}} = 3I_{12} - K_9$$

is exactly $3K_4$. In the frozen moving-twelve labels its components are

$$\{1,3,8,10\}, \qquad \{2,5,7,12\}, \qquad \{4,6,9,11\},$$

and, after block-ordering,

$$K_9 = I_3 \otimes (4I_4 - J_4), \qquad P_9 = I_3 \otimes \left(I_4 - \frac{1}{4}J_4\right).$$

Hence the protected common nine-space is simply the direct sum of the three within-block zero-sum spaces.

The sixteen Reye triples meet each of these four-point blocks once, and every cross-pair from any two blocks occurs in exactly one triple. Therefore the zero shell is a transversal design

$$\boxed{TD(3,4)},$$

equivalently a Latin square of order four. With the deterministic component ordering of the verifier its table is

$$\begin{pmatrix} 2 & 0 & 3 & 1 \\ 0 & 2 & 1 & 3 \\ 3 & 1 & 2 & 0 \\ 1 & 3 & 0 & 2 \end{pmatrix},$$

and the symbol relabel $(0,1,2,3) \mapsto (1,3,0,2)$ turns it into

$$\boxed{\begin{pmatrix} 0 & 1 & 2 & 3 \\ 1 & 0 & 3 & 2 \\ 2 & 3 & 0 & 1 \\ 3 & 2 & 1 & 0 \end{pmatrix}}$$

—the Cayley table of the Klein group $V_4 \cong \mathbb{F}_2^2$ under XOR. In the original thirteen-cover positions one explicit chart is

$$\begin{aligned} r = 0,1,2,3 &\longleftrightarrow 2,8,11,3, \\ c = 0,1,2,3 &\longleftrightarrow 13,6,5,9, \qquad \boxed{s = r \oplus c}. \\ s = 0,1,2,3 &\longleftrightarrow 7,10,12,4, \end{aligned}$$

The row/column/symbol names remain autoparatopy gauge choices; the recovered $TD(3,4)$ object is intrinsic.

The heavy shell is also recoverable from this Latin object alone. Among all

$$\binom{4}{2}^3 = 216$$

balanced six-subsets choosing two points from each four-block, the number of contained Reye triples has exact spectrum

$$\boxed{0^{12} \oplus 2^{192} \oplus 4^{12}}.$$

The four-line class is exactly the twelve intercalate supports of the Klein square, while the zero-line class is exactly the twelve multiplicity-six heavy supports. Complementation in the moving twelve exchanges the two exceptional classes:

$$\boxed{\text{heavy support} = \text{complement of a Klein intercalate support.}}$$

This reconstructs the heavy shell, but does not select a preferred bijection between individual points and individual heavy supports.

The common projector resolves the earlier character overlap. The three transitive carrier actions have rank three and pairwise permutation-character inner product two. Since both incidence matrices have rank ten and their centered parts have rank nine, their rational permutation modules decompose by dimension as

$$\boxed{\mathbb{Q}_P^{12} = \mathbf{1} \oplus W_9 \oplus U_{2,P},}$$

$$\boxed{\mathbb{Q}_H^{12} = \mathbf{1} \oplus W_9 \oplus U_{2,H},}$$

and

$$\boxed{\mathbb{Q}_L^{16} = \mathbf{1} \oplus W_9 \oplus V_6.}$$

Thus every pair shares exactly the trivial line and the same irreducible nine-space W_9.

This also makes the outer/sign distinction structural. The order-two carrier outer automorphism of Pass 5674 exchanges the point- and heavy-stabilizer classes. Because W_9 is their unique common nontrivial constituent, the involution fixes W_9 and swaps the two-dimensional spokes:

$$\boxed{W_9 \mapsto W_9, \qquad U_{2,P} \leftrightarrow U_{2,H}.}$$

By contrast the point-side sign tensor twist is disjoint from the heavy and line modules by Pass 5674. Its frozen odd-element point fixed-count distribution $0^{168}, 2^{108}, 6^{12}$ also gives

$$\langle \varepsilon\pi_P, \pi_P \rangle = \frac{3 \cdot 576 - 2(108 \cdot 2^2 + 12 \cdot 6^2)}{576} = 0.$$

Hence

$$\boxed{\varepsilon \otimes \mathbb{Q}_P^{12} \perp \mathbb{Q}_P^{12} \oplus \mathbb{Q}_H^{12} \oplus \mathbb{Q}_L^{16}.}$$

The source outer involution preserves the common core and exchanges spokes; the sign twist moves the whole point packet to a disjoint character sector.

Finally, this resolves a possible order-576 ambiguity. Pass 5300 concerns the projective-symplectic Hoffman-cover stabilizer $2_+^{1+4} : (S_3 \times C_3)$ with centre C_2. Pass 5417 instead defines `act` as the cover-cell permutation image of the full graph-automorphism stabilizer; its frozen producer certificate is

$$\boxed{2^4 : (S_3 \times S_3), \qquad |\mathtt{act}| = 576, \qquad Z(\mathtt{act}) = 1.}$$

The present Reye/Latin theorem concerns this latter centreless group. The two order-576 groups are not identified.

Prior art and evidence boundary. The classical Reye configuration and its order-576 Levi automorphism group are prior art. In particular Monson–Pellicer–Williams, *The tomotope*, Ars Math. Contemp. **5** (2012), 355–370, DOI 10.26493/1855-3974.189.e64, identify the tomotope medial layer graph with the Reye Levi graph. The new statement here is the exact q=5 multidesign bridge: identical centered Gram projector, intrinsic Klein-V_4 $TD(3,4)$, heavy/intercalate complement class, and the resulting representation split. No continuum, particle, gauge-force, mass/coupling, or physical-unification claim is inferred.

74.3 The q=5 Latin carrier as an affine $M_2(\mathbb{F}_2)$ left–right geometry

The Klein-V_4 chart reconstructed in Passes 5776–5783 admits a concrete matrix-algebra model that resolves the source outer involution. Choose $V = W = \mathbb{F}_2^2$. The full centreless order-576 Latin carrier is

$$\boxed{G_{576} = \mathrm{Hom}(W, V) \rtimes \big(GL(V) \times GL(W)\big).}$$

After choosing bases, $\mathrm{Hom}(W, V) \cong M_2(\mathbb{F}_2)$, so

$$\boxed{G_{576} \cong M_2(\mathbb{F}_2)_+ : \big(GL_2(2) \times GL_2(2)\big), \qquad 16 \cdot 6 \cdot 6 = 576.}$$

Explicitly,

$$(X, A, B) : M \longmapsto AMB^{-1} + X.$$

The verifier enumerates all 576 such affine maps. The normal matrix space contains six invertible and ten singular matrices, the classical $M_2(\mathbb{F}_2)$ census.

The two degree-12 carriers have a particularly simple dual description. The point carrier is

$$\boxed{P = \{(w, x) : 0 \neq w \in W,\ x \in V\}.}$$

For $0 \neq \phi \in V^*$ and $\psi \in W^*$ define

$$\boxed{H_{\phi,\psi} = \{(w, x) \in P : \phi(x) + \psi(w) = 1\}.}$$

There are twelve such six-subsets. Under the explicit q=5 coordinate chart of Pass 5778 they agree *exactly* with the twelve frozen multiplicity-six heavy supports. Replacing the right side by zero gives exactly the twelve Klein intercalate supports. Hence the preceding complement theorem is the single affine relation

$$\boxed{\phi(x) + \psi(w) = 0/1 \quad \Longleftrightarrow \quad \text{intercalate/heavy.}}$$

The induced point action is

$$(w, x) \longmapsto \big(Bw, Ax + X(Bw)\big),$$

while the dual heavy action is

$$(\phi, \psi) \longmapsto \left(\phi A^{-1}, \psi B^{-1} + \phi A^{-1} X\right).$$

The sixteen Reye/Latin lines are the graphs of the sixteen linear maps $W \to V$ restricted to $W \setminus \{0\}$. Exhausting all group elements gives faithful order-576 actions on the point, heavy and line carriers, with the two 12-actions having stabilizer order 48 and subdegrees $1, 3, 8$. The permutation-character Gram is

$$\boxed{\big(\langle \pi_i, \pi_j \rangle\big)_{i,j=P,H,L} = \begin{pmatrix} 3 & 2 & 2 \\ 2 & 3 & 2 \\ 2 & 2 & 3 \end{pmatrix},}$$

and the point-side sign twist satisfies

$$\boxed{\big(\langle \varepsilon\pi_P, \pi_P \rangle, \langle \varepsilon\pi_P, \pi_H \rangle, \langle \varepsilon\pi_P, \pi_L \rangle\big) = (0, 0, 0).}$$

Thus the independent affine-matrix model exactly replays the Pass 5667–5674 carrier-character certificate.

Now let $\Theta(M) = M^T$. Direct conjugation gives

$$\boxed{\Theta\,(X, A, B)\,\Theta = \tau(X, A, B) = (X^T, B^{-T}, A^{-T}),}$$

with $\tau^2 = 1$. Transpose normalizes the affine group but is not one of its 576 elements. It fixes eight of the sixteen matrices. More importantly, with the chosen bases the bijection

$$\boxed{F : P \to H, \qquad F(w, x) = (w^T, x^T)}$$

satisfies the exact intertwining law

$$\boxed{F(g \cdot p) = \tau(g) \cdot F(p)}$$

for every group element and every point. Hence the heavy action is precisely the point action twisted by the transpose factor-swap automorphism.

The outerness is visible inside the normal translation subgroup $T = M_2(\mathbb{F}_2)_+$. A point stabilizer meets T in

$$T_P = \{X : Xw = 0\},$$

a four-element fixed-right-kernel subspace whose aggregate image spans all of V. A heavy stabilizer meets T in

$$T_H = \{X : \phi X = 0\},$$

a four-element fixed-left-image subspace whose aggregate image has dimension one. Internal conjugation acts on T by $X \mapsto AXB^{-1}$ and cannot exchange these two types, whereas

$$\boxed{T_P^T = T_H.}$$

This supplies a concrete finite-algebra mechanism for the abstract carrier outer involution of Pass 5674.

Prior art and evidence boundary. The ring $M_2(\mathbb{F}_2)$ and its use in two-qubit projective-ring geometry are external prior art; see Saniga–Planat–Pracna, *Projective Ring Line Encompassing Two-Qubits*, arXiv:quant-ph/0611063. That work uses the projective line over the noncommutative order-16 ring to model the two-qubit Pauli commutation geometry. The theorem here is narrower: the q=5 Reye/Latin normal 16-space is the *additive* matrix space, its order-576 carrier is the affine left/right unit action, and transpose realizes the point/heavy factor swap. No identification of q=5 W33 carrier points with two-qubit observables, projective-ring points, entanglement classes, or physical states is made. No dynamics, gauge interaction, mass/coupling, or physical-unification conclusion follows.

74.3.1 Transpose carries point–line Reye incidence to heavy–line disjointness

The affine matrix coordinates sharpen the point/heavy outer twist to a full incidence theorem. Write the sixteen Reye lines as graphs

$$L_M = \{(w, Mw) : 0 \neq w \in W\}, \qquad M \in \mathrm{Hom}(W, V),$$

and the twelve heavy supports as

$$H_{\phi,\psi} = \{(w, x) : \phi(x) + \psi(w) = 1\}.$$

Restricting the heavy equation to L_M gives the linear functional $(\phi M+\psi)(w)$. A nonzero functional on $\mathbb{F}_2^2$ takes value one on exactly two of the three nonzero vectors, while the zero functional never does. Therefore

$$\boxed{|L_M \cap H_{\phi,\psi}| = \begin{cases} 0, & \psi = \phi M, \\ 2, & \psi \neq \phi M. \end{cases}}$$

The complete line–heavy intersection census is

$$\boxed{0^{48} \oplus 2^{144}}.$$

Define incidence by disjointness,

$$D_{M,(\phi,\psi)} = 1 \iff L_M \cap H_{\phi,\psi} = \varnothing.$$

Every line is incident with three heavy blocks and every heavy block with four lines. Hence D is a $12_4, 16_3$ incidence structure. In fact it is exactly a second Reye copy. Under

$$F(w, x) = (w^T, x^T), \qquad M \mapsto M^T,$$

the original point–line relation $x = Mw$ becomes

$$x^T = w^T M^T,$$

which is precisely the heavy-disjointness condition. Thus

$$\boxed{D[M, h] = R[F^{-1}(h), M^T].}$$

Transpose therefore carries the original point–line Reye configuration to the heavy–line disjointness Reye configuration on the same sixteen-line family. The carrier outer involution is an incidence dualization, not only a character or stabilizer-class equivalence.

There is also a canonical linear bridge between the two common nine-spaces. Let

$$C_R = 4R - J_{12\times 16}, \qquad C_H = 2H - J_{12}$$

be the integer-centered point–line and point–heavy incidence matrices. Then

$$\boxed{B = \frac{1}{4} C_R^T C_H = J_{16\times 12} - 4D.}$$

Every entry of B is 1 or -3, its row and column sums vanish, and

$$\boxed{\operatorname{rank}_{\mathbb{Q}} B = 9}.$$

Moreover

$$\boxed{BB^T = C_R^T C_R}, \qquad \boxed{B^T B = 4C_H^T C_H},$$

with

$$(C_R^T C_R)^2 = 64(C_R^T C_R), \qquad (C_H^T C_H)^2 = 16(C_H^T C_H).$$

Consequently

$$\boxed{U = \frac{1}{8}B}$$

is a rank-nine partial isometry satisfying

$$\boxed{UU^T = E_{W_9,L}, \qquad U^TU = E_{W_9,H}.}$$

Thus the disjointness Reye matrix is itself the signed cross-transform that identifies the heavy and line realizations of the common irreducible W_9.

Boundary. This is exact finite incidence geometry and rational linear algebra. It does not supply a quantum, continuum, dynamical, gauge, or particle-physics identification.

74.4 The $1 + 9 + 6$ line-carrier split is matrix-rank Fourier geometry

The affine matrix model makes the full rational decomposition of the sixteen Reye/Latin lines explicit. The line set is the additive torsor

$$T = M_2(\mathbb{F}_2),$$

and, using the Frobenius pairing $\langle Y, M\rangle = \mathrm{tr}(Y^TM)$, define Walsh vectors

$$\boxed{v_Y = \sum_{M\in M_2(\mathbb{F}_2)} (-1)^{\langle Y,M\rangle} e_M.}$$

They satisfy $\langle v_Y, v_Z\rangle = 16\delta_{YZ}$. The dual matrix labels split by rank as

$$\boxed{16 = 1 + 9 + 6},$$

namely one zero matrix, nine nonzero rank-one matrices, and six invertible rank-two matrices. This is exactly the carrier decomposition

$$\boxed{\mathbb{Q}_L^{16} = \mathbf{1} \oplus W_9^{\mathrm{rank}\,1} \oplus V_6^{\mathrm{rank}\,2}.}$$

Indeed every nonzero rank-one label has the unique factorization

$$Y = \phi^T w^T, \qquad 0 \neq \phi \in V^*, \quad 0 \neq w \in W,$$

so the nine labels form a literal 3×3 grid. Define the point- and heavy-fibre Walsh vectors

$$u_{w,\phi} = \sum_{x\in V} (-1)^{\phi(x)} e_{(w,x)}, \qquad h_{w,\phi} = \sum_{\psi\in W^*} (-1)^{\psi(w)} e_{(\phi,\psi)}.$$

For point–line Reye incidence R, point–heavy incidence H, and line–heavy disjointness incidence D, exact summation gives

$$\boxed{R^T u_{w,\phi} = v_{\phi^T w^T}}, \qquad \boxed{H^T u_{w,\phi} = -2h_{w,\phi}}, \qquad \boxed{Dh_{w,\phi} = v_{\phi^T w^T}}.$$

Thus the point, heavy and line realizations of the common W_9 are exactly the same nine rank-one additive characters, transported by finite Radon transforms.

The six invertible labels give the complementary line-only sector. For every $Y \in GL_2(2)$,

$$\boxed{Rv_Y = 0}, \qquad \boxed{D^T v_Y = 0},$$

while no nonzero rank-one Walsh vector is killed by either transform. Hence

$$\boxed{V_6 = \operatorname{span}\{v_Y : \det Y = 1\} = \ker R = \ker D^T.}$$

The full affine carrier also becomes monomial in this basis. For $g = (X, A, B)$,

$$\boxed{gv_Y = (-1)^{\langle Y', X\rangle} v_{Y'}, \qquad Y' = A^{-T} Y B^T.}$$

This identity was checked on all $576 \cdot 16 = 9216$ element/label pairs. The rank-one and rank-two sector characters satisfy

$$\boxed{\langle \chi_9, \chi_9 \rangle = 1}, \qquad \boxed{\langle \chi_6, \chi_6 \rangle = 1}, \qquad \boxed{\langle \chi_9, \chi_6 \rangle = 0}.$$

Because both sectors are explicitly realized over $\mathbb{Q}$ by integer Walsh vectors, each is absolutely irreducible.

Restriction to the normal translation group $T = M_2(\mathbb{F}_2)_+$ is especially transparent:

$$\boxed{W_9 \downarrow_T = \bigoplus_{\operatorname{rank} Y = 1} \chi_Y,} \qquad \boxed{V_6 \downarrow_T = \bigoplus_{\det Y = 1} \chi_Y.}$$

Thus the normal sixteen-group itself spectrally distinguishes the common-nine and line-only-six sectors.

Transpose acts on the Fourier labels by

$$\boxed{\Theta v_Y = v_{Y^T}}.$$

For $Y = \phi^T w^T$ this sends Y to $w^T \phi^T$, so the same outer involution that exchanges point and heavy carriers swaps the two factors of the 3×3 rank-one grid and preserves the six invertible labels as a set.

Finally, over $\mathbb{F}_2$ each nonzero matrix is already a unique projective point of $\mathrm{PG}(3, 2)$. The determinant-zero locus consists of precisely the nine rank-one points and its complement of the six invertible points:

$$\boxed{15 = 9 + 6}.$$

The nine-point locus has the explicit product parametrization $(\phi, w) \in 3 \times 3$, the standard hyperbolic-quadric/grid rank geometry of 2×2 matrices.

Prior art and evidence boundary. Finite translation/Fourier rank schemes are classical; an explicit modern reference for finite bilinear and quadratic-form translation schemes is K.-U. Schmidt, arXiv:1803.04274. The $M_2(\mathbb{F}_2)$ two-qubit projective-line use is also prior art in Saniga–Planat–Pracna, arXiv:quant-ph/0611063. The new repository statement is the exact identification of the already-certified q=5 Reye/heavy carrier modules and incidence maps with these rank-stratified Walsh sectors. The dimensions $1 + 9 + 6$ are not particle multiplets, qubit states or physical sectors absent a separately verified physical map.

74.5 The common rational W_9 has distinct integral and binary forms

The point, heavy and line carriers share one absolutely irreducible nine-dimensional module over $\mathbb{Q}$, but this equivalence does not persist unchanged over $\mathbb{Z}$ or $\mathbb{F}_2$. The exact saturated lattices are

$$\boxed{L_P = L_H \cong A_3^3}, \qquad \boxed{L_L \cong A_3 \otimes A_3}.$$

For the standard A_3 basis $e_i - e_3$,

$$G_{A_3} = \begin{pmatrix} 2 & 1 & 1 \\ 1 & 2 & 1 \\ 1 & 1 & 2 \end{pmatrix}, \qquad \det G_{A_3} = 4.$$

Hence

$$\boxed{\det L_P = \det L_H = 4^3 = 2^6},$$

whereas

$$\boxed{\det L_L = \det(G_{A_3} \otimes G_{A_3}) = 4^6 = 2^{12}}.$$

The discriminant groups are

$$\boxed{L_P^*/L_P \cong L_H^*/L_H \cong (\mathbb{Z}/4)^3},$$

and

$$\boxed{L_L^*/L_L \cong (\mathbb{Z}/4)^4 \oplus \mathbb{Z}/16}.$$

The line-lattice identification is constructive. The dual-label map

$$L = \begin{pmatrix} 0 & 1 & 1 & 0 \\ 1 & 0 & 1 & 1 \\ 0 & 1 & 1 & 1 \\ 1 & 0 & 0 & 1 \end{pmatrix}$$

sends the nine determinant-zero nonzero Fourier labels to the nine product labels (α, β) with $\alpha, \beta \neq 0$. Its primal coordinate map is $C = L^{-T}$,

$$C = \begin{pmatrix} 1 & 1 & 0 & 1 \\ 0 & 1 & 1 & 0 \\ 1 & 0 & 0 & 1 \\ 1 & 1 & 1 & 0 \end{pmatrix}.$$

After this integral coordinate permutation, the line W_9 is exactly the lattice of 4×4 integer arrays with every row sum and every column sum zero, with basis

$$(e_i - e_3) \otimes (e_j - e_3), \qquad 0 \leq i, j < 3.$$

Thus the equality $L_L \cong A_3 \otimes A_3$ is an explicit lattice isometry, not a discriminant guess.

The natural Walsh bases are themselves nonsaturated. On the point and heavy sides their column Smith form is

$$\boxed{1^3\, 2^6},$$

so each has index 2^6 in A_3^3. On the line side the rank-one Walsh basis has Smith form

$$\boxed{1\, 2^4\, 4^4},$$

and index 2^{12} in $A_3 \otimes A_3$.

Writing the Radon maps on saturated bases gives the exact Smith forms

$$\boxed{\mathrm{SNF}(R^T|_{W_9}) = \mathrm{SNF}(D|_{W_9}) = 1^5\,2^2\,4^2,}$$

and

$$\boxed{\mathrm{SNF}(H^T|_{W_9}) = 1^2\,2^5\,4^2.}$$

Therefore

$$\boxed{\mathrm{coker}(R^T|_{W_9}) \cong \mathrm{coker}(D|_{W_9}) \cong (\mathbb{Z}/2)^2 \oplus (\mathbb{Z}/4)^2,}$$

of order 2^6, while

$$\boxed{\mathrm{coker}(H^T|_{W_9}) \cong (\mathbb{Z}/2)^5 \oplus (\mathbb{Z}/4)^2,}$$

has order 2^9.

The full incidence Smith forms are

$$\boxed{\mathrm{SNF}(R) = \mathrm{SNF}(D) = 1^8\,2^2}, \qquad \boxed{\mathrm{SNF}(H) = 1^4\,2^6}.$$

For the projector numerator and centered transforms,

$$\boxed{\mathrm{SNF}(K_9) = 1^3\,4^6},$$

$$\boxed{\mathrm{SNF}(B) = \mathrm{SNF}(C_R) = 1\,4^6\,8^2}, \qquad \boxed{\mathrm{SNF}(C_H) = 1\,2^4\,4^4}.$$

Consequently the binary ranks are

$$\boxed{\mathrm{rank}_2\,R = \mathrm{rank}_2\,D = 8}, \qquad \boxed{\mathrm{rank}_2\,H = 4},$$

$$\boxed{\mathrm{rank}_2\,K_9 = 3}, \qquad \boxed{\mathrm{rank}_2\,B = \mathrm{rank}_2\,C_R = \mathrm{rank}_2\,C_H = 1}.$$

In the intrinsic three-block coordinates this last collapse is visible from

$$K_9 = I_3 \otimes (4I_4 - J_4) \equiv I_3 \otimes J_4 \pmod 2.$$

Coefficient-ring firewall. The safe statement is now explicit: over $\mathbb{Q}$ the three carriers share one W_9; over $\mathbb{Z}$ the point/heavy form is A_3^3 while the line form is $A_3 \otimes A_3$; over $\mathbb{F}_2$ even the incidence ranks split. Any future CSS/code claim using this common-nine theorem must state its coefficient ring and preserve these exact 2-primary cokernels. No physical significance is assigned to the powers of two without an independent operational map.

Determinant-polar doily and the integral binary shadow

The Pass 5832–5839 matrix packet survives mathematically, but its pass namespace was contaminated by a parallel packet landed after reservation. We therefore keep its exact certificate intact and continue with a collision-recovery addendum.

On $V = M_2(\mathbb{F}_2)$ put $q(X) = \det X$. Its polarization

$$B(X, Y) = q(X + Y) + q(X) + q(Y)$$

is nondegenerate alternating. Hence the fifteen nonzero matrices are a concrete $W(3,2)$ point set. The rank split is

$$15 = 9 + 6,$$

where the nine rank-one matrices are the hyperbolic quadric

$$Q^+(3,2) \cong \mathbb{P}^1(\mathbb{F}_2) \times \mathbb{P}^1(\mathbb{F}_2)$$

(the 3×3 grid) and the six units are its complement. Of the fifteen isotropic lines, six lie wholly in the grid and nine meet it in exactly one point. This is an incidence-level coordinatization of the standard two-qubit doily $9+6$ split; the nonzero ring elements here are not literally the projective-ring points of the Saniga–Planat–Pracna construction.

The full linear determinant stabilizer has order

$$72 = 2 \cdot 36,$$

with the 36-element left/right group preserving the two rulings and transpose exchanging them. Since $|Sp(4,2)| = 720$, the grid orbit has size

$$720/72 = 10,$$

matching the ten grid hyperplanes of $W(3,2)$. Affinely this gives

$$|2^4 : O^+(4,2)| = 1152.$$

The shared order with $W(F_4)$ is not an isomorphism: exact generation gives

$$|Z(2^4 : O^+(4,2))| = 1, \qquad |Z(W(F_4))| = 2,$$

with central $-I$ in the latter.

The integral W_9 firewall also sharpens modulo two. The point/heavy lattice A_3^3 has mod-2 Gram rank 6 and radical dimension 3, while $A_3 \otimes A_3$ has rank 4 and radical dimension 5. These equal the 2-torsion ranks of their discriminant groups

$$(\mathbb{Z}/4)^3, \qquad (\mathbb{Z}/4)^4 \times \mathbb{Z}/16,$$

respectively. Explicitly, the line radical is

$$\{\mathbf{1} \otimes a + b \otimes \mathbf{1} : a, b \in \mathbb{F}_2^3\}, \qquad \dim = 3 + 3 - 1 = 5,$$

whereas the point/heavy radical has one fibre-constant parity vector in each A_3 block.

Finally, over a finite field $\mathbb{F}_q$, rank-one Fourier labels in $M_2(\mathbb{F}_q)$ number $(q-1)(q+1)^2$ and each has $q-1$ factorizations. Thus the point-fibre Radon preimage has kernel

$$\boxed{(q-2)(q-1)(q+1)^2},$$

so $q = 2$ is the unique multiplicity-free case. The sharp binary W_9 identification must therefore not be extrapolated to larger fields without quotienting this factorization kernel.

Boundary. All statements above concern exact finite incidence geometry, integral lattices, finite Fourier/Radon transforms and finite reflection groups. They do not identify the selected $q = 5$ W33 carrier with a physical two-qubit system, and the mod-2 radicals are not physical gauge fields or error syndromes without an independent hardware/code map.

Collision-recovered matrix normalizer, Reye code, Pauli quadric, and all-field Fourier law

Passes 5848–5855 are the clean-namespace publication of an exact packet first staged under Passes 5832–5839 after that range had been reserved by this lane. An unrelated parallel theorem packet subsequently landed under the same numbers. The namespace move changes no finite computation: the corrected producer reuses the same exact routines and replays them before freezing a new certificate.

For

$$G = M_2(\mathbb{F}_2)_+ \rtimes \big(GL_2(2) \times GL_2(2)\big), \qquad |G| = 576,$$

acting by $M \mapsto AMB^{-1} + X$, exhaustive enumeration of all 20,160 elements of $GL_4(2)$ gives a linear normalizer of order 72 and trivial linear centralizer. Matrix transpose is in this normalizer but outside the 36-element left/right subgroup. The regular translation subgroup $T \cong C_2^4$ is $O_2(G)$ because $G/T \cong S_3 \times S_3$ has trivial 2-core. Hence T is characteristic and every S_{16}-normalizer of G lies in $N_{S_{16}}(T) = AGL(4,2)$. Therefore

$$\boxed{|N_{S_{16}}(G)| = 1152}, \qquad \boxed{N_{S_{16}}(G)/G \cong C_2},$$

with transpose representing the nontrivial coset.

For the 12-point carrier $P = \{(w,x) : w \neq 0\}$ and the 16 Reye lines $L_M = \{(w, Mw) : w \neq 0\}$, the binary incidence kernel is

$$C_{\text{Reye}} = [12, 4, 6], \qquad W(z) = 1 + 12z^6 + 3z^8.$$

Its twelve minimum words are exactly the heavy supports

$$c_{\phi,\psi}(w,x) = \phi(x) + \psi(w), \qquad \phi \neq 0,$$

and the three weight-8 words are the $\phi = 0$, $\psi \neq 0$ fiber-pair words. On the saturated common-W_9 lattices,

$$\mathrm{SNF}(R^T) = 1^5\, 2^2\, 4^2$$

has four even invariant factors and 2-adic cokernel valuation six, whereas the heavy transform has Smith form $1^2\, 2^5\, 4^2$, seven even invariant factors and valuation nine. Thus the characteristic-two collapses are coefficient-ring dependent and distinct. The local $[12, 4, 6]$ code is not identified with the global $q = 5$ binary CSS point-code family merely because their minimum distances agree.

The previously cardinality-only comparison with the two-qubit projective-ring geometry can now be sharpened. In binary Pauli coordinates $v = (x_1, z_1, x_2, z_2)$, the published Saniga–Planat–Pracna $9 + 6$ partition is the zero/one split of

$$q_{\text{SPP}}(v) = x_1 z_1 + x_2 z_2 + x_2.$$

For a nonzero dual Fourier label $Y = \left(\begin{smallmatrix} a & b \\ c & d \end{smallmatrix}\right)$, the matrix-rank split is the zero/one split of

$$q_M(Y) = \det Y = ad + bc.$$

Exactly 72 elements $L \in GL_4(2)$ satisfy $q_{\text{SPP}}(L(Y)) = \det Y$ for every Y. One explicit isometry sends the matrix-coordinate basis (a, b, c, d) to (XI, IZ, IY, ZI), maps the nine nonzero rank-one

labels exactly to the published Mermin nine, maps the six units to its six-point complement, and preserves all 105 polarized symplectic pairings. The rank-one 3×3 grid becomes

$$\begin{pmatrix} C_{10} & C_{13} & C_7 \\ C_{12} & C_{15} & C_9 \\ C_{11} & C_{14} & C_8 \end{pmatrix},$$

with every row and column a commuting triple. This is an isomorphism of the *nonzero dual Fourier-label quadratic/symplectic geometry* with the Pauli-point geometry; it is not an identification of the selected $q = 5$ cover points with physical qubit states or observables.

The binary $1 + 9 + 6$ decomposition is the $r = 2$ member of an all-finite-field theorem. For

$$R[(w, x), M] = 1 \iff x = Mw, \qquad 0 \neq w \in \mathbb{F}_r^2, \quad M \in M_2(\mathbb{F}_r),$$

additive Fourier labels split by matrix rank with multiplicities

$$N_0 = 1, \qquad N_1 = (r-1)(r+1)^2, \qquad N_2 = r(r-1)^2(r+1) = |GL_2(r)|.$$

Then

$$\boxed{\operatorname{im} R^T = \mathbf{1} \oplus \mathcal{F}_{\operatorname{rank} 1}}, \qquad \boxed{\ker R = \mathcal{F}_{\operatorname{rank} 2}},$$

and hence

$$\boxed{\operatorname{rank} R = 1 + (r-1)(r+1)^2}.$$

The nonzero squared singular values are $r^2(r^2-1)$ on the constant mode and $r^2(r-1)$ on rank one, while the companion line–hyperplane disjointness relation is

$$D[M, (\phi, \psi)] = 1 \iff \psi = -\phi M.$$

At $r = 2$ every rank-one label has a unique nonzero factorization $Y = \phi^T w^T$. For $r > 2$ each has $r-1$ factorizations, yielding an extra point-side kernel of dimension $(r-2)(r-1)(r+1)^2$. Complete Fourier character-sum replays at $r = 2, 3, 5, 7$ agree exactly; prime powers follow by composing a nontrivial additive character with the field trace.

Three outside-box probes expose the same finite structure from different sides. First, on additive $M_2(\mathbb{F}_2)$,

$$f(Y) = (-1)^{\det Y}$$

is a self-dual bent quadratic with

$$\boxed{\widehat{f}(Z) = 4f(Z)}.$$

Second, the Cayley graph

$$M \sim N \iff M - N \text{ is invertible}$$

is $\mathrm{SRG}(16, 6, 2, 2) = L_2(4)$. Its eight maximal K_4's form exactly two parallel classes, recovering intrinsic 4×4 rook coordinates. Its full automorphism group is

$$\boxed{S_4 \wr C_2}, \qquad |\operatorname{Aut}| = 1152,$$

and these 1,152 permutations are exactly the affine normalizer above. Thus the previously unexplained order-1152 symmetry comes from the six unit-difference directions, not from the Delsarte graph of the Reye two-weight code.

Third, the Reye code is exactly a projective-line puncture of the binary simplex code. Starting from the $[15, 4, 8]$ simplex code on $PG(3, 2)$ and deleting

$$\ell_0 = \{(0, x) : x \neq 0\}$$

gives

$$\boxed{C_{\text{Reye}} = \text{puncture}_{\ell_0}(\text{Simplex}[15, 4, 8])}.$$

For $\phi \neq 0$ the deleted line contains exactly two ones, so weight 8 drops to 6 and yields the twelve heavy words; for $\phi = 0$, $\psi \neq 0$ the deleted line is zero and the three words remain at weight 8. This gives a conceptual proof of $1 + 12z^6 + 3z^8$.

Boundary. These are exact statements in finite affine geometry, coding theory, integral Smith theory, Fourier analysis, graph theory, and two-qubit Pauli incidence. The Pauli bridge lives on nonzero dual Fourier labels and does not supply a $q = 5$ physical-state embedding, dynamics, mass or coupling law, continuum limit, or experimental prediction. The Pass 5832–5839 matrix insert is superseded only because of the namespace collision, not because its finite calculations failed.

Doily quadratic orbits, the six-letter model, and the binary Radon radical

The binary saturated Radon maps sharpen the integral firewall. On the common nine-dimensional rational constituent,

$$\text{im}(R^T \bmod 2) = \text{im}(D \bmod 2) = \text{rad}(A_3 \otimes A_3 \bmod 2), \qquad \dim = 5,$$

while $H^T \bmod 2$ has rank two and lands inside the three-dimensional heavy radical. The three point/heavy radical generators map under R^T and D to one common all-ones 3×3 vector, but are killed by H^T.

On $M_2(\mathbb{F}_2)$ the determinant polar form has sixteen quadratic refinements, split as ten hyperbolic grid forms and six elliptic ovoid forms. Their Boolean chirps satisfy

$$\widehat{(-1)^{q_v}} = +4(-1)^{q_v}$$

for the ten grids and

$$\widehat{(-1)^{q_v}} = -4(-1)^{q_v}$$

for the six ovoids. Thus the grid/ovoid hyperplane split is exactly the positive/negative bent-Walsh sign split.

The six ovoids reconstruct the classical six-letter model internally. Any pair of ovoids meets in one doily point. For a fixed grid, connect two ovoid labels when that point lies in the grid. The resulting graph is $K_{3,3}$, so each grid determines one unordered $3+3$ partition of the six labels, and all ten partitions occur. The 720 symplectic automorphisms induce 720 distinct permutations of the six ovoids, giving

$$\boxed{Sp(4, 2) \cong S_6};$$

the ten-grid action is the induced action on $3 + 3$ partitions.

Every two grids meet in five points forming $K_1 \vee 2K_2$, equivalently two isotropic lines through one center. All $\binom{10}{2} = 45$ intersections are distinct and coincide with the $15\binom{3}{2} = 45$ pointed unordered pairs of doily lines through a point.

The unit-difference rook graph contains the determinant grid literally as the distance-two subconstituent at zero:

$$L_2(4) \supset L_2(3) = \mathrm{SRG}(9, 4, 1, 2).$$

The six neighbours of zero are the units and the nine distance-two vertices are the rank-one matrices. The 72-element determinant stabilizer is the full row/column/ruling symmetry of this 3×3 subgrid.

Under the explicit product-coordinate relabeling, the three coordinates removed in the simplex $[15, 4, 8] \to [12, 4, 6]$ puncture form one of exactly two projective lines wholly contained in the six unit points. Both are nonisotropic, so the puncture does not delete a doily context.

Boundary. These are exact finite-geometry, binary-lattice, coding and Fourier statements. The six-letter model is not a particle multiplet, the Walsh sign is not a q=5 physical phase, and the mod-2 radicals are not physical gauge fields without a separately verified physical map.

Coherent determinant closure, exact binary Radon sequence, and the all-field rank-metric graph

On $V = M_2(\mathbb{F}_2)$ put $q(X) = \det X$ and $B(X, Y) = q(X + Y) + q(X) + q(Y)$. Color ordered pairs by diagonal status, $q(X + Y)$ and $B(X, Y)$. Exact coherent refinement stabilizes as

$$\boxed{5 \longrightarrow 15 \longrightarrow 15}.$$

The determinant stabilizer $O^+(4, 2)$ has order 72 and exactly the same fifteen orbitals, of sizes

$$1, 6, 6, 6, 9, 9, 9, 12, 18, 18, 18, 36, 36, 36, 36.$$

Thus determinant-polar commutation together with unit-difference adjacency recovers the full orbital coherent configuration. Its orbital algebra has dimension 15, center dimension 4, and over $\mathbb{C}$

$$\boxed{\mathcal{A} \cong M_3(\mathbb{C}) \oplus M_2(\mathbb{C}) \oplus \mathbb{C} \oplus \mathbb{C}}.$$

The 16-point permutation module has multiplicity pattern $1^3 \oplus \varepsilon \oplus V_{4,a} \oplus 2V_{4,b}$. Because the vertex orbits are 1+9+6, this is a three-fibre coherent configuration rather than a homogeneous association scheme.

The local Reye binary kernel $C_R = [12, 4, 6]$ does *not* embed by support extension into the $q = 5$ footprint check code $C_F = [156, 65, 12]$: a weight-six word would contradict $d(C_F) = 12$. More strongly, shortening C_F to any 12 coordinates has dimension at most one, since every nonzero shortened word must have all twelve coordinates in its support. Hence the local Reye defect is not a literal $q = 5$ CSS-check subcode. This does not rule out a relation to the line-code logical normalizer C_W; no canonical map from the moving twelve cover labels to the 156 $W(3, 5)$ point coordinates is certified here.

The correct local interface is instead integral. For the saturated Radon map $T_R : A_3^3 \to A_3 \otimes A_3$,

$$\boxed{T_R^T G_L T_R = 4G_P}, \qquad \det T_R = -64, \qquad \mathrm{SNF}(T_R) = 1^5\, 2^2\, 4^2.$$

Modulo two, its four-dimensional kernel maps objectwise to the complete Reye code, while its image is exactly the five-dimensional radical of the line Gram form:

$$\boxed{0 \to C_R \to \mathbb{F}_2^9 \xrightarrow{\bar{T}_R} \mathrm{Rad}(A_3 \otimes A_3 \bmod 2) \to 0}.$$

The remaining four-dimensional quotient inherits the even-lattice quadratic $q_L(x) = x^T G_L x/2 \pmod 2$. In an explicit complement basis it is literally

$$\boxed{q_L(a,b,c,d) = ad + bc = \det\begin{pmatrix} a & b \\ c & d \end{pmatrix}},$$

with $10+6$ value split. Thus the same integral morphism places the Reye code in its mod-two kernel and the determinant/two-qubit plus-type $9+6$ geometry in its mod-two cokernel; these objects are related, not identified.

For every finite field $\mathbb{F}_r$, the unit-difference Cayley graph

$$X \sim Y \iff \det(X - Y) \neq 0$$

is the complement of the bilinear-forms graph $H_r(2,2)$. Additive Fourier characters give

$$\boxed{\operatorname{Spec}\Gamma_r = k^1 \oplus r^{\,k} \oplus [-r(r-1)]^{(r-1)(r+1)^2}}, \qquad k = r(r-1)^2(r+1),$$

and hence

$$\boxed{(v,k,\lambda,\mu) = (r^4,\ r(r-1)^2(r+1),\ r(r^3-2r^2-r+3),\ r(r-1)(r^2-r-1))}.$$

The binary $L_2(4)$ graph is therefore the first member of this all-field rank-metric family. The classical full automorphism group of $H_r(2,2)$, and hence of its complement, is the affine semilinear left/right group extended by factor transpose; at $r = 2$ its order is 1152.

The 72 determinant-to-Pauli quadratic isometries also lift cleanly through the two-qubit Clifford quotient. Their relative group is $O^+(4,2) < Sp_4(2)$ with orders $72 < 720$. Conjugating the SPP quadratic form to the standard non-entangling form

$$q_{NE} = s(x_1,z_1) + s(x_2,z_2), \qquad s(x,z) = x + z + xz,$$

identifies its stabilizer with the 72-element local-factor-plus-swap quotient. Including the projective Pauli group of order 16 gives

$$\boxed{16 \cdot 72 = 1152},$$

which is Clifford-conjugate to the non-entangling two-qubit Clifford group classified by Kubischta–Teixeira as generated by local Cliffords and SWAP. This is a Clifford-conjugacy statement, not a claim that the original SPP frame is already the standard tensor-product frame.

Three outside-box probes close additional structure. For odd r and quadratic multiplicative character $\chi(0) = 0$,

$$\boxed{\widehat{\chi(\det)}(Y) = r^2\chi(-1)\chi(\det Y)},$$

so the transform vanishes on the singular rank-zero/rank-one labels. This is an explicit 2×2 instance of the established finite-field prehomogeneous-vector-space Fourier functional-equation framework. At $r = 3$, exhaustive clique enumeration of the unit-difference graph gives 648 maximum 9-cliques; under translations, left/right $GL_2(3)$ and transpose they split as

$$\boxed{162 + 486}.$$

The first orbit is exactly the affine cosets of the 18 anisotropic two-planes and has affine span dimension two; every clique in the 486-orbit has affine span dimension four, giving a genuinely nonlinear maximum-rank-distance orbit. Finally, the Reye code dual is

$$C_R^{\perp} = [12, 8, 3],$$

and its sixteen minimum weight-three supports are exactly the original Reye triples. The twelve minimum weight-six supports of C_R are exactly the heavy sets; their disjointness incidence has degrees 3 and 4 and reproduces the second $12_4, 16_3$ Reye copy.

Evidence boundary. All new statements above are exact finite algebra, coding, lattice, Fourier, or graph statements. Bilinear-forms graph automorphisms, MRD terminology and the non-entangling Clifford group are prior-art identifications. No q=5 physical qubit embedding, continuum dynamics, particle assignment, mass, coupling, fault-tolerance threshold or experimental prediction is inferred.

Passes 5888–5895: exact W33 Ihara factorization and graph-identity firewall

Passes 5880–5887 are superseded because they conflated the canonical $W(3,3)$ collinearity graph, a separate signed 4-regular 40-line mesh, and a 33-vertex circulant surrogate. The canonical collinearity graph is

$$\mathrm{SRG}(40, 12, 2, 4), \qquad |E| = 240,$$

with adjacency spectrum

$$12^1 \oplus 2^{24} \oplus (-4)^{15}.$$

Its Hashimoto operator therefore has 480 directed-edge states, outdegree 11, and exact Ihara–Bass factorization

$$\det(I - uB) = (1-u^2)^{200}(1 - 12u + 11u^2)(1 - 2u + 11u^2)^{24}(1 + 4u + 11u^2)^{15}.$$

Equivalently,

$$\mathrm{spec}(B) = 11^1 \oplus 1^{201} \oplus (-1)^{200} \oplus (1 \pm i\sqrt{10})^{24} \oplus (-2 \pm i\sqrt{7})^{15}.$$

Thus the exact surviving equal-modulus statement is

$$\boxed{\text{the 78 adjacency-induced nontrivial modes have } |\lambda| = \sqrt{11}.}$$

The structural ± 1 modes and Perron mode are not part of this shell.

The same finite spectrum contains only four distinct nontrivial phases, with multiplicities $24, 24, 15, 15$, so no eigenphase-equidistribution theorem follows. In particular Ihara data alone does not determine a physical free spectral range, Fabry–Perot finesse, Shannon capacity, or absolute loss/Q. Those require an independent propagation/coupling model specifying delays or lengths, dispersion, coupler amplitudes/losses, boundary conditions, and the map from the dimensionless spectral parameter to physical frequency.

Graph-identity firewall. The symbols must remain distinct: the canonical $W33$ collinearity graph has $(v, k, q_{\mathrm{nb}}) = (40, 12, 11)$; the Pass 5706 signed 40-line mesh is a separate 4-regular object with $q_{\mathrm{nb}} = 3$; and the Pass 5880 surrogate is the 33-vertex 4-regular circulant with jumps $\pm 1, \pm 11$, which is not canonical $W(3,3)$ and is not Ramanujan. No theorem may be transported between these objects by the label "W33" alone.

Passes 5913–5920: the binary matrix quotient is exactly a two-qubit doily

Write

$$M = \begin{pmatrix} a & b \\ c & d \end{pmatrix} \in M_2(\mathbb{F}_2), \qquad \Phi(M) = (a, d, b, c) = (x_1, z_1, x_2, z_2).$$

Then

$$\det M = ad + bc = x_1 z_1 + x_2 z_2$$

and, after polarization,

$$\det(M + N) + \det M + \det N = \langle \Phi(M), \Phi(N) \rangle_{\mathrm{sp}}.$$

Thus the determinant polarization is exactly the standard two-qubit Pauli commutation form. Removing the zero matrix leaves fifteen points whose commutation graph is

$$\boxed{\mathrm{SRG}(15, 6, 1, 3) = W(3, 2).}$$

The rank stratification is the geometric $9 + 6$ split:

$$\boxed{15 = 9_{\det=0,\, M\neq 0} + 6_{\det=1}.}$$

The nine rank-one matrices are the outer products uv^T with $0 \neq u, v \in \mathbb{F}_2^2$, hence form a literal 3×3 grid with induced point graph $\mathrm{SRG}(9, 4, 1, 2)$. The six units induce $K_{3,3}$, and the cross-commutation degrees are 2 from the grid side and 3 from the six-point side.

This agrees objectwise with the classical two-qubit $9 + 6$ factorization. In the Saniga–Planat–Pracna coordinate chart, the displayed grid $\{C_7, \ldots, C_{15}\}$ is the zero set of $q_0(x) + x_2$, while the determinant grid is the zero set of q_0. The local phase Clifford on the second qubit,

$$S_2 : (x_1, z_1, x_2, z_2) \mapsto (x_1, z_1, x_2, z_2 + x_2),$$

is symplectic and satisfies $q_0(S_2 x) = q_0(x) + x_2$, so it maps the displayed source grid exactly onto the determinant/rank-one grid.

The same model recovers the complete doily hyperplane census. The quadratic forms

$$q_v(x) = q_0(x) + \langle v, x \rangle$$

produce ten plus-type nine-point grids and six minus-type five-point ovoids; the complement of every ovoid induces the Petersen graph. The fifteen nonzero vectors also give the fifteen symplectic perp hyperplanes. Hence

$$\boxed{\text{10 grids,} \quad \text{6 ovoids,} \quad \text{15 perp-sets.}}$$

Radon quotient consequence. The four-dimensional mod-2 determinant quotient isolated in Pass 5876 is therefore no longer anonymous: its fifteen nonzero classes carry $W(3, 2)$, with the nine $q = 0$ classes forming the grid and the six $q = 1$ classes its complement.

Boundary. The affine nonzero matrices are not literally the fifteen projective-ring-line pairs used in the classical $P^1(M_2(\mathbb{F}_2))$ construction. What is proved is an explicit finite symplectic/local-Clifford isomorphism of the same two-qubit doily geometry. No physical q=5 two-qubit embedding, entanglement classification, particle assignment, or continuum claim follows.

Passes 5957–5964: physical prediction claims downgraded to ansatz tier

A source-code audit of the Pass 5913–5956 physical producers separates exact finite arithmetic from an independently derived observable map. The following items are *not* presently certified as physical predictions.

- The claimed L_∞ mass hierarchy is not an evaluated Maurer–Cartan solution: the producer records a nonzero residual $k - \lambda = 10$ and imports the quoted mass-denominator formulas instead of computing verified higher brackets.
- The claimed four-dimensional Weyl law is circular: the refinement function is defined with multiplicity factor n^4 and the same n^4 scaling is then used to infer $d = 4$. No physical four-volume follows from that definition.
- The electron packet $2 \cdot 49 \cdot 17 \cdot 16 \cdot 13 = 346528$ is exact arithmetic, but no mass/Yukawa operator forces its reciprocal to be m_e/m_t; the reported "sigma" was not obtained from a statistical uncertainty model.
- The 1818 MeV Yang–Mills producer explicitly solves an effective QCD scale from the target value, so the target is back-solved rather than predicted.
- The neutrino producer first obtains a factor four too large, then replaces 24 by 6 to hit 10,221,120; the integer identity survives, not the mass prediction.
- The 45 tritangent-plane count and the octahedron spanning-tree count $\tau(K_{2,2,2}) = 384$ survive exactly, but the maps $r := 1/45$ and $m_{\text{scalar}} := m_H(384/15)$ are assumed rather than derived from an inflationary action or a scalar pole equation.

Accordingly the Pass 5913–5956 physical claims are assigned **ANSATZ/COMPARISON-ONLY** status. Their exact combinatorial subclaims may remain in the corpus. Promotion to prediction status requires an independent dynamics theorem that supplies the observable map without inserting the desired scaling exponent, solving an input scale from the target, or repairing factors after comparison with the target.

Passes 6017–6024: post-6016 closure claims repaired

A producer-level audit of the Pass 5957–6016 closure packet found four claim-tier failures and repaired the live artifacts.

CE2 anchor 22. The historical producer did not enumerate an actual $W(3,3)$ automorphism orbit. It imported three witness rows and generated the remainder from a hard-coded coefficient rule on integer labels; its cancellation test checked only denominator integrality. Hence

anchor $(22, *)$ is open beyond the three imported witnesses.

Yukawa radical pairs. For

$$A = \begin{pmatrix} 367 & -55 \\ -55 & 175 \end{pmatrix}, \qquad B = \begin{pmatrix} 323 & 275 \\ 275 & 659 \end{pmatrix},$$

one has

$$(\operatorname{tr} A, \det A, \Delta_A) = (542, 61200, 48964),$$

$$(\operatorname{tr} B, \det B, \Delta_B) = (982, 137232, 415396),$$

so both displayed blocks have real spectra. However

$$A(1,1)^T = (312, 120)^T, \qquad B(1,1)^T = (598, 934)^T,$$

so $(1,1)$ is not an eigenvector of either block. The proposed generation-flag alignment is therefore refuted by the displayed matrices themselves.

K3 glue avatar. The advertised generator

$$(780, 7944, 62600, 53979)$$

has

$$\boxed{\gcd = 1},$$

not 217, so the historical producer's assertion failed. The identity $(217/12)780 = 14105$ survives as arithmetic. The nonzero I_{81} tail-to-head block was inserted by hand, hence the square-zero 162-dimensional operator is a *formal avatar*, not a realized K3 curvature/glue witness.

Qiskit avatar. The historical 21-qubit file preassigned a marked CE2/Yukawa/glue shard and its demonstration circuit only applied Hadamards and measurement. No reversible predicate or phase-marking circuit computed the theorem conditions. The live artifact is therefore classified as an encoding/search scaffold, with any Grover iteration count conditional on a future implemented predicate.

Inherited physics. The closure ledger now inherits the Pass 5957–5964 correction: the quoted Yang–Mills, neutrino, inflation and scalar-resonance numbers remain **ANSATZ/COMPARISON-ONLY**, not proved physical observables.

The repaired evidence rule is fail-closed: an invented label rule is not a group orbit computation, an inserted normal form is not a geometric realization, and a preassigned marked state is not a theorem oracle.

Passes 6137–6144: CE2 orbit and K3 witness claims fail-closed

The Pass 6041–6136 continuation did not establish the claimed CE2 global closure. Anchor 23 retained five seed rows but supplied family totals without enumerating orbit rows or constructing the automorphism action. Anchors 24–25 were introduced by analogy, and the anchor 26–39 batch scripts contained no CE2 rows at all: they assigned a constant coverage count and the label `CLOSED`. Accordingly,

$$\boxed{\text{CE2 global orbit closure remains open.}}$$

The live producers now retain only evidenced seed/hypothesis status and withdraw the canned family counts.

The historical global verifier was internally self-refuting: it constructed 20 ledger entries, printed $20/40 = 50\%$, asserted only `total>=20`, and then printed `VERIFIED COMPLETE`. The live verifier is fail-closed and counts only explicitly evidenced rows.

The historical K3 witness scan likewise did not scan the current K3 object. It allocated a fresh zero matrix of shape 2428×36 and confirmed that it had no nonzero entries. The corrected status is therefore

$$\boxed{\text{NO OBJECT LOADED — K3 witness scan not run.}}$$

A future scan must load or reconstruct the target curvature/cochain object, freeze its source hash, prove the coordinate map to the active block, and compute the zero/nonzero result from that object.

Evidence contract. An orbit closure requires explicit object values, a verified action or complete enumerator, coverage derived from enumerated objects, and a stable source certificate. A witness scan requires an actual target object plus a certified coordinate map. Analogy-generated rows, repeated count dictionaries and zero templates are not theorem certificates.

Passes 6233–6240: conditional scaffolds separated from certified geometry

The Pass 6189–6232 continuation is retained as useful problem scaffolding, but its historical claim tiers are reduced to the evidence actually supplied. The CE2 global orbit closure remains open, no real K3 curvature/cochain object has yet been loaded for the proposed witness scan, and the equal-coordinate Yukawa generation flag was already refuted by Pass 6017–6024.

The transport comparison between a chosen positive plane and an abstract hyperbolic plane therefore has only conditional status: if those were the actual inherited carrier forms, their signature mismatch would forbid a raw real isometry. It does not presently identify the project family/U1 carriers or supply a transport cocycle.

Likewise,

$$2428 \cdot 36 \cdot 2 = 174816$$

is the exact number of single-entry nonzero assignments in a hypothetical 2428×36 matrix over $\mathbb{F}_3$. It is an ambient upper bound, not an admissible K3-deformation count. The admissible set remains undefined until the actual K3 object, coordinate map and cocycle/curvature/lattice constraints are loaded and imposed.

Boundary. A scaffold may parameterize an open problem but cannot certify the geometry that it assumes. Provenance of the carriers and the defining equations of the admissible set precede any closure, obstruction or candidate-count theorem.

74.6 A frozen 51-point partial ovoid of $W(3,9)$ and its local rigidity

The previously recorded lower bound $\alpha(W(3,9)) \geq 51$ lacked a stored witness. Passes 7122–7129 repair that evidence gap. In the exact model $\mathbb{F}_9 = \mathbb{F}_3[i]/(i^2+1)$, an explicit set S of 51 projective points is now frozen and all $\binom{51}{2} = 1275$ pairs are verified non-collinear. Hence

$$\boxed{\alpha(W(3,9)) \geq 51}$$

now has a re-verifiable witness rather than only an incumbent size.

For $v \notin S$, put $b(v) = |N(v) \cap S|$. Its exact blocker distribution is

$$1^1,\ 2^{22},\ 3^{50},\ 4^{102},\ 5^{156},\ 6^{120},\ 7^{142},\ 8^{107},\ 9^{53},\ 10^{16},$$

with the SRG checks

$$\sum b(v) = 51 \cdot 90 = 4590, \qquad \sum \binom{b(v)}{2} = \binom{51}{2} 10 = 12750.$$

There is no zero-blocker, so this witness is inclusion-maximal. There is exactly one one-blocker, yielding a unique 1-for-1 move; the resulting second 51-set has only the reverse move. Exhaustive

augmenting-set search further proves that neither endpoint admits a gain-one exchange removing at most seven incumbent points.

The search neighborhood was also strengthened: after retaining a core $K \subset S$, the residual exact MILP is allowed to choose from every point of $W(3,9)$ compatible with K, rather than only from a previously freed local region. This "global-compatible" neighborhood independently recovered size 51 from a smaller incumbent. It has not produced a certified 52-set, and no negative search result is used as an upper bound.

Finally, the nontrivial Frobenius automorphism $x \mapsto x^3$ sends the frozen witness to a distinct 51-set with intersection size four. Thus this particular witness does not descend setwise to the $\mathbb{F}_3$-fixed structure.

Evidence boundary. These are exact finite-geometric and search-certificate statements. They do not prove $\alpha(W(3,9)) = 51$, do not rule out 52, do not validate the zero-degree-of-freedom quadratic interpolation, and carry no physical interpretation. The published Tallini upper bound remains 73.

74.7 A blocker-deficiency reformulation and an involutory symmetry of the $q = 9$ 51-set

Let S denote the verified 51-point partial ovoid of $W(3,9)$ frozen in the computational ledger. For an independent set $T \subseteq W(3,9) \setminus S$, define its blocker union

$$B_S(T) = \bigcup_{v \in T} \big(N(v) \cap S\big).$$

Then $(S \setminus B_S(T)) \cup T$ is independent. Conversely, if S' is any independent set with $|S'| > |S|$, then $T = S' \setminus S$ is independent and every point of $B_S(T)$ belongs to $S \setminus S'$, whence $|B_S(T)| < |T|$. Therefore

$$\alpha(W(3,9)) > 51 \quad \Longleftrightarrow \quad \exists\, T \text{ independent outside } S : \ |B_S(T)| - |T| < 0. \tag{10}$$

This is a global reformulation, not merely a local-search criterion. The unrestricted integer program remains open; the exact radius certificate of the preceding packet proves nonnegative deficiency for $|T| \le 8$ only.

A second exact computation identifies the setwise projective-semilinear symplectic stabilizer of S. For four projective points one may form the projective triple of perfect-matching products

$$[\, \langle v,a\rangle\langle b,c\rangle : \langle v,b\rangle\langle c,a\rangle : \langle v,c\rangle\langle a,b\rangle \,].$$

After quotienting by overall scalar, coordinate permutation, and the nontrivial automorphism of $\mathbb{F}_9$, these four-point types give an intrinsic fingerprint. On S the vertex fingerprints split as $1+25\cdot 2$, while the induced edge fingerprints force all 25 possible pair-flips to agree. The nontrivial flip is realised by

$$A = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 1 & 2 & 3 & 6 \\ 3 & 0 & 5 & 6 \\ 3 & 0 & 4 & 7 \end{pmatrix}, \qquad A^2 = I, \qquad A^{\mathsf{T}} J A = 2J,$$

with entries in $\mathbb{F}_9$ and $2 = -1$ in characteristic three. A projective-frame check against both field automorphisms excludes additional semilinear lifts. Hence

$$\mathrm{Stab}_{P\Gamma Sp(4,9)}(S) \cong C_2.$$

The involution has two 2-dimensional eigenspaces, and because its symplectic-similitude multiplier is -1, each eigenspace is totally isotropic. Thus its projective fixed locus consists of two generator lines of $W(3,9)$, ten points on each. The unique fixed witness point is index 80; the unique one-blocker outside point, index 40, is also fixed and lies on the same generator line. Consequently the previously observed two-state local swap

$$S \longleftrightarrow S \setminus \{80\} \cup \{40\}$$

has a structural explanation: it changes which fixed point on one invariant generator line is selected.

The blocker histogram refines equivariantly under this C_2. On the 769-point complement the same intrinsic four-point fingerprints produce exactly 19 singleton classes and 375 doubletons, objectwise equal to the fixed points and two-cycles of the involution. Thus the blocker counts are a coarse quotient of an intrinsic orbit partition rather than isolated search statistics.

There is also an exact rank-four Gram compression. For the four anchor positions $(0,1,2,5)$ in S, the principal Gram block G is nonsingular. If r_i records the four symplectic pairings of point i with those anchors, then all 51^2 Gram entries satisfy

$$A_{ij} = -r_i G^{-1} r_j^{\mathsf{T}}.$$

For a hypothetical 52-set this reduces the raw $\binom{52}{2} = 1326$ off-diagonal variables to $48 \times 4 + 6 = 198$ field variables before further gauge reduction, with the extremal condition becoming the nonvanishing of every reconstructed off-diagonal entry.

As a positive control, an explicit 33-point partial ovoid of $W(3,7)$ was frozen and replayed. The same invariant machinery again recovers a C_2 projective-similitude stabilizer and a two-generator-line fixed locus. This is compared only as a control with the exhaustive small-q computations of Cimráková, De Winter, Fack and Storme; no novelty claim is made for the $q = 7$ extremal value.

Two further exact probes sharpen the boundary. First, the Frobenius conjugate $F(S)$ satisfies $|S \cap F(S)| = 4$. On the remaining $47 + 47$ points, cross-collinearity is bipartite with a perfect matching of size 47; Kőnig's theorem therefore gives

$$\alpha\big(W(3,9)[S \cup F(S)]\big) = 51,$$

so no recombination using only the two Galois-conjugate copies can produce 52. Second, applying the quadratic character to the nonzero Gram entries yields a symmetric 51×51 sign matrix at $q = 9$ (full rational rank 51) but a skew-symmetric 33×33 sign matrix at $q = 7$ (rational rank 32). This is the elementary distinction $\chi(-1) = +1$ for $q \equiv 1 \pmod 4$ and $\chi(-1) = -1$ for $q \equiv 3 \pmod 4$; it is recorded as a finite-field resonance only, not as a physical chirality derivation.

74.8 C_2 normal form, finite Gram reduction, and a semilinear six-witness configuration

Let g be the involution stabilizing the verified 51-point partial ovoid $S \subset W(3,9)$. In dual Lagrangian bases $E_+ \oplus E_-$ it takes the normal form

$$g = \operatorname{diag}(I_2, -I_2), \qquad \langle (u,w), (u',w') \rangle = u \cdot w' - w \cdot u'.$$

Thus S consists of one fixed point together with 25 two-cycles. Each nonfixed cycle lies on a unique transversal joining the two fixed generator lines. More generally, for every odd q, a non-scalar projective involutory symplectic similitude of multiplier -1 has two two-dimensional totally

isotropic eigenspaces, hence fixed locus two disjoint generator lines. Its admissible nonfixed two-cycles number

$$\frac{q(q^2-1)}{2},$$

while the non-isotropic transversals number $q(q+1)$, with $(q-1)/2$ involution-pairs on each transversal.

The rank-four Gram search for a hypothetical 52-set admits a further exact gauge quotient. A nonsingular four-anchor block has one of only eight canonical matching-product types over $\mathbb{F}_9$,

$$(1,1,2),(1,1,3),(1,1,4),(1,1,5),(1,2,3),(1,2,4),(1,3,4),(1,3,5).$$

After fixing a type, every remaining point is represented by a normalized row $(1,a,b,c)$ with $a,b,c \in \mathbb{F}_9^*$, so there are exactly 512 row states. Consequently a 52-point partial ovoid exists if and only if at least one of the eight corresponding compatibility graphs contains a 48-clique. The known 51-set lies in type $(1,3,5)$ and supplies an exact 47-clique. No 48-clique impossibility is claimed here.

Collapsing the involution gives an all-q weighted conflict graph with $2(q+1)$ fixed weight-one nodes and $q(q^2-1)/2$ admissible weight-two nodes. Their valencies are

$$d_{\text{fixed}} = \frac{q^2+q+2}{2}, \qquad d_{\text{pair}} = \frac{2q^2-q+3}{2}.$$

At $q=9$ the quotient has 380 nodes and 14500 edges; at $q=7$ it has 184 nodes and 4180 edges. A compact spectral formula has been verified computationally at $q=3,5,7,9$ but remains a conjecture rather than an all-q theorem.

The transversal carrier itself has a matrix realization. A non-isotropic endpoint pair $([u],[w])$ determines

$$E = \frac{wu^{\mathsf{T}}}{u\cdot w}, \qquad E^2 = E, \quad \operatorname{rank} E = 1, \quad \operatorname{tr} E = 1.$$

Hence non-isotropic transversals are canonically the $q(q+1)$ rank-one trace-one idempotents of $M_2(\mathbb{F}_q)$. This is distinct from the larger nonzero rank-one Fourier sector used in the earlier matrix-ring construction.

Finally let $F : x \mapsto x^3$ be Frobenius on $\mathbb{F}_9$. The permutations induced by g and F generate a dihedral group of order 12 with $|gF| = 6$. Its orbit on S consists of six 51-point partial ovoids, every pair intersecting in exactly four points. Their union has 248 points with multiplicities $192\cdot 1 + 54\cdot 2 + 2\cdot 3$; the two triple points are graph indices 50 and 80. The six binary incidence vectors generate a

$$\boxed{[248,6,51]_2}$$

code with integer generator Gram matrix $47I_6 + 4J_6$ and binary Gram matrix I_6. Its weight enumerator is

$$1 + 6z^{51} + 15z^{94} + 18z^{129} + 2z^{133} + 9z^{156} + 6z^{160} + 6z^{179} + z^{194}.$$

These are finite symplectic, matrix, and coding statements only; in particular they neither establish $\alpha(W(3,9)) = 51$ nor imply a physical or CSS identification.

74.9 The C_2 quotient as a PGL_2 involution scheme and the semilinear hexad

Continue with the involution normal form

$$V = E_+ \oplus E_-, \qquad g(u,w) = (u,-w), \qquad B((u,w),(u',w')) = u\cdot w' - w\cdot u'.$$

For an eligible nonfixed orbit $u \cdot w \neq 0$, define

$$M(u,w) = \begin{pmatrix} u_1 & u_2 \\ w_2 & -w_1 \end{pmatrix}.$$

Then $\det M = -u \cdot w \neq 0$. Projective rescaling acts by $M \mapsto cM$ and g acts by left multiplication by $D = \mathrm{diag}(1,-1)$. Consequently the eligible pair vertices are canonically

$$\boxed{\mathrm{PGL}_2(q)/\langle D \rangle}, \qquad \# = \frac{q(q^2-1)}{2}.$$

If $R = MN^{-1}$, two pair vertices conflict exactly when

$$R_{11} = \pm R_{22},$$

equivalently when $\mathrm{tr}\, R = 0$ or $\mathrm{tr}(DR) = 0$. Thus R or DR is a projective involution. In the original symplectic coordinates the same condition factorizes as

$$(u \cdot w')^2 - (w \cdot u')^2 = -B(X,Y)B(X,DY)$$

up to the fixed sign convention for D.

Let $G = \mathrm{PGL}_2(q)$, $H = \langle D \rangle$, and let W be the Schreier operator obtained by summing the action of the complete projective involution class on G/H. The standard character calculation on $\mathrm{Ind}_H^G(1)$ gives

$$\mathrm{Spec}\, W = \{(q^2)^1,\ q^{\frac{(q+1)(q^2-q-4)}{4}},\ (-q)^{\frac{q(q-1)^2}{4}},\ 1^{\frac{q(q+1)}{2}}\}.$$

The weighted duplicate support is the split-torus normalizer graph

$$R_0 \cong \frac{q(q+1)}{2} K_{h,h}, \qquad h = \frac{q-1}{2},$$

and the simple pair graph is exactly $A_{\mathrm{pair}} = W - I - R_0$. Decomposing the commuting W and R_0 actions yields

λ	multiplicity
$(2q^2-q-1)/2$	1
$q-1$	$q(q-3)(q+1)/4$
$-(q+1)$	$q(q-3)(q-1)/4$
$(q-1)/2$	$(q-1)(q+2)/2$
$-(q+3)/2$	$q(q-1)/2$
0	$q(q-3)/2$
$-(q-1)/2$	q.

Adding the two fixed generator lines and their exact incidence block proves the previously conjectural full quotient spectrum for every odd q: besides the two simple roots of

$$2x^2 - (2q^2+q+1)x + (2q^3-q^2-1) = 0,$$

the eigenvalues and multiplicities are

$q-1$	$(q+1)(q^2-3q+4)/4$
$-(q+1)$	$q(q-3)(q-1)/4$
$-(q+3)/2$	$q(q+1)/2$
$(q-1)/2$	$(q-1)(q+2)/2$
0	$q(q-3)/2$
$-(q-1)$	q.

Hence the Pass 7141 spectral formula is upgraded from computational conjecture to theorem.

For the $q = 9$ witness, the involution together with field Frobenius generates a D_{12}-orbit of six 51-point partial ovoids. Since a single witness has exact $P\Gamma Sp(4,9)$ stabilizer C_2, any ambient stabilizer of the six-set has order at most $6 \cdot 2 = 12$; the known D_{12} attains this bound. Therefore

$$\boxed{\mathrm{Stab}_{P\Gamma Sp(4,9)}(\mathcal{H}) = D_{12}}.$$

As $|P\Gamma Sp(4,9)| = 6{,}886{,}425{,}600$, the hexad orbit has size 573,868,800. Multiplying by six equals the witness-orbit size 3,443,212,800, so every witness in this orbit belongs to exactly one such D_{12} hexad.

The six binary incidence generators on their 248-point union have column multiplicities: six singleton columns with multiplicity 32, six internal pair columns with multiplicity 3, nine cross-pair columns with multiplicity 4, and two complementary triple columns with multiplicity 1. Their $[248, 6, 51]_2$ code has dual distance 2 and exactly

$$\boxed{3048}$$

weight-two dual words. Its outer column-pattern group is $S_3 \wr C_2$ of order 72, while the ambient geometric hexad group has order 12; thus the code has an exact outer/geometric symmetry index 6. The full coordinate-permutation group is

$$\big((S_{32})^6 \times (S_4)^9 \times (S_3)^6\big) \rtimes (S_3 \wr C_2).$$

Puncturing one of the two complementary triple coordinates gives a $[247, 6, 50]_2$ code and breaks the outer block swap, reducing the outer group to $S_3 \times S_3$ of order 36; puncturing both gives $[246, 6, 50]_2$ and restores the $S_3 \wr C_2$ outer group of order 72.

Finally, the eight normalized $q = 9$ rank-four Gram cases are handled by a separate exact SAT replay. No statement $\alpha(W(3,9)) = 51$ is inferred from this subsection unless the frozen Pass 7146 certificate independently records UNSAT at residual clique size 48 in all eight anchor cases.

74.10 The Gram big cell, the hexad lifting invariant, and an audited E_8 boundary

The normalized rank-four Gram state space from Pass 7139 has a simple matrix stratification. Writing

$$(1, a, b, c) \longleftrightarrow \begin{pmatrix} 1 & a \\ b & c \end{pmatrix}, \qquad a, b, c \in \mathbb{F}_9^{\times},$$

there are exactly

$$\boxed{512 = 448 + 64}$$

states, with 64 rank-one boundary matrices ($c = ab$) and 448 invertible matrices. The invertible states are precisely the all-entry-nonzero big cell of $\mathrm{PGL}_2(9)$ after normalizing the upper-left entry to one. The involution $D = \mathrm{diag}(1, -1)$ acts freely on this big cell, yielding 224 of the 360 nodes of $\mathrm{PGL}_2(9)/\langle D \rangle$; the remaining 136 quotient nodes lie outside the big cell. Thus the Gram and involution-quotient models have an exact overlap but are not the same finite object.

The code/geometry symmetry gap from Pass 7152 also admits a concrete resolution. The two complementary triple columns split the six generators into two 3-sets, and the nine cross-pair column types form $K_{3,3}$. Hence the abstract outer group is

$$\mathrm{Aut}(K_{3,3}) \cong S_3 \wr C_2, \qquad |S_3 \wr C_2| = 72.$$

The actual geometric product AF acts on the six witnesses as the cycle

$$0 \to 1 \to 5 \to 4 \to 2 \to 3 \to 0.$$

Its edges are a Hamiltonian $C_6 \subset K_{3,3}$; the three omitted cross edges form a perfect matching. Since $K_{3,3}$ has six perfect matchings, the stabilizer of one complementary Hamiltonian C_6 has order $72/6 = 12$ and is D_{12}. Consequently a code-outer symmetry lifts to the ambient hexad geometry exactly when it preserves this selected C_6 (equivalently, the omitted perfect matching).

The two-channel involution theorem extends to all symplectic ranks. For odd q, let

$$V = U \oplus U^*, \qquad B((u,w),(u',w')) = u(w') - u'(w), \qquad D(u,w) = (u,-w),$$

with $\dim U = n$. Then the fixed projective locus has size

$$2\frac{q^n-1}{q-1},$$

the number of nonisotropic transversals is

$$q^{n-1}\frac{q^n-1}{q-1},$$

and the number of eligible D-pair nodes is

$$\boxed{\frac{q^{n-1}(q^n-1)}{2}}.$$

For two eligible orbits represented by X, Y, a conflict occurs exactly when

$$B(X,Y) = 0 \quad \text{or} \quad B(X,DY) = 0.$$

The extra $\mathrm{PGL}_2(q)$ Schreier description of Pass 7147 is special to $n = 2$ and is not asserted in higher rank.

The $q = 9$ witness orbit itself is the homogeneous bundle

$$\mathrm{P\Gamma Sp}(4,9)/C_2 \longrightarrow \mathrm{P\Gamma Sp}(4,9)/D_{12},$$

whose fibers are the six vertices of the natural D_{12} hexagon. The base has 573,868,800 hexads and the total space 3,443,212,800 witnesses, with the order-six AF element transporting the C_6 structure equivariantly from fiber to fiber.

There is also a new binary-projective 40-point object. The 248 code coordinates collapse to 23 distinct nonzero columns of $\mathbb{F}_2^6$: all six weight-one words, all fifteen weight-two words, and two complementary weight-three words. If the complementary triples define $\mathbb{F}_2^6 = A \oplus B$ with $\dim A = \dim B = 3$, then these 23 points are

$$(A \setminus \{0\}) \ \cup \ (B \setminus \{0\}) \ \cup \ \{e + f : e \in E_A, \ f \in E_B\},$$

where E_A, E_B are the chosen three-point bases. Thus

$$\boxed{23 = 7 + 7 + 9}, \qquad \boxed{63 - 23 = 40 = (7 \times 7) - (3 \times 3)}.$$

The full $\mathbb{F}_2$-linear setwise stabilizer of this 23/40 split is exactly

$$\boxed{(S_3 \times S_3) \rtimes C_2 = S_3 \wr C_2}, \qquad |G| = 72.$$

Indeed, $A\setminus\{0\}$ and $B\setminus\{0\}$ are the only projective planes wholly contained in the 23-set. If a mixed three-space H existed, every mixed nonzero vector would have to be a grid vector (e_i, f_j). Any two such vectors differing in both row and column sum to a forbidden mixed vector, so all mixed vectors of H lie in one grid row or one grid column; but three in one row or column also have a forbidden sum. Hence H has at most two mixed nonzero vectors. On the other hand, if $r_A = \dim(H \cap A)$ and $r_B = \dim(H \cap B)$, then $r_A + r_B \leq 3$ and a genuinely mixed H has at most four pure nonzero vectors, so its seven nonzero vectors require at least three mixed ones, a contradiction. Therefore a linear stabilizer must preserve or swap the two Fano planes. The cross grid then singles out the three basis points in each plane, leaving exactly $S_3 \wr C_2$.

On the 40-point complement this full linear stabilizer has five orbits

$$\boxed{1+6+6+9+18}.$$

It is therefore not transitive and cannot be permutation-isomorphic to the certified Pass 1021 $W(3,3)$ point action, which is transitive of rank three with subdegrees $1, 12, 27$. Hence the attractive equality $40 = (7\times 7) - (3\times 3)$ does *not* identify the new binary complement with the 40-point base of the E_8 root fibration through the natural projective-linear route.

The most direct coding-theoretic E_8 readings of the new length 248 code are likewise obstructed. First, the 23 distinct columns contain no affine 3-flat of eight points. Indeed, if $v + H$ were such a flat, summing Hamming weights over the coset gives $4s + 8f$, where s is the support size of the 3-space H and f counts fixed-one coordinates outside that support. The available column types force $f = 0$ and $s = 4$. The four possible hyperplane-coset weight distributions in $\mathbb{F}_2^4$, according to normal weight $1, 2, 3, 4$, are

$$(1,3,3,1), \quad (2,4,2,0), \quad (3,3,1,1), \quad (4,0,4,0)$$

in weights $1, 2, 3, 4$. Each contains either a weight-four word or at least two weight-three words, whereas the 23-set contains no weight-four word and at most one of its complementary weight-three words on any four-coordinate support. Hence no such affine flat exists, so the natural eight-column $[8, 4, 4]$ puncture route is absent.

Second, for the full binary code $C = [248, 6, 51]_2$ one has

$$GG^{\mathsf{T}} = I_6 \pmod 2.$$

Thus C is not self-orthogonal, and its weight-51 generators also show that it is not doubly even. The full code therefore does not realize the standard self-dual doubly-even binary Construction-A route to the E_8 lattice.

Finally, although the numerical Lie-algebra identity is

$$\dim \mathfrak{e}_8 = 248 = 240 + 8,$$

with 240 root spaces and an 8-dimensional Cartan subalgebra, the full coordinate-permutation automorphism group of the code has coordinate orbits

$$\boxed{192, 36, 18, 2}.$$

No union of these orbits has size 8 or 240. Hence the code carries no full-symmetry-invariant coordinate split that can canonically be interpreted as "240 roots plus 8 Cartan directions." The same subset-sum obstruction rules out an invariant coordinate realization of the standard dimension pattern $248 = 78 + 8 + 81 + 81$.

These negative statements complement, rather than contradict, the earlier certified E_8 result in the repository: Pass 1021 proves a canonical six-to-one Eisenstein fibration of the 240 E_8 roots onto the 40 *points* of $W(3,3)$. What the present audit shows is that the new 248-code does not recover that $E_8/W33$ bridge by any of the three most direct routes tested here: a canonical $240+8$ coordinate split, a standard binary Construction-A realization, or the natural projective-linear identification of its 40-point complement.

The eight target-48 Gram clique decisions are run by a separate exact parallel SAT certificate. No value $\alpha(W(3,9)) = 51$ is inferred here unless that independent certificate records UNSAT in all eight cases.

74.11 The E_8 root graph as a hexagonal lift of $W(3,3)$

We retain the exact six-to-one Eisenstein fibration of Pass 1021,

$$\Phi : \Phi(E_8) \longrightarrow W(3,3), \qquad 240 = 40 \cdot 6,$$

where the fibers are the $\langle c^5 \rangle \cong C_6$ orbits of a Coxeter element $c \in W(E_8)$. The present computation determines the positive-inner-product root graph relative to those fibers.

Each six-root fiber induces a single C_6. For two distinct fibers there are exactly two possibilities. If their base points are collinear in $W(3,3)$ there is no root-graph edge between the fibers. If their base points are noncollinear, there are exactly twelve such edges, every root has degree two into the opposite fiber, and the resulting bipartite graph is one C_{12}. Thus the 780 unordered fiber pairs split as

$$\boxed{240 \text{ zero-coupled pairs} + 540\ C_{12} \text{ pairs}},$$

and the full E_8 root degree and edge count decompose as

$$\boxed{56 = 2 + 27 \cdot 2}, \qquad \boxed{6720 = 40 \cdot 6 + 540 \cdot 12}.$$

In Coxeter phase coordinates $\mathbb{Z}_6$, every noncollinear base pair has cross-fiber difference set exactly $\{s, s+1\}$. Hence, with

$$\phi_{xy} = 2s + 1 \pmod{12},$$

reversal gives $\phi_{yx} = -\phi_{xy}$ and a change of fiber origins changes ϕ by a coboundary. On the 3240 triangles of the complement of $W(3,3)$ the exact holonomy distribution is

$$\boxed{1440 \times 1 + 1440 \times (-1) + 180 \times 3 + 180 \times (-3) \pmod{12}}.$$

This is a finite μ_{12}-valued cycle phase; no physical gauge-field interpretation is asserted.

Exact fiber Fourier decomposition. Because the root adjacency commutes with the global C_6 phase shift, Fourier transform along the six-root fibers decomposes the 240-dimensional adjacency module into six 40-dimensional sectors. Exact matrix arithmetic in $\mathbb{Z}[\zeta_6]$, with $\zeta_6^2 - \zeta_6 + 1 = 0$, gives

k	Spec M_k
0	$56^1,\ 8^{15},\ (-4)^{24}$
$1,5$	$28^4,\ (-2)^{36}$
$2,4$	$8^{10},\ (-4)^{30}$
3	$(-2)^{40}$.

Consequently the full positive-inner-product E_8 root graph has spectrum

$$\boxed{56^1 \oplus 28^8 \oplus 8^{35} \oplus (-2)^{112} \oplus (-4)^{84}}.$$

The phase-zero block is particularly transparent:

$$\boxed{M_0 = 2J - 2A_{W(3,3)}}.$$

Hence its spectrum follows directly from $12^1 \oplus 2^{24} \oplus (-4)^{15}$ of $W(3,3)$, giving $56^1 \oplus (-4)^{24} \oplus 8^{15}$. The other sector polynomials are certified exactly in the cyclotomic ring rather than inferred numerically.

Fiber-constant binary code. Pass 85 already gives the adjacency-row code

$$C_2(W) = [40, 16, 8]_2$$

with 45 minimum words. Repeating each base coordinate on its six Eisenstein roots gives an injective fiber-constant code

$$\boxed{C_{E_8,\mathrm{fib}} = [240, 16, 48]_2},$$

whose weight enumerator is obtained from that of $C_2(W)$ by $z^w \mapsto z^{6w}$.

The D_4/center-quad dictionary. Every weight-eight word induces $K_{4,4}$ on its eight base points. Its two four-point parts give 90 independent four-sets in total. Independently reconstructing the center-quads of $W(3,3)$ gives the same 90 four-sets objectwise. Lifting a center-quad through Φ gives 24 roots. Exact rational row reduction verifies for all 90 lifts that their span has rank four, contains no other E_8 roots, and that every root has positive-inner-product degree eight within the set. Therefore

$$\boxed{\text{90 center-quads} = \text{90 } D_4 \text{ root subsystems of } E_8}.$$

The old fixed-point-free center-quad pairing becomes orthogonal complementation of these D_4 subsystems. Consequently

$$\boxed{\text{45 center-quad pairs} = \text{45 selected } D_4 \perp D_4 \text{ subsystems}},$$

and their eight-point base supports are exactly the 45 minimum words/tritangent supports of $C_2(W)$.

The previously certified center-quad quotient

$$90 \longrightarrow 45 \longrightarrow 27$$

therefore admits the root-system translation

$$\boxed{90\, D_4 \longrightarrow 45\, (D_4 \perp D_4) \longrightarrow 27 \text{ five-pack partitions of the 240 } E_8 \text{ roots}}.$$

Each of the 27 five-packs contains five disjoint 48-root supports and partitions all 240 roots; each of the 45 selected $D_4 \perp D_4$ supports lies on three such five-packs. The identification of this 45-point/27-line incidence geometry with dual $GQ(4,2)$ and the cubic-surface 27/45 layer is prior repo work; the E_8 D_4 interpretation is the new bridge here.

Sixfold symmetry envelope. The internal Eisenstein fiber C_6 and the previously certified external controller $S_3 = C_3{:}C_2$ fit into

$$D_{12} = \langle r, s \mid r^6 = s^2 = 1,\ srs = r^{-1} \rangle,$$

with $C_6 = \langle r \rangle$ and $D_{12}/\langle r^3 \rangle \cong S_3$. This is the same abstract group that controls the q=9 witness hexad, but no objectwise identification of the two six-state systems is claimed.

The q=9 rank-one boundary. For the eight normalized q=9 Gram-anchor cases, the 512 residual states split as 64 rank-one and 448 invertible 2×2 matrices. The exact independence numbers of the eight rank-one induced conflict graphs are

$$\boxed{21, 25, 22, 25, 23, 24, 21, 26}.$$

The known 51-point witness lies in anchor type $(1, 3, 5)$ and its 47 residual rows split as

$$\boxed{5 \text{ rank-one} + 42 \text{ invertible}}.$$

This is an exact boundary refinement only. It does not close the full target-48 problem in the 512-state graphs, so no claim $\alpha(W(3, 9)) = 51$ is made here.

74.12 The $E_8/W(3,3)$ fibre scheme, selected D_4 geometry, and the H_{27} matter cover

The six-to-one E_8-root fibration of Section 74.11 extends to the complete five-class root association scheme. Ordering the relations by normalized inner product $2, 1, 0, -1, -2$, the valencies are

$$\boxed{1, 56, 126, 56, 1},$$

and the simultaneous eigenmatrix is

$$P = \begin{pmatrix} 1 & 56 & 126 & 56 & 1 \\ 1 & 28 & 0 & -28 & -1 \\ 1 & 8 & -18 & 8 & 1 \\ 1 & -2 & 0 & 2 & -1 \\ 1 & -4 & 6 & -4 & 1 \end{pmatrix},$$

with multiplicities $1, 8, 35, 112, 84$. The positive-inner-product adjacency has five distinct eigenspaces and therefore generates the full Bose–Mesner algebra.

The selected ninety D_4 subsystems. There are 3150 D_4 root subsystems in E_8. The ninety selected by the W33 center-quads form a rank-five association scheme with nontrivial valencies $1, 32, 32, 24$ and eigenmatrix

$$\begin{pmatrix} 1 & 1 & 32 & 32 & 24 \\ 1 & -1 & 8 & -8 & 0 \\ 1 & 1 & -4 & -4 & 6 \\ 1 & 1 & 2 & 2 & -6 \\ 1 & -1 & -4 & 4 & 0 \end{pmatrix}.$$

Its unique valency-one relation is $D_4 \leftrightarrow D_4^{\perp}$. The share-one-W33-point relation has exactly eighty maximal 9-cliques: forty point stars and forty neighborhood stars, interchanged by orthogonal complementation. Their quotient reconstructs W33, and consequently

$$\boxed{\mathrm{Aut}(\mathcal{D}_{90}) \cong \mathrm{Aut}(W33) \times C_2}, \qquad |\mathrm{Aut}(\mathcal{D}_{90})| = 103680.$$

All Krein parameters are nonnegative, but no primitive-idempotent ordering is Q-polynomial.

Each selected D_4 has exactly three mutually orthogonal four-frames on its twelve antipodal root lines; each frame uses one antipodal pair from each of the four constituent C_6 fibres. Its positive-inner-product root graph has spectrum

$$\boxed{8^1 \oplus 4^4 \oplus 0^9 \oplus (-2)^8 \oplus (-4)^2}.$$

Integral glue and the twenty-seven ten-D_4 spreads. The W33 relation of a selected D_4 pair determines its lattice behavior. Share-one-fibre pairs span rank six. The two disjoint nonorthogonal relations span rank eight with index one in E_8. Orthogonal complement pairs span $D_4 \oplus D_4$ with index four, with diagonal discriminant glue

$$\boxed{\{(0,0),(v,v),(s,s),(c,c)\} \cong (C_2)^2}.$$

The twenty-seven ten-D_4 spreads contain five such orthogonal pairs each; any pair of D_4 subsystems drawn from different orthogonal pairs already generates the full E_8 lattice.

On the forty-five orthogonal-pair coordinates, the twenty-seven spread-incidence words generate

$$\boxed{[45, 21, 5]_2},$$

and its dual is

$$\boxed{[45, 24, 6]_2}.$$

The latter has exactly 120 minimum words, objectwise the previously certified Steiner/$K_{3,3}$ circuits. The all-ones word lies in the 21-space; its even subcode is a twenty-dimensional full-group module. An explicit intertwiner identifies that module with the previously certified binary tritangent selector V_{20}, including the outer PGSp generator. Therefore

$$\boxed{C_{\mathrm{spread}} = \mathbf{1} \oplus V_{20}^{\mathrm{trit}}}, \qquad \boxed{C_{\mathrm{spread}}^{\perp} = V_{24}^{\mathrm{Steiner}}}.$$

Every selected pair in the disjoint cross-count-four relation gives an explicit unimodular E_8 chart. There are 1080 such $GL_8(\mathbb{Z})$ charts, partitioned by the twenty-seven spreads into forty each. Their ordinary coordinate transitions $X_j X_i^{-1}$ form a flat groupoid: closed products telescope to the identity. Thus any nontrivial triality-valued holonomy would require additional frame identifications and is not produced by basis changes alone.

$E_6 \times A_2$, affine area, and the Heisenberg matter graph. Choose one six-root fibre. It is an A_2 subsystem. The W33 shell $1 + 12 + 27$ becomes

$$\boxed{6_{A_2} + 72_{E_6} + 81 + 81}.$$

Either 81-sector projects to twenty-seven E_6 minuscule weights with three A_2 charges per weight, recovering the Schlaefli graph $\mathrm{srg}(27, 16, 10, 8)$. The twenty-seven W33 nonneighbor fibres themselves are not the twenty-seven weights: they group into nine triples and form a regular C_3 voltage cover of K_9.

After switching a spanning star to voltage zero, its twelve zero-holonomy triangles are precisely the twelve affine lines of $AG(2,3)$. Up to affine relabelling and global sign the voltage is

$$\boxed{\psi(u,v) = \det(u,v) \in \mathbb{F}_3},$$

so triangle holonomy is the oriented affine area $\det(v-u, w-u)$. Choosing the sign convention of the repo's canonical qutrit Heisenberg chart yields

$$(u,z)(v,w) = (u+v, z+w-\det(u,v)).$$

The resulting twenty-seven-vertex E8 matter-fibre graph is exactly

$$\boxed{\mathrm{Cay}(H_{27}, \{(u,0) : u \neq 0\})}.$$

It has intersection array

$$\boxed{\{8,6,1;1,3,8\}},$$

spectrum $8^1 \oplus 2^{12} \oplus (-1)^8 \oplus (-4)^6$, and full automorphism group

$$\boxed{H_{27}{:}GL_2(3)}, \qquad |\operatorname{Aut}| = 1296.$$

The vertex stabilizer is transitive on all three distance spheres, so the graph is distance-transitive.

Two phase structures remain distinct. The E_8 fibre cocycle has only odd $\mathbb{Z}_{12}$ triangle holonomies $1, 3, 9, 11$. A two-qutrit Weyl commutator cochain has edge phase in $4\mathbb{Z}/12$ and hence triangle holonomy in $\{0, 4, 8\}$. Since triangle holonomy is coboundary invariant, these two cocycles are not cohomologous. No identification is made merely because both use twelfth roots of unity.

Local q=9 exclusion. In the canonical $(1,3,5)$ anchor graph, the known residual 47-clique splits as forty-two invertible states plus five rank-one states. Exact branch-and-bound excludes a target 48 after deleting any $d \leq 8$ members of the forty-two-state invertible core and allowing arbitrary compatible additions from all remaining normalized states. Thus a hypothetical target-48 residual clique in this anchor graph must delete at least nine core states. This is a local basin theorem only:

$$\boxed{\text{no claim } \alpha(W(3,9)) = 51 \text{ is made.}}$$

74.13 Double-six sections of the E_8/D_4 spread code recover the doily codes

Fix a Schlaefli double-six $(a_1, \ldots, a_6)/(b_1, \ldots, b_6)$ on the cubic surface. The fifteen remaining lines are the c_{ij} and hence identify with the fifteen duads, or edges, of K_6. The existing exact cubic-surface classifier shows that the fifteen tritangent planes supported entirely on those lines are precisely

$$\{c_{ij}, c_{kl}, c_{mn}\},$$

where $(ij)(kl)(mn)$ is a perfect matching of K_6. They are therefore the fifteen synthemes in the classical duad–syntheme model of the doily $GQ(2,2)$.

A closed K_6 formula for the doily code. For $A \subseteq \{1,\dots,6\}$ let $\delta(A)$ be the binary cut vector on the fifteen edges of K_6. Then, with $A \sim A^c$,

$$\boxed{c(A) = \delta(A) + (|A| \bmod 2)\mathbf{1}_{15}}$$

generates the self-orthogonal code

$$\boxed{[15,5,6]_2}, \qquad W(y) = 1 + 10y^6 + 15y^8 + 6y^{10}.$$

Its even-$|A|$ sector is the $[15,4,8]_2$ simplex code. In this model the six ovoid zero-sets are the six vertex stars of K_6, the fifteen perp zero-sets are one duad together with its six disjoint duads, and the ten grid zero-sets are the $K_{3,3}$ edge sets from unordered $3+3$ bisections. The dual is $[15,10,3]_2$, and its fifteen minimum words are exactly the fifteen synthemes.

The six doily spreads are the six 1-factorizations of K_6. Consequently the two six-sets used in Passes 6533–6540 have the classical interpretation

$$\boxed{\text{six ovoids} = \text{six vertices of } K_6}, \qquad \boxed{\text{six spreads} = \text{six 1-factorizations of } K_6}.$$

The induced actions of all 720 permutations reproduce the earlier exceptional-S_6 cycle-type table exactly, including

$$2 \leftrightarrow 2^3, \qquad 3 \leftrightarrow 3^2, \qquad 3{\cdot}2 \leftrightarrow 6.$$

The forty-five-coordinate code contains this doily literally. Let

$$C_{\text{spread}} = [45,21,5]_2$$

be the Pass7182/7184 code on the forty-five orthogonal-D_4-pair / tritangent coordinates, generated by the twenty-seven ten-D_4 spreads. For any one of the thirty-six double-sixes D, let S_D denote the fifteen tritangent planes disjoint from D. Exact replay over all thirty-six choices gives

$$\boxed{\text{puncture}_{S_D}(C_{\text{spread}}) \cong [15,10,3]_2.}$$

This is objectwise, not parameter recognition: exactly fifteen of the twenty-seven spread generators restrict nontrivially, each restriction has weight three, and for every duad ij one such row is exactly the three synthemes containing ij. The other twelve generators restrict to zero.

Since Pass7182 proved $C_{\text{spread}}^{\perp} = [45,24,6]_2$, puncture/shorten duality gives

$$\boxed{\text{shorten}_{S_D}(C_{\text{spread}}^{\perp}) \cong [15,5,6]_2,}$$

and direct enumeration recovers $1 + 10y^6 + 15y^8 + 6y^{10}$. Thus every double-six supplies the exact local hierarchy

$$[45,21,5]_{\text{E8 spread}} \xrightarrow{\text{puncture}} [15,10,3]^{\perp}_{\text{doily}}, \qquad [45,24,6]_{\text{Steiner}} \xrightarrow{\text{shorten}} [15,5,6]_{\text{doily}}.$$

Boundary. The duad–syntheme doily, Schlaefli double-six notation, exceptional outer automorphism of S_6, and uniqueness of the optimal self-orthogonal $[15,5,6]_2$ code are classical. The result here is the explicit identification among the repo's concrete cubic-surface, E_8/D_4 spread-code, and earlier doily-code carriers. It is a finite binary/incidence theorem only; no physical identification is inferred.

74.14 The thirty-six doily sections are a second generating system for C_{spread}

Let M be the canonical 45×36 tritangent/double-six incidence matrix, with

$$M_{tD} = 1 \quad \Longleftrightarrow \quad |t \cap D| = 2.$$

For each double-six D, let the D-column of N indicate the fifteen tritangent planes disjoint from D, equivalently the fifteen syntheme coordinates of the doily section isolated in Section 74.13. A tritangent meets a double-six in either zero or two lines, so over $\mathbb{F}_2$ one has the exact incidence identity

$$\boxed{N = J + M}.$$

Exact reconstruction gives

$$\operatorname{rank}_2 M = 20, \qquad \operatorname{rank}_2 N = 21.$$

More strongly, on the same forty-five tritangent coordinates,

$$\boxed{\operatorname{col}(M) = C_{\text{spread}}^{\text{even}}}, \qquad \boxed{\operatorname{col}(N) = C_{\text{spread}} = [45, 21, 5]_2}.$$

Thus the Pass7184 decomposition $C_{\text{spread}} = \mathbf{1} \oplus V_{20}$ has a direct cubic-surface incidence realization: the even twenty-space is generated by the ordinary tritangent/double-six selector columns, while complementing those columns supplies the odd line and yields the full twenty-one-space.

The thirty-six doily sections themselves form a two-intersection family. Every section contains fifteen tritangents and every tritangent lies in twelve sections. For two distinct double-sixes D, D',

$$|S_D \cap S_{D'}| = \begin{cases} 6, & |D \cap D'| = 6, \\ 3, & |D \cap D'| \neq 6. \end{cases}$$

There are respectively 360 and 270 such pairs, exactly the edge/nonedge split of the standard 36-vertex double-six graph H_{36}.

Consequently the same code now has two explicit geometric generating systems:

$$\boxed{\text{27 ten-}D_4\text{ spread words}} \qquad \text{and} \qquad \boxed{\text{36 double-six doily-section words}},$$

with identical binary span. This is an exact finite incidence/coding identity; no continuum or physical claim is inferred.

74.15 The double-six doily system as a spectral design and ternary shadow

Let N be the 45×36 incidence matrix whose Dth column is the set of fifteen tritangents disjoint from a double-six D. If A_{36} is the double-six graph and A_{45} the tritangent-sharing graph, exact replay gives

$$N^T N = 12I + 3J + 3A_{36}, \qquad N N^T = 9I + 3J + 3A_{45},$$

with $A_{36} = \mathrm{SRG}(36, 20, 10, 12)$ and $A_{45} = \mathrm{SRG}(45, 12, 3, 3)$. Hence

$$\operatorname{spec}(N^T N) = 180^1 \oplus 18^{20} \oplus 0^{15}.$$

Writing $X = N - J/3$ yields the exact primitive-module intertwiner

$$\boxed{2A_{45}X = 3XA_{36}}.$$

The centered columns have squared norm 10, mutual inner products 1 or -2, and form a tight frame on a 20-space with frame eigenvalue 18.

A single double-six is transitive under the 36-point $PSp(4,3)$ orbit, and the binary span of its orbit columns is the full

$$\boxed{C_{\text{spread}} = [45, 21, 5]_2}.$$

Thus one local doily slice plus the ambient group action reconstructs both the spread code and the double-six overlap graph.

The $D_4 \oplus D_4$ diagonal glue has nonzero classes $(v,v),(s,s),(c,c)$. The complementary-pair stabilizer has order

$$2 \cdot 192^2 \cdot 6 = 442368,$$

where the factor 6 is simultaneous D_4 triality. It permutes the three nonzero diagonal glue classes transitively, so a bare orthogonal D_4 pair carries an S_3 torsor rather than a canonical $v/s/c$ label.

For a fixed double-six,

$$|\operatorname{Stab}_{PSp}(D)| = 720, \qquad |\operatorname{Stab}_{W(E_6)}(D)| = 1440,$$

but both images on the fifteen-tritangent doily slice have order 720. The extra kernel C_2 swaps the two sixers of the double-six and fixes the fifteen complementary c_{ij} lines; it is central, not the exceptional outer automorphism of S_6. Moreover the 27 minimum words of C_{spread} have weight five and are exactly the 27 cubic-line stars. Thus the code reconstructs the full 27-line/45-tritangent cubic-surface geometry from its minimum words.

Characteristic three exposes a second code. The Smith form of N has nonzero invariant factors

$$\boxed{1^{14}3^7}.$$

Since $N^T N \equiv 0 \pmod 3$, the ternary column span is self-orthogonal and exhaustive enumeration gives

$$\boxed{[45, 14, 15]_3}.$$

Its 72 minimum words are exactly $\pm$ the 36 doily-slice columns.

74.16 A q=9 local-section obstruction and blocker-frame fingerprint

A direct restriction of the fifteen-coordinate doily code to points of $W(3,9)$ is not canonical: the former is a cubic-surface tritangent carrier, the latter a point carrier. The q=9-native local test is instead intersection with embedded symplectic $W(3,3)$ sections. Every such intersection is a partial ovoid of $W(3,3)$ and therefore has size at most seven. The frozen 51-point witness meets the standard $\mathbb{F}_3$-fixed section in four points; a deterministic scan of 20,000 embedded sections under non-$\mathbb{F}_3$ symplectic transvections saw maximum intersection six. This scan is not exhaustive and is not an upper bound for $\alpha(W(3,9))$.

If B is the 769×51 blocker-incidence matrix of the frozen witness, then

$$\boxed{B^T B = 80 I_{51} + 10 J_{51}}.$$

After integer centering, the 51 columns form an exact regular simplex of rank 50. The third blocker moment is witness-specific: among the $\binom{51}{3}$ witness triads, exactly 20722 have one common center and 103 have ten common centers. Those 103 exceptional triads form a binary rank-51 three-uniform hypergraph.

Evidence boundary. These statements are finite combinatorial/coding results. The q=9 optimum remains open; no 52-set is excluded. No physical interpretation is assigned to the new ternary or Smith-form invariants.

74.17 A $7+10$ logical Hodge split and the curved integral 27–45–36 prism

Let $N : \mathbb{Z}^{36} \to \mathbb{Z}^{45}$ denote double-six/doily-slice incidence and let $R : \mathbb{Z}^{45} \to \mathbb{Z}^{27}$ denote tritangent/cubic-line incidence. The exact integral identity

$$RN = 3Q$$

for a binary 27×36 incidence matrix Q makes

$$\mathbb{F}_3^{36} \xrightarrow{N} \mathbb{F}_3^{45} \xrightarrow{R} \mathbb{F}_3^{27}$$

a chain complex with

$$\boxed{(\dim H_2, \dim H_1, \dim H_0) = (22, 10, 6)}.$$

For the self-orthogonal ternary code $C_3 = \operatorname{im} N = [45, 14, 15]_3$, whose dual gives the abstract qutrit CSS code $[[45, 17, 5]]_3$, the protected logical space decomposes canonically as

$$\boxed{\frac{C_3^{\perp}}{C_3} = \frac{\operatorname{im} R^T}{\operatorname{im} N} \perp \frac{\ker R}{\operatorname{im} N}.}$$

The first summand has dimension seven and pure distance five; its 27 projective minimum supports are the five-tritangent stars of the cubic-surface lines. It is the previously identified uniserial $W(E_6)$ module $\mathbf{1} \mid 5 \mid \mathbf{1}$. The second summand is literally H_1, has dimension ten, and has pure distance six: its 120 projective minimum supports are precisely the Steiner induced $K_{3,3}$ supports.

The integral curvature induces the secondary map

$$\kappa : H_2 \longrightarrow \operatorname{im}(RR^T), \qquad [z] \longmapsto Qz \pmod 3,$$

with

$$\boxed{\operatorname{rank} \kappa = 7, \qquad \dim \ker \kappa = 15},$$

and

$$\operatorname{im}(RR^T) \cong \operatorname{im}(R^T)/\operatorname{im} N.$$

Thus the curvature surjects onto the same seven-dimensional star/logical sector. We call this a *curvature transgression*; it is not promoted as the standard Bockstein homomorphism because RN is nonzero integrally.

The 2-primary shadow. Reducing Q^T modulo two gives a $[27, 7, 11]_2$ Schlaefli code. Its dual has exactly 270 minimum tetrads. Every tetrad induces $2K_2$ in the cubic-line meet graph and is obtained uniquely from a pair of intersecting tritangent planes by deleting their common cubic line. Meeting cubic-line pairs occur in four tetrads, whereas skew pairs occur in five.

74.18 The exact C_2 branch of the $q = 9$ partial-ovoid problem

The independently confirmed projective symplectic stabilizer of the frozen 51-point witness is C_2. Its action on $W(3, 9)$ has 20 fixed points and 400 two-cycles. Forty two-cycles are internally collinear and are forbidden in an invariant partial ovoid, leaving

$$\boxed{380}$$

allowed orbit variables. With all 820 isotropic-line clique inequalities, the weighted quotient LP has optimum 74; fixing the number of fixed points to $0, 1, 2$ gives LP optima $72, 73, 74$, respectively. An invariant 52-set can use only 0 or 2 fixed points. This is an exact symmetry branch, not a WLOG reduction of the unrestricted problem; $\alpha(W(3, 9))$ remains open.

74.19 Coxeter phase selects a local $3K_4$ chart

In the globally triality-resolved 45-coordinate $D_4 \oplus D_4$ atlas, the 12 phase-flat coordinates are exactly the neighborhood of one unique coordinate in the fixed Coxeter-phase gauge. Since every local graph of $\mathrm{SRG}(45, 12, 3, 3)$ is $3K_4$, the phase datum selects one distinguished local chart rather than a new graph type. This 12-coordinate $3K_4$ is not identified with the older 16-flag Levi $4K_4$ codec without an explicit carrier map.

74.20 Corrected E8 local descent: 40 A_2 fibres, Clebsch and Petersen

The Coxeter/Eisenstein fibration partitions the 240 E8 roots into

$$\boxed{\text{40 rank-two } A_2 \text{ root hexagons of six roots each}},$$

whose quotient is the W(3, 3) point graph $\mathrm{SRG}(40, 12, 2, 4)$. The nested positive-inner-product local chain has vertex counts

$$240 \to 56 \to 27 \to 16 \to 10,$$

with the previously computed spectra. The 16-vertex member is the complement of the Clebsch graph and the 10-vertex member is the complement of the Petersen graph. At the Schlaefli level a chosen vertex yields the exact partition

$$\boxed{27 = 1 + 16 + 10}.$$

The numerical resemblance to the standard $E_6 \to \mathrm{Spin}(10)$ branching is recorded as representation-theoretic context only. In particular, $27 + 6 = 33$ is not a W(3, 3) vertex count: the objectwise Eisenstein quotient has 40 fibres/points.

Transversal-gate firewall. Although C_3 is self-orthogonal and its deterministic basis rows have weights divisible by three, the cubic overlap form

$$T(u, v, w) = \sum_i u_i v_i w_i \pmod 3$$

is nonzero on the code: 275 basis triples have nonzero overlap. Hence naive ternary total-triorthogonality fails, and no transversal non-Clifford gate is claimed from the present divisibility data. Recent homological/Bockstein criteria for CSS transversal diagonal gates motivate a separate integral-lift test rather than an overlap-based extrapolation.

Evidence boundary. All statements above are exact finite incidence, coding, root-system, representation, or LP statements. They do not decide $\alpha(W(3,9))$, identify κ with a standard Bockstein, establish a physical E6 particle assignment, or prove a transversal non-Clifford gate for the qutrit code.

Passes 7401–7424: the global E_8 A_2 geometry and its Eisenstein $W(3,3)$ leaves

The corrected Eisenstein bridge can be globalized without changing its evidence tier. Starting from the 240 roots of E_8, the Pass7401 verifier reconstructs all

$$1120$$

root subsystems of type A_2. Orthogonality of their rank-two root planes defines a 120-regular graph on these 1120 objects with spectrum

$$\boxed{120^1 \oplus 20^{84} \oplus 8^{300} \oplus (-4)^{700} \oplus (-40)^{35}}.$$

Adjacent vertices have exactly two common neighbours, while nonadjacent pairs have exactly 10, 16, or 40 common neighbours. The corresponding five relation valencies are

$$\boxed{1,\ 120,\ 648,\ 270,\ 81}.$$

These relations close to a commutative rank-five association scheme.

The adjacent-pair parameter has a direct root-subsystem consequence. The two common A_2 neighbours of any orthogonal pair are themselves orthogonal, so every $2A_2$ extends to a unique $4A_2$. Hence the global incidence structure has

$$\boxed{1120\ A_2 \text{ points}, \qquad 11200\ A_2^4 \text{ lines},}$$

with four points per line and forty lines through each point. In particular

$$11200\binom{4}{2} = 67200$$

recovers every orthogonal $2A_2$ pair exactly once.

The already-certified regular order-three normalizer has order

$$|N_{W(E_8)}(\langle J\rangle)| = 311040.$$

Consequently the full Weyl group contains exactly

$$\boxed{696729600/311040 = 2240}$$

conjugate cyclic Eisenstein structures, hence 2240 conjugate $W(3,3)$ leaves. Double counting gives the exact replication numbers

$$\boxed{r_{A_2} = 80, \qquad r_{2A_2} = 8, \qquad r_{4A_2} = 8, \qquad r_{D_4} = 64.}$$

Thus one $W(3,3)$ is not an isolated 40-point occurrence in E_8; it is one forty-point slice in a global 1120-point A_2 geometry.

The eight-leaf fibre over one A_2^4. Fix $X = A_2^{(1)} \perp \cdots \perp A_2^{(4)}$. On each factor a regular order-three structure has the two Coxeter orientations c_i and c_i^{-1}. Four orientation bits therefore give $\mathbb{F}_2^4$, while replacing J by J^{-1} flips all four bits and does not change the cyclic Eisenstein leaf. Hence the eight leaves through X are canonically

$$\boxed{\mathbb{F}_2^4/\langle 1111\rangle \cong \mathbb{F}_2^3.}$$

One explicit gauge is

$$[x_1, x_2, x_3, x_4] \longmapsto (x_1 + x_4, x_2 + x_4, x_3 + x_4).$$

The seven nonzero differences split into four odd directions

$$100,\ 010,\ 001,\ 111$$

and three even directions

$$110,\ 101,\ 011.$$

The four odd translations are four disjoint perfect matchings whose union is $K_{4,4}$; the three even translations form $2K_4$. Thus

$$\boxed{K_8 = K_{4,4} \sqcup 2K_4.}$$

This is an explicit E_8 derivation of the previously abstract Fano-hinge chart.

The local A_2 reflections supply the translation subgroup 2^3, while the previously certified projective tetracode block action supplies S_4. The induced normalizer action on the eight leaves is therefore

$$\boxed{2^3{:}S_4 \cong W(D_4), \qquad |W(D_4)| = 192.}$$

Since $|N_{W(E_8)}(A_2^4)| = 62208$, the action has kernel 324:

$$\boxed{1 \longrightarrow K_{324} \longrightarrow N_{W(E_8)}(A_2^4) \longrightarrow W(D_4) \longrightarrow 1.}$$

This closes the local A_2/Weyl refinement that the earlier tetracode audit had left open; it does not re-claim the already-known abstract 192-element Fano chart.

Weyl orbital closure. The central element $-I$ acts trivially on A_2 subsystems, so the effective group has order 348364800. A point stabilizer has order 311040 and exactly five suborbits of sizes

$$\boxed{1,\ 120,\ 648,\ 270,\ 81,}$$

which are exactly the five relations above. Therefore the orbital algebra equals the commutative Bose–Mesner algebra and the 1120-point permutation representation is multiplicity-free:

$$\boxed{\mathbb{C}^{1120} \cong \mathbf{1} \oplus V_{84} \oplus V_{300} \oplus V_{700} \oplus V_{35}.}$$

Its exact first eigenmatrix is

$$\boxed{P = \begin{pmatrix} 1 & 120 & 648 & 270 & 81 \\ 1 & 20 & -12 & -30 & 21 \\ 1 & 8 & -24 & 18 & -3 \\ 1 & -4 & 12 & -6 & -3 \\ 1 & -40 & -24 & 30 & 33 \end{pmatrix}.}$$

With multiplicities $m = (1, 84, 300, 700, 35)$ and valencies $k = (1, 120, 648, 270, 81)$ the verifier checks the exact orthogonality identity

$$P^T \operatorname{diag}(m) P = 1120 \operatorname{diag}(k).$$

Evidence boundary. The 1120-point association scheme, unique $2A_2 \to 4A_2$ completion, Weyl orbital rank, eigenmatrix, and local $\mathbb{F}_2^3$ fibre are finite root-system theorems with executable witnesses. The number 2240 uses the independently certified regular-C_3 normalizer order, and the D_4 replication uses the certified count of 90 J-stable D_4 subsystems per leaf. No Standard-Model parameter, coupling, or photonic-hardware claim follows from these finite-geometric statements alone.

Pass8781–8828: CSS, Leech fixed spaces, and the W33 logical carrier

The characteristic-two logical half $D = C_0^{\perp}/C_0$ has dimension 92 and a certified composition series with factor multiset

$$1^4 \oplus 6^3 \oplus 8^2 \oplus 14 \oplus 40.$$

For the $1, 6, 8, 14$ factors every nonzero vector was checked as a cyclic seed. For the 40-dimensional factor an algebra element with characteristic polynomial $(x+1)^{40}$ has a six-dimensional kernel, and all 63 nonzero kernel vectors generate the full constituent.

The class-$2C$ fixed six-spaces in the 12-dimensional binary $G_2(4)$:2 module form a 20,800-point rank-14 coherent configuration with subdegrees

$$1, 63, 72, 126, 252, 252, 378, 1512, 1512, 1512, 2016, 3024, 4032, 6048.$$

Its orbital algebra is noncommutative with center dimension 11, hence over $\mathbb{C}$

$$\mathcal{A} \cong \mathbb{C}^{10} \oplus M_2(\mathbb{C}).$$

The unique degree-63 local suborbit, with adjacency defined by mutual intersection dimension four, is the point graph of the split generalized hexagon $H(2)$: it has intersection array $\{6, 4, 4; 1, 1, 3\}$ and spectrum $6^1 3^{21} (-1)^{27} (-3)^{14}$.

Inside the six-qutrit carrier $W(11, 3)$, the orbit of nondegenerate four-spaces carrying $W(3, 3)$ has exactly 31 double cosets under $Sp_4(3) \times Sp_8(3)$. The certified orbit sizes sum to

$$2{,}110{,}666{,}092{,}277{,}743.$$

The intersection shells relative to a fixed $W(3, 3)$ are

$$1,\ 262400,\ 6{,}076{,}864{,}200,\ 12{,}684{,}803{,}040{,}000,\ 2{,}097{,}975{,}212{,}111{,}142$$

for intersection dimensions $4, 3, 2, 1, 0$ respectively. This does not conflict with the parallel cyclotomic-descent theorem: that construction canonically selects $W(3, 3)$ as a coisotropic subquotient $K/K^{\perp}$, not as one preferred four-dimensional subspace.

The forty canonical weight-12 CSS point-stars span a 25-dimensional $W(E_6)$-module. Their Gram matrix is exactly A_{W33} modulo two, of rank 16; the bilinear radical has dimension 9. The module has composition pattern

$$1 \mid 8 \mid 1 \mid 14 \mid 1,$$

with radical $1 \mid 8$ and nondegenerate quotient $1 \mid 14 \mid 1$. Moreover the complete relation space among the forty point-stars is

$$\ker(\Phi) = \ker(N^T) = C_{\text{sentinel}} = [40, 15, 8]_2.$$

By Pass4593 its 45 minimum weight-eight words are the 45 center-quad/E_6 tritangent supports. Thus the 45 tritangents are precisely the 45 minimum linear dependencies among the forty canonical logical point-stars.

Finally, the Pass8481 objectwise weld extends to the CSS matching carrier. One 36-object mixed-Leech component is the 36 W33 lines avoiding a fixed point p; its twelve three-sheet fibres are indexed by the twelve neighbors $q \sim p$. Each neighbor selects the unique matching coordinate on the line pq containing the edge $\{p, q\}$, producing exactly the twelve coordinates of the weight-12 point-star at p. These twelve coordinates split canonically as 4×3 according to the four W33 lines through p.

Boundary. All statements in this insert are exact finite combinatorial, lattice-module, or code-theoretic identifications. No physical hardware equivalence is inferred.

74.21 Depth-three reguli as unique E_8 completion addresses

The depth-three blocking computation in the Holotrade track and the selected E_8/D_4 geometry in the present repository meet objectwise, not merely numerically. The forty-five minimum weight-eight tritangent supports are the forty-five orthogonal $D_4 \oplus D_4$ packets selected by the $W(3,3)$ polarity. Their disjointness graph is the point graph of $GQ(4,2)$: it has 45 vertices, degree 12, and 270 edges. Independently, the Holotrade blocking audit identifies its 270 all-isotropic depth-three obstruction reguli with exactly these 270 support-disjoint packet pairs.

The twenty-seven maximal five-cliques of this graph give a stronger completion law. Every disjoint packet pair is contained in exactly one five-clique, and every five-clique partitions the forty $W(3,3)$ fibres. Under the certified six-roots-per-fibre E_8 lift, each packet contains two orthogonal D_4 subsystems and therefore 48 roots. Consequently

$$\boxed{270 = 27\binom{5}{2}}$$

is an objectwise incidence identity: each depth-three obstruction regulus selects two 48-root packets, hence 96 roots, and determines a unique completion by the other three packets, hence another 144 roots, to one of twenty-seven partitions of the full 240-root shell into ten selected D_4 subsystems:

$$\boxed{\text{obstruction regulus} \longrightarrow 96 \text{ exposed } E_8 \text{ roots} \longrightarrow 96 + 144 = 240 \text{ roots uniquely.}}$$

Each of the forty-five packets lies on exactly three such completion charts, and each chart contains ten of the 270 obstruction edges. For every obstruction edge, all four cross choices of one D_4 half from each packet span rank eight; the verifier performs $270 \cdot 4 = 1080$ exact rank checks.

This theorem is deliberately finite-combinatorial. It does not assert that an E_8 completion removes a physical blocking obstruction, nor does it assign dynamics to the root system. It says that the independently certified Holotrade obstruction edge is a canonical address of one selected E_8 ten-D_4 completion chart.

74.22 The Schlaefli scheme on the twenty-seven completion charts

The twenty-seven completion charts themselves recover the cubic-surface incidence graph. Regard each chart as a partition of the same 240 roots into ten selected D_4 blocks, and join two charts when they have a common $D_4 \oplus D_4$ packet block. Any two charts have either zero or two common D_4 blocks. There are 216 pairs of the first kind and 135 of the second, and the overlap graph is exactly

$$\boxed{\mathrm{SRG}(27, 10, 1, 5)}.$$

This is the line-intersection graph of the twenty-seven lines on a smooth cubic surface; its complement is the usual Schlaefli graph $\mathrm{SRG}(27, 16, 10, 8)$.

The packet layer is recovered without extra labels. Every one of the forty-five selected $D_4 \oplus D_4$ packets lies in exactly three completion charts, those three charts form a triangle, and the overlap graph has exactly forty-five triangles. Conversely every triangle comes from exactly one packet. Thus, inside the selected E_8 partition catalogue,

$$\boxed{27 \text{ cubic lines} \longleftrightarrow 27 \text{ ten-}D_4 \text{ partitions}}$$

and

$$\boxed{45 \text{ tritangent planes} \longleftrightarrow 45 \text{ shared } D_4 \oplus D_4 \text{ packet blocks}}.$$

Incidence is literal containment of partition blocks.

All twenty-seven charts cover the same 240 roots, so the phrase "two charts intersect in 48 roots" would be misleading. Their underlying root sets are identical; the invariant proved here is the number of common *partition blocks*: two for adjacent charts and zero for nonadjacent charts.

74.23 The 1080 obstruction carrier: full Wedderburn decomposition and three explicit Steinberg copies

The equivariant factorization of the depth-three obstruction carrier as 27×40 has degree 1080, orbital rank 59, and point stabilizer order 24. Its exact orbital algebra has center dimension 15 and closes the ordinary complex decomposition:

$$\begin{aligned}\mathbb{C}^{1080} \cong\ & 1 \oplus 6 \oplus 2(15) \oplus 3(20) \oplus 2(24) \oplus 30 \\ & \oplus 2(30 \oplus \overline{30}) \oplus (40 \oplus \overline{40}) \oplus (45 \oplus \overline{45}) \\ & \oplus 3(60) \oplus 3(64) \oplus 3\,\mathrm{St}_{81}.\end{aligned}$$

The three non-rational central factors—of degrees 30, 40, and 45—all split over $\mathbb{Q}(\sqrt{-3})$. In particular the Eisenstein field appears at the full obstruction-module level rather than from a matching count.

The Steinberg isotypic component has rank 243. A deterministic symmetric orbital operator B has multiplicity-space eigenvalues $4, 0, -4$, so with E the central Steinberg projector the three rational primitive projectors are

$$P_+ = \frac{B(B+4E)}{32}, \qquad P_0 = E - \frac{B^2}{16}, \qquad P_- = \frac{B(B-4E)}{32}.$$

They are pairwise orthogonal, each has rank 81, and their sum is E. Thus the three Steinberg copies are represented by explicit equivariant projectors, not only by a character multiplicity.

74.24 The doubled D_4 prism has nonsplit binary homology

For the ninety-D_4 lift, $\widetilde{R}\widetilde{N} = 6Q$, so reduction modulo two gives a genuine complex with $\dim H_1 = 48$. The pair-injection subspace supplies a canonical exact sequence

$$\boxed{0 \longrightarrow A_{24} \longrightarrow H_{1,48} \longrightarrow B_{24} \longrightarrow 0}.$$

Solving the full generator-level splitting equations over $\mathbb{F}_2$ gives no solution. Moreover $\dim \mathrm{Hom}_G(B_{24}, A_{24}) = 2$, and a deterministic basis has map ranks 1 and 10, so no invertible intertwiner identifies the two 24-dimensional subquotients. Their global fixed-space dimensions are respectively 1 and 0.

The separate 48-root channel in the E_8 $\mathbb{Z}_{12}$ common refinement is not this module: an even $W(E_6)$ element sends a root from that joint 48-sector to the neighboring 30-sector. Hence that 48-root subset is not invariant under the inner $PSp(4,3)$ action. Equality of dimensions does not define an intertwiner.

74.25 Port-gauged holonomy on the twenty-seven E_8 completion charts

A correction is required before compiling the completion charts. The explicit degree-45 crosswalk now identifies the old Pass 4795 dependency-cube carrier with the native polar-pair/sentinel packet carrier under the same $PSp(4,3)$ generators. A packet stabilizer has order 576 and induces the full S_3 on its three incident completion charts. The earlier Pass 4795 claim of local image C_3, and the cyclic-orientation torsor inferred from it, are therefore withdrawn rather than retained on a second outer-twisted transitive degree-45 action. An independent Table-of-Marks computation for $U_4(2) \simeq PSp(4,3)$ confirms that the transitive index-45 action is unique.

Fix instead a complete ordering of the three incident chart ports at every packet. Every group element then has a unique correction $\sigma_g(p) \in S_3$, and the exact nonabelian cocycle law

$$\boxed{\sigma_{ab}(p) = \sigma_a(b \cdot p) \circ \sigma_b(p)}$$

holds in all $4 \cdot 25920 \cdot 45 = 4{,}665{,}600$ generator/group/packet checks. Only the identity has zero correction at all forty-five packets.

Each packet has exactly twenty-four order-three global elements inducing a chosen positive three-cycle in this port gauge. Deterministic choices at packet indices $0, 9, 11, 33$ generate subgroups of orders

$$3,\ 9,\ 288,\ 25920,$$

so four local packet rotations generate the full projective symplectic chart action. The chart-overlap graph has 135 edges; a spanning tree leaves 109 fundamental cycles. Their transported holonomies generate a group of order 960, exactly the stabilizer of a base completion chart.

Optimization boundary. The corresponding Holotrade chart-stabilizer attack is negative for the canonical regulus witness family. Fixing one completion chart gives an order-960 stabilizer, but its 240 ordered "bad triple plus omitted line twice" witnesses form one orbit, and all 269 relevant stabilizer leaf-orbits meet every witness. The restricted fractional and integer cover optima are therefore both one. Chart information can affect the current depth-five lower bound only after breaking symmetry below the chart stabilizer or by using a different nonlinear/integer witness family.

All statements above are finite incidence, representation, modular-homology, or permutation-group theorems. No optical dynamics, mass, coupling, or hardware threshold is inferred from these carriers.

74.26 One 27×45 atlas and the $81 \oplus 81 \oplus 81$ Steinberg frame

The same 27×45 matrix is, objectwise, the incidence matrix for $GQ(2,4)$ points/lines, cubic lines/tritangents, W33 $K_{4,4}$ factorizations/octets, and E_8 ten-D_4 charts/$D_4 \oplus D_4$ packets. It has row weight 5, column weight 3, and rank 21 over $\mathbb{Q}, \mathbb{F}_2, \mathbb{F}_3, \mathbb{F}_5, \mathbb{F}_7$, with

$$II^T = 5I_{27} + A_{GQ(2,4)}, \qquad I^T I = 3I_{45} + A_{GQ(4,2)}.$$

On the three-copy Steinberg block the Schlaefli $K_{3,3}$ Gram satisfies $K^2 = 8K$. Thus $Q = K/8$ is primitive of rank 81. With P the intrinsic $20_{\text{chart}} \otimes 15_{\text{W33}}$ copy,

$$PQP = \tfrac{1}{3}P, \qquad QPQ = \tfrac{1}{3}Q.$$

Writing $R = \frac{3}{2}(E-P)Q(E-P)$ and $S = (E-P) - R$ gives

$$E = P \oplus R \oplus S, \quad \operatorname{rank}(P,R,S) = (81,81,81), \quad RQR = \tfrac{2}{3}R, \quad SQ = QS = 0.$$

74.27 E6 odd-triangle and packet/global-$K_{3,3}$ no-go audits

The 1080 obstruction objects are exactly the E6-sign-even triangles of $H_{36} = \mathrm{SRG}(36, 20, 10, 12)$; the complementary 120 sign-odd triangles are the Steiner orbit. For intersection sizes $0, 1, 2$, the three canonical even/odd incidence Grams have Steinberg actual ranks respectively 0, 0, 0. Direct dark-projector hits: `[]`.

For a fixed packet, its order-576 stabilizer has orbit sizes [48, 72, 96, 144] on the 360 global Schlaefli $K_{3,3}$ witnesses. The classes meeting its three incident charts in $0, 1, 2$ vertices have sizes 192,96,72. A canonical equivariant eight-witness refinement is `False`; hence the local abstract $K_{4,4} \to S_4/V_4 \simeq S_3 \to K_{3,3}$ quotient is not an eight-element subfamily of the distinct global witness shell.

74.28 Explicit $M_3(\mathbb{Q})$ multiplicity algebra

The primitive frame P, R, S plus deterministic orbital connectors yields all nine rational matrix units e_{ij} and verifies

$$e_{ij}e_{kl} = \delta_{jk}e_{il}.$$

Thus the complete Steinberg multiplicity commutant is explicit as $M_3(\mathbb{Q})$. The geometric $K_{3,3}$ projector has matrix-unit coordinates `[['1/3', '1/2', '0'], ['4/9', '2/3', '0'], ['0', '0', '0']]`. The older $\{-4, 0, +4\}$ orbital spectral frame is expressed in the same coordinates. These are representation multiplicity coordinates, not a physical flavor/generation matrix.

74.29 Binary 48: MeatAxe comparison without guessing Ext

MeatAxe gives $H_{1,48} \cong \Omega_{48} =$ `False` and $A_{24} \cong B_{24} =$ `False`. Their factor-dimension multisets are $H_1 : [1, 1, 1, 1, 8, 8, 14, 14]$ and $\Omega : [1, 1, 1, 1, 8, 8, 14, 14]$; the 576-dimensional $\mathrm{Hom}(B_{24}, A_{24})$ has factor dimensions [1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 6, 8, 8, 8, 8, 8, 8, 8, 8, 8, 14, 14, 14, 14, 14, 14, 14, 14, 14, 14, 14, 40, 40, 40, 40, 40, 40]. The independent splitting-equation certificate proves $\mathrm{Ext}^1(B_{24}, A_{24}) \neq 0$, so its dimension is at least one; the exact value remains open because stock Cohomolo hits its MDIM ceiling on the full Hom module.

Boundary. These are exact finite incidence, root-system, representation, modular-module, and linear-algebra statements. The 1/3 overlap, dark 81-space, and 3×3 coordinates are not by themselves particle mixing, masses, couplings, fields, spacetime, or dynamics.

74.30 The two building homologies and their common obstruction router

The order-25920 group carried by the construction has two rank-two building realisations. Their Levi graphs have

$$(V, E) = (80, 160), \qquad (72, 135),$$

so their first-homology dimensions are respectively

$$160 - 80 + 1 = 81, \qquad 135 - 72 + 1 = 64.$$

The first is the $W(3,3)$ building. The second is the $GQ(4,2)$ building, and the existing objectwise atlas identifies its $27 + 45$ vertices and 135 incidences with the cubic-surface 27 lines and 45 tritangent planes, and simultaneously with the selected E_8 ten-D_4 charts and $D_4 \oplus D_4$ packets. The two homology characters have norm one and inner product zero. By the Solomon–Tits interpretation these are the degree-81 and degree-64 Steinberg modules for the two exceptional rank-two presentations; the finite character calculations themselves do not depend on that name.

The older 81-dimensional rational clique-Hodge sector is now identified without a dimension argument: its oriented simplicial Lefschetz character is equal, element by element on all 25920 group elements, to the $W(3,3)$ Levi-building H_1 character. Its value profile is

$$-3^{810},\ -1^{3240},\ 0^{16640},\ 1^{5184},\ 9^{45},\ 81^{1},$$

and its character norm is one. Thus the characteristic-zero harmonic 81-space used earlier in the paper is exactly the same irreducible Steinberg module as the building cycle space.

On the degree-1080 obstruction carrier the two building modules occur with multiplicity three each,

$$3\,H_1(W(3,3)) \oplus 3\,H_1(GQ(4,2)) = 3 \cdot 81 \oplus 3 \cdot 64$$

as part of the full Wedderburn decomposition. In contrast, the two nonconjugate degree-216 source shells select them complementarily: the five-circuit shell contains the 81 once and the hemisystem shell contains the 64 once.

The degree-2160 BT796/48-packet carrier contains nine copies of the 81 module and five copies of the 64 module. Projecting its complete 113-dimensional equivariant Hom space to the two multiplicity-three target blocks gives

$$\dim \operatorname{span}_{\mathbb{Q}}(81^3) = 9, \qquad \dim \operatorname{span}_{\mathbb{Q}}(64^3) = 9.$$

Consequently one finite geometric carrier generates both complete multiplicity algebras,

$$\operatorname{End}_G(81^3) \oplus \operatorname{End}_G(64^3) \simeq M_3(\mathbb{Q}) \oplus M_3(\mathbb{Q}).$$

74.30.1 Chain-level materialisation

This statement is no longer only character-theoretic. Exact oriented boundary matrices give integral cycle bases

$$Z_{81} \in \mathbb{Z}^{160\times 81}, \qquad Z_{64} \in \mathbb{Z}^{135\times 64}.$$

For each of the three primitive rank-81 obstruction projectors and each of the three primitive rank-64 projectors, a source-chamber/obstruction orbital incidence map was projected and composed with the appropriate cycle basis. This produces six explicit rational intertwiners

$$H_1(W(3,3)) \longrightarrow P_i\mathbb{Q}^{1080}, \quad i = 1,2,3,$$

$$H_1(GQ(4,2)) \longrightarrow Q_i\mathbb{Q}^{1080}, \quad i = 1,2,3.$$

Every map is generator-equivariant and has full column rank, independently verified modulo 1000003 and 1000033. Thus all six multiplicity copies are concrete images of building cycles rather than labels inferred from equal dimensions.

Boundary. These are exact statements in finite incidence geometry, building homology and characteristic-zero representation theory. The two H_1 modules, the $M_3(\mathbb{Q})$ multiplicity coordinates and the six primitive images are not thereby particle generations, matter fields, masses, mixing matrices, spacetime directions or physical propagation channels. The ternary CSS logical quotient also has dimension 81, but its characteristic-three module identification remains a separate modular question.

74.31 Outer parity, modular gluing, and the ternary logical Steinberg

The transitive obstruction carrier

$$\Omega_{1080} = \{27 \text{ completion charts}\} \times \{40 \text{ W33 lines}\}$$

contains multiplicity-three copies of both building Steinberg modules. The BT796 2160-state carrier realizes the corresponding multiplicity endomorphism algebra by explicit two-step incidence paths,

$$\mathrm{End}_G(St_{81}^{\oplus 3} \oplus St_{64}^{\oplus 3}) \supset M_3(\mathbb{Q})_{81} \oplus M_3(\mathbb{Q})_{64}, \qquad G = PSp_4(3).$$

The explicit multiplier--1 symplectic similitude

$$s = \mathrm{diag}(1, 2, 1, 2) \pmod 3$$

normalizes G and induces the $PGSp_4(3)/PSp_4(3)$ outer involution on all of these carriers. Solving its action on the exact matrix units gives the projective multiplicity-space conjugators

$$J_{81} = \mathrm{diag}(1, 1, -1), \qquad J_{64} = I_3.$$

Thus the degree-81 multiplicity space has a canonical outer-parity splitting

$$\mathbb{Q}^3 = \mathbb{Q}_+^2 \oplus \mathbb{Q}_-,$$

whereas the outer involution is trivial on the degree-64 multiplicity space. All three primitive rank-81 diagonal projectors are individually outer-fixed; the parity distinction occurs in the inter-copy morphisms. The independently constructed $K_{3,3}$-selected rank-81 projector is also outer-fixed.

This parity is visible already in concrete circuit incidence. The complete 17-orbital G-equivariant Hom family from the circuit-216 carrier into Ω_{1080} has two zero Steinberg maps and fifteen nonzero rank-81 images. Relative to J_{81}, their projective multiplicity lines split as

$$3 \text{ outer-odd}, \qquad 2 \text{ outer-even}, \qquad 10 \text{ mixed}.$$

The three odd incidences all select exactly the line

$$[0 : 0 : 1],$$

while the two pure even incidences select exactly

$$[1 : -8/3 : 0].$$

Hence parity-pure degree-81 channels occur as primitive incidence relations; they need not be manufactured by an outer symmetrization.

The characteristic-3 reduction is non-semisimple in precisely the direction suggested by this parity splitting. For the three integral numerator chain maps associated with the rational $St_{81}^{\oplus 3}$ projectors, all three individual reductions have rank 81, but

$$\operatorname{rank}_{\mathbb{F}_3}[Y_0\ Y_1\ Y_2] = 162,$$

with

$$\operatorname{im} Y_0 = \operatorname{im} Y_1, \qquad \operatorname{im} Y_0 \cap \operatorname{im} Y_2 = 0.$$

The two rational outer-even channels therefore glue to one modular 81-space, while the outer-odd channel survives as a second independent modular 81-space. More strongly, when the maps are written on the same integral W33 building-cycle basis Z, the exact source-coordinate intertwiner between the two even reductions is

$$F = I_{81} \quad \text{over } \mathbb{F}_3,$$

so

$$Y_0 h = Y_1 h \qquad (h \in \mathbb{F}_3^{81}).$$

The same building-cycle coordinates give an explicit bridge to the canonical ternary clique-chain CSS code. If

$$\Phi(p, L) = \sum_{q \in L \setminus \{p\}} [p \to q]$$

is the characteristic-3 chamber-to-edge map, then the previously proved splitting

$$\ker d_1 = \operatorname{im} d_2 \oplus \Phi(H_1(\text{W33 building}; \mathbb{F}_3))$$

identifies the logical module of the $[[240, 81, 3]]_3$ code with the modular building Steinberg. On the shared 81-column basis Z one now has the coordinate-level correspondence

$$(\Phi Z)h \ \longleftrightarrow\ Y_{\text{even}} h, \qquad h \in \mathbb{F}_3^{81},$$

where both matrices have rank 81. Thus the common modular obstruction image descending from the two rational outer-even channels and the CSS logical Steinberg are explicitly the same abstract $PSp_4(3)$ module in the same building coordinates, while living on different finite carriers.

The explicit $PGSp$ transport reveals an additional modular effect that is not visible at the restricted PSp level. Let S be the involution induced by s on the shared building-homology coordinates. Solving the source transport matrices rather than assigning them from the characteristic-zero labels gives

$$sY_{\text{even}} = Y_{\text{even}}(-S), \qquad sY_{\text{odd}} = Y_{\text{odd}} S, \qquad s(\Phi Z) = (\Phi Z)S.$$

All three rank-81 images are individually outer-invariant. Hence the chosen integral reduction modulo 3 *reverses the extension sign* attached to the rational parity labels: the image descending from the rational-even pair carries the sign-twisted $PGSp$ extension, whereas the image descending from the rational-odd channel and the CSS logical Steinberg carry the untwisted extension. Consequently the CSS–obstruction correspondence above is an exact $PSp_4(3)$ bridge but not an equality of $PGSp_4(3)$ extensions for the modular rational-even image. This sign inversion is a property of the explicit integral injection and characteristic-3 reduction; it is not a relabeling of the characteristic-zero multiplicity involution J_{81}.

For comparison, reducing the chosen integral numerator maps for $St_{64}^{\oplus 3}$ modulo 2 gives individual ranks $(64, 0, 64)$ and combined rank 128. This is a statement about the modular images of the

integral numerators, not a reduction of the characteristic-zero rational idempotents; the latter have denominators divisible by the defining primes.

Finally, the two degree-216 selector carriers over the common degree-36 spread/double-six base must be kept distinct. Circuit-216 and complementary hemisystem-pair-216 are the two nonconjugate S_5-over-S_6 fibrations, exchanged locally by the exceptional outer automorphism of S_6. The circuit carrier selects St_{81} and not St_{64}; the paired-hemisystem carrier selects St_{64} and not St_{81}. The actual global $PGSp/PSp$ outer involution exchanges neither carrier and neither Steinberg; indeed character degree forbids any automorphism from exchanging the degree-81 and degree-64 Steinbergs. The exceptional S_6 exchange is therefore a local nonextendable fibre twist. The carrier choice is a genuine binary finite carrier fork over the canonical 36-state base, not a substrate gauge equivalence, whereas the $2 + 1$ parity structure above is an internal global-outer grading of the degree-81 router after one carrier has been chosen.

Scope. All statements in this subsection are exact finite incidence, representation-theoretic, modular-homological, or CSS-code statements. The words "even", "odd", "channel", "carrier fork", "outer twist", and "sign inversion" refer to the explicitly computed finite group actions and integral modular reductions. They do not by themselves identify particle generations, physical chirality, continuum fields, or dynamical propagation.

74.32 A typed universal microVM above the W33 routing fabric

The existing packet VM and recursive HoloBox runtime can be sharpened into a typed virtual-machine contract by incorporating two corrections from the current frontier. First, the two order-51840 groups used by the architecture must occupy different instruction namespaces:

$$\mathrm{Sp}(4,3) \qquad \text{and} \qquad \mathrm{PGSp}(4,3) \cong W(E_6).$$

The former is the symplectic central double cover of $\mathrm{PSp}(4,3)$ used for a Clifford lift; the latter is the projective/similitude outer extension. Equal orders do not identify the extensions. Second, the two degree-216 carriers over the common 36-state spread/double-six base are not gauge-equivalent. They are immutable construction-time machine types:

$$\text{circuit-216} \longrightarrow St_{81}, \qquad \text{paired-hemisystem-216} \longrightarrow St_{64}.$$

Accordingly the reference VM rejects a carrier/module mismatch and exposes no runtime carrier-conversion opcode.

On top of this typed transport layer, the software-universality core is chosen deliberately from standard computability theory rather than inferred from the finite counts. A guest program is an arbitrary finite two-counter machine with macro instructions

$$\mathrm{INC}(r,j), \qquad \mathrm{DECJZ}(r, j_{\neq 0}, j_0), \qquad \mathrm{HALT}\,.$$

The counters range over $\mathbb{N}$ in the abstract semantics. Since two-counter machines are a universal model of computation, this gives Turing-complete *VM semantics*. Each semantic transition is then wrapped in a deterministic W33 transport certificate. Reconstructing the symplectic geometry gives

$$\mathrm{SRG}(40,12,2,4), \qquad \mathrm{diam} = 2,$$

so consecutive execution portals require at most two W33 hops. A certificate contains the pre- and post-state digests, typed instruction, program counters, immutable carrier, logical-module dimension, route, line buses, and the next hash-chain root.

The executable witness `analysis/w33_typed_universal_microvm.py` verifies the geometry and the type discipline, checks deterministic replay, and executes a regression guest

$$(c_0, c_1) = (7, 11) \longmapsto (18, 0)$$

in 24 certified steps, with maximum route length two. The companion tests exercise both carrier types and deliberately attempt the forbidden retyping.

Architectural interpretation. The resulting separation is

guest meaning $\longrightarrow$ typed state transition $\longrightarrow$ W33 placement and route $\longrightarrow$ physical realization.

Thus routing is proof-carrying realization metadata around a computation, not a silent redefinition of the guest semantics. The existing content-addressed recursive runtime supplies the natural scalable state mechanism: a network of microVMs can be stored as a Merkle-rooted state object and loaded through the same interface as one leaf VM.

Scope. This is a theorem about a software virtual machine whose transitions are certifiably routed by W33. It does *not* prove that one finite 40-node physical device contains unbounded memory; an implementation needs recursive or external scalable storage. It also does not make the finite Clifford kernel quantum-universal. The photonic quantum architecture still requires the separately validated non-Clifford resource port, together with physical threshold, loss, and calibration closure.

74.33 Persistent 40-ary memory and monotone W33 capabilities

The abstract counter-machine semantics of the typed microVM does not require us to pretend that one finite 40-point cell stores an infinite tape. Instead the memory family is a sparse persistent 40-ary Merkle trie. An address of depth d is a tuple

$$a = (a_1, \ldots, a_d), \qquad a_i \in \{0, \ldots, 39\},$$

so the complete depth-d address space has capacity

$$\boxed{40^d}.$$

Only written paths consume content-addressed nodes. A write returns a new root digest; the previous root remains a valid snapshot and all untouched subtrees are shared by SHA-256 identity. Repeating an identical write is deduplicated and returns the same root.

Memory authority is represented by an immutable capability

$$(\text{carrier},\ \text{address prefix},\ \text{rights}).$$

Derived capabilities may extend the prefix and remove rights, but may not widen the rights set, escape the prefix, or change the construction-time carrier. Thus a capability for the circuit-216/ St_{81} machine cannot be applied to a paired-hemisystem-216/ St_{64} memory and vice versa.

The same address digits give a virtual placement geometry. For equal-depth addresses, route one coordinate at a time through $W(3, 3)$. Since the base routing diameter is two, the Cartesian execution-address metric satisfies

$$\boxed{d_{\mathrm{VM}}(a, b) \le 2d}.$$

The executable witness `analysis/w33_merkle_capability_memory.py` reconstructs the W33 routing geometry and verifies persistent snapshots, subtree sharing, deduplication, prefix confinement, rights monotonicity, carrier isolation, and the $2d$ route bound. A depth-5 test route uses nine hops against the bound ten; a write at depth three creates exactly the four path nodes expected.

Scope. The family has no fixed depth ceiling in the abstract model, but each concrete snapshot has finite depth and finitely many blobs. This is a scalable virtual memory architecture, not literal infinite storage in one finite device. It supplies the missing systems interpretation of unbounded universal-machine memory: any finite execution consumes only finite content-addressed state, while the address family can be extended as the computation grows.

74.34 Validated guest code, reversible history, and heterogeneous execution

The typed universal microVM now has a real guest-language front end rather than only hand-written counter programs. The executable witness `analysis/w33_wasm3_frontend.py` decodes the standard WebAssembly binary envelope and a deliberately bounded Core-3.0 integer/control subset, validates the operand/control stack, executes a structured `block/loop/br_if/br` program, and only after successful validation assigns W33 portals and Holonet packet slots. The regression program computes $1 + 2 + 3 + 4 + 5 = 15$. A type-invalid mutation is rejected both by validation and by lowering, so invalid guest code receives no transport identity. The scope is intentionally narrower than the complete WebAssembly 3.0 instruction set; unsupported valid constructs are rejected rather than approximated.

The history-as-time construction has also been promoted from an in-memory undo stack to persistent carrier-bound storage. In `analysis/w33_bennett_merkle_reversible_runtime.py`, each certified undo token is mirrored into the 40-ary Merkle memory and authenticated again before an inverse step is accepted. The resulting Bennett cycle is executable:

$$\text{compute} \longrightarrow \text{copy output} \longrightarrow \text{uncompute}.$$

For the 24-step sample $(7, 11) \mapsto (18, 0)$, the copied output survives while the work state and journal return to their exact initial values. An explicit `DISCARD_HISTORY` operation remains the noninvertible boundary. The software records byte and Merkle-blob counts only; no thermodynamic energy is inferred from those counts.

The semantic-to-hardware refinement is now explicit as well. The witness `analysis/w33_universal_to_holone` composes the counter-machine certificates with the already verified BT1698 packet machine and BT1377 physical-computation contract. The 24 semantic steps occupy 24 of the Q6/tomotope body slots, hence two 72-tick packet microframes. Each occupied slot retains the fixed

$$\texttt{LOAD_FLAG} \to \texttt{FLIP_Q6_AXIS} \to \texttt{LATCH_VERTEX}$$

three-phase packet transition. Separately, the BT1377 optical-word contract retains its three tritter/EOM pulses plus five delay-line switch pulses. These 3-phase and 8-tick decompositions are linked as distinct refinement objects and are not falsely identified term-by-term. The deterministic kernel remains Clifford/control; the non-Clifford resource port remains explicitly required for quantum universality and is not implemented by this software lowerer.

The two inequivalent 216-state carriers are now treated as heterogeneous processors rather than two views of one processor. Writing a local state as

$$s = 6b + t, \qquad b \in \{0, \dots, 35\}, \quad t \in \{0, \dots, 5\},$$

the executable IPC witness `analysis/w33_heterogeneous_36_ipc.py` exposes only the common base address b through the neutral syscalls `SEND36`, `RECV36`, and `ACK36`. The private fibre tag t is never translated between circuit/ST81 and paired-hemisystem/ST64. Thus the common 36-state quotient is a message/syscall ABI, not a gauge transformation; an attempted carrier-state translation is rejected.

On the deployment side, the sibling Holotrade runtime now consumes the same construction-time distinction: scheduler placement and launch admission require an exact carrier match, GoMicroVM deployment identity commits to the W33 profile, and the RTL admission predicate refuses invalid profiles, carrier mismatches, and aliases between the equal-order Clifford-lift and projective/Weyl namespaces.

Scope. These are executable software/RTL architecture statements. They strengthen the path from validated guest code to typed virtual hardware and expose the exact remaining physical boundary. They do not constitute a complete WebAssembly implementation, fabricated reversible photonics, a calibrated optical machine, or a proof that the explicit non-Clifford port has been physically realised.

74.35 Capability-backed guests, finite RTL refinement, and typed irreversibility

The validated guest front end now has an executable multi-function runtime rather than only a one-function arithmetic witness. In `analysis/w33_wasm3_capability_runtime.py`, a deliberately bounded WebAssembly Core binary subset supports typed calls and function imports, mutable/immutable `i32` globals, and `i32.load/store` against one linear memory. A WebAssembly page is not translated into an unchecked host pointer. Instead, each 64-KiB page is placed below one top-level digit of the persistent 40-ary W33 Merkle trie,

$$a = (p, d_1, d_2, d_3, d_4), \qquad p \in \{0, \dots, 39\}, \quad d_i \in \{0, \dots, 39\},$$

and memory access is mediated by a carrier-bound prefix capability. The current executable mapping therefore supports at most forty WebAssembly pages; that ceiling is a software choice of this page-to-prefix construction, not a bound implied by WebAssembly or by $W(3,3)$. The regression module contains two defined functions, a mutable global and one memory, computes the value 5, and checks that an invalid call target fails validation before receiving any W33 transport identity.

The semantic-to-packet refinement now also has a finite RTL realisation. The module `rtl/w33_universal_pack` accepts one lowered `INC`, `DECJZ`, or `HALT` macro-instruction and refines it into

$$\texttt{LOAD_FLAG} \longrightarrow \texttt{FLIP_Q6_AXIS} \longrightarrow \texttt{LATCH_VERTEX}.$$

Architectural state is frozen through the first two phases and the counter, program counter and target portal commit only at the latch edge. The companion formal module and `rtl/verify_w33_universal_packet_` prove those one-step equations over all valid opcodes and all finite 32-bit pre-states. The independent Python witness replays the existing 24-step $(7, 11) \mapsto (18, 0)$ computation and checks the RTL equations macrostep by macrostep. This is a finite-width refinement theorem; it does not replace the unbounded-counter theorem used for abstract Turing completeness.

The non-Clifford boundary is now split into its two physically different nine-outcome objects instead of giving them one overloaded name. The executable port `analysis/w33_qutrit_t_teleportation_port.py` uses

$$T = \mathrm{diag}(1, \zeta_9, \zeta_9^{-1}), \qquad \zeta_9 = e^{2\pi i/9}.$$

A nine-outcome Hesse SIC is used as an ideal factory/admission fingerprint for a consumed $T|+\rangle$ sample. Separately, the injection step uses the nine qutrit Bell outcomes $(a, b) \in \mathbb{F}_3^2$. For the Choi resource $(I \otimes T)|\Phi_3\rangle$, Bell outcome (a, b) produces $TX^aZ^{-b}|\psi\rangle$ up to the common postselection amplitude, and the feed-forward

$$C_{ab} = TZ^bX^{-a}T^\dagger$$

is checked to normalize both qutrit Pauli generators for every one of the nine outcomes and to restore $T|\psi\rangle$. The 72-tick packet keeps the existing $48 + 24$ split: the three eight-tick epilogue words are typed as Hesse factory audit, Bell-outcome record, and Clifford feed-forward commit. A magic ledger accounts separately for the audit sample and the accepted injected resource. No code-level fault-tolerance threshold, finite-shot Hesse calibration, detector efficiency, optical loss, or physical magic-state factory follows from this state-vector refinement.

The common 36-state carrier quotient has likewise been promoted from a minimal mailbox to a small heterogeneous kernel in `analysis/w33_heterogeneous_36_kernel.py`. Per-channel sequence numbers, one-use nonces, replay rejection, bounded queues/backpressure, receiver-bound immutable content handles, and one-shot acknowledgements are now explicit. An exhaustive software noninterference check varies the sender's private six-state fibre tag over all six values while holding carrier, base address, destination, payload and sequence fixed; the public transcript is identical in all six runs and contains neither `state216` nor the private fibre tag. The real WebAssembly import surface is `SEND36`, `RECV36`, and `ACK36`; endpoint identity is host-bound, so guest code never receives a private-fibre operand. This proves noninterference for the deterministic message transcript of this kernel, not a cache/timing side-channel theorem for fabricated hardware.

Finally, irreversible erasure is now a typed economic event rather than an implicit side effect. The sibling Holotrade module `js/reversible-compute-settlement.js` distinguishes `REVERSIBLE_COMPUTE`, `HISTORY_RETAIN`, `UNCOMPUTE`, and `DISCARD_HISTORY`. Uncomputation can retire live history without creating an erasure charge. Only explicit discard of b bits at temperature T creates the comparison floor

$$E_{\mathrm{L}} = b k_{\mathrm{B}} T \ln 2.$$

That value is stored as a theoretical lower bound and is never added to or substituted for Holotrade's modeled/measured device-joule field. Supplemental prices for reversible operations, retained bit-seconds, and discarded bits are explicit market-policy tariffs whose defaults are zero. A three-objective Pareto routine then exposes non-dominated choices in execution latency, peak history storage, and irreversible erase count rather than collapsing those resources into one invented scalar physics cost.

Scope. This closure strengthens the executable software/RTL path from a standard guest binary through capability memory, finite packet hardware, a concrete qutrit non-Clifford gate-teleportation model, heterogeneous syscalls and explicit erasure accounting. It does not establish unbounded physical RAM, a fault-tolerant magic factory, a fabricated reversible processor, a physical side-channel proof, or a measured approach to the Landauer limit.

74.36 Asynchronous components, typed checkpoints, and proof-carrying execution

The heterogeneous execution stack now has a component boundary rather than only raw host calls. The executable witness `analysis/w33_component_async36.py` requires exact import/export type agreement and restricts cross-carrier interfaces to neutral values. Bounded `SEND36` backpressure is represented by a future: a full destination queue leaves the future pending, receiving one message frees capacity, and a runtime pump resolves the pending send. Streams and futures therefore compose without exposing the private six-state fibre coordinate. This is a W33-native component layer inspired by contemporary typed asynchronous WebAssembly runtime patterns; it is not presented as an implementation of the external Component Model specification.

The data plane is likewise tightened. In `analysis/w33_zero_copy_merkle36.py`, a carrier-bound persistent memory may publish an immutable Merkle subtree by digest into the common

36-state fabric. Publication and delegation allocate no additional content blobs: distinct endpoint-bound read handles refer to the same immutable subtree root. A later copy-on-write update of the source memory produces a new subtree root while the previously published view remains unchanged. Here "zero-copy" means content-address reuse in the software model, not a claim about DMA, cache coherence, or physical optical copy energy.

Migration is split into two typed operations. A full checkpoint preserves the VM state, carrier-local fibre coordinate, trace root, and memory snapshot and is restorable only on the same 216-state carrier. A cross-carrier handoff uses a neutral continuation at an explicit syscall boundary. It carries classical guest state, the common base-36 address, and immutable shared-object roots, but not the private fibre tag or an ST81/ST64 quantum state. Resumption on the other carrier creates a new machine instance, a fresh private fibre coordinate, and a new trace lineage. Thus heterogeneous failover does not introduce an unproved 81-dimensional to 64-dimensional state isomorphism.

A new execution passport then binds the previously separate proof obligations. For a packet, the content-addressed passport commits to the guest validator, component link, Merkle memory root and capability, immutable carrier and logical dimension, the distinct Clifford-lift and projective/Weyl namespaces, packet refinement evidence, non-Clifford resource budget, history root, and erasure policy. Packet admission refuses a carrier relabel, magic-budget overdraft, namespace alias, stale passport identity, or missing evidence. The passport hash is an integrity commitment; authorization and remote attestation remain a separate signed/hardware-root layer.

Finally, `analysis/w33_causal_time_ledger.py` makes the project's "time as history" intuition operational at the VM layer. Events form an append-only causal DAG. Reversible computation can revisit an earlier semantic state at a later causal depth because retained history distinguishes the two occurrences. Branches from a common snapshot are causally incomparable, and content-equal branches may join without erasing their distinct histories. An explicit `DISCARD_HISTORY` event creates a non-reversible authority cut: subsequent execution cannot traverse backward across that edge using retained undo state. This is a software causal/recoverability model, not a claim that physical time is derived from computation or that a logical discard proves thermodynamic erasure.

Magic as a typed accelerator resource. The non-Clifford scheduler now reserves and consumes content-addressed `HESSE_T_RAW` tokens at typed packet slots rather than treating "magic-capable" as a Boolean host feature. Exact logical qutrit-T execution and fault-tolerant qutrit-T execution are different assurance classes. The latter remains fail-closed until a W33-specific encoding map and threshold/noise certificate are present, even if an external qutrit distillation code is registered as a candidate adapter.

74.37 Revocation, deadlock control, and hardware passport admission

The capability system now separates immutable authority tokens from a mutable revocation root. The executable witness `analysis/w33_capability_epoch_revocation.py` attaches an issuer and epoch to the existing monotone Merkle-memory capability. Selective revocation of a capability invalidates descendants carrying its ancestry marker while unrelated siblings remain usable; rotating the issuer epoch invalidates all old tokens at once. Fresh tokens in the new epoch can recover only the rights and prefixes granted by the underlying monotone capability. Revocation therefore does not require in-place mutation and does not create a rights-escalation channel. This is a software authority plane, not a hardware-tag or distributed consensus implementation.

Asynchronous component composition also gains a liveness control plane. The witness `analysis/w33_async_de` converts neutral future/stream/mailbox dependencies into a wait-for graph and computes strongly

connected components. A three-component cyclic wait is detected, while an ordinary provider–consumer chain is not. Cycle breaking requires a scoped cancellation capability; unauthorized cancellation fails, and a derived single-task capability can cancel one deterministic low-priority victim and release the cycle. The detector operates only on neutral task/resource identities and never serializes a carrier-private six-state fibre coordinate.

Finally, the execution passport reaches RTL admission. The module `rtl/w33_passport_packet_gate.v` compares the complete 256-bit packet passport digest with the admitted digest and permits the downstream microsequencer start only when all of

$$\texttt{profile_valid}, \qquad P_{\mathrm{packet}} = P_{\mathrm{admitted}}, \qquad C_{\mathrm{req}} = C_{\mathrm{host}}, \qquad N_{\mathrm{Clifford}} \neq N_{\mathrm{Weyl}}, \qquad m_{\mathrm{req}} \leq m_{\mathrm{budget}}$$

hold. The companion Yosys SAT harness proves the combinational gate equation and each fail-closed implication. The RTL does not compute SHA-256 or establish who authorized the admitted digest; it enforces an already authenticated passport identity at the finite hardware boundary.

On the sibling Holotrade runtime, recovery now follows the same carrier theorem: a healthy same-carrier host is preferred for full checkpoint restoration even when a cross-carrier host is cheaper. Only when no same-carrier target exists may the scheduler choose a cross-carrier neutral continuation, and then only at an explicit syscall safe point with a content-addressed neutral-state record. The target begins a new machine identity rather than retyping the checkpoint.

74.38 Execution identity beyond the guest image: attestation, concurrency, revocation, retention, and magic

The runtime frontier now makes five previously separate control planes part of the execution contract. The relevant executable witnesses are

`analysis/w33_concurrency_replay_certificate.py`	deadlock/cancellation plus deterministic wake replay,
`analysis/w33_execution_passport.py`	passport v3 and packet admission,
`analysis/w33_signed_epoch_bus.py`	signed authority rotation over the common 36-state bu
`analysis/w33_qutrit_20_7_2_adapter_attack.py`	exact external-code reconstruction and W33 adapter a
`analysis/w33_magic_resource_scheduler.py`	audit-derived non-Clifford assurance gate.

The sibling Holotrade witnesses are `js/w33-measured-boot-attestation.js`, `js/w33-strong-root-storage.js` `js/w33-passport-deployment.js`, and `js/w33-failover-orchestrator.js`.

Concurrency is part of execution identity. A deterministic replay certificate now commits the pre-resolution wait-for graph, the detected strongly connected deadlock component, deterministic victim selection, scoped cancellation authority and event, the post-cancellation graph, and the asynchronous wake schedule. Thus two executions with the same guest and final payload but different deadlock resolution or wake order carry different concurrency roots. In particular the passport has been strengthened to

$$P = H(G, M, C, \Gamma, \Pi, \mathcal{M}, \mathcal{H}, e, R, W, X, S, Q),$$

where G is guest identity, M memory state/capability, C component link, Γ the immutable carrier and the two non-aliased symmetry namespaces, Π packet refinement, $\mathcal{M}$ magic budget, $\mathcal{H}$ reversible-history policy, e the capability epoch, R the revocation root, W the wait-for root, X the cancellation-event root, S the asynchronous schedule root, and Q the temporal-GC registry root. Changing any committed control-plane root changes the passport identity.

Authenticated rolling authority on the neutral 36-state bus. The capability authority can now issue an Ed25519-signed transition

$$(e, R, T_{i-1}) \longrightarrow (e+1, R', T_i),$$

where T_i commits the issuer, old and new epoch/root, and previous transition identity. A replica accepts the transition only after signature verification, exact chain matching, exact current-state matching, and a one-generation increment; replay, epoch jumps, and body tampering are refused. The signed transition is transported as an immutable shared object through the existing

$$\mathrm{ST81} \leftrightarrow 36 \leftrightarrow \mathrm{ST64}$$

message fabric without exposing the private six-state fibre coordinate. This is authenticated issuer propagation, not Byzantine consensus.

A checkpoint is therefore pinned to the authority state under which it was created. Even an ST81-to-ST81 restore is not a full restore after the authority has rotated. Recovery must instead cross a verified syscall boundary as a neutral continuation and mint a fresh target passport under the current epoch/root. The construction-time 81- and 64-dimensional carriers remain distinct; no runtime $81 \leftrightarrow 64$ state isomorphism is introduced.

Measured boot and confidential-VM binding. On the Holotrade side, the deployment passport is now bound to a measured-boot challenge containing the exact passport identity, GoMicroVM deployment digest, runtime-public-key digest, machine type and logical dimension, and current capability epoch/revocation root. A provider-specific TPM2 or SEV-SNP verifier may reduce raw hardware evidence to a normalized verdict containing launch measurement, reported TCB identity, signer-chain identity, and explicit verification bits for the vendor signature, measurement policy, TCB policy, and runtime-key binding. Holotrade accepts that verdict only when it is Ed25519-signed by a pinned verifier key and every required verification bit is true; software-only evidence cannot be relabelled as hardware-backed. The resulting binding is inserted into the signed delivery-receipt metadata.

This is deliberately a two-layer trust statement. The current Holotrade module verifies the signed normalized verifier verdict; it does *not* itself parse TPM event logs, verify TPM quotes, validate AMD VCEK certificate chains, or establish a hardware root of trust. Those operations belong to the external provider-specific verifier until a native verifier is added.

Persistent-state economics follows reachability, not Landauer. The temporal Merkle collector distinguishes strong roots—live VM, checkpoint, retained history, and delegated shared objects—from hash-only receipt/audit roots. Holotrade now mirrors that distinction with

$$B_s = \int N_{\text{reachable blobs}}(t)\, dt,$$

implemented discretely as strong-root blob-seconds, with an optional byte-second companion. Only strong roots accrue storage-retention tariffs. A hash-only receipt can preserve content identity after the underlying bytes become unreachable without continuing to pin storage. The scheduler can therefore optimize a three-axis frontier

$$(\text{latency},\ \text{strong blob-seconds},\ \text{irreversible erased bits}).$$

These tariffs are explicit market policy and are kept separate from both measured device joules and the Landauer lower bound.

Exact reconstruction of the external $[[20,7,2]]_3$ candidate. The qutrit magic-state-distillation attack now reconstructs the Prakash–Saha ternary triorthogonal family directly rather than storing the candidate as metadata. For $m = 3$ one starts with length 27 vectors

$$w = (0, 1, 2, 0, 1, 2, \ldots),$$

and block vectors $v^{(a)}$ that are 1 on block a, 2 on the final three coordinates, and zero elsewhere. Puncturing the coordinates

$$1, 4, 7, 10, 13, 16, 19$$

produces the 9×20 matrix with seven logical rows $H_1 = (v^{(1)}, \ldots, v^{(7)})$ and two X-stabilizer rows $H_0 = (w, v^{(8)})$. The executable audit verifies

$$\operatorname{rank}_{\mathbb{F}_3} H = 9, \qquad \operatorname{rank}_{\mathbb{F}_3} H_0 = 2, \qquad k = 20 - 2 - (20 - 9) = 7,$$

pairwise/triple triorthogonality, cubic row norms $2^7 0^2$, absence of a weight-one logical Z, and existence of a weight-two logical Z, reproducing the advertised $[[20,7,2]]_3$ code parameters.

But code validity is not a Holonet FT adapter. The resulting scheduler decision remains

`REFUSE_FAULT_TOLERANT_ADAPTER`.

The repository does not yet contain an explicit twenty-physical-qutrit W33/Holonet selector/intertwiner carrying H_0, H_1 into physical stabilizer/logical operators, a mapped syndrome/distillation packet compiler, or a threshold/noise certificate for that mapped circuit. Moreover the existing Pass-78 audit records that the architecture's cited $[[66,8,3]]_3$ substrate still lacks a canonical generator/stabilizer witness in the audited spine; the exact runnable threshold demonstration remains the $[[5,1,3]]_3$ stand-in. Accordingly the magic scheduler now derives the $[[20,7,2]]_3$ adapter state from the executable audit: the external code can be verified while fault-tolerant scheduling remains disabled.

Engineering boundary. This closure establishes content-addressed execution identity across concurrency, authority rotation, persistence, deployment attestation, and non-Clifford scheduling. It does not establish a native TPM/SEV-SNP verifier, distributed consensus on revocation roots, secure physical media erasure, a fabricated photonic processor, or a W33-specific fault-tolerant magic-state-distillation threshold. Those remain separate witness obligations rather than being inferred from the software architecture.

75 Native attestation, quorum authority, storage-aware placement, and replay receipts

This pass closes five runtime frontiers while preserving the distinction between mathematical certificates, software security policy, and fabricated hardware. The resulting execution chain is

native hardware evidence → execution passport → quorum epoch authority → storage-aware placement → signed

Native TPM2 and SEV-SNP verification. The Holotrade sibling repository now contains `js/w33-native-attestation.js`. For SEV-SNP it parses the 1184-byte attestation report, binds the 64-byte `REPORT_DATA` field to the W33 challenge and runtime public-key digest, enforces launch-measurement and reported-TCB policy, converts the firmware P-384 signature representation to DER, and verifies the report directly with SHA-384. It supports either an explicitly pinned VCEK key or an in-process ARK–ASK–VCEK certificate chain. For TPM2 it parses `TPMS_ATTEST` for a quote, binds `extraData` to the W33 challenge, verifies the AK signature, replays supplied event digests into PCR banks, and recomputes the quoted PCR digest in the selected-PCR order. Thus the preferred path no longer depends on the older normalized "external verifier said yes" envelope. A pinned AK/VCEK remains a deployment trust anchor; vendor provenance is stated separately from cryptographic signature validity.

Quorum-certified authority epochs. `analysis/w33_quorum_epoch_authority.py` replaces the single-signer authority transition with a 4-of-5 Ed25519 quorum certificate transported through the same neutral 36-state ST81/ST64 fabric. Honest members enforce a one-vote-per-predecessor rule. With $n = 5, t = 4$, any two quorums intersect in at least

$$2t - n = 3$$

members. Under the explicit assumption of at most one Byzantine authority, at least two members of that intersection are honest, so conflicting certified successors require violation of the honest one-vote rule. If conflicting valid certificates are nevertheless presented, the runtime emits content-addressed fork evidence naming the intersecting signer set. This is quorum certification, not a complete asynchronous BFT protocol and not an aggregated threshold-signature primitive.

Persistence enters placement. Holotrade's `js/w33-storage-aware-placement.js` now augments the ordinary ExecutionEngine placement score with forecast terms for live strong roots, retained reversible history, checkpoint retention, expected recovery storage, expected recovery compute time, energy-policy cost, and irreversible-erasure policy cost. The objective is exposed rather than collapsed into an opaque number:

$$C_{\text{total}} = C_{\text{base}} + C_{\text{strong root}} + \mathbb{E}[C_{\text{recovery}}] + C_{\text{energy}} + C_{\text{erase}}.$$

The strong-root term is measured in blob-seconds/byte-seconds before a market tariff is applied. No blob tariff or erasure tariff is identified with Landauer work; measured device energy remains a distinct quantity.

A restricted but exact $[[20, 7, 2]]_3$ no-go. The appropriate type-compatible parent for the external qutrit code is not the 40 W33 point set (whose points are two-qutrit Pauli classes), but the exact 240-edge qutrit CSS code with $H_X = d_1$ and $H_Z = d_2^T$. The executable certificate `analysis/w33_qutrit_20_7_2_edge_css_no_go.py` computes the W33 graph edge connectivity by Stoer–Wagner and obtains

$$\lambda(W(3,3)) = 12.$$

For any vertex potential $y \in \mathbb{F}_3^{40}$, a nonzero parent X-stabilizer $y^T d_1$ is supported precisely on edges joining unequal potential values. Hence every nonzero word in $\mathrm{row}(H_X)$ has weight at least 12; a one-vertex potential attains weight 12. By contrast, the frozen external H_0 span contains a nonzero weight-6 stabilizer. Coordinate permutation, injection, and nonzero $\mathbb{F}_3$ rescaling preserve support weight. Therefore

no literal CSS-preserving monomial zero-extension $20 \to 240$ intertwiner exists.

This is an UNSAT certificate for that adapter class, not a theorem excluding all embeddings. General symplectic Clifford maps that mix X/Z, introduce ancillas, or encode external coordinates nonlocally remain open.

Attested replay flight recorder. Holotrade's `js/w33-attested-replay-receipt.js` builds one Merkle-like content commitment over the execution passport, deployment digest, native hardware-attestation evidence, complete epoch-transition chain, wait-for root, cancellation root, deterministic wake-schedule root, temporal-GC root evolution, magic-token reservation/consumption events, and final artifact set. That flight-recorder root is embedded in the existing deterministic CBOR/COSE Ed25519 delivery receipt. Reordering, omitting, or substituting any bound history changes the signed payload. The receipt proves integrity and identity of the supplied evidence; it does not by itself prove that a fabricated sensor or external authority was truthful.

Scope. The five additions materially tighten the runtime trust chain, but they do not claim a fabricated SEV-SNP platform, a certified TPM deployment, secure physical media erasure, complete asynchronous Byzantine consensus, or a W33-specific fault-tolerant magic-state-distillation threshold. In particular the new weight-6 versus weight-12 obstruction closes only the literal CSS-preserving monomial embedding class; the broader symplectic/ancilla-assisted adapter search is now the correct remaining target.

75.1 Raw attestation, BFT authority, nonlocal qutrit embedding, measured placement, and portable audit closure

The execution stack now separates five previously open trust and implementation boundaries. First, the Holotrade verifier consumes the raw PC Client TPM event log: the initial legacy `TCG_PCClientPCREvent` carries the Spec-ID event, which declares the digest widths used by subsequent crypto-agile `TCG_PCR_EVENT2` records. Informational `EV_NO_ACTION` records are excluded from PCR extension, while the remaining digests are replayed and compared with the signed TPM quote. The raw TPM wire `TPMT_SIGNATURE` is also parsed directly for RSASSA, RSA-PSS, and ECDSA, so the quote hash/signature scheme is derived from the signed TPM object rather than supplied as a normalized verifier claim. AK/EK X.509 provenance is typed separately from quote validity and from an AK–EK credential-activation binding.

Second, capability epochs are no longer authorized by a static multisignature object alone. Five Ed25519 validators execute proposal, PREPARE-QC, and COMMIT-QC phases with quorum four. A four-vote timeout certificate rotates the leader; anti-equivocation votes, prepare locks, finalization state, and the highest commit certificate are durable across restart. The executable partition witness shows that a two-node side cannot finalize, the connected four-node side advances after a timeout, and the lagging replica reconciles from the final commit certificate. For $n = 5, t = 4$, two quorums intersect in at least

$$2t - n = 3,$$

which exceeds the assumed one-Byzantine budget. This is an executable BFT state-machine certificate, not a claim of a production asynchronous network stack.

Third, the qutrit fault-tolerance frontier changes qualitatively. The previous certificate remains valid:

$$\boxed{\text{no monomial/zero-extension 20-edge CSS embedding exists}},$$

because the external H_0 span contains weight six whereas every nonzero parent X-stabilizer in the W33 edge code has weight at least twelve. However that is a locality obstruction, not a general

symplectic obstruction. The new construction produces

$$A, B \in \mathbb{F}_3^{20\times 240}, \qquad AB^T = I_{20},$$

so

$$(x, z) \longmapsto (xA, zB)$$

is an injective symplectic Pauli embedding. The seven external H_1 rows map to independent logical-X classes of the exact $[[240, 81, 3]]_3$ parent and the two H_0 rows map into its X-stabilizer rowspace. Thus the broad nonlocal algebraic embedding class is **SAT**. Fault-tolerant scheduling nevertheless remains refused: the verified map has no low-weight/local optical compiler, mapped decoder, or mapped threshold/noise certificate.

Fourth, Holotrade placement now closes the prediction loop. Linux RAPL counter deltas and Kepler Prometheus energy counters can be ingested as physically measured energy, while strong-root storage ledgers provide realized blob-seconds and byte-seconds. Per-node calibration factors update from prediction error and feed back into the next storage/recovery/energy/erasure-aware placement ranking. CI fixtures exercise this controller but are explicitly labeled non-physical.

Finally, one portable audit verifier now accepts a bundle containing the signed delivery receipt and its constituent evidence. It independently re-verifies raw TPM (including the PC Client event log and, when supplied, the wire-format `TPMT_SIGNATURE`) or SEV-SNP evidence, verifies each four-of-five epoch certificate against trusted authority keys, recomputes the passport content identity, rebuilds the flight-recorder root from epoch/GC/magic histories and the final artifact set, and only then accepts the COSE/Ed25519 receipt. The portable acceptance predicate is therefore

$$\boxed{\text{hardware} \wedge \text{authority} \wedge \text{passport} \wedge \text{replay} \wedge \text{artifacts} \wedge \text{receipt signature}}.$$

These closures do not constitute a fabricated photonic processor, a measured fault-tolerance threshold, a locality-optimal symplectic embedding, or a formal proof of BFT liveness under every asynchronous schedule. Those remain separate physical and protocol frontiers.

75.2 Sparse symplectic realization, Clifford compilation, TPM activation, BFT stress, and host capture

The nonlocal $[[20, 7, 2]]_3 \to [[240, 81, 3]]_3$ symplectic witness has been refined without weakening its exact algebraic constraints. Writing H for the nine-row external triorthogonal matrix, each physical column of A lies in an affine solution space of $Ha_j = t_j$. A first deterministic $\mathbb{F}_3$ coordinate descent verifies that support can be reduced while retaining $\operatorname{rank} A = 20$. The stronger certificate then fixes one displayed invertible twenty-column minor of A and uses CP-SAT to minimize each of the remaining 220 columns exactly subject to $Ha_j = t_j \pmod 3$. With that minor frozen, the column problems separate, so their sum is the global minimum total A support in this fixed-minor affine class. For the optimized A, each row b_i of B independently solves

$$Ab_i^T = e_i,$$

and CP-SAT certifies each row's minimum Hamming support. Thus

$$AB^T = I_{20}$$

with globally minimum total B support for this optimized A. This does *not* claim a joint global optimum over every possible rank-preserving minor, nor does algebraic Hamming support alone establish physical locality or a fault-tolerance threshold.

The exact CP-SAT pair extends to an explicit 240×240 reversible linear qutrit Clifford. Choose C spanning $\ker B$ and set

$$F = \begin{bmatrix} A \\ C \end{bmatrix} \in GL(240, 3).$$

Then $FB^T = [I_{20}; 0]$, so the first twenty rows of F^{-T} equal B. Consequently $U_F|x\rangle = |xF\rangle$ realizes the desired Pauli embedding on the first twenty data qutrits. Column Gauss–Jordan synthesizes F exactly from ternary `SUM_ALPHA`, `SCALE2`, and `SWAP` Clifford generators. Non-conflicting gates are packed into the existing sixteen-slot, 72-tick Holonet packet body with a per-wire dependency frontier: every gate is placed strictly after the previous packet frame touching either of its wires, so disjoint Clifford macros parallelize without reversing circuit causality. Every occupied slot refines through

`LOAD_FLAG` $\rightarrow$ `FLIP_Q6_AXIS` $\rightarrow$ `LATCH_VERTEX`.

This closes the exact algebraic Clifford/compiler path while leaving optical pulse calibration, geometric routing/noise spread, decoder design, and mapped threshold separate.

The TPM trust path now contains an executed-protocol implementation rather than only certificate provenance. Holotrade invokes `tpm2_makecredential`, opens an endorsement-policy session, authorizes it with `tpm2_policysecret`, executes `tpm2_activatecredential`, and requires constant-time equality of the registrar secret recovered by the TPM. The transcript may be signed by an Ed25519 enrollment authority. Fixture tests replace only the command transport and are explicitly marked non-hardware; production execution uses the real TPM2 tools/TCTI. Thus AK/EK X.509 provenance, quote validity, and credential-activation residency evidence remain distinct evidence classes rather than being collapsed into one boolean.

The epoch-consensus safety layer now has two complementary mechanizations. A finite lock-aware TLA+ model contains five validators, quorum four, two competing values, one explicitly Byzantine validator, and bounded view changes. Its invariants include

$$\boxed{|\text{Committed}| \leq 1}$$

and persistence of the prepared lock. Focused CI downloads the pinned TLA+ 1.8.0 tool release and runs TLC on this model rather than merely checking that a `.tla` file exists. An executable adversarial fuzzer separately stresses the actual Python state machine with randomized conflicting proposal delivery, one Byzantine double-signer, durable crash/restart after honest votes and prepare locks, timeout/view-change certificates, and post-finalization conflicts. These artifacts strengthen finite safety evidence; they do not claim production network liveness under every asynchronous schedule.

Finally, physical host telemetry is now cryptographically bound to the portable receipt. RAPL and/or Kepler measurements plus strong-root realization are normalized into a content-addressed telemetry object before receipt signing. The signed receipt commits its telemetry digest, and the portable verifier rejects any later mutation. A Linux-host collector packages the signed receipt, raw TPM event log, raw quote and `TPMT_SIGNATURE`, AK key, passport, authority chain, GC/magic/concurrency histories, measured telemetry, and final artifacts, then invokes `w33-verify-receipt.js` as the acceptance oracle. A dedicated `[self-hosted, linux, w33-tpm]` workflow executes the real MakeCredential/ActivateCredential ceremony and capture path. Ordinary GitHub fixture runners are intentionally insufficient to assert that a physical host bundle has been produced.

The combined frontier is therefore

algebraic symplectic map $\rightarrow$ exact support-optimized representative $\rightarrow$ explicit qutrit Clifford $\rightarrow$ causality-preserv

Fault-tolerant admission remains gated on a physical locality/noise-propagation bound, a mapped syndrome decoder, and a mapped threshold certificate.

75.3 Multi-minor locality tournament, W33 routing, distance-two decoding, and hardware capture request

The $[[20,7,2]]_3 \to [[240,81,3]]_3$ symplectic adapter has been extended from a single fixed-minor support optimization to a finite, explicitly scored tournament of distinct rank-preserving minors. For every displayed candidate minor, its twenty columns are frozen so that $\operatorname{rank} A = 20$ is structural. Every remaining column is then solved by deterministic CP-SAT in two lexicographic stages,

$$\min |\operatorname{supp}(a_j)|, \qquad \min \sum_{r \in \operatorname{supp}(a_j)} d_{L(W33)}(e_r, e_{\operatorname{anchor}(r)}),$$

subject to $Ha_j = t_j$ over $\mathbf{F}_3$. For the resulting A, each row of B is optimized by the same exact support-first/locality-second rule subject to $Ab_i^T = e_i$. Candidate classes are compared by total $A+B$ support, anchor locality, maximum row radius, and W33 line-graph spanning-tree cost. The winner is therefore exact inside each displayed fixed-minor class and best among the finite candidate family; no claim is made that all $\binom{240}{20}$ possible rank minors have been exhausted.

The selected pair (A, B) is lowered all the way to an explicit topological nearest-neighbour circuit. The 240 physical carrier qutrits are the 240 edges of $W(3,3)$, and a primitive two-qutrit interaction is declared local only when the two carrier edges share a W33 point. Remote ternary `SUM_ALPHA` and `SWAP` macros are replaced by shortest-path swap networks in the 240-vertex edge line graph. Each replacement is replayed over $\mathbf{F}_3$ and required to equal the original linear Clifford action. Route supports that overlap are serialized, while disjoint supports remain parallel. The certificate reports topological depth, shortest-path lengths, physical-edge load, point-coupler load, and a content hash of the resulting local schedule. This is a topological locality theorem for the explicit W33 interaction graph, not yet a calibrated optical loss/crosstalk or fault-spread theorem.

The mapped CSS syndrome layer is now explicit as well. The external code uses rank-two X checks H_0 and rank-eleven Z checks $H^\perp$, hence $20 - 2 - 11 = 7$ logical qutrits. Under $(x, z) \mapsto (xA, zB)$ the mapped checks are H_0A and $H^\perp B$. Thirteen weighted-check ancillas are scheduled into 72-tick packet microframes with no data-edge or check-ancilla collision inside a round. The distance-two boundary is kept exact: all $20 \times 8 = 160$ nonidentity single-qutrit Pauli errors are required to produce nonzero syndrome, but an unknown-location syndrome is corrected only when unique. Ambiguous syndromes are detected and refused. If the damaged coordinate is known as an erasure, all nine Pauli possibilities at that coordinate are distinguished and the corresponding correction is emitted as the W33 Pauli frame

$$X : -aA_q, \qquad Z : -bB_q.$$

Thus the decoder closes exact detection and one-known-erasure recovery without misrepresenting a $d = 2$ code as an arbitrary single-error-correcting code.

A parameterized noise experiment is tied to the routed circuit while remaining separate from physical fault-tolerance admission. If E_i is the conservative routed-program exposure count of input qutrit i, the stated phenomenological model uses

$$p_i = 1 - (1 - p_{\text{gate}})^{E_i}$$

and distributes each nonidentity qutrit Pauli uniformly over its eight choices. All $\binom{20}{2}8^2 = 12160$ weight-two Pauli patterns are exhaustively classified as detected, stabilizer-trivial, or zero-syndrome

logical. Weight-zero, weight-one, and weight-two probability are evaluated exactly at each grid point; all weight-≥ 3 mass is retained adversarially rather than discarded. The reported interval is a conditional *block* logical-failure interval. No unsupported division by the seven encoded logical coordinates is used, and a grid point is called below bare p only if even the adversarial block upper bound is below p_{gate}. This is a conservative routed-exposure pseudothreshold experiment, not a calibrated photonic threshold.

The admission policy now distinguishes these evidence classes explicitly:

$$\begin{aligned}
\text{exact symplectic embedding} &: \text{implemented},\\
\text{W33 topological route compiler} &: \text{implemented},\\
\text{mapped packet decoder} &: \text{implemented},\\
\text{routed-exposure block pseudothreshold} &: \text{implemented},\\
\text{calibrated optical locality/noise propagation} &: \text{open},\\
\text{physical mapped threshold certificate} &: \text{open},\\
\text{canonical } [[66,8,3]]_3 \text{ substrate witness} &: \text{open}.
\end{aligned}$$

Consequently fault-tolerant magic-resource admission remains fail closed.

Finally, the Holotrade hardware lane was changed from a manual-only workflow to an explicit execution-request mechanism. A request committed on master targets `[self-hosted, linux, w33-tpm]`, requires a real TPM2 device and measured boot log, runs `tpm2_makecredential/tpm2_activatecreden` requires the enrollment result to state `hardwareBacked=true`, captures configured RAPL and/or Kepler evidence into the signed host bundle, and then requires the portable verifier to pass before uploading an audit artifact. At the time of this insert the hardware request had been issued but the self-hosted job was still queued. A queued request is not evidence that a physical bundle exists; only a completed hardware job plus its verifier-approved artifact can close that claim.

The focused hosted-software closure was likewise queued at publication time. Accordingly the repository contains the executable certificates and their fail-closed acceptance logic, while hosted-run numerical metrics remain subject to the corresponding workflow result rather than being asserted in advance.

76 Optical primitive, circuit-noise, logical-quotient, and protected-store closure

The current qutrit fault-tolerance frontier now separates compiler evidence from measured-device evidence all the way down the stack. The selected exact $[[20,7,2]]_3$ symplectic embedding is still routed on the 240 W33-edge line graph, but every shared-point local primitive has now been lowered one further level to a coherent qutrit optical candidate circuit. For SUM_α, the control is coherently sorted into three mode branches, the target receives the conditional cyclic shift $X^{\alpha j}$ on branch j, and the control branches are recombined. A local SWAP is replayed exactly over $\mathbf{F}_3$ as three SUMs plus the $j \mapsto -j$ mode permutation. The finite basis-state truth tables close; measured insertion loss, crosstalk, leakage and phase RMS do not. Those quantities may enter only through a hardware-backed calibration packet, so the optical compiler gate and the hardware-calibration gate are distinct.

The mapped 13-check extraction circuit is now attacked directly rather than through an external-coordinate exposure proxy alone. Every additive nonzero syndrome-trit corruption at every check outcome is injected into the clean state and all 160 nontrivial single-qutrit external Pauli syndromes. The current unique/ambiguous/refuse decoder policy is replayed exactly. Heralded loss is fail-closed, unheralded leakage and arbitrary ambient 240-edge data faults are kept conservative,

and the exact independent-location probability of two or more faults is retained as an adversarial envelope. This is a circuit-level fault census, not a calibrated photonic threshold.

A separate quotient certificate now constructs seven dual logical pairs $X_{L,i}, Z_{L,i}$ satisfying

$$X_L Z_L^{\mathsf{T}} = I_7 \pmod 3.$$

Consequently a zero-syndrome error is no longer reduced to a single block-level "logical/nonlogical" bit. Every enumerated weight-two Pauli ($\binom{20}{2}8^2 = 12160$ cases) and, in the exhaustive lane, every weight-three Pauli ($\binom{20}{3}8^3 = 583680$ cases) is assigned either to the stabilizer class or to one exact 14-trit logical Pauli coordinate. No division of a block failure probability by seven is used.

76.1 The 66-qutrit store and the K12 correction

Pass 79 already supplied an explicit finite $[[66, 8, 3]]_3$ stabilizer witness: eight cyclic $[[5, 1, 3]]_3$ blocks plus 26 frozen single-site Z ancillas. The new bridge derives a symplectic logical pair for the five-qutrit block and maps the seven logical qutrits of the $[[20, 7, 2]]_3$ source into seven independent logical blocks of this distance-three store. This is a logical decode/code-switch/re-encode bridge, not a monomial embedding of twenty physical qutrits into sixty-six. After a successful recode the stored state has distance three; source-side operations before that recode remain distance two.

The same calculation exposes an important correction to older architecture prose. The committed orientable K_{12} completion has

$$V = 12, \qquad E = 66, \qquad F = 44, \qquad g = 6.$$

Building its actual boundary matrices over $\mathbf{F}_3$ gives

$$\operatorname{rank} \partial_1 = 11, \qquad \operatorname{rank} \partial_2 = 43,$$

and therefore the standard closed orientable edge surface code has

$$k = 66 - 11 - 43 = 12 = 2g,$$

not 8. Thus the phrases "the 66-edge K_{12} compiler surface" and "the explicit $[[66, 8, 3]]_3$ protected store" must not be identified with the standard homological K_{12} surface code. A K_{12}-native $k = 8$ claim would need four additional independent commuting stabilizer/gauge-fixing constraints specified explicitly.

76.2 Physical admission boundary

The executable evidence now closes: external code reconstruction, symplectic embedding, W33 topological routing, optical candidate compilation, mapped syndrome/decoder, circuit-level single-fault census, exact seven-logical quotient resolution, and a logical bridge into an explicit distance-three 66-qutrit store. Fault-tolerant magic admission nevertheless remains fail-closed because (1) the optical primitive has no hardware-backed calibration packet, (2) no hardware-calibrated physical threshold certificate exists, and (3) the distance-three storage bridge does not yet have a fault-tolerant physical code-switch certificate.

On the deployment side, Holotrade now admits a real host bundle only after the portable host verifier returns `PORTABLE_W33_HOST_AUDIT_PASS`. The verified bundle is then content-addressed and its digest is signed into a *new* second-stage settlement receipt, avoiding a circular receipt–bundle–same-receipt dependency. A fresh self-hosted `[self-hosted,linux,w33-tpm]` capture request was issued separately; that request is not physical evidence by itself and becomes a hardware result only if the TPM/measured-boot/energy workflow actually executes and passes.

76.3 A two-punctured Hesse plane is the exact 11-bin gate–route alphabet

The gauge-fixed CZ/context–Hashimoto weld admits a sharper projective description. For odd prime q, its common moving alphabet is

$$\mathbb{F}_q^2 \sqcup \mathbb{F}_q^* \cong PG(2,q) \setminus \{[1{:}0{:}0],[0{:}1{:}0]\}.$$

The q^2 transverse CZ-context orbits are the affine points $[a{:}c{:}1]$, while the $q-1$ moving intersecting orbits are the surviving infinity points $[1{:}s{:}0]$, $s \neq 0$. The two deleted infinity directions are exactly the two fixed intersection directions of CZ. Hence the alphabet has $q^2+q-1 = k-1$ points, equal to the Hashimoto outdegree. Its retained lines comprise one of size $q-1$, $2q$ of size q, and $q(q-1)$ of size $q+1$.

At $q=3$ this exactly explains the existing frequency plan: $11 = 9+2$. Bins $H_0,\dots,H_8$ already carry $(\texttt{route_trit},\texttt{phase_trit}) \in \mathbb{F}_3^2$, so they are the nine affine Hesse points; the two Hashimoto sidebands are the two surviving points at infinity. Their gauge/chiral ordering is only an ABI gauge choice.

The setwise $PGL(3,3)$ stabiliser of the deleted pair is

$$\mathbb{F}_3^2 \rtimes D_8, \qquad |\mathbb{F}_3^2 \rtimes D_8| = 9 \cdot 8 = 72.$$

With $R = \left(\begin{smallmatrix} 0 & -1 \\ 1 & 0 \end{smallmatrix}\right)$ and $S = \left(\begin{smallmatrix} 1 & 0 \\ 0 & -1 \end{smallmatrix}\right)$, $R^4 = S^2 = 1$ and $SRS = R^{-1}$. The existing packet frame therefore admits the exact overlay

$$72 = 9 \text{ Hesse bins} \times 2 \text{ Hashimoto sectors} \times 4 \text{ probe slots}, \qquad (h,b,r) \mapsto (t_h, S^b R^r).$$

The faithful action on the eleven retained points has exactly two orbits, of sizes 9 and 2. Thus the compiler's $9+2$ split is an orbit decomposition, not merely a numerical match.

Evidence boundary. The finite projective geometry, the 72-element stabiliser and the slot bijection are exact. The sideband ordering is conventional, and the group overlay is a control semantics rather than a claim that present optical hardware dynamically implements $PGL(3,3)$. Executable witness: `analysis/w33_punctured_hesse_packet_group.py`; frozen certificate: `data/w33_punctured_hesse_pa`

77 Passes 4137–4144: matrix Wilson pumping, extended horizons, microscopic scale flow, and autonomous history dynamics

The exact certificate for this packet is `d16f8ab7ce51f2953cfd4866e7a716e31a271b3337a05b6105b367736bcecb6c`
All statements in this section concern finite group, Gaussian, Markov, clock, transfer-matrix, circuit, or band-topology models.

Matrix-valued gauge-singlet holonomy. The color space $(\mathbf{3} \otimes \bar{\mathbf{3}})^{\otimes 3}$ contains six independent contraction singlets, with Gram spectrum

$$\left\{\frac{2}{9}, \left(\frac{8}{9}\right)^4, \frac{20}{9}\right\}.$$

Three orthonormal singlet channels support a tripod Hamiltonian whose rank-two dark bundle has two exact Wilson loops

$$U_y = \begin{pmatrix} -\frac{1}{2} & -\frac{\sqrt{3}}{2} \\ \frac{\sqrt{3}}{2} & -\frac{1}{2} \end{pmatrix}, \qquad U_z = \mathrm{diag}(e^{-2\pi i/3}, e^{2\pi i/3}).$$

Their group commutator has trace $-1/4$, so the adiabatic Wilson response is genuinely matrix-valued rather than a center phase.

Extended active horizon lattice. Nine localized squeezing cells act on one outgoing, nine partner, and nine environment modes. The resulting 38×38 Nambu map has paraunitary residual 1.11×10^{-15}. At $\omega = 0.3$ the outgoing occupation is 0.01195894, the greybody ratio is 0.48573560, and the outgoing/partner logarithmic negativity is 0.20853530. The partner profile is centered at cell 4.0048 with RMS width 1.1977 cells. The inside-flow lattice dispersion has two ultraviolet roots with opposite group velocities, giving explicit mode conversion without promoting the finite analogue model to gravitational Hawking radiation.

Microscopic channel-balance flow. Four independent local Markov channels sum to

$$ds = \gamma(\ln 80 - 4s)dt + \sqrt{2D}\, dW.$$

The stationary law is Gaussian around $s_* = \ln 80/4$, the Fokker–Planck gap is 4γ, and the deterministic spectral dimension is exactly

$$d_s = \frac{\ln 80}{s_*} = 4.$$

For $D = 0.01$ and $\gamma = 1$, the mean noisy value is 4.00838502 and relative entropy to stationarity decreases monotonically.

Autonomous history-state scar gadget. Three repetitions of the eight adjacent-SWAP branch compiler define a 24-gate program. The static engineered history Hamiltonian

$$H = \Omega \sum_{t=0}^{23} \sqrt{(t+1)(24-t)}\, (|t+1\rangle\langle t| \otimes U_{t+1} + \text{h.c.})$$

has a 25-state clock, an equally spaced spectrum from -24Ω to 24Ω, perfect endpoint transfer at $\pi/(2\Omega)$, and full history revival at π/Ω. The endpoint data operation is $U_{\text{shift}}^3 = I$.

Curvature scaling. For N independent dark-reservoir cells, $Z_N = Z_1^N$, $g_N = N g_1$, and the scalar curvature satisfies

$$R_N = \frac{R_1}{N}.$$

The sign change remains at $\beta U = 14.5791667571$, but its magnitude vanishes in the thermodynamic limit. A positive 2×2 transfer matrix for a weakly coupled one-dimensional dark/bright hierarchy is analytic for finite coupling and has correlation length 0.14340675 cells in the frozen demonstration, excluding a finite-temperature singularity in this class.

Outside-box probes. Ordering $U_y U_z$ versus $U_z U_y$ yields output fidelity $7/16$, furnishing a geometric phase-order transistor. Levi edge connectivity four and the $2 \ln 3$ entropy-change bound per two-qutrit cut gate imply a throughput ceiling of $8 \ln 3$ nats per layer and at least 74 layers for 80 maximally mixed dark cells. Finally, a spin-one Qi–Wu–Zhang control Hamiltonian on three singlet channels has band Chern numbers $(-2, 0, 2)$ and realizes a charge-two synthetic control-space monopole.

Boundary. No continuum QCD, fabricated non-Abelian pump, observed Hawking radiation, derivation of physical spacetime, thermodynamic phase transition, non-Abelian anyon, physical monopole, gravity, cosmology, or theory of everything follows from these finite exact results.

77.1 The 200-cover orbital dictionary and Gram reconstruction

The 200 nine-tritangent covers split canonically as 40 point-covers and 160 flag-covers. Exact cover overlap is constant on the 19 point/flag orbitals. The point fiber has overlap values 9, 3, 1 on identity, collinear, and noncollinear pairs, while the eight flag relative positions have overlaps 9, 3, 0, 0, 0, 3, 4, 1. The full integer cover Gram reconstructs the two fibers, W33 collinearity, the 40 maximal four-point lines, and every incident point-line flag. Its cross-fiber level 6 is the previously certified 480-incidence cover graph. After integer centering, the 40 point-covers and 160 flag-covers are separately tight frames for the same tritangent degree-24 constituent, with frame operators 300 P24 and 1200 P24 respectively. These are finite incidence statements only.

Passes 5056–5057: $q = 4$ theta code and the local cut-space law

A direct construction of $W(3,4)$ gives 85 points, 85 lines, 425 flags and 13,600 apartments. The binary apartment cycles have rank $256 = 4^4$. The point- and line-side theta construction gives 54,400 weight-three relations of rank $13{,}344 = 13{,}600 - 256$, so at $q = 4$ the theta relations generate the full dual. The exact minimum support is 256, hence

$$\boxed{C_4 = [13600, 256, 256]_2}.$$

Together with Pass 5051, the family is therefore exact at $q = 2, 3, 4$.

For arbitrary q, fix an opposite same-type pair. Its $q+1$ geodesics form the vertices of K_{q+1}; apartments are edges and theta relations are triangles. If x_{ij} satisfies every triangle relation, then

$$x_{ij} = x_{0i} + x_{0j} = a_i + a_j.$$

Thus the local theta kernel is exactly the cut space of K_{q+1}, has dimension q, and every nonzero local word has weight $s(q+1-s) \geq q$.

Every apartment belongs to four opposite-pair charts, so

$$4\,\mathrm{wt}(x) = \sum_O \mathrm{wt}(x|_O) \geq qA(x).$$

Consequently the still-open family distance theorem reduces to one statement:

$$\boxed{A(x) \geq 4q^3 \Longrightarrow d = q^4}.$$

At $q = 4$ the chamber-star witness has $A = 128_{\text{point}} + 128_{\text{line}} = 256 = 4q^3$ and saturates the bound. Arbitrary-q full-dual generation and the active-chart inequality remain open; no stronger claim is promoted here.

Passes 5058–5065: minimum-shell rigidity, Jacobian bicycle, and orientation channels

The $q = 3$ apartment code $[1620, 81, 81]_2$ now has a complete minimum-shell classification. After excluding the 160 chamber-star words, the exact weight-81 theta-check feasibility problem is inconsistent. Hence those chamber stars are all minimum words. Their pairwise intersections are

$27, 9, 3, 1$ at gallery distances $1, 2, 3, 4$, so the code reconstructs the 160-chamber graph, its 80 maximal K_4 panels, and hence a $40 + 40$ bipartite 4-regular girth-8 panel graph isomorphic to the original W33 Levi graph.

The first two-adic lift layer of the subdivided-Levi Jacobian is the bicycle module

$$\mathcal{B}_{29} = \operatorname{im} B^{\mathsf{T}} \cap \ker B.$$

Its point half has profile $1 \mid 14$, while its line half has profile $1 \mid 8 \mid 6$. Thus $\mathcal{B}_{29}$ has a natural codimension-six 23-space with factors $14, 1, 8$. This does not identify it with the older apartment radical R_{29}: the exact equivariant Hom-space has dimension one and its unique nonzero map $R_{29} \to \mathcal{B}_{29}$ has rank 15, with a 14-dimensional kernel. The equality $29 = 29$ is therefore replaced by an explicit partial bridge and obstruction.

Apartment orientation also sharpens the multiplicity-five Steinberg statement. If H is the order-16 setwise stabilizer of an apartment, an oriented apartment cycle affords a nontrivial sign character ε of H: eight elements preserve orientation and eight reverse it. Both St^H and $\mathrm{St}^{H,\varepsilon}$ have dimension five. An integral basis of the twisted space has supports $8, 16, 8, 40, 40$; the standard signed apartment is one distinguished support-eight channel, not a unique Steinberg copy in the unsigned apartment carrier.

The point-local V_{24} compiler also has a quantified arithmetic tradeoff. Among 2672 rank-preserving one-row substitutions of the frozen 24-apartment basis, replacing row 7 by row 53 lowers the exact inverse denominator from 9360 to 3120, while increasing the numerical condition number from about 186.704 to 302.504. The full 162-row point-star lattice has largest nonzero Smith invariant 780. Unrestricted Smith combinations are not promoted as physical channels because their coefficient growth is uncontrolled.

Two outside-box incidence tests remain sharply finite. At $q = 4$ the 13600 apartment vectors contain 54400 theta projective lines, twelve through each vector, but no complete contained binary projective plane. The apartment/theta Tanner graphs have no four-cycles; their girths for $q = 2, 3, 4$ are $8, 6, 6$, with respectively $0, 4320, 108800$ six-cycles.

Finally, the minimum-shell reconstruction is rigid enough to determine the coordinate-permutation symmetry. Each of the 1620 apartment coordinates has a unique signature of eight minimum chamber-star words. Hence a code coordinate automorphism acts faithfully on the reconstructed building, while every building automorphism preserves the code. Using $\operatorname{Aut} W(3,3) = \mathrm{PGSp}(4,3)$ at $q = 3$, the apartment code has coordinate-permutation automorphism group exactly $\mathrm{PGSp}(4,3)$ of order 51840. This is a finite code-automorphism statement, not an identification of arbitrary linear automorphisms of the message space.

Passes 5066–5073: apartment presentation, Jacobian heights, twisted Hecke channels, and arithmetic Pareto structure

For the incidence graph Γ of any finite generalized quadrangle, let $\mathcal{A}$ be its 8-cycle apartments and let Θ be the binary span of the local three-apartment theta relations. A base-vertex fan decomposition proves the exact presentation

$$\mathbb{F}_2^{\mathcal{A}}/\Theta \;\cong\; Z_1(\Gamma; \mathbb{F}_2).$$

Indeed, after choosing a geodesic from a base vertex to every graph vertex, each edge closes to either zero or one apartment because the graph has girth eight; summing these fan apartments around a cycle cancels the chosen geodesics. The only geodesic choices occur at opposite vertices, and changing such a choice changes the fan by a local theta relation. For $W(3,q)$ this gives apartment-code dimension q^4 and proves that theta triples generate the complete dual for every prime power q.

The all-q minimum-distance assertion $d = q^4$ remains open; it is exact at $q = 2, 3, 4$. A strengthened $q = 4$ shell search, including a 256-generator gauge-fixed MILP, reached its bounded solver horizon without an incumbent and therefore supplies no SAT/UNSAT verdict.

For the fully subdivided $W(3, 3)$ Levi graph, the characteristic-two height filtration of the critical group is now identified as actual subspaces, not only dimensions:

$$H_1^{(81)} \supset \mathcal{B}_{29} = \mathcal{B}_{29} \supset W_{23} \supset J = J \supset 0,$$

with dimensions $81, 29, 29, 23, 1, 1, 0$. Here $\mathcal{B}_{29} = \operatorname{im} C^{\mathsf{T}} \cap \ker C$ is the binary bicycle space, $W_{23} = P_{15} + L_9$, and all 23 basis vectors of W_{23} lift through modulus eight. The one-dimensional terminal layer is the unique fixed binary line J.

The five orientation-twisted Steinberg channels also split canonically. The outer involution gives a $2 + 3$ decomposition. Two commuting twisted-Hecke operators have characteristic polynomials

$$(x - 8)^2(x + 6)(x^2 - 2x - 16), \qquad (x - 4)(x + 4)(x + 3)(x^2 - x - 4),$$

and joint eigenchannels

$$(8, 4),\ (8, -4),\ (-6, -3),\ (1 + \sqrt{17}, (1 + \sqrt{17})/2),\ (1 - \sqrt{17}, (1 - \sqrt{17})/2).$$

On the quadratic channel the second operator is represented over $\mathbb{Q}$ by $A = \left(\begin{smallmatrix} 1 & 4 \\ 1 & 0 \end{smallmatrix}\right)$. The corrected historical transfer block $B_2 = \left(\begin{smallmatrix} 4 & 2 \\ 2 & 5 \end{smallmatrix}\right)$ satisfies $A \sim B_2 - 4I$, and $4A + 10I$ has characteristic polynomial $x^2 - 24x + 76$, the corrected B_3 transfer polynomial. This is an exact rational operator-polynomial bridge; no geometric intertwiner between the two constructions is claimed yet.

For the point-local cubic-surface V_{24} compiler, 24 literal apartments attain the full point-star Smith floor: an exact inverse denominator of 780. Thus there is no raw-subset denominator gap. The floor basis is, however, extremely ill-conditioned ($\kappa_2 \approx 7.24 \times 10^4$). A separate three-substitution raw basis has denominator 3120 and $\kappa_2 \approx 105.46$, improving both denominator and conditioning over the original 9360, $\kappa_2 \approx 186.70$ basis. Arithmetic exactness and numerical conditioning are therefore distinct optimization objectives.

Three finite probes sharpen the surrounding structure. The apartment stabilizer normalizer tower has orders $16 < 32 < 64$ in $PSp < PGSp$, with full quotient $N_{PGSp}(H)/H \cong V_4$ and exactly two H-fixed apartments, exchanged by the inner normalizer. An independent $q = 5$ build gives 73125 apartments and 390000 theta checks; its Tanner graph has exactly $1170000 = 390000(5 - 2)$ six-cycles, extending the local law to the fourth anchor $q = 2, 3, 4, 5$. A symbolic no-cross-chart lemma remains before that six-cycle formula is promoted for arbitrary q.

Passes 5074–5081: gauge-test distance reduction, sharbly dictionary, local decoder, and three outside-box closures

Pass 5066 identifies apartments modulo theta relations with the binary Levi cycle space. Dualizing sharpens the still-open family distance problem: a codeword is the evaluation of an edge 1-cochain modulo cuts on apartment boundaries. On an opposite-pair chart its values form a cut of K_{q+1}, and therefore

$$4 \operatorname{wt}(c_y) = \sum_O \operatorname{wt}(c_y|_O) \geq q\, A(y).$$

Thus $d = q^4$ would follow from the single local-test inequality $A(y) \geq 4q^3$ for every non-cut cochain. A chamber/edge cochain saturates the target for $q = 2, 3, 4, 5$: it has weight q^4, exactly $4q^3$ active charts, and every active chart is a minimum cut of weight q. At this pass the universal inequality remained open; Pass 5083 below closes it sharply at $q = 3$ while leaving the all-q theorem open.

The recent symplectic-sharbly presentation has an exact rank-two overlap with this finite picture. Its V_0 terms are symplectic-basis apartment generators, and a $V_{1,1}$ genus-one sharbly boundary reduces mod 2 to the three apartments through a fixed opposite point pair: the point-theta relation. At this pass the $V_{1,2}$ genus-two split differential was firewalled as only structurally dual; Pass 5085 below completes the standard rank-two $V_{1,2}$ identification with line-theta, while Pass 5066 remains the independent finite-GQ presentation proof.

The $q = 4$ shell search is sharpened exactly. Among all sums of at most three distinct chamber-star generators, only a single star has weight 256; every pair and every triple has weight at least 384. Hence at this stage any hypothetical non-star minimum word required at least four stars. Pass 5084 below exhausts the four-star orbit shell, pushes every exotic minimum beyond four literal generators, and identifies the complete weight-five panel shell of the chamber-generator kernel. At $q = 5$, all pairs of the 936 chamber stars have weight at least 1000 and a bounded multi-star descent never beats the chamber-star weight 625. The q=5 statement remains a falsifier, not a minimum-distance proof.

Locally, the cut-space theorem is now an explicit decoder. A complete syndrome has rank $q(q-1)/2$. In the physical $q = 3$ case the chart has six raw bits, three potential bits, three syndrome bits, and only eight syndromes, so exact nearest-cut correction is an eight-entry ROM. The corresponding exact ROM sizes for $q = 2, 4, 5$ are $2, 64, 1024$.

Three outside-box continuations also close. First, the apartment/theta Tanner graph has for every q exactly

$$N_6 = q^3(q+1)^2(q^2+1)\binom{q}{3} = T(q)(q-2)$$

six-cycles: a genuine Tanner six-cycle is precisely three apartments through one common length-four root. Second, with μ uniform on apartment boundaries,

$$\mathrm{wt}(c_y) = \frac{N_A}{2}\big(1 - \widehat{\mu}(y)\big),$$

so the family distance theorem is equivalently the sharp nontrivial Fourier bound

$$\widehat{\mu}(y) \le 1 - \frac{16}{(q+1)^2(q^2+1)}.$$

The complete $q = 2$ enumerator has exactly 45 minimum words, all chamber stars. Third, the dual minimum shell is intrinsic: every weight-three dual word is exactly a local theta triple. Hence $d(C^\perp) = 3$ and

$$A_3(C^\perp) = q^3(q+1)(q^2+1)\binom{q+1}{3}.$$

These are finite code/building statements. No physical threshold or continuum dynamics is inferred.

Passes 5082–5089: sharp $q = 3$ expansion, panel dependencies, intrinsic decoding, and the integral theta presentation

The apartment-boundary Fourier identity

$$\mathrm{wt}(c_y) = \frac{N_{\mathcal{A}}}{2}(1 - \widehat{\mu}(y))$$

is now exact at the first three nontrivial anchors: the maximum nonconstant coefficients are $29/45$, $9/10$, and $409/425$ for $q = 2, 3, 4$. The equality shell is completely the chamber stars at $q = 2, 3$; it

remains unclassified at $q = 4$. In the local coarea coordinates an exact $q = 3$ mixed-integer model closes the sharper statement

$$A(y) \geq 108 = 4 \cdot 3^3$$

for every nonzero apartment-code word. Since every active K_4 chart has cut weight at least three, $\mathrm{wt}(c_y) \geq 3A(y)/4 \geq 81$. A chamber star attains equality. This is the sharp tester theorem at $q = 3$, not yet an all-q proof.

At $q = 4$, an orbit-complete four-star census fixes one chamber and tests all $\binom{424}{3} = 12614424$ representatives. The only weight-256 outputs are other chamber stars. Their induced five-star zero relations are exactly the two panel relations through the fixed chamber. Transitivity gives the complete minimum shell of the 425-generator dependency code:

$$\boxed{K_{\mathrm{chamber}} = [425, 169, 5]_2, \qquad A_5 = 170 = 85 + 85,}$$

where the 170 minimum dependencies are the point and line panels. Thus a hypothetical exotic weight-256 q=4 word requires at least five distinct chamber-star generators in every literal representation. Independently, Passes 5090 and 5096 force such an exotic word into the heavy 2|3 chart sector.

The remaining rank-two sharbly dictionary is also explicit. For a symplectic basis e_1, f_1, e_2, f_2 and $a \neq 0$, the standard $V_{1,2}$ split terms

$$\{e_1, f_1, e_2, f_2\}, \quad \{e_2 + ae_1, f_2, e_1, f_1 - af_2\}, \quad \{f_1, e_2 + ae_1, e_2, f_1 - af_2\}$$

are three apartments through the same opposite lines $\langle e_1, e_2\rangle$ and $\langle f_1, f_2\rangle$. Exact checks at $q = 3$ and $q = 5$ put them on one line-side theta triangle for every nonzero a. With ordered geodesic roots R_i and $A_{ij} = R_i - R_j$, the relation is already integral,

$$A_{01} + A_{12} - A_{02} = 0,$$

and reduces to binary theta parity. Together with the previous $V_{1,1}$ point-theta identification, the two first relation types in the rank-two specialization of Pal's symplectic sharbly presentation match the point/line theta families.

The local eight-entry $q = 3$ correction ROM now has a global finite-code guarantee. Every apartment belongs to four charts and no apartment pair belongs to more than one. The vote decoder exhaustively corrects all 1620 single errors and all 1311390 double errors in one sweep. Among the 21600 triples contained in one chart, 17280 clear in one sweep; the remaining 4320 are the local weight-three K_4 cut words, leave residual weight two, and clear on the second sweep. This is hard-decision code arithmetic, not an optical threshold.

Three outside-box closures sharpen the architecture. First, if A_Θ is the degree-16 theta point graph on q=3 apartments and V is the apartment lift of the 15-dimensional line-side Levi kernel, then exact integer arithmetic gives

$$(A_\Theta^2 - 2A_\Theta - 16I)V = 0, \qquad \mathrm{rank}[V, A_\Theta V] = 30.$$

Thus this invariant space has characteristic polynomial $(x^2 - 2x - 16)^{15}$ and exact channels $1 \pm \sqrt{17}$. Writing $\lambda = (1 + \sqrt{17})/2$, the theta generator 2λ realizes the conductor-two order $\mathbb{Z} + 2\mathcal{O}_{\mathbb{Q}(\sqrt{17})}$ of discriminant 68, sitting between the conductor-one and conductor-four orders of Pass5091.

Second, the code synthesizes its own decoder charts. Pass5081 makes the 4320 theta triples the intrinsic minimum dual shell. Their 21-regular intersection graph has 114480 K_4 cliques; selecting those whose four triples have six-coordinate union with every coordinate occurring twice leaves

exactly 1080 objects, exactly the opposite-pair charts. Hence the local ROM placement can be reconstructed without external W33 labels.

Third, the apartment presentation lifts from $\mathbb{F}_2$ to $\mathbb{Z}$. For any finite generalized quadrangle incidence graph Γ,

$$\boxed{\mathbb{Z}[\text{oriented apartments}]/\Theta_{\mathbb{Z}} \cong Z_1(\Gamma;\mathbb{Z}).}$$

The same base-vertex fan decomposition works integrally: each reduced fan has length at most eight and is therefore zero or one oriented apartment, while geodesic-choice changes are oriented theta relations. The quotient is consequently torsion-free; for $W(3,q)$ its rank is q^4. At $q=2$ the signed theta matrix has Smith form 1^{74} and quotient $\mathbb{Z}^{16}$.

Passes 5090–5097: derivative root sheets, $q=4$ defect rigidity, and the integral $\sqrt{17}$ order

A collision-reconciliation against the concurrently executed Passes 5074–5081 leaves six genuinely new finite results plus two synthesis theorems. At $q=4$, if every active opposite-pair chart is a minimum $1|4$ cut, fixing one selected apartment gives sixteen local seeds; exact propagation leaves eight solutions and eight contradictions, and the eight solutions are precisely the eight chamber stars through that apartment. Hence any non-chamber weight-256 word must contain a heavier $2|3$ chart.

The old factor-17 bridge is stronger than rational similarity. With

$$A=\begin{pmatrix}1&4\\1&0\end{pmatrix},\quad B_2=\begin{pmatrix}4&2\\2&5\end{pmatrix},\quad P=\begin{pmatrix}2&-1\\-1&1\end{pmatrix},$$

one has $\det P=1$ and $AP=P(B_2-4I)$. Thus the common integral lattice is the maximal order $\mathbb{Z}[(1+\sqrt{17})/2]$. The $q=3$ recurrence generator $\mu=10+4\lambda$ spans the conductor-four order $\mathbb{Z}+4\mathcal{O}_K$, whose discriminant is $272=16\cdot 17$. This is an arithmetic order/lattice theorem, not a new projective-group intertwiner.

The raw point-local V_{24} compiler that reaches the Smith denominator floor 780 is an exhaustive strict one-swap local optimum for conditioning among denominator-780 raw bases: among 3289 nonsingular one-apartment swaps, only eight remain at denominator 780, and all seven alternatives are worse than the frozen basis. A sampled two-swap search gives additional Pareto evidence but no global optimum theorem.

The formal derivative noticed in the apartment distance reduction has an exact discrete meaning. A chamber lies on q^4 apartments. Their active opposite-pair charts split into four incidence roles—point endpoint, point interior, line endpoint and line interior—and each role contains exactly q^3 charts. Hence

$$q^3+q^3+q^3+q^3=4q^3=\frac{d}{dq}q^4.$$

This is a finite coarea/codimension-one derivative, not infinitesimal calculus in the prime-power parameter q. At $q=3$ a normal unipotent subgroup of order 81 acts regularly on the 81 chamber-star apartments and its local switches split into four root directions.

Those directions are not Cartesian. At $q=3$ the six pair-generated subgroup orders are $9,9,9,9,27,81$; at $q=2$ they are $4,4,4,4,4,8$. Correspondingly the chamber-star switch graph has q^4 vertices and degree $4(q-1)$, but is spectrally non-isomorphic to $H(4,q)$ for $q=2,3,4$. The derivative carrier is therefore root-curved rather than a four-coordinate Hamming cube.

For a weight-256 q=4 word let A_1 and A_2 count $1|4$ and $2|3$ charts. Writing $A_2=2t$, exact coarea gives

$$A_1=256-3t,\qquad A_{\text{active}}=256-t,$$

and the supported local Tanner-triangle count is $1024 - 8t$. Pass5090 forces $t \geq 1$ for every exotic minimum word, so the unresolved shell is naturally graded by a discrete curvature defect.

Finally, the coarea and Fourier distance attacks are exactly the same functional in two coordinate systems. If μ is uniform on apartment boundaries and $N_A = q^4(q+1)^2(q^2+1)/8$, then

$$\widehat{\mu}(y) = 1 - \frac{1}{2N_A} \sum_{O} s_O(q + 1 - s_O).$$

Thus minimizing local chart energy and maximizing nontrivial Fourier bias are equivalent formulations of the remaining all-q distance theorem.

Passes 5098–5101: exact root-coset incidence behind the formal derivative

The four-sheet derivative count of Passes 5090–5097 admits a stronger incidence interpretation. For $q = 2$ and $q = 3$, the hypergraph whose vertices are the q^4 apartments through a fixed chamber and whose hyperedges are the $4q^3$ active chamber-star charts is explicitly isomorphic to the hypergraph of the maximal unipotent group U of type C_2 and the right cosets of its four positive-root subgroups. Thus the correspondence matches the q-element sheets themselves, not only their number.

At $q = 3$ the derivative point graph has full automorphism group

$$\mathrm{Aut}(\Gamma_\partial) \cong U_{81} \rtimes V_4, \qquad |\mathrm{Aut}(\Gamma_\partial)| = 324.$$

The left-regular U_{81} is normal, the identity stabilizer has order census $1^1 2^3$, and its V_4 fixes each of the four positive-root parallel classes setwise. Since $324 = |PGSp(4,3)|/160$, this is exactly the full projective chamber stabilizer rather than an accidental graph-symmetry enlargement.

More generally, a split finite Chevalley group with N positive roots has maximal-unipotent size q^N and Nq^{N-1} positive-root subgroup cosets, the formal derivative of q^N. In type C_2, the only nonzero brackets among a standard set of four positive-root nilpotents are

$$[X_0, X_1] = X_2, \qquad [X_0, X_2] = 2X_3.$$

Hence in odd characteristic the six unordered direction pairs generate subgroup sizes $q^2, q^2, q^2, q^2, q^3, q^4$. Characteristic two kills the second bracket coefficient and produces the observed bad-characteristic collapse.

Boundary. The root-coset derivative law explains the chamber equality geometry and its symmetry. It remains distinct from the still-open global expansion statement that every nontrivial Levi cohomology class activates at least $4q^3$ charts.

Passes 5102–5109: $q = 4$ expansion closure, the U_{81} controller, and rank-two root calculus

The active-chart distance attack now closes completely at $q = 4$. Two chamber stars at gallery distance d share exactly q^{4-d} apartments, so any XOR of $1 \leq m \leq q$ distinct chamber stars obeys

$$\mathrm{wt} \geq q^3 m(q + 1 - m) \geq q^4,$$

with equality realized by panel subsets. At $q = 5$ this forces any counterexample to have chamber-generator leader at least six; the minimum-local-cut propagator independently forces any nonstar candidate to contain a heavier local cut.

For $q = 4$, Pass5090 already proved that a word whose active K_5 charts are all minimum $1|4$ cuts is a chamber star. Conditioning a heavy $2|3$ chart in each of the four fixed-apartment chart roles gives exact MILP optimum 384. The local $PGL(2,4)$ edge stabilizer is transitive on the six heavy cut patterns. Hence the complete $[13600, 256, 256]_2$ minimum shell is exactly the 425 chamber stars, and every nonzero word activates at least

$$A(y) \geq 256 = 4q^3.$$

The factor-17 bridge also becomes integral and global. On each quadratic lane the theta companion

$$C = \begin{pmatrix} 0 & 16 \\ 1 & 2 \end{pmatrix}$$

and twisted block $T_6 = \left(\begin{smallmatrix} 2 & 8 \\ 2 & 0 \end{smallmatrix}\right)$ satisfy $CP = PT_6$ for $P = \left(\begin{smallmatrix} 2 & -2 \\ 0 & 1 \end{smallmatrix}\right)$ of determinant 2. Every nonsingular integral solution has even determinant, so index two is minimal. Across the fifteen Levi line-kernel lanes this gives an explicit index-2^{15} map into the exact 30-dimensional global theta carrier.

The type-C_2 maximal unipotent controller now literally contains the two BT865 torsors:

$$U_{81} = H_{27}\,\mathbb{F}_3^3, \qquad H_{27} \cap \mathbb{F}_3^3 = U' \cong C_3^2,$$

with $Z(U) = Z(H_{27}) \cong C_3$. The canonical V_4 complement normalizes both subgroups. On protected memory,

$$H_1(\mathbb{F}_3)\downarrow_U \cong \mathbb{F}_3[U],$$

one regular copy; restricting to either index-three subgroup recovers the previous $3\,\mathrm{Reg}(H_{27})$ and $3\,\mathrm{Reg}(\mathbb{F}_3^3)$ coordinate systems.

The derivative/curvature calculus extends across rank two. In good characteristic the pair-generated positive-root counts are encoded by

$$A_2 : 2z^2 + z^3, \qquad C_2 : 4z^2 + z^3 + z^4, \qquad G_2 : 10z^2 + 3z^3 + z^5 + z^6,$$

while the first-root derivatives are $3q^2$, $4q^3$, and $6q^5$. The G_2 bad-prime reductions recorded here are only Lie-bracket shadows, not full bad-characteristic group laws.

Three auxiliary probes sharpen the same structure. The 81×108 $q = 3$ root-coset incidence matrix has Smith form $1^{68}, 3, 0^{12}$, so its cokernel is $\mathbb{Z}^{12} \oplus \mathbb{Z}/3$. The regular U_{81} memory has augmentation-layer Hilbert series

$$(1 + t + t^2)^2(1 + t^2 + t^4)(1 + t^3 + t^6),$$

which records the C_2 root heights $1, 1, 2, 3$ and restricts to the Heisenberg and flat BT865 memory filtrations. Finally, the canonical diagonal V_4 splits the rational 12-dimensional incidence defect into character sectors $4 + 4 + 2 + 2$. The same defect is phase-pure for the canonical center $Z(U) = Z(H_{27}) \cong C_3$: a central generator has characteristic polynomial $(x^2+x+1)^6$, so over $\mathbb{C}$ the defect is $6\omega \oplus 6\omega^2$ with no center-trivial vectors. Two V_4 involutions invert the center and exchange those conjugate six-spaces, while the third fixes the center.

Boundary. The all-q and $q = 5$ minimum-distance theorem remains open. The $q = 4$ minimum shell and active-chart theorem are closed. The controller, memory, Smith-defect, and center-phase statements are exact finite group/module results, not fabricated-hardware performance claims.

Passes 5110–5117: Levi cut gauge, intrinsic chart recovery, radius-three decoding, and perfect apartment duality

The chamber-generator gauge is exactly the binary cut space of the Levi graph. Indeed every panel star maps to zero on apartment coordinates, these stars span the connected Levi cut space, and Pass 5066 gives the complementary rank q^4. Hence

$$\ker\bigl(\mathbb{F}_2^{E(\Gamma)} \to C_{\mathrm{apt}}\bigr) = \mathrm{Cut}(\Gamma;\mathbb{F}_2), \qquad \dim C_{\mathrm{apt}} = q^4.$$

Thus a minimum chamber-generator representative is a cut-minimal Levi edge set.

At $q = 5$ this cut gauge, together with girth eight and the exact pair intersections of chamber stars, first forces every hypothetical word of weight below 625 to have chamber leader at least 14. Pass 5118 subsequently strengthens the barrier to at least 17; the distance-625 theorem itself remains open.

The local tester geometry is intrinsic to the code. Pass 5081 recovers theta triples as the complete dual minimum shell, and Pass 5079 identifies genuine Tanner six-cycles with apartments through a common length-four geodesic root. From these data one reconstructs the q-apartment root blocks and then the unique $(q+1)$-root opposite-pair charts. The construction is a finite-generalized-quadrangle theorem and has exact replay anchors at $q = 2, 3, 4$.

For $q = 3$ the local decoder can be made chart-equivariant by abstaining on the unique three-way weight-two syndrome tie. Apartment transitivity reduces the complete weight-three test to

$$\binom{1619}{2} = 1,309,771$$

triples through one fixed apartment. Every such pattern clears within two sweeps; $47,520$ first leave residual weight two and 450 first leave residual weight one, with no second-sweep failures. The certified hard-decision radius is therefore three.

The factor-17 arithmetic is now a literal order tower. If $\lambda = (1+\sqrt{17})/2$, then

$$\mathbb{Z} + 4\mathcal{O}_K \subset \mathbb{Z} + 2\mathcal{O}_K \subset \mathcal{O}_K,$$

with discriminants $272, 68, 17$ and per-lane inclusion indices $2, 2, 4$. Across the fifteen Levi-kernel lanes these become $2^{15}, 2^{15}, 4^{15}$.

Three outside-box probes sharpen the same architecture. The C_2 root-coset incidence matrix has defining-characteristic rank drops $0, 1, 8$ at $q = 2, 3, 5$; the tempting two-anchor odd-q extrapolation is explicitly retracted because Pass 5123 gives q7 drop 10, not 27. The q3 code reconstructs its own local $U_{81} \rtimes V_4$ controller, with the two index-three torsors identified as the extraspecial H_{27} state shell and flat $\mathbb{F}_3^3$ program shell, up to the natural point/line swap. Finally the cut-gauge and theta presentations are perfect duals:

$$\mathbb{F}_2^{E(\Gamma)}/\,\mathrm{Cut}(\Gamma) \cong \mathrm{Hom}_{\mathbb{F}_2}(Z_1(\Gamma),\mathbb{F}_2),$$

and the pairing is exactly evaluation of a chamber cochain on an apartment boundary.

Boundary. The q5/all-q minimum-distance theorem and radius-four decoding remain open. The perfect pairing is quotient-versus-dual, not an orthogonal self-duality statement. Decoder claims are finite code statements, and the quadratic-order ladder is arithmetic rather than a historical geometric identification.

Passes 5118–5125: q=5 cut–Delsarte barrier, theta isoperimetry, and the explicit U_{81} compiler

The cut-gauge theorem of Pass 5110 and the q=5 leader bound of Pass 5111 admit a sharper distance-scheme continuation. The q=5 chamber graph has shells $1, 10, 50, 250, 625$ and spectrum $10, 4, -2, 4 \pm \sqrt{10}$. Universal subcubic girth-eight bounds give at most $20, 22, 24$ adjacent chamber pairs for cut-minimal leaders of sizes $14, 15, 16$. Exact Delsarte enumeration then gives apartment-weight lower bounds

$$1160, \qquad 925, \qquad 680,$$

respectively. Hence a hypothetical q=5 word of weight below 625 has minimum chamber leader at least 17.

There is also an all-q support law. The theta point graph is $8(q-1)$-regular. Because every apartment lies in $4(q-1)$ theta checks and every codeword has even parity on each theta triple, every selected apartment has exactly $4(q-1)$ selected and $4(q-1)$ unselected theta neighbors. Thus for every codeword support S,

$$\Gamma_\theta[S] \text{ is } 4(q-1)\text{-regular}, \qquad |\delta_\theta(S)| = 4(q-1)|S|.$$

This is a necessary intrinsic isoperimetric constraint, not a converse to the theta parity equations.

The local controller now has literal polynomial coordinates. For the standard positive-root ordering,

$$u(a,b,c,d) = x_0(a)x_1(b)x_2(c)x_3(d) = [x_0(a)x_2(c)x_3(d)]x_1(b)$$

and

$$u = [x_1(b)x_2(c+ab)x_3(d+2ac+a^2b)]x_0(a).$$

Hence the H_{27} state coordinates and the $\mathbb{F}_3^3$ program coordinates are related by an explicit polynomial permutation of the regular U_{81} basis.

The q=3 root-coset Smith defect is also explicit. An extra modular kernel vector a gives an integral torsion generator $w = H^T a/3$, and the unique $\mathbb{Z}/3$ quotient has trivial U_{81} action and V_4 character $(+,-,+,-)$. This is exactly the conjugation character of $Z(U_{81}) = Z(H_{27})$, so

$$\operatorname{Tor}\operatorname{coker}(H^T) \cong Z(U_{81})$$

as $\mathbb{F}_3[U_{81} \rtimes V_4]$-modules, up to the nonzero scalar choice.

Finally, the protected-memory filtration extends through Jennings theory: in the safe prime-field range its Hilbert series is the product of one truncated p-string at every positive-root height. Exact $A_2, p = 3$, $C_2, p = 5$, and $G_2, p = 7$ profiles are frozen, while the separately computed $C_2, p = 3$ packet remains a small-prime anchor.

Three outside-box tests sharpen the firewall. The q=7 root-coset ranks are 1183 generically and 1173 in characteristic seven, killing the naive cubic native-drop extrapolation. Binary Levi bicycle dimensions at q=3,5,7 are $29, 129, 349$; Pass 5130 subsequently promotes their odd-q pattern to a theorem using the established binary incidence-rank formula. The torsion/triality identification above is equivariant, not a count coincidence.

Boundary. Pass 5126 continues the q=5 wall to leader at least 18 and Pass 5130 closes the odd-q bicycle formula. The q=5 minimum-distance theorem itself remains open. No physical charge, particle, hardware-latency, or fault-tolerance interpretation is inferred from the arithmetic and modular modules.

Passes 5126–5133: q=5 leader wall, decoder radius five, and the all-q unipotent controller

The q=5 cut–Delsarte attack advances one more exact chamber-leader shell. A cut-minimal 17-edge leader is a bipartite maximum-degree-three girth-eight subgraph of the Levi graph. Exhaustive degree-sequence feasibility rejects every profile with more than 25 adjacent selected-edge pairs, while 25 is realizable. Exact Delsarte positivity at that sharp cap gives the extremal chamber-distance distribution

$$(N_1, N_2, N_3, N_4) = (25, 66, 45, 0)$$

and the apartment-weight lower bound 625. Thus every hypothetical q=5 word of weight below 625 has minimum chamber leader at least 18.

The weight-625 equality shell also obeys an integral coarea congruence. For either chart type separately the local-cut sum is $2 \cdot 625 = 1250$. Since a nonzero K_6 cut has size $5, 8$, or 9, if A is the active-chart count and h_8, h_9 are the heavy counts then

$$5A + 3h_8 + 4h_9 = 1250.$$

Hence $3h_8 + 4h_9 \equiv 0 \pmod 5$. The smallest nonzero defect is uniquely $(h_8, h_9) = (2, 1)$, so an exotic minimum must contain at least three heavy charts in one point/line type and has at most 498 active charts in total, versus 500 for a chamber star.

The q=3 equivariant local-vote decoder now has a larger exact Hamming guarantee. The apartment chart-sharing graph is 20-regular. Exhaustive connected-component censuses through one apartment contain 13269 connected four-sets and 381480 connected five-sets. Every max-vote correction through weight five is a subset of the true errors, and connected components of sizes $1, 2, 3, 4, 5$ clear within $1, 1, 2, 2, 3$ sweeps. Component separation therefore proves a global hard-decision radius-five guarantee with at most three sweeps.

The controller construction also becomes uniform in q. For the type-C_2 maximal unipotent group $U(q)$, a reconstructed chamber determines a regular q^4-apartment torsor, and the $4q^3$ active opposite-pair charts are exactly the right cosets of the four positive-root subgroups. Full hypergraph equality is replayed at $q = 2, 3, 4, 5$, including $\mathbb{F}_4$. On a chamber-star support the intrinsic theta graph is consequently

$$\mathrm{Cay}\left(U(q), \bigcup_{i=1}^{4} (H_i \setminus \{1\})\right),$$

a $4(q-1)$-regular graph whose root-subgroup cosets are the active q-cliques.

The state/program coordinate change is likewise field-uniform. With state coordinates $(b; a, c, d)$, program coordinates are

$$(a; b, C, D), \qquad C = c + ab, \qquad D = d + 2ac + a^2 b,$$

with inverse $c = C - ab$ and $d = D - 2aC + a^2 b$. The root-subgroup matrix factorization is exact over the coefficient field; in characteristic two the $2ac$ term vanishes automatically.

Finally, the binary Levi bicycle formula is no longer merely an odd-q conjecture. The established binary incidence-rank theorem for the symplectic generalized quadrangle gives, for every odd prime power q,

$$\operatorname{rank}_{\mathbb{F}_2} N = 1 + \frac{q(q+1)^2}{2}, \qquad \operatorname{null}_{\mathbb{F}_2} N = \frac{q(q^2+1)}{2}.$$

Because the Levi degree $q+1$ is even,

$$\dim \mathrm{Bike}_2(\Gamma_{\mathrm{Levi}}) = 2 \operatorname{null}_{\mathbb{F}_2} N - 1 = q^3 + q - 1.$$

The repo independently rebuilds the $q = 3, 5, 7, 11$ values $29, 129, 349, 1341$.

Boundary. The q=5/all-q apartment-code distance theorem remains open for leaders at least 18; the coarea congruence constrains but does not eliminate exotic weight-625 words. The q=3 hard-decision radius-five guarantee is sharp: Pass 5136 supplies an explicit weight-six false-vote counterexample. The odd-q bicycle theorem does not cover even q. The controller and compiler are exact finite algebraic objects, not hardware-performance claims.

Passes 5134–5141: the q=5 third-order breakthrough, sharp decoder radius, and root-Cayley spectral geometry

The q=5 chamber-leader attack first reaches an exact methodological boundary at leader size 18. A cut-minimal 18-edge leader is bipartite, subcubic, and girth at least eight. Exhaustive degree-sequence realization gives the sharp adjacent-pair cap 27. Exact chamber-scheme Delsarte positivity at that cap has extremal pair-distance distribution

$$(N_1, N_2, N_3, N_4) = (27, 73, 53, 0),$$

but its second-order Bonferroni lower bound is only 320. Thus pairwise information alone cannot close $m = 18$.

The equality shell already carries a third-order defect. In a q=5 local K_6 cut, the three nonzero cut types have weights $5, 8, 9$ and selected line-graph triangle counts $10, 8, 6$. Hence for one point/-line chart type,

$$T_{\text{type}} = 10A_{\text{type}} - 2h_8 - 4h_9 = 2500 - 8h_8 - 12h_9.$$

Together with $5A_{\text{type}} + 3h_8 + 4h_9 = 1250$, the unique smallest exotic profile $(h_8, h_9) = (2, 1)$ has $A_{\text{type}} = 248$, $T_{\text{type}} = 2472$, a triangle-moment defect of 28 from the chamber-star value 2500.

The missing triple-intersection coefficient is now explicit for every finite q. For three distinct chamber stars, the common-apartment count depends only on the sorted three pairwise gallery distances:

(d_{12}, d_{13}, d_{23})	$(1,1,2)$	$(1,2,3)$	$(1,3,4)$	$(2,2,4)$	$(2,3,3)$
$\lvert S_1 \cap S_2 \cap S_3 \rvert$	q^2	q	1	1	1.

Every other distance triangle has zero common apartments. These are the five dihedral three-edge patterns of an apartment C_8. Full rooted triple censuses replay the law at $q = 2, 3, 4, 5$, including $\mathbb{F}_4$; at q=5 the fixed-base histogram is $25^{75}, 5^{750}, 1^{7500}, 0^{428320}$.

Crucially, the triple law closes the q=5 leader-18 shell. Let N_1 be the number of adjacent selected chamber pairs and let P_3 count selected three-edge Levi paths. Since for each selected edge uv one has $d(u) - 1, d(v) - 1 \in \{0, 1, 2\}$ and $xy \geq 2x + 2y - 4$ on this set,

$$P_3 = \sum_{uv} (d(u) - 1)(d(v) - 1) \geq \max\{0, 4(N_1 - 18)\}.$$

Every such path has gallery signature $(1, 1, 2)$ and therefore contributes $q^2 = 25$ to the q=5 triple-overlap sum. The pointwise parity minorant

$$\mathbf{1}_{r \text{ odd}} \geq r - 2\binom{r}{2} + \frac{6}{17}\binom{r}{3}, \qquad 0 \leq r \leq 18,$$

combined with exact Delsarte pair maxima for each $N_1 \leq 27$ has its worst shell at $N_1 = 27$. There the pair-only lower bound is 320, $P_3 \geq 36$, and the triple overlap is at least 900, so

$$17\,\text{wt} \geq 17 \cdot 320 + 6 \cdot 900 = 10840, \qquad \text{wt} \geq 638 > 625.$$

Consequently every hypothetical q=5 word of weight below 625 now has minimum chamber leader at least 19.

The q=3 hard-decision decoder frontier is sharp. Pass 5131 proves every error of weight at most five is corrected. At weight six, the structured error set

$$\{1, 2, 3, 6, 27, 54\}$$

uses three charts through false apartment 0, with two errors in each. Each local two-error syndrome votes for the false center; the global maximum vote is 3, and the first correction set is

$$\{0, 1, 2, 3, 6, 27, 54\}.$$

Thus the guaranteed radius of this specific equivariant max-vote decoder is exactly five.

The chamber-star theta graph also admits an exact Fourier/spectral description. The abelianization $U(q)/[U(q), U(q)] \cong \mathbb{F}_q^2$ gives a uniform q^2-dimensional linear-character sector with eigenvalues

$$4(q-1)^{[1]}, \qquad (3q-4)^{[2(q-1)]}, \qquad (2q-4)^{[(q-1)^2]}.$$

For $q = 2, 3, 4, 5$ the full spectra are certified over the integers by square-free annihilator polynomials and exact closed-walk traces. In all four anchors the second eigenvalue is $3q - 4$, giving spectral gap q; the uniform nonlinear bound remains open.

The state/program compiler is compatible with the protected-memory filtration. In canonical state coordinates,

$$(a, b, c, d)(A, B, C, D) = (a + A, b + B, c + C - Ab, d + D - 2Ac + A^2 b),$$

whereas program coordinates obey

$$(a, b, C, D) \circ (A, B, E, H) = (a + A, b + B, C + E + aB, D + H + 2aE + a^2 B).$$

The Pass 5133 polynomial map intertwines these laws exactly. Its linear extension to $k[U(q)]$ preserves the augmentation ideal J and every power J^r, hence every Jennings layer J^r/J^{r+1}; exhaustive product checks are supplied at $q = 2, 3, 4, 5$.

A separate all-q cut theorem closes the chamber-dependency code. Girth eight controls small Levi cuts while the nontrivial Levi eigenvalue $\sqrt{2q}$ controls every larger half-cut. Consequently

$$C_{\mathrm{dep}} = \left[(q+1)^2(q^2+1),\ 2(q+1)(q^2+1) - 1,\ q+1\right]_2,$$

and its $2(q+1)(q^2+1)$ minimum words are exactly point- and line-panel stars.

Finally, the four-root Cayley metric has diameter at most four by canonical positive-root factorization. Exact BFS anchors at odd primes $q = 5, 7, 11, 13$ obey

$$|S_0| = 1, \quad |S_1| = 4(q-1), \quad |S_2| = 8(q-1)^2,$$
$$|S_3| = (q-1)^2(10q-21), \qquad |S_4| = (q-1)^2(q-4)^2,$$

which sum identically to q^4. This polynomial shell law remains a four-anchor conjectural family until a symbolic factorization count is supplied; $q = 2, 3, 4$ show small-field compression.

Boundary. The q=5/all-q apartment-code distance theorem remains open for leaders at least 19. Pass 5140 closes leader 18 cubically; higher shells may require fourth and higher parity intersections. Decoder radius five is a theorem for the specified hard-decision max-vote rule and radius six is explicitly false for that rule. The full all-q nonlinear theta spectrum and uniform gap-q proof remain open. The odd-q Cayley shell polynomial is conjectural beyond the exact anchors. None of the controller, spectrum, compiler, or Jennings statements is a hardware-performance claim.

77.2 The protected shells close into $O^+(8,2)$ and reach the exceptional six-space (Passes 4579–4586)

Pass 4579: the W33 lifts reconstruct all 255 nonzero vectors of $O^+(8,2)$. Start only from the two geometric lifts established in Passes 4558–4559: the 1620 apartments map 12-to-1 onto 135 singular classes, while the 240 protected edges map 2-to-1 onto 120 anisotropic classes. These two sets are disjoint and exhaust the 255 nonzero classes of $V_8 = V_9/\langle j \rangle$. With

$$q([x]) = \frac{\mathrm{wt}(x)}{4} \pmod 2, \qquad B(x,y) = q(x+y) + q(x) + q(y),$$

the lift-native polar degrees are

	singular	anisotropic
singular	70	56
anisotropic	63	63

.

Every two distinct nonzero vectors determine a binary projective line; the 10795 lines split into 1575 all-singular triples, 3780 triples with one singular and two anisotropic points, and 5440 all-anisotropic triples. Thus the W33 lifts reconstruct the complete projective quadratic incidence geometry, not merely its two shell cardinalities.

Pass 4580: the elliptic binary-rank problem reduces to one exact dual-containing code theorem. Let N be the point–line incidence matrix of $Q^-(5,q) = GQ(q,q^2)$ for odd q and let $C = \operatorname{im} N \subseteq \mathbb{F}_2^{|\mathcal{P}|}$. The candidate formulas from Passes 4537/4552 are equivalent to

$$\dim C = q^4 + q^2 + 1, \qquad C^\perp = \ker N^T \subseteq C, \qquad \dim C^\perp = q(q^2 - q + 1).$$

Indeed these imply

$$\boxed{\operatorname{rank}_2(N^T N) = \dim(C/C^\perp) = (q^2+1)(q^2-q+1).}$$

The exact $q = 3, 5, 7$ computations satisfy the full dual-containing identity, with radical dimensions $21, 105, 301$. A targeted literature audit did not locate the required cross-characteristic binary point–line theorem for the elliptic family; defining-characteristic rank theorems for related polar spaces do not supply it. The infinite rank formula therefore remains open, now as one precisely isolated code-theoretic statement.

Pass 4581: every twelve-apartment fiber is an equivariant 3×4 resolution. For a singular class, the three independent sets of four in its $K_{4,4,4}$ fiber are not arbitrary: each set consists of four pairwise-disjoint apartments and each of the three sets partitions the same canonical 16-line support. The singular-class stabilizer has order 192 and line-orbit sizes

$$16, 8, 8, 8,$$

with the common support the unique 16-orbit. Its action on the twelve apartments has image order 96 and kernel order two; the induced action on the three four-sets is the full S_3, with elementary-abelian 2^4 kernel. A setwise stabilizer of one four-set acts on its four apartments as D_8.

Pass 4582: optimal protected readout needs 11 channels for one erasure and 14 for two. Allow the natural 280 protected carriers: forty line-stars and 240 edge vectors. A selected carrier set survives t arbitrary erasures precisely when every nonzero linear functional on H_{10} has support at least $t+1$ on the selected columns. Equivalently its ten-dimensional binary row code has minimum distance at least $t+1$. Exact witnesses give

$$\boxed{n_{t=1} = 11}, \qquad \boxed{n_{t=2} = 14}.$$

The first is optimal because deleting one carrier must still leave ten independent channels. For two erasures, lengths 12 and 13 are excluded by the binary Hamming bound for a $[n, 10, d \geq 3]$ code, while the fourteen-carrier witness survives every pair deletion. The parity coordinate is therefore no longer tied to one distinguished center line-star.

Pass 4583: the alternating square supplies the first equivariant protected-to-$O_6^-(2)$ bridge. Pass 4556 rules out every nonzero equivariant linear map $H_{10} \leftrightarrow U_6$, and the independently completed Pass 4576 sharpens the unary obstruction: there is no nonzero equivariant Boolean polynomial map $V_8 \to U_6$ or $U_6 \to V_8$ of degree at most two. Pass 4583 does not evade that result with a different polynomial presentation; it changes the domain to a *pair* of protected vectors. The relevant functor is $\Lambda^2 V_8$. Contraction with the protected alternating form gives an invariant hyperplane

$$K_{27} = \ker\big(B : \Lambda^2 V_8 \to \mathbb{F}_2\big)\,.$$

It contains a 15-dimensional invariant core K_{15} and exact exhaustion of the quotient gives

$$\boxed{K_{27}/K_{15} \cong U_6 \oplus U_6}.$$

There are exactly three invariant six-submodules in this twelve-space. Each is irreducible, has faithful $PSp(4,3)$ image of order 25920, and has nonzero orbits of sizes 27 and 36, reproducing the natural $O_6^-(2)$ singular and anisotropic shells. Hence every distinct orthogonal protected pair has the bilinear equivariant route

$$(v, w) \longmapsto v \wedge w \longmapsto K_{27}/K_{15} \longmapsto U_6.$$

For a fixed invariant factor, all 64 target vectors occur: zero has 945 unordered orthogonal-pair preimages and each nonzero target has exactly 240. This is a pair-valued bridge; choosing one of the three U_6 factors is an additional equivariant splitting choice.

Pass 4584 (outside the box): singular–anisotropic incidence is a new $[120, 9, 56]$ code. Let R be the 135×120 matrix with $R_{sa} = 1$ when singular class s is polar-orthogonal to anisotropic class a. Then

$$\operatorname{rank}_2 R = 9, \qquad RR^T = 0, \qquad R^T R = J_{120},$$

and the row code is the self-orthogonal code

$$\boxed{[120, 9, 56], \qquad W(z) = 1 + 255z^{56} + 255z^{64} + z^{120}.}$$

It contains the all-ones word, so quotienting by that fixed line gives another eight-dimensional realization of the protected orthogonal geometry.

Pass 4585 (outside the box): the singular shell has a canonical $135 \to 45$ quotient. The twelve apartments over a singular class use sixteen W33 lines, but only 45 distinct sixteen-line supports occur. Each support is shared by exactly three singular classes; the three are pairwise orthogonal and sum to zero in V_8, hence form a totally singular projective line. The 45 supports form one $PSp(4,3)$ orbit with stabilizer order 576. Its action on the three singular points is C_3, with kernel order 192, exactly the singular-point stabilizer of Pass 4581. Thus the 135 shell is an explicit three-sheeted lift of a natural forty-five-object orbit.

Pass 4586 (outside the box): a rank-15 45×40 incidence crosses the non-self-dual W33 boundary. For each original W33 point, its four incident line-vertices form a K_4 pencil; the three opposite-edge pairs define three anisotropic classes, an all-anisotropic projective line. There are forty such lines. Declare one of the forty-five singular support-lines incident with one of these forty anisotropic lines iff all nine cross pairs are polar-orthogonal. The resulting matrix T has row weight eight, column weight nine, and

$$\boxed{\operatorname{rank}_2 T = 15}.$$

Its integer Gram identities are

$$\boxed{TT^T = 8I_{45} + 2A_{45}}, \qquad \boxed{T^T T = 8I_{40} + 2A_{\text{point}} + J_{40}},$$

where

$$A_{45} = \mathrm{SRG}(45, 32, 22, 24)$$

and A_{point} is *exactly* the point-side $\mathrm{SRG}(40, 12, 2, 4)$ of W33. The executable explicitly checks that $A_{\text{point}} \neq A_*$, the protected line-side graph. Thus this construction crosses the odd-q point/line non-self-duality instead of identifying the two forty-sets. The repository already contains natural forty-five-object carriers with the same SRG parameters; identity with any particular E_6/center-quad carrier is deliberately withheld until an action intertwiner is certified.

> **Evidence boundary.** Passes 4579–4586 are exact finite binary geometry, incidence coding, and representation theory. The all-q elliptic binary-rank formula remains open beyond $q = 3, 5, 7$. The exceptional bridge is bilinear on orthogonal pairs, not a canonical unary state map. The forty-five-object parameter match is not promoted to an E_6 identification without an explicit intertwiner. Erasure bounds and Hamming/polar incidence are not physical fault thresholds or spacetime locality.

Current protected frontier: finite D_4 triality from the W33 lift

The protected binary quotient reconstructed from the W33 line/apartment system has 256 classes and a plus-type quadratic form. Pass 4579 had already shown that its 255 nonzero classes split as 135 singular apartment classes and 120 anisotropic opposite-edge classes. Passes 4587–4591 now reconstruct the full outer-node triality geometry *inside that same W33-derived quotient*, without importing an E_8 coordinate model.

Exact finite triality theorem. The totally singular subspaces occur in the exact counts

$$135, \qquad 1575, \qquad 2025, \qquad 270$$

in vector dimensions $1, 2, 3, 4$. The 270 maximal totally singular 4-spaces split into two families of 135. Thus the three outer D_4 types are

$$\mathcal{P}_{135}, \qquad \mathcal{S}^{+}_{135}, \qquad \mathcal{S}^{-}_{135}.$$

For any two distinct outer types, let M be the 135×135 incidence matrix. Every row and column has weight 15, and each outer type carries the same relation

$$A = \mathrm{SRG}(135, 70, 37, 35), \qquad \mathrm{spec}(A) = 70^1 \oplus 7^{50} \oplus (-5)^{84}.$$

The incidence Gram law is

$$MM^{\mathsf{T}} = 15I + 3A.$$

More strongly, for cyclically ordered outer types,

$$M_{12}M_{23} = J + 6M_{13}.$$

After removing the trivial all-ones constituent with the integral centering

$$D_{ij} = 9M_{ij} - J,$$

the three maps satisfy the exact triality algebra

$$\boxed{D_{12}D_{23} = 54D_{13}}$$

cyclically, and

$$D_{ij}D_{ij}^{\mathsf{T}} = 1215I + 243A - 135J = 54^2E_{50}, \qquad \mathrm{rank}_{\mathbb{Q}}\, D_{ij} = 50.$$

This is an explicit rank-50 intertwiner layer, not a numerical coincidence of three cardinalities.

What the 1620 **W33 apartments do inside this triality geometry.** For an apartment $\{a, b, c, d\}$ in the W33 line graph, its two opposite line pairs give two singular quotient vectors; together with the apartment's Pass 4579 singular fiber label they form one totally singular projective line. The resulting map has exact multiplicities

$$1620 \longrightarrow 270 \quad \text{(6-to-1)},$$

where the selected 270 singular lines form one $\mathrm{PSp}(4, 3)$ orbit. They define a regular incidence structure

$$135_6 - 270_3,$$

and the apartments are a two-sheet cover of its 810 point–line flags.

The apartment-selected singular graph. Let $N \in \{0, 1\}^{135\times 270}$ be the incidence matrix of the 135 singular points against those 270 selected lines. Then every row has weight 6 and every column has weight 3. Writing

$$NN^{\mathsf{T}} = 6I + A_{\mathrm{sel}},$$

the selected point graph is 12-regular on 135 vertices and has exact spectrum

$$\boxed{12^1 \oplus 6^{15} \oplus 3^{20} \oplus 0^{60} \oplus (-3)^{24} \oplus (-6)^{15}}.$$

Its annihilator is

$$(x - 12)(x - 6)(x - 3)x(x + 3)(x + 6).$$

Every adjacent pair has exactly one common neighbor. Hence every edge lies in a unique triangle and the graph has exactly $810/3 = 270$ triangles. These are precisely the 270 selected totally singular lines, so the apartment image can be recovered from the graph alone. Moreover,

$$\mathrm{rank}_{\mathbb{Q}}\, N = 120, \qquad \mathrm{rank}_{\mathbb{F}_2}\, N = 119.$$

The tempting $120 = 120$ identification is false. The protected quotient also has 120 anisotropic points. Pass 4591 compares the actual $\mathrm{PSp}(4,3)$ characters rather than the dimensions. On the deterministic five-transvection generating set, all five generators happen to have trace 3 on both the rational rowspace of N and the anisotropic permutation module, so a shallow generator check is misleading. The short order-6 word $g_4 g_0$ separates them:

$$\chi_{\mathrm{row}_{\mathbb{Q}}\, N}(g_4 g_0) = -1, \qquad \chi_{\mathrm{aniso}}(g_4 g_0) = 3.$$

Therefore the two 120-dimensional rational $\mathrm{PSp}(4,3)$ modules are not isomorphic. This rules out a cardinality/rank promotion while leaving nonlinear or subquotient relationships as separate questions.

A useful obstruction, not an identification. A selected singular line lies in six maximal singular 4-spaces and has six W33 apartment lifts. The equality $6 = 6$ does *not* define a canonical bridge. Its stabilizer has order 96. On the six apartments it acts transitively; on the six maximal generators its orbit sizes are $3 + 2 + 1$. The two actions have the same image order 12 and even the same kernel of order 8, but their fixed-point characters differ. Therefore there is no stabilizer-equivariant bijection between those two six-sets.

The positive replacement. Under the projective W33 group the 270 maximal singular generators decompose as

$$135 \sqcup 36 \sqcup 36 \sqcup 36 \sqcup 27.$$

The three degree-36 orbits were checked as G-sets rather than named from their sizes: for each orbit, a representative stabilizer has order 720 and fixes exactly one of the 36 W33 spreads. Hence each is genuinely equivariantly isomorphic to the W33 spread carrier. The degree-27 orbit is deliberately left unnamed until the same stabilizer/permutation-character test identifies it.

Evidence boundary. Everything above is finite W33-derived $O^+(8,2)$ / D_4 building geometry and exact permutation-module algebra. "Half-spinor family" is the standard finite orthogonal-building term. No physical spinor field, particle generation, E_8 lattice shell, or dynamical triality is inferred here. Pass 104 already provides the separate explicit anisotropic $E_8/2E_8$ isometry and must not be replaced by a cardinality argument.

Executable witnesses: `analysis/w33_pass4587_w33_derived_d4_triality.py`, `analysis/w33_pass4588_ap` `analysis/w33_pass4589_apartment_selected_singular_graph.py`, and `analysis/w33_pass4591_rank120_an`

77.3 The two cubic incidence axes fuse to simplex/Hamming and enter Golay through the hexacode (Passes 4592–4615)

Pass 4592: the two self-orthogonal cubic axes are complementary restrictions of one simplex code. Pass 4575 gave the two rank-six binary codes

$$C_{36} = [36, 6, 16], \qquad C_{27} = [27, 6, 12]$$

by evaluating the same $x \in U_6 \cong \mathbb{F}_2^6$ on, respectively, the 36 anisotropic and 27 nonzero singular vectors of the minus quadratic space. Keep the same message x on both coordinate sets and concatenate. For nonzero singular x the two partial weights are $16 + 16$, while for anisotropic x they are $20 + 12$. Hence every nonzero concatenated word has weight 32 and

$$\boxed{C_{63} = [63, 6, 32], \qquad W_{C_{63}}(z) = 1 + 63 z^{32}.}$$

Thus C_{63} is the binary six-dimensional simplex code and $C_{63}^{\perp} = [63, 57, 3]$ is the Hamming code. Its 63 coordinates are literally all nonzero vectors of $\mathbb{F}_2^6$; the original $27 \mid 36$ split is the singular/anisotropic coloring supplied by the minus quadratic form. The full coordinate symmetry of the uncolored simplex is $GL(6, 2)$, whereas $O^-(6, 2) \cong PGSp(4, 3)$ is the subgroup preserving this quadratic coloring.

Choose a compatible $\mathbb{F}_4$-structure $\mathbb{F}_2^6 \cong \mathbb{F}_4^3$. The standard hexacode $\mathcal{H}_6 = [6, 3, 4]_4$ has

$$W_{\mathcal{H}_6}(z) = 1 + 45z^4 + 18z^6.$$

Concatenating each $\mathbb{F}_4$ symbol with the binary inner simplex $[3, 2, 2]$ produces a binary

$$\boxed{[18, 6, 8], \qquad 1 + 45z^8 + 18z^{12}.}$$

The repository's explicit cyclic construction of the extended binary Golay code G_{24} contains exactly such a six-dimensional subcode: the first six message generators vanish on six coordinates, and after restriction to the other eighteen an explicit frozen coordinate permutation identifies the code word-for-word with the binary concatenated hexacode. This is an actual code embedding, not a parameter match:

$$C_{36} \oplus_x C_{27} \longrightarrow [63, 6, 32] \longrightarrow \mathcal{H}_6 \longrightarrow [18, 6, 8] \subset G_{24}.$$

The middle arrow requires a choice of compatible $\mathbb{F}_4$ structure and is therefore not claimed canonical under $O^-(6, 2)$.

Pass 4593: the exact apartment-code census reaches support ten. A native fixed-weight XOR/popcount kernel exhausts all

$$\binom{40}{10} = 847660528$$

ten-row coefficient subsets. The complete support-ten spectrum has 147 distinct weights, ranging from 582 to 1080, with multiplicities 2160 at 582 and 36 at 1080. Together with Pass 4572, all labelled support spectra are now exact through support ten. The complete numerical $[1620, 39, 162]$ enumerator remains open because supports 11 through 20 have not all been accumulated.

Pass 4601: one complete eleven-factor extension skeleton is explicit inside S_{186}. Lifting the deterministic MeatAxe witnesses of Pass 4571 gives the exact composition series

$$\boxed{0 < 14 < 54 < 60 < 74 < 80 < 120 < 126 < 134 < 140 < 146 < 186}$$

with ordered simple factor dimensions

$$\boxed{14, 40, 6, 14, 6, 40, 6, 8, 6, 6, 40.}$$

This refines the previously proved multiset $40^3 + 14^2 + 8 + 6^5$. The displayed series is exact, but the complete unlabeled submodule lattice, radical/socle series and all extension classes are not claimed classified.

Pass 4602: the exceptional $GQ(2,2)$ C_8 collision disappears already in $GQ(2,4)$. Pass 4573 showed that in $GQ(2,2)$ coefficient 36 is shared by all 90 apartments and 60 non-apartment $K_{1,3}$ supports. Exhausting every four-line support of $Q^-(5,2) = GQ(2,4)$ gives the full primitive-C_8 degree-four spectrum and finds exactly 1080 supports with coefficient 60; they are exactly the 1080 apartments. Thus the three exact anchors are

$$GQ(2,2):\ \text{fail}, \qquad GQ(2,4):\ \text{succeed}, \qquad GQ(3,3):\ \text{succeed at coefficient } 712.$$

A closed symbolic criterion in arbitrary (s,t) remains open. The universal fallback remains Pass 4523: $C_6^{(2)}$ reconstructs line adjacency for every thick GQ, after which apartments are induced C_4s.

Pass 4603: the 135 apartment fibers form an imprimitive five-class association scheme. For two distinct twelve-apartment fibers, let n_2 count cross-fiber pairs sharing exactly two W33 lines. The five values

$$n_2 \in \{0, 2, 6, 12, 48\}$$

together with the diagonal satisfy every intersection-number axiom of a symmetric five-class association scheme. The nontrivial valencies are

$$\boxed{24, 12, 32, 64, 2.}$$

The valency-two $n_2 = 48$ relation is $45K_3$. Quotienting these 45 triples, there are only two cross-patterns: 6 relations of type $n_2 = 12$ plus 3 of type $n_2 = 6$, or 6 of type $n_2 = 0$ plus 3 of type $n_2 = 2$. Joining the first type gives

$$\boxed{\mathrm{SRG}(45, 32, 22, 24)}.$$

Hence the earlier $135 \to 45$ support quotient is an exact imprimitivity quotient of the apartment-fiber association scheme.

Pass 4604: the unary protected-to-cubic bridge is impossible at every degree. Under $G = PSp(4,3)$, the protected V_8 has nonzero orbits of sizes 135 and 120, while the natural cubic U_6 has nonzero orbits of sizes 27 and 36. Constant-fiber arithmetic rules out every nonzero orbit map except potentially $135 \to 27$, which would require a block system of block size five. The actual stabilizer of a protected singular point has order 192 and suborbit sizes

$$\boxed{1, 1, 1, 12, 12, 12, 32, 32, 32},$$

so no block containing the point can have size five. Therefore every unary $PSp(4,3)$-equivariant set map

$$\boxed{V_8 \longleftrightarrow U_6}$$

is zero. This supersedes the degree-≤ 2 polynomial no-go. The Pass 4583 exterior-square bridge survives because it is intrinsically a two-input map $(v, w) \mapsto v \wedge w$ through a larger module.

Pass 4605 (outside the box): forgetting the quadratic color enlarges the 63-point carrier to symplectic geometry. Keep the alternating polar form B on the 63 nonzero vectors of $\mathbb{F}_2^6$ and join x, y when $B(x,y) = 1$. The resulting graph is

$$\boxed{\mathrm{SRG}(63, 32, 16, 16)},$$

the symplectic graph for $Sp(6,2)$, whose natural linear group has order 1451520. The minus-quadratic color-preserving group $O^-(6,2)$ has order 51840 and index 28. The 64 quadratic refinements $q_v(x) = q(x) + B(v,x)$ split into 28 minus and 36 plus refinements; relative to a chosen minus form, the 63 nonzero shifts split as $27 + 36$.

Pass 4606 (outside the box): the two axes are a two-periodic differential and yield CSS codes. Because Pass 4575 proved $RR^T = R^T R = 0$ over $\mathbb{F}_2$, the cubic incidence gives the exact 2-periodic complex

$$\cdots \to \mathbb{F}_2^{27} \xrightarrow{R^T} \mathbb{F}_2^{36} \xrightarrow{R} \mathbb{F}_2^{27} \xrightarrow{R^T} \cdots .$$

With $\operatorname{rank} R = 6$, its two homology dimensions are

$$\boxed{24 \quad \text{and} \quad 15.}$$

These happen to equal the two nontrivial W33 adjacency multiplicities, but no module identification is inferred from dimension alone. The two individual self-orthogonal axes give CSS codes $[[36, 24, 3]]$ and $[[27, 15, 3]]$, while the fused simplex check space gives

$$\boxed{[[63, 51, 3]]},$$

the binary quantum Hamming code for $m = 6$.

Pass 4615 (outside the box): the Golay ambient code uniquely completes the six-dimensional section to a MOG sextet. The 45 weight-eight words of the embedded $[18, 6, 8]$ section are Golay octads. On the eighteen active coordinates every point lies in 20 of them, and pair frequencies are 10 on exactly 18 pairs and 8 on the other 135. The frequency-10 graph is exactly six disjoint triangles, reconstructing the six binary $[3, 2, 2]$ inner-code columns. The section is zero on six Golay coordinates. Testing all $6! = 720$ assignments of these six positions to the six triangles yields exactly one assignment for which the six resulting tetrads form a Golay sextet, i.e. every union of two tetrads is a Golay octad. Thus the paired-axis hexacode section internally reconstructs and is uniquely completed to a six-column MOG/sextet in the repository's frozen coordinate model.

> **Evidence boundary.** All claims above are exact finite code, group-action, association-scheme or binary-module statements backed by executable certificates. The full apartment weight enumerator remains open beyond support ten, the all-(s, t) C_8 criterion remains open, and the complete S_{186} submodule/Ext lattice is not claimed closed. The Golay bridge is a code embedding after choosing an $\mathbb{F}_4$ structure; it is not a claim that $O^-(6, 2)$ embeds in M_{24}. Indeed the group orders do not permit such an embedding. None of these finite structures is promoted to a physical particle, field or hardware channel without an additional dynamics theorem.

77.4 The forty-five carrier closes, the sentinel shell becomes self-describing, and outer symmetry glues the exceptional six-space (Passes 4616–4623)

Pass 4616: the protected forty-five is exactly the center-quad/E_6 forty-five. The forty-five 16-line supports constructed from the protected singular shell in Pass 4585 and the older forty-five antipodal center-quad quotient points are not merely graphs with the same parameters. In the common W33 model the stabilizer of a protected support has order 576 and fixes exactly one old center-quad quotient point. Sending $gU_0 \mapsto gQ_0$ therefore gives an explicit $PSp(4, 3)$-equivariant bijection of the two 45-sets; generator checks certify well-definedness and equivariance. Under this bijection the Pass 4586 $\mathrm{SRG}(45, 32, 22, 24)$ is exactly the established center-quad transport/disjointness graph. Thus the former parameter-only E_6/tritangent comparison is now an exact finite G-set intertwiner.

Pass 4617: the 45×40 transport is the complete minimum shell of the sentinel code. The same row permutation strengthens the previous graph identity to a matrix identity: a transport row is exactly the eight-point support of the corresponding center-quad quotient point. Let T be this 45×40 support matrix and let N be W33 point–line incidence. Over $\mathbb{F}_2$,

$$\operatorname{rank} T = 15, \qquad \operatorname{rank} N = 25, \qquad TN = 0.$$

Consequently

$$\boxed{\ker T = \operatorname{im} N}, \qquad \boxed{\operatorname{row} T = \ker N^T}.$$

The latter is the sentinel $[40, 15, 8]$ code. Every row of T has weight eight, and the exact sentinel enumerator has exactly forty-five weight-eight words, so these rows are the *entire* minimum shell:

$$1 + 45z^8 + 720z^{12} + 6930z^{16} + 17376z^{20} + 6930z^{24} + 720z^{28} + 45z^{32} + z^{40}.$$

Pass 4618: the three exceptional six-spaces form an S_3 multiplicity line, but the W33 outer involution singles out one. Pass 4583 found exactly three $PSp(4,3)$-invariant six-submodules in $Q_{12} = K_{27}/K_{15}$. Their full PSp commutant has dimension four over $\mathbb{F}_2$, hence sixteen elements; exactly six are units, and those six realize all six permutations of the three submodules. Thus the multiplicity space is a projective line with

$$\operatorname{Aut}_{PSp}(Q_{12})_{\text{units}} \cong GL(2,2) \cong S_3,$$

and no individual factor is canonical under the inner group. The actual W33 outer similitude acts on the three factors with cycle type $1 + 2$: it fixes one and swaps the other two. The fixed factor has inner image order 25920 and outer image order 51840, giving a unique $PGSp(4,3)$-stable six-submodule. The commutant S_3 is a multiplicity-space symmetry; no identification with geometric D_4 triality is made here.

Pass 4619: both half-spinor families now have concrete W33 lifts. The 270 maximal totally singular four-spaces of the protected $O^+(8,2)$ geometry have $PSp(4,3)$ orbit sizes

$$\boxed{27, 36, 36, 36, 135}.$$

For the transitive 135-orbit, a representative stabilizer has order 192 and fixes exactly three maximal size-eight W33 partial spreads. Those are exactly the three eight-line orbits in its line-orbit decomposition $8+8+8+16$, and each has full stabilizer 192. Thus this half-spinor object has a concrete three-valued lift by maximal partial spreads. For the other half-spinor family, the degree-27 orbit is explicitly the 27 center-quad/E_6 quotient lines via a unique fixed object under the order-960 stabilizer, while each of the three degree-36 orbits is the W33 spread G-set via a unique fixed spread under the order-720 stabilizer. This covers all 270 generators without collapsing the genuine inner-orbit decomposition.

Pass 4620: the elliptic binary-rank conjecture is exactly a Hermitian generator-code problem. The duality

$$Q^-(5,q) = GQ(q,q^2) \quad \longleftrightarrow \quad H(3,q^2) = GQ(q^2,q)$$

turns the same incidence matrix into the generator–point matrix of the Hermitian surface. The conjectural all-odd-q rank becomes

$$\boxed{\dim_{\mathbb{F}_2} C_1(H(3,q^2)) = q^4 + q^2 + 1 = \theta_2(q^2) = |PG(2,q^2)|},$$

equivalently $C^\perp \subseteq C$ with $\dim C^\perp = q(q^2-q+1)$. For odd q the line-graph SRG coefficients are all even, so its adjacency satisfies $A^2 = 0$ over $\mathbb{F}_2$ automatically. The exact $q = 3, 5, 7$ anchors continue to satisfy the proposed dimensions, but square-zero alone does not determine rank and no all-q proof is claimed.

Pass 4621 (outside the box): the sentinel minimum shell is self-describing. Forget the construction and retain only the forty-five weight-eight sentinel words. Two minimum words meet in either zero or two coordinates; declaring intersection two to be adjacency recovers exactly the center-quad/E_6 transport graph, with pair counts 270 and 720. Dually, two of the forty coordinate positions occur together in either one or three minimum words; declaring co-occurrence three to be adjacency recovers exactly the *point* side W33 graph, with pair counts 540 and 240. The recovered point graph is explicitly distinct from the protected line-side A_*. Thus the complete minimum shell alone reconstructs both sides of the 45×40 incidence.

Pass 4622 (outside the box): the 135 maximal partial spreads carry a second canonical three-cover. Pass 1100's 135 maximal/unextendable size-eight partial spreads are transitive. Pass 4619 shows that an order-192 stabilizer H fixes exactly three of them, and each of those three has full stabilizer H. Hence there are $135/3 = 45$ conjugacy packets of such stabilizers. Orbit–stabilizer gives

$$|N_G(H)| = 576, \qquad N_G(H)/H \cong C_3,$$

and the quotient acts regularly on the three spreads in each packet. This is a second exact $135 \to 45$ cover with a C_3 deck action. It is deliberately not identified with the center-quad forty-five without a new explicit intertwiner.

Pass 4623 (outside the box): outer symmetry makes the exceptional $6 \mid 6$ extension nonsplit. The unique outer-stable six-space of Pass 4618 is a submodule, not an outer-equivariant direct summand. Indeed Q_{12} restricts to $PSp(4,3)$ as $U_6 \oplus U_6$ and has exactly three inner-invariant six-spaces; the outer involution fixes only one of them. Any $PGSp$-stable complement would therefore be a second outer-stable member of that exhaustive three-element set, which does not exist. Thus

$$\boxed{0 \longrightarrow U_6 \longrightarrow Q_{12} \longrightarrow U_6 \longrightarrow 0}$$

splits over $PSp(4,3)$ but is nonsplit over $PGSp(4,3)$. Accordingly the orthogonal-pair wedge map of Pass 4583 is canonically outer-equivariant into Q_{12}, whereas projection to one six-space necessarily drops to inner equivariance or breaks the outer symmetry.

> **Evidence boundary.** Passes 4616–4623 are finite incidence, characteristic-two coding, and modular representation theory. The Hermitian binary generator-code dimension is an exact reformulation but remains open for all odd q beyond the checked $q = 3, 5, 7$ cases. The E_6, D_4 and $O_6^-(2)$ names refer to explicit finite G-sets/modules; no particle, spacetime, or dynamical identification follows from these results alone.

77.5 The packet 45 closes onto the E6 carrier, while the 45-by-40 incidence exposes H10 and the hexacode choice space (Passes 4624–4631)

Pass 4624: the maximal-partial-spread packet 45 is exactly the protected/E6 45. For a packet of the three maximal size-eight partial spreads fixed by the same order-192 subgroup H, their union contains 24 W33 lines. Its complement among the 40 lines is one of the Pass 4585 protected 16-line supports. The full orbit of this complement is exactly the 45 protected supports; its $PSp(4,3)$

stabilizer has order 576 and contains H with index three. Consequently the complement map is an explicit equivariant bijection

135 maximal partial spreads $\longrightarrow$ 45 packets $\cong$ 45 protected supports $\cong$ 45 center-quad/E6 objects.

The final identification is the frozen Pass 4616 intertwiner.

Pass 4625: one unlabeled 45×40 matrix reconstructs all three carriers. Let T be the center-quad eight-point support incidence. Its exact integer Smith form is

$$\boxed{\mathrm{SNF}(T) = 1^{15}\, 2^{10}\, 0^{15}},$$

so $\mathrm{rank}_{\mathbb{Q}}\, T = 25$, every odd-characteristic rank is 25, and only characteristic two drops to 15. Row intersections reconstruct $\mathrm{SRG}(45, 32, 22, 24)$ through $TT^T = 8I + 2A_{45}$; column co-occurrences reconstruct the point-side W33 graph through $T^T T = 8I + 2A_{\mathrm{point}} + J$. Over $\mathbb{F}_2$, $\ker T$ is the $[40, 25, 4]$ context code; its exactly 40 minimum words are the W33 lines, and their intersection graph reconstructs the inequivalent line-side W33 carrier. Thus the single incidence object intrinsically contains the E6 45, W33 points, and W33 lines.

Pass 4626: the outer nonsplitting is one explicit descent bit. Choose a PSp splitting $Q_{12} = U \oplus W$ with U the unique outer-stable six-space. Every inner generator is block diagonal, whereas the W33 outer involution is

$$\begin{pmatrix} A & B \\ 0 & D \end{pmatrix}, \qquad \mathrm{rank}\, B = 6.$$

Direct intertwiner equations give $\dim_{\mathbb{F}_2} \mathrm{Hom}_{PSp}(W, U) = 1$. The two PSp-equivariant complements therefore form an $\mathbb{F}_2$ torsor and the outer involution exchanges them. The obstruction restricts to zero on PSp and is the nonzero affine C_2 cocycle on this one-dimensional complement torsor. This computes the descent class in the already split inner problem; it is not asserted to be a complete computation of $\mathrm{Ext}^1_{PGSp}(U_6, U_6)$.

Pass 4627: the Hermitian rank problem is exactly a two-saturation theorem. For $Q^-(5, q) = GQ(q, q^2)$ with point-line incidence N, the point graph has nontrivial eigenvalues $q - 1$ and $-(q^2 + 1)$, the latter with multiplicity $q(q^2 - q + 1)$. Since

$$NN^T = (q^2 + 1)I + A_{\mathrm{point}},$$

the rational kernel is exactly the negative eigenspace and therefore

$$\boxed{\mathrm{rank}_{\mathbb{Q}}\, N = q^4 + q^2 + 1}.$$

For odd q, the still-open binary formula is now equivalent to saying that modulo two introduces no extra rank loss: all nonzero Smith invariant factors are odd, or equivalently the integral incidence image is 2-saturated. The $q = 3, 5, 7$ cases satisfy this exactly; no all-q proof is claimed.

Pass 4628: the noncanonical $\mathbb{F}_4$ choice in the Golay bridge is the W33 point carrier. On the outer-stable U_6, compatible unoriented $\mathbb{F}_4$ structures are pairs $\{J, J^2\}$ with $J^2 + J + I = 0$. The actual $PGSp$ action contains 80 oriented J, hence 40 such structures. For a representative,

$$|C_{PGSp}(J)| = 648, \qquad |N_{PGSp}(\langle J \rangle)| = 1296.$$

That normalizer fixes exactly one W33 point and no W33 line, proving by an explicit stabilizer-fixed-point orbit map that the 40 compatible $\mathbb{F}_4$ structures are exactly the point-side W33 G-set. Thus W33 points parameterize the extra choice used in Pass 4592 before the hexacode $[18, 6, 8]$ and frozen Pass 4615 MOG-sextet completion. The Golay coordinate embedding itself is not $PGSp$-equivariant.

Pass 4629 (outside the box): the three-spread lift is a genuine outer S_3 fiber. The PSp support stabilizer has order 576 and quotient C_3 over the common H_{192}. Adjoining the outer similitude doubles the support stabilizer to 1152. Its induced action on the three maximal partial spreads is all six permutations, with kernel exactly H. Hence

$$\boxed{1 \longrightarrow H_{192} \longrightarrow \widetilde{H}_{1152} \longrightarrow S_3 \longrightarrow 1},$$

and the PSp image is the even subgroup $A_3 = C_3$.

Pass 4630 (outside the box): H_{10} is binary homology, CSS logic, and Smith two-torsion at once. Because $TT^T = 0$ over $\mathbb{F}_2$,

$$\mathbb{F}_2^{45} \xrightarrow{T^T} \mathbb{F}_2^{40} \xrightarrow{T} \mathbb{F}_2^{45}$$

is a complex with middle homology $\ker T / \operatorname{im} T^T = C^\perp / C = H_{10}$. The reduction modulo two of the integral kernel of T is exactly $\operatorname{row}_{\mathbb{F}_2} T$. Therefore the Bockstein $[x] \mapsto [Tx/2]$ identifies H_{10} with the $(\mathbb{Z}/2)^{10}$ torsion supplied by the ten Smith factors 2. Taking $H_X = H_Z = T$ gives the same $[[40, 10, 4]]$ CSS code, with the ten-dimensional middle homology as its logical space.

Pass 4631 (outside the box): the 45×40 matrix is E6 incidence on $\mathbb{F}_4$-choice moduli. Combining Passes 4625 and 4628, the 40 columns of T are the compatible $\mathbb{F}_4$ structures on U_6. Every E6/center-quad row contains eight of them and every structure lies on nine rows. A pair of structures lies together on three rows for exactly the 240 W33-adjacent pairs and on one row for the other 540. Finally the exactly 40 minimum weight-four words of $\ker T$ are minimal even tetrads of $\mathbb{F}_4$ structures and are precisely the W33 lines. Thus both W33 point and line geometry sits inside the finite moduli of hexacode-compatible choices.

> **Evidence boundary.** All positive claims above are exact finite incidence, integral-lattice, representation, code, or group-action statements with executable certificates. The all-odd-q Hermitian binary-rank equality remains open and has only been reduced to 2-saturation. The $\mathbb{F}_4$/Golay bridge identifies a choice space, not an embedding $PGSp(4, 3) \subset M_{24}$, and none of the finite E6, D4, S_3, Bockstein, or CSS structures is promoted to a physical field, particle, spacetime, or anomaly without an independent dynamics theorem.

78 Passes 4640–4647: explicit triality, Schlaefli carriers, spread sheets, and cover holonomy

4640: the degree-27 half-spinor orbit is the Schlaefli carrier. The previously unnamed 27-orbit of maximal totally singular four-spaces is now identified by its actual $\mathrm{PSp}(4,3)$ action rather than by cardinality. A point stabilizer has order 960, with subdegrees

$$1,\ 10,\ 16.$$

The degree-16 orbital is exactly

$$\mathrm{SRG}(27,16,10,8), \qquad \mathrm{spec} = 16^1 \oplus 4^6 \oplus (-2)^{20},$$

so this is the Schlaefli/cubic-surface-line permutation carrier.

4641: explicit split-octonion D_4 triality. Put the protected plus-type quotient into the split-octonion Zorn model over $\mathbf{F}_2$, with norm

$$N(a,b,u,v) = ab + u\cdot v.$$

For every one of the 135 nonzero singular elements x, the left and right annihilators are 16-element maximal totally singular four-spaces. The two annihilator families contain $135+135$ distinct spaces and exhaust all 270 maximal singular generators. After an explicit hyperbolic transport to the W33-derived V_8, the order-three map

$$P(x) \longmapsto L\mathrm{Ann}(x) \longmapsto R\mathrm{Ann}(x) \longmapsto P(x)$$

preserves all three outer-type incidence relations exactly. Independently, the type-preserving centralizer of the embedded $\mathrm{PSp}(4,3)$ is C_3; together with the W33 outer similitude it gives

$$(3 \times \mathrm{PSp}(4,3)){:}2, \qquad |\cdot| = 155520, \qquad N/\mathrm{PSp}(4,3) \cong S_3.$$

The order-three type-cycling triality and this type-preserving normalizer are logically distinct constructions.

4642: the selected 135_6–270_3 incidence has one binary torsion defect. For its incidence matrix $N \in \{0,1\}^{135\times 270}$,

$$\mathrm{rank}_{\mathbf{Q}}\, N = 120, \qquad \mathrm{rank}_{\mathbf{F}_2}\, N = 119,$$

while the Smith nonzero invariants are exactly

$$1^{119},\ 2^1.$$

Thus the one-dimensional binary rank loss is explained by one and only one $\mathbf{Z}/2$ torsion factor; the cokernel is $\mathbf{Z}^{15} \oplus \mathbf{Z}/2$. The $\mathrm{PSp}(4,3)$ point action has a noncommutative rank-9 Schurian coherent configuration with subdegrees $1,1,1,12,12,12,32,32,32$. This pass also corrects the selected-line intersection spectrum to

$$15^1 \oplus 9^{15} \oplus 6^{20} \oplus 3^{60} \oplus 0^{24} \oplus (-3)^{150};$$

the former multiplicity 165 double-counted the 15-dimensional point-gram nullity.

4643 and 4646: three spread sheets and the cubic-line weld. The three degree-36 half-spinor orbits are three genuine $\mathrm{PSp}(4,3)$-equivariant copies of the 36 W33 spreads: a representative stabilizer has order 720 and fixes exactly one spread. The building-centralizer C_3 cycles the three sheets and the outer involution supplies a transposition, realizing S_3 on the sheet fiber. For the degree-27 orbit X and any one sheet Y, the natural relation $|X \cap Y| = 1$ gives a 27×36 matrix R with

$$\mathbf{1}^T R = 16\,\mathbf{1}^T, \qquad R\mathbf{1} = 12\,\mathbf{1}, \qquad \operatorname{rank}_{\mathbf{Q}} R = 21,$$

and exact Gram laws

$$RR^T = 10I + 2A_{27} + 6J, \qquad R^T R = 6I - 2A_{36} + 6J.$$

These are precisely the previously frozen Schlaefli-line/double-six identities. After indexing all three sheets by their unique maps to the same spread carrier,

$$R_1 = R_2 = R_3.$$

Hence the combined coupling is $[R\ R\ R]$: it sees only the symmetric sheet mode and has a 72-dimensional sheet-difference dark sector.

4644: routing falsifier. The selected point graph is a 135-vertex, 12-regular, diameter-3 router with shell profile $(1, 12, 56, 66)$ and vertex/edge connectivity 12. The selected-line graph is a 270-vertex, 15-regular, diameter-3 router with shell profile $(1, 15, 118, 136)$ and vertex/edge connectivity 15. These exact unweighted metrics outperform the Levi flag line graph on diameter and connectivity at larger address count; W33 itself remains the stronger compact 40-address mixer. Optical loss, latency, detector noise, weighted coupler cost, and fault-tolerance remain outside this finite comparison.

4645: flat triality Fourier cycle. For the centered cross-incidence matrices $D_{ij} = 9M_{ij} - J$,

$$D_{ij} D_{ij}^T = 54^2 E_{50}, \qquad D_{PA} D_{AB} = 54 D_{PB}$$

cyclically. Normalizing by 54 gives partial isometries whose three-cycle is exactly the identity projector on the active 50-dimensional constituent. Thus the finite triality connection has trivial three-cycle holonomy; no Berry or optical phase is inferred.

4647: apartment-cover monodromy. The apartment map is the homogeneous six-sheet cover

$$G/K \longrightarrow G/H, \qquad |G| = 25920, \quad |K| = 16, \quad |H| = 96,$$

from 1620 apartments to 270 selected singular lines. The local monodromy image on the six sheets is the dihedral group D_{12} of order 12, with order census $1^1 2^7 3^2 6^2$. The natural 3×2 block system records the three singular points of the selected line and the two apartment lifts over each point-line flag. Its quotient is S_3, while the kernel is the central C_2 half-turn, acting fixed-point-freely by swapping the two lifts in every block.

Evidence boundary. All statements in this section are finite incidence, group-action, integral linear-algebra, graph-routing, or cover-monodromy results. Equal dimensions are never used as identifications without an explicit action or intertwiner. No particle-generation, physical-spinor, optical-phase, or laboratory-performance claim follows from these finite theorems alone.

78.1 Triality closure, dark sheet modules, and internal Schlaefli reconstruction

The three degree-36 half-spinor sheets of Pass 4643 become literally identical copies of the same W33 spread carrier in the canonical spread chart. Writing $R \in \{0,1\}^{27\times 36}$ for the Schlaefli-line/double-six incidence map, the three-sheet coupling is therefore

$$\mathcal{R} = [R\ R\ R].$$

Its sheet-difference kernel is not merely a 72-dimensional count. Over characteristic zero it is exactly

$$\mathrm{Std}_2(S_3) \otimes \mathbb{Q}[36],$$

and since the spread permutation module restricts to $PSp(4,3)$ as $1 \oplus 20 \oplus 15$, the dark sector restricts as

$$2(1 \oplus 20 \oplus 15).$$

The remaining bright kernel is the 15 killed by R, so

$$\ker \mathcal{R} \downarrow_{PSp(4,3)} \cong 1^2 \oplus 20^2 \oplus 15^3, \qquad \dim \ker \mathcal{R} = 87.$$

On the dark factor a sheet 3-cycle has minimal polynomial $x^2 + x + 1$; over $\mathbb{C}$ this is $36_\omega \oplus 36_{\omega^2}$. Characteristic three is exceptional: the natural sheet module has the nonsplit filtration

$$0 < T \subset W \subset \mathbb{F}_3^3, \qquad T \cong 1, \quad W/T \cong \mathrm{sgn}, \quad \mathbb{F}_3^3/W \cong 1,$$

because $(1,1,1) \in W = \ker(x_1 + x_2 + x_3)$. Thus the rational bright/dark Fourier projectors $J/3$ and $I - J/3$ do not descend to characteristic three. This is a modular representation obstruction, not a physical generation or phase statement.

Full finite D_4 triality closure. Transporting the W33-derived plus-type V_8 to the split-octonion Zorn model produces an explicit order-three triality

$$P(x) \longmapsto L\mathrm{Ann}(x) \longmapsto R\mathrm{Ann}(x) \longmapsto P(x).$$

The three triality-conjugate embedded copies of $PSp(4,3)$ generate the full type-preserving group

$$\Omega_8^+(2), \qquad |\Omega_8^+(2)| = 174182400.$$

Adjoining the order-three triality gives order 522547200, and adjoining split-octonion conjugation, which inverts triality, gives

$$\Omega_8^+(2) : S_3, \qquad |\Omega_8^+(2) : S_3| = 1045094400.$$

Pairwise triality-conjugate $PSp(4,3)$ copies intersect in order 216; all three intersect in an S_3 of order 6.

The order-216 pairwise intersection fixes pointwise the three nonzero vectors of one anisotropic $\mathbb{F}_2$ two-space. Its $PSp(4,3)$ orbit consists of 40 pairwise disjoint anisotropic two-spaces partitioning all 120 nonsingular vectors as 40×3. Two such planes have either 3 or 9 polar-orthogonal cross-pairs; total cross-orthogonality gives exactly

$$\mathrm{SRG}(40, 12, 2, 4).$$

An action-level stabilizer test decides which W33 carrier this is: the base plane stabilizer has order 648, fixes exactly one W33 point and no W33 line, and the map $gP_0 \mapsto gp_0$ is a well-defined equivariant bijection. Hence this triality-intersection construction reconstructs the W33 *point* carrier, preserving the odd-q point/line inequivalence.

Global apartment-cover factorization. Let K be an apartment stabilizer, H its selected-line stabilizer, and C the core of K in H. The exact subgroup orders are

$$|C| = 8 < |K| = 16 < |N_H(K)| = 32 < |H| = 96.$$

Since $H/C \cong D_{12}$ and K/C is a reflection, its normalizer in D_{12} is V_4. Therefore the six-sheet apartment cover factors globally as

$$1620 \text{ apartments} \xrightarrow[\text{deck } C_2]{2:1} 810 \text{ selected point–line flags} \xrightarrow[\text{monodromy } S_3]{3:1} 270 \text{ selected lines.}$$

The central half-turn is a genuine global deck involution of the first stage. No nonzero cohomology class is asserted without first specifying a connected base graph or complex.

The selected incidence geometry contains its own spread and cubic-surface carriers. For the selected 135_6–270_3 incidence matrix N, the binary left relation code is exactly

$$C = \ker_{\mathbb{F}_2}(N^T) = [135, 16, 30]_2.$$

Its full 2^{16}-word census has exactly 36 minimum words. Every pair of minimum supports meets in 6 coordinates, each of the 135 coordinates lies in 8 minimum supports, and a minimum-word stabilizer has order 720 and fixes exactly one W33 spread. Hence the 36 minimum words are equivariantly the W33 spread carrier.

Now compare the 27-orbit of maximal singular generators with these 36 minimum supports. Removing zero, each generator has 15 singular points and each minimum support has 30. Exhaustively,

$$|G \cap c| \in \{0, 6\}, \qquad 0^{432},\ 6^{540}.$$

Declare incidence when $|G \cap c| = 0$. The resulting 27×36 matrix has row degree 16, column degree 12, rational rank 21, and satisfies

$$RR^T = 10I + 2A_{27} + 6J, \qquad R^T R = 6I - 2A_{36} + 6J,$$

$$3A_{27}R + RA_{36} = 20J,$$

where

$$A_{27} = \mathrm{SRG}(27, 10, 1, 5), \qquad A_{36} = \mathrm{SRG}(36, 15, 6, 6).$$

Thus the selected geometry internally reconstructs the complete Schlaefli-line/double-six incidence carrier from its own maximal singular objects and binary code, without importing classical labels.

The point and line graph critical-group orders are additionally

$$|K_{135}| = 2^{150}3^{166}5^{23}, \qquad |K_{270}| = 2^{284}3^{436}5^{23},$$

with $(2, 3, 5)$-ranks $(62, 74, 23)$ and $(164, 164, 23)$ respectively.

Weighted routing is a Pareto frontier. For a common per-hop power transmission $0 < \eta < 1$, the exact distance-shell profiles give the strict mean destination-delivery hierarchy

$$W33 > 135\text{-router} > 270\text{-router} > 160\text{-flag router}.$$

Conversely, the 270-router has strictly larger aggregate delivered-destination score than each of the other three for every $0 < \eta \leq 1$. Therefore no architecture is a scalar winner before a workload objective is specified: W33 is the compact loss/latency optimum per destination, whereas the 270-router is the aggregate-address-throughput/connectivity extreme. The component-loss examples used in the associated executable witness deliberately mix published component platforms and are sensitivity anchors only, not a measured integrated Holonet stack.

Evidence firewall. Passes 4648–4655 are finite group, module, incidence, coding, critical-group, cover, and symbolic routing theorems with executable witnesses. The words "triality", "octonion", "Schlaefli", "spread", and "Holonet" here do not by themselves identify particles, generations, optical phases, or hardware performance.

Current paired-axis frontier: homology, Golay stabilizers, and exact glue

The equal-dimensional periodic homologies are not the W33 point modules. Let $R \in \mathbb{F}_2^{27\times 36}$ be the cubic-line/double-six incidence matrix of Pass 4575, so $RR^{\mathsf{T}} = R^{\mathsf{T}}R = 0$ and $\operatorname{rank}_2 R = 6$. The two periodic homologies have dimensions

$$H_{36} = \ker R/\operatorname{im} R^{\mathsf{T}}, \quad \dim H_{36} = 24, \qquad H_{27} = \ker R^{\mathsf{T}}/\operatorname{im} R, \quad \dim H_{27} = 15.$$

Pass 4632 compares them with the point-side 40-object W33 module produced by the compatible-$\mathbb{F}_4$ structures of Pass 4628. Its adjacency matrix has $\operatorname{rank}_2 A = 16$, hence comparison layers

$$Q_{24} = \mathbb{F}_2^{40}/\operatorname{row}(A), \qquad Q_{15} = \operatorname{row}(A)/\langle \mathbf{1}\rangle.$$

The full equivariance equations give one-dimensional Hom spaces in all four directions, but the unique nonzero maps have ranks

$$H_{36} \to Q_{24} : 9, \qquad Q_{24} \to H_{36} : 1,$$

$$H_{27} \to Q_{15} : 14, \qquad Q_{15} \to H_{27} : 1.$$

Thus neither equal-dimensional pair is isomorphic. The shared dimensions encode nontrivial subquotient relationships, not an identification.

Corrected Golay sextet and its exact M_{24} stabilizers. Pass 4633 re-executes the Pass 4615 720-matching search and repairs a stale frozen certificate. The unique zero-coordinate assignment is

$$(21, 20, 19, 18, 22, 17),$$

producing tetrads

$$02721,\ 161620,\ 341319,\ 581823,\ 9\,11\,14\,22,\ 10\,12\,15\,17$$

(where the compressed notation only lists coordinate labels). Conjugating the standard 24-point M_{24} generators into the repository Golay coordinates and applying Schreier orbit–stabilizer gives

$$|M_{24}| = 244823040, \qquad |\mathcal{O}_{\text{sextet}}| = 1771, \qquad |H_{\text{sextet}}| = 138240.$$

The action on the six tetrads has image S_6 and kernel 192. The actual six-zero-coordinate transversal has orbit 64 inside the sextet; its stabilizer K has

$$|K| = 2160.$$

It acts faithfully and transitively on the 18 active coordinates and on the 45 section octads. Its orbits on the 64 section codewords have sizes

$$1 + 18 + 45.$$

The exact labelled apartment enumerator now reaches support eleven. Pass 4634 evaluates every

$$\binom{40}{11} = 2311801440$$

eleven-row coefficient subset by a native XOR/popcount census. The support-11 shell contains 153 distinct weights, from

$$614 \quad (12960 \text{ words})$$

to

$$1026 \quad (1080 \text{ words}).$$

Together with Pass 4593, complete labelled support spectra are therefore exact through support 11. Supports 12–20, and hence the complete 2^{39} numerical enumerator, remain open.

A six-species local criterion explains the exceptional C_8 collision. Pass 4635 classifies every length-eight nonbacktracking walk contributing to a four-line primitive-C_8 coefficient. Apartments admit exactly four line-multiplicity species

$$1111|22, \qquad 1115|, \qquad 1133|, \qquad 1111|4,$$

while $K_{1,3}$ supports admit only

$$1111|22, \qquad 1113|2.$$

The primitive coefficient is one eighth of the total raw mass, so collision occurs exactly when the four apartment masses equal the two star masses. In $GQ(2,2)$,

$$224 + 64 = 96 + 192 = 288,$$

explaining the $36 = 36$ collision as cancellation between different walk species. In $GQ(2,4)$ the masses give 60 versus 36; in W33 they give 712 versus 180. Closed arbitrary-(s,t) formulas for the six masses remain open.

Construction A reaches A_1^{24} before Leech. For

$$L(C) = \frac{1}{\sqrt{2}}\{x \in \mathbb{Z}^{24} : x \bmod 2 \in C\},$$

Pass 4636 finds

$$\det L(C_6) = 2^{12} = 4096, \qquad \det L(G_{24}) = 1, \qquad [L(G_{24}) : L(C_6)] = 64.$$

The 64 quotient words of G_{24}/C_6 are exactly the glue cosets. Both lattices contain the 48 coordinate roots $\pm\sqrt{2}e_i$, so the immediate unimodular endpoint is the rooted A_1^{24} Niemeier lattice, not rootless Leech. A further neighbor/shift (holy-construction) step is required.

Outside-box closure I: the 64 sextet transversals are the 64 section codewords. Under K, the orbit of the chosen sextet transversals and the section codewords both split as $1 + 18 + 45$. Pass 4637 proves more: stabilizer-fixed-point tests leave exactly one equivariant bijection on the 18-orbits and exactly one on the 45-orbits, with the chosen zero transversal forced to the zero word. Transporting XOR therefore gives this 64-transversal orbit an $\mathbb{F}_2^6$ affine structure relative to the chosen section.

Outside-box closure II: Golay glue is the six-tetrad permutation module. Pass 4638 computes the K-action on G_{24}/C_6. Its image has order 720 and kernel 3, exactly as on the six tetrads. The intertwiner space between the two six-dimensional binary modules has dimension two; its three nonzero maps have ranks

$$1, 6, 6.$$

Hence two explicit full-rank intertwiners identify the 64 lattice glue cosets with the binary permutation geometry of the six tetrads, while the rank-one sum records the residual ambiguity.

Outside-box closure III: characteristic-two differential cancellation. On all 63 nonzero vectors of the natural six-space, split the polar matrix into the cross-shell differential D_0 and within-shell differential Δ. Both satisfy

$$D_0^2 = \Delta^2 = 0, \qquad \operatorname{rank} D_0 = \operatorname{rank} \Delta = 12,$$

and they have the same 12-dimensional image. Their sum is the full polar matrix D, but in characteristic two

$$\operatorname{rank}(D_0 + \Delta) = 6.$$

Thus homology jumps from

$$63 - 2 \cdot 12 = 39$$

to

$$63 - 2 \cdot 6 = 51.$$

The row code of D is the $[63, 6, 32]$ simplex code, giving the fused CSS code

$$\boxed{[[63, 51, 3]]}.$$

Evidence boundary. All statements in this insert are finite code, group, graph, module, or lattice statements with executable witnesses and frozen certificates. Equal dimensions are not treated as module identifications; the stale Pass 4615 sextet certificate is explicitly repaired; the full apartment enumerator is still open beyond support 11; the six C_8 signature masses do not yet have closed all-(s, t) formulas; and the paired-axis Construction-A lattice is explicitly *not* the Leech lattice.

Passes 4656–4663: cover cohomology, code closure, internal E_6, and routing structure

A nonzero apartment deck class. Choose the labelled Schreier graph on the 810 selected point–line flags for the five deterministic $PSp(4, 3)$ transvections used throughout the reconstruction. It has 4050 labelled edges and first Betti number $4050 - 810 + 1 = 3241$. Its 1620-apartment lift is connected. With the lexicographically sorted local section the $\mathbb{F}_2$ voltage cochain has 636 one-edges, and an explicit length-six closed base word

$$g_3 g_0^{-1} g_1 g_2^{-1} g_4 g_3^{-1}$$

lifts from one apartment sheet to the other. Hence the regular C_2 cover of Pass 4650 represents a nonzero class in H^1 of this canonical Schreier graph.

The order-216 triality intersection. The W33 point stabilizer has derived-series orders

$$648, 216, 54, 27, 3, 1.$$

The order-27 term is extraspecial of exponent three. Modulo it, the order-216 derived subgroup has quotient Q_8, whereas the full order-648 point stabilizer has quotient $SL(2,3) = 2A_4$. Combining this with the Passes 4649 and 4654 action-level identification gives

$$G_0 \cap G_1 \cong 3^{1+2}{:}Q_8, \qquad 3^{1+2}{:}Q_8 < 3^{1+2}{:}2A_4 < PSp(4,3).$$

The selected binary code closes on its dual and full symmetry. For $C = \ker_{\mathbb{F}_2}(N^T) = [135, 16, 30]_2$, MacWilliams gives

$$C^\perp = [135, 119, 3]_2,$$

with exactly 270 weight-three words. Since $C^\perp = \mathrm{row}(N^T)$, these are precisely the 270 selected lines: the code reconstructs its own 135_6–270_3 geometry. A code-intrinsic joint-Jacobi relation on the 36 minimum words splits their 630 pairs as $270 + 360$; the 270 relation is the spread/double-six $\mathrm{SRG}(36, 15, 6, 6)$. Distinct coordinate signatures make this action faithful, so the independently certified graph automorphism order 51840 is an upper bound for $\mathrm{Aut}(C)$. The explicit $PGSp(4,3)$ outer similitude preserves the selected triples and supplies the matching lower bound:

$$\mathrm{Aut}(C) = PGSp(4,3), \qquad |\mathrm{Aut}(C)| = 51840.$$

Internal 27–36–45 cubic-surface closure. The 27 maximal singular generators and 36 code minima reproduce the zero-intersection matrix R of rank 21. The recovered meeting graph on the 27 has exactly 45 triangles, five through each line. If T is line–triangle incidence and D is triangle–double-six disjointness, then every triangle/double-six intersection contains zero or two lines, with census $0^{540}2^{1080}$, and

$$T^T R = 2(J - D).$$

The triangle stabilizer has order 576 and fixes exactly one protected 16-line support; hence this internal 45 is $PSp(4,3)$-equivariantly the protected center-quad/E_6 tritangent carrier.

Topology-aware router. Exact fractional all-shortest-path flow separates the 2025 edges of the selected 270-router into 1620 edges of load $38.377\ldots$ and 405 edges of load $66.155\ldots$. The 405 high-load edges are exactly 27 disjoint Petersen graphs, one on the ten selected lines contained in each internal 27-carrier object. Deleting the entire Petersen shortcut orbit leaves a connected 12-regular graph of diameter four and edge-connectivity 12. Component-mixed photonic sensitivity calculations retain the earlier Pareto conclusion; they do not constitute measured Holonet performance.

Three outside-box closures. First, the 1120 anisotropic binary two-planes split under $PSp(4,3)$ as $40 + 1080$. The 40-orbit partitions the 120 nonsingular vectors into 40×3 and carries a four-class association scheme of valencies

$$1, 2, 36, 27, 54$$

whose complete intersection tensor equals the historical 120-selector algebra. The actions are nevertheless inequivalent: the new quotient is W33 points, while the historical selector quotient is W33 lines.

Second, the code alone reconstructs the protected 45. Its intrinsic 36-vertex Jacobi graph has 135 maximal K_4's; their anticompleteness graph is exactly $45C_3$. The three K_4's in each component unite to a 12-subset of the 36 carrier, and the resulting 45-object orbit has stabilizer 576 and is equivariantly the protected/E_6 tritangent 45.

Third, the apartment duo bit does *not* descend to a 36-spread signing. An apartment stabilizer of order 16 fixes no spread. Its spread-stabilizer intersection orders have profile $1^{16}4^{16}8^4$; transporting the four order-eight cases yields a deck-blind incidence

$$135_4\text{–}36_{15},$$

rowwise disjoint from the code-minimum incidence 135_8–36_{30}. Thus the proposed binary spread signing fails closed rather than being promoted from numerology.

Evidence boundary. Every statement above is an exact finite group, graph, code, incidence, or graph-cover calculation. The routing numbers use explicitly stated component-mixed sensitivity assumptions. No particle, generation, gauge-field, optical-phase, or measured-hardware identification is inferred.

79 Passes 4664–4671: transverse triality symmetries and the integral protected incidence

4664: the two three-sheet symmetries are transverse, not identical. The S_3 acting on the three maximal-partial-spread lifts over one protected 45-object and the S_3 acting on the three global degree-36 D4 spread sheets have different ambient order-three directions. The packet rotation C_3^{pkt} lies inside $\mathrm{PSp}(4,3)$, while the sheet rotation C_3^{sh} is the type-preserving centralizer C_3 outside the distinguished $\mathrm{PSp}(4,3)$. Hence they cannot be identified by an automorphism preserving that subgroup. They commute and intersect trivially. A common outer reflection inverts both, giving the joint finite symmetry

$$(C_3^{\mathrm{pkt}} \times C_3^{\mathrm{sh}}){:}C_2, \qquad |\cdot| = 18.$$

Their abstract three-point permutation representations are isomorphic, but their ambient actions are transverse.

4665: the full automorphism group of the 45×40 incidence. Let T be the center-quad/sentinel incidence of Pass 4625. Its two bipartite parts have sizes $45, 40$ and degrees $8, 9$, so they cannot be interchanged. Column co-occurrence intrinsically reconstructs the point-side W33 graph, whose 40 maximal K_4 cliques reconstruct the W33 lines and therefore the full $W(3,3)$ incidence geometry. Thus every automorphism of T injects into $\mathrm{Aut}(W(3,3))$. Conversely projective symplectic similitudes preserve both W33 and the complete 45-row center-quad/sentinel shell. Since $\mathbf{F}_3$ has no nontrivial field automorphism,

$$\boxed{\mathrm{Aut}(T) = \mathrm{PGSp}(4,3), \qquad |\mathrm{Aut}(T)| = 51840.}$$

Thus one 85-vertex bipartite incidence packages the E6/center-quad 45 and both inequivalent W33 point/line carriers under their complete common automorphism group.

4666: the Hermitian binary-rank problem is a 2-adic eigenlattice problem. For $Q^-(5,q) = GQ(q,q^2)$ let N be the integral point-line incidence matrix, $L = \mathrm{im}_{\mathbf{Z}}\, N$, and $K = \ker_{\mathbf{Z}}\, N^T$. The kernel K is primitive and

$$NN^T = (q^2+1)I + A_{\mathrm{point}}, \qquad K = \ker_{\mathbf{Z}}(NN^T),$$

so K is exactly the integral $-(q^2+1)$ eigenlattice of the point graph. Since $L_{\mathbf{Q}} = K_{\mathbf{Q}}^{\perp}$,

$$L_{\mathrm{sat}} = (L \otimes \mathbf{Q}) \cap \mathbf{Z}^v = K_{\mathbf{Z}}^{\perp}.$$

Therefore the all-odd-q binary rank conjecture is precisely

$$\boxed{L \otimes \mathbf{Z}_2 = K_{\mathbf{Z}}^{\perp} \otimes \mathbf{Z}_2.}$$

Equivalently the finite saturation quotient $K^{\perp}/L$ has no 2-primary part, or every nonzero Smith factor of N is odd. The exact $q = 3, 5, 7$ anchors satisfy this equality. The general 2-adic equality remains open.

4667: the selected one-bit Smith defect pins the head and socle of H_{10}. The selected 135×270 incidence has one $\mathbf{Z}/2$ Smith torsion factor, hence a one-dimensional trivial $\mathbf{F}_2\mathrm{PSp}(4,3)$ module. The protected module has canonical filtration

$$0 < \langle j \rangle < V_9 = \ker \pi < H_{10}, \qquad 1 \mid 8 \mid 1.$$

There is therefore one nonzero equivariant injection of the selected bit into H_{10} and one nonzero quotient back out:

$$i(1) = j, \qquad \pi : H_{10} \to \mathbf{F}_2.$$

Since $\pi(j) = 0$, their composition vanishes. Equivalently

$$n = i\pi, \qquad n(x) = \pi(x)j, \qquad n^2 = 0,$$

with rank one, image $\langle j \rangle$, and kernel V_9. The selected Smith bit therefore detects the trivial head/socle layers but no direction in the irreducible eight-dimensional middle factor.

4668: the hexacode $\mathbf{F}_4$ choice is a D4 triality-plane modulus. Pass 4628 identifies the 40 compatible unoriented structures $\{J, J^2\}$ on U_6 with W33 points. Pass 4654 independently identifies the 40 anisotropic 2-planes fixed by pairwise triality-conjugate $\mathrm{PSp}(4,3)$ intersections with the same W33 point carrier. Composing the two frozen charts gives an explicit equivariant bijection

$$\{J, J^2\} \longmapsto p(J) \longmapsto P(p(J)).$$

The stabilizer tower is

$$216 < 648 < 1296,$$

for pointwise triality-plane intersection, PSp point/plane stabilizer, and full semilinear F4 normalizer respectively. Thus the noncanonical F4 choice feeding the hexacode/Golay construction has a concrete D4-side moduli realization.

4669: oriented moduli form an 80-to-40 double cover. There are 80 oriented operators J above the 40 pairs $\{J, J^2\}$. On the triality side, the $648/216 \cong C_3$ quotient gives a cyclic orientation of the three nonzero vectors of each anisotropic plane, and the full outer involution reverses that orientation. Hence both descriptions possess the same $80 \to 40$ orientation cover. An equivariant oriented identification is unique after one base orientation is chosen; the other choice is simultaneous global reversal.

4670: the D4-selected lane reconstructs T, H_{10}, and the CSS code. The selected 135_6–270_3 geometry internally reconstructs the 45 cubic tritangents, with an action-level map to the protected 45. Triality-conjugate subgroup intersections reconstruct the 40 W33-point/F4 moduli. Transporting the cross relation along these two maps recovers the same 45×40 matrix T. Consequently the D4-derived carriers recover

$$\mathrm{SNF}(T) = 1^{15}2^{10}0^{15}, \qquad H_{10} \cong \mathrm{Tor}_2(\mathrm{coker}\, T), \qquad [[40, 10, 4]].$$

This is a commuting finite-incidence reconstruction, not an implementation claim.

4671: the local F4/triality stabilizer has an exact S_3 quotient. The subgroup classification gives

$$(3^{1+2}{:}Q_8)_{216} < (3^{1+2}{:}SL(2,3))_{648} < H_{1296}.$$

The first group is the pairwise triality-conjugate PSp intersection and fixes the three nonzero plane vectors pointwise. The quotient $648/216 = C_3 = A_3$ rotates them cyclically. The full semilinear layer adds the orientation-reversing outer involution, so

$$\boxed{1 \to (3^{1+2}{:}Q_8)_{216} \to H_{1296} \to S_3 \to 1,}$$

with the 648 subgroup the preimage of A_3.

Evidence boundary. All closed statements above are finite group, incidence, module, code, or integral lattice theorems. The general odd-q Hermitian 2-saturation statement in Pass 4666 remains open. The oriented double cover requires one global orientation choice. No M24 subgroup, physical chirality, family symmetry, or dynamical interpretation follows from these finite structures alone.

Passes 4681–4688: dual-shell reconstruction, complementary incidence algebra, and the Petersen routing bundle

This block continues the selected 135_6–270_3 geometry and its binary code while preserving a strict finite-evidence boundary. All identifications below are explicit code, incidence, graph, group-action, graph-cover, or parameterized-routing statements.

The dual weight-132 shell is the protected 45. For the selected code $C = [135, 16, 30]_2$, the dual $C^\perp = [135, 119, 3]_2$ has exactly 45 words of weight 132. Their three-coordinate complements are pairwise disjoint and partition the 135 coordinates as

$$135 = 45 \cdot 3.$$

These 45 triples are literally the singular-fibre triples attached to the previously certified protected 16-line supports. They form one $PSp(4,3)$ orbit with stabilizer 576, and one $PGSp(4,3)$ orbit with

stabilizer 1152. Projecting the 270 dual weight-three selected lines through these packets gives 270 distinct triples on the 45 packets. Every occurring packet pair occurs three times, and the packet-pair graph is

$$\mathrm{SRG}(45, 12, 3, 3),$$

the complement of the protected $\mathrm{SRG}(45, 32, 22, 24)$.

The complementary 135×36 incidences close an exact algebra. Let Q be the Pass-4663 incidence 135_4–36_{15} and let M be the code-minimum/spread incidence 135_8–36_{30}. Their rows are disjoint, both have rational rank 36, and their combined rational column space still has dimension 36. If A is the spread/double-six graph $\mathrm{SRG}(36, 15, 6, 6)$, then

$$Q^T Q = 15I + 3A, \qquad M^T M = 24I + 6J,$$
$$Q^T M = M^T Q = 6(J - I - A),$$

and therefore

$$(Q + M)^T (Q + M) = 9(3I + 2J - A).$$

Thus $Q+M$ has rank 21 and annihilates exactly the 15-dimensional $+3$ eigenspace of A. Its nonzero Smith factors are $1^{14}3^7$. Individually,

$$\mathrm{SNF}(Q)_{\neq 0} = 1^{29}2^6 4, \qquad \mathrm{SNF}(M)_{\neq 0} = 1^{15}2^{14}4^6 8.$$

On the 135 side the Gram operators generate a commutative four-dimensional algebra with joint multiplicities $1, 15, 20, 99$ and exact relation

$$MM^T = 2QQ^T + QM^T.$$

The apartment cohomology class has only a C_2 presentation normalizer. The nonzero Pass-4656 deck class lives in the first cohomology of a particular five-factor labelled Schreier multigraph. The natural normalizer of those five cyclic transvection factors is trivial inside $PSp(4, 3)$ and has order two inside $PGSp(4, 3)$. The nonidentity normalizer element lies in the outer coset, lifts to the apartment cover, and therefore fixes the deck class. Full $PSp(4, 3)$ does not preserve this frozen labelled base. Consequently a PSp orbit or PSp submodule generated by this class inside that fixed 3241-dimensional H^1 is not defined. An equivariant module question requires a different, PSp-invariant base complex.

The selected-270 edge split is a homogeneous bundle over the Schlaefli 27. The 405 Petersen shortcut edges form one $PSp(4, 3)$ orbit with stabilizer 64 and map 15-to-1 onto the 27 internal Schlaefli objects, whose stabilizer has order 960. The 1620 base edges form one orbit with stabilizer 16 and map 12-to-1 onto the 135 edges of $\mathrm{SRG}(27, 10, 1, 5)$, whose edge stabilizer has order 192. Hence there are exact homogeneous quotient maps

$$G/H_{64} \longrightarrow G/H_{960}, \qquad G/H_{16} \longrightarrow G/H_{192}.$$

The 27-vertex quotient module has rational spectral dimensions $1 + 20 + 6$. Locally the order-960 component stabilizer acts on the ten Petersen vertices through A_5 with kernel 16; its edge stabilizer image is V_4. Under $PGSp(4, 3)$ the component stabilizer doubles to 1920, the local image becomes S_5, and the edge stabilizer image becomes D_8. Thus the shortcut module is literally induced from the local Petersen-edge action:

$$\mathbb{Q}[405] = \mathrm{Ind}_{H_{960}}^{PSp} \mathbb{Q}[A_5/V_4] = \mathbb{Q}[PSp/H_{64}],$$

with the analogous S_5/D_8 statement for $PGSp$.

Mixed base/shortcut technologies have exact routing breakpoints. Write $c_b > 0$ and $c_s > 0$ for arbitrary scalar costs assigned to base and shortcut edges and set $r = c_s/c_b$. Exact all-pairs two-objective path enumeration gives only four policies, separated by

$$r = 1, \qquad r = \frac{3}{2}, \qquad r = 2.$$

The per-source (base traversals, shortcut traversals) totals are

$$(420, 239),\ (548, 111),\ (620, 63),\ (746, 0)$$

in the four consecutive regions. The same breakpoints apply to independent-edge reliability after $c = -\log q$. A component-mixed sensitivity example places a four-stage degree-12 MZI fabric on base edges and a two-stage degree-3 EO fabric on the Petersen shortcuts. Under those explicit assumptions the loss ratio lies in $1 < r < 3/2$ while the latency ratio lies in $r < 1$, so the mixed and shortcut-favoring policies are the two Pareto choices. These component numbers come from separate demonstrations and are not a measured integrated Holonet stack.

Two fail-closed outside-box tests. The 45 weight-132 complement triples alone form nothing more than 45 disjoint three-sets. Their full hypergraph automorphism group is

$$S_3 \wr S_{45} = S_3^{45} : S_{45},$$

so that shell alone cannot select the protected $PGSp$ action. Adding the dual weight-three shell yields the 270 packet triples and reduces the full automorphism group to $PGSp(4, 3)$ of order 51840.

Likewise, the nonzero apartment voltage does not directly sign either selected-270 routing-edge orbit. Every one of its 4050 labelled Schreier edges projects to a pair of selected lines at graph distance three. The projection has 1275 distinct distance-three pairs, with multiplicity profile $3^{1200}6^{75}$, and has zero intersection with both the 1620 base edges and the 405 Petersen shortcuts. Any routing signing therefore requires an additional choice of a length-three path/transgression; no canonical hot/cold bias follows directly from the deck class.

Evidence boundary. These results certify finite code shells, incidence algebras, group actions, graph-cover scope, homogeneous permutation modules, and parameterized routing. They do not identify particle generations, gauge fields, optical phases, or measured device performance.

Affine Golay, Leech neighbor, and support-twelve apartment closure

Pass 4697: the three dimension-39 carriers. For the cross-shell differential

$$D_0 = \begin{pmatrix} 0 & R \\ R^{\mathsf{T}} & 0 \end{pmatrix}$$

the homology splits canonically as

$$H_{\mathrm{cross}} \cong H_{27} \oplus H_{36}, \qquad 15 + 24 = 39.$$

The rank-39 apartment code, however, is the permutation quotient

$$C_{\mathrm{ap}} \cong \mathbb{F}_2^{40}/\langle \mathbf{1} \rangle.$$

Exact $\mathrm{PSp}(4,3)$ equivariance gives two-dimensional Hom spaces in both directions. The three nonzero maps $H_{\mathrm{cross}} \to C_{\mathrm{ap}}$ all have rank 14, while the three nonzero maps in the reverse direction all have rank 1. Hence the periodic direct sum and cross-shell homology are the same module, but the apartment code is not.

Pass 4698: the corrected Golay sextet stabilizer is internally affine. Inside the order-138240 sextet stabilizer H, the kernel of the six-tetrad action has order 192 and element-order census

$$1^1\,2^{63}\,3^{128}.$$

Identity plus the 63 involutions form a normal elementary abelian subgroup

$$N \cong C_2^6,$$

which acts regularly on the 64 sextet transversals. If K is the stabilizer of the chosen zero transversal, then

$$|K| = 2160, \qquad N \cap K = 1, \qquad H = N \rtimes K.$$

The action $K \to S_6$ on the tetrads has kernel C_3, and the two nonzero K-orbits on N have sizes 18 and 45. This internally recovers the affine structure conventionally denoted $2^6{:}3.S_6$.

Pass 4699: an explicit A_1^{24}-to-Leech two-neighbor. Let

$$N_{A_1^{24}} = \frac{1}{\sqrt{2}}\{x \in \mathbb{Z}^{24} : x \bmod 2 \in G_{24}\}$$

and choose one corrected-sextet coordinate i. For

$$v_i = \frac{1}{\sqrt{2}}(1,\dots,1,\underset{i}{3},1,\dots,1), \qquad v_i^2 = 16,$$

define

$$M_i = \{x \in N_{A_1^{24}} : (x, v_i) \equiv 0 \pmod 2\}, \qquad L_i = M_i + \mathbb{Z}\, v_i/2.$$

A frozen 24-vector basis has integer numerator determinant 2^{36} at scale $1/(2\sqrt{2})$, hence Gram determinant 1; its Gram matrix is integral and even. All 48 coordinate roots of $N_{A_1^{24}}$ have odd pairing with v_i and disappear. Every vector in the new coset has odd numerator in all 24 coordinates and therefore norm at least 3, which evenness strengthens to at least 4; a norm-4 basis vector is exhibited. Thus L_i is the rootless even unimodular 24-lattice, i.e. the Leech lattice. The 24 distinguished-coordinate neighbors form one orbit under the corrected sextet stabilizer.

Pass 4700: the primitive-C_8 masses close only after adding embedding invariants. Put $u = s-1$. For an apartment let ρ count intersecting cross-pairs between its two external-transversal families and let σ count intersecting transversal/single-hit outside-line pairs. For an induced $K_{1,3}$ let τ count outside common transversals to the three leaves. The six Pass 4635 raw masses are

$$A_{1111|22} = 16\big((4u^2+2)\rho + u^2\sigma + (4t-2)u^4 + 2(t-1)\big),$$

$$A_{1115} = 64u(u^3-u^2+2u-1), \quad A_{1133} = 96u^2(u-1)^2,$$

$$A_{1111|4} = 64(u+1)u(u-1)(t-1),$$

$$S_{1111|22} = 48(u+1)u^3, \qquad S_{1113|2} = 48(u+1)u\tau.$$

The primitive coefficient is one eighth of the appropriate raw sum. W33 and its dual have the same order $(3,3)$ but

$$(\rho,\sigma,\tau) = (0,16,1) \quad \text{versus} \quad (4,0,3),$$

and exact apartment/star coefficients

$$(712,180) \quad \text{versus} \quad (728,252).$$

Therefore no formula in (s,t) alone can encode primitive-C_8 apartment tomography for both embeddings.

Pass 4701: the exact apartment-code enumerator reaches support twelve. Let A_w count all support-12 coefficient sets producing codeword weight w, and B_w those containing one fixed coefficient position. Coefficient transitivity gives the exact double count

$$12A_w = 40B_w, \qquad A_w = \frac{10}{3}B_w.$$

Thus only

$$\binom{39}{11} = 1676056044$$

fixed-position subsets need be exhausted. The native XOR/popcount census yields, after exact rescaling,

$$\binom{40}{12} = 5586853480$$

subsets in 151 weight classes. The extremes are

$$608\ (1620), \qquad 990\ (4320).$$

Complete labelled spectra are now exact through support 12; supports 13–20 remain open.

Pass 4702: the Golay affine six-space is not the cubic orthogonal six-space. The faithful six-dimensional K-module carried by the translation subgroup N admits neither a nonzero invariant quadratic form nor a nonzero invariant bilinear form: both full invariance systems have nullity zero. Hence it cannot be identified with the cubic $O_6^-(2)$ module merely because both are six-dimensional.

Pass 4703: all support-12 minima are apartment corner-star thickenings. For an apartment A, let $\mathcal{T}(A)$ consist of all W33 lines through the four corner points of A. Since there are two additional lines at each corner,

$$|\mathcal{T}(A)| = 4 + 4 \cdot 2 = 12.$$

All 1620 thickenings are distinct and have apartment-code weight 608. Pass 4701 proves there are exactly 1620 support-12 minima, so these are all of them. Each thickening contains eleven apartments; exactly one has overlap profile $\{0{:}2, 2{:}8\}$ against the other ten, providing an intrinsic inverse $\mathcal{T}(A) \mapsto A$.

Pass 4704: the thickening shell generates the even apartment subcode and recovers the edge carrier. The 1620 thickening coefficient masks have weight 12 and rank 39, hence span the full even-weight hyperplane $E_{40} \subset \mathbb{F}_2^{40}$. Because the all-ones kernel also lies in E_{40}, their codeword span is

$$E_{40}/\langle \mathbf{1} \rangle,$$

a 38-dimensional subcode. The exhaustive low-weight apartment certificate gives

$$\boxed{[1620, 38, 270]},$$

with exactly 240 minimum words, the adjacent generator-pair sums corresponding to the 240 W33 edges. Thus

$$1620 \text{ apartment thickenings} \longrightarrow [1620, 38, 270] \longrightarrow 240 \text{ edges}.$$

Evidence boundary. The canonical theorem numbers are Passes 4697–4704; the first implementation files were created under collision aliases 4689–4696 before a parallel namespace conflict surfaced. Equal dimensions are not treated as representation identities. The Leech statement is an explicit lattice two-neighbor with determinant, evenness, rootlessness, and minimum-norm certificates. Primitive-C_8 requires the embedding invariants ρ, σ, τ. The full apartment enumerator remains open beyond support 12.

79.1 Invariant flag cohomology and the dual-shell $GQ(4,2)$ closure

The apartment double cover can be placed over a base carrying the *full* $\mathrm{PSp}(4,3)$ action. On the 810 selected point–line flags, the smallest connected self-paired PSp orbital graph is 16-regular, with 6480 edges, diameter five and

$$b_1 = 6480 - 810 + 1 = 5671.$$

Its equivariant lift to the 1620 apartments is a connected regular C_2 cover, also 16-regular, with exactly two lift edges above each base edge. A base triangle $0 \to 482 \to 367 \to 0$ lifts between the two apartments over flag zero, so the deck class is nonzero. The $\mathrm{PGSp}(4,3)$ outer similitude preserves both base and lift; consequently the deck class spans an honest one-dimensional trivial PGSp submodule of $H^1(-;\mathbb{F}_2)$. This replaces the earlier five-generator Schreier base, for which no full PSp action on the frozen cohomology space existed.

Independently, the selected binary code reconstructs a classical generalized quadrangle without importing the protected-45 labeling. The 45 complements of the dual weight-132 shell partition the 135 selected coordinates into 45×3. Projecting the 270 dual weight-three words to those packets gives 270 triples. Their pair graph is

$$\mathrm{SRG}(45, 12, 3, 3),$$

and its maximal cliques are exactly 27 copies of K_5. Every projected triple is a three-subset of a unique K_5, and each K_5 contributes all $\binom{5}{3} = 10$ triples. Hence the dual shells intrinsically recover $GQ(4,2)$: 45 points, 27 lines, three lines per point and five points per line. The dual line graph is $\mathrm{SRG}(27, 10, 1, 5)$. If H is the 45×270 point–triangle incidence and B the 45×27 point–line incidence, then

$$HH^T = 18I + 3A_{45}, \qquad BB^T = 3I + A_{45},$$

with Smith profiles

$$\mathrm{SNF}(H)_{\neq 0} = 1^{44}3, \qquad \mathrm{SNF}(B)_{\neq 0} = 1^{21}.$$

The reconstructed 27-vertex graph has full automorphism order 51840.

79.2 Exact routing-edge character kernels

The two homogeneous routing-edge carriers admit complete ordinary-character resolution. The 405 Petersen shortcut edges have rank 24 and permutation character

$$1 \oplus 6 \oplus 2(15_L) \oplus 2(20) \oplus 24 \oplus 2(30_C) \oplus 2(\overline{30_C}) \oplus 2(60) \oplus 64.$$

Subtracting the 27-object quotient $1 \oplus 6 \oplus 20$ gives

$$\boxed{378 = 2(15_L) \oplus 20 \oplus 24 \oplus 2(30_C) \oplus 2(\overline{30_C}) \oplus 2(60) \oplus 64.}$$

Locally the Petersen-edge permutation module is $1 \oplus 4 \oplus 5 \oplus 5$ under A_5, so the same kernel is $\mathrm{Ind}_{H_{960}}^{\mathrm{PSp}}(4 \oplus 5 \oplus 5)$.

The 1620 base edges have orbital rank 146. Their 135-edge quotient has character

$$1 \oplus 6 \oplus 2(20) \oplus 24 \oplus 64.$$

The resulting 1485-dimensional fiber kernel is

$$\boxed{\begin{aligned} 1485 = {} & 4(15_L) \oplus 2(20) \oplus 2(24) \oplus 30_R \oplus 4(30_C) \oplus 4(\overline{30_C}) \\ & \oplus 40_C \oplus \overline{40_C} \oplus 45_C \oplus \overline{45_C} \oplus 5(60) \oplus 3(64) \oplus 5(81). \end{aligned}}$$

The independent 12-edge local fiber has image order 96 and complex permutation split $1 \oplus \omega \oplus \bar{\omega} \oplus 3 \oplus 6$, giving the induced-kernel check

$$\mathrm{Ind}_{H_{192}}^{\mathrm{PSp}}(\omega \oplus \bar{\omega} \oplus 3 \oplus 6),$$

with induced dimensions $135 + 135 + 405 + 810 = 1485$.

79.3 The S_3 connection reconstructs the selected geometry

The selected135 graph is a connected three-sheet cover of the $GQ(4,2)$ point graph. Each base edge carries a perfect matching between its two three-point packets, hence an S_3 connection. After spanning-tree gauge, the 226 cotree voltages comprise 64 identities and 54 copies of each of the three transpositions; the generated monodromy is all of S_3.

Every one of the 270 base triangles has transposition holonomy, with the three transpositions occurring $90 + 90 + 90$ times. Its unique fixed sheet recovers one selected singular three-point line. Recovering all 270 fixed-sheet triangles reproduces the original 135_6–270_3 incidence, and their intersection graph is exactly selected270.

The 27 $GQ(4,2)$ lines are precisely the ten-vertex Petersen fibers. Adjacent fibers share one 45-packet. Their 12 cross-fiber base edges split as

$$3K_{2,2},$$

one $K_{2,2}$ for each of the packet's three singular coordinates. Thus the full selected270 router is recoverable from its 27-object quotient together with this coordinate-preserving connection law.

The regular six-sheet S_3 closure gives a second canonical 270-vertex graph. A parity gauge makes every edge voltage odd, yielding an explicit isomorphism with the bipartite/Kronecker double cover of selected135. Its spectrum is

$$\{12^1, 6^{30}, 3^{44}, 0^{120}, (-3)^{44}, (-6)^{30}, (-12)^1\}.$$

It is *not* the 1620-edge selected270 base graph, which is non-bipartite; this closes the tempting $270 = 270$ identification by an action-level graph invariant rather than by count.

79.4 Capacity envelope and local Petersen coding

Let one unit of base-edge service have capacity $C_b = 1$ and write $\rho = C_s/C_b$ for shortcut capacity. The four exact all-pairs path policies have uniform per-edge load vectors

$$P_0 = (35, 239/3), \quad P_1 = (137/3, 37), \quad P_2 = (155/3, 21), \quad P_3 = (373/6, 0).$$

Convexifying this exact two-resource frontier gives the maximum symmetric all-pairs demand

$$\lambda_{\max}(\rho) = \begin{cases} 3(\rho+2)/373, & 0 < \rho < 63/155, \\ 3(3\rho+8)/1429, & 63/155 < \rho < 111/137, \\ 3(\rho+4)/659, & 111/137 < \rho < 239/105, \\ 1/35, & \rho \geq 239/105. \end{cases}$$

For equal capacities the optimal mixture is $13P_0/80 + 67P_1/80$, equalizing both edge-orbit loads at $659/15$ and giving $\lambda_{\max} = 15/659$. Independent erasure/retransmission is incorporated, as an explicit model, by replacing C_i with $C_i q_i$; an independent M/M/1 layer gives the corresponding queue divergence at the capacity boundary.

Finally, each 15-edge Petersen fiber carries its canonical binary cycle and cut codes

$$[15, 6, 5]_2, \qquad [15, 9, 3]_2.$$

The cycle-code enumerator is

$$1 + 12z^5 + 10z^6 + 15z^8 + 20z^9 + 6z^{10};$$

its 12 minimum words are the Petersen five-cycles. The code is invariant under the full local S_5, and therefore under the certified A_5/S_5 local actions. It corrects every pattern of at most four erased edge symbols. Over all 27 fibers the direct sum is $[405, 162, 5]_2$. This is redundancy, not free throughput: the raw cycle-code rate is $2/5$, so no fault-free capacity increase is inferred.

Evidence boundary. All statements above are finite graph, graph-cover, group-character, design, binary-code, or explicitly parameterized network-model statements. In particular, the C_2 and S_3 holonomies are not identified with optical phase or gauge fields, and the queue/erasure formulas are not measured Holonet performance.

Support-twelve involution and square-root cover closure

Pass 4721: disjoint support turns the 1620 **minima into** 540 **triangles.** Let $\mathcal{T}$ be the exact support-12 minimum shell from Pass 4703, so $|\mathcal{T}| = 1620$ and every element is the corner-star thickening $T(A)$ of a unique W33 apartment. Join two thickenings when their twelve-line supports are disjoint. Exact enumeration gives degree two at every vertex and

$$\boxed{\Delta_{12} = 540K_3.}$$

The three supports in a component cover 36 of the 40 W33 lines. Their four-line complement is always pairwise disjoint. The 540 components yield exactly 270 distinct complements, each with two preimages.

Pass 4722: the old unnamed 270 is the four-fixed-line involution orbit. The inner group $G = \mathrm{PSp}(4,3)$ has 315 involutions in the explicit line action, with fixed-line census

$$\boxed{4^{270} \oplus 16^{45}.}$$

The 270 four-fixed-line sets are distinct and equal exactly to the 270 Pass 4721 residues. A residue stabilizer has order 96, hence orbit size $25920/96 = 270$, and each residue determines a unique inner involution. This corrects the negative conclusion in historical Pass 1830: that GAP script defined its permutation group on the 40 W33 *points* and then applied it to a set of *line indices*. The reported orbit 2880 was therefore not the induced action on the four-line object. Under the actual line action the four-line invariant is the desired 270-orbit.

Pass 4723: the two triangle sheets are outer order-four square-root sheets. Fix a residue R and its unique inner involution g. In $\mathrm{PGSp}(4,3)$ there are exactly eight outer solutions of $h^2 = g$; all have order four, and exactly two fix four W33 lines. Those two are h and h^{-1}. There are also exactly two support-disjointness triangles over R, and either four-fixing root swaps the two. More strongly, for either triangle C over R and either four-fixing root,

$$\boxed{\mathrm{Stab}_G(C) = C_G(h), \qquad |C_G(h)| = 48.}$$

Thus

$$\boxed{\{540 \text{ support-disjointness triangles}\} \cong_G \{540 \text{ four-fixing outer order-four elements}\}.}$$

Both are two-fold covers of the same 270 residue/involution orbit. The two G-equivariant identifications differ by $h \leftrightarrow h^{-1}$. The full $\mathrm{PGSp}(4,3)$ triangle stabilizer and root centralizer both have order 96 but are distinct extensions with common inner intersection of order 48; accordingly no untwisted full-PGSp identification is claimed.

Pass 4724: the 270 residues factor the complement line relation. Let $B \in \{0,1\}^{40\times 270}$ be line-versus-residue incidence and let A_* be the W33 line-intersection adjacency matrix. Every residue has four lines, every line lies in 27 residues, every skew line-pair lies in exactly three, and an intersecting pair lies in none. Hence

$$\boxed{BB^{\mathsf{T}} = 27I + 3(J - I - A_*).}$$

Since the complement of $\mathrm{SRG}(40,12,2,4)$ has spectrum $27^1 \oplus (-3)^{24} \oplus 3^{15}$,

$$\boxed{\mathrm{spec}(BB^{\mathsf{T}}) = 108^1 \oplus 18^{24} \oplus 36^{15}.}$$

Thus B has real rank 40. Over $\mathbb{F}_2$ its residue-mask span has rank 30; no module identification is inferred from that dimension alone. A representative 270-class involution fixes exactly 24 support-12 thickenings and eight of the 540 triangles.

Evidence boundary. These are exact finite incidence and permutation-group statements verified by `analysis/w33_pass4721_4724_support12_involution_square_root_cover.py`. The result repairs an action-domain error in Pass 1830 and then adds a genuine minimum-shell/square-root-cover theorem. Equal cardinalities are never used as a substitute for an intertwiner: fixed sets, square maps, stabilizers, centralizers, orbits, and the Gram identity are checked explicitly. No physical interpretation is inferred.

The 270 involution residues are the complete minimum shell of $H_{10}^{\perp}$

Pass 4725: the residue span is the adjacency-kernel code. Let A_* be the W33 line-intersection adjacency matrix over $\mathbb{F}_2$ and let K_R be the span of the 270 four-line residues of Passes 4721–4724. Every residue mask r satisfies

$$A_* r = 0.$$

The exact ranks are

$$\operatorname{rank}_2 A_* = 10, \qquad \dim K_R = 30.$$

Hence inclusion plus dimension gives the canonical equality

$$\boxed{K_R = \ker_{\mathbb{F}_2}(A_*) = (\operatorname{im}_{\mathbb{F}_2} A_*)^{\perp}.}$$

Exhausting all subsets of the forty line coordinates through weight four gives

$$A_1 = A_2 = A_3 = 0, \qquad \boxed{A_4 = 270},$$

and the 270 weight-four words are exactly the four-line fixed sets of the inner involution class. Therefore

$$\boxed{K_R = [40, 30, 4].}$$

Pass 4726: the involution orbit is the complete minimum parity-check shell of H_{10}. The protected code of Pass 4536 is

$$H_{10} = \operatorname{im}_{\mathbb{F}_2}(A_*), \qquad [40, 10, 12].$$

Since A_* is symmetric, Pass 4725 gives

$$\boxed{K_R = H_{10}^{\perp}.}$$

Consequently the 270 involution residues are not merely codewords of the dual: they are its complete minimum shell, and they reconstruct the protected code by orthogonality,

$$\boxed{H_{10} = \{x \in \mathbb{F}_2^{40} : \langle r, x \rangle = 0 \text{ for every one of the 270 residue checks } r\}.}$$

Enumerating the 2^{10} words of H_{10} gives

$$W_{H_{10}}(z) = 1 + 40z^{12} + 135z^{16} + 672z^{20} + 135z^{24} + 40z^{28} + z^{40}.$$

The binary MacWilliams transform then gives the complete dual enumerator

$$\begin{aligned} W_{K_R}(z) = 1 &+ 270z^4 + 6720z^6 + 152685z^8 + 1651392z^{10} + 10921000z^{12} + 45288000z^{14} \\ &+ 122873490z^{16} + 221227200z^{18} + 269500308z^{20} + 221227200z^{22} + 122873490z^{24} \\ &+ 45288000z^{26} + 10921000z^{28} + 1651392z^{30} + 152685z^{32} + 6720z^{34} + 270z^{36} + z^{40}. \end{aligned}$$

The all-one word lies in K_R, accounting for the paired weight-4 and weight-36 shells.

Prior-art boundary. The binary adjacency code itself is not claimed as new. Haemers, Peeters, and van Rijckevorsel, *Binary Codes of Strongly Regular Graphs*, Designs, Codes and Cryptography **17** (1999), 187–209, computed the adjacency codes for all SRG$(40, 12, 2, 4)$ graphs. For their GQ$(3, 3)$ entry no. 23 they report dimension 10 and exactly the weight enumerator above, with the forty adjacency rows comprising all weight-12 words. The new content here is the W33-specific dual identification

$$H_{10}^{\perp} = \text{span}\{270 \text{ inner-involution fixed-line residues}\},$$

the proof that those 270 words are the *complete* dual minimum shell, and the upstream support-12/outer-order-four double-cover interpretation of Passes 4721–4724.

> **Evidence boundary.** The code equality is proved by direct annihilation and rank, while completeness of the minimum shell is verified by exhaustive weights 1–4. The full 2^{30} dual need not be enumerated: its exact weight enumerator follows from the verified 2^{10} adjacency code via MacWilliams. Literature establishes the underlying $[40, 10, 12]$ adjacency code; this work claims only the new involution/support-shell identification and exact dual-minimum reconstruction. The result is binary coding and finite W33 incidence; no physical interpretation is inferred from code duality.

The involution residues reconstruct the selected270 router, its optimal check schedule, and a finite parity Hamiltonian

Pass 4737: the 270 residue action closes the selected270 router. The four-line residues of Passes 4721–4726 form one transitive PSp$(4, 3)$-set with point stabilizer of order 96 and permutation rank 12. The stabilizer subdegrees are

$$1, 12, 16, 48, 16, 6, 24, 96, 12, 12, 24, 3.$$

Its orbital centralizer algebra has dimension 12 and center dimension 9. The orbital joining two residues that share exactly two W33 lines is connected, 12-regular, and has diameter 4, with distance shell

$$1, 12, 67, 160, 30.$$

Its characteristic polynomial is

$$(x - 12)(x - 8)^{15}(x - 2)^{84}(x + 1)^{64}(x + 4)^{60}(x + 6)^{6}(x^2 - 2x - 12)^{20}.$$

A second orbital has degree 3 and decomposes into 27 Petersen graphs of 10 vertices. Each Petersen fiber consists of ten pairwise-disjoint residue supports and partitions all forty W33 line coordinates.

This is exactly the independently constructed selected270 router of Pass 4716. The identification is not inferred from the common order or spectrum: an order-96 selected270 point stabilizer fixes a unique involution residue, yielding a well-defined PSp$(4, 3)$-equivariant bijection. Under it, the 1620 share-two-lines edges are exactly the selected270 *cold* edges and the 405 degree-three edges are exactly its 27 Petersen *hot* fibers. The quotient of the cold graph by the Petersen fibers is SRG$(27, 10, 1, 5)$; across each quotient edge the twelve cold edges split as three disjoint $K_{2,2}$ blocks, recovering the Pass 4716 finite-connection law from involution residues alone.

Pass 4738: the square-root extension mismatch is the normalizer C_2. For a four-fixing outer square root h, put

$$K = C_{\mathrm{PSp}(4,3)}(h), \qquad |K| = 48.$$

Exact enumeration gives

$$N_{\mathrm{PSp}(4,3)}(K) = H, \qquad |H| = 96,$$

where H is the residue stabilizer. Therefore $H/K \cong C_2$ is the intrinsic sheet character. The full $\mathrm{PGSp}(4,3)$ support-triangle stabilizer and root centralizer are distinct order-96 extensions whose intersection is K. Representatives may be chosen with

$$t^2 = n^2 = 1, \qquad n \in H \setminus K, \qquad h = tn, \qquad nt = h^{-1},$$

so $nhn^{-1} = h^{-1}$. Thus the outer mismatch is the unique nontrivial normalizer-quotient twist. No stronger group-cohomology class is inferred.

Pass 4739: the $q = 3$ minimum-shell theorem is exceptional as stated. Direct prime-field tests at $q = 2, 3, 5, 7$ give binary line-intersection adjacency ranks

$$14, \quad 10, \quad 26, \quad 50,$$

respectively; the tested odd values equal q^2+1. At $q = 3$ the canonical elliptic projective involution fixes the established four-line minimum word. At $q = 5$, however, an exact MILP proves that the adjacency-kernel minimum is

$$\boxed{d = 6},$$

while the canonical elliptic involution fixes eight lines. Hence the statement "the involution fixed sets are the complete minimum shell" does not extend verbatim to all odd q. At $q = 7$ the corresponding involution supplies an 8-line kernel word and hence only the certified upper bound $d \le 8$ here; no exact $q = 7$ minimum is claimed.

Pass 4740: the standard Golay-coordinate route is blocked. A faithful coordinate-permutation action would embed $\mathrm{PSp}(4,3)$ into the extended binary Golay coordinate automorphism group M_{24}, but

$$|\mathrm{PSp}(4,3)| = 2^6 3^4 5 \quad \text{does not divide} \quad |M_{24}| = 2^{10} 3^3 5\, 7\, 11\, 23.$$

The new involution geometry also supplies a canonical 24-coordinate minor: delete the sixteen W33 lines fixed by a 45-class involution. Puncturing H_{10} gives

$$\boxed{[24, 10, 6]},$$

with enumerator

$$1 + 16z^6 + 87z^8 + 240z^{10} + 336z^{12} + 240z^{14} + 87z^{16} + 16z^{18} + z^{24}.$$

Its weight-6 words preclude it from being a subcode of the extended binary Golay $[24, 12, 8]$ code. Shortening gives $[24, 2, 16]$, while puncturing $H_{10}^{\perp}$ gives $[24, 22, 2]$. This is a coordinate-code no-go only; a non-coordinate Conway/Leech representation remains open.

Pass 4741: the Petersen fibers are an optimal 27-round check schedule. The 27 Petersen fibers partition all 270 residue checks. Each fiber contains ten pairwise-disjoint weight-4 checks and covers all forty line coordinates once. Since every W33 line participates in exactly 27 residue checks, any single-use-per-coordinate schedule requires at least 27 layers, and the Petersen resolution attains that lower bound. It is therefore an exact optimal $\mathrm{PSp}(4,3)$-equivariant schedule.

The 270 checks have binary rank 30. The $[40, 10, 12]$ protected code has unique syndromes through weight five. At weight six the only collisions are the complementary $6 + 6$ halves of the forty weight-12 codewords: exactly 18,480 syndrome classes are doubletons and there are no triple collisions. The distinct leader count at weight six is 3,819,900.

Pass 4742: the redundant checks carry a $[270, 240, 3]$ circuit code. The dependency code of the 270 residue masks is

$$\boxed{[270, 240, 3]}.$$

Its complete minimum shell consists of exactly 540 weight-three dependencies. Every such triple has pairwise two-line intersections and six-line union, and the 540 circuit triangles partition all 1620 cold edges exactly once. A second tempting $540 = 540$ identification is false: the circuit-triangle stabilizer and the Pass 4723 support/root-triangle stabilizer both have order 48, but their element-order censuses are respectively

$$1^1 2^{19} 3^8 4^{12} 6^8 \quad \text{and} \quad 1^1 2^7 3^8 4^{24} 6^8,$$

so the two subgroups are not conjugate and the two 540-sets are not the same $\mathrm{PSp}(4,3)$-set.

Pass 4743: a finite commuting four-body parity model. For each residue R define

$$S_R = \prod_{i \in R} Z_i, \qquad \mathcal{H}_R = -\sum_R S_R.$$

The 270 commuting checks have rank 30, so the common $+1$ ground space has computational-basis degeneracy $2^{40-30} = 2^{10} = 1024$ and is exactly H_{10}. The syndrome code is

$$\boxed{[270, 30, 27]}.$$

An exact MILP proves the minimum 27, and a second exclusion MILP proves that the complete weight-27 shell is the forty single-line syndrome rows. Hence this finite model has ground energy -270, gap 54, and first-excited degeneracy $40 \cdot 2^{10} = 40{,}960$. One line violates 27 terms; two skew lines violate 48, while two meeting lines violate 54. Thus the two-defect spectrum resolves W33 line incidence. The 540 Pass 4742 circuits become operator identities $S_a S_b S_c = I$, and Pass 4741 gives the optimal 27-layer measurement schedule. No microscopic or thermodynamic-limit interpretation is claimed.

Pass 4744: the second canonical 24-coordinate family also misses Golay. Deleting the support of any of the 135 weight-16 words of H_{10} gives the same puncture/shorten signatures

$$\boxed{[24, 9, 4]}, \qquad \boxed{[24, 1, 24]}.$$

Thus both intrinsic 24-coordinate families tested here contain words below Golay distance 8. The old W33/Golay parameter equalities remain arithmetic observations, but these two canonical coordinate intertwiners are now structurally excluded.

Evidence boundary. Passes 4737–4744 are finite group, graph, binary-code, optimization, and commuting-check statements. The selected270 identification is certified by an explicit equivariant bijection through equal point stabilizers, not by matching counts. The q-family computation deliberately records the $q = 5$ counterexample. The Golay obstruction applies only to the standard 24 coordinate action and canonical punctures; it does not rule out a non-coordinate Leech-lattice representation. The parity Hamiltonian is a finite algebraic model and is not presented as a microscopic theory of nature.

Passes 4745–4752: invariant cohomology, bundle spectrum, coding, and adversarial capacity

This packet continues the exact $45 \to 135 \to 270$ reconstruction while using the independent involution-residue realization of the 270-vertex router as a cross-check. All claims below are finite graph, group, cohomology, representation, coding, or explicitly parameterized capacity statements.

The apartment deck line is intrinsically characteristic two. For the 16-regular invariant orbital graph on 810 selected flags,

$$\dim H^1(\Gamma; \mathbb{Q}) = 6480 - 810 + 1 = 5671.$$

The complete ordinary $\mathrm{PSp}(4,3)$ character of this H^1 is

$$\begin{aligned} &5_a + 5_b + 3(10_a + 10_b) + 4(15_a) + 20 + 4(24) + 7(30_a) \\ &\quad + 4(30_b + 30_c) + 10(40_a + 40_b) + 12(45_a + 45_b) + 11(60) + 14(64) + 19(81), \end{aligned}$$

where repeated-degree subscripts are the deterministic character fingerprints of the verifier. In particular the trivial constituent occurs with multiplicity zero. The self-paired edge stabilizer has order 4 and contains two endpoint reversers, so the oriented characteristic-zero edge module has no invariant line. By contrast Pass 4713 produced a nonzero $\mathrm{PGSp}(4,3)$-fixed deck class in $H^1(\Gamma; \mathbb{F}_2)$. Hence that deck line is not the mod-2 reduction of a PGSp-invariant integral or rational line.

Full base symmetry does not make the S_3 connection unique. The explicit $\mathrm{PGSp}(4,3)$ image on the 45 packets has order 51840, equal to the independently computed full automorphism group of the reconstructed $GQ(4,2)$ point graph, and the inner generators plus the outer generator satisfy the fiber-lift equation. Thus every base automorphism lifts to the selected three-cover. In spanning-tree gauge the monodromy is already generated by two triangular fundamental cycles,

$$\langle a, b \mid a^2 = b^2 = (ab)^3 = 1 \rangle \cong S_3.$$

However, the condition that all 270 base triangles have transposition holonomy is not characterizing: changing a single cotree voltage on edge $(1, 12)$ to the third transposition gives a distinct connected S_3 connection for which all 270 triangle holonomies still have order two. Thus the triangle rule is necessary but not sufficient.

The radical router spectrum is a multiplicity-space phenomenon. The cold 270-vertex adjacency representation decomposes as

$$1 \oplus 6 \oplus 15_b \oplus 2(20) \oplus 24 \oplus 30_b \oplus 30_c \oplus 60 \oplus 64.$$

The two irrational eigenspaces are both copies of the same 20-dimensional irreducible. On its two-dimensional multiplicity space, the cold adjacency operator has trace 2 and determinant -12, hence minimal polynomial

$$x^2 - 2x - 12,$$

and therefore eigenvalues $1 \pm \sqrt{13}$. The full characteristic polynomial factorization is

$$(x-12)(x-8)^{15}(x-2)^{84}(x+1)^{64}(x+4)^{60}(x+6)^6(x^2-2x-12)^{20}.$$

The remaining eigenspaces are respectively 1, 15_b, $24 \oplus 30_b \oplus 30_c$, 64, 60, and 6.

A genuine cross-fiber code family. The $3K_{2,2}$ connection law partitions all 2025 router edges into 135 disjoint 15-edge cells indexed by a 45-packet and one of its three internal coordinates. A cell contains three hot Petersen edges and three cold $K_{2,2}$ blocks. After compressing each cold block to one repeated symbol, the symbolic cell is a triangle with three coordinates of physical weight 1 and three coordinates of physical weight 4. Exhausting all 2825 binary subspaces of $\mathbb{F}_2^6$ leaves exactly 25 S_3-invariant subspaces. Their weighted rate–distance Pareto frontier is

$$(k, d_w) = (1,15), (2,10), (3,7), (4,3), (5,2), (6,1).$$

Consequently the global invariant families include

$$[2025, 135, 15]_2,\ [2025, 270, 10]_2,\ [2025, 405, 7]_2, [2025, 540, 3]_2,\ [2025, 675, 2]_2,\ [2025, 810, 1]_2.$$

The $[2025, 405, 7]_2$ member improves the explicit product Kd from 2268 for the uncoupled $[2025, 567, 4]_2$ baseline to 2835, while deliberately trading rate for distance; no universal coding optimum is inferred.

Exact adversarial capacity. Normalize every cold-edge capacity to 1 and every hot-edge capacity to $\rho > 0$. The cold graph has edge-connectivity 12, each Petersen fiber has edge-connectivity 3, the 27-vertex quotient has edge-connectivity 10, and every quotient edge carries exactly 12 cold physical edges. Therefore a cut that splits a Petersen fiber costs at least $12 + 3\rho$, while a cut splitting no fiber is a union of whole fibers and costs at least $12 \cdot 10 = 120$. Both bounds are attained, giving the exact worst-pair min-cut

$$\lambda_{\min}(\rho) = \min\{12 + 3\rho, 120\},$$

with the sole technology breakpoint $\rho = 36$. At equal capacities all $\binom{270}{2} = 36315$ vertex pairs have min-cut 15. Deleting all 15 shortcut edges in one Petersen fiber lowers the global min-cut to exactly 12 for every $\rho > 0$. Removing one entire ten-vertex fiber leaves a connected 260-vertex graph of min-cut 13 and diameter 3; removing two representative fibers leaves min-cut 11 and diameter 3 for both quotient-adjacent and quotient-nonadjacent pairs.

Dependency circuits give a chain complex, but not a code map. The 540 minimum weight-three dependency words of the residue $[270, 240, 3]_2$ code are exactly the 540 cold triangles whose edge sets partition all 1620 cold edges. Sending a free circuit generator to its triangle boundary gives an exact chain complex

$$\mathbb{F}_2^{540} \xrightarrow{d_2} \mathbb{F}_2^{1620} \xrightarrow{d_1} \mathbb{F}_2^{270},$$

with

$$\operatorname{rank} d_2 = 540, \qquad \operatorname{rank} d_1 = 269, \qquad \dim H_1 = 1620 - 540 - 269 = 811.$$

The stronger tempting map from the dependency code itself fails: the 540 circuit words span dimension 240 and hence obey 300 independent relations, whereas their 540 edge-disjoint triangle boundaries are linearly independent.

Finite S_3 Fourier decomposition and a falsified radical analogy. The three-sheet permutation representation is $1 \oplus \mathrm{Std}_2$. In the integral standard lattice basis with Gram matrix

$$\begin{pmatrix} 2 & -1 \\ -1 & 2 \end{pmatrix},$$

the 90×90 matrix-valued voltage block is Gram-self-adjoint and satisfies exactly

$$S(S^2 - 36I) = 0.$$

Its spectrum is $6^{15}, 0^{60}, (-6)^{15}$; adjoining the trivial 45-block gives the selected135 spectrum, and trivial + sign + two standard copies reproduces the regular six-sheet S_3 closure. No block contains the factor $x^2 - 2x - 12$. Thus the router's $1 \pm \sqrt{13}$ sector is not the direct Fourier sector of the S_3 cover; it is the distinct multiplicity-two 20-dimensional PSp sector above. An initial source/target transpose error in this calculation was detected by independent execution and corrected before freezing the theorem.

The apartment deck twist is the residue normalizer cover after descent. The canonical projection from 810 flags to their 270 selected lines admits an exact cochain descent

$$\alpha(u, v) + s_u + s_v = \beta(\pi u, \pi v)$$

for the apartment deck voltage. The projected relation is a distinct 16-regular orbital with 2160 edges, disjoint from the hot and cold router relations. The descended voltage defines a connected 540-vertex, 4320-edge, degree-16 double cover of diameter 4. Its induced $\mathrm{PSp}(4, 3)$ action has order 25920 and is transitive, so a point stabilizer has order 48. For the corresponding residue stabilizer H of order 96, the sheet character has kernel exactly

$$K = C_{\mathrm{PSp}(4,3)}(h), \qquad |K| = 48,$$

where h is the Pass 4738 outer order-four root. Therefore the descended apartment deck cover is literally the homogeneous normalizer cover

$$\mathrm{PSp}(4, 3)/K \longrightarrow \mathrm{PSp}(4, 3)/H.$$

This identifies the two C_2 twists by an explicit equivariant descent and subgroup equality, not by matching orders.

Evidence boundary. The packet asserts only the exact finite structures above. The cohomology classes are graph-cover data, the word "Fourier" denotes finite-group representation decomposition, the codes are binary linear codes, and the capacity formula is an undirected finite-network theorem. None is promoted to an optical phase, continuum gauge field, particle assignment, measured hardware threshold, or fault-tolerance threshold.

Passes 4753–4760: residue algebra, odd-q distance, dependency cubes, and the 24-dimensional boundary

Pass 4753: the complete residue orbital algebra. For the transitive 270-residue action of $G = \mathrm{PSp}(4,3)$, the orbital algebra $\mathcal{A}_{\mathbb{Q}}$ has dimension 12 and center dimension 9. Exact structure constants and a split rank-20 idempotent in the unique noncommutative block give

$$\boxed{\mathcal{A}_{\mathbb{Q}} \cong \mathbb{Q}^6 \times \mathbb{Q}(\sqrt{-3}) \times M_2(\mathbb{Q})}, \qquad \mathcal{A}_{\mathbb{C}} \cong \mathbb{C}^8 \times M_2(\mathbb{C}).$$

The M_2 block is the multiplicity-two degree-20 constituent already responsible for the cold-router eigenvalues $1 \pm \sqrt{13}$. A primitive rank-24 central projector is also obtained exactly.

Pass 4754: the odd-q line-kernel distance theorem. Let $A_*(q)$ be the line-intersection adjacency matrix of $W(3,q)$. For every odd prime power q, a generalized-quadrangle double count gives $d(\ker_{\mathbb{F}_2} A_*) \geq q+1$. In the dual parabolic quadrangle $Q(4,q)$, an anisotropic-plane conic supplies a kernel word of weight $q+1$. Hence

$$\boxed{d(\ker_{\mathbb{F}_2} A_*(q)) = q+1 \quad (q \text{ odd}).}$$

The canonical projective J-involution fixes $q+1$ lines when $q \equiv 3 \pmod 4$, but $q+3$ when $q \equiv 1 \pmod 4$. Thus the distance law is uniform while the involution/minimum-shell coincidence has a quadratic-character branch. Related odd-q binary codes appear in the finite-geometry literature; no publication-novelty claim is attached without a full prior-art comparison.

Pass 4755: representation bridge versus Leech-lattice firewall. The rank-24 projector sends the 270 residues to an integral Gram orbit after normalization to norm 24, with pair inner products $9, 4, -1, -6, -16$. The lattice generated by the orbit has

$$\boxed{\det L = 2^{10}3^{10}5^{23}}.$$

Because the Gram contains an entry 1, every scalar rescaling that remains integral has integral scalar and therefore preserves the odd parity of the 5-adic determinant valuation. Consequently this *canonical projector lattice* cannot be a full-rank sublattice of an integral unimodular 24-lattice such as Leech. This does not exclude another commensurable G-invariant lattice in the same rational representation.

Pass 4756: higher dependency geometry. The cold graph has 1080 triangles: 540 XOR-zero dependency circuits and 540 nondependency triangles. Every cold edge belongs to exactly one triangle of each species. The dependency code $[270, 240, 3]$ begins

$$A_3 = 540, \qquad A_4 = 3645 = 1620 + 1620 + 405, \qquad A_5 = 29376,$$

where the displayed decomposition is the exact G-orbit split of the weight-4 shell.

Pass 4758: the triangle incidence is $135Q_3$ and reconstructs selected135. Join a dependency triangle to a nondependency triangle when they share a cold edge. The resulting cubic bipartite graph is

$$\boxed{135\,Q_3}.$$

Each cube uses six residues forming $K_6 - 3K_2$; their W33 support union is an eight-line word of $H_{10}^{\perp}$. The 135 such words form one G-orbit. Their support-intersection-4 graph is explicitly G-equivariantly identical to the selected135 graph, and the six residues in each cube map to exactly the six selected270 lines incident with the corresponding selected135 vertex. Thus the dependency geometry reconstructs the full $135 \leftrightarrow 270$ incidence layer.

Pass 4759: a 45-vector spherical quotient of the same 24-space. Sum the six rank-24 residue vectors in each cube. The 135 sums collapse in three-element packets to 45 distinct vectors. After dividing their Gram by 9, they have norm 16 and mutual inner products -4 or 1. If A_{45} is the -4 relation, then

$$\boxed{G_{45} = 15I - 5A_{45} + J}, \qquad A_{45} \text{ is } \mathrm{SRG}(45, 12, 3, 3).$$

The Gram has rank 24 and nonzero eigenvalue 30, giving the canonical 24-dimensional spherical embedding of the 45-point quotient directly from the residue dependencies.

Pass 4760: the binary 24-dimensional intersection is now explicit. Let $C_\star$ be the binary code on the forty W33 line coordinates generated by the forty point-stars. Then $\dim C_\star = 25$, while $H_{10}^{\perp}$ has dimension 30 and the combined rank is 31. The 135 cube-union words lie in both codes and span rank 24, so

$$\boxed{\mathrm{span}\{\text{cube unions}\} = C_\star \cap H_{10}^{\perp} = [40, 24, 6].}$$

Its complete enumerator begins $1 + 240z^6 + 1485z^8 + 27792z^{10} + 169600z^{12} + \cdots + z^{40}$. The 240 minimum words are exactly the sums of point-stars at the 240 collinear W33 point pairs. No cross-characteristic identification with the rank-24 characteristic-zero constituent of Pass 4753 is inferred from the shared dimension.

Pass 4757: exact radius-six parity-Hamiltonian sectors. For $\mathcal{H} = -\sum_R \prod_{i \in R} Z_i$, the syndrome/coset-leader census is exhaustive through original error weight six. At weight six there are 3,819,900 distinct syndromes and exactly 18,480 doubleton classes, with no triples. Two skew line defects cost 96, giving binding -12 relative to two isolated 54-cost defects; meeting defects cost 108. For independent line flips of probability p, writing $a = 1 - 2p$ gives

$$\mathbb{E}[\mathcal{H}] = -270a^4,$$

$$\mathrm{Var}(\mathcal{H}) = 270(1 - a^8) + 21600(a^6 - a^8) + 3240(a^4 - a^8).$$

This last statement is an exact classical independent-noise calculation, not a thermal-equilibrium or microscopic-physics claim.

> **Evidence boundary.** All finite claims above are accompanied by executable reconstruction scripts. The Leech statement is a no-go for the canonical projected lattice only; the all-odd-q result is a finite-geometry theorem with an explicit prior-art firewall; and the Hamiltonian statements remain within the commuting parity-check model.

Passes 4769–4776: modular cohomology, nonabelian moduli, the normalizer cover, and globally coupled routing codes

Scope. This packet continues the exact finite geometry after Passes 4753–4760. Every statement below is a graph, group, cohomology, code, semisimple-algebra, or fractional-flow theorem. In

particular, the terms "gauge", "Fourier", and "transfer matrix" refer only to finite covers/representations and do not assert a continuum gauge field or measured photonic dynamics.

Pass 4769: the characteristic-two deck line sits in a nonsplit modular socle. For the invariant 810-flag graph, $\dim_{\mathbf{F}_2} H^1 = 5671$. Exact spanning-tree coordinates give

$$\dim(H^1)^{PSp(4,3)} = \dim(H^1)^{PGSp(4,3)} = 4, \qquad \dim H^1_{PSp} = \dim H^1_{PGSp} = 1,$$

where the latter denotes coinvariants. The augmentation subspace $\sum_g (g-1)H^1$ has dimension 5670. All four invariant vectors lie in that augmentation subspace. The apartment deck class is one of them; in the deterministic tree gauge it has weight 2296. Consequently no invariant trivial line, including the deck line, splits as a direct summand. This sharpens the characteristic-zero no-lift theorem: the mod-2 fixed sector is a genuinely nonsplit modular extension.

Pass 4770: the all-triangle-transposition rule has a huge exact moduli space. Put the S_3 connection on the 45-vertex, 270-edge $GQ(4,2)$ point graph into spanning-tree gauge, leaving 226 cotree voltages. Because the odd elements of S_3 are exactly its three transpositions, requiring all 270 base triangles to have transposition holonomy is exactly a binary sign condition. Its 270×226 affine system has rank 162, hence a 64-dimensional affine sign space:

$$2^{64} \quad \text{sign sectors.}$$

For each fixed sign sector every cotree edge has three lifts of the prescribed parity. Modulo vertex gauge and residual global conjugation, the connected classes in one sign sector number

$$\frac{3^{225}-1}{2}.$$

Thus before the further $|\operatorname{Aut}(GQ(4,2))| = 51840$ quotient, the connected gauge classes number

$$2^{64}\frac{3^{225}-1}{2}.$$

All 452 Hamming-radius-one same-sign changes of the selected tree-gauge representative remain connected. The triangle rule is therefore strongly non-rigid, not merely nonunique by one exceptional deformation.

Pass 4774: the nonabelian deformation fiber is twisted $\mathbf{F}_3$ cohomology. Writing an S_3 voltage as $r^a s^p$ with $r^3 = s^2 = 1$ and $srs = r^{-1}$ turns the A_3 exponent into a rank-one $\mathbf{F}_3$ local system twisted by the sign cocycle. Its coboundary has rank 45 on $C^0 \cong \mathbf{F}_3^{45} \to C^1 \cong \mathbf{F}_3^{270}$, so

$$H^0 = 0, \qquad \dim H^1 = 225.$$

Each of the 2^{64} binary sign sectors therefore carries the projective point set of nonzero vectors in $\mathbf{F}_3^{225}$ modulo $\{\pm 1\}$, i.e. a $PG(224,3)$ point set, before quotienting by base automorphisms. There is no nonzero additive linear map from the characteristic-two deck line into this characteristic-three deformation space, so the two effects are explicitly separated rather than identified by shared "gauge" language.

Pass 4771: the descended deck graph is a cohomology-selected homogeneous double cover. Let H be a residue stabilizer, $|H| = 96$, and let $K = C_{PSp(4,3)}(h)$ be the Pass-4738 order-48 kernel. The descended carrier is

$$PSp(4,3)/K \longrightarrow PSp(4,3)/H, \qquad 540 \longrightarrow 270.$$

Among the two subdegree-16 residue orbitals, the desired base is characterized intrinsically: for adjacent residues the product of their unique four-fixed involutions has order 3 and fixes seven W33 lines; the other subdegree-16 orbital fixes only one. The selected base has 2160 edges, degree and edge-connectivity 16, diameter 4, 2880 triangles, binary adjacency rank 78, cycle-code dimension 1891, and spectrum

$$16^1 + (-8)^6 + 6^{24} + (-3)^{64} + 0^{135} + (2 + 2\sqrt{13})^{20} + (2 - 2\sqrt{13})^{20}.$$

Above this base there are two connected degree-16 homogeneous lifts with the same easy metrics. They contain 1440 and 4320 triangles. Exact comparison of their tree-gauged cover classes with the Pass-4752 descended cocycle selects the 4320-triangle lift. Its signed sheet spectrum is

$$8^{20} + 4^{81} + (-1)^{64} + (-4)^{105},$$

and its binary adjacency rank is 226 with cycle-code dimension 3781.

Pass 4775: the degree-16 base uses the unique $M_2(\mathbf{Q})$ block, but the sheet sector does not. The residue centralizer algebra remains

$$\mathbf{Q}^6 \times \mathbf{Q}(\sqrt{-3}) \times M_2(\mathbf{Q}).$$

Recovering the rank-40 projector intrinsically by Chinese-remainder projection of the cold adjacency onto $x^2 - 2x - 12$ and then taking a primitive rank-20 idempotent gives a concrete two-dimensional left ideal. In one exact rational basis the distinguished orbital matrices are

$$A_{\text{cold}} \mapsto \begin{pmatrix} 0 & 12 \\ 1 & 2 \end{pmatrix}, \qquad A_{\text{hot}} \mapsto \begin{pmatrix} 3 & 6 \\ 0 & -2 \end{pmatrix}, \qquad A_{16} \mapsto \begin{pmatrix} 4 & -24 \\ -2 & 0 \end{pmatrix}.$$

Hence A_{16} has polynomial $x^2 - 4x - 48$ and eigenvalues $2 \pm 2\sqrt{13}$. In contrast, the signed sheet representation is

$$10_a + 10_b + 15_a + 45_a + 45_b + 64 + 81,$$

with degree-20 multiplicity zero. Thus the degree-16 *base* adjacency acts nontrivially in the unique noncommutative block, while the C_2 sheet module itself is representation-theoretically transverse to that block.

Pass 4776: dependency cubes are literally the cross-fiber coding cells. The 135 dependency Q_3 components from Pass 4758 and the 135 fifteen-edge cells from Pass 4748 are the same $PSp(4,3)$ G-set under an explicit equivariant map; representative stabilizers are literally equal subgroups of order 192. Each cube uses six residue vertices and is $K_6 - 3K_2$ in the cold graph. Under the residue-to-selected270 intertwiner, the three missing pairs are exactly the three Petersen-hot edges. Adding them completes the physical cell to K_6, and the other twelve edges are precisely the three $K_{2,2}$ cold blocks. The resulting 135 completed K_6 cells partition all 2025 router edges exactly once.

Pass 4772: GQ-line coupling doubles the cross-fiber code distance. Use the intrinsic K_6 cell coordinates. A basis for the local $[15,3,7]_2$ code is indexed by the three quotient GQ lines through the cell: the generator associated with one line consists of all three hot matching edges plus the cold $K_{2,2}$ block between the other two line fibers. The 405 logical coordinates therefore split canonically into 27 disjoint groups of 15, one group per quotient line. Imposing one even-parity check on each group gives

$$\boxed{[2025, 378, 14]_2}.$$

The distance is exact: logical weight two must occupy two distinct cells of the same line group and therefore has physical weight $7+7=14$; logical weight at least four has physical weight at least 16 because the local physical weights for one, two, and three active logical bits are $7, 8, 15$. This raises the explicit Kd metric from $405 \cdot 7 = 2835$ to $378 \cdot 14 = 5292$. Repetition on each 15-coordinate line group yields the second exact family

$$\boxed{[2025, 27, 105]_2}.$$

These are symmetry-preserving code constructions, not universal coding-optimality or fault-tolerance claims.

Pass 4773: exact all-pairs concurrent flow reduces to four resource vertices. For unit demand on every ordered distinct selected270 pair, cold-edge capacity 1, and hot-edge capacity ρ, the eleven nontrivial $PSp(4,3)$ pair orbitals have exact nondominated path signatures. Orbit averaging makes every cold edge and every hot edge carry uniform load. Their Minkowski sum has only four lower-frontier vertices, written as total cold/hot traversals per unit concurrent demand:

$$(113400, 64530), \quad (147960, 29970), \quad (167400, 17010), \quad (201420, 0).$$

Consequently the exact fractional concurrent throughput is

$$\lambda(\rho) = \begin{cases} 3(\rho+2)/746, & 0 < \rho \le 63/155, \\ 3(3\rho+8)/2858, & 63/155 \le \rho \le 111/137, \\ 3(\rho+4)/1318, & 111/137 \le \rho \le 239/105, \\ 1/70, & \rho \ge 239/105. \end{cases}$$

At equal capacities,

$$\boxed{\lambda(1) = 15/1318 \approx 0.01138088}.$$

The 27-fiber quotient has exact ordered-all-pairs throughput $10/7$ when each quotient edge receives its twelve cold physical-edge capacities. For symmetry-breaking hot-fiber outages and full-fiber removals the packet freezes explicit all-shortest-path feasible lower bounds and cut upper bounds only; those failure-case values are not promoted to optima.

Evidence. Executable witnesses are `w33_pass4769_modular_h1_head_socle.py`, `w33_pass4770_4774_s3_modu` `w33_pass4771_4775_degree16_cover_hecke_certified.py`, `w33_pass4772_4776_global_cube_cell_code.py`, and `w33_pass4773_symmetry_reduced_multicommodity_flow.py`. Frozen certificates live in `data/PART_W33_PAS` through `data/PART_W33_PASS4776_*`, with a cross-certificate regression in `tests/test_w33_pass4769_4776_modu`

Passes 4777–4784: matrix units, BLT minima, D_4 triality, and the 45-point triangle router

Pass 4777: literal matrix units in the unique noncommutative block. Let E_{40} be the rank-40 central idempotent of the 270-residue orbital algebra and let $A_{\mathrm{hot}}, A_{\mathrm{cold}}$ denote the degree-3 and degree-12 orbital elements. With

$$e_{11} = \frac{1}{5}E_{40}(A_{\mathrm{hot}} + 2E_{40}), \qquad e_{22} = E_{40} - e_{11},$$

$$e_{12} = e_{11}A_{\mathrm{cold}}e_{22}, \qquad e_{21} = \frac{25}{324}e_{22}A_{\mathrm{cold}}e_{11},$$

exact multiplication gives $e_{ij}e_{k\ell} = \delta_{jk}e_{i\ell}$. These are rational matrix units for the $M_2(\mathbb{Q})$ factor of Pass 4753. The outer PGSp/PSp involution fixes all four matrix units and swaps only the paired orbital relations $8 \leftrightarrow 9$.

Pass 4778: minimum words are BLT-sets, and $q = 5$ has two orbits. Equality in the odd-q distance theorem is precisely the BLT condition: $q+1$ pairwise-skew lines such that every external $W(3,q)$ line meets zero or two selected lines. At $q = 3$ all 270 minima are planar. At $q = 5$ the complete minimum shell has two $\mathrm{PSp}(4,5)$ orbits,

$$\boxed{6500 + 13000 = 19500},$$

with stabilizers 720 and 360 and Pluecker span ranks 3 and 5. A MILP excluding both orbits is infeasible. These are the classical Linear and Fisher/Fi BLT classes; the BLT naming and small-order classification are prior art.

Pass 4779: rational square-class firewall against Leech. The 45-vector quotient has Gram matrix $G_{45} = 15I - 5A_{45} + J$, rank 24, and

$$\det G_{45} = 2^{10}3^{10}5^{23}.$$

Hence its determinant square class over $\mathbb{Q}$ is 5. Rational basis changes multiply determinant by a square, while rational rescaling in dimension 24 contributes a 24th power, also a square. Since the Leech lattice is unimodular with square class 1, no lattice commensurable with this rational orthogonal constituent can be rationally isometric to Leech, even after rational scaling. This is a quadratic-form obstruction, not a denial of other abstract 24-dimensional representations of $U_4(2)$.

Pass 4780: the dependency-cube stabilizer is $W(D_4)$ with literal triality. The stabilizer of one dependency cube has order 192, kernel C_2^3 on its six residue vertices, and quotient S_4 in the six-edge action of a tetrahedron. An order-24 complement is explicit, hence

$$\boxed{H_{\mathrm{cube}} \cong 2^3{:}S_4 = W(D_4).}$$

It fixes a canonical packet of three cubes. The packet stabilizer has order 576 in $\mathrm{PSp}(4,3)$ and quotient C_3 over $W(D_4)$; adjoining the outer coset gives order 1152 and quotient S_3. Thus the three-cube packet carries literal D_4 triality.

Pass 4781: exact landscape bounds without overclaiming the radius. The explicit H10 coset represented by 253626779097 has minimum distance 14 and weight distribution

$$64z^{14} + 128z^{16} + 192z^{18} + 256z^{20} + 192z^{22} + 128z^{24} + 64z^{26}.$$

Orthogonal-array strength three and complement symmetry exclude coset minimum at least 17, so

$$\boxed{14 \le \rho(H_{10}) \le 16}.$$

The exact value $14, 15$, or 16 remains open here. For the $[270, 30, 27]$ syndrome code, the 540 dependency triangles imply weight at most 180; equality would require a 90-point exact transversal meeting every dependency triangle once, and an exact binary MILP proves this infeasible. Hence syndrome weight is at most 179, giving the finite parity Hamiltonian energy ceiling $-270+2(179) = 88$.

Pass 4782: the 270 residues are the 270 triangles of the 45-point quotient. The three-cube triality packets form 45 quotient vertices. The selected-135 graph projects three-to-one on edges to

$$\mathrm{SRG}(45, 12, 3, 3).$$

Each residue belongs to three cubes lying in three distinct packets, and those three quotient vertices form a triangle. The resulting 270 triangles are distinct and exhaust all triangles of the quotient:

$$\boxed{\{\text{involution residues}\} \cong \{\text{triangles of } \mathrm{SRG}(45, 12, 3, 3)\}.}$$

Pass 4783: Petersen fibers are the triangle geometry of the 27 maximal K_5's. The quotient has exactly 27 maximal cliques, all K_5, and every quotient triangle lies in exactly one of them. Each K_5 contains ten triangles. Joining two when they intersect in one quotient vertex gives a Petersen graph. Across all 27 cliques these are exactly the 405 hot router edges.

Pass 4784: the outer involution is a triangle-chirality reversal. The neighborhood of every quotient vertex is $3K_4$. In the triangle model, shared-edge pairs form the degree-6 orbital 5; pairs sharing exactly one quotient vertex split into orbitals $1, 8, 9, 11$. Orbital 1 is cold, orbital 11 is hot, and $8, 9$ are paired directed relations of degree 12. The outer involution fixes the shared-edge, cold, and hot relations and swaps precisely

$$\boxed{8 \longleftrightarrow 9}.$$

Thus its simplest nontrivial router action is a reversal of this paired triangle chirality, not an action on the $M_2(\mathbb{Q})$ multiplicity space.

> **Evidence boundary.** All finite claims above have executable reconstruction scripts and frozen JSON certificates. The Linear/Fisher BLT classification is prior art; Pass 4779 is a rational quadratic-form no-go only; and Pass 4781 deliberately records the unresolved covering-radius trichotomy rather than promoting a radius-14 witness to an equality.

Support-12 minima reconstruct the protected 45, dual cycle code, point-edge shell, and Golay neighbor relations

Pass 4785: the thickening edge code is the full even cycle hyperplane. For every one of the 1620 support-12 apartment thickenings, record the 28 edges induced in the 40-vertex W33 line-intersection graph X. The resulting 1620×240 binary incidence has constant column weight 189 and rank 200. Every row is an even-weight Eulerian edge set. Since

$$\dim Z_1(X;\mathbb{F}_2) = 240 - 40 + 1 = 201,$$

the row code is exactly

$$\boxed{C_{\text{thick}} = Z_1(X;\mathbb{F}_2) \cap \{\text{even edge weight}\} = [240, 200, 4]_2.}$$

Its dual is

$$\boxed{C_{\text{thick}}^{\perp} = \text{Cut}(X) + \langle \mathbf{1}_E \rangle = [240, 40, 12]_2.}$$

The dual distance is 12: the ordinary cut space has edge-connectivity 12, while the all-edge coset has weight at least 80 by the $\lambda_{\min} = -4$ max-cut bound.

Pass 4786: a canonical partner involution recovers the protected 45 literally. For two thickening edge-vectors, their intersection sizes lie in

$$0, 1, 2, 6, 7, 8, 12, 16, 21.$$

Every minimum has exactly one partner at overlap 8, producing 810 pairs. The two 12-line supports of a partner pair meet in eight lines and have a 16-line union. The 810 unions collapse 18-to-1 onto exactly 45 supports. Every support induces

$$\text{SRG}(16, 6, 2, 2)$$

with eight maximal K_4s, hence the 4×4 rook graph $L_2(4)$. Rebuilding the old 135 singular apartment fibers shows that these 45 subsets are *literally the same* 45 protected/E_6 center-quad–tritangent supports, not merely an isomorphic carrier.

Pass 4787: the support-12 shell independently reconstructs the exceptional transport graph. Two of the 45 rook grids meet in either 7 or 4 W33 lines. Declaring intersection 7 adjacent gives

$$\boxed{\text{SRG}(45, 32, 22, 24).}$$

For the 45×40 grid-line incidence matrix T,

$$TT^{\mathsf{T}} = 12I_{45} + 3A_{45} + 4J_{45}, \qquad T^{\mathsf{T}}T = 12I_{40} + 3A_{\text{dual}} + 6J_{40}.$$

Hence $\text{rank}_{\mathbb{Q}}\, T = 25$ and $\text{rank}_2\, T = 24$. Modulo two, the two Gram matrices reduce to A_{45} and A_{dual}, of ranks 14 and 10 respectively.

Pass 4788: the local 36-state shell is a rectangle product with an extra central partner. Each 16-line rook grid contains exactly

$$\binom{4}{2}\binom{4}{2} = 36$$

support-12 minima. The eight rook K_4s split into two families of four, so a minimum is canonically labelled by

$$(R, C) \in \binom{[4]}{2} \times \binom{[4]}{2}.$$

The overlap-8 partner is simultaneous complementation

$$(R, C) \mapsto (R^c, C^c),$$

and the partner apartment is exactly the four-line complement of the thickening inside the grid. The $PGSp$ and PSp grid stabilizers have orders 1152 and 576, each with pointwise kernel 2 on the sixteen lines; their induced rectangle actions therefore have orders 576 and 288 and are transitive. The partner involution is not in the $PGSp$ image, centralizes it, and doubles the 36-set permutation group to order 1152.

Pass 4789: the two 240 edge coordinate carriers are not equivariantly identical. The new code lives on edges of the W33 line-intersection graph, whereas the established CSS/Hodge carrier uses edges of the W33 point-collinearity graph. A dual-line-edge stabilizer has order 108 and suborbits

$$1, 1, 2, 2, 18, 18, 18, 18, 27, 27, 54, 54$$

on its own 240-set, but on the point-edge 240-set its suborbits are

$$6, 6, 6, 6, 54, 54, 54, 54.$$

It fixes no point edge. The $PGSp$ outer twist leaves the obstruction unchanged. Thus there is no canonical PSp coordinate bijection between the two edge carriers.

Pass 4790: nevertheless the 45-grid code recovers the point-edge carrier as its minimum shell. The binary row code of T is

$$\boxed{C_{45} = [40, 24, 6]_2}$$

with 240 minimum words. If B is the 40×40 point-line incidence matrix and $p \sim q$, then

$$w_{pq} = \mathrm{Star}(p) \triangle \mathrm{Star}(q)$$

has weight six; the 240 such words are exactly the entire minimum shell of C_{45}. Algebraically,

$$C_{45} = B^{\mathsf{T}}(\text{even point coefficients}).$$

The dual is

$$\boxed{C_{45}^{\perp} = [40, 16, 10]_2 = \{y : By \in \langle \mathbf{1} \rangle\}.}$$

Its 252 minimum words split into 216 kernel words with point-degree profile $0^{20}2^{20}$ and exactly 36 spreads with point-degree profile 1^{40}.

Pass 4791: the 24 Leech-neighbor parity characters have Golay as their full relation code. For the explicit two-neighbors of Pass 4699 let

$$v_i = (1, \dots, 1, 3_i, 1, \dots, 1)/\sqrt{2}, \qquad \chi_i(x) = (x, v_i) \pmod 2.$$

Evaluating the 24 characters on an exact generating set of the Golay Construction-A Niemeier lattice gives a rank-12 character system whose binary relation space is *exactly* the extended Golay code G_{24}. Therefore every subset of at most seven neighbor characters is independent and the first dependencies are precisely the 759 octads. The corrected sextet supplies 15 explicit octad relations as unions of two tetrads. Its order-138240 stabilizer is transitive on the 24 neighbors; a neighbor stabilizer has order 5760 and point suborbits $1 + 3 + 20$.

Pass 4792: the deck and even-cycle parity lines are analogous but not canonically the same. The codimension-one quotient $Z_1(X)/C_{\text{thick}}$ is dual to the mod-two all-edge cohomology class on X. A triangle witnesses that the class is nonzero. It is group-fixed in characteristic two, while the edge stabilizer contains 54 endpoint reversers, eliminating an invariant characteristic-zero oriented lift. This parallels the Pass 4745/4752 apartment deck line. However the two transitive bases have PSp vertex stabilizers of orders 648 and 96. Since neither divides the other, no equivariant map exists between the 40- and 270-vertex bases in either direction. The shared one-dimensional $\mathbb{F}_2$ type is therefore not promoted to a common cohomology object.

Evidence firewall. Passes 4785–4792 are exact finite graph/code/group/lattice/cohomology statements. The canonical numbering repairs a later namespace collision; the original 4761–4768 implementation files are retained as provenance aliases. The point- and line-edge coordinate carriers remain nonisomorphic under the canonical action even though the grid code recovers the point-edge carrier nonlinearly as a minimum-word shell. The apartment enumerator remains open beyond exact support 12.

Passes 4793–4800: BLT closure, orientation chirality, F_4/E_6 crosswalk, and a qutrit triangle code

Pass 4793: the $q = 7$ shell has two BLT equivalence classes. Passes 4754 and 4778 identify the minimum words of $\ker_{\mathbb{F}_2} A_*(W(3, q))$ with BLT-sets. Betten's complete $q = 7$ census has exactly the Linear and Fi/K2 classes, with full projective-orthogonal stabilizer orders 5376 and 384. Since the full group has order 276595200, the corresponding class sizes are 51450 and 720300. Thus the complete minimum shell has two classes at this equivalence level and total size 771750. The finer $\mathrm{PSp}(4, 7)$ orbit split is not asserted without a separate index-two certificate.

Pass 4794: the H10 covering radius is 14 or 15. For a coset let s be the number of the 270 weight-four dual checks evaluating oddly. Pass 4781 gives $s \le 179$. If an even coset had minimum at least 16, complement symmetry and OA strength three force

$$A_{16} = A_{24} = a, \quad A_{18} = A_{22} = 1280 - 4a, \quad A_{20} = 6a - 1536, \qquad 256 \le a \le 320.$$

The fourth Krawtchouk moment and coset MacWilliams identity give $a = 1760 - 8s$, hence $a \ge 328$, a contradiction. Therefore

$$\boxed{14 \le \rho(H10) \le 15}.$$

Only an odd distance-15 coset can still make the upper value sharp; a separate exact MILP producer records that final decision only if it terminates decisively.

Pass 4795: orbitals 8/9 are an orientation torsor. The 45-point quotient has three maximal K_5 lines through each point. The $\mathrm{PSp}(4,3)$ point stabilizer has order 576 and induces C_3 on those three lines, whereas the full outer extension has stabilizer order 1152 and induces S_3. Hence there are exactly two opposite global cyclic-orientation sheets: PSp preserves either sheet and the outer coset reverses it. After the cold orbital is removed, the two local orientation signs are exactly the paired residue orbitals 8 and 9. Cold orbital 1 occurs in both signs, so orientation and cold selection are distinct data; no H^2 claim is made.

Pass 4796: the 270 carrier is intrinsic to $GQ(4,2)$. Starting from $Q^-(5,2)$ alone gives the 45-point graph $\mathrm{SRG}(45,12,3,3)$ with exactly 27 maximal K_5 lines. Every graph triangle lies in a unique K_5, so

$$27\binom{5}{3} = 270$$

is the complete carrier. Equivalently a carrier state is the complement duad of a triangle inside its unique K_5. The ten triangles of each K_5, adjacent when their intersection has size one, form Petersen, recovering all 27 hot fibers and 405 hot edges. The triangle hypergraph is lossless: the 45 original points are its 18-triangle stars and adjacency is recovered by triangle co-occurrence three. No 40-line W33 coordinates are needed.

Pass 4797: the cube-triality quotient is explicitly the compiler F_4/E_6 quotient. An executable graph isomorphism maps the 45 three-cube $W(D_4)$ packets of Pass 4782 to the independently reconstructed BT167/168 F_4-normalizer quotient. The witness preserves all 27 maximal K_5 lines and therefore all 270 triangle states. BT169 already supplies the explicit line-preserving second leg from the compiler quotient to the older W33 center-quad/E_6 geometry. Thus the new router is attached to the established F_4/E_6 carrier by finite crosswalks rather than order coincidences. The central-versus-outer order-51840 extensions remain distinct, and the existing tomotope-H obstruction is unchanged.

Passes 4798–4799: a characteristic-three triangle code. Let B be the 45×270 point–triangle incidence matrix. Each row has weight 18, each column weight 3, adjacent quotient points co-occur in three triangles, and nonadjacent points in none, so

$$BB^T = 18I + 3A_{45} \equiv 0 \pmod 3.$$

The only ternary row dependency is the global all-point sum, giving $\mathrm{rank}_{\mathbb{F}_3} B = 44$; the same rows have rank 45 over $\mathbb{F}_2$ and $\mathbb{F}_5$. On one K_5, a nonconstant coefficient pattern has local triangle weight 6 or 9. Removing fewer than three GQ lines never disconnects the constant-coefficient graph, while the 45 minimum three-line cuts are exactly point pencils. Hence

$$\boxed{C_\triangle = [270, 44, 18]_3}$$

is self-orthogonal, with exactly 90 minimum words, the two nonzero single-point perturbations at each quotient point.

Pass 4800: the intrinsic triangle CSS code. Taking $H_X = H_Z = B$ is valid because $BB^T = 0$ over $\mathbb{F}_3$. Both check ranks are 44, so $k = 270 - 88 = 182$. The dual has no dependency of weight at most three among distinct weight-three triangle columns. A weight-four dependency is supplied by

any four points inside one K_5: the four corresponding 3-subsets sum to zero because every point occurs three times. Since $d(C_\triangle) = 18$, these dual weight-four words are not stabilizers. Therefore

$$\boxed{[[270, 182, 4]]_3}.$$

This is a finite qutrit CSS theorem only; no physical locality, fault-tolerance threshold, or microscopic energy scale is inferred.

> **Evidence boundary.** The finite claims have executable producers and frozen JSON certificates under Passes 4793–4800. BLT class names/completeness at $q = 7$ are prior art. The exact H10 radius remains unpromoted unless the separate distance-15 MILP terminates decisively. The F_4/E_6 bridge is a quotient/incidence crosswalk and does not identify the inequivalent central and outer order-51840 extensions or revive the previously falsified tomotope=$W(D_4)$ count identification.

79.5 The apartment-parity trace law for a general $\mathrm{GQ}(s, t)$

The $W(3, 3)$ identities above are not isolated numerical features. Let $\mathcal{Q}$ be any finite generalized quadrangle of order (s, t), let G be its point-collinearity graph, and assign one sign $\sigma_\ell \in \{\pm 1\}$ to each geometric line ℓ. Every line induces a clique K_{s+1} in G and every graph edge lies on a unique geometric line. With

$$n = (s + 1)(st + 1), \qquad L = (t + 1)(st + 1), \qquad d = s(t + 1),$$

the line-signed adjacency matrix obeys the parameter-exact trace laws

$$\mathrm{tr}(A_\sigma^2) = nd, \tag{11}$$

$$\mathrm{tr}(A_\sigma^3) = 6\binom{s+1}{3} \sum_\ell \sigma_\ell, \tag{12}$$

$$\mathrm{tr}(A_\sigma^4) = nd(2d - 1) + 24L\binom{s+1}{4} + 8W_{\mathcal{Q}}(\sigma), \tag{13}$$

where $W_{\mathcal{Q}}$ is the sum of the products of the four side-line signs over all induced quadrangles. The fourth-moment classification is exhaustive: repeated-edge closed walks give $nd(2d - 1)$; a simple 4-cycle with a chord contains a triangle and is therefore forced into one geometric line; and every remaining simple 4-cycle is an induced generalized-quadrangle apartment using four distinct lines.

The number of induced quadrangles is

$$\boxed{Q = \frac{ns^2t^2(t + 1)}{8}.} \tag{14}$$

If H denotes line–quadrangle incidence and A^* the line-collinearity adjacency matrix (equivalently the point graph of the dual $\mathrm{GQ}(t, s)$), then one line occurs in

$$r = \frac{(s + 1)s^2t^2}{2}$$

quadrangles, two intersecting lines occur together in

$$\alpha = s^2t,$$

and two disjoint lines occur together in

$$\beta = \binom{s+1}{2} = \frac{s(s+1)}{2}.$$

Consequently

$$\boxed{HH^T = (r-\beta)I + (\alpha-\beta)A^* + \beta J.} \tag{15}$$

For independent random line signs the distinct quadrangle supports are distinct quartic Walsh characters, so

$$\mathbb{E}W_{\mathcal{Q}} = 0, \qquad \mathrm{Var}(W_{\mathcal{Q}}) = Q, \qquad \mathbb{E}f_{\mathcal{Q}} = \frac{1}{2}, \qquad \mathrm{sd}(f_{\mathcal{Q}}) = \frac{1}{2\sqrt{Q}}.$$

This theorem also clarifies the recent cross-generalized-quadrangle signing experiments without reviving the refuted "coarseness law". The dual parameter sets $(s,t) = (3,9)$ and $(9,3)$ both have

$$\boxed{Q = 102060}$$

quadrangle observables, but their line-sign registers have respectively 280 and 112 degrees of freedom and their signed cliques have sizes 4 and 10. Thus duality preserves the apartment count while not preserving line-signing granularity. The theorem predicts exact low moments and null variances; it does *not* predict the probability that a random line signing is Ramanujan. The measured $\mathrm{GQ}(3,9)$ counterexample from the recent signing frontier therefore remains a genuine boundary on any stronger (s,t)-only heuristic.

Executable boundary. The formulas are generated and the $W(3,3)$ specialisation is rebuilt exactly by `analysis/w33_pass4465_general_gq_line_signing_trace.py`, with the frozen certificate `data/PART_W33_PASS4465_GENERAL_GQ_LINE_SIGNING_TRACE.json`. The result is a finite generalized-quadrangle theorem. It does not turn the line signs into a physical gauge field and does not infer spectral optimality from the parameters alone.

79.6 Correction: legacy "four-cycle frustration" versus apartment frustration

The general apartment theorem exposes a normalization issue in the recent Pass 4433 signing experiment. Its helper `four_cycles(A)` was documented as "Every simple 4-cycle ... counted once", but the implementation iterates over every unordered diagonal pair and every pair of common neighbours. On $W(3,3)$ it therefore emits

$$\boxed{3480 \text{ records}}$$

representing only

$$\boxed{1740 \text{ underlying simple } C_4\text{s}},$$

each exactly twice. The 1740 split as

$$\boxed{1620 \text{ induced building apartments} + 120 \text{ line-internal } C_4\text{s}.}$$

The second family lies inside the forty geometric K_4 lines. Under a line signing every edge on such a line has the same sign, so every line-internal C_4 has parity $+1$ and can never be frustrated.

Consequently the historical fraction is not the pure apartment fraction. For $W(3,3)$ they are related exactly by

$$\boxed{f_{\text{legacy}} = \frac{27}{29} f_{\text{apartment}}.} \tag{16}$$

Its independent-random-line-signing mean is therefore 27/58, not 1/2. This does *not* invalidate the standardized z-score quoted in Pass 4433: both the optimized value and its random baseline are multiplied by the same positive constant, so the z-score is invariant. The correction is to the label and raw normalization, not to the separate Ramanujan verdict.

For a general GQ(s,t) the same audit is parameter-exact. With Q induced quadrangles and $L=(t+1)(st+1)$ geometric lines, the number of line-internal simple four-cycles is

$$C_{\text{line}} = 3L\binom{s+1}{4},$$

and the legacy helper returns $2(Q+C_{\text{line}})$ records. Hence

$$\boxed{f_{\text{legacy}} = \frac{Q}{Q+C_{\text{line}}} f_{\text{apartment}}.} \tag{17}$$

This matters sharply in the recent dual-pair comparison:

$$\text{GQ}(3,9): \quad \frac{f_{\text{legacy}}}{f_{\text{apartment}}} = \frac{243}{245}, \qquad \text{GQ}(9,3): \quad \frac{f_{\text{legacy}}}{f_{\text{apartment}}} = \frac{81}{137}.$$

The same 102060 apartment count can therefore sit underneath very different raw legacy normalizations. Cross-generalized-quadrangle comparisons should use the induced-apartment observable or apply the exact undilution before comparing fractions.

Correction boundary. The executable audit is `analysis/w33_pass4466_legacy_four_cycle_frustration_audit.py`. It corrects cycle enumeration semantics and normalization only. It does not withdraw Pass 4433's separate statement that a Ramanujan line signing was found on $W(3,3)$ while the searched GQ$(9,3)$ line-signing family remained above its Ramanujan bound.

79.7 Apartment parity and the protected binary label space (Passes 4469–4471)

Let N be the 40×40 point–line incidence matrix of $W(3,3)$ and let H be the 40×1620 line–apartment incidence matrix. Passes 4463–4464 established

$$\operatorname{rank}_{\mathbb{F}_2} H = 39, \qquad \dim \operatorname{rad}(\operatorname{im} H^T) = 29, \qquad HH^T = N^T N = A_* \pmod 2,$$

with A_* the dual line-collinearity adjacency. Pass 201 independently owns the binary sentinel code

$$C = \ker N^T = [40,15,8], \qquad C^\perp = \operatorname{im} N,$$

and the 10-dimensional logical-label quotient $H_{10} = C^\perp/C$ of the $[[40,10,4]]$ CSS code.

Theorem 79.1 (Canonical apartment–H_{10} symplectic bridge)**.** *The incidence map induces an exact isometry of nondegenerate alternating spaces*

$$\boxed{\frac{\operatorname{im} H^T}{\operatorname{rad}(\operatorname{im} H^T)} \cong \frac{\mathbb{F}_2^{40}}{\ker(N^T N)} \xrightarrow{[b]\mapsto[Nb]} \frac{\operatorname{im} N}{\ker N^T} = H_{10}.}$$

Its kernel statement and pairing statement are literal:

$$Nb \in \ker N^T \iff N^T N b = 0,$$

$$\langle H^T b, H^T c\rangle = b^T N^T N c = \langle Nb, Nc\rangle \pmod 2.$$

The executable witness checks the quotient dimensions, the three Gram matrices, and all 2^{10} quotient classes.

The two natural Hamming quadratic refinements,

$$q_{\mathrm{ap}}([y]) = \frac{\mathrm{wt}(y)}{2} \pmod 2, \qquad q_{H_{10}}([x]) = \frac{\mathrm{wt}(x)}{2} \pmod 2,$$

both descend and both have 528 singular classes including zero; hence both are of plus type $O^+(10,2)$. The raw incidence isometry is not, however, a quadratic isometry. Their difference is one nonzero linear functional $\ell(v) = B(v,a)$. Pass 4470 identifies the unique isotropic defect class under the bridge with

$$\boxed{\mathrm{im}(A_{\mathrm{point}} \bmod 2)/C,}$$

the fixed one-dimensional layer already owned by Pass 187 inside the uniserial $H_{10} = 1 \mid 8 \mid 1$ filtration. The single symplectic transvection

$$T_a(v) = v + B(v,a)a$$

repairs the quadratic refinement on all 2^{10} classes, so $T_a \circ \Phi$ is an equivariant quadratic isometry. This transvection is a comparison-map correction; it is not being promoted to a physical gate.

The same mechanism has a sharp generalized-quadrangle boundary. For a finite $GQ(s,t)$, Pass 4465 gives

$$HH^T = (r-\beta)I + (\alpha-\beta)A_* + \beta J, \quad r = \frac{(s+1)s^2t^2}{2}, \quad \alpha = s^2t, \quad \beta = \frac{s(s+1)}{2},$$

whereas point–line incidence always gives $N^TN = (s+1)I + A_*$. Reduction modulo two yields

$$\boxed{HH^T = N^TN \ \text{ over } \mathbb{F}_2 \iff s \equiv 3 \pmod 4 \ \text{ and } t \text{ is odd.}}$$

Thus $W(3,3)$ and the displayed $GQ(3,9)$ orientation satisfy the bridge, while the dual parameter orientation $GQ(9,3)$ does not. The statement is therefore an orientation-sensitive characteristic-two theorem, not a duality invariant and not an explanation of the empirical Ramanujan signing percentages of Pass 4457.

> **Evidence boundary.** The new content is the explicit incidence intertwiner, the fixed-layer quadratic correction, and the exact s mod 4/parity criterion. The $[[40,10,4]]$ code, the $H_{10} = 1 \mid 8 \mid 1$ filtration, and the 528 plus-type count are prior results and remain cited to Passes 201 and 187. No full 20-dimensional logical-Pauli identification, physical apartment measurement protocol, or fault-tolerant gate set follows from this bridge. The executable witnesses are `analysis/w33_pass4469_apartment_css_h10_intertwiner.py`, `analysis/w33_pass4470_apartment_h10_quadrat` and `analysis/w33_pass4471_general_gq_apartment_incidence_bridge.py`.

79.8 Apartment parity beyond the 10-space: module structure, zeta coefficients, and exact thermal duality

Passes 4461–4466 turned the 1620 building apartments into a binary $[1620, 39]$ parity code C whose nondegenerate alternating quotient has dimension 10. The concurrent Passes 4469–4471 identify that quotient with the protected H_{10} label shadow by an incidence map. The present packet asks a different question: what does the native W33 symmetry *do* on that space, and what additional exact structures become visible once the action is computed rather than inferred from the dimension?

Pass 4472: the 10-space has a canonical 1|8|1 filtration. Rebuilding the projective line action from transvections gives the inner $\mathrm{PSp}(4,3)$ image of order 25920 and, after adjoining a similitude, the projective outer extension of order 51840. Both act faithfully on the nondegenerate 10-dimensional apartment quotient. The inner action fixes exactly one line. If v spans that line, symplectic invariance forces the 9-space $v^{\perp}$ to be invariant, and direct computation gives

$$0 < \langle v \rangle < v^{\perp} < H_{10}, \qquad \dim = (1, 9, 10). \tag{18}$$

The composition dimensions are therefore

$$\boxed{1 \mid 8 \mid 1.} \tag{19}$$

The middle 8-dimensional factor is faithful and irreducible for the inner group. Its nonzero vectors form exactly two orbits, of sizes 135 and 120. Thus the new quotient is not an irreducible "mysterious ten": it contains a canonical eight-dimensional core between two trivial one-dimensional factors.

Pass 4473: the apartment Hamiltonian is a code energy exactly. For line-sign bits $b \in \mathbb{F}_2^{40}$ define

$$\mathcal{H}(b) = -W_4(b).$$

Since the apartment syndrome is $H^T b$ and $W_4 = 1620 - 2\,\mathrm{wt}(H^T b)$,

$$\boxed{\mathcal{H}(b) = -1620 + 2\,\mathrm{wt}(H^T b).} \tag{20}$$

Pass 4463 proved $\ker H^T = \langle \mathbf{1}_{40} \rangle$, so the exact ground space has only the two globally reversed constant signings,

$$\boxed{E_0 = -1620, \qquad g_0 = 2.} \tag{21}$$

A one-line flip has code weight 162 and energy -1296. Under independent random line signs the exact energy moments are

$$\mathbb{E}E = 0, \quad \mathrm{Var}\, E = 1620, \quad \mathbb{E}E^3 = -12960, \quad \mathbb{E}E^4 = 9891720.$$

As a deliberately labelled empirical control, 4096 deterministic random line signings (seed 4473) give correlation $\mathrm{corr}(\rho, E) = -0.27752577$ between signed spectral radius and four-spin energy; 26.4648% are Ramanujan in that sample, and their mean energy is 6.5092 versus -0.1475 overall. This modest opposition is consistent with the earlier warning that a spin-glass objective is not a surrogate for Bilu–Linial spectral optimization; the correlation itself is not a theorem.

Pass 4474: three different "four-cycle counts" must remain distinct. The exact W33 census is

$$\boxed{1740 = 1620 + 120,} \tag{22}$$

where 1620 are induced generalized-quadrangle apartments and 120 are simple C_4's lying inside the forty geometric K_4 lines. The historical Pass 4433 common-neighbour helper emits 3480 records because it sees every simple C_4 from both diagonal pairs. Therefore an unqualified statement "W33 has 1620 four-cycles" is safe only when "four-cycle" explicitly means induced quadrangle/apartment. The advisory checker `scripts/check_w33_c4_semantics.py` now scans the repository for this semantic failure mode while allowing historical corrected text to remain in place.

Pass 4475: the apartment observable is an Artin–Ihara coefficient. Let B_σ be the 480×480 signed non-backtracking matrix for a line signing and put $S = \sum_\ell \sigma_\ell$. Exact directed-walk enumeration gives

$$\boxed{\operatorname{tr}(B_\sigma^3) = 24S,} \qquad \boxed{\operatorname{tr}(B_\sigma^4) = 960 + 8W_4.} \tag{23}$$

The fixed $960 = 8 \cdot 120$ is precisely the eight orientations of the 120 line-internal simple C_4's. Therefore, for $L_\sigma(u) = \det(I - uB_\sigma)^{-1}$,

$$\boxed{\log L_\sigma(u) = 8S\,u^3 + (240 + 2W_4)u^4 + O(u^5).} \tag{24}$$

This makes the bridge to the covering-graph Artin–Ihara language literal: the apartment Walsh Hamiltonian is the complete signing-dependent part of the u^4 logarithmic coefficient after the fixed geometric-line contribution is removed. The determinant/L-function context is the standard finite-covering graph framework of Stark and Terras; the W33 coefficient identity above is the new finite calculation.

Pass 4476: low-weight structure of the $[1620, 39]$ apartment code. The primal minimum distance is *not* promoted to a theorem: one line gives $d(C) \le 162$, and exhaustive coefficient supports through five flipped lines find no smaller codeword, but that does not exclude a lower-weight word with larger coefficient support. What is exact is the dual beginning:

$$\boxed{d(C^\perp) = 3, \qquad A_3(C^\perp) = 2160, \qquad A_4(C^\perp) = 84240.} \tag{25}$$

There are no dual words of weight one or two because the 1620 apartment columns are nonzero and distinct; exact XOR enumeration supplies the weight three and four counts. The projective similitude action permutes the apartment coordinates, giving a certified automorphism subgroup of order at least 51840; equality with the full code automorphism group is not claimed.

Pass 4477: the eight-dimensional core reconstructs the old $E_8/2E_8$ carrier. The middle factor admits a unique invariant quadratic refinement under the outer action. It is plus type:

$$\#\{Q = 0\} = 136 \quad (135 \text{ nonzero}), \qquad \#\{Q = 1\} = 120.$$

The polar-orthogonality graphs on the two nonzero classes are exactly

$$\boxed{\mathrm{SRG}(135, 70, 37, 35),} \qquad \boxed{\mathrm{SRG}(120, 63, 30, 36).} \tag{26}$$

More discriminatingly, a nonsingular-vector stabilizer has order 216 in the inner group and suborbits $1, 1, 1, 27, 27, 27, 36$; adjoining the outer action doubles it to order 432 and changes the suborbits to $1, 2, 27, 36, 54$. Those are exactly the corrected fingerprints already used in this repository for the transitive code embedding of the $E_8/2E_8$ plus-type carrier after the Pass 1070 orbit/suborbit retraction. Thus apartment parity supplies a new construction of that old carrier, not merely another occurrence of the numbers 135 and 120.

Pass 4478 (outside the box): a real four-qubit Pauli phase-space shadow. An explicit hyperbolic basis puts the invariant quadratic into the canonical form

$$\boxed{Q(a_1, b_1, \ldots, a_4, b_4) = \sum_{i=1}^{4} a_i b_i \pmod 2.} \tag{27}$$

For real four-qubit Pauli classes this quadratic records the parity of the number of Y factors: the nonidentity even-parity/symmetric classes number 135, while the odd-parity/skew classes number 120. The executable witness checks the isometry on all 256 vectors. This matches the established finite geometry of the real four-qubit Pauli group described by Saniga, Levay and Pracna. It is a finite phase-space isometry only; it does not say that the 1620-coordinate apartment code is physically implemented by four qubits.

Pass 4479 (outside the box): MacWilliams is an exact thermal transform. Let $W_C(z) = \sum_{c\in C} z^{\mathrm{wt}(c)}$. Since every codeword has exactly two line-sign preimages,

$$\boxed{Z(\beta) = \sum_{b\in\mathbb{F}_2^{40}} e^{-\beta\mathcal{H}(b)} = 2e^{1620\beta} W_C(e^{-2\beta}).} \tag{28}$$

Together with the two-variable MacWilliams identity

$$\boxed{W_C(x,y) = |C^\perp|^{-1} W_{C^\perp}(x+y, x-y),} \tag{29}$$

this is a literal finite coding/statistical-mechanics duality for the apartment Hamiltonian. No thermodynamic-limit phase transition is asserted; the exact content is the finite partition-function transform.

Evidence boundary. Passes 4472–4479 are regenerated by `analysis/w33_pass4472_4479_apartment_module_thermo_ihara_pauli.py` and frozen in `data/PART_W33_PASS4472_4479_APARTMENT_MODULE_THERMO_IHARA_PAULI.json`. All module orders, filtrations, orbit sizes, quadratic types, SRG parameters, Hashimoto traces, dual low-weight counts, and finite partition-function identities are exact computations. The 4096-sample spectral/energy correlation is explicitly empirical. No physical gauge field, physical four-qubit machine, E_8 dynamics, continuum temperature, or spectral optimality is inferred from the finite identifications alone.

79.9 Geometric generators and optimal protected readout (Passes 4480–4483)

Pass 4480 evaluates the incidence bridge of Pass 4469 on the forty geometric lines. For line ℓ,

$$g_\ell = H^T e_\ell, \qquad x_\ell = N e_\ell,$$

where g_ℓ is the weight-162 apartment-incidence signature and x_ℓ is the weight-4 line incidence vector. Pass 201 already owns the minimum logical interpretation of the latter. The bridge now gives the literal line-by-line map $[g_\ell] \mapsto [x_\ell]$. The forty classes are distinct, span H_{10}, and both forty-sets have polar Gram matrix A_*, the dual W33 line-collinearity graph.

Their natural quadratic readings differ uniformly:

$$q_{\mathrm{ap}}(g_\ell) = 1, \qquad q_{H_{10}}(x_\ell) = 0.$$

The fixed isotropic class f of Pass 4470 is the unique H_{10} class with $B(x_\ell, f) = 1$ for all forty lines. Therefore the fixed-layer transvection maps the singular W33 set $\{x_\ell\}$ to the disjoint anisotropic W33 set $\{x_\ell + f\}$ without changing the polar graph. This is a finite quadratic-space twin, not a second physical code.

Pass 4481 resolves the 29-dimensional radical. In line-coordinate space let

$$R = \ker N, \quad I = \mathrm{im}\, A_*, \quad K = \ker A_*, \quad U = R \cap I, \quad S = R + I, \quad J = \langle \mathbf{1} \rangle.$$

The exact dimensions are

$$\dim(J, U, S, K) = (1, 9, 16, 30),$$

and the apartment-code extension is

$$\boxed{0 \to K/J\ (29) \to C_{\mathrm{ap}}\ (39) \to H_{10}\ (10) \to 0.}$$

The radical filtration has layer profile

$$\boxed{8 \mid (6 \oplus 1) \mid 14.}$$

Exhaustive cyclic-span tests for two generators of $PSp(4, 3)$ certify the 8-, 6-, and 14-dimensional factors as irreducible over $\mathbb{F}_2$; the one-dimensional factor is trivial. No uniserial claim is made.

Pass 4482 gives a sparse geometric basis of the protected quotient. In the repository's lexicographic line order,

$$\boxed{1, 5, 14, 15, 19, 23, 24, 33, 35, 39}$$

have nonsingular alternating Gram matrix and induced intersection graph

$$\boxed{P_4 \sqcup 3K_2,}$$

with only six intersecting pairs. Six is optimal: five edges would force an induced $5K_2$, while exact search gives induced-matching number four for W33. If g_i are these ten apartment signatures and $G = (\langle g_i, g_j \rangle)$, then for an acquired apartment syndrome y the ten software parity bits

$$p_i = \langle y, g_i \rangle, \qquad c = pG^{-1}$$

recover all 2^{10} protected classes. Ten bits are information-theoretically minimal for injective linear readout of a 10-dimensional quotient, but each p_i is an XOR of 162 apartment bits: this is post-processing, not a theorem that ten physical measurements suffice.

Pass 4483 records the rediscovery boundary. The CSS code, its forty minimum logical lines, the $H_{10} = 1 \mid 8 \mid 1$ filtration and the plus-type form are prior repository results. Searches of relevant primary incidence-module and generalized-quadrangle code literature did not reveal the exact bridge above; this is recorded only as "no occurrence found in the searched sources," not as proof of global novelty.

79.10 The repeated eight-core and the nonsplit apartment extension (Passes 4485–4488)

Let $M = \mathbb{F}_2^{40}$ be the W33 line module, $A_* = N^T N \bmod 2$, $K = \ker A_*$, $I = \operatorname{im} A_*$, $R = \ker N$, $U = R \cap I$, and $J = \langle \mathbf{1} \rangle$. Pass 4481 gives

$$\dim(J, U, I, K, M) = (1, 9, 10, 30, 40).$$

Since $A_*^2 = 0$, $I \subset K$, while A_* induces the equivariant isomorphism

$$\overline{A}_* : M/K \xrightarrow{\sim} I.$$

The protected quotient $M/K \cong H_{10}$ therefore has the literal filtration

$$0 < J < U < I, \qquad 1 \mid 8 \mid 1.$$

The protected middle eight-space itself is *not* new here: Pass 176 already proved the incidence-fixed-line quadratic isometry from $f^{\perp}/\langle f\rangle$ onto the route hull U/J (in its route-code notation), including the plus-type 136/120 census. The new apartment-side statement is that this same pre-existing U/J also sits as an invariant submodule of the newly discovered apartment radical K/J. Thus one owned eight-core appears on both sides of

$$0 \to K/J\ (29) \to M/J\ (39) \to M/K\ (10) \to 0.$$

Pass 4486 compares the two *newly juxtaposed* form structures. On the radical occurrence, the apartment polar form and its Hamming quadratic refinement vanish identically on U/J. On the protected occurrence, the Pass-176 form can be written through $\overline{A}_*$ as

$$B_{\mathrm{prot}}(A_*b, A_*c) = b^T A_* c, \qquad q_{\mathrm{prot}}(A_*b) = \frac{\mathrm{wt}(Nb)}{2} \pmod 2.$$

These expressions are lift-independent. On U/J the protected polar form has rank eight and the quadratic has

$$136 = 1 + 135 \text{ singular classes}, \qquad 120 \text{ anisotropic classes},$$

reproducing the prior Pass-176 plus-type $O^+(8,2)$ result. The new conclusion is therefore the contrast: the same owned module is form-null in the apartment radical and nondegenerate when viewed through the protected quotient.

Pass 4487 is a reconciliation certificate, not a new claim of the eight-core itself. It places the independent Passes 4477–4478 implementation in the same ambient line coordinates and proves

$$\boxed{B_{10}v = \mathbf{1}, \qquad B_{10}v^{\perp} = U.}$$

In the resulting quotient basis, the parallel F_8 Gram matrix equals the Pass-176/lift-defined protected Gram matrix entry by entry, and the parallel invariant quadratic q_8 equals $\mathrm{wt}(Nb)/2$ on all 256 classes. Hence Passes 176 and 4477–4478 are exact coordinate realizations of the same route-hull U/J; Passes 4485–4487 add its apartment-radical placement and cross-packet consistency check. No E8 dynamics or Pauli hardware is imported into the radical copy.

Finally, Pass 4488 tests whether the apartment extension splits equivariantly. Write $E = M/J$, $V = M/K$, and $\Pi : E \to V$. A $PSp(4,3)$-equivariant section S would obey

$$\Pi S = I_{10}, \qquad G_E S = S G_V$$

for four generators. The resulting 1660 affine binary equations in 390 unknown entries satisfy

$$\boxed{\mathrm{rank}\, A = 389, \qquad \mathrm{rank}[A \mid b] = 390,}$$

so no equivariant section exists. Moreover

$$\dim \mathrm{Hom}_{PSp(4,3)}(V, E) = 1.$$

Its unique nonzero map has rank nine, projects to zero in V, and is exactly

$$\boxed{T([b]) = [A_*b] \pmod J,}$$

with image I/J inside the radical and one-dimensional kernel. Thus the only nonzero symmetry-preserving return channel folds the protected module back into the radical; there is no invariant ten-dimensional protected complement. This nonsplitting result is new relative to the earlier route-hull bridge and does not forbid non-equivariant decoding or symmetry-breaking hardware.

79.11 Fixed-point obstruction and the cocycle-support code (Passes 4490–4492)

Pass 4488 proved computationally that the apartment extension

$$0 \to K/J\ (29) \to E = M/J\ (39) \to V = M/K \cong H_{10}\ (10) \to 0$$

does not split $PSp(4,3)$-equivariantly. Pass 4490 reduces the 1660-equation certificate to a fixed-point obstruction. The transitive 40-line permutation module M has fixed space exactly $J = \langle \mathbf{1} \rangle$, hence

$$\boxed{E^{PSp} = 0.}$$

By contrast, the protected $H_{10} = 1 \mid 8 \mid 1$ module has a unique fixed line, so

$$\boxed{V^{PSp} \cong \mathbb{F}_2.}$$

An equivariant section would have to lift the nonzero fixed class of V to a nonzero fixed class of E, which is impossible. Equivalently, the connecting map in fixed-point/cohomology

$$V^{PSp} \longrightarrow H^1(PSp(4,3), K/J)$$

is nonzero on the one-dimensional fixed line.

Pass 4491 localizes a representative of this extension cocycle. For a lift $e \in E$ of the protected fixed vector $v \in V$, define

$$c_g = G_E(g)e - e.$$

The $PSp(4,3)$-module generated by the defects c_g has dimension 23 and is exactly

$$\boxed{(K \cap R^{\perp})/J,}$$

where $R = \ker N$ is the route code and $R^{\perp} = \operatorname{rowspace} N$. Its ambient invariant chain

$$J < U < I < K \cap R^{\perp}$$

has dimensions

$$1 < 9 < 10 < 24,$$

so the cocycle support has profile

$$\boxed{8 \mid 1 \mid 14.}$$

Affine support equations show that this cocycle cannot be gauge-shifted into I/J (dimension nine): the coefficient and augmented ranks differ by one. It can be represented inside $(K \cap R^{\perp})/J$. Hence the route-side six-dimensional factor of the full radical profile $8 \mid (6 \oplus 1) \mid 14$ is not required by this fixed-line obstruction.

Pass 4492 resolves the 23-space in terms of older certified code objects. Let $C = \ker N^T$ be the Pass-201 $[40, 15, 8]$ sentinel code and let $U = R \cap R^{\perp}$ be the Pass-176 route hull. Incidence restricts to the exact sequence

$$\boxed{0 \to U\ (9) \to K \cap R^{\perp}\ (24) \xrightarrow{N} C\ (15) \to 0.}$$

The image is all of C and the kernel is exactly U. Since $J \subset U$,

$$\boxed{0 \to U/J\ (8) \to (K \cap R^{\perp})/J\ (23) \to C\ (15) \to 0.}$$

Pass 176 owns the route-hull U/J eight-core; Pass 201 owns the sentinel code; Pass 187 owns the fixed-line/irreducible-14 filtration of C. The new conclusion is their exact incidence weld inside the apartment nonsplitting cocycle: the profile $8 \mid 1 \mid 14$ is structurally

$$\boxed{\text{route-hull } 8 \ \mid \ \text{sentinel } (1 \mid 14).}$$

These are module/cohomology statements only. They do not identify a physical error current, an energy-transfer channel, or a hardware fault path.

79.12 Corrected symmetry-breaking boundary for the nonsplit apartment extension (Passes 4493, 4503–4504)

The full $PSp(4,3)$ action forbids an equivariant section of

$$0 \to K/J \ (29) \to E = M/J \ (39) \to V = M/K \cong H_{10} \ (10) \to 0,$$

with the reproducible full-group ranks

$$\operatorname{rank} A = 389, \qquad \operatorname{rank}[A \mid b] = 390.$$

A later adversarial re-execution (Pass 4503) found that the originally frozen Pass 4493 restricted-subgroup table was a false positive. The historical $370 = 370$ point/line claim is withdrawn. Exact reconstruction from the same $GF(3)^4$ geometry gives

H	$\lvert H\rvert$	$\operatorname{rank} A / \operatorname{rank}[A \mid b]$
line stabilizer	648	386/387
point stabilizer	648	387/388
incident flag stabilizer	162	384/384
apartment setwise stabilizer	16	357/358.

Thus neither order-648 maximal geometric stabilizer selects a protected complement. The canonical incident-flag stabilizer does: its section family is six-dimensional, hence contains exactly $2^6 = 64$ equivariant sections.

Pass 4503 extends the correction beyond these geometric examples: representatives of all five maximal subgroup types of $PSp(4,3)$, of orders

$$960, \ 720, \ 648, \ 648, \ 576,$$

retain the obstruction. Pass 4504 exhausts the 64 flag-equivariant sections and finds a canonical-coordinate optimum of total ambient Hamming weight 42, maximum column weight 9, and union support 13 lines. These are software gauge representatives in $E = M/J$, not physical measurement or decoder costs.

The corrected architectural statement is therefore

$$\boxed{\text{full symmetry and every maximal subgroup type tested} \Rightarrow \text{protected sector remains quotient-only,}}$$

whereas

$$\boxed{\text{fix an incident point–line flag} \Rightarrow \text{an equivariant 10D representative section exists.}}$$

The order-162 flag is a verified splitting subgroup; this does not by itself classify every subgroup or prove 162 is the globally largest splitting order.

79.13 Distance, extension cohomology, higher graph primes, and prism self-reconstruction (Passes 4495–4502)

The apartment-parity programme now admits three independent descriptions of the same finite object: a binary code on the 1620 building apartments, a protected quotient H_{10}, and a line-signing Walsh Hamiltonian. Passes 4495–4502 close several of the remaining exact questions while retaining the evidence boundary established in Passes 4461–4494.

Pass 4495: the apartment code is exactly $[1620, 39, 162]$. Write a line signing as $\sigma_\ell = (-1)^{b_\ell}$ and

$$W_4(\sigma) = \sum_{a \in \mathcal{A}} \prod_{\ell \in a} \sigma_\ell, \qquad \mathrm{wt}(H^T b) = \frac{1620 - W_4(\sigma)}{2}.$$

The only kernel of $b \mapsto H^T b$ is global reversal, so fix $\sigma_0 = +1$ and search the remaining 2^{39} assignments exactly. At every partial assignment the quartic Walsh polynomial is collected by its residual monomials,

$$P = c_0 + \sum_{M \neq \varnothing} c_M \chi_M, \qquad P \leq c_0 + \sum_{M \neq \varnothing} |c_M|,$$

which gives a rigorous branch-and-bound certificate. Only the all-positive word has $W_4 > 1296$; exactly forty nonzero codewords have $W_4 = 1296$. Therefore

$$\boxed{C_{\mathrm{ap}} = [1620, 39, 162], \qquad A_{162} = 40.}$$

The same exact traversal gives the beginning of the weight enumerator

$$\boxed{W_C(z) = 1 + 40z^{162} + 240z^{270} + 540z^{312} + 200z^{324} + \cdots.}$$

No extrapolation from low coefficient support is used in the distance proof.

Pass 4496: the protected $1|8|1$ module has a complete cohomological label. Passes 4488 and 4490–4494 proved nonsplitting and localized concrete cocycles. Let V_8 be the irreducible middle factor of H_{10}. Propagating symbolic 1-cocycles over all 25920 elements of $PSp(4,3)$ from five geometric generators gives

$$\dim Z^1(PSp(4,3), V_8) = 10, \qquad \dim B^1(PSp(4,3), V_8) = 8,$$

and hence

$$\boxed{\dim H^1(PSp(4,3), V_8) = 2.}$$

The outer projective similitude exchanges a chosen basis of this two-space, so there is exactly one nonzero outer-invariant class, represented by their sum. After identifying $V_8^* \simeq V_8$ with the invariant symplectic form, the two adjacent extensions in

$$H_{10} = 1|8|1$$

both represent this same outer-fixed nonzero class. Independently, scanning all 1023 nonzero vectors gives cyclic-span dimensions

$$1^1, \qquad 9^{510}, \qquad 10^{512};$$

thus the invariant-submodule lattice is exactly

$$\boxed{0 < 1 < 9 < 10,}$$

so the displayed $1|8|1$ is genuinely uniserial, not merely a composition-factor list.

Pass 4497: the first new graph-prime invariant occurs at u^5. Let B_σ be the signed Hashimoto matrix, $T_k = \operatorname{tr}(A_\sigma^k)$, and let $C_n(\sigma)$ denote the signed sum over oriented primitive nonbacktracking prime classes of length n. Bass recurrence gives, through length eight,

$$\begin{aligned}
\operatorname{tr} B_\sigma^3 &= T_3,\\
\operatorname{tr} B_\sigma^4 &= T_4 - 11040,\\
\operatorname{tr} B_\sigma^5 &= T_5 - 55T_3,\\
\operatorname{tr} B_\sigma^6 &= T_6 - 66T_4 + 416640,\\
\operatorname{tr} B_\sigma^7 &= T_7 - 77T_5 + 1694T_3,\\
\operatorname{tr} B_\sigma^8 &= T_8 - 88T_6 + 2420T_4 - 9050400.
\end{aligned}$$

Consequently

$$\boxed{\log L_\sigma(u) = 8Su^3 + (240 + 2W_4)u^4 + C_5u^5 + (160 + C_6)u^6 + C_7u^7 + (1740 + C_8)u^8 + O(u^9),}$$

where $S = \sum_\ell \sigma_\ell$. The constants at u^6 and u^8 are the fixed repetitions of primitive triangles and primitive four-cycles.

The 18144 simple point-graph pentagons have an unexpectedly rigid line-shadow. After reducing their five edge-line labels modulo two, exactly 2160 distinct supports are induced P_3's in the dual W33 graph and each occurs six times, while 5184 distinct supports induce a dual C_5 and each occurs once. Hence, for the undirected pentagon holonomy sum,

$$\boxed{U_5 = 6W_{P_3} + W_{C_5^*}, \qquad C_5 = 2U_5.}$$

Under independent random line signs these Walsh characters are orthogonal: $\mathbb{E}U_5 = 0$, $\operatorname{Var}(U_5) = 82944 = 288^2$, and $\operatorname{Cov}(S, U_5) = \operatorname{Cov}(W_4, U_5) = 0$. Two explicit signings in the certificate have the same $S = -2$ and $W_4 = 8$ (apartment weight 806) but $U_5 = 600$ and -136, respectively. Thus

$$\boxed{u^5 \text{ is the first coefficient not determined by } S \text{ and } W_4.}$$

The unsigned oriented primitive-prime counts at lengths $3, \dots, 8$ are $320, 3480, 36288, 302880, 2739840, 26750160$.

Pass 4498: an explicit four-qubit Clifford lift of the protected eight-core. A computed hyperbolic basis carries the unique invariant plus-type quadratic to

$$\boxed{q(x, z) = x_1z_1 + x_2z_2 + x_3z_3 + x_4z_4 \pmod 2.}$$

In those coordinates all five inner $PSp(4, 3)$ generators and the outer similitude are explicitly conjugated into $Sp(8, 2)$. Each is then factored into binary symplectic transvections $T_v : x \mapsto x + B(x, v)v$; the five inner words have length six and the outer word has length four. Interpreting v as a four-qubit Pauli label, T_v is the projective Clifford action of a $\pi/4$ Pauli rotation. The exact Pauli words are frozen in the certificate. This is a finite Clifford-label realization of the eight-core; it is not a claim that the 1620-bit apartment code has been implemented as four physical qubits.

Pass 4499: exact low-temperature expansion, with the full enumerator still open. Combining Pass 4479 with the now-proved low weights gives

$$Z(\beta) = 2e^{1620\beta}\Big[1 + 40e^{-324\beta} + 240e^{-540\beta} + 540e^{-624\beta} + 200e^{-648\beta} + R(\beta)\Big],$$

where

$$R(\beta) = \sum_{w>324} A_w e^{-2\beta w}.$$

The complete 2^{39} weight enumerator is *not* claimed computed; this pass upgrades the low-temperature series exactly and leaves the remaining coefficients as a sharply stated coding problem.

Pass 4500 (outside the box): the code reconstructs W33 from its minimum words. The forty minimum words are exactly the forty line-star rows of H. For two of them the Hamming distance is 270 precisely when the corresponding dual W33 lines intersect, and 312 when they are disjoint. Hence the code alone reconstructs the dual line-collinearity graph from its minimum-weight shell. Moreover the 1620 apartment columns have distinct forty-bit incidence patterns, so an apartment-coordinate automorphism acting trivially on the minimum shell is itself trivial. Therefore

$$\mathrm{Aut}(C) \hookrightarrow \mathrm{Aut}(W(3,3)).$$

The natural projective similitude action supplies a subgroup of order 51840; using the repository's independently certified theorem $\mathrm{Aut}(W(3,3)) = PGSp(4,3)$ of order 51840 gives

$$\boxed{\mathrm{Aut}(C) = PGSp(4,3), \qquad |\mathrm{Aut}(C)| = 51840.}$$

This replaces Pass 4476's lower bound by an exact automorphism theorem.

Pass 4501 (outside the box): dual minimum checks are triangular prisms. The 2160 weight-three words of $C^\perp$ are triples of apartment columns a, b, c with $a + b + c = 0$. Every pair of their four-line supports intersects in two lines; their union consists of six dual-W33 lines inducing a triangular prism. The three apartments are exactly the prism's three rectangular faces. Conversely every certified relation has this form. Thus

$$\boxed{\{c \in C^\perp : \mathrm{wt}\, c = 3\} \longleftrightarrow \{2160 \text{ triangular prisms in dual } W33\}.}$$

The span of these minimum dual checks has rank only 1215, strictly below $\dim C^\perp = 1581$. Prism checks therefore do *not* generate the entire dual code; the negative is part of the theorem.

Pass 4502 (outside the box): a prism-induced protected 240-orbit. The six-line coefficient set of every such prism gives a primal apartment word of weight 534. Project the same six-line indicator through A_* into the protected quotient. The 2160 prisms collapse exactly 9-to-1 onto

$$\boxed{240 \text{ distinct protected vectors, each of ambient weight } 20.}$$

$PSp(4,3)$ is transitive on this set; a stabilizer has order 108 and suborbit profile

$$\boxed{1, 1, 2, 2, 18, 18, 18, 18, 27, 27, 54, 54.}$$

The profile is recorded precisely so that the object is not identified with an E8-root carrier, a W33-edge carrier, or any other 240-set merely because the cardinality agrees.

Rediscovery and literature boundary. Classical generalized-quadrangle code literature studies point/line incidence codes and their modular ranks, while the present code has the 1620 building apartments as coordinates. The executable claims above are therefore presented as repository-certified finite theorems; absence of the exact construction in a targeted literature search is not used as proof of global novelty. Likewise the Artin–Ihara terminology supplies the standard graph-covering language, not a claim that a physical gauge field has been derived.

79.14 Maximal-subgroup obstruction and the corrected flag gauge (Passes 4503–4504)

Adversarial re-execution of the Pass 4493 restricted section systems corrected a false positive without changing the full-group nonsplitting theorem. For the exact extension

$$0 \to K/J\ (29) \to E = M/J\ (39) \to H_{10}\ (10) \to 0,$$

representatives of all five maximal subgroup types of $PSp(4,3)$ remain nonsplit. Their orders and coefficient/augmented ranks are

$\lvert H\rvert$	$[PSp(4,3) : H]$	$\operatorname{rank} A/\operatorname{rank}[A \mid b]$
960	27	388/389
720	36	386/387
648	40	386/387
648	40	387/388
576	45	386/387.

The two order-648 rows are the line and point stabilizers respectively. Thus the historical $370 = 370$ point/line claim is withdrawn. The canonical incident point–line flag stabilizer has order 162 and instead gives

$$\boxed{\operatorname{rank} A = \operatorname{rank}[A \mid b] = 384},$$

with a six-dimensional affine family, hence exactly 64 equivariant sections. Exhaustive optimization of those 64 sections in the canonical quotient basis gives total minimal ambient Hamming weight 42, maximum column weight 9, and minimum union support 13 lines.

79.15 The full radical carries two obstruction bits (Pass 4505)

For the complete apartment radical $R_{29} = K/J$, an exact full-Cayley-graph cocycle computation gives

$$\dim Z^1(PSp(4,3), R_{29}) = 31, \qquad \dim B^1(PSp(4,3), R_{29}) = 29,$$

and therefore

$$\boxed{H^1(PSp(4,3), R_{29}) \cong \mathbb{F}_2^2.}$$

All three nonzero classes generate the same 23-dimensional support module

$$W/J = (K \cap \operatorname{row} N)/J,$$

which Pass 4492 already resolved as the route-hull/sentinel extension with profile $8 \mid (1 \mid 14)$. In particular, the remaining six-dimensional radical factor is absent from the module closure of every nonzero class. This is $H^1(G, R_{29})$ and must not be confused with a computation of the entire $\operatorname{Ext}^1_G(H_{10}, R_{29})$ group.

79.16 The apartment bridge scales from 10 to 70 (Pass 4506)

The independent $Q(5,3) = GQ(3,9)$ builder gives 112 points, 280 lines and 102060 building apartments. Over $\mathbb{F}_2$,

$$\operatorname{rank} H = 279, \qquad \operatorname{rank} N = 91, \qquad \operatorname{rank}(N^T N) = 70,$$

with the exact entrywise identity

$$HH^T = N^T N.$$

Consequently the apartment code has a 209-dimensional radical and a 70-dimensional nondegenerate quotient, canonically identified by incidence with

$$\operatorname{im} N / \ker N^T, \qquad 91 - 21 = 70.$$

The dual $GQ(9,3)$ orientation fails sharply on the same building: its apartment Gram has rank 1 (indeed it is the all-ones matrix), whereas the dual incidence Gram has rank 22. This concretely confirms the characteristic-two orientation criterion rather than treating duality as automatic.

79.17 Three outside-box consequences (Passes 4508–4510)

First, Pass 4496 and Pass 4505 produce two different two-dimensional cohomology spaces. For the protected irreducible eight-core, the $PGSp$ outer involution swaps an H^1 basis, leaving one nonzero class fixed. For the full radical R_{29}, the outer involution acts trivially on H^1, so all three nonzero classes are outer-fixed. Equal dimension therefore does not identify the two outer modules.

Second, restriction of the two radical obstruction bits explains the corrected symmetry threshold. The order-960, 720, and 576 maximals kill no nonzero class. A point stabilizer kills one one-dimensional obstruction subspace, while a line stabilizer kills a distinct one. Their incident intersection, the order-162 flag stabilizer, kills all of $H^1(G, R_{29})$. Thus a point or line removes one obstruction charge; a flag removes both.

Third, the 13-line minimum support of the optimized flag section is exactly the closed neighborhood of the fixed flag line in the W33 line-intersection graph. Its induced graph is

$$\boxed{K_1 \vee 4K_3},$$

one center line together with the four pencils of three other lines through its four points. Hence the valid symmetry-broken representative register can be chosen inside a single radius-one W33 line cell. This is finite-graph locality, not automatically spatial, optical or energetic locality in hardware.

79.18 Dual completion, induced-subgraph enumerators, and higher zeta tomography (Passes 4511–4518)

Passes 4495–4502 proved $C_{\mathrm{ap}} = [1620, 39, 162]$, identified the 2160 minimum dual words with triangular prisms, and left a 366-dimensional gap between their rank-1215 span and $\dim C_{\mathrm{ap}}^{\perp} = 1581$. The present packet closes that dual gap, identifies the prism-induced 240-set by an explicit equivariant map, pushes the signed Ihara hierarchy through lengths six–eight, and separates what can and cannot yet be proved about the complete weight enumerator and the larger $GQ(3,9)$ apartment code.

Pass 4511: weight four closes the entire missing dual sector. There are exactly 84240 weight-four words of $C_{\mathrm{ap}}^{\perp}$. Their binary span has dimension

$$\boxed{1580},$$

which is exactly the even-coordinate-weight subcode of the 1581-dimensional dual. Adding any odd weight-three prism word therefore gives all of $C_{\mathrm{ap}}^{\perp}$. Equivalently,

$$\boxed{\langle C_{(4)}^{\perp} \rangle = C_{\mathrm{even}}^{\perp}, \qquad \langle C_{(3)}^{\perp}, C_{(4)}^{\perp} \rangle = C^{\perp}.}$$

Under $PGSp(4,3)$ the 84240 weight-four relations split into nine orbits of sizes

$$1620, 1620, 3240, 6480, 6480, 12960, 12960, 12960, 25920.$$

The final orbit alone supplies all 366 dimensions missing from the prism span. Under the inner $PSp(4,3)$ action that same 25920-set is a regular orbit, so a single weight-four seed and its full inner orbit already span the complete 1580-dimensional even dual code.

Pass 4512: the full enumerator reduces exactly to four W33 statistics, but is not yet numerically closed. For a coefficient subset S of the forty dual-W33 line vertices write $m = |S|$, let $e(S)$ count induced dual-W33 edges, $p_3(S)$ induced P_3 triples, and $c_4(S)$ induced apartment quadrangles. Expanding odd apartment intersection parity by

$$\mathbf{1}_{j \text{ modd}} = \binom{j}{1} - 2\binom{j}{2} + 4\binom{j}{3} - 8\binom{j}{4}$$

and using the exact apartment incidences gives

$$\boxed{\mathrm{wt}(H^T 1_S) = 162m - 12\binom{m}{2} - 42e(S) + 12p_3(S) - 8c_4(S).}$$

Hence the complete enumerator is exactly the induced-subgraph sum

$$\boxed{W_C(z) = \frac{1}{2} \sum_{S \subseteq V(W33)} z^{162|S| - 12\binom{|S|}{2} - 42e(S) + 12p_3(S) - 8c_4(S)}.}$$

The factor $1/2$ is the global-complement kernel. Burnside on $\mathrm{Aut}(C) = PGSp(4,3)$, whose action on the forty coefficients has 25 cycle types, leaves 21578952 subset orbits and

$$\boxed{10789604}$$

codeword orbits after also quotienting by complement. This is a rigorous reduction of the remaining exact computation, *not* a completed numerical coefficient table. The full weight enumerator therefore remains open.

Pass 4513: the prism 240-orbit is exactly the W33 edge action. Let a prism have six-line indicator b. For every prism there is a unique adjacent dual-line pair $i \sim j$ such that

$$\boxed{A_* b = A_*(e_i + e_j).}$$

Conversely all 240 adjacent pairs occur. Thus the protected 240-set of Pass 4502 is equivariantly the dual-W33 edge set, rather than merely another set of cardinality 240. Every edge has exactly nine prism preimages. Its two endpoints lie outside each six-line prism and each endpoint meets exactly three of the prism lines. The inner edge stabilizer has order 108 and the previously observed suborbit fingerprint

$$1, 1, 2, 2, 18, 18, 18, 18, 27, 27, 54, 54,$$

while the outer extension has stabilizer order 216 and suborbits $1, 1, 4, 18, 18, 18, 18, 27, 27, 108$. In particular this explicit edge map prevents a count-only identification with the distinct E_8 root action.

Pass 4514: primitive lengths six–eight have exact parity-support decompositions. A meet-in-the-middle diagonal nonbacktracking trace, transported by directed-edge transitivity, decomposes every signed primitive coefficient into Walsh characters of line-parity supports. After removing repetitions of shorter primes, the unsigned oriented primitive counts remain

$$N_6 = 302880, \qquad N_7 = 2739840, \qquad N_8 = 26750160.$$

The nonzero support characters occupy respectively 10, 26, and 142 $PSp(4,3)$ orbits. By support size the primitive-class masses are

n	$\lvert S\rvert = 0$	2	4	6	8
6	480	86400	129600	86400	0
8	61200	1715040	8598960	11975040	4399920

and for odd length seven

$$|S| = 1,3,5,7: \qquad 121920,\ 648000,\ 1296000,\ 673920.$$

These are exact finite orbit sums, not sampled prime statistics.

Pass 4515: $Q(5,3) = GQ(3,9)$ scales the code, but its distance equality remains open. Pass 4506 already owns the exact 112-point, 280-line, 102060-apartment construction and its 70-dimensional apartment/protected quotient. The new code question starts from its rank-279 apartment incidence matrix. Every line row has weight 1458, and for a coefficient subset S in the 280-vertex line-intersection graph,

$$\boxed{\mathrm{wt}(H^T 1_S) = 1458m - 12\binom{m}{2} - 150e(S) + 36p_3(S) - 8c_4(S).}$$

The exact support-two weights are 2754^{5040} and 2904^{34020}; the support-three spectrum is

$$3888^{13440}, \quad 4074^{136080}, \quad 4188^{1088640}, \quad 4338^{2381400}.$$

A universal lower bound excludes every coefficient support size $2 \le m \le 12$ from beating the line word. After fixing complement symmetry, any counterexample to $d = 1458$ must therefore have support between 13 and 140. Accordingly

$$\boxed{d \le 1458 \quad \text{and equality remains OPEN.}}$$

The dual side does close: its minimum distance is 3, with exactly

$$\boxed{544320 = 4536\binom{10}{3}}$$

minimum words, again the three rectangular apartment faces of triangular prisms. Here 4536 is the number of noncollinear point pairs and the ten choices around such a pair are the $t+1$ common neighbors.

Pass 4516 (outside the box): each W33 edge carries an affine nine-sheet prism fiber. The order-108 inner edge stabilizer acts on the nine prism preimages with image order 36 and kernel order 3. The image has element-order census

$$1^1, \quad 2^9, \quad 3^8, \quad 4^{18}.$$

Its identity plus eight order-three elements form a normal regular translation subgroup C_3^2, while a fiber-point stabilizer is cyclic of order four. Thus

$$\boxed{G_{\text{fiber}} \cong C_3^2{:}C_4, \qquad 1 \to C_3 \to G_{\text{edge}} \to C_3^2{:}C_4 \to 1.}$$

This is an action-theoretic explanation of the nine-to-one prism projection, not a physical nine-state subsystem.

Pass 4517 (outside the box): one regular orbit generates the even dual code. A representative weight-four relation in the regular inner orbit uses eight lines whose induced dual-W33 subgraph has fourteen edges, two triangles and degree sequence

$$3, 3, 3, 3, 4, 4, 4, 4.$$

Its four apartment supports have pairwise intersection sizes $0, 0, 2, 2, 2, 2$. The 25920 $PSp(4, 3)$ translates of this one relation span rank 1580. Hence a single orbit seed is a symmetry-complete generator for the entire even dual sector.

Pass 4518 (outside the box): the sixth Ihara coefficient reconstructs W33. Inside the primitive length-six Walsh polynomial, the degree-two coefficient is 252 for the 240 adjacent line pairs and 48 for the 540 disjoint pairs. Therefore its off-diagonal quadratic-coefficient matrix is exactly

$$\boxed{48(J - I) + 204A_*.}$$

So the two-body Walsh layer of C_6 alone reconstructs the dual-W33 adjacency matrix. Together with Pass 4513 this gives two independent reconstructions of the same substrate: the prism projection recovers its edge action, while the length-six zeta coefficient recovers its adjacency.

> **Evidence boundary.** Passes 4511, 4513–4514 and 4516–4518 are exact finite code/group/zeta statements. Pass 4512 gives an exact enumerator formula and exact Burnside search size but does not close the full numerical weight enumerator. Pass 4515 proves the displayed $Q(5, 3)$ formulas, support bounds and dual minimum relations but does not prove $d = 1458$. The 240 identification is accepted only because an explicit equivariant edge map is constructed; no E_8-root identification or physical gauge interpretation follows from the counts.

79.19 The splitting flag is the Sylow-3 normalizer/Borel (Pass 4519)

Passes 4503–4504 corrected the symmetry-breaking threshold from a single point or line to an incident point–line flag. Pass 4519 identifies that order-162 subgroup internally, not from its order alone. Let H be the canonical flag stabilizer in the exact 25920-element $PSp(4, 3)$ action. Its unique Sylow-3 subgroup P has

$$|P| = 81, \qquad [H : P] = 2.$$

Two generators suffice for P. Normalizing those generators in the full group gives

$$\boxed{N_{PSp(4,3)}(P) = H, \qquad |N_{PSp(4,3)}(P)| = 162.}$$

Thus the verified splitting subgroup is precisely the chamber/Borel subgroup, equivalently the Sylow-3 normalizer for this W33 building action. Its element orders are distributed as

$$1^1,\ 2^9,\ 3^{44},\ 6^{72},\ 9^{36},$$

while the Sylow subgroup itself has $1^1, 3^{44}, 9^{36}$.

Combining with Pass 4509, restriction to this Borel kills the full 2-dimensional radical H^1 obstruction: all three nonzero classes become trivial after restriction. The corrected structural statement is therefore not merely "break enough symmetry," but

$$\boxed{\text{pass to one chamber/Borel gauge} \Longrightarrow \text{both radical obstruction bits vanish and a section exists.}}$$

This is a finite-group/building statement; it does not by itself identify a physical gauge field or a hardware subgroup implementation.

79.20 Enumerator frontier, exact $Q(5,3)$ distance, and the orthogonal dual quotient (Passes 4520–4527)

Pass 4520: the full W33 enumerator remains open, with a sharper exact frontier. The exact Burnside reduction of Pass 4512 leaves 10,789,604 codeword orbits modulo $PGSp(4,3)$ and global complement. Pass 4520 does not relabel that reduction as a completed coefficient table. Instead it exhaustively computes the coefficient-support shells $m = 6, 7$: all $\binom{40}{6} = 3{,}838{,}380$ and $\binom{40}{7} = 18{,}643{,}560$ subsets are traversed. Weight 486 first occurs with multiplicities 1440 and 240 in those two shells respectively. The exact $PGSp$ subset-orbit counts for $m = 0, \ldots, 20$ are

$$1, 1, 2, 5, 16, 48, 165, 571, 1961, 6252, 18226, 47911, 113314, 240735, 460273, 793280, 1234880, 1739041, 2218732, 25668$$

with 1,347,360 complement-orbits at the middle shell $m = 20$. **Boundary:** the complete numerical weight enumerator and Fisher-zero table remain OPEN.

Pass 4521: the $Q(5,3) = GQ(3,9)$ apartment code is exactly $[102060, 279, 1458]$. For coefficient support S in the 280-vertex line graph, write $m = |S|$, $e = e(S)$, $p_3 = p_3(S)$ and $c_4 = c_4(S)$. Pass 4515 gives

$$w = 1458m - 12\binom{m}{2} - 150e + 36p_3 - 8c_4.$$

The line graph is $SRG(280, 36, 8, 4)$ with nontrivial eigenvalues $8, -4$, so

$$\frac{m^2}{14} - 2m \le e \le 4m + \frac{m^2}{20}.$$

If $t_{uv} \le 4$ counts common neighbours inside S for a nonedge uv, then $p_3 = \sum t_{uv}$ and $2c_4 = \sum \binom{t_{uv}}{2}$, whence $36p_3 - 8c_4 \ge 30p_3$. Also

$$p_3 = \sum_x \binom{d_x}{2} - 3T \ge \frac{2e^2}{m} - 9e,$$

because $3T \le 8e$. Therefore

$$w \ge 1458m - 12\binom{m}{2} - 150e + 30\max\left(0, \frac{2e^2}{m} - 9e\right).$$

Minimizing this convex piecewise expression on the spectral edge interval gives

$$\begin{cases} 864m - \frac{27}{2}m^2, & 2 \le m \le 10, \\ m(789 - 6m), & 10 \le m \le 91, \\ \dfrac{3m(5m^2 - 868m + 41552)}{49}, & 91 \le m \le 140. \end{cases}$$

Its minimum on $2 \le m \le 140$ is $1674 > 1458$. Global complement lets every nonzero codeword use $m \le 140$, while the 280 support-one line-star words all have weight 1458. Hence

$$\boxed{C_{Q(5,3)} = [102060, 279, 1458], \qquad A_{1458} = 280.}$$

Pass 4522: the 366 missing dual dimensions contain a faithful $O_6^-(2)$ quotient. Let $D = C^\perp$, P be the span of the 2160 odd weight-three prism checks, and $E \le D$ the even-weight subcode. Since parity is nonzero on P,

$$\boxed{\dim(D, P, E, P \cap E) = (1581, 1215, 1580, 1214),}$$

so

$$\boxed{\dim(D/P) = \dim(E/(P \cap E)) = 366.}$$

This corrects the tempting but false picture of P as a submodule of E. The 366-space has a canonical fixed line inside a canonical fixed hyperplane; the middle quotient has dimension 364. A deterministic outer-invariant 358-submodule yields a faithful six-dimensional quotient. On it the inner and outer images have orders 25920 and 51840, the invariant alternating form is unique and nondegenerate, and the invariant quadratic refinement is minus type with

$$28 = 1 + 27 \text{ singular vectors}, \qquad 36 \text{ anisotropic vectors}.$$

Thus this quotient realizes the standard $PSp(4,3) \cong \Omega_6^-(2)$ shadow and adjoining the projective outer involution gives $O_6^-(2)$. The pass does *not* claim that the displayed 358-submodule completes the Loewy series of the 364-space.

Pass 4523: primitive-six zeta tomography works for every thick $GQ(s,t)$. For the signed primitive length-six Ihara polynomial, the degree-two Walsh coefficient for two geometric lines is

$$\boxed{c_{\mathrm{dis}} = s(s+1)(s-1)^2}$$

when they are disjoint and

$$\boxed{c_{\mathrm{adj}} = s^2(s-1)^2(2t+1)}$$

when they intersect. Indeed a fixed pair belongs to $\beta = s(s+1)/2$ or $\alpha = s^2 t$ apartments, each apartment contributes $2(s-1)^2$ oriented simple hexagons to the parity pair, and an intersecting pair has the additional $s^2(s-1)^2$ triangle–triangle figure-eight family. Therefore

$$c_{\mathrm{adj}} - c_{\mathrm{dis}} = s(s-1)^2(2st - 1) > 0$$

for every thick generalized quadrangle, and the degree-two primitive-six Walsh matrix reconstructs the line-intersection graph exactly.

Pass 4524: $Q(5,3)$ falsifies a naive nine-sheet prism extrapolation. There are $4536\binom{10}{3} = 544320$ triangular prisms. Projecting each six-line indicator b by $b \mapsto A_* b$ gives

$$\boxed{544320 \text{ distinct images, all of weight } 104.}$$

Thus the map is injective, not nine-to-one. For each noncollinear point pair, the XOR of all ten rung pairs is in $\ker A_*$, so a three-rung prism has the same image as its complementary seven-rung fan. This is the precise mechanism that changes from W33.

Pass 4525 (outside the box): the 27 singular vectors are explicitly the cubic-surface lines. Polar orthogonality on the nonzero singular vectors of the six-space gives $SRG(27, 10, 1, 5)$. Rather than infer a Schlaefli identification from those parameters, the executable gives an explicit 27-vertex graph isomorphism to the repo's existing $W(E_6)$ cubic-surface-line carrier and conjugates all five inner generators plus the outer generator into the existing $W(E_6)$ permutation group. Hence the permutation representations are literally isomorphic.

Pass 4526 (outside the box): the odd-t fan-kernel theorem explains W33's exceptional collapse. For noncollinear points x, y of any $GQ(s,t)$, their $t+1$ common neighbours give two complete line-stars joined into a rung fan. When t is odd, every fan line meets $t+1$ fan lines and every external line meets exactly two, so the full fan lies in $\ker A_{\text{line}}$ over $\mathbb{F}_2$. Consequently a k-rung selection and its $(t+1-k)$-rung complement have the same protected image. For a three-rung prism the canonical complement has $t-2$ rungs, which is a single edge exactly at $t=3$. Thus the W33 edge collapse is the special $4 = 3+1$ case; $Q(5,3)$ has $10 = 3+7$ instead.

Pass 4527 (outside the box): the 36 anisotropic vectors are explicitly the 36 double-sixes. Polar orthogonality on the anisotropic vectors gives $SRG(36, 15, 6, 6)$. An explicit 36-vertex isomorphism identifies it with the repo's double-six carrier, where two double-sixes are adjacent exactly when their 12-line supports intersect in four cubic-surface lines. Generator conjugation again matches the full order-51840 permutation action. This is an explicit representation bridge, not a $36 = 36$ coincidence.

> **Evidence boundary.** The exact executable certificates are `w33_pass4520_apartment_enumerator_frontier.py`, `w33_pass4521_q53_apartment_distance_proof.py`, `w33_pass4522_4525_4527_dual_orthogonal_schlafli.py`, `w33_pass4523_general_gq_c6_tomography.py`, `w33_pass4524_q53_prism_fiber_exception.py`, and `w33_pass4526_general_gq_prism_fan_kernel.py`. The complete W33 numerical weight enumerator remains open. No finite group, code, graph-zeta or cubic-surface identification in this section is promoted to a physical hardware or field-theory statement.

79.21 Borel maximality, local compilation, and protected-edge compression (Passes 4528–4535)

Pass 4519 identified the corrected splitting flag with the order-162 Sylow-3 normalizer/Borel H. The next packet asks whether this chamber gauge is merely one convenient section or is structurally singled out, how it scales, and how much protected information can be confined to its local cell.

Pass 4528: the Borel is maximal by inclusion inside its splitting overgroup interval. The exact H–double-coset decomposition of $G = PSp(4,3)$ has eight cells of sizes

$$162,\ 486,\ 486,\ 1458,\ 1458,\ 4374,\ 4374,\ 13122.$$

For a representative g of each cell, the generated group $\langle H, g\rangle$ is always one of only four groups:

$$H, \qquad P_{\text{point}}, \qquad P_{\text{line}}, \qquad G,$$

with orders $162, 648, 648, 25920$. In particular the two maximal parabolics intersect exactly in H. Recomputing the apartment-extension section system gives

K	$\operatorname{rank}(A_K)/\operatorname{rank}(A_K\|b)$	section
H	384/384	yes, affine dimension 6
P_{line}	386/387	no
P_{point}	387/388	no
G	389/390	no.

Hence adjoining any element outside the chamber either restores one simple parabolic or generates all of G, and in every case the obstruction returns. This proves maximality by inclusion among splitting overgroups containing this Borel; it is not a census of unrelated subgroup conjugacy classes.

Pass 4529: the two obstruction bits are the two parabolic directions. Pass 4509 gives $H^1(G, K/J) \cong \mathbb{F}_2^2$. Choose

$$e_P = [\text{fixed_line}], \qquad e_L = [\text{sum}].$$

Then the third nonzero class is $e_P + e_L = [\text{second}]$, while restriction kernels are

$$\ker \operatorname{res}_{P_{\text{point}}} = \langle e_P\rangle, \qquad \ker \operatorname{res}_{P_{\text{line}}} = \langle e_L\rangle, \qquad \ker \operatorname{res}_H = \langle e_P, e_L\rangle.$$

Thus the computed two-bit obstruction admits an exact rank-two-building coordinate system: point and line residues remove distinct axes, and their incident chamber removes both. This is a re-coordinatization of the computed radical cohomology, not a general theorem about all Ext^1 modules of rank-two groups.

Pass 4530: an infinite symbolic $Q(5, q)$ bridge, with the hard rank kept explicit. For $Q(5, q) = GQ(q, q^2)$ and $q \equiv 3 \pmod 4$, Pass 4471 specializes to

$$HH^T = N^T N \pmod 2.$$

The family has

$$|\mathcal{P}| = (q+1)(q^3+1), \qquad |\mathcal{L}| = (q^2+1)(q^3+1),$$
$$r = \frac{q^6(q+1)}{2}, \qquad |\mathcal{A}| = \frac{(q^2+1)(q^3+1)q^6(q+1)}{8}.$$

Writing $h(q) = \operatorname{rank}_2 H$ and $\rho(q) = \operatorname{rank}_2(N^T N)$, the apartment module therefore has

$$\boxed{\dim V_{\text{protected}} = \rho(q), \qquad \dim \operatorname{rad} = h(q) - \rho(q).}$$

For $q = 3$, Pass 4506 supplies $h(3) = 279$, $\rho(3) = 70$, and radical dimension 209. No polynomial formula for $h(q)$ or $\rho(q)$ is extrapolated from this single anchor; obtaining a closed binary-rank formula remains a separate classical-code problem.

Pass 4531: the exact flag section compiles in nine single-port clocks. The ten optimal Pass 4504 section columns have weights

$$1, 1, 1, 1, 5, 5, 5, 5, 9, 9$$

and 42 total source-line incidences on the 13-line cell. In the explicit Boolean model where each line may feed at most one quotient accumulator per clock and each accumulator accepts at most one source, compilation is bipartite edge coloring. The maximum degree is 9, so Kőnig's theorem gives a lower bound of nine clocks; the executable witness supplies a conflict-free nine-round coloring. Hence

$$\boxed{42 \text{ primitive XOR routes}, \qquad \text{depth} = 9 \text{ exactly in this model.}}$$

This is a register/scheduling theorem, not FPGA timing closure, optical PPA, fault tolerance, or a physical optimum under a different port model.

Pass 4532: the Borel splits the protected 240 edges into a local/boundary/exterior hierarchy. Using Pass 4513's exact identification of the protected 240-set with the dual-W33 edges, the Borel orbit sizes are

$$\boxed{3, 3, 9, 9, 27, 27, 81, 81 = 2(3 + 9 + 27 + 81).}$$

Its line-vertex orbits are $1, 3, 9, 27$. The optimal 13-line gauge cell is the closed neighborhood of the fixed line and induces $K_1 \vee 4K_3$. Exactly the four smallest edge orbits lie wholly inside this cell:

$$24 = 3 + 3 + 9 + 9,$$

while $108 = 27 + 81$ edges cross its boundary and another $108 = 27 + 81$ lie wholly outside. The internal 24 split as twelve center spokes and twelve triangle edges.

Pass 4533 (outside the box): a power-of-three Borel staircase. The preceding orbit arithmetic is exact at every shell:

$$|\mathcal{O}_{\text{vertex}}| = 3^0, 3^1, 3^2, 3^3, \qquad |\mathcal{O}_{\text{edge}}| = 2 \times (3^1, 3^2, 3^3, 3^4),$$

with edge stabilizer orders $54, 18, 6, 2$. This gives a finite orbit filtration aligned with the order-81 Sylow core. It is not promoted here to a physical scale, energy, causal depth, or Bruhat-length variable.

Pass 4534 (outside the box): nine local spokes saturate the entire edge-accessible protected layer. The vectors $A_*(e_i + e_j)$ over all 240 adjacent pairs span dimension *nine*, not ten. Because this span is $PSp(4, 3)$-invariant and Pass 4496 proved that

$$H_{10} : \qquad 0 < 1 < 9 < 10$$

is the complete invariant-submodule lattice, the edge-image span is exactly the unique nine-dimensional submodule $V_9 \subset H_{10}$. Yet the localization is complete relative to that carrier:

$$\text{rank(all 240)} = \text{rank(internal 24)} = \text{rank(center spokes 12)} = 9.$$

Indeed nine explicitly certified center spokes already form a basis. Thus one Borel cell recovers every edge-accessible protected direction, while the tenth logical direction lies outside the entire 240-edge family. This is finite linear tomography, not a physical measurement protocol.

Pass 4535 (outside the box): an eight-state quotient retains the complete distinct edge spectrum. Form the line graph of the 240 protected dual-W33 edges, joining two carrier states when their W33 edges share an endpoint. It is 22-regular. The eight Borel edge orbits form an equitable partition with quotient

$$Q = \begin{pmatrix} 2 & 2 & 9 & 0 & 9 & 0 & 0 & 0 \\ 2 & 2 & 0 & 0 & 18 & 0 & 0 & 0 \\ 3 & 0 & 8 & 2 & 0 & 0 & 9 & 0 \\ 0 & 0 & 2 & 2 & 0 & 0 & 18 & 0 \\ 1 & 2 & 0 & 0 & 8 & 2 & 3 & 6 \\ 0 & 0 & 0 & 0 & 2 & 2 & 6 & 12 \\ 0 & 0 & 1 & 2 & 1 & 2 & 10 & 6 \\ 0 & 0 & 0 & 0 & 2 & 4 & 6 & 10 \end{pmatrix}.$$

It satisfies detailed balance $|O_i|Q_{ij} = |O_j|Q_{ji}$ and

$$\chi_Q(x) = (x-22)(x-12)^2(x-6)(x+2)^4.$$

The full 240-state line graph is annihilated by $(L-22I)(L-12I)(L-6I)(L+2I)$, so the quotient already contains every distinct full-graph eigenvalue:

$$\boxed{\mathrm{Spec}_{\mathrm{distinct}}(Q) = \mathrm{Spec}_{\mathrm{distinct}}(L) = \{22, 12, 6, -2\}.}$$

This is an exact equitable spectral compression, not a Hamiltonian or measured transfer function.

> **Evidence boundary.** Passes 4528–4535 sharpen the chamber/Borel theorem into an exact overgroup classification, a two-axis cohomology compass, a symbolic $Q(5, q)$ family law, a model-optimal nine-clock compiler, and three independently checked local-edge compressions. The executable witnesses and frozen JSON certificates under `analysis/` and `data/` are authoritative. Count coincidences do not identify E8 roots, finite locality is not spacetime locality, and the symbolic $Q(5, q)$ statement intentionally leaves the difficult binary-rank function explicit.

79.22 The missing protected bit is parity, and the Borel cell already contains full H_{10} (Passes 4536–4543)

Pass 4536: the missing tenth direction is coefficient parity. Let A_* be the dual-W33 line-intersection matrix over $\mathbb{F}_2$. Pass 4534 showed that the protected edge vectors $A_*(e_i + e_j)$ span the unique nine-dimensional invariant submodule $V_9 \subset H_{10} = \mathrm{im}\, A_*$. Since the connected line graph's endpoint vectors span the full even-weight hyperplane of $\mathbb{F}_2^{40}$ and every vector in $\ker A_*$ has even coefficient parity,

$$\boxed{\pi(A_* b) = \sum_i b_i \pmod 2}$$

is a well-defined nonzero functional on H_{10} with

$$\ker \pi = V_9 = A_*(\text{even coefficient vectors}).$$

Thus any single line-star $A_* e_i$ supplies the missing tenth direction. The complete parity-refined protected weight enumerator is

$\pi = 0$	$w = 0$	16	20	24	40
A_w	1	135	240	135	1

,

$\pi = 1$	$w = 12$	20	28
A_w	40	432	40.

The 240 even weight-20 vectors are exactly the protected edge shell; the forty odd minimum vectors are exactly the forty line-stars.

Pass 4537: a second exact $Q(5,q)$ rank anchor and a closed-rank conjecture. An independent elliptic-quadric construction gives

q	$\lvert\mathcal{P}\rvert$	$\lvert\mathcal{L}\rvert$	$\operatorname{rank}_2 N$	$\dim\ker N^T$	$\operatorname{rank}_2(N^T N)$
3	112	280	91	21	70
7	2752	17200	2451	301	2150.

Both anchors satisfy

$$\rho(q) = (q^2+1)(q^2-q+1) = \frac{|\mathcal{L}|}{q+1}, \qquad \dim\ker N^T = q(q^2-q+1).$$

For every odd q, the line-graph SRG parameters $k = q^2(q+1)$, $\lambda = q^2-1$, $\mu = q+1$ are even, hence

$$\boxed{A_*^2 = 0 \quad \text{over } \mathbb{F}_2}.$$

The displayed closed rank formula is therefore a strongly supported conjecture, not yet an all-q theorem; only the two exact anchors and square-zero theorem are claimed here.

Pass 4538: the Borel attains the global maximum splitting order. Pass 4503 already proved all five maximal subgroup types nonsplit. Using the standard subgroup structures of those maximals, every remaining proper subgroup of order above 162 reduces to seven large types of orders

$$360, 324, 288, 216, 216, 192, 192.$$

Exact representatives have section ranks

$$386/387,\ 386/387,\ 386/387,\ 385/386,\ 386/387,\ 385/386,\ 380/381,$$

respectively, so all are nonsplit. Therefore

$$\boxed{\max\{|H| : H \le PSp(4,3) \text{ and the apartment extension splits on } H\} = 162,}$$

attained by the chamber/Borel of Pass 4519. Completeness of the order bound uses the standard finite-group subgroup classification of the five maximal types; the executable verifies representatives and section ranks independently.

Pass 4539: ten local samples decode every protected vector. Take the parity-odd center line-star together with the nine local spokes

$$(0,1),(0,2),(0,3),(0,4),(0,5),(0,7),(0,8),(0,28),(0,32).$$

These form a basis of H_{10}. Restriction to ambient coordinates

$$0,1,2,3,4,5,7,8,10,11$$

is invertible; the frozen 10×10 inverse was exhaustively checked on all 1024 protected states. Its XOR fan-ins are

$$4,5,3,3,4,4,4,4,8,6$$

with 45 total input incidences. The first decoded coordinate is π and the remaining nine are local-spoke coordinates. The separate eight-state Borel equitable quotient remains a spectral/orbit compression, not an identity- preserving decoder.

Pass 4540: primitive-six zeta tomography reconstructs the protected filtration. Pass 4523 specializes in W33 to

$$M_6 = 48(J - I) + 204A_*.$$

Thus the degree-two Walsh data determines A_* exactly and consequently the entire chain

$$M_6 \longrightarrow A_* \longrightarrow H_{10} = \operatorname{im} A_* \longrightarrow V_9 = A_*(\text{even}) \longrightarrow H_{10}/V_9 \cong \mathbb{F}_2.$$

The same cross-lane comparison explains the prism exception: for odd t a three-rung fan equals its $(t-2)$-rung complement modulo $\ker A_*$. Only $t = 3$ makes the complement one rung, yielding W33's nine-sheet edge collapse; for $Q(5,3) = GQ(3,9)$ the complement has seven rungs and the 544320 prism images are injective.

Pass 4541 (outside the box): parity is pairing with the unique fixed vector. The all-ones protected vector has coefficient preimage $e_0 + e_1 + e_2 + e_3$, and the protected alternating form gives

$$\boxed{\pi(A_* b) = B(A_* b, \mathbf{1}) = b^T \mathbf{1}.}$$

Pass 4496 proved that the fixed space is one-dimensional and its perpendicular has dimension nine. Hence

$$0 < \langle \mathbf{1} \rangle < \mathbf{1}^\perp = V_9 < H_{10}$$

is exactly the established $1|8|1$ uniserial chain: the missing bit is the symplectic coordinate dual to the unique fixed vector.

Pass 4542 (outside the box): the odd minimum shell reconstructs W33. The forty $\pi = 1$ minimum vectors $s_i = A_* e_i$ all have weight 12. For $i \neq j$,

$$\operatorname{wt}(s_i + s_j) = \begin{cases} 20, & i \sim j, \\ 16, & i \not\sim j. \end{cases}$$

Among the 780 pairs there are exactly 240 weight-20 and 540 weight-16 differences. Joining the former reconstructs exactly $\mathrm{SRG}(40, 12, 2, 4)$, the dual W33 line graph, while the 240 distinct adjacent differences are exactly the protected edge shell. Thus the parity-refined H_{10} weight geometry remembers W33 intrinsically.

Pass 4543 (outside the box): the local cell contains exactly 108 full bases. Remove the center from the $K_1 \vee 4K_3$ Borel cell and choose nine of its twelve neighbors, equivalently omit three. The rank depends only on the omitted triple's induced type in $4K_3$:

omitted triple	K_3	$K_2 \sqcup K_1$	$3K_1$
count	4	108	108
rank of chosen nine	7	8	9.

Therefore the 108 independent omitted triples give all local nine-line bases of V_9 of this form, and adjoining the center line-star yields exactly 108 ten-line bases of full H_{10}. The center is essential: any ten-line subset using only the twelve neighbors has rank at most nine.

> **Evidence boundary.** Passes 4536–4543 are finite GF(2), finite-group, graph-zeta, and representable-matroid statements. The $Q(5,q)$ closed rank formula remains explicitly a conjecture beyond the exact $q = 3, 7$ anchors. Coefficient parity is not called a physical charge, local bases are not physical hardware layouts, and Ihara/Walsh reconstruction is not promoted to dynamics without an additional theorem.

79.23 The dual-module lattice, cubic transport, and higher zeta tomography (Passes 4544–4551)

The preceding packets exposed a faithful six-dimensional $O_6^-(2)$ quotient of the apartment dual, an explicit Schlaefli/double-six realization of its singular and anisotropic shells, and primitive-six zeta tomography of generalized quadrangles. Passes 4544–4551 push those bridges in three directions: the actual binary submodule lattice above the unresolved core, an explicit cubic-surface incidence transport, and higher primitive-prime tensors that recover the apartment code itself.

Pass 4544: the 364-dimensional middle has three 358-submodules, not one. Let M denote the 364-dimensional middle quotient from Pass 4522. Exact cyclic-span computation on the standard basis gives

$$284^2, \qquad 330^{10}, \qquad 358^{49}, \qquad 364^{303}.$$

There is a unique cyclic S_{284} and a unique cyclic S_{330}, but the 49 basis vectors of cyclic dimension 358 generate exactly three distinct submodules T_0, T_1, T_2. All three contain S_{330}, every pair sums to all of M, and every pair has the same intersection

$$\boxed{K_{352} = T_0 \cap T_1 = T_0 \cap T_2 = T_1 \cap T_2.}$$

The quotient M/K_{352} has dimension twelve. Exhausting all 4095 nonzero vectors shows that it has exactly three proper nonzero invariant submodules; each has dimension six, every nonzero vector in each cyclically generates the whole six-space, and

$$\boxed{M/K_{352} \simeq U_6 \oplus U_6.}$$

The three six-submodules are the three one-dimensional directions in the multiplicity space $\mathbb{F}_2^2$. The projective outer involution fixes one T_i and exchanges the other two.

The next layer also splits exactly:

$$\boxed{K_{352}/S_{330} \simeq V_8 \oplus V_{14},}$$

with irreducibility of both summands verified by exhaustive cyclic generation of all $2^8 - 1$ and $2^{14} - 1$ nonzero vectors. On the S_{284} branch,

$$\dim(S_{284} \cap S_{330}) = 256, \qquad \dim(S_{284} \cap K_{352}) = 278,$$

the intervening 22-space is again $V_8 \oplus V_{14}$, and the top quotient is an irreducible six-space. Inside the 256-space the exact standard-basis census exposes a unique chain

$$S_{186} < S_{250} < K_{256},$$

with quotient dimensions 64 and 6; the six-dimensional top is exhaustively irreducible. The complete Loewy lattice *below* S_{186} and the irreducibility/composition structure of the displayed 64-quotient remain open. No stronger closure is claimed.

Passes 4545 and 4549: the 27- and 36-carriers are joined by an exact incidence intertwiner. Use the explicit Passes 4525/4527 conjugations to regard the apartment-derived 27 singular vectors as the cubic-surface lines and the 36 anisotropic vectors as the Schlaefli double-sixes. Let R be the 27×36 incidence matrix recording membership of a cubic line in the twelve-line

support of a double-six. Exact enumeration gives: every line lies in 16 double-sixes, every double-six contains 12 lines, a meeting line-pair lies in 8 double-sixes, and a skew pair lies in 6. Two double-sixes meet in either four lines (270 pairs) or six lines (360 pairs).

Let A_{27} be meet adjacency on the 27 cubic lines and A_{36} the four-line-intersection adjacency on the 36 double-sixes. Then

$$\boxed{RR^T = 10I + 2A_{27} + 6J,} \qquad \boxed{R^T R = 6I - 2A_{36} + 6J,}$$

and, more sharply,

$$\boxed{3A_{27}R + RA_{36} = 20J.}$$

After centering, R is an exact adjacency intertwiner. Its rational rank is 21: it transmits the common $1 \oplus 20$ constituent while killing the six-dimensional Schlaefli constituent on the 27-side and the fifteen-dimensional constituent on the 36-side. A deterministic (a_i, b_i, c_{ij}) labeling is frozen in the certificate, giving an explicit classical-coordinate transport rather than a parameter match.

Pass 4546: an orbit-native exact enumerator engine, with the full run still open. The complete numerical weight enumerator still requires the full 10,789,604 $PGSp(4,3)$-plus-complement codeword orbits. The new engine turns this into a resumable exact computation rather than a raw $\binom{40}{m}$ scan. A coefficient subset S is encoded by adjoining a fixed 41st marker vertex to dual W33 and connecting it exactly to S. Canonical colored-graph certificates therefore classify $PGSp(4,3) = \mathrm{Aut}(W33)$ subset orbits without permitting an accidental $S \leftrightarrow S^c$ swap. Each representative is weighted by

$$w(S) = 162m - 12\binom{m}{2} - 42e(S) + 12p_3(S) - 8c_4(S),$$

and its multiplicity is $51840/|\,\mathrm{Stab}(S)|$.

Every support shell must reproduce the exact Burnside schedule

$$1, 1, 2, 5, 16, 48, 165, 571, 1961, 6252, 18226, 47911, 113314, 240735, 460273, 793280, 1234880, 1739041, 2218732, 25668$$

Supports 0–19 are counted once; the labeled support-20 spectrum is halved because $S \sim S^c$. The final acceptance gates are

$$\sum_w A_w = 2^{39}, \qquad 9{,}442{,}244 + 1{,}347{,}360 = 10{,}789{,}604.$$

The executable and checkpoint contract are complete; the final support-20 run and hence the numerical coefficient table remain **OPEN** until those checksums are emitted.

Passes 4547 and 4550: every $Q(5,3)$ noncollinear pair carries a 9-dimensional fan code. Fix noncollinear points x, y in $Q(5,3) = GQ(3,9)$. Their ten common neighbors give ten rung pairs. If k rungs are selected and their protected images are summed, exact GQ counting gives

$$\boxed{w(k) = 20(k \bmod 2) + 4k(10-k).}$$

The only coefficient relation is the full ten-rung fan, so each pair carries a binary $[280, 9, 56]$ code with complete weight enumerator

$$\boxed{1 + 10z^{56} + 45z^{64} + 210z^{96} + 120z^{104} + 126z^{120}.}$$

The 120 weight-104 words are exactly the three-rung prism images associated with that fan. For two triples, Hamming distance 64 occurs exactly when they intersect in two rungs; hence the distance-64 graph is the Johnson graph $J(10,3)$ of degree 21. Intersections one and zero both give distance 96, so the protected Hamming metric deliberately coarsens the full Johnson scheme. Together with Pass 4524's global injectivity, the 4536 fans account for all 544320 distinct protected prism images without resurrecting the exceptional W33 nine-sheet edge collapse.

Pass 4548: C_7 sees P_3 triples and C_8 directly sees apartments. For the primitive signed length-seven coefficient, the degree-three Walsh layer has exactly two nonzero support species:

$$\boxed{c_7 = 48 \text{ on the 4320 one-edge triples}, \qquad c_7 = 204 \text{ on the 2160 induced } P_3 \text{ triples.}}$$

Independent triples and line-graph triangles have zero coefficient.

The first genuinely four-body layer is stronger. Primitive length eight has ten $PSp(4,3)$ support orbits at Walsh degree four, but

$$\boxed{c_8 = 712}$$

occurs on exactly one orbit of size 1620, and that orbit is exactly the set of building apartments. Thus $C_8^{(4)}$ reconstructs the apartment hypergraph directly. It also detects ambient embedding beyond the induced four-vertex line graph: $P_3 \sqcup K_1$ supports split between coefficients 56 and 80, while $2K_2$ supports split between 64 and 156; the splits correlate with distinct point-union collinearity profiles in the underlying GQ.

Pass 4551 (outside the box): primitive length-eight zeta data reconstructs the apartment code itself. Take the forty Walsh variables as row labels and the coefficient-712 supports of $C_8^{(4)}$ as binary columns. The resulting matrix H_ζ has

$$\boxed{\text{shape}(H_\zeta) = 40 \times 1620, \qquad \text{rank}_2\, H_\zeta = 39,}$$

row weight 162, column weight four, and

$$\boxed{H_\zeta H_\zeta^T = A_* \pmod 2.}$$

Its column-support set equals the original apartment incidence matrix exactly. Consequently the primitive length-eight Walsh tensor reconstructs the same binary apartment code that Pass 4495 independently proved to be $[1620, 39, 162]$; Pass 4500 then reconstructs dual W33 from its forty minimum words. The new theorem is the exact $C_8^{(4)} \to H$ bootstrap. It is not a claim that a physical zeta observable or decoder has been implemented.

> **Evidence boundary.** Passes 4544–4551 are finite binary-module, cubic-surface incidence, generalized-quadrangle coding, and signed graph-zeta statements. The complete numerical W33 weight enumerator remains open until the orbit engine finishes its support-20 checksum. The upper 364-dimensional module lattice is exact through the displayed $186 < 250 < 256$ frontier, but the lower structure of the 186-space and the 64-quotient is not silently declared simple. No finite carrier, incidence intertwiner, or zeta tensor is promoted to a physical field, particle, energy, or hardware observable without a separate theorem.

79.24 Protected parity geometry after the zeta bootstrap (Passes 4552–4559)

Pass 4552: a third exact elliptic-quadric rank anchor, and a literature-scope correction. An independent construction of $Q^-(5,5) = GQ(5,25)$ gives 756 points and 3276 lines and, over $\mathbb{F}_2$,

$$\operatorname{rank} N = 651, \qquad \operatorname{rank}(N^T N) = 546.$$

Together with the exact $q = 3, 7$ anchors this gives

q	3	5	7
$\operatorname{rank} N$	91	651	2451
$\operatorname{rank}(N^T N)$	70	546	2150

and all three agree with $\operatorname{rank} N = q^4+q^2+1$ and $\operatorname{rank}(N^T N) = (q^2+1)(q^2-q+1)$. The closed odd-$q$ formulas remain open. In particular, the Bagchi–Brouwer–Wilbrink $O(5,q)$ binary-code paper concerns the dual of the square symplectic quadrangle $Sp(4,q)$, not the elliptic $Q^-(5,q) = GQ(q,q^2)$ family, so it is not used as a proof here.

Pass 4553: the $1 \mid 8 \mid 1$ chain is intrinsic parity geometry. Let j be the all-ones protected vector. Pass 4541 gives $\pi(x) = B(x,j)$, hence

$$\boxed{0 < \langle j \rangle < j^\perp = V_9 < H_{10}}.$$

On $V_8 = V_9/\langle j \rangle$ the formula

$$\boxed{q_8([x]) = \frac{\operatorname{wt}(x)}{4} \pmod 2}$$

is well defined under $x \mapsto x + j$ and polarizes exactly to B. It has 136 singular classes including zero and 120 anisotropic classes, so this is an explicit plus-type $O^+(8,2)$ model. The fixed line and nine-space are now located without cyclic-submodule search; irreducibility of the middle eight is inherited from the independent Passes 4477/4496 certificate.

Pass 4554: the 108 local bases form a basis-switching codebook. The one-spoke exchange graph on the 108 Pass 4543 bases is 15-regular with 810 edges, diameter three, distance distribution $(1, 15, 48, 44)$, and spectrum

$$15^1, \quad 9^8, \quad 3^{27}, \quad 0^{16}, \quad (-3)^{56}.$$

The order-162 Borel has two basis orbits of sizes 81 and 27 with equitable quotient

$$\begin{pmatrix} 12 & 3 \\ 9 & 6 \end{pmatrix}.$$

Every specified spoke is omitted by 27 bases; two erased spokes in distinct pencils are simultaneously omitted by six bases, while two in one pencil are never simultaneously omitted. An erased three-spoke set has exactly one surviving basis iff it meets three distinct pencils.

Pass 4555: one primitive-C_8 selector layer suffices for the whole protected bootstrap. Pass 4551 proves that coefficient 712 at Walsh degree four selects exactly the 1620 apartments. Keeping only that Boolean selector already gives

$$C_8^{(4)}[712] \to H \to HH^T = A_* \to W33^\vee \to H_{10} \to (j, \pi, V_9).$$

Thus no C_6 or C_7 layer is required once this C_8 selector is available. This is a sufficiency theorem, not an absolute lower bound on all possible encodings of the same geometry.

Pass 4556: no linear equivariant shortcut from H_{10} to the exceptional six-space. The protected module has composition factors $1, 8, 1$, while the faithful $O_6^-(2)$ module U_6 from Passes 4522/4544 is simple of dimension six. Therefore

$$\boxed{\mathrm{Hom}_{PSp(4,3)}(H_{10}, U_6) = \mathrm{Hom}_{PSp(4,3)}(U_6, H_{10}) = 0.}$$

Any nonzero map would force a six-dimensional simple composition factor in H_{10}. The Schlaefli/double-six incidence intertwiner acts on different 27- and 36-point permutation carriers and does not evade this obstruction.

Pass 4557 (outside the box): cross-shell Hamming distance recovers line pencils. For an even edge vector $e_{jk} = s_j + s_k$ and the forty odd line-stars, the cross-shell distance profile is

$$d = 12 : 2, \qquad d = 20 : 36, \qquad d = 28 : 2.$$

The two distance-12 stars are exactly j, k; the two distance-28 stars are exactly their common neighbors. These four vertices form the unique K_4 line pencil through the geometric intersection point. Thus protected Hamming geometry reconstructs vertex–edge incidence and point pencils, not merely the SRG adjacency relation.

Pass 4558 (outside the box): apartments uniformly lift the singular $O^+(8,2)$ shell. The 1620 apartment indicators have only 135 distinct protected images under $b \mapsto A_* b$. Every image has weight 16, every image has exactly twelve apartment preimages, and these images are precisely the 135 nonzero singular classes of V_8. In each twelve-element fiber, join two apartments when they share one line. Every fiber is

$$\boxed{K_{4,4,4}},$$

with degree eight, 48 intersecting pairs and 18 disjoint pairs.

Pass 4559 (outside the box): the 240 edges are a two-sheeted anisotropic lift. Every protected edge has weight 20, hence represents an anisotropic class of V_8. Addition of j pairs the 240 edge vectors into 120 classes. On the W33 carrier this involution sends an edge to the opposite edge in the unique four-line K_4 pencil through the same point. Therefore

$$\boxed{240 \longrightarrow 120}$$

is the canonical opposite-edge double cover of the anisotropic shell; its polar orthogonality quotient is again $\mathrm{SRG}(120, 63, 30, 36)$.

> **Evidence boundary.** Passes 4552–4559 are finite geometry, binary module, graph-zeta, and representable-matroid statements. The $Q^-(5,q)$ closed rank formula is exact only at $q = 3, 5, 7$ here. The exceptional-six result excludes linear equivariant maps only. Hamming distance, twelve-fold apartment fibers, and the edge double cover are not physical distances, degeneracies, or particle labels without a separate dynamics theorem.

79.25 Composition closure, executed enumerator mass, and exact cross-carrier boundaries (Passes 4571–4578)

Pass 4571: the remaining 186- and 64-dimensional module frontiers close at the composition-factor level. Inside the unique $S_{186} < S_{250} < K_{256}$ chain of Pass 4544, the 64-dimensional

quotient is irreducible over $\mathbb{F}_2$. A deterministic MeatAxe-style verifier finds a group-algebra element with irreducible full-degree characteristic polynomial, which precludes every proper invariant subspace. The 186-space is reducible: exactly one standard coordinate seed generates a visible 120-space while the other 185 generate all of S_{186}. Recursive primal/contragredient spins and multiplicity-one factor kernels give the exact composition-factor multiset

$$\boxed{S_{186}: \quad 40^3 + 14^2 + 8 + 6^5.}$$

More specifically,

$$S_{120}: \quad 40^2 + 14^2 + 6^2, \qquad S_{186}/S_{120}: \quad 40 + 8 + 6^3.$$

Every displayed 6-, 8-, and 14-dimensional terminal factor is checked by exhaustive nonzero-vector spin; the 40- and 64-dimensional terminal factors use full-degree irreducible group-algebra witnesses. This closes the composition factors, not every extension class or every node of the complete Loewy lattice.

Pass 4572: the numerical apartment enumerator is now executed through supports eight and nine. Pass 4520 ended the exhaustive labelled-support census at $m = 7$, while Pass 4546 supplied a symmetry engine without claiming the complete run. A compiled incremental XOR/popcount kernel now evaluates all

$$\binom{40}{8} = 76{,}904{,}685, \qquad \binom{40}{9} = 273{,}438{,}880$$

coefficient subsets, adding

$$\boxed{350{,}343{,}565}$$

new exact labelled representatives. The complete support-8 spectrum has 112 distinct weights, from 528 to 960, with

$$A^{(8)}_{528} = 540, \qquad A^{(8)}_{960} = 1755.$$

The support-9 spectrum has 134 distinct weights, from 582 to 1026, with

$$A^{(9)}_{582} = 4320, \qquad A^{(9)}_{1026} = 360.$$

The full spectra are frozen in the Pass 4572 certificate. A monolithic support-10 sweep was attempted but did not complete within the execution window; supports 10 through 20 therefore remain open and no 2^{39} checksum is claimed.

Pass 4573: the W33 C_8 apartment selector is special, not universal. Pass 4548 showed that in $GQ(3,3)$ the primitive degree-four length-eight coefficient 712 singles out exactly the 1620 apartments. Exact nonbacktracking trace arithmetic on the smallest thick symplectic quadrangle refutes the all-GQ extrapolation. In

$$W(3,2) = GQ(2,2)$$

all 90 apartments have primitive $C^{(4)}_8$ coefficient 36, but so do 60 non-apartment induced $K_{1,3}$ supports in the line graph. Thus coefficient value alone does not universally select apartments. The collision is not forced merely by $s = 2$: in $Q^-(5,2) = GQ(2,4)$ a sample apartment has coefficient 60 while a $K_{1,3}$ has coefficient 36. The universal theorem that survives is Pass 4523:

$$C^{(2)}_6 \longrightarrow A_{\text{line}} \longrightarrow \text{induced } C_4 \text{ apartments}$$

for every thick GQ. W33's C_8-alone sufficiency is therefore genuinely stronger and exceptional relative to this counterexample.

Pass 4574: the 544320 Q(5,3) prisms are one observed projective-unitary orbit. The previously fail-closed Pass 4547 target is independently reproduced without pynauty. Starting from the repository's explicit $GF(9)$ construction of $H(3,9)$, four concrete unitary transvections generate $PSU(4,3)$ of order 3265920. Adding the unitary diagonal $\mathrm{diag}(3,1,1,1)$ gives the full dual action on the 112 points of $Q(5,3)$ with order

$$\boxed{13063680.}$$

A noncollinear point pair has pointwise stabilizer 1440, setwise stabilizer 2880, and ten common-neighbor rungs. The setwise stabilizer acts on those ten rungs with image order 1440 and kernel two; its ordered-distinct-triple orbit has size 720 and its unordered three-subset orbit has size 120. Hence

$$\boxed{4536 \cdot 120 = 544320}$$

prisms form one orbit and a prism stabilizer has order

$$\boxed{24.}$$

No abstract name is assigned to the order-1440 rung image from order alone.

Pass 4575: cubic line–double-six incidence is exactly the binary natural $O_6^-(2)$ code. Let R be the actual 27×36 cubic-surface incidence matrix of Passes 4545/4549. Through the frozen Passes 4525/4527 conjugations to the six-dimensional minus space,

$$\boxed{R_{s,a} = B(s,a)}$$

for every nonzero singular vector s and anisotropic vector a of U_6. Consequently

$$\boxed{\operatorname{rank}_2 R = 6, \qquad RR^T = R^T R = 0 \pmod 2.}$$

Its two natural image codes are

$$\boxed{[36,6,16], \quad W = 1 + 27z^{16} + 36z^{20}},$$

$$\boxed{[27,6,12], \quad W = 1 + 36z^{12} + 27z^{16}}.$$

Their dual kernels have dimensions 30 and 21, minimum distance three, with low relation counts

$$(A_3, A_4) = (120, 945), \qquad (45, 270),$$

respectively. Thus the rational rank-21 incidence transport collapses mod two to the exact natural six-dimensional orthogonal carrier.

Pass 4576 (outside the box): the protected/cubic no-go extends through unary quadratic maps. Take the protected $V_8 = O^+(8,2)$ module and cubic $U_6 = O^-(6,2)$ module with aligned $PSp(4,3)$ generators. In the complete square-free Boolean polynomial bases of degree at most two, including constants, equivariance gives linear systems of sizes

$$222 \times 222 \quad (V_8 \to U_6), \qquad 176 \times 176 \quad (U_6 \to V_8).$$

Both have full rank. Hence

$$\boxed{\text{no nonzero equivariant Boolean map of degree } \le 2}$$

exists in either unary direction. This does not conflict with the later Pass 4583 alternating-square bridge: $(v,w) \mapsto v \wedge w$ is a bilinear map of two independent inputs into a larger functorial module, not a unary quadratic map $V_8 \to U_6$.

Pass 4577 (outside the box): the twelve-apartment fibers reconstruct the $O^+(8,2)$ polar graph themselves. For two distinct Pass 4558 fibers F_x, F_y, let $n_2(x,y)$ count cross-fiber apartment pairs sharing exactly two W33 lines. Exhausting all $\binom{135}{2}$ fiber pairs gives

$$\boxed{B(x,y)=1 \iff n_2(x,y)=12,}$$

while orthogonal pairs have

$$n_2 \in \{0,2,6,48\}$$

with multiplicities $1620, 810, 2160, 135$. Thus the quotient fibers and their own line-intersection statistics reconstruct the nonzero-singular orthogonality graph

$$\boxed{\mathrm{SRG}(135,70,37,35)}$$

without supplying external eight-dimensional coordinates.

Pass 4578 (outside the box): the tempting cubic 120-orbit is a false friend. The 36 double-sixes have five $PSp(4,3)$ orbits on unordered triples, of sizes

$$\boxed{120, 540, 1080, 2160, 3240.}$$

The unique 120-orbit is numerically tempting because Pass 4559 has exactly 120 protected anisotropic classes. Both transitive actions even have stabilizer order 216. They are nevertheless inequivalent: their stabilizer suborbit signatures are

$$[1,1,1,27,27,27,36] \quad \text{and} \quad [1,2,27,36,54].$$

A generator-by-generator propagation over all possible base identifications finds no equivariant bijection. The equality $120 = 120$ is therefore explicitly rejected rather than promoted into a correspondence.

> **Evidence boundary.** Passes 4571–4578 are exact finite $\mathbb{F}_2$ module/code computations, finite generalized-quadrangle zeta arithmetic, and finite permutation geometry. The complete numerical apartment-code enumerator is still open beyond support nine; Pass 4573 is a counterexample to an overbroad C8 selector conjecture, not an all-parameter classification; and the negative unary protected/cubic results do not forbid higher-functor, pair-valued, symmetry-broken, or physical maps. No finite incidence count is promoted to a field, particle, energy, or hardware quantity without a separate implementation theorem.

79.26 Doily quadratic-evaluation code and intrinsic exceptional S_6 symmetry

Reader entry. The two-qubit doily admits a compact coding-theoretic closure that unifies its $10+15+6$ hyperplane census, the determinant $9+6$ split, the duad–syntheme dictionary, and the exceptional outer automorphism of S_6. This is a finite binary theorem only; it is not a new physical identification.

Let $V=\mathbb{F}_2^4$ carry the standard alternating form B, and let $q_0(x)=x_1x_2+x_3x_4$, so that the polarization of q_0 is B. On the 15 nonzero vectors define

$$C=\left\{\big(B(a,x)+tq_0(x)\big)_{x\neq 0} : a\in V,\ t\in\mathbb{F}_2\right\}.$$

Exact exhaustive verification gives

$$\boxed{C\cong[15,5,6]_2}, \qquad W_C(y)=1+10y^6+15y^8+6y^{10}.$$

The $t = 0$ subcode is the canonical $[15, 4, 8]_2$ symplectic simplex code, hence

$$\boxed{C = S + \langle q_0 \rangle}.$$

The three nonzero weight strata are exactly the complements of the three kinds of doily geometric hyperplanes:

$$10 \times w_6 \leftrightarrow 10 \text{ grids}, \qquad 15 \times w_8 \leftrightarrow 15 \text{ perps}, \qquad 6 \times w_{10} \leftrightarrow 6 \text{ ovoids}.$$

The determinant word q_0 is one distinguished weight-six word: its nine zero coordinates are the nonzero singular matrices of $M_2(\mathbb{F}_2)$ and its six one-coordinates are the units. Thus the determinant $9 + 6$ split is one particular member of the ten plus-type/grid class.

The dual closes the incidence geometry:

$$\boxed{C^\perp \cong [15, 10, 3]_2},$$

and its exactly fifteen minimum-weight words have supports precisely the fifteen totally isotropic doily lines $\{x, y, x + y\}$ with $B(x, y) = 0$. Consequently the point-line doily can be reconstructed from the code as coordinates plus minimum dual supports.

The automorphism statement is also intrinsic. All 720 elements of $Sp(4, 2)$ preserve C. Conversely every coordinate automorphism permutes the six weight-ten words. If $O_1, \ldots, O_6$ are their five-point zero sets, then $|O_i \cap O_j| = 1$ for $i \neq j$ and the fifteen pairwise intersections are all fifteen coordinates. Hence this six-point action is faithful and

$$\boxed{\mathrm{Aut}(C) = Sp(4, 2) \cong S_6}.$$

Finally the fifteen minimum dual supports admit exactly six spreads. Comparing the action on the six ovoids with the action on these six spreads gives the exceptional class swaps

$$\boxed{2 \leftrightarrow 2^3, \qquad 3 \leftrightarrow 3^2, \qquad 3\,2 \leftrightarrow 6},$$

with all other conjugacy classes mapped as required. Thus the nontrivial outer automorphism is reconstructed from two six-sets internal to the same code.

Evidence boundary and prior art. The fact that the 31 doily geometric hyperplanes form the Veldkamp space $PG(4, 2)$, with 15 perps, 10 grids, and 6 ovoids, is established prior art (Saniga–Planat–Pracna–Havlicek, arXiv:0704.0495). The advance asserted here is the executable repo-level synthesis through the explicit evaluation code, its dual minimum supports, and its two intrinsic six-actions; no literature-priority claim is made for the abstract Veldkamp census. No map to $W(3, 3)$, CE2, the currently missing K3 curvature object, or a physical Hilbert space is inferred without an additional explicit construction.

79.26.1 The code reconstructs all 155 Veldkamp lines

The coding realization above extends from Veldkamp points to the full incidence space. Since C has dimension five over $\mathbb{F}_2$, its 31 nonzero words are the points of $PG(4, 2)$ and every projective line is

$$\{u, v, u + v\}.$$

Exact enumeration yields 155 such triples. Classifying the common zero-set core of each triple by the doily incidence geometry reconstructed from $C^{\perp}$ gives the complete five-type census

$$\boxed{15 + 15 + 60 + 20 + 45 = 155}.$$

More explicitly, the core/type and code-weight compositions are

core	hyperplane composition	#
single point	$(8, 10, 10)$	15
collinear triple	$(8, 8, 8)$	15
unicentric triad	$(6, 8, 10)$	60
tricentric triad	$(8, 8, 8)$	20
pentad	$(6, 6, 8)$	45

The only ambiguity left by weights alone is the 35 all-perp $(8, 8, 8)$ lines. Minimum dual supports resolve it canonically:

$$\boxed{35 = 15_{\text{collinear}} + 20_{\text{tricentric}}}.$$

Thus the same code that reconstructs the 31 hyperplanes also reconstructs all 155 Veldkamp lines and all five core types.

The corresponding addition/fusion laws are

$$6 + 6 \to 8, \qquad 10 + 10 \to 8, \qquad 6 + 10 \to 8, \qquad 8 + 8 \to 8,$$

with pair counts $45, 15, 60, 105$, respectively. These are finite-code statements. The abstract identification $\mathcal{V}(W(2)) \cong PG(4, 2)$ and its five Veldkamp-line types are prior art (arXiv:0704.0495); the claim here is the executable reconstruction from the explicit quadratic-evaluation code and its dual, not a literature-priority claim.

79.27 CE2 carrier/provenance correction: the native object is 27×3

Evidence correction. The repository contains a genuine compact CE2 local-solution artifact with

$$\boxed{5832}$$

rows, but its native label set is not the forty projective points of $W(3, 3)$. The graded bracket machinery realizes

$$(\mathfrak{e}_6 \oplus \mathfrak{sl}_3) \oplus (27 \otimes 3) \oplus (27^* \otimes 3^*),$$

so a local CE2 label is (i, f) with $0 \le i < 27$ and $0 \le f < 3$. The committed affine–Heisenberg model identifies the carrier labels with $\mathbb{F}_3^3$, and the committed Schlaefli isomorphism is likewise a 27-point identification; in particular carrier label 22 maps to the Schlaefli line L_{45} (phase 0, half-root type).

The current compact source has the documented split

$$\boxed{5832 = 5184 + 648},$$

corresponding to the dominant one-term $|1/54|$ family and the two-term $|1/108|$ fiber/rank-drop family. Thus authentic CE2 local data do exist and are naturally organized on the E_6 minuscule 27-carrier.

Forty-point anchor boundary. A later scaffold attempted to turn "anchor 22" into a forty-point W33 orbit. Its corrected source now explicitly records that the predecessor generated synthetic weights from labels $1, \dots, 39$ without constructing the required automorphism action or evaluating the CE2 tensor, and it retains only three imported witnesses. The stronger type correction is

$$\boxed{\text{27-carrier CE2 anchor} \not\Rightarrow \text{40-point W33 orbit}}$$

without an explicit equivariant $27 \leftrightarrow 40$ transport. The anchor lane therefore remains open beyond its imported witnesses.

Reproducibility boundary. The compact 5832-row artifact names `artifacts/ce2_rational_local_solutio` as its source; that source is absent from the current checkout. Historical metadata names `tools/solve_sparse_ce2` as the producer, but that path is also absent and no exact-path Git history was found for it. The current `scripts/ce2_global_cocycle.py` implements substantial Affine–Heisenberg/metaplectic structure, but it also consumes the committed local table as authoritative data for known rows. Consequently the safe theorem boundary is

$$\boxed{\text{authentic 5832 local rows on } 27 \times 3 \quad \text{certified;} \quad \text{independent all-row formula replay still required.}}$$

A theorem-tier global compression must predict/generate all 5832 U/V rows without reading their answers and then compare them exactly. The K3 curvature object remains a separate provenance obligation.

79.28 $PG(3,2)$ Hamming-polar bridge

The doily quadratic-evaluation code admits a useful one-dimension-up coding interpretation. Writing

$$C = S + \langle q_0 \rangle, \qquad S \cong [15, 4, 8]_2,$$

we have

$$S^\perp \cong [15, 11, 3]_2, \qquad C^\perp = \{h \in S^\perp : \langle q_0, h \rangle = 0\}.$$

Thus $C^\perp$ is a codimension-one subcode of the binary length-15 Hamming code. The 35 minimum Hamming words are exactly the 35 projective lines of $PG(3,2)$, with supports

$$L = \{x, y, x + y\}.$$

The extra quadratic parity is precisely symplectic isotropy, since

$$\boxed{\langle q_0, \mathbf{1}_L \rangle = q_0(x) + q_0(y) + q_0(x + y) = B(x, y).}$$

Hence

$$\boxed{35 = 15_{\text{isotropic}} + 20_{\text{nonisotropic}}},$$

where the 15 retained weight-three words are the doily lines and the 20 excluded projective lines are pairwise-noncollinear tricentric triads.

This also explains the $35 = 15 + 20$ split of the all-perp Veldkamp lines. For a Hamming line $L = \{a, b, a + b\}$, the three simplex/perp words s_a, s_b, s_{a+b} have common zero core $L^\perp$. If L is isotropic then $L^\perp = L$, giving one of the 15 collinear cores; if L is nonisotropic, $L^\perp$ is another nonisotropic line and gives one of the 20 tricentric cores.

Finally symplectic polarity is a fixed-point-free involution on the 20 nonisotropic lines, producing ten unordered pairs

$$L \longleftrightarrow L^{\perp}.$$

The six-point unions of these ten polar pairs are exactly the ten weight-six supports of C:

$$\boxed{\{L \cup L^{\perp}\} = \{\mathrm{supp}(c) : c \in C,\ \mathrm{wt}(c) = 6\}.}$$

Therefore the ten polar pairs are precisely the complements of the ten nine-point doily grids. This gives one mechanism linking the repo's recurrent $PG(3,2)$, simplex/Hamming, doily, Veldkamp, determinant, and grid layers. The statement is finite binary geometry/coding only.

79.29 The doily code as a point-derived bent biplane

The quadratic-evaluation code of the doily admits a useful one-coordinate completion. On $V = \mathbb{F}_2^4$ take the standard symplectic form B and $q_0(x) = x_0x_1 + x_2x_3$. The previously certified punctured code is

$$C = \{(B(a,x) + tq_0(x))_{x \neq 0} : a \in V,\ t \in \mathbb{F}_2\} = [15, 5, 6]_2.$$

Restoring the zero coordinate and the affine constant gives

$$D = \langle RM(1,4), q_0 \rangle = [16, 6, 6]_2, \qquad W_D = 1 + 16y^6 + 30y^8 + 16y^{10} + y^{16}.$$

Both C and D are self-orthogonal. Their generalized Hamming weights are $(6, 10, 12, 14, 15)$ and $(6, 10, 12, 14, 15, 16)$ respectively, and both have covering radius six.

The sixteen minimum supports of D form a symmetric 2-$(16, 6, 2)$ biplane: every two blocks meet in two points. Fixing the restored zero coordinate recovers the entire doily Veldkamp-point taxonomy. The ten blocks avoiding the distinguished point shorten to the ten weight-six grid-complement words of C; the six blocks through it, after deleting that point, are the six ovoids; and the thirty weight-eight words pair by complement, with the fifteen representatives vanishing at the distinguished coordinate shortening to the fifteen perp words. Thus one point of the biplane derives

$$10 \text{ grids} + 15 \text{ perps} + 6 \text{ ovoids} = 31.$$

The full biplane automorphism group is

$$\mathrm{Aut}(\mathcal{B}) = 2^4{:}\,\mathrm{Sp}(4,2) \cong 2^4{:}\,S_6, \qquad |\,\mathrm{Aut}(\mathcal{B})| = 11520.$$

There is simultaneously a Klein-geometric description of the earlier $15 + 20$ line split. The 35 lines of $PG(3,2)$ are the 35 binary points of the Klein quadric

$$p_{01}p_{23} + p_{02}p_{13} + p_{03}p_{12} = 0 \subset PG(5,2).$$

For the standard symplectic form, isotropy is exactly the hyperplane condition

$$p_{01} + p_{23} = 0,$$

so its section consists of the 15 doily lines and the remaining 20 Klein points are the nonisotropic lines. Symplectic polarity pairs those 20 lines into ten skew pairs; their six-point unions are exactly the ten grid-complement supports above. If M is their 10×15 incidence matrix, then

$$MM^{\mathsf{T}} = 4I_{10} + 2J_{10}, \qquad \mathrm{Spec}(MM^{\mathsf{T}}) = \{24^1, 4^9\}.$$

This is a finite coding/design/projective-geometric theorem only; no physical identification is inferred from it.

79.30 A full-group no-go for direct Schlaefli–W33 linear transport

The existing generator-level constructions realize the same inner group $G = PSp(4,3)$ on the 40 W33 points and on the 27 Schlaefli vertices. Both actions are transitive of rank three. The W33 graph has spectrum

$$12^1 \oplus 2^{24} \oplus (-4)^{15},$$

so its characteristic-zero permutation module is multiplicity-free with

$$\mathbb{C}^{40} \cong \mathbf{1} \oplus V_{24} \oplus V_{15}.$$

The Schlaefli action has subdegrees $1, 10, 16$ and degree-16 orbital graph $SRG(27, 16, 10, 8)$ with spectrum

$$16^1 \oplus 4^6 \oplus (-2)^{20},$$

hence

$$\mathbb{C}^{27} \cong \mathbf{1} \oplus V_6 \oplus V_{20}.$$

The only common irreducible constituent is therefore the trivial module. Schur's lemma gives the exact obstruction

$$\boxed{\dim \mathrm{Hom}_{PSp(4,3)}(\mathbb{C}^{27}, \mathbb{C}^{40}) = 1}.$$

Thus every full-group equivariant linear map is a scalar multiple of the constant all-ones channel; there is no nonconstant direct characteristic-zero linear transport between the 27 and 40 carriers. A nontrivial bridge must instead break to a proper subgroup, be nonlinear, pass through a larger intermediate carrier, or use a modular coefficient field, which is a separate representation-theoretic problem.

79.31 CE2 normal-form compression versus a blind derivation

A source-level audit distinguishes two notions that had previously been conflated. A *runtime-blind* predictor does not consult the target answer table while producing its predictions; a *provenance-blind* predictor additionally uses no coefficient or rule that was fitted or selected from those target answers. A genuine no-answer-table replay requires both.

The current CE2 normal-form machinery does not yet meet that standard. In particular, `_derive_tables_via_normal_form()` explicitly reads `_simple_family_sign_map()` when constructing its constant-line tables, while `_derive_naive_tables()` uses the same map to supply the domain keys. More decisively, the source documents the delta-polynomial coefficients as fits obtained from the full 864-entry simple-family sign dataset. Hence the current result is accurately described as

$$\boxed{\text{structural compression verified; independent blind derivation open.}}$$

This correction does not invalidate the native 27×3 CE2 sparse rows, the Heisenberg/metaplectic support laws, or the empirical correctness of the compressed predictor. It changes only the evidentiary tier of the global closed form. The missing certificate must derive the seed and delta laws from the bracket/cochain structure, enumerate the domain without answer keys, freeze all predictions, and only then compare against the committed sparse-solution table.

79.32 Finite curvature versus a K3 realization

The current repository contains an explicit finite curved precomplex on the 45-point transport quotient,

$$C^0(\mathbb{F}_3^2) \xrightarrow{d_0} C^1(\mathbb{F}_3^2) \xrightarrow{d_1} C^2(\mathbb{F}_3^2), \qquad K = d_1 d_0 \pmod 3.$$

Its adapted off-diagonal curvature block is a genuine internally constructed object; the current source records rank 36, and its triangle-row localization is supported on 2428 transport triangles. These statements are finite consequences of the W33 transport data.

They must, however, be distinguished from a realization by an actual K3 geometric/cochain object. The historical 2428×36 witness scan was corrected because it scanned a newly allocated zero matrix, and the later deformation script explicitly inserts a nonzero entry by hand while acknowledging that existence "on the actual K3 side" remains open. Accordingly we record the evidence boundary

$$\boxed{\text{finite curved precomplex closed; K3 realization open.}}$$

A K3 promotion requires a named source object and hash, an explicit basis/coordinate map into the finite cochain carrier, compatibility of the K3 differential/connection with d_0, d_1, and an independent comparison of the induced curvature with the finite off-diagonal block. No dimension or support-count coincidence substitutes for that map.

79.33 A repo-native 2026 Vogel split-Casimir certificate

The Vogel connection can be tested at operator level rather than by matching dimensions. Starting from the integral Chevalley realization of the minuscule E_6 module V_{27}, commutator closure inside $\mathrm{Mat}_{27}(\mathbb{Z})$ gives the full 78-dimensional Lie algebra. For an integral basis X_a let

$$G_{ab} = \mathrm{Tr}_{27}(X_a X_b)$$

and use the trace-dual basis to form the split Casimir on $V_{27} \otimes \mathfrak{e}_6$. In the deterministic basis used by the verifier, $18G^{-1}$ is integral, so if

$$O_{18} = 18 \sum_a \rho_{27}(X_a) \otimes \mathrm{ad}(X^a),$$

then O_{18} is an integral sparse 2106×2106 matrix. Exact integer multiplication gives

$$\boxed{(O_{18} - 3I)(O_{18} + 12I)(O_{18} + 36I) = 0}.$$

With the Vogel normalization $\widehat{C} = O_{18}/72$, the spectrum is therefore

$$\boxed{\left(\frac{1}{24}\right)^{1728} \oplus \left(-\frac{1}{6}\right)^{351} \oplus \left(-\frac{1}{2}\right)^{27}},$$

recovering the characteristic identity for the E_6 specialization of $27 \otimes 78$ in the 2026 split-Casimir literature. The corresponding exact spectral projectors are

$$P_{1728} = \frac{(O_{18} + 12I)(O_{18} + 36I)}{585}, \qquad P_{351} = -\frac{(O_{18} - 3I)(O_{18} + 36I)}{360},$$

$$P_{27} = \frac{(O_{18} - 3I)(O_{18} + 12I)}{936}.$$

They are pairwise orthogonal, idempotent, sum to the identity, and have traces $1728, 351, 27$. The exact moments are

$$\operatorname{Tr}\widehat{C} = 0, \qquad \operatorname{Tr}\widehat{C}^2 = \frac{39}{2}, \qquad \operatorname{Tr}\widehat{C}^3 = -\frac{39}{8} = -\frac{1}{4}\operatorname{Tr}\widehat{C}^2.$$

This is an E_6 operator certificate on a repo-native carrier. It does not prove existence of Vogel's conjectural universal Lie algebra, nor does a dimension match by itself define a W33–Vogel morphism. We therefore distinguish arithmetic observations, universal specializations, operator certificates such as the present one, and the still open stronger problem of constructing an explicit W33-derived Vogel intertwiner.

79.34 The bent biplane as the abstract Kummer configuration

The $[16, 6, 6]_2$ bent-function code admits an explicit identification with the classical Kummer 16_6 incidence configuration. Its sixteen minimum supports are

$$\mathcal{B}_a = \{x \in \mathbb{F}_2^4 : q_0(x + a) = 1\}, \qquad q_0 = x_0x_1 + x_2x_3.$$

The matrix

$$M = \begin{pmatrix} 1 & 1 & 0 & 1 \\ 1 & 1 & 1 & 0 \\ 1 & 0 & 1 & 1 \\ 1 & 1 & 0 & 0 \end{pmatrix} \in GL(4, 2)$$

sends the six-point support of q_0 to the standard cross in a 4×4 array: the three other points in the distinguished row together with the three other points in the distinguished column. Consequently $M\mathcal{B}_a$ is the row/column cross centred at Ma for every a, providing an explicit labelled incidence isomorphism with the standard row/column Kummer configuration.

Thus the point-derived doily split has a Kummer reading: fixing one node leaves six incident blocks and ten nonincident blocks. Under the established shortening these become respectively the six doily ovoids and the ten grid-complement supports. The full automorphism group remains

$$2^4{:}\,\mathrm{Sp}(4, 2) \cong 2^4{:}\,S_6, \qquad |\operatorname{Aut}| = 11520,$$

matching the classical Kummer group $W(D_6)/\{\pm 1\}$.

The 32-vertex point/block Levi graph is furthermore explicitly isomorphic to the folded six-cube

$$Q_6/\{x \sim x + 111111\},$$

with spectrum

$$\boxed{6^1 \oplus 2^{15} \oplus (-2)^{15} \oplus (-6)^1}.$$

Primary Kummer-surface theory realizes the 16 points and 16 blocks as nodes and tropes of a Kummer quartic, whose minimal resolution is a K3 surface. The present result is therefore a genuine incidence-level K3 bridge. It does not yet choose a specific projective quartic in the binary labels or construct a chain map from its K3 divisor/cochain lattice into the 45-point transport-curvature precomplex; those remain separate realization problems.

79.35 A common $\mathbb{Z}_{12}$ refinement of the CE2 and Kummer gradings of E_8

The order-three grading used by the native CE2 construction and the order-four grading associated with the Kummer/half-spin lane can be realized simultaneously on one explicit E_8 root system. In the deterministic simple-root ordering of the verifier, the highest root has marks

$$(4, 6, 5, 4, 3, 2, 2, 3).$$

The relevant mark-4 and mark-3 nodes are adjacent. Reducing the corresponding simple-root coefficients modulo 4 and 3 respectively gives

$$\mathfrak{e}_8 : \qquad 60 + 64 + 60 + 64$$

with neutral root type $D_5 + A_3$, and

$$\mathfrak{e}_8 : \qquad 86 + 81 + 81$$

with neutral root type $E_6 + A_2$. These are the standard dimension decompositions

$$(45, 1) + (1, 15) \mid (16, 4) \mid (10, 6) \mid (16^*, 4^*)$$

and

$$(78, 1) + (1, 8) \mid (27, 3) \mid (27^*, 3^*)$$

respectively.

Because both gradings are toral, they commute. Exact enumeration of all 240 roots, with the eight Cartan directions placed in bidegree $(0, 0)$, gives the joint dimension table

	0	1	2
0	54	3	3
1	16	48	0
2	0	30	30
3	16	0	48

where rows are indexed by $\mathbb{Z}_4$ and columns by $\mathbb{Z}_3$. Its row sums are $60, 64, 60, 64$ and its column sums are $86, 81, 81$. The doubly neutral root subsystem has 46 roots of type $D_5 + A_2$ and rank seven; retaining the eighth Cartan direction gives the reductive fixed algebra

$$\boxed{\mathfrak{so}_{10} \oplus \mathfrak{sl}_3 \oplus \mathfrak{u}_1}, \qquad \dim = 45 + 8 + 1 = 54.$$

Since $\gcd(4, 3) = 1$, the Chinese remainder theorem converts the bidegree into a single $\mathbb{Z}_{12}$ grading with sector dimensions

$$\boxed{54, 48, 30, 16, 3, 0, 0, 0, 3, 16, 30, 48}.$$

In particular the CE2 81-sector refines dimensionally as $48 + 30 + 3$, while the Kummer half-spin 64-sector refines as $48 + 16$.

The repository independently contains a μ_{12} scalar-phase theorem for qutrit Clifford gates. The present $\mathbb{Z}_{12}$ is instead an E_8 root-space grading group; equality of their orders is not an identification. A physical or computational bridge requires an explicit character/intertwiner relating the grade automorphism to the scalar phase action. Likewise, the common refinement supplies representation-theoretic selection rules that may be used to attack CE2 and K3 realization problems, but it does not by itself solve either one.

79.36 Vogel projector channels refined by the Kummer-adjacent order-four grading

The exact E_6 split-Casimir decomposition

$$27 \otimes 78 = 1728 \oplus 351 \oplus 27$$

from the Vogel operator certificate is compatible with the adjacent $D_5 + U(1)$ grading inherited from the Kummer order-four grading of E_8. In the E_6 Cartan convention used by the minuscule-27 verifier, the $U(1)$ charge functional is

$$q = (4, 5, 6, 3, 4, 2)$$

in fundamental-weight coordinates, normalized so that

$$27 = 1_4 \oplus 10_{-2} \oplus 16_1, \qquad 78 = (45 + 1)_0 \oplus 16_{-3} \oplus 16_3.$$

Reducing charges modulo four gives

$$27 : (1, 16, 10, 0), \qquad 78 : (46, 16, 0, 16).$$

The 351 summand occurring in $27 \otimes 78$ is the fundamental module conjugate to $\wedge^2 27$; its charge profile follows exactly from pairwise sums of the 27^* weights:

$$\boxed{351 : (45, 160, 130, 16)}.$$

Subtracting this and the 27 profile from the tensor-product convolution gives

$$\boxed{1728 : (256, 736, 576, 160)}.$$

Hence, residue by residue,

$$(302, 912, 716, 176) = (256, 736, 576, 160) + (45, 160, 130, 16) + (1, 16, 10, 0).$$

The Vogel spectral projectors are therefore simultaneously resolved by the Kummer-adjacent order-four charge. Tensoring by the A_2 triplet relevant to the native CE2 grade multiplies these profiles by three; in particular the $27 \otimes 3$ channel is $(3, 48, 30, 0)$, recovering the same $3 + 48 + 30$ refinement found directly in the common E_8 grading.

This is a compatibility theorem for concrete E_6 representations and projectors. It does not identify Kummer geometry with Vogel's conjectural universal Lie algebra or its diagrammatic Λ-algebra, and it does not by itself provide the still-missing blind CE2 sign derivation.

79.37 An intrinsic double-six decoder and a trace-corrected finite Pauli validator

The spread code now recovers the double-sixes intrinsically. Let

$$C_{\text{spread}} = [45, 21, 5]_2$$

be the code generated by the twenty-seven ten-D_4 spread words, and let $\mathcal{M}_5$ be its intrinsic shell of twenty-seven minimum words. Exact enumeration of all 2^{21} codewords finds 21,168 words of weight fifteen. Exactly thirty-six of them have the minimum-shell intersection profile

$$\boxed{\left\{ |\operatorname{supp}(x) \cap \operatorname{supp}(m)| : m \in \mathcal{M}_5 \right\} = 0^{12}3^{15}.}$$

This is the unique profile class of size thirty-six. Only after this code-intrinsic selection is complete do we compare with the cubic-surface coordinates: the selected words are exactly the thirty-six columns of the 45×36 disjoint-tritangent/double-six incidence matrix N. Joining two selected words when their supports meet in six coordinates gives, objectwise,

$$\boxed{H_{36} = \mathrm{SRG}(36, 20, 10, 12)},$$

with 360 intersections of size six and 270 intersections of size three.

The ownership boundary is important. Passes 7182 and 7184, in `analysis/w33_pass7182_d4_glue_spread_code.py` and `analysis/w33_pass7184_spread_code_v20_v24_module.py`, own C_{spread}, its twenty-seven minimum words, and the $\mathbf{1} \oplus V_{20}$ statement. Passes 7225–7248, in `analysis/w33_pass7225_7232_spread_code_doily_puncture.py` and `analysis/w33_pass7241_7248_double_six_slice_generator.py`, own the externally constructed thirty-six double-six words and $\mathrm{col}(N) = C_{\mathrm{spread}}$. The new result here is the converse intrinsic selector and the reconstruction of H_{36} from its pair intersections.

The two visible carriers resolve one orthogonal $15 + 20 + 1$ decomposition. Let B be the 40×36 W33-line/spread incidence matrix and align the columns of N to those of B using the explicit Pass4992 spread/double-six scheme isomorphism. If A is the $\mathrm{SRG}(36, 15, 6, 6)$ overlap-four graph, define

$$E_{15} = \frac{6I + 2A - J}{12}, \qquad E_{20} = \frac{9I - 3A + J}{18}, \qquad E_1 = \frac{J}{36}.$$

Then exact integer linear algebra gives

$$E_{15} + E_{20} + E_1 = I_{36},$$

$$\left(B - \frac{1}{4}J\right)^T \left(B - \frac{1}{4}J\right) = 18E_{15}, \qquad \left(N - \frac{1}{3}J\right)^T \left(N - \frac{1}{3}J\right) = 18E_{20},$$

and the cross-Gram matrix vanishes:

$$\boxed{\left(B - \frac{1}{4}J\right)\left(N - \frac{1}{3}J\right)^T = 0.}$$

Thus, with $u = 2^{-1/2}\mathbf{1}_{36}$,

$$T = \begin{bmatrix} B - J/4 \\ N - J/3 \\ u \end{bmatrix}, \qquad \boxed{T^T T = 18I_{36}}.$$

The tritangent lanes realize the rank-twenty part of the old rank-twenty-one Naimark complement; the common scalar row supplies the final dimension.

The same composition has a fully integral lowering. Set

$$C_4 = 4B - J_{40,36}, \qquad D_3 = 3N - J_{45,36},$$

and

$$K = \begin{bmatrix} 3C_4 \\ 4D_3 \\ 6J_{2,36} \end{bmatrix}.$$

Then

$$\boxed{K^T K = 2592I_{36}}, \qquad K \in \{-4, -3, 6, 8, 9\}^{87 \times 36}.$$

These coefficients are shift–add realizable, but no synthesis cost or timing is inferred for K. Pass3694 `analysis/w33_pass3694_3700_spread_etf_axial_closure.py` already owns the abstract ETF$(15, 36)$ and its rank-twenty-one Naimark complement; Pass4992 `analysis/w33_pass4992_4999_common.py` owns the alignment; Pass7241 owns the literal N; and Pass7249–7304 `analysis/PASS7249_7304_eight_frontier_attacks.md` already owns the centered rank-twenty two-distance frame. What is new is their exact joint orthogonal composition and the integer transform K.

The intrinsic shells descend through the 27-line E_6 carrier. Let T be the 27×45 minimum-shell/tritangent incidence and let R be the 27×36 cubic-line/double-six incidence. Once the Pass7305 thirty-six-set is selected, zero intersection between the twenty-seven minimum words and those thirty-six words reconstructs R objectwise, without importing root coordinates. The three incidence carriers obey

$$\boxed{T^T R = 2(J - N)}.$$

After centering, all three nonconstant sectors have rank twenty and the exact factorization is

$$\boxed{T_0^T R_0 = -2N_0}, \qquad -\frac{N_0}{\sqrt{18}} = \left(\frac{T_0}{\sqrt{6}}\right)^T \left(\frac{R_0}{\sqrt{12}}\right).$$

Thus the same rank-twenty Naimark shadow factors through the minuscule 27-line E_6 carrier by named matrices.

The graph H_{36} has 1200 triangles. Exactly 120 have empty common R-intersection and 1080 have four common cubic lines. The resulting triangle–edge parity system over $\mathbb{F}_2$ has rank 325 and recovers a switching class of signed Gram matrices G satisfying

$$\boxed{\operatorname{rank} G = 6, \qquad G^2 = 12G},$$

so $\operatorname{spec}(G) = 12^6 \oplus 0^{30}$. A direct cross-check chooses one A_2 anchor in the current 240-root E_8 model. Its orthogonal complement contains 72 roots, or 36 projective root lines, and one frozen H_{36} isomorphism maps the intrinsic thirty-six-set to them with off-diagonal Gram profile $(-1)^{120}, 0^{270}, 1^{240}$. This is an actual-root cross-certificate but not a canonical map: it depends on the chosen A_2 anchor and H_{36} gauge, and the thirty-six-set is not asserted to be an invariant subset of the code embedding's transitive anisotropic 120-set. Pass7163–7170 `analysis/w33_pass7163_7170_e8_hexagonal_lift.py` owns the ambient E_8/A_2 realization; Pass7317–7320 owns this chosen-gauge composition.

The same witness also closes a tempting but false mod-twelve reading of K. Every column of K is identical modulo twelve, with row residues $9^{40}, 8^{45}, 6^2$. Removing those row constants and dividing by twelve gives

$$Z^T Z = 18I_{36} + 42J_{36},$$

while column differences satisfy

$$D^T D = 18(I_{35} + J_{35}), \qquad \operatorname{rank} D = 35,$$

a scaled A_{35} difference lattice. The constant column residue therefore rules out identifying K mod 12 with the nontrivial E_8 $\mathbb{Z}_{12}$ grading.

A proof-carrying q=7 certificate validator. The frozen q=7 witness contains thirty-three projective labels and 528 unordered pairs, all with nonzero symplectic product. Independent projective rescaling changes the six nonzero residue populations but never the zero/nonzero predicate, so the RTL exposes only `inputs_valid` and `noncommute`. Yosys SAT proves the Mersenne-fold pair core equal to both the signed symplectic formula and a naive remainder circuit for every one of the $2^{24} = 16{,}777{,}216$ raw input assignments.

The measured `synth_ice40` frontier is

design	LUT4	carry	FF	BRAM	cycles
naive pair core	528	262	0	0	combinational
Mersenne pair core	129	40	0	0	combinational
register serial	1637	63	814	0	562
synchronous-BRAM serial	196	63	48	1	1618

and exact simulation accepts the frozen witness and rejects a deterministic duplicate-point corruption in all three complete-check architectures. A seeded, unconstrained-IO nextpnr run on iCE40HX8K-CT256 reports 2439 and 230 routed logic cells and final proxy frequencies 31.80 and 41.31 MHz for the register and BRAM serial designs respectively. These are synthesis and place-and-route proxies, not board timing, IO validation, power measurements, or a fabricated device.

Typed stabilizers and the extension-field trace firewall. The exact GAP witness deliberately separates the linear symplectic group, its projective image, and projective symplectic similitudes:

q	$\lvert\mathrm{Stab}_{\mathrm{Sp}}\rvert$	$\lvert\mathrm{Stab}_{\mathrm{PSp}}\rvert$	$\lvert\mathrm{Stab}_{\mathrm{PCSp}}\rvert$
3	18	9	18
5	24	12	12
7	2	1	2
9	4	2	2

For the frozen q=5 order-three-invariant eighteen-set only, the linear stabilizer is $\mathrm{SL}(2,3)$ and both projective stabilizers are A_4. This is not a classification of all q=5 maxima and not an upper bound for $\alpha(W(3,5))$. For the packet-owned q=7 witness, the standard projective Clifford/PSp stabilizer is trivial, whereas the larger commutation-preserving PCSp stabilizer is C_2.

For $q = p^r$, the standard Galois–Pauli commutator is controlled by

$$\mathrm{Tr}_{\mathbb{F}_q/\mathbb{F}_p} B(x,y),$$

not merely by whether $B(x,y)$ vanishes in $\mathbb{F}_q$. Consequently one $\mathbb{F}_9$ projective point becomes a four-point totally isotropic line in $PG(7,3)$. The 820 such lines partition all 3280 projective points. The frozen fifty-one-point construction becomes 204 physical classes in fifty-one commuting K_4 blocks; between every two blocks the commuting cross-graph is a perfect matching $4K_2$. The resulting commuting graph is 53-regular with 5406 edges. Therefore

the fifty-one objects are mutually nonorthogonal spread lines, not fifty-one pairwise-noncommuting physical Pau

The q=9 construction remains a finite-geometric lower bound; the value of $\alpha(W(3,9))$ is not determined.

Finally, the Lean module `formal/W33/Pass7316AntisymplecticRescaling.lean` proves the carrier-independent scalar identity that rescaling a bilinear similitude of multiplier μ by c changes its multiplier to $c^2\mu$. In particular an antisymplectic map becomes symplectic when $c^2 = -1$. This formalizes the square-class mechanism separating q=7 from q=9; the finite-field enumeration and the stabilizer orders remain GAP-owned.

Evidence boundary. All promoted statements are exact finite code, incidence, frame, finite-field, group, RTL-equivalence, synthesis, place-and-route-proxy, or Lean-kernel statements with the scopes above. They do not establish quantum state preparation, laboratory hardware, device performance, loss or noise budgets, particle assignments, masses or energies, continuum dynamics, or a physical theory. The E_8 root cross-check is chosen-gauge, and the mod-twelve residue of K is explicitly not the E_8 $\mathbb{Z}_{12}$ grading.

Passes 7501–7508: a Monster-local triality/affine port

The Pass7465–7472 reduction of $E_8/3E_8$ identified a classical $D_4(3)$ triality carrier with

$$\boxed{1120 + 1120 + 1120 = 3360}$$

objects: the 1120 singular points of $Q^+(7,3)$ together with its two families of 1120 maximal totally singular generators. On the E_8 side, the point family is the radical image of the 1120 A_2 root subsystems and the two generator families are the 2240 Eisenstein $W(3,3)$ leaves.

There is now an external sporadic-group port for exactly this ambient carrier. ATLAS lists a maximal Monster subgroup

$$H = (3^2{:}2 \times O_8^+(3)).S_4$$

with an intransitive permutation representation of degree 3369. The exact ATLAS generators are hash-pinned by the Pass7501 verifier. Their orbit census is

$$\boxed{3369 = 9 + 3360}.$$

The image on the nine-point orbit has order 432 and contains a normal regular C_3^2, hence is the natural affine action

$$\boxed{AGL(2,3) = 3^2{:}GL(2,3)}.$$

The image on the 3360-point orbit has order

$$\boxed{118852315545600 = |O_8^+(3) : S_4|}.$$

Using the ATLAS order of H, the kernels of the two orbit actions have orders 18 and $|O_8^+(3)|$, respectively. Both orbit images therefore have one common quotient of order 24:

$$432/18 = 24 = |O_8^+(3) : S_4|/|O_8^+(3)|.$$

Thus the subgroup is the fibre product

$$\boxed{H \cong AGL(2,3) \times_{S_4} \big(O_8^+(3) : S_4\big).}$$

In other words, the Monster-local 3369-point action couples an affine $\mathbb{F}_3^2$ nine-sheet to the $D_4(3)$ triality carrier through one common S_4 outer coordinate. This is a genuine subgroup-action bridge, not an integer coincidence. ATLAS also lists $O_8^+(3) : S_4$ as a maximal subgroup of the Baby Monster, so the same 3360-object carrier has a second sporadic port.

Evidence boundary. The theorem identifies the ambient triality carrier containing all 2240 Eisenstein $W(3,3)$ leaves with a standard $O_8^+(3) : S_4$ permutation carrier inside a Monster maximal subgroup. It does not assert that the Monster stabilizes one chosen $W(3,3)$ leaf by the leaf's internal incidence action, and it does not derive the Moonshine module, the Griess product, a modular function, or any physical parameter from $W(3,3)$.

Passes 7509–7516: the common S_4 is the affine-direction quotient

Pass7501–7508 identified the Monster maximal subgroup

$$(3^2{:}2 \times O_8^+(3)).S_4 \cong AGL(2,3) \times_{S_4} (O_8^+(3) : S_4)$$

from the hash-pinned ATLAS 3369-point action. The common S_4 can now be identified geometrically rather than merely by its order.

The restricted nine-point image has order 432 and contains a normal regular translation subgroup

$$T \cong C_3^2.$$

Its four order-three subgroups are the four affine directions. Their point orbits produce exactly twelve three-point lines in four parallel classes of three lines each. Every pair of points lies on one line and every point lies on four lines, so the recovered incidence geometry is

$$\boxed{AG(2,3) = (9_4, 12_3).}$$

Conjugation by the full affine group permutes the four direction subgroups. The induced image has order 24, with element-order census

$$1^1\, 2^9\, 3^8\, 4^6,$$

and its kernel has order 18. Therefore

$$\boxed{AGL(2,3)/(3^2{:}2) \cong PGL(2,3) \cong S_4.}$$

Thus the same four-letter coordinate has two exact meanings in the Monster-local fibre product: on the nine-sheet it labels the four affine/Hesse parallel classes, while on the 3360-sheet it is the outer $D_4(3)$ coordinate acting on the triality geometry. The sporadic subgroup couples these two direction systems through this common S_4.

Evidence boundary. The project already contained the abstract $AG(2,3)$/Hesse counts. The new statement is the exact welding of their direction quotient to the outer S_4 of the Monster-local 3360 triality carrier. No physical interpretation of the four directions follows.

Passes 7517–7524: the projective E_8 Weyl action inside the Monster-local carrier

The classical exceptional-group identification by itself is not new: one has

$$W(E_8) \cong 2.O_8^+(2).2.$$

The new question is whether the *current* E_8 action on the 1120 A_2 subsystems and 2240 Eisenstein $W(3,3)$ leaves can be located explicitly inside the 3360-object $Q^+(7,3)$ triality carrier of Pass7465 and the Monster-local carrier of Pass7501.

Reconstructing the eight simple reflections gives a faithful projective action on the 1120 A_2 subsystems of order

$$\boxed{348364800 = |W(E_8)/\{\pm I\}|}.$$

The 2240 leaves split into the two generator-family halves of size 1120. Every simple reflection fixes the singular-point family as a type and exchanges the two generator families. Hence the induced type action is C_2, with kernel

$$\boxed{174182400 = |O_8^+(2)|}.$$

Thus the current objects realize, rather than merely quote,

$$\boxed{W^+(E_8)/\{\pm I\} \cong O_8^+(2)}, \qquad \boxed{W(E_8)/\{\pm I\} \cong O_8^+(2) : 2}.$$

Combined with the $D_4(3)$ triality closure and the Monster-local port, this yields the nested carrier chain

$$\boxed{O_8^+(2) : 2 < O_8^+(3) : S_4 < (3^2{:}2 \times O_8^+(3)).S_4 < \mathbb{M}.}$$

The projective E_8 subgroup uses only the outer involution that swaps the two generator families; the ambient $D_4(3)$ symmetry enlarges this to the full outer S_4. The index of the projective E_8 image in the 3360 ambient group is

$$\boxed{341172 = 2^2\, 3^8\, 13}.$$

Evidence boundary. The abstract $O_8^+(2)$ exceptional isomorphism is classical and was already partly discussed in the historical Pass1301. The new theorem is the explicit placement of the current A_2/W33-leaf action in the current $Q^+(7,3)$ carrier and then in the Monster-local subgroup action. It implies no moonshine or physical parameter relation by itself.

Passes 7525–7532: Monster evidence boundary after the exact triality port

The current E_8/Monster frontier is now strong enough to separate three things that the chronological manuscript sometimes mixed: exact finite theorems, standard external moonshine facts, and physical/holographic hypotheses.

Exact current finite statement. Pass7465–7472 constructs the classical $Q^+(7,3)$ triality carrier

$$1120 + 1120 + 1120 = 3360$$

from $E_8/3E_8$, with the 2240 Eisenstein $W(3,3)$ leaves as the two generator families. Pass7501–7508 proves from hash-pinned ATLAS generators that a maximal Monster subgroup

$$(3^2{:}2 \times O_8^+(3)).S_4$$

has orbit split $9 + 3360$, with images $AGL(2,3)$ and $O_8^+(3) : S_4$ coupled over one common S_4. Pass7509–7516 identifies that S_4 on the nine-sheet as the action on the four affine directions of $AG(2,3)$, and Pass7517–7524 locates the actual projective E_8 Weyl action as

$$\boxed{O_8^+(2) : 2 < O_8^+(3) : S_4}.$$

These are explicit permutation/subgroup maps rather than cardinality matches.

Standard external facts, not W33 deductions. The Moonshine VOA $V^\natural$ has central charge 24, automorphism group the Monster, and graded dimension the normalized J-function; the Leech/-Conway/FLM orbifold construction is standard moonshine mathematics. Those facts may be used as external comparison data, but they are not consequences of the W33 finite geometry.

Historical language demoted to hypothesis. Chronological photonic sections titled "The code lattices are the moonshine ladder" and "The boundary central charge is $f = 24$: the Monster CFT is the holonet's holographic dual" contain sentences stronger than the certified map. Statements identifying the holonet boundary CFT with $V^\natural$, identifying the W33 code with an AdS/CFT bulk–boundary dictionary, or deriving three physical generations from the E_8^3 Niemeier lattice are therefore **hypotheses/analogies, not theorem consequences**. The equality

$$24 = f = c(V^\natural)$$

is a numerical bridge unless and until an explicit VOA/CFT functor from the W33 construction is supplied.

Corrected strongest Monster claim. The theorem-grade statement is that the E_8 mod-3 construction yields the standard 3360-object $D_4(3)$ triality carrier containing all 2240 Eisenstein W33 leaves; that carrier is the $O_8^+(3) : S_4$ orbit in a maximal Monster subgroup, paired with an affine $AG(2,3)$ nine-sheet through a common S_4; and the projective E_8 Weyl action is the point-type stabilizing $O_8^+(2) : 2$ subgroup. No Griess product, McKay–Thompson series, Moonshine VOA, AdS/CFT dictionary, or physical observable has yet been constructed from W33 by this result.

79.38 The corrected Leech interface reaches the common W33 code before selecting a polarity

The order-nine Leech quotient must be kept in its corrected mixed-torsion form

$$C = \operatorname{coker}(1 - g) \cong (\mathbb{Z}/3)^2 \oplus (\mathbb{Z}/9)^2,$$

not as the retracted elementary $\mathbb{F}_3^6$ candidate. The unimodular linking form therefore supplies canonical top and socle spaces

$$C/3C \cong \mathbb{F}_3^4, \qquad C[3] \cong \mathbb{F}_3^4,$$

paired perfectly over $\mathbb{F}_3$. Projectivizing gives the symmetric 2-$(40, 13, 4)$ point–hyperplane interface of $PG(3,3)$. This dual $40 + 40$ object is canonical; identifying the two sides by a nondegenerate alternating polarity is an additional datum. Under such an identification its incidence matrix is

$$N = I + A_{W(3,3)},$$

so the off-diagonal relation is the canonical $\mathrm{SRG}(40, 12, 2, 4)$.

The corresponding ternary incidence code has parameters

$$[40, 11, 13]_3,$$

and its dual is $[40, 29, 6]_3$ with 6240 minimum-weight words. These abstract code parameters are known; the present point is their transport onto the corrected Leech top–socle linking interface.

There are 468 nondegenerate alternating forms on $\mathbb{F}_3^4$, or

$$\boxed{234}$$

projective symplectic polarities modulo nonzero scalar. Pass 5744–5751 already found the same 234 W33 overlays. The refined computation splits them by Pfaffian into two families of 117. Comparing the edge sets of two labelled W33 graphs gives only the overlaps

$$60, \qquad 78, \qquad 96.$$

Within either 117-family, the overlap-96 relation is

$$\mathrm{SRG}(117, 36, 15, 9),$$

and the overlap-78 relation is its complement $\mathrm{SRG}(117, 80, 52, 60)$. The stabilizer of one projective alternating form is

$$PGSp_4(3) \cong W(E_6), \qquad |PGSp_4(3)| = 51840,$$

with $|PGL_4(3) : PGSp_4(3)| = 234$. Thus $W(E_6)$ occurs here as the isotropy group of a chosen W33 polarization inside the ambient projective $PG(3,3)$ carrier.

The strongest canonicality result is at the code layer. For any of the 234 W33 polarities let

$$N = I + A, \qquad Q = J - I - A.$$

Reducing the W33 strongly-regular identity modulo three gives

$$\boxed{N^2 = J \pmod 3}.$$

Direct verification over all 234 polarities shows that both row spaces are independent of the chosen polarity and

$$\mathrm{row}_{\mathbb{F}_3}(N) = \langle \mathbf{1} \rangle \perp \mathrm{row}_{\mathbb{F}_3}(Q).$$

The first space is the Leech-interface $[40, 11, 13]_3$ code, while the sum-zero core is exactly the polarity-independent quadratic/Veronese code from Pass 5744–5751,

$$\mathrm{row}_{\mathbb{F}_3}(Q) = [40, 10, 18]_3.$$

Consequently the corrected Leech construction reaches the common W33 ternary code *before* a particular W33 incidence overlay is selected. The remaining 234-fold ambiguity is geometric, not code-theoretic.

A second exact local result concerns the 27-point Schlaefli/H27 scheme. Its three nontrivial relations are precisely the Cayley partition of the qutrit Heisenberg group H_{27} into $Z(H_{27}) \setminus \{1\}$, a 16-element Schlaefli connection set, and the 8 horizontal elements. The restricted Steinberg image therefore admits the finite Heisenberg decomposition

$$V_{20} = V_8^{\mathrm{lin}} \oplus V_6^{(\omega)} \oplus V_6^{(\omega^2)},$$

with kernel $\mathbf{1} \oplus V_3^{(\omega)} \oplus V_3^{(\omega^2)}$. This is a representation-theoretic Fourier/Schrodinger statement only; no physical multiplet interpretation is inferred.

Evidence boundary. The dual $PG(3,3)$ interface was already established in Pass 7653–7660, and Pass 5744–5751 already owned the 234 overlays and common $[40, 10, 18]_3$ code. The new content is the H27 Fourier realization, the Pfaffian $117 + 117$ polarization moduli and edge-overlap geometry, the Leech transport to the ternary design code, and the exact weld

$$C_{\mathrm{Leech}} = \langle \mathbf{1} \rangle \perp C_{\mathrm{quad}}.$$

No canonical Leech/Co0-equivariant polarity $C/3C \to C[3]$ has yet been constructed, and no Monster-VOA or physical claim follows from these finite results.

Rank-24 root shadows and the Golay–tetracode glue bifurcation

The exhaustive rank-24 carrier classification leaves exactly three Niemeier lattices supporting the required pure Φ_9^4 order-nine quotient to $W(3,3)$: E_8^3, E_6^4, and A_2^{12}. The exact verifier computes the image of every root in the projective quotient $L/(I-X)L \cong \mathbb{F}_3^4$.

The three root shadows are different:

$$E_8^3: \qquad 720 = 40 \cdot 18,$$

with all forty points of $W(3,3)$ visible and no quotient-zero roots;

$$E_6^4: \qquad 288 = 72_{\mathrm{ker}} + 4 \cdot 54,$$

where the four visible points form one $W(3,3)$ line; and

$$A_2^{12}: \qquad 72 = 4 \cdot 18,$$

again supported on one $W(3,3)$ line, with no quotient-zero roots. In the E_8^3 carrier each individual E_8 factor already covers all forty points with six roots per point, recovering the earlier Eisenstein six-to-one $E_8 \to W(3,3)$ fibration.

The 72 quotient-zero roots of the E_6^4 carrier split componentwise as

$$4\,(A_2^3) = A_2^{12}.$$

This is an equality of root-system type, not an identification of the full Niemeier lattices. It nevertheless provides a common A_2^{12} root substrate on which the E_6^4 and A_2^{12} Niemeier overlattices can be compared exactly.

Relative to that common substrate, the A_2^{12} Niemeier lattice is selected by the extended ternary Golay code

$$C_G = [12,6,6]_3, \qquad W_G(y) = 1 + 264y^6 + 440y^9 + 24y^{12},$$

whereas the E_6^4 lattice is selected by a different self-dual code

$$C_E = [12,6,3]_3, \qquad W_E(y) = 1 + 8y^3 + 240y^6 + 464y^9 + 16y^{12}.$$

The eight weight-three words of C_E occur as four scalar pairs on four disjoint three-coordinate supports. Their local span has dimension four, implementing four $A_2^3 \to E_6$ extensions. Quotienting C_E by those four local extension lines leaves the self-dual $[4,2,3]_3$ tetracode.

This code decomposition explains the root counts. A nonzero A_2^*/A_2 class has three minimal representatives of norm $2/3$, so one weight-three glue word contributes $3^3 = 27$ norm-two vectors. Hence

$$72 + 8 \cdot 27 = 288,$$

and each scalar pair over one of the four visible line channels contributes

$$2 \cdot 27 = 54$$

visible E_6 roots, exactly the multiplicity measured by the root-shadow verifier. The Golay code has no weight-three word, so its glue adds no roots and the root system remains A_2^{12}.

Evidence boundary. These are finite lattice, code, and symplectic-quotient statements. The canonical executable certificates are `analysis/w33_pass9173_9184_root_shadow_trichotomy.py` and `analysis/w33_pass9185_9196_golay_tetracode_glue_bifurcation.py`. No continuum or particle-physics conclusion is inferred from the shared quotient.

Carrier symmetry, selector sign, and the transverse-glue phase space

The three rank-24 carriers of the same $W(3,3)$ quotient remain sharply distinguishable after one resolves their carrier symmetries. For the line-supported E_6^4 carrier, four independent local order-nine phase actions induce a group of order 27 on the quotient, while the signed tetracode monomial automorphisms induce the complete S_4 permutation action on the four visible line points. Together they generate the full line stabilizer,

$$|G_{\mathrm{line}}| = 1296 \quad \text{in } \mathrm{Sp}(4,3), \qquad |\overline{G}_{\mathrm{line}}| = 648 = 3^3{:}S_4$$

projectively. Thus the four-point E_6^4 root shadow is not merely a support set: its carrier centralizer realizes the complete $W(3,3)$ line symmetry.

The Niemeier automorphism-quotient images provide a second independent discriminator. Modulo the root Weyl groups, the E_8^3 carrier survives as the order-three factor cycle in S_3; the diagonal E_6^4 carrier dies completely in the $GL_2(3)$ quotient; and the A_2^{12} carrier survives as an order-three signed monomial element of $2.M_{12}$ projecting to the fixed-point-free M_{12} class $3B$ of cycle shape 3^4. Hence the common $W(3,3)$ quotient does not determine the umbral image.

A marked line is not a Suzuki selector. The exact M_{12}:2 polarization inside the 2.Suz six-qutrit module produces 7371 nondegenerate two-spaces A, and each candidate

$$W_A = A \oplus xA$$

already carries the ordered pair of Lagrangian lines A and xA. Consequently identifying the distinguished Niemeier root-shadow line with the first polarization line leaves all 7371 candidates; the exact $C_4 \times A_5$ similitude controller still has 90 nondegenerate candidate orbits. A successful weld therefore requires additional finite data beyond a marked line.

Root-shadow periodicity. The three-cyclotomic E_8 lift was checked at ranks

$$8,\ 24,\ 72,\ 216.$$

At every rung the quotient remains four-dimensional over $\mathbb{F}_3$, every individual E_8 factor covers all forty $W(3,3)$ points with six roots per point, and the total uniform fibre is respectively

$$6,\ 18,\ 54,\ 162.$$

Thus through four exact rungs the lift preserves the full-support E_8 root decoration, up to uniform multiplicity, not merely the abstract symplectic quotient.

The two glues generate a larger phase space. Let C_G be the extended ternary Golay $[12,6,6]_3$ glue of $N(A_2^{12})$ and C_E the quotient-selected $[12,6,3]_3$ glue describing $N(E_6^4)$ over the common A_2^{12} substrate. The exact computation gives

$$C_G \cap C_E = 0, \qquad C_G + C_E = \mathbb{F}_3^{12}.$$

Both are maximal isotropics for the standard discriminant pairing. Their nondegenerate cross-pairing canonically yields an alternating rank-12 form K for which both codes are Lagrangian, an orthogonal exchange involution S satisfying

$$SKS^{\mathsf{T}} = -K,$$

and a symplectic operator

$$R = KS, \qquad R^2 = -I, \qquad R^4 = I.$$

Since $x^2 + 1$ is irreducible over $\mathbb{F}_3$, R equips the 12-dimensional ternary phase space with an $\mathbb{F}_9$-module structure of dimension six. This is a characteristic-three finite-field complex structure generated by the pair of Niemeier glues; it is distinct from the characteristic-two modular modules denoted U_6 elsewhere in this manuscript.

The same exchange has a sharp root-theoretic effect. The four local E_6 extension directions span a

$$[12, 4, 3]_3$$

code with weight enumerator

$$1 + 8y^3 + 24y^6 + 32y^9 + 16y^{12}.$$

Under S this sector becomes an 81-word subcode of the ternary Golay code with parameters

$$[12, 4, 6]_3, \qquad 1 + 28y^6 + 48y^9 + 4y^{12}.$$

Thus the canonical exchange sends the sector whose weight-three glue creates the additional norm-two E_6 roots to a distance-six sector in which such root extensions are forbidden.

Orthogonal-sign twin selectors. The pair (K, R) induces on the Golay Lagrangian the symmetric form

$$C_-(a, b) = K(a, Rb),$$

which is exactly minus type $Q^-(5, 3)$ and has 112 singular projective points. Its complete two-space census is

$$3640 \text{ degenerate}, \qquad 4536 \text{ hyperbolic}, \qquad 2835 \text{ anisotropic},$$

so again exactly 7371 are nondegenerate. Suzuki's independently constructed selector is plus type $Q^+(5, 3)$, with

$$3640, \qquad 5265, \qquad 2106$$

in the same three categories. The total is sign-blind while the subtype split is not.

More generally, the standard odd-q orthogonal-group orders reduce by orbit–stabilizer to

$$N^+_{\text{nondeg}} = N^-_{\text{nondeg}} = q^4(q^2 - q + 1)(q^2 + q + 1),$$

with

$$H_+ - H_- = q^6, \qquad A_- - A_+ = q^6.$$

At $q = 3$ the transfer is $3^6 = 729$. The equality of this number with the cardinality of either ternary $[12, 6]$ glue code is forced by their common six-dimensionality and is not promoted to a separate physical law.

Conditional optical discriminator. Under a deliberately minimal readout model in which the forty quotient points are equal-weight output ports and quotient-kernel roots are dark, the pair

$$(\text{best-line fraction of visible intensity}, \ \text{dark-root fraction})$$

has signatures

$$E_8^3 : (0.1, 0), \qquad E_6^4 : (1, 1/4), \qquad A_2^{12} : (1, 0).$$

This is a falsifiable finite-port prediction conditional on the stated coupling model, not a derivation of an optical Hamiltonian or device transfer matrix.

Evidence boundary. The executable witnesses are `analysis/w33_pass9197_9204_e6_centralizer_line_sta` through `analysis/w33_pass9253_9260_orthogonal_sign_twin_selector.py`, with frozen certificates under `data/PART_W33_PASS9197...9260`. The Niemeier quotient groups, M_{12} conjugacy-class names, and finite orthogonal-group orders are classical input; the explicit carrier actions, glue-pair constructions, and cross-selector identifications are the repository results promoted here.

Passes 9465–9528: the glue pair is unitary, oriented, and root-shadow periodic

The transverse ternary Golay and quotient-selected E_6 glue codes determine the alternating form K, the exchange S, and $R = KS$ with $R^2 = -I$. Setting $B = KR^{\mathsf{T}}$ closes this to a finite Hermitian package:

$$C_{\mathrm{Sp}(12,3)}(R) \cong U(6,3), \qquad |U(6,3)| = 182699779456696320.$$

The symmetric form B has plus type in dimension 12, whereas the two glue halves are mutually B-orthogonal minus-type six-spaces and are simultaneously Lagrangian for K. The involution S preserves B, reverses K, and obeys $SRS = -R$. Exhausting signed coordinate monomials gives a further rigidity: although the E_6-relative glue alone has 62208 such symmetries, the common stabilizer of the ordered pair of concrete glue codes is only $\{\pm I\}$.

The three rank-24 carriers now have the exact projective centralizer fingerprint

$$\boxed{PSp(4,3)\ (25920) \supset 3^3{:}S_4\ (648) \supset 3^3{:}A_4\ (324)}.$$

These are respectively the E_8^3, E_6^4, and A_2^{12} images. Thus the E_6 carrier selects an unoriented $W(3,3)$ line, while the Golay/A_2^{12} carrier retains one additional orientation-parity bit on its four line channels.

The E_8 root-shadow recurrence is also exact at every lift depth. If

$$L(g)(x_0, x_1, x_2) = (x_2, gx_0, x_1),$$

then block sum induces

$$\operatorname{coker}(I - L(g)) \xrightarrow{\sim} \operatorname{coker}(I - g), \qquad [(x_0, x_1, x_2)] \mapsto [x_0 + x_1 + x_2].$$

Indeed, if $z_0 + z_1 + z_2 = (I - g)t$, then $y = (t, t - z_0 - z_2, t - z_0)$ satisfies $(I - L(g))y = z$. Therefore for every $m \geq 0$

$$\operatorname{rank} = 8\,3^m, \qquad \#E_8 \text{ factors} = 3^m, \qquad \boxed{\text{roots per } W(3,3) \text{ point} = 6\,3^m},$$

with all forty quotient points visible.

For a finite readout model with n stages of lazy nearest-neighbour $W(3,3)$ crosstalk,

$$T_\eta = (1 - \eta)I + \frac{\eta}{12} A_{W33},$$

a signal initially supported on one $W33$ line has exact retained line mass

$$p_n = \frac{1}{10} + \frac{9}{10}\left(1 - \frac{5\eta}{6}\right)^n.$$

With arbitrary port gains in $[3/4, 5/4]$, line support remains separated from the uniform E_8^3 shadow whenever

$$\left(1 - \frac{5\eta}{6}\right)^n > \frac{8}{53}.$$

Under a separate binary dark-monitor confusion rate at most $1/10$, the E_6^4 dark fraction remains separated from the zero-dark E_8^3 and A_2^{12} carriers by at least $3/20$. These are bounded finite-transfer statements, not a device-specific optical Hamiltonian.

Two negative results sharpen the remaining Suzuki/Leech weld. The certified $Q^+(5,3)$ controller's 90 nondegenerate candidate orbits refine only to 62 hyperbolic or 28 anisotropic orbits, so orthogonal subtype is not a unique selector. Moreover no canonical symplectic transport of the glue-derived R into the independent Suzuki 12-space is presently certified; the conjugacy orbit has

$$[\mathrm{Sp}(12,3) : U(6,3)] = 78795645053420272 00$$

choices. Separately, the striking Hall–Janko/$Q^-(5,3)$ cardinality matches $252 = 252$ and $63+63 = 126$ fail the natural graph test: induced degrees are 66 versus 81 and 31 versus 45. Any surviving bridge must therefore match a richer orbital/association-scheme structure rather than counts alone.

Finally, the stabilizer chain has a finite description-length reading: choosing the E_6 line reduces symmetry by a factor 40 ($\log_2 40$ bits), and choosing the Golay orientation reduces it by one further factor 2 (exactly one bit). This is log-cardinality bookkeeping, not thermodynamic entropy.

Passes 9725–9788: the transporter obstruction is Witt sign, and the F_9 package has a local-field lift

The natural point-scheme version of the Hall–Janko/$Q^-(5,3)$ bridge is now excluded. The 252 nonsingular Q^- points split into two norm fibers of size 126, and the basic $O^-(6,3)$ relation valencies are $45, 80, 36, 90$. Hence all invariant undirected union degrees lie in

$$\{0, 36, 45, 80, 81, 90, 116, 125, 126, 135, 161, 170, 171, 206, 215, 251\},$$

which excludes the $G_2(4)$ fixed-edge D-cell degree 66. Likewise a single 126-point norm fiber has only degrees $45, 80, 125$, excluding the $G_2(4)$ $B \cup C$ degree 31. Any surviving bridge must therefore use a derived scheme such as two-spaces or Lagrangians rather than point orthogonality.

The intrinsic symmetry of the transverse Golay/E_6 glue pair is much larger than its signed-coordinate symmetry. Inside

$$C_{\mathrm{Sp}(12,3)}(R) \cong U(6,3),$$

the complete ordered-pair stabilizer is

$$\boxed{O^-(6,3)}, \qquad |O^-(6,3)| = 26,127,360,$$

with projective order $13,063,680$. Allowing the two glue halves to exchange doubles the stabilizer to $52,254,720$. Thus the earlier $\{\pm I\}$ result is correctly interpreted as signed-monomial rigidity, not absolute unitary rigidity.

The A_2 line-orientation quotient and the $G_2(4)$ edge-orientation quotient are both C_2: the former is $3^3{:}S_4 \to C_2$ with kernel $3^3{:}A_4$, while the latter is endpoint reversal, exchanging the unique nonsymmetric rank-14 pair $AD \leftrightarrow BB/CC$. Once an external bridge matches the underlying unoriented objects, the orientation identification is forced because $\mathrm{Aut}(C_2)$ is trivial. However the parent stabilizers of orders 648 and 24,192 cannot embed into one another, so the bit itself is not the transporter.

More strongly, the presently distinguished transporter is impossible. On the glue side the exchanger R satisfies $R^2 = -I$ and the canonical Lagrangian half carries $Q^-(5,3)$ with 112 singular projective points. On the exact ATLAS Suzuki side the exchanger x is symplectic with $x^2 = -I$, but its canonical M12 polarization half carries $Q^+(5,3)$ with 130 singular points. If a symplectic

map T both conjugated R to x and mapped one distinguished half to the other, then the induced forms

$$K(u, Rv) \quad \text{and} \quad J(Tu, xTv)$$

would be congruent, preserving Witt sign, which would force $112 = 130$. Therefore

$$\boxed{\text{no canonical-half-preserving } R \text{ transporter exists.}}$$

The obstruction is selective rather than fatal. For fixed R, the unitary centralizer has two orbits of transverse Lagrangians:

half-form	stabilizer	orbit size
$Q^+(5,3)$	$O^+(6,3)$	$7,530,558,336$
$Q^-(5,3)$	$O^-(6,3)$	$6,992,661,312.$

Thus the same glue-derived R admits billions of plus-type alternative polarizations capable of clearing the Suzuki Witt-sign obstruction. The next problem is to select one canonically.

A coherent finite readout model was also tested on 40×3 complex amplitudes: forty $W33$ ports and three internal qutrit/OAM–time-bin modes, with unitary propagation $\exp(-i\theta A_{W33}/12)$, bounded phase disorder, loss, random internal 3×3 unitary mixing, finite detector shots and a noisy dark monitor. A line-plus-dark classifier remained correct in all $1,500$ trials under both the moderate and heavier seeded stress profiles. A conditional direct phase tag for the A_2 orientation bit survived the moderate profile but failed under heavier phase/loss disorder before carrier identity failed. This is a robustness simulation, not a measured hardware Hamiltonian.

Two cross-lane consequences are especially suggestive. First, using the corrected Leech result that the canonical V_2 generator contains $4,095$ intrinsic type-8 frames, together with the 416 Hall–Janko vertices and $20,800$ $G_2(4)$ edges,

$$\gcd(4095, 416, 20800) = 13.$$

Hence any common selector with constant fiber size on all three canonical sets can have only one nontrivial cardinality,

$$\boxed{13 = \Phi_3(3)}.$$

Existence is not asserted; the parallel frame reconstruction additionally shows that naive mod-2 frame coordinates cannot construct it.

Second, the F_9 glue phase space and the parallel Bruhat–Tits cyclotomic filtration combine naturally in local-field arithmetic. The relation $R^2 = -I$ supplies the unramified quadratic residue extension $\mathbb{F}_9/\mathbb{F}_3$, lifted by $\mathbb{Q}_3(i)/\mathbb{Q}_3$, while the order-9 cyclotomic tower supplies the totally ramified degree-6 extension $\mathbb{Q}_3(\zeta_9)$ with uniformizer $\pi = 1 - \zeta_9$. Their compositum

$$L = \mathbb{Q}_3(i, \zeta_9)$$

has

$$(e, f) = (6, 2), \qquad [L : \mathbb{Q}_3] = 12,$$

residue field $\mathbb{F}_9$, and $3 = u\pi^6$. Consequently $\mathcal{O}_L/3\mathcal{O}_L$ has six successive π-adic graded pieces, each $\mathbb{F}_9$, so its associated graded additive space is

$$\boxed{\mathbb{F}_9^6 \cong \mathbb{F}_3^{12}}.$$

This gives an arithmetic lift candidate for the independently discovered glue phase space: R is the unramified direction and $I - M$ the ramified uniformizer direction. No integral Niemeier–$\mathcal{O}_L$ identification is claimed.

79.39 Selector obstructions, explicit $\mathbf{F}_9$ coordinates, and cyclic phase clocks

The next selector sweep replaced several count coincidences by exact obstruction theorems. For a fixed glue complex structure R, plus-type transverse Lagrangians form $U(6,3)/O^+(6,3)$. Orbit–stabilizer divisibility shows that a faithful $G_2(4)$:2, J_2:2, or $G_2(4)$ edge-stabilizer action can have no single fixed plus polarization: its orbit has size at least 560, 35, or 7, respectively. Thus repairing the previously proved Q^-/Q^+ Witt-sign mismatch requires controlled symmetry breaking, a nontrivial selected orbit, or extra datum rather than a hidden fully symmetric point selector.

The proposed 13-state global quotient is also obstructed. The rank-three $G_2(4)$:2 action on 416 Hall–Janko vertices has point-stabilizer subdegrees $1, 100, 315$. A block containing a chosen vertex is therefore a union of those suborbits and can have size only $1, 101, 316$, or 416; a 13-block quotient would require blocks of size 32. Hence the earlier identity $\gcd(4095, 416, 20800) = 13$ is a necessary cardinality observation, not an imprimitivity system.

On the arithmetic side the transverse-glue $\mathbf{F}_9$ structure can now be made explicit. Let G be the ternary Golay glue basis and let K, R be the alternating form and order-four complex structure manufactured by the transverse Golay/E_6 glue pair. With

$$P = \begin{bmatrix} G \\ GR \end{bmatrix}, \qquad J_0 = \begin{bmatrix} 0 & I_6 \\ -I_6 & 0 \end{bmatrix},$$

the exact $C_- = I_6$ identity gives

$$PKP^{\mathsf{T}} = J_0, \qquad PR = J_0 P.$$

Thus the actual finite phase space is explicitly the standard $\mathbf{F}_9^6$ module, with R acting as multiplication by i and

$$K(z,w) = \mathrm{Tr}_{\mathbf{F}_9/\mathbf{F}_3}\left(-i\sum_j z_j\overline{w_j}\right).$$

For $L = \mathbf{Q}_3(i, \zeta_9)$ and $\pi = 1-\zeta_9$, reduction modulo 3 gives $\mathcal{O}_L/3\mathcal{O}_L \cong \mathbf{F}_9[\pi]/(\pi^6)$, so its six graded coefficient layers are additively the same $\mathbf{F}_9^6$. This is an explicit mod-3 intertwiner; an integral $\mathcal{O}_L$–Niemeier lattice lift remains open.

The common count 7371 on the glue $Q^-(5,3)$ and Suzuki $Q^+(5,3)$ sides also does not conceal an isomorphism of the natural derived schemes. Exhaustive stabilizer-orbital classification of all nondegenerate two-spaces, using the Gram matrix plus relation kernel and Witt extension, gives orbital ranks

$$(39,28) \quad \text{for } Q^-, \qquad (40,27) \quad \text{for } Q^+,$$

for hyperbolic and anisotropic basepoints respectively. A future weld must therefore pass through a coarser fusion, broken symmetry, or external structure.

For the photonic orientation bit, an absolute phase is replaced by the three-qutrit Bargmann–Pancharatnam loop

$$\mathcal{B} = \langle\psi_0|\psi_1\rangle\langle\psi_1|\psi_2\rangle\langle\psi_2|\psi_0\rangle.$$

Its phase is exactly invariant under independent $U(1)$ port gauges and under a common $U(3)$ mode rotation, while complex conjugation reverses $\mathrm{Im}\,\mathcal{B}$. In the deterministic seeded stress model the chirality classifier is perfect under gauge-only and mild perturbations and is $1993/2000 = 99.65\%$ accurate at the moderate profile; these numbers are simulation outputs, not hardware measurements.

The number 13 survives in a different, cyclic form. Since neither the J_2:2 vertex stabilizer nor the $G_2(4)$ edge stabilizer has a factor 13, every order-13 subgroup acts semiregularly on the corresponding carriers:

$$416 = 32 \cdot 13, \qquad 20800 = 1600 \cdot 13, \qquad 41600 = 3200 \cdot 13.$$

Thus a chosen C_{13} supplies length-13 vertex, edge, and flag clocks; the identification with a $PG(2,3)$ Singer clock requires the noncanonical choice of that subgroup and orbit.

There is also an exact finite-field binary phase channel. The norm

$$N(z) = z^4 : \mathbf{F}_9^\times \longrightarrow \mathbf{F}_3^\times \cong C_2$$

is surjective with kernel $\{1, -1, i, -i\} \cong C_4$. Hence $N(uz) = N(z)$ for every norm-one phase u, giving a gauge-invariant C_2 parity candidate. In the unramified local lift this is the Teichmuller quotient $\mu_8/\mu_4 \cong C_2$.

Finally, the parallel Leech controls change the V_2 interpretation. The larger Pass9861–9884 sample falsifies the claim that the frame-pair relation is a function only of the sum class, while Pass9921–9944 identifies each type-8 frame direction as a bridge to an A_1^{24} two-neighbour whose glue is the binary Golay code. Accordingly no additive map $V_2 \cong \mathbf{F}_2^{12} \to C_{13}$ can exist, since 4096 is coprime to 13. Multiplicatively, however, $\mathrm{ord}_{13}(2) = 12$, so the companion matrix of Φ_{13} over $\mathbf{F}_2$ has order 13 and fixes no nonzero vector. Abstractly this partitions the 4095 nonzero frame/neighbour directions into

$$4095 = 315 \cdot 13$$

cycles. Whether such a C_{13} lies in the actual Co_0 stabilizer of the canonical V_2 is the next exact group-theoretic test; it is not assumed here.

Passes 9985–10048: the selector narrows while the $\mathbf{F}_9$ arithmetic closes

The attempted C_{13} weld into the canonical Leech filtration now has a sharp boundary. If $C_{13} \leq \mathrm{Stab}_{Co_0}(V_2)$, then it is fixed-point-free on the 4095 nonzero frame directions and therefore has exactly 315 thirteen-cycles. It cannot normalize the unique pure order-eight generator M: the exact centralizer has order

$$|C_{Co_0}(M)| = 48384 = 2^8 3^3 7,$$

and $N(\langle M \rangle)/C(M)$ embeds in $\mathrm{Aut}(C_8)$ of order four. The remaining search is consequently forced into the 13-bearing maximal-overgroup branches 3.Suz:2 and $(A_4 \times G_2(4))$:2. No explicit Co_0 word of order thirteen stabilizing V_2 is claimed yet.

The abstract irreducible clock on $V_2 \cong \mathbf{F}_2^{12}$ has a stronger classification. Since $\mathrm{ord}_{13}(2) = 12$,

$$C_{GL(12,2)}(C_{13}) = \mathbf{F}_{2^{12}}^\times = C_{4095}, \qquad N_{GL(12,2)}(C_{13}) = C_{4095}{:}C_{12}.$$

Thus its 315 cycles form a regular $C_{315} = C_{4095}/C_{13}$ torsor. By contrast an order-thirteen torus in $G_2(4)$:2 has normalizer $C_{13}{:}C_{12}$, while its certified permutation carriers split into 32 vertex cycles, 1600 edge cycles, and 3200 flag cycles. The shared local clock is therefore $C_{13}{:}C_{12}$ and the exact extra ambiguity on the abstract V_2 side is C_{315}.

A second tempting geometric weld fails. The coarsest canonical fusion of the 7371 nondegenerate two-space selectors—self, meet in one projective point, or disjoint—has identical valencies

$$\boxed{1,\ 320,\ 7050}$$

for $Q^-(5,3)$ and $Q^+(5,3)$. Nevertheless their 320-regular point-intersection graphs have different exact spectra:

$$Q^- : \quad 320^1, 86^{112}, 80^{90}, 68^{160}, (-4)^{7008},$$
$$Q^+ : \quad 320^1, 86^{142}, 74^{90}, 68^{130}, (-4)^{7008}.$$

Hence even this natural nontrivial fusion is not an isomorphism.

The arithmetic side closes much further. Put

$$K = \mathbf{Q}_3(i), \qquad L = K(\zeta_9), \qquad t = \zeta_9 - 1.$$

Because

$$\Phi_9(1+t) = t^6 + 6t^5 + 15t^4 + 21t^3 + 18t^2 + 9t + 3,$$

one obtains the exact residue algebra

$$\boxed{\mathcal{O}_L/3\mathcal{O}_L \cong \mathbf{F}_9[t]/(t^6)}.$$

An explicit regular nilpotent N and $U = I+N$ satisfy $U^9 = I$, $U^3 \neq I$, and preserve a nondegenerate Hermitian Gram $H = iA$. Thus the earlier six $\mathbf{F}_9$ layers are the complete truncated residue module, not merely an associated-graded dimension match. This is still a mod-3 theorem; an integral self-dual $\mathcal{O}_L$ realization of the Niemeier lattice remains open.

The parallel $E_8/3E_8 = H(3,9)$ result and the rank-six transverse-glue construction are also instances of one exact Hermitianization mechanism. For a symplectic form K and symplectic complex structure $R^2 = -I$, set

$$B = KR^{\mathsf{T}}, \qquad h = B - iK.$$

Then

$$h(xR, y) = ih(x, y), \qquad h(x, yR) = -ih(x, y), \qquad h(y, x) = \overline{h(x, y)}.$$

The actual glue realizes this in $\mathbf{F}_9^6$; the parallel E_8 theorem is the rank-four $\mathbf{F}_9$ instance.

For a finite readout, encode the same orientation bit in the qutrit Bargmann chirality and in the $\mathbf{F}_9$ norm parity, then accept only when the two bits agree. With independent Bargmann flip probability p_B and uniform nonzero-symbol corruption probability ϵ,

$$p_N = \frac{4\epsilon}{7}, \qquad a = (1-p_B)(1-p_N) + p_B p_N, \qquad e_{\mathrm{cond}} = \frac{p_B p_N}{a}.$$

At the frozen moderate Bargmann error $p_B = 0.0035$ and a 5% symbol-corruption stress,

$$a = \frac{67769}{70000} \simeq 0.96812857, \qquad \boxed{e_{\mathrm{cond}} = \frac{7}{67769} \simeq 1.03292 \times 10^{-4}}.$$

These are exact decoder consequences of the stated error model, not hardware performance data.

Two further structural consequences emerge. First, the common clock automorphism group $C_{12} = \mathrm{Aut}(C_{13})$ has the canonical orientation character

$$C_{12} \twoheadrightarrow C_{12}/C_6 \cong C_2.$$

On $G_2(4)$:2 this is precisely the outer-extension quotient $G_2(4)$:$2/G_2(4)$; on the abstract Singer side it is Frobenius parity. Its identification with the earlier Golay $A_4 < S_4$ orientation bit remains a test, not a claim.

Second, since L/K is totally ramified of degree six and $3 = ut^6$ for a unit u, the lattice chain

$$\mathcal{O}_L \supset t\mathcal{O}_L \supset \cdots \supset t^5\mathcal{O}_L \supset t^6\mathcal{O}_L = 3\mathcal{O}_L$$

has six one-dimensional $\mathbf{F}_9$ residue quotients. Therefore

$$[\mathcal{O}_L], [t\mathcal{O}_L], \ldots, [t^5\mathcal{O}_L]$$

form a full six-vertex chamber, a maximal 5-simplex, in the Bruhat–Tits building of $PGL_6(\mathbf{Q}_3(i))$. Multiplication by $\zeta_9 = 1 + t$ fixes this chamber vertex-by-vertex. This is arithmetic building geometry only; no physical spacetime or holographic interpretation is asserted.

Passes 10049–10516: canonical V_2, internal F_4^6, explicit $G_2(4)$ clocks, and the 27-state transport frontier

The canonical type-4-free Leech generator V_2 belongs to the unique good-sublattice orbit whose stabilizer can contain the exact order-48384 centralizer of the pure order-eight generator. This is orbit 7, with

$$\mathrm{Stab}_{Co_1}(V_2) \cong G_2(4) \times A_4, \qquad \text{profile } 64^{4095}.$$

Consequently an actual $C_{13} < G_2(4)$ stabilizes canonical V_2. The commuting quotient

$$A_4/V_4 \cong C_3 \cong \mathbf{F}_4^\times$$

acts as the internal scalar field, so

$$\boxed{V_2 \cong \mathbf{F}_4^6}$$

as the natural characteristic-two $G_2(4)$ module. Projectivizing gives

$$PG(V_2) = PG(5, 4),$$

and the natural $G_2(4)$ incidence is the split Cayley hexagon $H(4)$ on 1365 points.

The Suzuki orbit acquires a local dictionary around the canonical V_2 vertex:

$$1782 = 1 + 416 + 1365.$$

The 1365 shell is the $H(4)$ point geometry. The 416 shell is the Hall–Janko/J_2 controller carrier. A provenance correction is essential: these 416 objects are Hall–Janko suboctagon/J_2:2 controller objects in the Suzuki-tower geometry, not 416 copies of $H(2)$. Within one Hall–Janko realization there is separately a local family of 100 embedded $H(2)$ subhexagons forming the $HJ(100)$ vertex set.

Wilson's explicit $A_4 \times G_2(4) < Co_1$ words have been evaluated in the stored 24-dimensional matrices. With commutator convention $[x, y] = x^{-1}y^{-1}xy$, the exact orders are

$$|c_1| = 26, \quad |a_1| = 2, \quad |a_2| = 3, \quad |g_1| = |g_2| = 13, \quad |g_1 g_2| = 15,$$

and the two factors commute. Their common V_4 fixed space

$$E = \mathrm{Fix}(V_4)$$

is a 12-dimensional totally singular type-4-free orbit-7 generator. The order-three element $a_2|_E$ obeys

$$S^2 + S + I = 0,$$

thereby giving explicit $\mathbf{F}_4$ coordinates on $E \cong \mathbf{F}_4^6$. The order-thirteen generator has a degree-six irreducible factor p over $\mathbf{F}_4$ satisfying

$$p(x)\overline{p(x)} = \Phi_{13}(x),$$

so its commutant is the field $\mathbf{F}_{4^6}$.

The Wilson generator E and stored canonical V_2 are transverse:

$$E \cap V_2 = 0, \qquad E \oplus V_2 = \mathbf{F}_2^{24},$$

with perfect Leech pairing. They therefore form a binary hyperbolic polarization. Swapping the two halves gives an orthogonal involution, while the $\mathbf{F}_4$ scalar on E transfers uniquely by pairing duality to an order-three operator on stored V_2. At the abstract orthogonal level the polarization stabilizer drops from $GL(12,2)$ to $GL(6,4)$ after imposing the scalar field. Membership of the particular exchange and pairing-dual scalar in Co_1 is not claimed without explicit words.

For the internal C_{13} clock,

$$\mathrm{ord}_{13}(4) = 6.$$

Thus it is fixed-point-free on $V_2 \setminus \{0\}$ and on $PG(V_2)$. Projectivization by the intrinsic scalar triples reduces the former 315 vector cycles to

$$\boxed{105}$$

projective cycles. An explicit 13:6 normalizer has been constructed in the stored matrices, with complement acting by $g \mapsto g^4$. On the 105 projective states the C_6 complement has orbit distribution

$$1^3,\ 2^6,\ 3^6,\ 6^{12},$$

so the complete normalizer produces exactly 27 states. The cyclic torsor is C_{105}, and the C_6 action fixes the C_3 factor of $C_{105} \cong C_3 \times C_{35}$, giving a canonical nine-triple carrier.

The natural $H(4)$ transport on these 27 states is *not* the H27 or Schlaefli adjacency. Its weighted point quotient has spectrum

$$20^1,\ 7^8,\ (-1)^{12},\ (-5)^6.$$

The full Levi quotient is instead a $27 \mid 27$ point–line incidence transport M of rank 21 with

$$MM^\vee = 5I + R,$$

and squared singular spectrum

$$25^1,\ 12^8,\ 4^{12},\ 0^6.$$

The old cubic-surface E_6 incidence transport also has rank 21 and a six-dimensional kernel, while H27 has eigenspace dimensions $1+12+8+6$. The exact shared constituent fingerprint is therefore

$$E_6 : 1+20+6, \qquad H(4)/(13{:}6) : 1+8+12+6, \qquad H27 : 1+12+8+6.$$

This is a spectral-constituent bridge only; an explicit $8 \leftrightarrow 12$ Fourier/Steinberg intertwiner remains open.

A second objectwise bridge occurs inside W33 itself. The 16 Hermitian-isotropic points of the chamber-selected W33 form the graph

$$\Gamma_{16} = \mathrm{Cay}\big(C_4^2, \{(0,\pm1),(0,2),(\pm1,2),(2,2)\}\big),$$

with four K_4 fibres and

$$\mathrm{Aut}(\Gamma_{16}) \cong S_4 \times D_8, \qquad |\,\mathrm{Aut}\,| = 192.$$

Exhaustive spread enumeration proves that this is exactly the induced geometry on the 16 points lying on the four common lines of a four-intersection W33 spread pair; the unordered spread-pair stabilizer acts as the full automorphism group. The graph is a nontrivial C_2-voltage twist of the 4×4 rook geometry rather than the tesseract rotation graph. Its adjacency row space is the self-dual binary $[16, 8, 4]$ code with weight enumerator

$$1 + 12y^4 + 64y^6 + 102y^8 + 64y^{10} + 12y^{12} + y^{16}.$$

Finally, the split Cayley hexagon itself supplies a uniform homological identity. If $P = (q + 1)(q^4 + q^2 + 1)$ is the number of points and lines of $H(q)$, then its Levi graph has $(q + 1)P$ edges and

$$\boxed{\beta_1(\mathrm{Levi}\, H(q)) = q^6}.$$

Hence

$$\beta_1(H(4)) = 4096 = |V_2|, \qquad \beta_1(H(2)) = 64.$$

For the free C_{13} quotient of $H(4)$,

$$\beta_1 = 316 = 1 + 315.$$

Moreover, over $\mathbf{F}_2$ the restrictions to C_{13} of the hexagon cycle space and the permutation module on all vectors of V_2 have the same semisimple decomposition

$$H_1(\mathrm{Levi}\, H(4); \mathbf{F}_2) \downarrow C_{13} \cong \mathbf{F}_2[V_2] \downarrow C_{13} \cong 1^{316} \oplus W_{12}^{315},$$

where W_{12} is the unique nontrivial irreducible $\mathbf{F}_2[C_{13}]$-module. This is an exact C_{13}-module theorem, not yet a full $G_2(4)$-equivariant chain-level identification.

Passes 10517–10580: the 27-state selector becomes a 3–5–7 harmonic tensor cube

Let H be the repo H27 adjacency and let R be the weighted 27-state quotient obtained from the explicit $H(4)$ geometry by the 13:6 normalizer. Their multiplicity pattern is the same $1|8|12|6$. The unique cubic sending the H27 eigenvalues $8, -1, 2, -4$ to the quotient eigenvalues $20, 7, -1, -5$ is

$$f(x) = \frac{97x^3 - 429x^2 - 1590x + 3472}{648}.$$

Because H27 is distance regular,

$$f(H) = \frac{34A_0 + 25A_1 + 7A_2 + 97A_3}{27}.$$

After the natural orbit-size symmetrization of R, an orthogonal spectral intertwiner with $f(H)$ therefore exists. It cannot be a permutation or a local three-point Fourier operation: the quotient has nonconstant diagonal and the canonical nine-packet projector does not commute with the transport.

The C_{13}-equivariant hexagon-homology match also admits a chain proof. If $\mathcal{R} = \mathbf{F}_2[C_{13}]$, the free quotient of the $H(4)$ Levi graph has 210 vertex orbits and 525 edge orbits, giving

$$0 \to H_1 \to \mathcal{R}^{525} \to \mathcal{R}^{210} \to \mathbf{F}_2 \to 0.$$

Maschke splitting yields

$$\boxed{H_1(\mathrm{Levi}\, H(4); \mathbf{F}_2) \cong \mathbf{F}_2 \oplus \mathcal{R}^{315}}.$$

The permutation module on V_2 has exactly the same decomposition: one fixed zero vector plus 315 free thirteen-cycles. Hence the two are isomorphic as $\mathbf{F}_2[C_{13}]$-modules by the covering resolution itself.

The 27 point-orbits and 27 line-orbits of the normalizer are not 13:6-equivariantly bijective, but the normalized incidence operator has rank 21 and singular values

$$5^1, \quad (2\sqrt{3})^8, \quad 2^{12}, \quad 0^6.$$

Its polar decomposition therefore supplies a canonical rank-21 partial isometry between the transmitted point and line sectors, with six-dimensional kernels on both sides.

The binary and ternary transverse rank-six packages are also now distinguished categorically. On the Leech side the $\mathbf{F}_4^\times$ scalar preserves the two transverse $\mathbf{F}_4^6$ halves and a separate involution exchanges them. On the ternary glue side the distinguished $\mathbf{F}_9$ scalar R itself exchanges the two $\mathbf{F}_3^6$ Lagrangians. Thus the two packages realize a split-semilinear versus rotating-complex polarization duality, not a literal polarization-preserving equivalence.

The strongest arithmetic refinement comes from the canonical 105-state selector. With normalizer multiplier 79,

$$C_{105} \cong C_3 \times C_5 \times C_7, \qquad 79 \equiv (1, -1, 2) \pmod{(3, 5, 7)}.$$

Hence the C_6-invariant harmonic space factors exactly as

$$\boxed{\mathbf{C}[C_{105}]^{C_6} \cong \mathbf{C}[C_3] \otimes \mathbf{C}[C_5]^{\langle -1 \rangle} \otimes \mathbf{C}[C_7]^{\langle 2 \rangle}}$$

with dimensions

$$\boxed{27 = 3 \times 3 \times 3}.$$

The three local orbit systems are

$$C_3 : \ \{0\}, \{1\}, \{2\},$$
$$C_5/\{\pm 1\} : \ \{0\}, \{1, 4\}, \{2, 3\},$$
$$C_7/\langle 2 \rangle : \ \{0\}, \{1, 2, 4\}, \{3, 6, 5\}.$$

For the standard 105-point Fourier kernel the CRT idempotents give local character coefficients $(2, 1, 1)$, so the restricted transform factors as

$$\boxed{F_{105}^{C_6} = F_3^{(2)} \otimes F_5^{C_2} \otimes F_7^{C_3}}$$

in the CRT orbit bases. Its eigenvalue multiplicities are

$$1^8, \quad (-1)^7, \quad i^6, \quad (-i)^6.$$

This is a canonical 3–5–7 harmonic tensor cube. Only the first factor is the ordinary C_3 qutrit group algebra; the other two are three-dimensional cyclotomic invariant sectors. In particular the reduced nine-state factor is not the ordinary Hesse/two-qutrit Fourier plane: $\operatorname{tr}(F^2) = 3$ there, versus 1 on $\mathbf{F}_3^2$.

Finally, the C_3 Fourier functor is exactly the one already present in the Schlaefli–Steinberg A_2 color torsor. Its integral color basis has Smith diagonal $(1, 1, 3)$; applying it to nine packets gives index 3^9, while the old eighty-one-coordinate color sector gives index 3^{81}. Thus the prime 3 Fourier denominator is structural and scales only with multiplicity.

Passes 10837–10900: modular extension defect and the ten-state projective carrier

The order-two normalizer obstruction is now completely localized in the 316-dimensional C_{13}-fixed sector. As $\mathbf{F}_2[C_2]$-modules,

$$\mathbf{F}_2[V_2]_{C_{13}\text{-fixed}} \cong 1^{64} \oplus J_2^{126}, \qquad H_1(\operatorname{Levi} H(4); \mathbf{F}_2)_{C_{13}\text{-fixed}} \cong J_2^{158},$$

where J_2 is the two-dimensional regular indecomposable. Thus the exact stable repair is

$$\mathbf{F}_2[V_2] \oplus J_2^{32} \cong H_1(\operatorname{Levi} H(4); \mathbf{F}_2) \oplus 1^{64}$$

on this defect sector. The nontrivial W_{12}^{315} C_{13} sector already has the unique compatible semilinear extension.

For Wilson's explicit order-six complement $n = su$ with $s = n^4$ of order three and $u = n^3$ of order two, the natural $\mathbf{F}_4^6$ module has Jordan form

$$J_2(1) \oplus J_2(\omega) \oplus J_2(\omega^2).$$

Hence $\operatorname{Fix}(u) \cong \mathbf{F}_4^3$ and projectivizes to $PG(2,4)$. The fixed $H(4)$ Levi incidence is a tree selecting an affine projective frame: one distinguished origin, one line at infinity, and five radial projective directions. The unique s-fixed $\mathbf{F}_4$ line gives a scalar-gauge family of three local translations, each pairing the 64 fixed states into 32 pairs. No nonzero such translation extends C_{13}-equivariantly because the order-thirteen action is irreducible.

On the Hall–Janko controller, the full $C_{13}{:}C_{12}$ normalizer acts on the 32 C_{13} cycles with cycle profile

$$1^1 3^1 4^1 6^2 12^1.$$

The inner C_6 quotient has ten states and the residual outer C_2 acts as $1^2 2^4$. This is not $\mathbf{F}_9/\mathbf{F}_3$ Frobenius on $\mathbf{P}^1(\mathbf{F}_9)$, which has profile $1^4 2^3$. It is instead the split projective involution

$$z \longmapsto -z,$$

which fixes $0, \infty$ and pairs the eight nonzero affine points. Its centralizer in $PGL_2(9)$ is D_{16}, and the quotient carrier is

$$\boxed{\{0,\infty\} \sqcup \mathbf{F}_9^\times/\{\pm 1\}} \cong 2 \text{ poles} + C_4.$$

Only this C_2-set/six-state quotient is identified; no C_4 cross-ratio or full $PGL_2(9)$ transporter to the Hall–Janko ten states is claimed.

Finally, the integers 32 and 64 acquire an exact modular meaning. Since

$$\mathbf{F}_2[C_2] \cong \mathbf{F}_2[\varepsilon]/(\varepsilon^2), \qquad \operatorname{Ext}^1(1,1) \cong \mathbf{F}_2,$$

there is a unique nonzero nonsplit self-extension

$$0 \longrightarrow 1 \longrightarrow J_2 \longrightarrow 1 \longrightarrow 0.$$

The order-two defect consists of exactly 32 copies of this class. Tate cohomology gives

$$\widehat{H}^n(C_2, 1) \cong \mathbf{F}_2, \qquad \widehat{H}^n(C_2, J_2) = 0$$

for every degree n. Thus the V_2 fixed sector carries 64 stable/Tate classes whereas the homology sector carries none. The identity

$$\boxed{64 = 2 \cdot 32}$$

is therefore forced by the length-two projective extension rather than by a cardinality coincidence.

Current frontier: the Hermitian polarity matrix generates the sentinel code

Let B be the already-certified 40×45 Hermitian cross-incidence between the 40 nonisotropic and 45 isotropic points of $\mathrm{PG}(3, \mathbb{F}_4)$. If

$$P = \begin{pmatrix} A_{W(3,3)} & B \\ B^T & A_{\mathrm{GQ}(4,2)} \end{pmatrix}$$

is the loopless polarity adjacency, then restoring the 45 absolute-point loops gives

$$H = P + \mathrm{diag}(0^{40}, 1^{45}).$$

An exact reconstruction from the native $W(3,3)$ data verifies

$$\boxed{H^2 = 16I_{85} + 5J_{85}}.$$

Thus H is the symmetric $2-(85, 21, 5)$ point–plane design matrix of $\mathrm{PG}(3, 4)$. Its spectrum is

$$21^1, \qquad 4^{45}, \qquad (-4)^{39},$$

so $\det H = -21\, 4^{84}$ and $H^{-1} = H/16 - 5J/336$.

The same certificate gives a binary closure that is specific to the repository's independently constructed coordinates. The 45 columns of B, each an eight-subset of the 40 nonisotropic points, have

$$\mathrm{rank}_2\, B = 15$$

and span a doubly-even self-orthogonal code with weight enumerator

$$1 + 45z^8 + 720z^{12} + 6930z^{16} + 17376z^{20} + 6930z^{24} + 720z^{28} + 45z^{32} + z^{40}.$$

This is exactly the historical sentinel $[40, 15, 8]_2$, and set comparison shows that the 45 columns of B are *all* 45 weight-eight sentinel words. Hence the same 45 objects are simultaneously the Hermitian nonisotropic neighborhoods of the 45 absolute points, the trade-lattice/GQ(4,2) eight-supports, and the complete minimum-word orbit of the sentinel code.

Over $\mathbb{F}_2$, H has rank 17, recovering the classical $[85, 17, 21]_2$ plane code. Restricting the 45 absolute-point plane rows to the 40 nonabsolute coordinates gives exactly the rank-15 sentinel:

$$\boxed{\mathcal{S} = \langle \text{polar planes of the 45 absolute points} \rangle_{\mathbb{F}_2}|_{\text{40 nonabsolute points}}\,.}$$

Evidence and attribution boundary. The $2-(85, 21, 5)$ design, its $[85, 17, 21]_2$ code, and the existence of the $S_4(3)$-invariant $[40, 15, 8]_2$ code are classical/published and are not re-claimed here. The certified project contribution is their explicit identification through the independently reconstructed B, including the equality of its 45 columns with the complete minimum-weight sentinel orbit. The executable witness is `analysis/w33_20260829_pg34_polarity_sentinel.py`. This is an exact finite-geometric/code statement; no physical Hamiltonian or particle interpretation is inferred.

79.40 Index-protected residue, qutrit–chirality synthetic coordinate, and Koopman period-two boundary

The 85-state Hermitian incidence coupling admits a sharper flat-band statement than the bare 15+20 zero-mode count. With off-diagonal block $B \in M_{40\times 45}$ of rank 25, chiral sublattice imbalance alone gives the Fredholm-style finite index

$$(40 - \operatorname{rank} B) - (45 - \operatorname{rank} B) = -5.$$

Hence an arbitrary chiral-symmetric off-diagonal perturbation can raise the rank to 40 and leave only five zero modes. A concrete integer perturbation does so. The full thirty-five zero modes persist only with the established $PSp(4,3)$ representation split

$$\mathbb{C}^{40} = \mathbf{1} \oplus 24 \oplus 15, \qquad \mathbb{C}^{45} = \mathbf{1} \oplus 24 \oplus 20,$$

because the unmatched 15 and 20 sectors cannot couple equivariantly. Thus five modes are protected by rectangular/chiral index, whereas the larger flat band is protected by finite symmetry. In the natural equivariant family $aB + bJ$, generic rank remains 25; the trivial channel cancels on $9a + 45b = 0$, giving rank 24 rather than opening the dark sectors.

The exact six-completion action also has a useful internal-coordinate normal form. After labelling the unique $3 + 3$ block system by $\chi \in \mathbb{F}_2$ and each block by $t \in \mathbb{F}_3$, the image is

$$C_3 \times S_3 \cong (C_3 \times C_3) \rtimes C_2.$$

One may choose generators

$$z : (\chi, t) \mapsto (\chi, t+1), \qquad r : (0,t) \mapsto (0,t+1),\ (1,t) \mapsto (1,t-1),$$
$$s : (\chi, t) \mapsto (1-\chi, t), \qquad srs = r^{-1},$$

with z central. The C_2 coordinate is not arbitrary: it is exactly which residual point of the defect hinge lies in the high-release tetrad. The minimal synthetic three-site/two-leg Hamiltonian

$$H = Z + Z^\dagger + gX_\chi$$

therefore has exact characteristic polynomial

$$\boxed{((x-2)^2 - g^2)((x+1)^2 - g^2)^2}.$$

This is a finite synthetic-coordinate normal form analogous to the internal-state synthetic dimensions used in photonic and atomic simulators; it is not yet a physical mode assignment or a magnetic-flux model.

Finally, the deterministic Holotrade recovery cycles admit a Koopman audit that blocks an overstrong time-crystal reading. On each two-cycle the Koopman operator is the swap

$$U = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \qquad \operatorname{spec} U = \{+1, -1\},$$

so a formal π mode exists for observables odd under the swap. But the actually tracked free-line headroom has nonzero overlap with that mode only on the 36 starts ending in a 16/17 cycle. The remaining 2844 starts end in 19/19, 17/17, or 16/16 cycles and therefore have no period-doubled headroom observable at all. Moreover the map is a finite deterministic scheduler with lexicographic tie breaking, not a demonstrated periodically driven many-body Hamiltonian; there is no thermodynamic limit or perturbation-robust spontaneous time-translation breaking. The exact -1 Koopman mode is therefore a useful controller-spectrum object, not evidence for a discrete time-crystal phase.

Evidence boundary. These are exact finite linear-algebra, representation, permutation-group, and deterministic dynamical-system statements. Flat-band, synthetic-dimension, chirality, quasienergy, and Koopman language is used only at the level justified by those operators. No material band, fermion species, laboratory synthetic dimension, Floquet phase, or physical time crystal is claimed.

Current frontier: the sentinel minimum shell carries $GQ(4,2)$ and a 216-circuit S_5 orbit

The 45 weight-eight words supplied by the Hermitian cross-incidence B do more than generate the historical $[40,15,8]_2$ sentinel. Their Hamming metric reconstructs the 45-point generalized quadrangle:

$$m \sim_{GQ(4,2)} n \iff d_H(b_m, b_n) = 16 \iff \operatorname{supp}(b_m) \cap \operatorname{supp}(b_n) = \varnothing,$$

whereas noncollinear pairs have distance 12 and intersection size 2.

There are $45 \cdot 32/2 = 720$ noncollinear pairs. Their pairwise XORs are all distinct and exhaust the 720 weight-twelve words in the sentinel:

$$\boxed{\{w \in \mathcal{S} : \operatorname{wt}(w) = 12\} = \{b_m + b_n : m \not\sim n\}.}$$

Thus every weight-twelve word has a unique two-minimum decomposition.

Regarded as a binary matroid, the 45 columns have no dependency of size less than five. Exact enumeration finds precisely 216 five-circuits. Each circuit is a five-coclique of $GQ(4,2)$, and every GQ nonedge belongs to exactly three such circuits. Reconstructing the projective transvection action shows that all 216 circuits form one $PSp(4,3)$-orbit. The stabilizer of a circuit has order 120 and acts faithfully as the complete S_5 on its five elements:

$$\boxed{\mathcal{C}_5 \cong PSp(4,3)/S_5, \qquad |\mathcal{C}_5| = 216.}$$

The equality $216 = |\mathrm{Clifford}_3^{\mathrm{proj}}|$ is only a numerical comparison at this stage: the certificate does not identify the 216-element coset orbit with the order-216 qutrit Clifford group. The executable witness is `analysis/w33_20260829_sentinel_shell_matroid.py`.

Current frontier: the 216 sentinel circuits are not an internal Clifford torsor

The 216 five-circuits of the binary sentinel minimum-word matroid form the homogeneous space

$$\mathcal{C}_5 \cong \mathrm{PSp}(4,3)/S_5.$$

Because the projective single-qutrit Clifford group also has order 216, an obvious next question is whether $\mathcal{C}_5$ is a regular orbit for an order-216 subgroup of $\mathrm{PSp}(4,3)$. Exact native-coordinate computation, together with the complete Connor–Leemans subgroup lattice, gives a no-go.

There are exactly two conjugacy classes of order-216 subgroups. A representative of the first is the derived subgroup of a point stabilizer; its normalizer has order 648, hence class length 40, and its orbit partition on $\mathcal{C}_5$ is

$$108 + 36 + 36 + 36.$$

A representative of the second is obtained by fixing a perfect matching of the four points on a $W(3,3)$ line; its normalizer has order 216, hence class length 120, and its circuit-orbit partition is

$$108 + 36 + 27 + 27 + 18.$$

Neither class is transitive. Therefore no internal order-216 subgroup of $\mathrm{PSp}(4,3)$ acts regularly, or even transitively, on the 216 circuits.

The already-certified projective qutrit Clifford of order 216 arises instead as the quotient of the order-648 point stabilizer by its central C_3. That quotient does not descend to the circuit action: each nontrivial central element acts on $\mathcal{C}_5$ as 72 disjoint three-cycles and fixes no circuit. Thus the central C_3 is not contained in the kernel.

Consequently the numerical equality

$$|\mathcal{C}_5| = 216 = |\mathrm{Clifford}_3^{\mathrm{proj}}|$$

is not an internal equivariant identification. Any future bridge must use additional structure (for example a cover/quotient correspondence or cocycle) rather than a regular subgroup action. The executable witness is `analysis/w33_20260829_216_clifford_torsor_nogo.py`.

79.41 The central C_3 Clifford cover is locally C_9 on three fifths of the order-three directions

The exact point-stabilizer audit gives a nonsplit central extension

$$1 \longrightarrow Z \cong C_3 \longrightarrow K \longrightarrow Q \longrightarrow 1, \qquad |K| = 648, \qquad |Q| = 216,$$

where Q is the projective one-qutrit Clifford/Hessian $\mathrm{ASL}(2,3)$ quotient. Its certified lift-order census contains 32 order-three elements of Q with lift orders $(3,3,3)$ and 48 with lift orders $(9,9,9)$.

For $q \in Q$ of order three and any lift $g \in K$, define the central cube charge

$$\omega(q) := g^3 \in Z.$$

This is independent of the lift, since $(gz^a)^3 = g^3 z^{3a} = g^3$ for central $z^3 = 1$, and it obeys $\omega(q^{-1}) = \omega(q)^{-1}$.

The full preimage of $\langle q \rangle$ has order nine. If $\omega(q) = 1$, all lifts have order three and the preimage is $C_3 \times C_3$; if $\omega(q) \neq 1$, all lifts have order nine and the preimage is C_9. Since the 80 order-three elements of Q form 40 cyclic subgroups, the census therefore yields the exact local split

$$\boxed{40 = 16\,_{C_3 \times C_3} + 24\,_{C_9}}.$$

Consequently the global extension class restricts nontrivially to

$$\boxed{24/40 = 3/5}$$

of the cyclic order-three subgroups of Q. After choosing a generator z of Z, inversion pairs the two nonzero charges and forces the 48 nonsplit oriented generators to divide as

$$\boxed{24 \text{ with } g^3 = z \quad + \quad 24 \text{ with } g^3 = z^2}.$$

Thus the previously global nonsplitting obstruction localizes on concrete order-three Clifford directions: 24 cyclic C_3 directions thicken to C_9 in the three-sheeted cover, while 16 restrict trivially. This is an exact finite-group/cohomology statement; identifying the deck charge with a measured optical phase requires an additional physical intertwiner.

79.42 The C_9 obstruction is one affine Clifford conjugacy orbit

The local lift-charge theorem leaves a $16 + 24$ split among the 40 cyclic order-three subgroups of

$$Q \cong \mathrm{ASL}(2,3) = \mathbb{F}_3^2 \rtimes \mathrm{SL}(2,3).$$

Constructing this affine group directly resolves those 40 subgroups into three conjugacy orbits,

$$\boxed{40 = 4 + 12 + 24}.$$

The orbit of size 4 consists of the pure translations; their nonidentity elements have no affine fixed points. The orbit of size 12 consists of nontranslation unipotents with an affine fixed line, hence three fixed points. The orbit of size 24 consists of nontranslation unipotents with no affine fixed point. The explicit quotient model has element-order distribution

$$1^1\, 2^9\, 3^{80}\, 4^{54}\, 6^{72},$$

matching the certified 216-element Clifford quotient census.

Splitting of a central extension over a cyclic subgroup is invariant under quotient conjugacy. Since the exact lift audit contains precisely 24 nonsplit cyclic C_3 restrictions, the unique 24-subgroup orbit must be the entire nonsplit locus. Therefore

$$\boxed{4_{\text{translation}} + 12_{\text{fixed line}} \;\longmapsto\; C_3 \times C_3}$$

whereas

$$\boxed{24_{\text{fixed-point-free nontranslation}} \;\longmapsto\; C_9}.$$

Thus the 3/5 obstruction is geometrically homogeneous: the central deck charge is nontrivial exactly on the fixed-point-free order-three affine directions whose linear part is itself nontrivial unipotent. Pure translations are also fixed-point-free, but they split, so fixed-point-freeness alone is not the discriminant. This classification is exact in the canonical $\mathrm{ASL}(2,3)$ quotient model; an optical or hardware phase interpretation still requires a separately proved physical coordinate intertwiner.

79.43 The nonsplit C_9 species avoids both 36-fibre stabilizer geometries

The free central C_3 action on the 216 sentinel five-circuits produces 72 fibres. The quotient

$$Q \cong \mathrm{ASL}(2,3), \qquad |Q| = 216,$$

acts faithfully with two orbits of size 36, whose point stabilizers are respectively S_3 and C_6. The 40 cyclic order-three subgroups of Q split into conjugacy classes of sizes $4 + 12 + 24$.

The four pure-translation subgroups have cycle shape $1^9 3^{21}$ on the 72 fibres: each fixes nine fibres in the Q/S_3 orbit and none in the Q/C_6 orbit. The twelve fixed-line unipotent subgroups have cycle shape $1^3 3^{23}$: each fixes three fibres in Q/C_6 and none in Q/S_3. The twenty-four fixed-point-free nontranslation unipotents have cycle shape 3^{24} and fix no fibre in either orbit; these are exactly the subgroups whose full preimage is cyclic C_9 rather than split $C_3 \times C_3$.

Since $4 \cdot 9 = 36$ and $12 \cdot 3 = 36$, every S_3-stabilized fibre contains the unique order-three subgroup from the translation class, and every C_6-stabilized fibre contains the unique subgroup from the fixed-line class. Thus

$$\boxed{\text{nonsplit 24-class} = \text{the order-three species lying in neither fibre-stabilizer geometry.}}$$

This is an exact finite permutation statement; a photonic coordinate interpretation requires an independently proved intertwiner.

79.44 A 216×540 coherent circuit incidence geometry

The sentinel matroid contains a 216-orbit of five-circuits and a 540-orbit of six-circuits. The diagonal $\mathrm{PSp}(4,3)$ action on the 116640 ordered cross-pairs has exactly 17 orbitals. By support intersection size the pair counts are

$$|C_5 \cap C_6| = 0 : 54000, \quad 1 : 51840, \quad 2 : 6480, \quad 3 : 4320,$$

carried respectively by $8, 6, 1, 2$ orbitals.

The maximal-overlap relation $|C_5 \cap C_6| = 3$ is biregular of degrees

$$\boxed{\text{20 on the 216-side,} \qquad \text{8 on the 540-side}},$$

and splits into two equal 2160-pair orbitals, each of degrees 10 and 4.

Fix a six-circuit. Its six labels induce $3K_2$ in the $\mathrm{GQ}(4,2)$ graph. Each of its eight maximal-overlap five-circuit neighbours chooses one endpoint from each of the three matching edges, hence the local neighbour set is the full 2^3 cube. The order-48 stabilizer $C_2 \times S_4$ acts on that cube through the faithful S_4 quotient, with central kernel C_2, and splits the eight vertices into two invariant tetrahedra

$$\boxed{8 = 4 + 4}.$$

After orienting the three matching edges these are the even- and odd-parity cube classes; reversing endpoint conventions can exchange their names but not the intrinsic unordered partition. No identification with a separate chirality variable is made without an explicit equivariant map.

79.45 Duality turns the sentinel extension into the W33 line-code extension

Write C_S for the sentinel $[40, 15, 8]_2$ code and C_A for the rank-16 W33 adjacency-row code. The universal line-parity theorem gives $C_S < C_A$ with quotient C_2. Exact enumeration now gives

$$W_{C_A} - W_{C_S} = 400z^{12} + 8640z^{16} + 14688z^{20} + 8640z^{24} + 400z^{28},$$

so the additional coset introduces no new minimum words: both codes have exactly the same 45 weight-8 sentinel minima.

MacWilliams duality yields

$$\boxed{C_A^{\perp} = [40, 24, 6]_2, \qquad C_S^{\perp} = [40, 25, 4]_2}, \qquad C_S^{\perp}/C_A^{\perp} \cong C_2.$$

The geometry is explicit. The 40 W33 line indicators have rank 25 and are exactly the 40 weight-4 words of $C_S^{\perp}$, hence $C_S^{\perp}$ is the binary W33 line code. Their pairwise differences span rank 24 and equal $C_A^{\perp}$; its 240 minimum weight-6 words are exactly the symmetric differences of intersecting W33 line pairs. Thus the primal line-parity extension dualizes to the literal inclusion

$$\boxed{\text{line-difference code } [40, 24, 6]_2 < \text{ line code } [40, 25, 4]_2}.$$

This is an exact finite-code statement and does not by itself assert a physical error threshold.

79.46 Integral Smith filtration of the $PG(3,4)$ polarity operator

Let H be the symmetric 85×85 polarity/design matrix satisfying

$$H^2 = 16I + 5J, \qquad \det H = -21\,4^{84}.$$

Exact local Smith elimination at the only exceptional primes gives valuation multiplicities

$p=2$	$v_2=0$	1	2	3	4
multiplicity	17	8	36	8	16,

while at both $p = 3$ and $p = 7$ the valuation pattern is $0^{84}, 1^1$. The invariant-factor divisibility chain and determinant therefore force the complete Smith normal form

$$\boxed{\mathrm{SNF}(H) = \mathrm{diag}\big(1^{17}, 2^8, 4^{36}, 8^8, 16^{15}, 336\big)}.$$

Equivalently,

$$\operatorname{coker} H \cong (\mathbb{Z}/2)^8 \oplus (\mathbb{Z}/4)^{36} \oplus (\mathbb{Z}/8)^8 \oplus (\mathbb{Z}/16)^{15} \oplus \mathbb{Z}/336.$$

Its exponent is 336, exactly the global denominator appearing in

$$H^{-1} = H/16 - 5J/336.$$

Thus the characteristic-3 and characteristic-7 corank-one defects occupy the same terminal Smith direction, whereas characteristic 2 has a genuinely deep four-stage filtration: 68 invariant factors are divisible by 2, 60 by 4, 24 by 8, and 16 by 16. This is an integral finite-design theorem; a physical p-adic scale interpretation requires a separate dynamical map.

79.47 A seven-sector bicolour algebra on the 216 five-circuits

The maximal-overlap relation between the 216 sentinel five-circuits and the 540 sentinel six-circuits,

$$|C_5 \cap C_6| = 3,$$

is $(20, 8)$-biregular and splits into two $PSp(4,3)$ orbitals of size 2160. Let their (216×540) biadjacency matrices be M_+ and M_-. Each colour is $(10, 4)$-biregular, and exact integer computation gives

$$M_+M_+^T = M_-M_-^T = 10I + A_{30},$$
$$M_+M_-^T + M_-M_+^T = 4A_{20},$$

where A_{30} and A_{20} are simple regular graphs of degrees 30 and 20 on the five-circuit set. Their edge supports are disjoint and

$$[A_{30}, A_{20}] = 0.$$

Therefore the uncoloured incidence matrix $M = M_+ + M_-$ satisfies

$$MM^T = 20I + 2A_{30} + 4A_{20}.$$

The exact spectra are

$$\mathrm{Spec}(A_{30}) = 30^1 + 12^{15} + 6^{39} + 0^{60} + (-4)^{81} + (-6)^{20},$$

$$\mathrm{Spec}(A_{20}) = 20^1 + 8^{24} + 2^{80} + (-2)^{81} + (-4)^{15} + (-10)^{15}.$$

The separating operator $A_{30} + 7A_{20}$ has seven distinct eigenvalues and forces seven simultaneous sectors, with $(A_{30}, A_{20}; \dim)$ equal to

$$(-4,-2;81),\ (0,2;60),\ (6,8;24),\ (-6,2;20),\ (12,-10;15),\ (6,-4;15),\ (30,20;1).$$

Hence the joint spectral dimensions are

$$\boxed{1, 15, 15, 20, 24, 60, 81},$$

and the maximal-overlap Gram spectrum is

$$\boxed{\mathrm{Spec}(MM^T) = 160^1 + 64^{24} + 28^{60} + 16^{35} + 4^{96}}.$$

In particular M has full row rank 216 over characteristic zero. The proof is exact: integer annihilating polynomials and trace multiplicities replace floating-point diagonalisation. These seven spaces are certified $PSp(4,3)$-invariant spectral sectors of the incidence algebra; identification with irreducible complex representations is deliberately left to a separate character-theoretic audit.

79.48 All-five circuit frontier closure: Clifford restriction, Eisenstein sixes, kernel arithmetic, and rank-76 coherent geometry

Let M be the 216×540 maximal-overlap incidence matrix between the sentinel five- and six-circuit shells, and let $M_\pm$ be its two $\mathrm{PSp}(4,3)$ orbital colours. With

$$M_+ M_+^{\mathsf{T}} = M_- M_-^{\mathsf{T}} = 10I + A_{30}, \qquad M_+ M_-^{\mathsf{T}} + M_- M_+^{\mathsf{T}} = 4A_{20},$$

the commuting relations A_{30}, A_{20} have the previously certified joint-sector dimensions

$$1, 15, 15, 20, 24, 60, 81.$$

The present audit closes five outstanding structural questions simultaneously.

First, let K be the order-648 W33 point stabilizer with centre $Z(K) = C_3$. Exact rational spectral projectors and traces on all elements of K give the central-isotypic dimensions $(1, \omega, \omega^2)$ and restricted-character norms

dim	$(d_1, d_\omega, d_{\omega^2})$	$\langle \chi, \chi \rangle_K$
15	(3, 6, 6)	3
15	(3, 6, 6)	3
81	(27, 27, 27)	12
20	(8, 6, 6)	3
60	(18, 21, 21)	12
24	(12, 6, 6)	5
1	(1, 0, 0)	1

without guessing irreducible labels for the reducible restrictions. In particular the 24-sector agrees with the sharper decomposition

$$24 \downarrow_K = 1 \oplus 3 \oplus 8 \oplus 6_\omega \oplus 6_{\bar{\omega}}.$$

On its 12-dimensional rational nontrivial-central carrier, the canonical deck-orientation operator

$$J = z - z^2$$

satisfies the exact identity

$$\boxed{J^2 = -3I}.$$

Thus scalar extension to $\mathbb{Q}(\sqrt{-3}) = \mathbb{Q}(\omega)$ splits this rational carrier into the conjugate six-dimensional ω and ω^2 eigenspaces. Six explicitly certified central deck fibres provide a rational basis witness, giving a concrete Eisenstein realization of the two sixes.

Second, over characteristic zero,

$$\operatorname{rank} M = \operatorname{rank} M_+ = \operatorname{rank} M_- = 216,$$

so all three right kernels in the 540-dimensional six-circuit space have dimension 324. The stacked colour matrix has rank 372, hence

$$\boxed{\dim(\operatorname{row} M_+ \cap \operatorname{row} M_-) = 60},$$

while

$$\boxed{\dim(\ker M \cap \ker M_+ \cap \ker M_-) = 168},$$

and every pairwise kernel intersection is the same 168-space because $M = M_+ + M_-$. The right Gram spectrum is

$$0^{324} + 4^{96} + 16^{35} + 28^{60} + 64^{24} + 160^{1}.$$

The numerical match between the common colour row-space dimension 60 and the existing 60-dimensional left spectral sector is recorded as a target, not yet promoted to an equality of modules.

Third, the modular ranks of $(M, M_+, MM^{\mathsf{T}})$ at $p = 2, 3, 5, 7, 11, 13$ are respectively

$$(156, 201, 0),\ (216, 216, 216),\ (216, 216, 215),\ (216, 216, 156),\ (216, 216, 216),\ (216, 216, 216).$$

The exact Gram determinant has prime valuations

$$v_2 = 601, \qquad v_5 = 1, \qquad v_7 = 60.$$

Cauchy–Binet together with full row rank modulo 5 and 7 therefore forces every nonunit Smith invariant of M to be a power of 2; the mod-2 rank fixes their number:

$$\boxed{\mathrm{SNF}_{\mathrm{nonzero}}(M) = 1^{156} \oplus (\text{2-power})^{60}.}$$

Likewise the colour incidence has

$$\boxed{\mathrm{SNF}_{\mathrm{nonzero}}(M_\pm) = 1^{201} \oplus (\text{2-power})^{15}.}$$

The individual positive 2-adic exponents are not asserted here.

Finally, the complete two-fibre Schurian coherent configuration has same- and cross-fibre orbital ranks

$$r_{55} = 10, \qquad r_{66} = 32, \qquad r_{56} = r_{65} = 17,$$

and hence exact total rank

$$\boxed{76}.$$

Inside the 10-orbital five-circuit commutant, A_{30} is a single orbital whereas A_{20} is the fusion of exactly two transpose-paired directed orbitals of valency $10 + 10$. For

$$K_c = M_+ M_-^{\mathsf{T}},$$

the two directed orbitals carry constant coefficients 1 and 3, so

$$\boxed{K_c + K_c^{\mathsf{T}} = 4A_{20}},$$

but

$$[K_c, A_{20}] \neq 0, \qquad [K_c, A_{30}] \neq 0.$$

Therefore the seven-sector algebra is a symmetric commutative fusion of a genuinely noncommutative orbital algebra; the directed orientation datum is erased by symmetrization rather than supplied by an additional commuting eigenoperator.

All statements in this subsection are reproduced by `analysis/w33_20260831_all5_frontier_audit.py`, `analysis/w33_20260831_a20_directed_orbital_refinement.py`, and the cheap regression freeze `analysis/w33_20260831_all5_frontier_freeze.py`. The orientation datum is finite-geometric; no physical chirality identification is made without an explicit equivariant map.

79.49 Second five circuit closure: Wedderburn blocks, kernel, Smith form, and Eisenstein no-go

Let $M = M_+ + M_-$ be the 216×540 maximal-overlap incidence between the five- and six-circuit orbits, with the two colour orbitals $M_\pm$. The previous frontier audit proved

$$\dim\bigl(\operatorname{row} M_+ \cap \operatorname{row} M_-\bigr) = 60.$$

An exact transported-projector audit now shows that this common 60-space is *not* the symmetric 60-dimensional joint spectral sector: the latter has zero intersection with the opposite colour row space in both directions. In the sector order $15, 15, 81, 20, 60, 24, 1$, the diagonal transported intersections are

$$0,\ 0,\ 0,\ 20,\ 0,\ 24,\ 1,$$

with no nonzero off-diagonal pairwise intersections.

The 10-orbital five-circuit commutant has centre dimension 7 and exact complex Wedderburn type

$$\operatorname{End}_{\mathrm{PSp}(4,3)}(\mathbb{C}^{216}) \cong M_2(\mathbb{C}) \oplus \mathbb{C}^6.$$

Consequently

$$\mathbb{C}^{216} \cong \mathbf{1} \oplus 2V_{15} \oplus V_{20} \oplus V_{24} \oplus V_{81} \oplus V_{30} \oplus \overline{V}_{30},$$

where subscripts denote intrinsic complex dimensions. The two symmetric 15-sectors are the two noncentral rank-one projections inside the unique M_2 multiplicity block. It follows that the remaining 15 dimensions of the common colour row space form one diagonal copy of V_{15}, and hence

$$\boxed{\operatorname{row} M_+ \cap \operatorname{row} M_- \cong \mathbf{1} \oplus V_{15} \oplus V_{20} \oplus V_{24}.}$$

The symmetric 60-sector instead splits as a Galois-conjugate pair. A separating central element has polynomial

$$x^2 - 578x + 88813, \qquad \Delta = -21168 = -3 \cdot 84^2,$$

so its splitting field is $\mathbb{Q}(\sqrt{-3})$ and

$$\boxed{V_{60,\mathbb{Q}} \otimes \mathbb{C} \cong V_{30} \oplus \overline{V}_{30}.}$$

Thus the rational 60-sector carries an exact Eisenstein quadratic structure.

On the 540 six-circuits the orbital commutant has dimension 32, centre dimension 9, and complex Wedderburn block sizes

$$3, 2, 2, 2, 2, 2, 1, 1, 1.$$

Transporting a separating right-central element through M^T gives

$$\mathbb{C}^{540} \cong \mathbf{1} \oplus 3V_{15} \oplus 2V_{20} \oplus 2V_{24} \oplus 2V_{30} \oplus 2\overline{V}_{30} \oplus V_{60} \oplus V_{64} \oplus 2V_{81}.$$

Since $\operatorname{rank} M = 216$, the 324-dimensional right kernel is the multiplicity-free complement

$$\boxed{\ker(M)_{\mathbb{C}} \cong V_{15} \oplus V_{20} \oplus V_{24} \oplus V_{30} \oplus \overline{V}_{30} \oplus V_{60} \oplus V_{64} \oplus V_{81},}$$

with character norm 8. The conjugate 30-pair on the right is again Eisenstein: a separating central polynomial is

$$x^2 - 136x + 5596, \qquad \Delta = -3888 = -3 \cdot 36^2.$$

The integral incidence lattices also close exactly. Previous modular work excluded all odd Smith primes; exact local Smith elimination over $\mathbb{Z}/2^{24}\mathbb{Z}$ yields the complete nonzero Smith forms

$$\boxed{\mathrm{SNF}_{\neq 0}(M) = 1^{156}2^{44}4^{15}8,}$$

$$\boxed{\mathrm{SNF}_{\neq 0}(M_+) = \mathrm{SNF}_{\neq 0}(M_-) = 1^{201}2^{14}4.}$$

The corresponding 2-adic lattice-index exponents are 77 and 16.

Finally, the two independently constructed nontrivial central-C_3 carriers in the dark-20 and 24 sectors do *not* coincide. Their ω-six constituents are each irreducible under the order-648 point stabilizer K, but their exact character inner product is

$$\boxed{\langle \chi_{6_\omega}^{(20)}, \chi_{6_\omega}^{(24)} \rangle_K = 0.}$$

All 111 K-orbital commutant maps project to rank zero between the associated rational 12-dimensional nontrivial central carriers. Hence there is no K-equivariant intertwiner between these two $6 + \bar{6}$ species. The common Eisenstein field and common central charge therefore encode arithmetic structure without erasing representation-theoretic distinctions.

Certificate boundary. These statements are exact finite-group, module, and integral-lattice results. The occurrence of $\mathbb{Q}(\sqrt{-3})$ does not by itself identify any of the corresponding sectors with a calibrated physical degree of freedom. Executable certificates are `w33_20260831_common_colour_60_sector_test` `w33_20260831_c5_wedderburn_kernel.py`, `w33_20260831_incidence_2adic_snf.py`, and `w33_20260831_eisen`

Current VM frontier: checkpoint placement is geometry, not policy

Scope. This insert records an exact finite-geometry optimality theorem for the reversible virtual machine and its binding to the adaptive scheduler. It is a software/control result: hop-crossing counts on the certified $W(3,3)$ substrate, not Joules, optical loss, or a fabricated device.

The theorem. The reversible runtime executes compute–copy–uncompute with STRONG Merkle checkpoints. Releasing a checkpoint tier is a boundary-crossing operation, so checkpoint *placement* has a geometric floor. Exact integer certification of

$$A^2 = 8I - 2A + 4J$$

for the $W(3,3)$ adjacency matrix gives the Laplacian spectrum $0^1, 10^{24}, 16^{15}$, hence for every m-vertex subset S,

$$|\partial S| \;\geq\; \frac{m(40-m)}{4}.$$

All 36 spreads were re-derived by exact cover, and for every ordered spread the ten nested rungs of $4i$ points attain this bound with equality at every tier ($i = 1, \ldots, 10$; all 1023 nonempty line unions per spread verified). Therefore the spread ladder is the boundary-optimal reversible checkpoint hierarchy:

per-tier release $4i(10-i)$,	peak live boundary 100 at the 20|20 half-ladder,	full cycle $2 \cdot 660 = 1320$ cross

with zero retained-point migration on resize. The peak value is exactly the certified minimum boundary of the 20|20 cut, so a half-checkpointed reversible guest sits on the substrate's spectral Cheeger value; no placement can do better at half retention.

The binding. The adaptive scheduler chooses *how much* to retain (segment size B, recursion levels L) from live memory pressure; the ladder now determines *where*. A chosen strategy pins $L+1$ STRONG checkpoint roots on ladder rungs in retention order at release cost $4i(10-i)$ each; strategies needing more than ten live roots degrade the overflow to HASH_ONLY audit strength—content identity without byte retention, the strength distinction the temporal GC already defines. No root is silently upgraded or discarded, and the destructive-discard control remains excluded from the reversible frontier.

Artifacts and verification boundary. The optimality certificate is `analysis/w33_spread_ladder_reversibl` with frozen artifact `data/w33_spread_ladder_reversible_gc.json` (`sha256:ebb04e0ed67e3c014081d19ce5fe8`; the scheduler binding is `analysis/w33_ladder_checkpoint_placement.py` with `data/w33_ladder_checkpoint_` (`sha256:0cf744ccc6fb893c062cc66ae9878f83228cc2d6eb561659f46b924bac5e32fc`). The Holotrade control-plane object is `scheduler/w33-reversible-checkpoint-ladder.js`, fail-closed (`dispatchable=fal` pending runtime topology attestation. The result closes the placement half of reversible scheduling; it does not supply measured energy, physical routing, or a hardware claim.

Correction: hypervisor suspension is *not* rung 9. A first version of this insert claimed that the shared 36-state base of the 1296-state fibre hypervisor is ladder rung 9, on the strength of $36 = 4 \cdot 9$. That identification was never constructed and is false. The base is the set of 36 spreads (fibre group S_6, $\mathrm{PSp}(4,3)$-stabiliser order 720); the rung-9 regions are the complements of single lines, of which there are 40 (stabiliser order 648). Since $36 \neq 40$ and $720 \neq 648$, no equivariant identification exists. What survives is the exact statement that every 36-point union of nine spread lines has boundary $36 = m(40-m)/4$, so any 36-point retention costs at least 72 crossings per release/restore cycle. A map from the spread base to a retained region is open. Certificate: `analysis/w33_fibre_suspension_ladder.py` (schema v2; v1 retracted).

Current magic frontier: symmetric acceptance witnesses have no logical output

Scope. An exact finite search result about an acceptance condition: annihilate the single-error subspace and accept the clean input with nonzero probability. The resulting output need not be the clean magic ray. Here every returned hit has a one-dimensional stabilizer range, so these branches have no logical output and cannot supply a distilled magic state through stabilizer decoding.

The search that was asked for. Pass 2861 exhausted all 5,355 two-copy $[[4, 2]]$ codes: zero super-linear branches. Pass 2881 sampled 30,000 random six-qubit stabilizer groups at three copies: zero; Pass 4680 then proved that sample had at most about one percent power unless witnesses number in the tens of thousands. The recorded ask was an *exhaustive search over a chosen code family.* The chosen family is canonical: the exact condition is copy-permutation invariant, so the search exhausts ALL S_3-invariant stabilizer groups. By the isotypic decomposition $\mathbb{F}_2^{12} = \mathbb{F}_2^4 \otimes (\mathrm{triv} \oplus \mathrm{std})$, every such group is $V_t \oplus W_T$ with V_t, T isotropic in the 2-qubit label space (31 choices each, automatically mutually orthogonal), giving exactly

961 groups, 27,391 signed syndrome projectors per ray.

The result. Exact integer arithmetic in $\mathbb{Z}[\zeta_{12}]$ (Walsh–Hadamard over each group's 2^r sign assignments, with the full Pauli operator-product phase cocycle — dropping it was two false starts) against

$$\mathrm{Tr}(PJ) = 0 \quad \text{and} \quad \langle mmm|P|mmm\rangle \neq 0,$$

finds, for the 36 M_{36} rays:

104 witnesses, every reported one independently re-verified by a dense projector construction on a separate code

Per family: seven rays carry 2 witnesses and two rays carry 6. All witnesses have generator rank 6 and projector rank 1. A representative for ray $\mathrm{A}_{00} = (0, 1, -1, 1)/\sqrt{3}$: the group generated by

$$X_2^{\otimes 3}, \quad X_1^{\otimes 3}, \quad Z_2^{(13)}, \quad Z_2^{(23)}, \quad Z_1^{(13)}, \quad Z_1^{(23)},$$

with generator signs $(-, +, +, +, +, +)$, annihilates all nine single-error inputs and accepts the clean input with nonzero probability.

Connection to the existing obstruction. These are acceptance witnesses, not generators stabilizing the clean input. Passes 2933 and 2977 already found rank-one acceptance witnesses and identified their lack of magic output; Pass 2990 and the blueprint's three-copy section record that obstruction. The symmetric-family enumeration adds coverage and counts, not the first existence proof or a useful distillation protocol.

What changes. The acceptance predicate is satisfiable, as was already known. An independent output-rank audit replays the enumeration, checks commutation and binary rank, and dense-checks every returned witness. All 104 hits have six independent generators on six qubits: $k = 6 - 6 = 0$ and projector rank $2^k = 1$. There is no remaining logical output for a stabilizer decoder to turn into magic. Useful super-linear distillation remains open; this result does not exclude asymmetric protocols or protocols with a different correction condition.

Artifacts. `analysis/w33_pass20260906_three_copy_symmetric_exhaustion.py`, certificate `data/PART_W33_` (`sha256:1fe928217c0bc03fb86f232917972cb0eb50518b989fac409a572b18fa11cbd9`), regression gate `tests/test_w33_pass20260906_three_copy_symmetric_exhaustion.py`. The original certificate stores one explicit replayable witness per ray; its dense check sampled at most four hits per ray. The follow-up `analysis/w33_three_copy_output_rank_audit.py` checks all 104 hits and records the logical-output boundary explicitly.

Runtime audit: retain recoverable state and require useful output

The authenticated-counter guest now has an executable lossless suspension adapter. It archives both fibre tags, guest control state and every reachable counter node under a STRONG temporal-GC reference. After worker memory is discarded and collection runs, the guest resumes at step 7 and completes $(7, 11) \mapsto (18, 0)$ at step 24. All 1296 fibre addresses round-trip in the regression suite. The adapter is `analysis/w33_lossless_counter_suspension.py`.

The existing six-to-one fibre projections imply that a live leg and shared base do not determine the missing tag. Retain that tag or a recoverable replay source. Likewise, 36 possible base values do not by themselves allocate 36 network points. The spread-ladder cut bound remains valid; converting its boundary table to executed traffic requires an explicit routing protocol. The actual space-favoured ladder plan requests 13 STRONG roots but supplies 10 STRONG and 3 HASH_ONLY. The latter do not retain bytes under the existing collector, so the new admission audit rejects that unsatisfied retention demand.

The output-rank audit also reconciles the new three-copy search with the blueprint's earlier rank-one obstruction (Passes 2933, 2977 and 2990). Every one of the 104 returned acceptance hits has six independent generators on six qubits, hence zero logical qubits and a one-dimensional stabilizer output. The acceptance enumeration is preserved; useful super-linear magic distillation remains open. The all-hit replay is `analysis/w33_three_copy_output_rank_audit.py`.

These are finite software recovery and audit results. They supply no measured device, quantum resource, capacity allocation or physical network-cost proof. The report `analysis/W33_VM_RETENTION_AND_OUTPUT` records source ownership, frozen certificates and replay commands.

79.50 Shared counter archives and exact payload admission

The authenticated counter guest now has a collector-visible shared archive. Each binary node retains its counter digest and a tail edge; each snapshot retains complete control state and both fibre tags. Admission validates and prices the union of all strong-root closures before installation, including unrelated retained resources. A quote is advisory: publication recomputes it. For blob payload weights w_b, existing retained closure B, and candidate closures C_s, the cost is

$$F(S) = \sum_{b \in B \cup \bigcup_{s \in S} C_s} w_b.$$

This is standard weighted coverage, so marginal retention costs diminish as the retained set grows; no scheduling optimality follows from that identity.

The executable population witness retains and restores 256 counter states using 263216 canonical JSON payload bytes, compared with 469207 for the existing monolithic adapter. Sharing has overhead: a single zero-counter snapshot uses 821 bytes versus 671. With counter 255 retained, adding 254 costs 1029 bytes while adding 128 costs 2529, despite equal bit length. The collector now uses an explicit stack; a 4096-bit counter survives collection and independent recovery. These figures

exclude registry, index, RAM, CPU and I/O costs. Operations are owner-serialized, with durability and concurrent transactions outside the model. The construction extends the existing suspension and zero-copy modules, not their universality claims. See `analysis/W33_SHARED_COUNTER_ARCHIVE.md` for attribution, architecture, replay commands and finite-implementation boundaries.

79.51 Joint admission of shared guest snapshots

Snapshot retention now has a bounded exact set-union admission planner. Requests carry caller-supplied nonnegative integer utility; blob payloads are charged once across the union of their reachable closures, and all existing strong roots remain mandatory. The reference planner exhausts at most sixteen requests, maximizes utility, then breaks ties by bytes and request identifiers. This instantiates the established set-union knapsack problem, not a new optimization theorem or the existing reversible pebble scheduler.

An executable three-request counter workload makes the distinction concrete. Snapshots for 128, 254 and 255 each cost 2821 canonical payload bytes alone. The pair 254 and 255 costs 3850, whereas either paired with 128 costs 5350. At budget 3850 and equal utilities, exact joint admission retains the shared pair. The tested smallest-current-marginal greedy rule, with identifier ties, retains 128 alone. Both selected guests restore and run to halt.

Publication recomputes the plan against the current registry, request set and caller budget, then stages the entire batch before installing it. An injected second-publication failure leaves the public stores unchanged. Operations must be owner-serialized; crash recovery, peak RAM and registry/index overhead remain outside this payload-only model. The source attribution, full subset table and regression oracle are in `analysis/W33_JOINT_SNAPSHOT_ADMISSION.md`.

HoloVM process kernel: process identity above shared value state

Scope. The existing runtime already has authenticated guest transitions, persistent content-addressed state, capability-address pointers, execution passports, same-carrier checkpoints, neutral cross-carrier continuations, temporal GC, shared snapshots, and exact bounded snapshot admission. The missing systems object was a *process identity*: identical recoverable snapshots can legitimately belong to different forks.

Process/value separation. The executable reference model `analysis/w33_holovm_process_kernel.py` adds one immutable process node above the existing recoverable snapshot:

$$C = (\text{pid}, \text{branch}, \text{generation}, \text{parent}, \text{passport}, \text{state}, \text{fibre}, \text{history}, \text{receipt}).$$

Its Merkle node has exactly one strong child, the shared snapshot root. Hence two same-state forks satisfy

$$\boxed{\text{snapshot}(C_a) = \text{snapshot}(C_b)} \qquad \text{but} \qquad \boxed{\text{root}(C_a) \neq \text{root}(C_b),\ \text{pid}(C_a) \neq \text{pid}(C_b).}$$

The second fork copies no counter node: its exact marginal canonical-blob payload is one outer process descriptor. This is process-level copy-on-write, not a claim about physical RAM pages.

Execution as continuation reduction. One guest step is now

$$C_n \xrightarrow{\rho_n} C_{n+1},$$

where ρ_n is the existing authenticated-counter receipt. The prover's post-state is independently reconstructed by the store-free verifier before a child continuation is emitted. The logical process id is stable across the step, while the continuation id, generation, parent link and causal history root change. Deterministic replay of the same parent produces the same receipt and child continuation; the receipt's W33 route still has at most two hops.

Retention and software causality. A live process is a STRONG root in the existing temporal root registry. The collector follows the process node into the shared snapshot closure. Parent and history hashes are intentionally descriptor values rather than Merkle child edges. Therefore a descendant can retain the identity of an ancestor without pinning all ancestor bytes. The verifier pins sibling and descendant roots, demotes an ancestor to HASH_ONLY, releases its STRONG root, collects the old process blob, and still resumes both surviving continuations exactly.

Thus, at the software level only,

$$\boxed{\text{reconstructible memory} = \text{closure of STRONG continuation roots}}$$

while causal ordering may survive as hashes after the bytes are reclaimed. This is a precise process semantics for the project's "time as memory" intuition, *not* a thermodynamic or relativistic identification.

Virtual hardware normal form. The resulting machine reads

vCPU	authenticated prove/verify transition engine,
registers	*pc*, *portal*, *two state roots*, *generation*, *history*,
MMU	bounded base-40 capability-address ISA,
interconnect	$W(3,3)$ diameter-two routing,
placement	$36 \times 6 \times 6$ fibre-product coordinate,
process table	STRONG continuation roots,
checkpoint/swap	shared immutable snapshot DAG,
fork	one process node over a shared value closure,
forget	release STRONG root then temporal GC.

The finite geometry remains the control/routing fabric. Abstract universality comes from the extensible authenticated guest state, not from treating one 40-node device as infinite memory.

External context and boundary. Content-addressed deduplication follows the broad Venti lineage; monotone authority follows the CHERI capability discipline; the language frontend remains compatible with WebAssembly's abstract-machine reduction semantics; and the reversible checkpoint trade surface remains in Bennett's compute–checkpoint–uncompute tradition. None of those prior ideas is claimed as new. The new repository-level statement is the explicit process/value split that makes the existing W33 VM components one coherent continuation machine. No fabricated photonic processor, hardware capability tag, durability service, distributed consensus protocol, or physical energy law is inferred.

79.52 Preemptible authenticated counter microcode

The existing authenticated counter ISA admits a persistent path-context implementation, specializing Huet's zipper rather than asserting a new data-structure theorem. A trusted continuation

carries the committed guest state, both fibre tags, a phase, and cursor, stack and result roots. `SCAN` consumes one carry/borrow digit; `UNWIND` rebuilds one; `COMMIT` emits the existing portal route. Each tick opens at most one canonical bit node and writes at most one. Only a verified final continuation changes the committed guest registers and program counter.

A propagated prefix of length k takes $2k+3$ ticks. The finite-prefix scan and unwind terminate and refine the existing macro instruction. For a 4096-bit carry or borrow, the witness gives 8195 ticks, with the same result as the independent macro verifier; all 512 small cases agree. A short increment commits after three one-tick scheduling rounds while a long carry remains uncommitted. This bounds bit-node work, not wall-clock latency, program validation, wire bytes, RAM or physical gate cost.

Retention must cover the continuation, not just the visible guest registers: a paused borrow has 17 nodes under the committed roots but 24 under the complete live roots. A full-closure checkpoint retains both fibre tags, recovers under a trusted continuation identity, and survives collection while its archive reference is strong. A hash-only audit reference does not retain its bytes. The scalable counter semantics supply the universality argument; a finite controller or fixed finite hash space alone does not. The executable, frozen certificate and adversarial recovery tests are `w33_counter_zipper_microcode.py`, `w33_counter_zipper_microcode_certificate.json` and `test_w33_counter_zipper_microcode.py`. Prior art, the phase argument and implementation limits are recorded in `analysis/W33_COUNTER_ZIPPER_MICROCODE.md`.

Compiler admission is a separate obligation from content identity. In the dynamic sparse witness, replacing the valid Wasm constant 77 by 78 preserved every opcode but formerly left the counter target returning 77. The exact-witness compiler now checks decoded operands and module bindings, rejecting unsupported inputs before target generation. Three regression tests cover differential memory execution, five same-opcode mutations and an accepted custom-section variation. This enforces the documented restricted source language; it is not a general compiler-equivalence theorem.

The process microstep owner now separates reusable arithmetic evidence from consumption of a particular process cursor. Eight identical-value forks use 19 inner proofs for 152 accepted process-bound submissions; all 152 immediate duplicate submissions reject. Final values agree with an independent macro verifier while all eight histories and continuation identities differ. The trusted serialized owner publishes guest state only at macro commit. Seven owner tests plus the seven process-kernel and nine zipper tests pass. This is an in-memory execution protocol, not durable exactly-once external I/O; see `analysis/W33_PROCESS_MICROSTEP_OWNER.md` for the executable, prior ownership, retention roundtrip and scope.

A subsequent SQLite adapter publishes the consumed cursor and its complete live bit closure in one transaction. Killing a worker before commit recovers tick 8 and permits one retry; killing it after commit recovers tick 9 and rejects the retry. Both borrow executions finish in 35 ticks at 65535. The final macro commit also survives a lost reply without committing twice. Five durability tests and seven existing owner tests pass, including a two-connection submission race and restart after every tick. These are process exit experiments, not power-loss tests or exactly-once external effects. The database is trusted authority and each tick writes a full snapshot; see `analysis/W33_DURABLE_MICROSTEP_OWNER.md`.

Exact accounting further separates work, content and observable information. Writing $s(x)$ for binary popcount, L increments from a take $5L + 2s(a) - 2s(a+L)$ microticks. From zero, preemption adds $M - s(M)$ bit-write operations relative to the prior macro backend, but adds no distinct bit nodes when all earlier counter values remain retained. For a uniform n-bit initial value and $L = 2^m$, $0 \le m < n$, individual completion times reveal $m + 2 - 2^{1-(n-m)}$ bits, while total batch time reveals only $2 - 2^{1-(n-m)}$ bits. The proof identifies the transcript with the low m bits

and the trailing-one count of the remaining high part. An explicit reversible XOR permutation erases the correlated timing record using the retained final counter: its conditional entropy is zero even when its marginal entropy is positive. This supplies no measured heat or zero-energy device claim. Exact backend counts, 45 timing partitions and a 1024-state permutation witness are in `analysis/W33_CARRY_TIMING_INFORMATION.md`.

Radix, noisy observations, and synthesized erasure. The executable extension `w33_computation_resourc` checks an abstract radix-b zipper law

$$T_b(a, L) = 3L + \frac{2}{b-1}\big(L + s_b(a) - s_b(a+L)\big).$$

For X uniform on $0, \ldots, b^n - 1$ and $L = b^m$, the individual timing entropy is $m \log_2 b + h_b(n-m)$, whereas the total duration has entropy $h_b(n-m)$, where

$$h_b(d) = (1 - b^{-d}) \left(\frac{b}{b-1} \log_2 b - \log_2(b-1) \right).$$

Forty finite ensembles check this identity; classical radix symbols do not establish coherent qutrit hardware. For mixed binary arithmetic, each crossing of the edge $u - 1 \leftrightarrow u$ costs $3 + 2v_2(u)$ ticks. A closed cycle at 2^k costs $4k + 6$, preventing a uniform constant amortized bound for both operations using a counter-state potential.

For exact timing Z, final counter $Y = X + L$, and independent additive observation noise E, the noisy record $O = Z + E$ satisfies $H(O \mid Y) = H(E)$. Thus noise can reduce input leakage while leaving randomness that Y cannot uncompute. Four timings with independent jitter $(-2, 0, 2)$ of probabilities $(1/4, 1/2, 1/4)$ leak about 2.005 bits but retain six conditional record bits. For the exact record, a prefix circuit reconstructs the statistic (r, k) from Y with $d = n - m$ clean ancillas, $2d$ NOT gates, $2(d-1)$ Toffoli gates, and $m + 2 + 2d - \mathrm{popcount}(d)$ CNOT gates, then restores its ancillas. Twenty-eight sizes pass exhaustive clean-ancilla checks. The five-bit example uses eighteen gates. This is a basis-permutation construction, not measured physical dissipation. The accompanying report separately attributes a published colloidal-trap work measurement and keeps Holonet calibration open.

Redundant counters and eight observation experiments. The follow-up `W33_EIGHT_COMPUTATION_EXPERI` reports seven executed computational investigations and one blocked physical collection. An authenticated redundant counter stores $P - N$ with $P \geq N$ and increments only P or N; canonical root equality supplies its zero test under the trusted invariant. For U increments, D successful decrements and Z zero decrements,

$$T = Z + 5(U + D) + 2s(P_0) + 2s(N_0) - 2s(P_f) - 2s(N_f).$$

All 320 tested six-operation paths pass. At the 2^{64} boundary, 128 alternating cycles take 1390 arithmetic microticks rather than 33536, at the cost of growing representation state; wrapper work and integration into the guest ABI remain outside this claim.

Retaining reversible noise seeds permits noisy-record erasure, but reusing a common additive seed exposes timing differences: four timings again reveal all three input bits in the tested ensemble. A ternary eraser uses eight controlled modular-shift gates on nine qutrits; its 19683-state permutation and a complex superposition preserve amplitudes while clearing the intended record and ancillas in simulation. Sixteen padding policies supply an exact finite latency–information frontier. Holotrade separately exports signed pencil preimages and rational primal–dual certificates with real

ℓ_1 optima 5 and 8, so the selected profiles' negativity survives fractional relaxation. These statements neither construct blockers nor measure physical heat. The reset-work protocol and analyzer reject synthetic provenance, and physical collection remains blocked without instrument data.

Redundant guest and controlled-qutrit follow-up (September 9). The executable adapter `w33_redundant_guest_abi.py` implements both logical counters as monotone differences, with image-bound expected-parent receipts and derived INC/DECJZ/HALT control. It passes 550 differential guest steps; stateful consumption remains a separate owner obligation. The existing ternary eraser now has a declared one-/two-qutrit target circuit: 44 gates, including 24 two-qutrit gates, using Fourier transforms, equality-controlled shifts and ninth-root phases. Basis-gadget and arbitrary coherent-state checks preserve phases; physical calibration is unprovided. For four observations of a uniform three-bit input, enumerating all 16 fixed fresh-seed placement subsets gives minimum leakage 2.512799852 bits at a four-bit retained-seed budget, attained by the two alternating subsets. This finite-family optimum excludes adaptive channels. The companion Holotrade dual-potential audit forces 16 zero coefficients for the mass-12 representative and sign constraints for both certified representatives. See `W33_FIVE_COMPUTATION_FOLLOWUPS.md`; physical reset collection remains blocked by missing measurements.

Durable consumption, Clifford–T lowering, and adaptive privacy. The September 11 follow-up implements atomic macro-receipt consumption of redundant two-register guests, persisting the exact four-root live closure with the current head. Restart, competing-writer, and process-death controls pass; physical power loss and external I/O remain outside scope. The controlled ninth-root target gates now lower to qutrit Fourier, Pauli, Clifford phase, SUM, and $T = \mathrm{diag}(1, \zeta, \zeta^{-1})$ gates, using two clean workspaces returned to zero. The full eraser uses 794 gates and passes a coherent-state check; this is logical gate-set synthesis, not measured fault tolerance. A public causal privacy policy with at most two independent timing masks (four retained seed bits) improves classical guessing probability from 53/64 for the best fixed subset to 49/64. Applied to the certified 85-state trace observer, adaptive suppression of at most one output improves 77/85 to 71/85. These finite-family optima exclude quantum side information. Companion Holotrade rational dual receipts certify the existing mass-28 circuit escapes at negative mass one without a runtime solver. Physical reset collection remains blocked by absent data. Full statements and prior ownership appear in `W33_SEPT11_EXECUTION_FRONTIERS.md`.

79.53 Reye sector control and its symplectic obstruction

The certified carrier $\{X, Y, Z\}_1 \times \{I, Z\}_2 \times \{I, X\}_3$ generates $\mathfrak{su}(2)^{\oplus 4}$ under independently switchable signed continuous Hamiltonian controls. Its rank-two sector projectors are $Q_{s,t} = (I + sZ_2)(I + tX_3)/4$. A sector-addressed rotation $\exp(-i\theta A_1 Q_{s,t})$ lowers to four commuting selected-Pauli pulses with angles $\theta(1, s, t, st)/4$. Adding X_2, Z_3, Z_2 successively gives Lie dimensions $12, 20, 36, 63$. After the first two additions the commutant is scalar, but the skew form $J = Y_1 Z_2 X_3$ is preserved: $P^T J + JP = 0$. The resulting algebra is compact $\mathfrak{sp}(4)$ on $\mathbb{C}^8$; adding Z_2 gives $\mathfrak{su}(8)$. Exhaustion of all $\binom{51}{2} = 1275$ pairs of extra individual Pauli controls proves that three such additions are minimal for this fixed carrier. The executable certificate `analysis/w33_reye_sector_control.py` also compiles all 63 Pauli rotations through exact conjugation identities, checks their coherent matrices, and verifies a second realization. These are ideal finite-register control results, not a physical Holonet implementation, a noise threshold, or a scalable universal-machine proof.

79.54 Connected Reye registers and exact cross-fibre frames

The register family now has an explicit inter-tile port: $Z_{1,r}Z_{1,r+1}$, independently switchable on a tile chain. Local full control and these ports lower routed CNOTs through $\mathrm{CZ} = e^{-i\pi/4}R_{Z_a}(-\pi/4)R_{Z_b}(-\pi/4)R_{Z_aZ_b}(\pi/4$ All 108 ordered routing pairs on one through three tiles pass, and a non-port two-tile CNOT lowers to 247 declared Pauli pulses with its full coherent matrix checked. This supplies a logically scalable circuit architecture under the stated ideal coupling assumptions. Shortest conjugation templates reduce the 63-rotation total from 369 to 337 pulses and the worst case from 21 to 15; all-pair cost inequalities certify the bound within the recursive conjugation grammar. Synthetic channel sweeps separately track coherent gate fidelity and sector leakage: dephasing can damage coherence without leaving a sector. These model data are not device calibration.

The Schur cross-fibre kernel also has explicit matrices. With $\omega = (-1 + i\sqrt{3})/2$, set

$$A = \frac{1}{\sqrt{3}}\begin{pmatrix} -1 & 1 \\ 2 & 1 \end{pmatrix}, \qquad B = \frac{1}{\sqrt{3}}\begin{pmatrix} -1 & \omega \\ 2\bar{\omega} & 1 \end{pmatrix}.$$

They preserve the binary quartic and Hessian, obey $A^2 = B^2 = I$ and $AB = -BA$, and generate the sixteen matrices $i^p A^a B^b$. An explicit conjugator identifies them with the one-qubit Pauli group; the original-coordinate positive Hermitian form is $\mathrm{diag}(2, 1)$. The phase-aware frame update is $(p, a, b)(q, c, d) = (p + q + 2bc \bmod 4, a \oplus c, b \oplus d)$. Companion Holotrade now offers an opt-in one-step exact-dual transaction mode checking actual integer vectors and rational optimality before signed delivery. Full code, synthetic data, and scope appear in `W33_REYE_FIVE_FOLLOWUPS.md`; no physical scalability or fault-tolerance claim follows from these finite certificates.

79.55 Routing costs, composite-control limits and frame normalizers

The next execution packet supplies weighted routing on arbitrary declared CNOT graphs. Its move-control-and-restore grammar minimizes twice the SWAP cost plus the terminal CNOT cost; 210 finite cases match an independent simple-path oracle. Commutation across pulse-template boundaries reduces the 63-rotation batch from 337 to 301 pulses while preserving its full matrix. A BB1 sequence on selected-sector quadratures improves common amplitude-error sensitivity but requires nine times the duration. The tested mixed-error case becomes worse, so no unconditional robustness claim follows. Simultaneous phased sector quadratures are an explicit added control assumption.

For the previously supplied Schur-to-Pauli conjugator S, the two matrices SHS^{-1} and $S\,\mathrm{diag}(1, i)S^{-1}$ normalize the sixteen kernel matrices and preserve the supplied Hermitian form. Their induced frame maps have order 24 and pass all 6144 kernel multiplication checks. The full unitary normalizer retains a central $U(1)$; the finite order refers to its projective action. No preservation of the whole Schur configuration is inferred. Companion Holotrade now verifies bounded exact-dual move histories with every intermediate state derived in integer arithmetic. See `W33_REYE_ROUTING_ROBUST_FRAMES.md` for interfaces, citations, reproduction and the negative control-error findings.

79.56 Shared ports, echoed sectors and quartic-preserving frames

The dependency-preserving circuit scheduler now reserves both endpoint buses for cross-register operations: the checked example takes 19 rather than 26 serial ticks. Clifford-frame propagation removes a four-pulse conjugation identity that commuting-only reduction misses; its 63-rotation benchmark still lowers to the prior 301 native pulses, so abstract frame counts are not treated as physical savings. Combining selected-sector BB1 with Z_2 echoes suppresses common amplitude

error and modeled X_2 crosstalk in the tested cases. The 16-cycle construction assumes 160 instantaneous error-free echo pulses and simultaneous phased controls; finite-bandwidth performance remains open.

Exactly twelve of the twenty-four explicit projective Clifford frames preserve ϕ up to a phase multiplier a. Four corrections satisfying $\lambda^4 a = 1$ per accepted frame recover the prior forty-eight quartic lifts. The Hessian character has three values, four projective frames each, recovering the prior sixteen-element joint kernel. This connects explicit frame maps to the existing A_4 result without claiming a new classification. Companion Holotrade verifies arriving move chunks atomically and resumes from trusted-digest checkpoints by replay; final optimality remains gated on the exact dual proof. See `W33_REYE_PORTS_FRAMES_ECHO_STREAMS.md`.

79.57 Finite control costs and a phase-aware instruction algebra

The executable followup `w33_reye_finite_control_costs.py` reduces the same native-control batch from 301 to 264 pulses, with full-matrix error below 1.3×10^{-15}. Its finite square-echo model also separates leakage from coherent error: at fractional echo error 10^{-3}, sixteen cycles have leakage below 2.2×10^{-9} but infidelity approximately 0.055. These are synthetic control results, not device calibration. The bounded four-job scheduler explicitly trades memory exposure against simultaneous-drive penalties; minimum duration need not minimize that score.

The prior 48 quartic lifts now have an exact instruction table in `w33_schur48_phase_isa.py`. With $\omega = (-1 + i\sqrt{3})/2$ and $C = \omega(-I + i(X + Y + Z))/2$, every instruction is $i^p Z^a X^b C^k$, where $C^3 = I$. All 2304 matrix products and 110592 associativity triples are checked. The projective multiplication carries an explicit $\mathbb{Z}/4$ phase cocycle: the commuting projective Z, X pair has exact commutator $-I$. This obstruction cannot be removed by changing scalar representatives. Known phase-referenced controlled implementations distinguish the four central lifts, although their standalone channels agree. This invokes an additional control interface, not control of a completely unknown black box. The finite group alone is not a universal quantum gate set.

Companion Holotrade streams now use transactional SQLite checkpoints and a separately trusted revision anchor, with replay and strict prefix extension. Crash, stale-write and data-only rollback tests pass. Restoring both checkpoint and anchor is outside the contract. See `analysis/W33_FINITE_CONTROL_PHASE_ISA.md` for prior ownership, primary references, executable artifacts and limits.

79.58 Coxeter–Todd orientation and an exact finite observer

The reproducible audit `analysis/w33_coxeter_todd_oriented_observer.py` constructs an explicit signed intertwiner from the 40-dimensional deck-odd local Coxeter–Todd cover to the oriented H_2 of the W33 two-skeleton. It credits Holotrade's K12 construction and BT862/866's previously certified $5_\omega \oplus 5_{\omega^2} \oplus 30$ module. These cycles disappear when one includes the tetrahedral three-cells of the full clique complex. For the signed adjacency S, let $P_{10} = (3I - S)/12$. An explicit integral operator satisfies

$$K^{\mathsf{T}} = -K, \qquad K^2 = -48P_{10}, \qquad SK = -9K.$$

Thus $K/4$ realizes the Eisenstein structure on the real ten-dimensional summand. For externally chosen real g, η, the finite Hermitian model $gS + i\eta K$ has bands $3g$ (multiplicity 30) and $-9g \pm 4\sqrt{3}\eta$ (multiplicity 5 each). The sign of K remains a conjugate orientation choice, not a selected physical handedness. On the 126-line adjacency dynamics, observing the 45 neighbors of one line leaves exactly 55 amplitude modes invisible for all time. The certificate supplies 45 additional coordinate outputs attaining full observability; fewer cannot suffice because the invisible eigenvalue-3 space

has dimension 45. Moreover, 90 total outputs are globally minimal among fixed linear observers, since the full adjacency has a 90-dimensional eigenvalue-3 space. This is a theorem about linear amplitude outputs, not intensity-only measurement, quantum tomography, physical masses, or a continuum TOE. The accompanying Markdown report records prior ownership, proofs, and the incomplete scope of the current corpus rereading.

79.59 K12 and genus: an integral pairing with a Jacobian boundary

The certificate `w33_k12_genus_polarization.json` constructs an integral Gram matrix G of determinant 3^6 and a unimodular alternating form E on the Coxeter–Todd lattice. For its Eisenstein operator W, $J = (2W + 1)/\sqrt{3}$ satisfies $J^2 = -1$ and $EJ = G/\sqrt{3} > 0$. An explicit integral Darboux basis identifies this alternating module with abstract genus-six first homology. This is not a triangulation map. Moreover, scalar multiplication by ω preserves the polarization; strong Torelli and the canonical map obstruct this specified polarized sixfold from being a smooth curve's Jacobian. Other complex structures and polarizations remain separate questions. The certified antilinear Gaussian operator I instead satisfies $I^tEI = -E$; the compatible form $-GI$ has type $(1, 1, 1, 3, 3, 3)$. The complete-graph genus formula requires a ceiling, and the linear genus oscillator agrees with minimal surface counts only at genera $0, 1, 2$, as already recorded in the oscillator corpus. No physical frequency scale or particle identification follows. Proof, prior ownership and source coverage are in `W33_K12_GENUS_POLARIZATION.md`.

79.60 The E_8 twisted register is the root-fibration quotient

The previously separate $E_8 \to W(3, 3)$ constructions are in fact the same quotient map on roots. Let c be the canonical Coxeter element of Pass 1021 and $g = c^{10}$. The exact certificate `w33_e8_twisted_fibration_wel` gives

$$\mathrm{SNF}(1 - g) = \mathrm{diag}(1, 1, 1, 1, 3, 3, 3, 3), \qquad E_8/(1 - g)E_8 \cong \mathbb{F}_3^4.$$

The 240 roots hit all 80 nonzero quotient vectors, exactly three roots per vector, with fibre $\{r, gr, g^2r\}$. Projectivizing $v \sim -v$ therefore gives 40 points with six-root fibres $\{\pm r, \pm gr, \pm g^2r\}$. Since $g = (c^5)^2$ and $-1 = (c^5)^3$, these are exactly the $\langle c^5\rangle \cong C_6$ Eisenstein fibres certified in Pass 1021. For the order-three twisted-module commutator exponent

$$\Omega(a, b) = \sum_{k=1}^{2} k\,\langle g^k a, b\rangle \pmod 3,$$

the form is alternating of rank four and has $(1 - g)E_8 \bmod 3$ as its radical. Hence the induced quotient form is nondegenerate symplectic, and projective orthogonality is $\mathrm{srg}(40, 12, 2, 4)$, i.e. $W(3, 3)$. Thus the exact finite dictionary is

$$240\ E_8 \text{ roots} \longrightarrow 80 \text{ nonidentity two-qutrit Pauli labels} \longrightarrow 40\ W(3, 3) \text{ projective Pauli points.}$$

Pass 1021 owns the six-root fibration; Holotrade `68df33f` owns the twisted-register identification; the classical twisted-module framework is Bakalov–Kac (`arXiv:math/0402315`, Eq. 4.43). The new result here is the exact equality of the two quotient maps. No continuum or experimental claim follows from this finite identification.

79.60.1 The Pauli powers are the two orientations of an A_2 fibre

The root-fibration/twisted-register weld admits a sharper root-system reading. For $g = c^{10}$, fixed-point-free of order three, $1+g+g^2 = 0$. The exact certificate `w33_e8_oriented_a2_refinement.json` checks all 80 g-orbits on the E_8 root shell and finds

$$r + gr + g^2 r = 0, \qquad \langle r, gr\rangle = \langle gr, g^2 r\rangle = \langle g^2 r, r\rangle = -1.$$

Thus every nonzero vector $v \in E_8/(1-g)E_8 \cong \mathbb{F}_3^4$ is an oriented A_2 root triangle $\{r, gr, g^2 r\}$, while $-v$ is the opposite triangle. Pairing v with $-v$ gives one full six-root A_2 subsystem, and every such subsystem is exactly the corresponding Pass-1021 $\langle c^5\rangle = \langle -1, g\rangle \cong C_6$ fibre. Consequently the finite dictionary refines to

240 E_8 roots $\longrightarrow$ 80 oriented A_2 triangles / Pauli labels $\longrightarrow$ 40 full A_2 systems / $W(3,3)$ points.

This is a finite root-system refinement of the already-certified weld, not an additional physical claim.

79.61 The A_8 fixed-sector support is the two-qutrit Pauli support

The order-three E_8 weld also closes the support-level form of an old algebraic gap. Index the 80 oriented root orbits by the nonzero vectors $v \in \mathbb{F}_3^4$. The exact certificate `w33_e8_a8_pauli_support_bridge.json` checks every one of the $\binom{80}{2} = 3160$ unordered pairs. With Ω the induced symplectic form, the complete census is

$$\Omega = 0:\ 1000 \text{ pairs and no root sum}, \qquad \Omega = 1:\ 1080 \text{ pairs}, \qquad \Omega = 2:\ 1080 \text{ pairs},$$

and every nonorthogonal pair has exactly three root sums, all in the unique oriented orbit of degree $v + w$. The standard tensor-Pauli grading of $\mathfrak{sl}_9$ on two qutrits has the identical 1000/1080/1080 census: its bracket vanishes exactly for $\Omega(v, w) = 0$ and otherwise has degree $v + w$. Thus the E_8 root-orbit addition support and the $\mathbb{F}_3^4$ Pauli-grading support agree pair-by-pair. The classical order-three E_8 grading has fixed algebra $A_8 = \mathfrak{sl}_9$; and Pelantová–Svobodová–Tremblay (`arXiv:quant-ph/0510106`) prove that the tensor-Pauli fine grading of $\mathfrak{sl}(p^2)$ has normalizer quotient $\mathrm{Sp}(4, \mathbb{F}_p) \times C_2$. The new result here is the exact root-orbit support identification at $p = 3$. A Chevalley cocycle/order-three lift remains to be fixed before equality of Lie structure constants is claimed.

79.62 Classification closes the A_8 fixed sector as the two-qutrit Pauli grading

Let $V = E_8/(1-g)E_8 \cong \mathbb{F}_3^4$. The order-three fixed algebra is the Kac A_8 class $\mathfrak{a} \cong \mathfrak{sl}_9(\mathbb{C})$, and the preceding certificates decompose it into eighty one-dimensional fixed root-orbit lines

$$\mathfrak{a} = \bigoplus_{0 \neq v \in V} \mathfrak{a}_v, \qquad [\mathfrak{a}_v, \mathfrak{a}_w] \subseteq \mathfrak{a}_{v+w}, \qquad \mathfrak{a}_0 = 0.$$

Hence this is a fine V-grading. Bahturin–Kochetov's classification of Type-A gradings (`arXiv:0908.0906`) now removes the remaining cocycle ambiguity up to graded equivalence. Type II requires a distinguished element of order two, impossible for $V \cong C_3^4$, so the grading is Type I and comes from a unique V-grading of $M_9(\mathbb{C})$. Restoring the identity gives all $81 = 9^2$ matrix components one-dimensional; therefore it is a division (Pauli) grading, classified by a nondegenerate alternating bicharacter on V. All such forms on $\mathbb{F}_3^4$ are symplectically equivalent. Consequently the

fixed $\mathfrak{sl}_9$ grading is, up to symplectic relabeling and homogeneous rescaling, exactly the tensor two-qutrit Pauli grading studied by Pelantová–Svobodová–Tremblay (`arXiv:quant-ph/0510106`). Thus the eighty oriented E_8 root triangles are the eighty homogeneous nonidentity Pauli degrees, with W33's symplectic form deciding exactly which brackets vanish. The remaining freedom is normalization/phase choice of one-dimensional generators, not the graded Lie-algebra class. No additional physical claim is inferred.

79.63 Explicit Pauli normalizer, Cartan system, A_8^3 glue, and the rank–24 six-qutrit bridge

The order-three E_8 construction now admits a completely explicit matrix-level closure. The lattice-cocycle certificate and its four table shards materialize all eighty oriented A_2 root orbits as the eighty nonzero two-qutrit Pauli degrees, with

$$\Phi(E_v) = \frac{\zeta_{12}^{m_v}}{\sqrt{3}}\big(X^{x_1}Z^{z_1} \otimes X^{x_2}Z^{z_2}\big),$$

and all 2160 nonzero Lie brackets matched. The four shards are checked by `w33_e8_pauli_cocycle_lift_shard_v`

The Weyl-group symmetry closes just as sharply. For the canonical $g = c^{10}$,

$$|C_{W(E_8)}(g)| = 155520, \qquad |N_{W(E_8)}(\langle g\rangle)| = 311040.$$

An explicit involution reverses g, and on the eighty oriented Pauli degrees the kernel is exactly $\langle g\rangle$. Hence

$$C_{W(E_8)}(g)/\langle g\rangle \cong Sp(4,3),$$

of order 51840, while the normalizer induces the order-103680 anti-symplectic extension. The centralizer generators preserve the standard F_3^4 symplectic form and the reversing involution negates it.

Every line of $W(3,3)$ is a two-dimensional Lagrangian subspace of F_3^4. Its four projective points are the eight nonzero oriented Pauli degrees in that subspace. These eight homogeneous matrices commute and are semisimple, and their span has dimension eight, equal to $\operatorname{rank}\mathfrak{sl}_9$. Thus all forty W33 lines lift to Cartan subalgebras of $\mathfrak{sl}_9$. Of the $\binom{40}{2}$ pairs, 240 intersect in dimension two and 540 are disjoint. Joining Cartans with nonzero intersection again gives

$$\operatorname{srg}(40, 12, 2, 4),$$

so the Cartan-intersection graph is another copy of W33.

For the anomaly-free triple, the A_8^3 Niemeier extension couples the three $SU(9)_1$ factors through the discriminant glue

$$C = \langle (1,1,4), (1,4,1), (4,1,1)\rangle \le (\mathbb{Z}_9)^3, \qquad C \cong \mathbb{Z}_9 \times \mathbb{Z}_3.$$

The code has 27 sectors and is totally isotropic and S_3-invariant. Its nonidentity ground weights are eighteen sectors at weight 2 and eight at weight 3; there is no weight-one glue. Hence the weight-one algebra remains $\mathfrak{sl}_9^3$. The first cross-factor fields are simple-current sectors such as

$$9 \otimes 9 \otimes \Lambda^4 9, \qquad h = 2,$$

from the word $(1,1,4)$. The glue constrains the three $SU(9)$ center charges, not the three adjoint F_3^4 Pauli labels, so the two-qutrit gradings remain independent at weight one and are coupled only by higher-weight center-charge sectors.

Finally, the diagonal order-three twist of E_8^3 and the fixed-point-free order-three Leech twist have the same abstract twisted register:

$$E_8^3/(1-g)E_8^3 \cong \Lambda/(1-g)\Lambda \cong F_3^{12},$$

with symplectic geometry $W(11,3)$, conformal ground weight $4/3$, and $729 = 3^6$ ground states. By finite Stone–von Neumann, after a symplectic identification the two ground spaces are equivalent six-qutrit Heisenberg modules. Their distinguished shells are not equivalent. The E_8^3 root shadow is the 120-point union of three orthogonal W33 copies, with outside intersection numbers 66 and 39, and therefore is not tight. The Leech minimal shell is the certified 32760-point 90-tight 2.Suz orbit. Thus the universal object is the six-qutrit register kinematics; the ambient lattice selects the shell and the orbifold extension.

A parallel heterotic audit in Holotrade gives an important boundary. All decorated two-Cartan hinges form one $PSp(4,3)$ orbit, so the hinge incidence of the known net-three witness is not itself a selector. The frozen three-family $SU(5)$ witness does carry the canonical embedding $Y^2 = 5/6$, hence $k_Y = 5/3$, with three chiral tens and net three antifives, but its nine additional $5+\bar{5}$ pairs are only vectorlike after forgetting spectator charges: no weighted state has an exact opposite under the full rank–16 Cartan. Level-one GUT breaking and exotic lifting therefore remain open.

79.64 Suzuki–E_6 incidence, instanton support, and quantum-computation frontiers

The exact 12-dimensional $\mathbf{F}_3$ representation of 2.Suz now exposes a second local geometry inside the 32760-point Leech tight orbit. Fixing one tight-orbit point, the 165 certified full $W(3,3)$ four-spaces through it form

$$\mathrm{srg}(165, 36, 3, 9),$$

the $U_5(2)$ polar graph (equivalently the point graph of $GQ(4,8)$). Its spectrum is

$$36^1 + 3^{120} + (-9)^{44},$$

so the permutation module splits as $165 = (1+44) + 120 = 45 + 120$. This is an exact spectral coincidence with the repository's 45 tritangent and 120 Steiner carriers; no equivariant identification of those modules is asserted without a separate intertwiner. The 36 neighbours of a base four-space split as nine non-isotropic projective lines through the chosen point, four neighbours on each line.

The 1216215 orthogonal three-$W33$ decompositions carry a natural refactorization graph: two frames are adjacent when they share one $W33$ block. Each frame has $3(27-1) = 78$ neighbours, hence the graph has 47432385 edges. The complete local move libraries fixing the blocks generate Suz projectively and 2.Suz in the symplectic lift. They do not generate the full six-qutrit Clifford group:

$$[\mathrm{Sp}(12,3) : 2.\mathrm{Suz}] = 160545074438725411109875 20.$$

Thus refactorization is an exact large Clifford compiler primitive, but it is neither full-Clifford universal nor a non-Clifford resource by itself.

On the cubic side, an individual ζ_{12} phase assigned to one of the 45 E_6 tritangent triples is not invariant under the homogeneous rephasing allowed by the exact E_8 →Pauli cocycle lift. Let R be the 27×45 line–tritangent incidence matrix and N the canonical 45×36 tritangent–double-six matrix. The earlier integral theorem $RN = 3Q$, together with

$$\mathrm{rank}_{\mathbf{F}_3} R = 21, \qquad \mathrm{rank}_{\mathbf{F}_3} N = 14,$$

gives

$$\dim\ker R = 24, \qquad \dim H_1 = 10.$$

Hence single-triangle Pauli-center phases cannot supply magic. If an enriched Pauli/VOA transport exists, its first gauge-invariant global cubic phase target is the ten-dimensional mod-3 homology sector.

A separate totally isotropic $PG(3,3)$ section of the Suzuki orbit meets the tight set in $PG(3,3)\setminus PG(1,3)$. Its 81 internal graph lines identify with $M_2(\mathbf{F}_3)$. Rank-two difference gives

$$\mathrm{srg}(81, 48, 27, 30)$$

with spectrum $48^1 + 3^{48} + (-6)^{32}$. Exactly 18 two-dimensional MRD subspaces occur; their nine affine cosets give 162 distinct nine-line parallel frames, each closing with the deleted line to a ten-line projective spread. These are projective spreads in a totally isotropic four-space and are not the 36 symplectic $W33$ spreads.

The local 165 carrier also reconstructs all 297 lines of $GQ(4,8)$ as five-element cliques, with nine lines through each point and every collinear pair on a unique line. This is the same finite $U_5(2)$ degree-165/297 incidence carrier that admits the classical quaternionic tight-projective-3-design realization in $\mathbf{H}P^4$. The present theorem identifies the finite G-set only; a physical complex/fusion-frame realization remains open.

On the heterotic branch, the Rule–4/Rule–5-safe exotic channels have positive classical $A_2^3/\mathbf{Z}_3$ worldsheet-instanton kernels. Writing

$$K_S(T) = \sum_{m,n\in\mathbf{Z}} e^{-2\pi T(m^2-mn+n^2)}, \qquad K_D(T) = \sum_{m,n\in\mathbf{Z}} e^{-2\pi TQ(m+1/3,n+2/3)},$$

both are strictly positive for $T > 0$. The surviving sextic and nonic aggregate factors are products and positive sums of these kernels, so classical-instanton cancellation does not erase the combined structural rank-nine support. This is still not a numerical low-energy mass matrix: Kahler metrics, singlet VEVs, quantum/OPE normalization and physical-state phases remain to be supplied.

Finally, the exact all-level twining identities

$$Z^{A_8^3}_{(123)} = T_{3C}, \qquad Z^{A_8^3}_{(12)} = T_{2A} + 80$$

do not imply a direct A_8^3 orbifold construction of Moonshine. The factor 3-cycle fixes diagonal $\mathfrak{sl}_9 \subset \mathfrak{sl}_9^3$, of dimension 80, while $V_1^\natural = 0$, and its permutation-twisted vacuum shift is 8/9. The certified $\mathbf{Z}_9$ center/simple-current glue cannot remove those currents because the center is trivial on the adjoint. The Monster match is therefore an exact twining shadow; any literal surgery requires structure beyond factor permutation plus center glue.

The executable certificates are `data/w33_suzuki_local_165_gq48_spectral_bridge.json`, `data/w33_suzuki_refactorization_compiler.json`, `data/w33_e6_tritangent_pauli_holonomy_frontier.j` `data/w33_isotropic36_rank_metric_m2.json`, `data/w33_suzuki_165_quaternionic_design_shadow.json`, and `data/w33_a8cubed_monster_orbifold_surgery_obstruction.json`. The heterotic instanton certificate lives in the companion Holotrade repository as `data/w33_exotic_worldsheet_instanton_kernel.j`

79.65 The local $45 + 120$ split, cubic adjoint holonomy, exotic rank, and the non-Clifford boundary

The local $U_5(2)$ degree-165 carrier admits an exact restriction to the ATLAS maximal subgroup $3 \times U_4(2)$ with orbits $45 + 120$. The 45-orbit small orbital is $\mathrm{srg}(45, 12, 3, 3)$ and is explicitly

graph-isomorphic to the cubic-surface tritangent intersection graph. The 120 orbit is a near twin of the classical Steiner trihedral-pair action: its unordered-pair orbit sizes are $120, 1620, 2160, 3240$ and its central C_3 gives forty three-element blocks. However, the 2160 relation descends to an $\mathrm{srg}(40, 12, 2, 4)$ quotient with

$$\mathrm{rank}_{\mathbf{F}_3}(A + I) = 11,$$

so it is the standard $W(3, 3)$ point action. Pass 4870 proves the classical Steiner quotient is instead $Q(4, 3)$ with rank 15. Hence only the 45 half is the old cubic carrier; the 120 half is a distinct Steiner-twin cover.

The ten-dimensional global tritangent-holonomy space from the mod-3 cubic complex is now identified representation-theoretically. On common exact $PSp(4, 3)$ generators the simultaneous intertwiner equations between

$$H_1 = \ker(R : \mathbf{F}_3^{45} \to \mathbf{F}_3^{27}) / \operatorname{im}(N : \mathbf{F}_3^{36} \to \mathbf{F}_3^{45})$$

and $\Lambda^2(\mathbf{F}_3^5)$ have a one-dimensional Hom space, and the unique nonzero intertwiner has rank ten. Therefore

$$\boxed{H_1 \simeq \Lambda^2(\mathbf{F}_3^5) \simeq \mathfrak{so}_5(\mathbf{F}_3) \simeq \mathfrak{sp}_4(\mathbf{F}_3).}$$

Thus the ten linear cubic holonomy channels are the finite symplectic adjoint/controller module; membership in this space is not by itself a non-Clifford or magic witness.

On the heterotic branch, the positive-instanton $K_{9,12}$ exotic support contains an explicit rank-nine specialization. Choosing allowed dimensionless coefficients $C_{rc} = (r + 1)^c$ gives a first-nine-column Vandermonde minor

$$\det C = 5056584744960000 \neq 0.$$

Multiplication by the certified positive sextic/nonic instanton factors preserves rank. This proves that rank nine occurs on a nonempty Zariski-open region of the allowed coefficient/VEV space. It does not select a physical vacuum: D/F-flat singlet VEVs, canonical field metrics and complete physical-state/OPE phases remain open inputs.

The local 165 geometry also has a canonical complex six-qutrit operator-space shadow. Associate to each full $W33$ the Pauli Hilbert–Schmidt subspace generated by its 80 nonzero oriented degrees, and remove the common two-operator $\{\pm p\}$ core. The resulting projections have rank 78 and normalized overlap $1/13$ on adjacent vertices and 0 on nonadjacent vertices. Hence their normalized projection Gram matrix is

$$G = I + \frac{1}{13} A_{165},$$

with spectrum

$$(49/13)^1 + (16/13)^{120} + (4/13)^{44}.$$

The second projection-frame potential is $33825/169$, so this is a two-distance complex fusion-frame shadow, but not a tight frame.

Finally, the currently certified internal candidates do not yet provide a non-Clifford endomorphism. The refactorization moves generate $2.\mathrm{Suz} < Sp(12, 3)$, the ten cubic channels are $\mathfrak{sp}_4(\mathbf{F}_3)$ adjoint data, and the A_8^3 $\mathbf{Z}_9$ center acts on $\Lambda^k(9)$ by a scalar ninth root. A scalar ninth root conjugates every Pauli trivially and is not the qutrit third-level phase gate

$$T = \mathrm{diag}(1, \xi, \xi^{-1}), \qquad \xi^9 = 1,$$

for which $T^3 = Z$ but TXT^{-1} is not Pauli. The first A_8^3 weight-two simple-current sectors are inter-sector fields, not certified endomorphisms of the fixed six-qutrit ground register. The open

universality datum is therefore an explicit sector-return non-Clifford intertwiner or a certified magic-state injection, in agreement with the blueprint's existing M_{36} firewall.

Executable certificates are `data/w33_u52_165_e6_45_120_split.json`, `data/w33_e6_cubic_h1_is_sp4_adj`
`data/w33_suzuki_165_complex_pauli_fusion_shadow.json`, and `data/w33_nonclifford_extension_search.`
The rank-nine benchmark is in the companion Holotrade repository as `data/w33_exotic_benchmark_mass_matrix`

79.66 Sector return, dual covers, protected singlet directions, and the first nonlinear adjoint invariant

The A_8^3 Niemeier glue code $C \le (\mathbb{Z}/9)^3$ has order 27 and conformal-weight census $0^1 + 2^{18} + 3^8$. Hence its discriminant quadratic form $q(c) = h_c \bmod 1$ vanishes identically, and so does the simple-current monodromy bicharacter

$$b(c,d) = q(c+d) - q(c) - q(d).$$

The 26 nonzero sectors therefore form 13 inverse pairs $c, -c$ with bosonic/local return $V_c V_{-c} \to V_0$. The abelian glue fusion data cannot by themselves supply a qutrit-T-like ninth-root exchange phase. Moreover, on the irreducible 729-dimensional 3^{1+12} Heisenberg ground module, any return endomorphism commuting with the full Heisenberg action is scalar. A non-Clifford return, if present, must therefore use noncentral descendant/OPE structure not encoded by the simple-current group alone.

The Suzuki 120-cover and the classical Steiner 120-cover are now separated exactly. Their forty three-element fibers quotient respectively to the standard $W(3,3)$ point graph and the dual $Q(4,3)$ line graph. Both rational degree-40 permutation modules are $\mathbf{1} \oplus V_{24} \oplus V_{15}$, while literal point–line incidence Z obeys

$$ZZ^T = 4I + A_{\mathrm{pt}}, \qquad Z^T Z = 4I + A_{\mathrm{line}}, \qquad \operatorname{rank} Z = 25.$$

Thus incidence transmits exactly $\mathbf{1} \oplus V_{24}$ and annihilates the two distinct 15-dimensional dark constituents. The modular separator

$$\operatorname{rank}_{\mathbf{F}_3}(A_{\mathrm{pt}} + I) = 11, \qquad \operatorname{rank}_{\mathbf{F}_3}(A_{\mathrm{line}} + I) = 15$$

is a characteristic-three extension effect, not a new four-dimensional characteristic-zero module.

On the heterotic branch, the frozen SU(5) witness has 24 untwisted and 22 twisted selected-SU(5) singlet momentum types. Exact sixteen-dimensional lattice-momentum enumeration finds 36 neutral cubics and exactly 16 primitive neutral quartics, all of type

$$U\, T_0 T_1 T_2.$$

For every one of these sixteen supports, no neutral cubic contains two support fields, no dangerous neutral term occurs at degrees $5, 6, 7$, the unique degree-8 self-square is forbidden by the $\mathbb{Z}_3$ R rule, and degrees $9, 10, 11$ are empty again. The first gauge-plus-R-admissible self-lift is the degree-12 cube, with three untwisted copies distributed one per complex plane. Hence these are exact lattice-neutral zero-FI D-flat candidates protected against gauge-plus-R F-terms through order eleven. The anomalous-U(1) Fayet–Iliopoulos shift and the degree-12 space-group/Rule–4/Rule–5 amplitude remain open.

For the local 165 complex Pauli fusion shadow, the normalized projection Gram matrix

$$G = I + \frac{1}{13} A_{165}$$

has the exact inverse

$$\boxed{G^{-1} = \frac{91}{64} I - \frac{13}{64} A_{165} + \frac{117}{3136} J}.$$

Its gains on the constant, 120-dimensional, and 44-dimensional SRG eigenspaces are respectively 49/13, 16/13, and 4/13. Thus the canonical dual is a fixed rational combination of self, nearest-neighbour sum and global mean. Every principal subframe is positive definite and has condition number at most 49/4 by interlacing. Since the full Gram matrix is nonsingular, this is robust surviving-subframe conditioning rather than exact erasure recovery of the deleted coefficient.

Finally, the ten global cubic-holonomy coordinates, already identified with the adjoint $\mathfrak{sp}_4(\mathbf{F}_3)$, have invariant-polynomial dimensions

$$\dim \mathbf{F}_3[H_1]_d^{Sp_4(3)} = (0, 1, 0, 3), \qquad d = 1, 2, 3, 4.$$

There is no invariant cubic. The quadratic is $q_2(X) = \operatorname{tr}(X^2)$. A formal quartic basis is q_2^2, $\det X$, and the Frobenius lift q_F; on $\mathbf{F}_3$-points $q_F = 2q_2$, so $\det X$ is the first genuinely new nonlinear pointwise invariant. Exhausting all $3^{10} = 59049$ adjoint elements realizes all nine pairs $(q_2, \det) \in \mathbf{F}_3^2$. Therefore a phase $\omega^{r \det X}$, $r = 1, 2$, is a concrete quartic magic candidate only after an explicit coupling maps the adjoint controller variable into a basis-dependent phase on the six-qutrit register; no such gate is asserted here.

The executable certificates are `data/w33_a8cubed_sector_return_monodromy.json`, `data/w33_steiner_twi` `data/w33_suzuki_165_fusion_frame_decoder.json`, and `data/w33_h1_adjoint_nonlinear_invariants.json` The protected-singlet certificate lives in the companion Holotrade repository as `data/w33_su5_singlet_flat_dire`

79.67 The quartic determinant is a mod–3 matroid basis count, and every building apartment has phase one

The preceding controller analysis left one exact finite candidate for a genuinely nonquadratic phase: for a collection of Pauli directions $V = [v_1 \ \cdots \ v_m] \in \mathbb{F}_3^{4 \times m}$, form $S = VV^T$ and $X = SJ$, where J is the standard symplectic form. The single-three-label weight–two operator has $\operatorname{rank} X \leq 3$ and hence zero determinant, while two operators can supply four independent directions. The following observation makes the latter statement coordinate free.

Theorem 79.2 (Determinant–Tutte basis law)**.** *Let $M(V)$ be the column matroid represented by V over $\mathbb{F}_3$. Then*

$$\boxed{\det((VV^T)J) = T_{M(V)}(1, 1) \pmod 3.}$$

Equivalently, the determinant is the number of rank–four column bases modulo three. In particular, with exactly four projective directions the determinant is nonzero iff they span $\mathbb{F}_3^4$, and then it equals 1.

Indeed, Cauchy–Binet gives

$$\det(VV^T) = \sum_{|I|=4} \det(V_I)^2.$$

Every nonzero square in $\mathbb{F}_3$ is 1, and $\det J = 1$; the sum therefore counts the bases of $M(V)$ modulo 3. Since $T_M(1, 1)$ is the standard Tutte basis evaluation, the proposed synchronized-sector phase can be written

$$\omega^{r \det X} = \omega^{r T_M(1,1)}.$$

Thus its exponent also inherits deletion–contraction modulo three.

The exhaustive $PG(3,3)$ census is

$$\binom{40}{4} = 91{,}390 = 63{,}180 + 28{,}210,$$

with $63{,}180 = |GL(4,3)|/(2^4 4!)$ projective bases and 28,210 dependent quadruples. For all 658,008 five-subsets the numbers of bases are distributed as

$$0^{51,480}, \qquad 3^{252,720}, \qquad 4^{252,720}, \qquad 5^{101,088},$$

so the determinant values occur with multiplicities

$$\boxed{0^{304,200}, \qquad 1^{252,720}, \qquad 2^{101,088}.}$$

Theorem 79.3 (Apartment determinant bridge)**.** *Every one of the* 1620 *induced W33 quadrangles/apartments is a projective basis of* $\mathbb{F}_3^4$ *and satisfies*

$$\boxed{\det((VV^T)J) = 1.}$$

Each such point quadrangle lifts uniquely to one alternating point–line Levi 8*-cycle. Hence the determinant candidate is uniform on the complete apartment set: its value is* ω^r *in central-character sector* r*.*

For a cyclic apartment $p_1 - p_2 - p_3 - p_4 - p_1$, adjacent symplectic pairings vanish and the two opposite pairings $a = \langle p_1, p_3\rangle$, $b = \langle p_2, p_4\rangle$ are nonzero. Therefore

$$\det(V^T J V) = (ab)^2 = 1$$

in $\mathbb{F}_3$, proving directly that the four points form a basis. This statement uses the repository's corrected Pass–4474 semantics: the 1620 *induced* quadrangles are the apartments, while the separate 120 simple four-cycles lying inside geometric K_4 lines are not included.

Evidence boundary. The identities and both exhaustive censuses are regenerated by `analysis/w33_h1_det_matroid_basis_phase.py` and `analysis/w33_h1_det_apartment_phase_bridge.py`, with frozen JSON certificates in `data/`. They prove an exact finite combinatorial observable and its apartment support. They do *not* prove that the A_8^3 VOA OPE couples through $\det X$, that the coefficient is independently addressable, or that a physical Holonet implements an apartment phase gate.

79.68 Affine-return control, vacuum-profile rank, determinant depth, decoder distance, and the quartic dark bridge

The A_8^3 order-three construction carries a certified $9 \times 9 \times 9 = 729$ ground register with local current algebra $\mathfrak{sl}_9^3$. For a nontrivial glue word such as $(1,1,4)$, the lattice-VOA return OPE $V_\lambda V_{-\lambda}$ has quadratic descendant $(J_\lambda)^2/2$ and therefore nonzero cross terms on all three factor pairs. Conditional on independent continuous control of the local $\mathfrak{sl}_9$ zero modes and at least one such cross Hamiltonian on a connected block graph, simplicity of $\mathfrak{sl}_9$ gives the full dynamical algebra

$$\boxed{\mathfrak{sl}_{729}}, \qquad \dim = 729^2 - 1 = 531440.$$

This is a controllability theorem for the certified operator algebra, not a claim that the present hardware independently addresses those Hamiltonians.

On the heterotic branch, the frozen $SU(5)$ witness has $\operatorname{Tr} Q_A = -72$ in the convention $Q_A = P_9/6$. Its two minimal FI-cancelling untwisted bilinears are U_0U_1 and U_2U_3, each of total anomalous charge $+2$, and these are exactly the untwisted pairs entering the sextic exotic-mass channels. Thus FI cancellation and exotic lifting are compatible at charge level. Fixed-point resolution is nevertheless decisive. The mass matrix factorizes as

$$M(f,c) = \sum_s A_s(f) B_s(c),$$

through four twisted-singlet pair profiles. Translation-invariant twisted VEVs give rank one, one-point support gives rank at most four, and the diagonal profile used by the allowed degree-twelve quartic cube also gives rank one. Rank nine is reachable only for sufficiently nonuniform fixed-point condensates. Consequently the old unconstrained Vandermonde rank-nine matrix is an algebraic existence witness, not a physical-vacuum certificate.

The ten global cubic-holonomy variables form the adjoint $\mathfrak{sp}_4(\mathbf{F}_3)$, whose first new pointwise nonlinear invariant is $\det X$. A single synchronized weight-two operator supplies only three Pauli directions and all equivariant moment maps have rank at most three, hence $\det X = 0$. Two insertions are sufficient: two copies of $c = (1,1,4)$ fuse to the weight-two sector $(2,2,8)$ of synchronized central character $r = 2$, and Pauli labels (e_1,e_2,e_3) and $(e_4,0,0)$ give

$$S = I_4, \qquad X = SJ = J, \qquad \det X = 1,$$

so the finite fusion layer admits the candidate phase $\omega^{r \det X} = \omega^2$. This is a kinematic/equivariant witness, not yet an evaluated nonlinear VOA phase coupling.

The 165 local Suzuki/W33 encodings and 297 five-point lines of $GQ(4,8)$ also give an exact redundant-readout theorem. A peeling stopping set S induces degree at least nine, so $2e(S) \geq 9|S|$. Since the point graph is $\operatorname{srg}(165,36,3,9)$ with largest nontrivial eigenvalue 3, the Rayleigh bound gives

$$2e(S) \leq 3m + \frac{m^2}{5}, \qquad m = |S|.$$

Hence $m \geq 30$. An explicit Hermitian-model 30-set meets the 297 lines as $0^{162} + 2^{135}$, proving

$$\boxed{d_{\mathrm{stop}} = 30}.$$

Thus every pattern of at most 29 erased point channels is exactly peel-decodable from the surviving point values plus all line-sum measurements; the statement concerns peeling and does not preclude a stronger global solver at weight 30.

Finally, the inequivalent 15-dimensional dark constituents of the W33 point and line actions remain disconnected at linear, quadratic and cubic degree, including under the certified PGSp outer twist. Exact full-group characters give

$$\operatorname{Hom}_{PSp}(\operatorname{Sym}^2 V_{15}^{\mathrm{line}}, V_{15}^{\mathrm{point}}) = 0, \qquad \operatorname{Hom}_{PSp}(\operatorname{Sym}^3 V_{15}^{\mathrm{line}}, V_{15}^{\mathrm{point}}) = 0,$$

but

$$\boxed{\dim \operatorname{Hom}_{PSp}(\operatorname{Sym}^4 V_{15}^{\mathrm{line}}, V_{15}^{\mathrm{point}}) = 1}.$$

The first ordinary equivariant nonlinear point–line transceiver is therefore quartic and unique up to scale. A preferred local polynomial and a physical/VOA realization remain open.

The executable certificates are `data/w33_a8cubed_affine_return_universality.json`, `data/w33_h1_det_t` `data/w33_suzuki_gq48_stopping_distance.json`, and `data/w33_dark15_first_nonlinear_bridge.json`. The heterotic vacuum-profile correction is cross-certified in the companion Holotrade repository by `data/w33_su5_fi_degree12_flatness.json`, `data/w33_exotic_mass_rank_by_condensate.json`, and `data/w33_fi_exotic_condensate_compatibility.json`.

79.69 The quartic determinant needs a geometry bit: six projective-basis orbits and a minimal two-trit classifier

The determinant/matroid bridge gives a quartic invariant of a finite set of Pauli projective directions, but an exact census shows a sharp limitation at support size four. Let $B = \{v_0, v_1, v_2, v_3\} \subset \mathrm{PG}(3,3)$ be a projective basis. Exhausting all $\binom{40}{4} = 91390$ four-point subsets gives 63180 bases and 28210 dependent sets. The inner group $\mathrm{PSp}(4,3)$ has exactly six orbits on the bases. More strongly, the induced $W(3,3)$ orthogonality graph on the four points classifies the orbit completely:

orthogonality graph	orbit size	$\lvert\mathrm{Stab}_{\mathrm{PSp}}(B)\rvert$
C_4	1620	16
$2K_2$	3240	8
$4K_1$	6480	4
$K_2 + 2K_1$	12960	2
P_4	12960	2
$P_3 + K_1$	25920	1

The C_4 orbit is exactly the generalized-quadrangle apartment shell; its size 1620 agrees with the point shadows of the 1620 minimum-weight Levi 8-cycle apartments already certified in the apartment-code arc. Thus apartments comprise exactly 1/39 of all projective bases.

There is a compact projective classifier. Write

$$z_{ij} = 1 - \langle v_i, v_j \rangle^2 \in \mathbb{F}_3.$$

Because every nonzero scalar of $\mathbb{F}_3$ has square one, z_{ij} is precisely the orthogonality indicator. Define

$$E = \sum_{i<j} z_{ij}, \qquad W = \sum_{i} \sum_{\substack{j<k \\ j,k\neq i}} z_{ij} z_{ik} \pmod 3.$$

The six orbit values are respectively

$$C_4 : (1,1), \quad P_4 : (0,2), \quad P_3{+}K_1 : (2,1), \quad 2K_2 : (2,0), \quad K_2{+}2K_1 : (1,0), \quad 4K_1 : (0,0).$$

Hence (E, W) is a complete two-trit orbit classifier. It is minimal in the literal information sense: one trit has only three values and cannot distinguish six orbits, while the displayed pair distinguishes all six.

The same computation also supplies an important no-go. If V is the 4×4 matrix of any projective basis, then the determinant/matroid quartic is

$$\det(VV^T J) = \det(V)^2 \det J = 1 \in \mathbb{F}_3.$$

Thus the four-direction determinant phase takes the same value on every one of the six basis orbits and cannot by itself select the apartment geometry. On an ordered apartment $a - b - c - d - a$, however, the symplectic Gram matrix has only the two diagonal pairings nonzero and

$$\mathrm{Pf}(G) = -\langle a, c \rangle \langle b, d \rangle, \qquad \mathrm{Pf}(G)^2 = 1.$$

This makes the apartment determinant-one statement incidence-theoretic while also showing why a second observable is required to distinguish the apartment from other bases.

Evidence boundary. The exhaustive witness is `analysis/w33_projective_basis_orbits_two_trit_classif` with frozen certificate `data/w33_projective_basis_orbits_two_trit_classifier.json`. This is exact finite geometry and representation theory. The two trits are canonical discrete projective observables; no Hamiltonian addressability, optical implementation, or physical non-Clifford gate follows from the classification alone.

79.70 The Suzuki block stabilizer: symplectic double cover upstairs, inner projective action downstairs

The full-W33 incidence tower gives a 135135-element 2.Suz orbit of nondegenerate 4-spaces $U \cong W(3,3)$ inside the twelve-dimensional symplectic carrier, with 27 complementary three-W33 decompositions through each fixed U. The latter carry the Schläfli/cubic-surface graph $\mathrm{SRG}(27,10,1,5)$. The next question is not whether that graph *admits* the usual E_6 symmetry, but which part of that symmetry is actually induced by the ambient Suzuki action.

Using the vendored ATLAS matrices, the orbit-stabilizer order is

$$|\operatorname{Stab}_{2.\mathrm{Suz}}(U)| = \frac{896690995200}{135135} = \boxed{6635520}.$$

A Schreier transversal over the complete orbit shows that restriction to the four-dimensional block is surjective onto

$$\boxed{\mathrm{Sp}(4,3)}, \qquad |\mathrm{Sp}(4,3)| = 51840,$$

with kernel of order

$$\boxed{128 = 2^7}.$$

Thus the embedded block sees the full symplectic double cover.

Projectivising changes the answer. The action on the 27 complementary decompositions has image

$$\boxed{\mathrm{PSp}(4,3)}, \qquad |\mathrm{PSp}(4,3)| = 25920,$$

and kernel

$$\boxed{256 = 2^8}.$$

The computation is exhaustive rather than sampled. A five-vertex base for the full 51840-element automorphism group of the local Schläfli graph is fixed; all $270270 = 2 \cdot 135135$ Schreier generators are then classified by their images on that base. Every generator lies in the inner 25920-element projective subgroup. No outer-coset generator occurs.

Extension firewall. Two order-51840 groups occur here and they must not be identified. The linear block action is the central double cover $\mathrm{Sp}(4,3) \to \mathrm{PSp}(4,3)$. The full cubic-surface Weyl symmetry is the different extension $W(E_6) \cong \mathrm{PSp}(4,3){:}2$. The ambient 2.Suz action realizes the former upstairs and only the inner $\mathrm{PSp}(4,3)$ action on the projective 27-carrier. The outer E_6 involution is absent from this induced action.

This sharpens the earlier local-E_6 statement. The 27 decompositions still form the exact cubic-surface incidence carrier, whose full graph automorphism group is the Weyl group of type E_6; what is new is the actual subgroup selected by the Suzuki embedding. Standard cubic-surface geometry identifies the automorphism group of the 27-line incidence graph with $W(E_6)$, while the repository computation determines the induced subgroup and both kernels.

The executable certificate is `analysis/w33_suzuki_w33_stabilizer_projective_quotient.py`, with frozen output `data/w33_suzuki_w33_stabilizer_projective_quotient.json`. The statement is finite group theory only: it does not make the absent outer involution into a physical gate or assert that any enlargement of the Suzuki action is dynamically available.

79.71 The local cubic carrier sees $PSp(4,3)$ in 2.Suz and the full $W(E_6)$ in 2.Suz:2

The 32760-point Suzuki/Leech tight shell contains a transitive family of 135135 full nondegenerate $W(3,3)$ subspaces. Fix one such subspace U. Its 54 orthogonal full-$W33$ partners pair by symplectic complement into 27 unordered decompositions

$$\mathbf{F}_3^{12} = U \perp V \perp V^{\perp(U\oplus V)}.$$

The parent incidence certificate proves that these 27 decompositions carry $\mathrm{SRG}(27,10,1,5)$; its complement is the Schläfli graph of the 27 lines on a smooth cubic surface.

The exhaustive stabilizer computation already separates two order-51840 extensions which must not be conflated. On the four-dimensional block itself, $\mathrm{Stab}_{2.\mathrm{Suz}}(U)$ restricts onto the symplectic double cover $\mathrm{Sp}(4,3)$, order 51840, with kernel 2^7. After projectivizing to the local 27 decompositions, however, all 270270 Schreier generators lie in the inner subgroup

$$\boxed{\mathrm{PSp}(4,3) \cong U_4(2)}, \qquad |\mathrm{PSp}(4,3)| = 25920,$$

with projective kernel 2^8. The outer Weyl coset is genuinely absent from 2.Suz.

The new result constructs that missing coset explicitly. We vendor the ATLAS 12-dimensional $\mathbf{F}_3$ representation of 2.Suz:2. Its second standard generator D is literally the old Suzuki generator B. The new generator C satisfies

$$CJC^T = -J,$$

so it is a symplectic similitude of multiplier -1 rather than an element of the old symplectic image. For the chosen block U, direct computation finds that $C(U)$ is also reached from U by the old-group word

$$\boxed{\texttt{BABABABABABBABABABABBABABA}}$$

of length 26. If T is the matrix of that word, then

$$h = CT^{-1}$$

fixes U projectively while retaining multiplier -1. Thus h is an explicit outer-coset block-stabilizer element, not merely an order argument.

The published ATLAS subgroup structure closes the proof. The degree-135135 Suzuki point stabilizer is

$$2^{1+6}.U_4(2),$$

whereas the corresponding stabilizer in the outer extension is

$$2^{1+6}.U_4(2).2,$$

of order

$$6635520 = 128 \cdot 51840.$$

The normal 2-core is invisible on the transitive odd 27-set: its equal-size orbits are powers of two dividing 27, hence singletons. The inner $U_4(2)$ socle is already faithful, and the explicit multiplier--1 element supplies the nontrivial outer coset. Therefore

$$\boxed{\mathrm{Im}_{2.\mathrm{Suz}:2}(27) = U_4(2){:}2 \cong W(E_6), \qquad |W(E_6)| = 51840.}$$

This is exactly the classical automorphism group of the Schläfli/cubic-surface 27-line graph. The factor of two missing inside 2.Suz is therefore restored constructively by the Suzuki outer automorphism.

The executable/frozen artifacts are `analysis/w33_suzuki_w33_stabilizer_projective_quotient.py`, `data/w33_suzuki_w33_stabilizer_projective_quotient.json`, `analysis/w33_suz_outer_completes_local_` and `data/w33_suz_outer_completes_local_e6_weyl.json`. The ATLAS outer matrices are vendored as `data/atlas/2Suzd2G1-f3r12aB0.m1` and `data/atlas/2Suzd2G1-f3r12aB0.m2`.

Evidence boundary. The matrix similitude, transporter word, block stabilization, and inner Suzuki projective action are exact finite computations. The abstract names of the point stabilizers and the classical identification of the full cubic-surface graph automorphism group with $W(E_6)$ are published finite-group/geometric inputs. No physical E_6 gauge symmetry, continuum unification mechanism, or hardware availability of the outer similitude is inferred.

79.72 The hidden E_6 binary carrier inside the Suzuki W33 kernel

The stabilizer calculation identifies the linear kernel of one embedded W33 block as the extraspecial minus group

$$K_{\mathrm{lin}} \cong 2_-^{1+6}, \qquad |K_{\mathrm{lin}}| = 128.$$

For an extraspecial 2-group the quotient by the center carries the canonical quadratic form $q(\bar{x}) = x^2 \in Z(K) \cong \mathbf{F}_2$. Minus type therefore gives

$$K_{\mathrm{lin}}/Z(K_{\mathrm{lin}}) \cong \mathbf{F}_2^6$$

with a nondegenerate minus quadratic form. Its 63 nonzero vectors split as

$$\boxed{63 = 27 + 36},$$

with 27 nonzero singular vectors and 36 nonsingular vectors.

This is not only a count. The 27 singular vectors form the elliptic quadric $Q^-(5,2) = GQ(2,4)$; polar orthogonality gives

$$\boxed{\mathrm{SRG}(27, 10, 1, 5)}.$$

The executable certificate constructs this graph and an explicit vertex-by-vertex isomorphism to the repository's independent W33 center-quad quotient

$$90 \longrightarrow 45 \longrightarrow 27,$$

whose 27 quotient lines carry the same cubic-surface incidence graph. Thus the new Suzuki stabilizer kernel itself contains a canonical binary realization of the old W33$\to E_6$ 27-line carrier.

The complementary 36 nonsingular vectors close just as strongly. The Pass4992 common reconstruction builds the repository's five $\mathrm{PSp}(4,3)$ generators from orthogonal symmetries of this same $Q^-(5,2)$ model. Propagating those identical generator words on the nonsingular vectors and on the 36 Schläfli double-sixes yields *exactly one* equivariant bijection. It also intertwines the additional orthogonal symmetry that enlarges the inner group to the full Weyl action. Hence the identification

is $W(E_6)$-equivariant, not merely a match of orbit sizes:

$$\boxed{\begin{array}{c}\text{36 nonsingular kernel vectors}\\ \updownarrow\\ \text{36 Schläfli double-sixes}\\ \updownarrow\\ \text{36 W33 spreads}\\ \updownarrow\\ \text{36 doily complements}\\ \updownarrow\\ \text{36 signed Pfaffian sections of } C_{E_6}.\end{array}}$$

The inner point stabilizer has order $25920/36 = 720$, while the full orthogonal/Weyl stabilizer has order $51840/36 = 1440$, reproducing the classical double-six stabilizer.

Most importantly, the extension puzzle is now structural. The full automorphism group of the minus quadratic quotient is

$$\mathrm{Out}(2_-^{1+6}) \cong O_6^-(2) \cong W(E_6),$$

whereas the Suzuki W33 block stabilizer acts through only the index-two subgroup

$$\Omega_6^-(2) \cong U_4(2) \cong \mathrm{PSp}(4,3).$$

So the "missing" outer E_6 involution is not mysterious: it is an intrinsic automorphism of the extraspecial kernel that is not induced by conjugation from the ambient Suzuki block stabilizer. This explains simultaneously why the local 27-carrier admits the full Weyl symmetry and why the actual 2.Suz action sees only the inner half.

The executable artifacts are `analysis/w33_suzuki_w33_kernel_structure_reconciliation.py`, `analysis/w33_suzuki_kernel_e6_quadratic_shell_bridge.py`, and `analysis/w33_suzuki_kernel_e6_36_ob` with frozen JSON certificates of the same names under `data/`. These are finite-group and finite- geometry statements; no physical implementation of the binary shell or missing outer automorphism is inferred.

79.73 Weyl involutions reconstruct the 36 double-sixes, the 45 tritangents, and their cross-incidence

There is a second, independent route to the cubic-surface 27–36–45 triangle that does not start from the W33 apartment/code carrier. Work in the Picard lattice of a smooth cubic surface with basis $H, E_1, \ldots, E_6$ and intersection form $\mathrm{diag}(1, -1^6)$. The 27 (-1)-curve classes are

$$E_i, \qquad H - E_i - E_j, \qquad 2H - \sum_{j \neq i} E_j.$$

The six simple root reflections generate the full Weyl permutation group

$$|W(E_6)| = 51840,$$

and the sign kernel has order 25920.

Exhaustive enumeration of the 891 nonidentity involutions gives the four class sizes

$$\boxed{36,\ 270,\ 540,\ 45},$$

corresponding to involution degrees $1, 2, 3, 4$. The simultaneous fixed-carrier fingerprints on the $(27, 36, 45)$ objects are

d	$\lvert C_d\rvert$	$\#\,\mathrm{Fix}(27)$	$\#\,\mathrm{Fix}(45)$	$\#\,\mathrm{Fix}(36)$
1	36	15	15	16
2	270	7	5	8
3	540	3	7	4
4	45	3	13	12.

The degree census is classical; the objectwise identifications below are the new executable reconstruction.

The 36 reflection class is literally the double-six carrier. For every root reflection r, the 12 cubic lines moved by r are exactly the support of one double-six. The 36 moved supports are distinct and exhaust the 36 double-sixes. Thus

$$\boxed{\{\text{reflections of } W(E_6)\} \longleftrightarrow \{\text{double-sixes}\}}.$$

Equivalently, the classical root-pair/double-six correspondence is visible directly in the 27-line permutation action, without importing labels.

The 540 odd degree-three involutions form a 12-sheeted cover of the 45 tritangents. Every degree-three involution fixes exactly three of the 27 lines pointwise, and those three lines form a tritangent. Conversely every tritangent occurs as the fixed triple of exactly twelve such involutions. Hence

$$\boxed{540 = 45 \cdot 12}.$$

Write F_T for the twelve degree-three involutions above a tritangent T, and let r_D be the reflection corresponding to a double-six D.

The group law reconstructs the 45×36 incidence matrix. A direct census gives the sharp dichotomy

$$|T \cap D| = 0 \quad \Longleftrightarrow \quad \#\{w \in F_T : wr_D = r_D w\} = 4,$$

while

$$|T \cap D| = 2 \quad \Longleftrightarrow \quad \#\{w \in F_T : wr_D = r_D w\} = 0.$$

Therefore the commutation relation internal to $W(E_6)$ alone reconstructs the tritangent/double-six cross-incidence. The exact census is

$$\boxed{0^{540} + 2^{1080}}, \qquad 45 \cdot 36 = 540 + 1080.$$

This is precisely the cross-incidence independently reconstructed in Pass 4659 from the W33 internal 27/36 carrier, where $T^{\mathsf{T}} R = 2(J - D)$ and the same $0^{540}, 2^{1080}$ intersection census appears. Thus the W33/code route and the classical Weyl-involution route meet objectwise, not merely numerically.

The executable certificate is `analysis/w33_e6_involution_reconstructs_double_six_tritangent.py`, with frozen output `data/w33_e6_involution_reconstructs_double_six_tritangent.json`. The classical involution-degree census agrees with Carter's Weyl-group classification and with the cubic-surface involution discussion of Dolgachev–Duncan. The finite theorem does not assert a physical E_6 gauge field; transport to the W33/Suzuki carriers uses the separately certified 27–36–45 equivariant intertwiners.

79.74 The full E_6 involution ladder closes on the cubic 36–45 incidence geometry

The preceding involution reconstruction can be sharpened so that all four nontrivial involution degrees of $W(E_6)$ acquire direct cubic-surface meaning. The degree-one class is the 36 reflections, already identified objectwise with the 36 double-sixes through their moved twelve-line supports.

For two distinct double-sixes D_1, D_2, their supports meet in either four or six cubic lines, with exact census

$$\binom{36}{2} = 270 + 360.$$

The corresponding reflections commute if and only if the overlap is four. Their 270 products are distinct and exhaust the degree-two involution class. Thus

$$\boxed{\{d = 2 \text{ involutions}\} \longleftrightarrow \{\text{syzygetic double-six pairs}\}}, \qquad |D_1 \cap D_2| = 4.$$

The remaining 360 pairs have six-line overlap and are noncommuting.

At the opposite end, each degree-four involution fixes exactly three cubic lines pointwise, those three lines form a tritangent, and the resulting map is a bijection

$$\boxed{\{d = 4 \text{ involutions}\} \longleftrightarrow \{45 \text{ tritangents}\}}.$$

Write q_T for the unique degree-four involution attached to tritangent T.

Now let w be one of the 540 degree-three involutions. Its three fixed lines form a tritangent T, and w commutes with q_T. The product

$$r = wq_T$$

is a degree-one reflection. If D is the double-six moved by r, then

$$T \cap D = \varnothing.$$

For each fixed T, the twelve degree-three involutions above T map to the twelve double-sixes disjoint from T, each exactly once. Globally this gives the canonical bijection

$$\boxed{\{d = 3 \text{ involutions}\} \longleftrightarrow \{(T, D) : T \text{ tritangent},\ D \text{ double-six},\ T \cap D = \varnothing\}},$$

and therefore

$$\boxed{540 = 45 \cdot 12}.$$

So the four involution degrees organize the cubic geometry as

$$36 \ \longrightarrow\ 270 \ \longrightarrow\ 540 \ \longrightarrow\ 45,$$

with carriers double-sixes, syzygetic double-six pairs, disjoint tritangent–double-six flags, and tritangents respectively. The complementary 1080 tritangent/double-six pairs have two-line intersection, giving again the Pass 4659 census

$$45 \cdot 36 = 540 + 1080.$$

The executable certificate is `analysis/w33_e6_involution_ladder_flags.py`, with frozen output `data/w33_e6_involution_ladder_flags.json`. This is an exact finite $W(E_6)$/cubic-surface theorem. Transport to the W33/Suzuki carriers uses the separately certified equivariant bridges and does not by itself assert a physical E_6 gauge symmetry.

79.75 The Suzuki outer involution is determinant-reversing on the six-qutrit Heisenberg carrier

The six-qutrit carrier has extraspecial Heisenberg group

$$H = 3^{1+12}, \qquad H/Z(H) \cong \mathbb{F}_3^{12},$$

with two faithful irreducible Schrödinger sectors

$$\rho_r : H \to U(729), \qquad r \in \{1, 2\}, \qquad \rho_r(z) = \omega^r I.$$

The constructive Suzuki outer completion supplies a ternary symplectic similitude of multiplier -1. Abstractly, any such similitude satisfies

$$\Omega(gv, gw) = -\Omega(v, w),$$

so its lift τ to H sends the center to its inverse,

$$\boxed{\tau(z) = z^{-1}}.$$

Consequently

$$\boxed{\rho_r \circ \tau \simeq \rho_{-r}}, \qquad 1 \leftrightarrow 2.$$

This immediately gives a representation-theoretic firewall. No complex-linear similarity can implement τ inside a single faithful sector: similarity preserves the scalar $\rho_r(z) = \omega^r I$, whereas τ requires $\omega^{-r} I$. In the standard qutrit model

$$X|j\rangle = |j + 1\rangle, \qquad Z = \mathrm{diag}(1, \omega, \omega^2),$$

complex conjugation gives

$$X \mapsto X, \qquad Z \mapsto Z^{-1}, \qquad \omega \mapsto \omega^{-1},$$

and therefore realizes the determinant-reversing operation antiunitarily. On the doubled carrier

$$\rho_1 \oplus \rho_2,$$

a block swap implements the same outer action complex-linearly.

This is the rank-12 completion of Passes 5725–5732, where the determinant character of $GL(2, 3)$ separated the unitary Clifford $SL(2, 3)$ sector from a determinant-reversing antiunitary coset. It also sharpens the current quartic phase proposal $\omega^{r \det X}$: the central-character label r is exchanged by the outer symmetry, so the pair $r = 1, 2$ is the outer-closed object; a single-r realization explicitly breaks that completion unless an antiunitary implementation is intended.

There is a suggestive cross-repository consequence but not yet a physical identification. The Holotrade order-three GUT audit now finds that both the Georgi–Glashow and flipped-$SU(5)$ routes require an even-order ingredient for Standard-Model species to coexist. The finite six-qutrit carrier now has a canonical determinant-reversing C_2, but no certificate identifies that C_2 with a heterotic space-group/deck element or proves an even-order orbifold realization.

The executable certificate is `analysis/w33_suzuki_outer_heisenberg_sector_swap.py`, with frozen output `data/w33_suzuki_outer_heisenberg_sector_swap.json`.

79.76 Conditional S_3 closure of the doubled determinant-phase sector

The quartic adjoint invariant supplies the candidate phase

$$\omega^{r \det X}, \qquad r \in \{1, 2\},$$

while the Suzuki outer similitude exchanges the two faithful Heisenberg central-character sectors $r = 1 \leftrightarrow 2$. On the doubled sector write

$$D_f = \begin{pmatrix} \omega^f & 0 \\ 0 & \omega^{-f} \end{pmatrix}, \qquad S = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \qquad f = \det X \in \mathbb{F}_3.$$

Then

$$S^2 = 1, \qquad S D_f S = D_f^{-1}.$$

For $f = 1, 2$, D_f has order three, so

$$\boxed{\langle D_f, S \rangle \cong C_3{:}C_2 \cong S_3}.$$

For $f = 0$ the ternary factor collapses and only the C_2 sector swap remains.

This is precisely the noncentral ternary/binary presentation left open in Passes 5725–5732: the required inversion is now supplied by the certified outer action on the doubled six-qutrit carrier. The closure also shows why the $r = 1, 2$ pair is the natural outer-complete object for the determinant phase; fixing one central character removes the linear C_2 completion.

The group theorem is exact, but the gate claim remains conditional. The repository still lacks a physical intertwiner that couples the cubic-holonomy controller variable X to the six-qutrit register with phase $\omega^{r \det X}$. Therefore this subsection certifies *algebraic compatibility and closure*, not a realized non-Clifford gate.

There is again a cross-repository alignment with the Holotrade order-three GUT audit: both Georgi–Glashow and flipped-$SU(5)$ routes now require an even-order ingredient. The finite carrier supplies an exact $C_3{:}C_2$ extension, but no heterotic space-group/orbifold embedding of this S_3 is currently certified.

The executable certificate is `analysis/w33_det_phase_outer_s3_closure.py`, with frozen output `data/w33_det_phase_outer_s3_closure.json`.

79.77 Execute-all-five closure: the 270 carrier, doubled determinant phase, and the even-order heterotic branch

The four nontrivial involution degrees of $W(E_6)$ now admit an objectwise dictionary in native $W(3, 3)$ language. The formerly missing degree-two case is no longer an order coincidence. Starting from the selected 135_6–270_3 geometry, the intrinsic $[135, 16, 30]_2$ minimum shell gives the 36 double-six carrier. Each selected three-point line determines the twelve double-sixes meeting it in two singular points. Independently, each syzygetic pair of double-sixes determines the twelve double-sixes nonadjacent to both endpoints in the $\mathrm{srg}(36, 15, 6, 6)$. The two collections of 270 twelve-subsets are exactly equal. Hence

$$\boxed{270_{\text{selected lines}} \;\cong\; 270_{\text{syzygetic pairs}} \;\cong\; 270_{\deg 2 \text{ involutions}}}$$

as $PSp(4, 3)$-sets, with stabilizer order $25920/270 = 96$.

Composing this bridge with the already certified double-six/spread and tritangent/protected-carrier intertwiners closes the complete ladder

$W(E_6)$ involution degree	cubic-surface carrier	$W33$ carrier
1	36 double-sixes	36 spreads
2	270 syzygetic double-six pairs	270 spread-overlap-4 pairs / selected lines
3	540 disjoint tritangent–double-six flags	540 unselected tritangent–spread flags
4	45 tritangents	45 protected / center-quad carriers.

Thus the $1620 = 270 \cdot 6 = 45 \cdot 36$ apartment/flag scale is now tied to the full involution ladder through explicit equivariant maps rather than through cardinality alone.

The quartic determinant branch also acquires a sharp representation-theoretic boundary. On one irreducible 729-dimensional Schrödinger sector V_r of $H = 3^{1+12}$, Schur's lemma gives

$$\mathrm{End}_H(V_r) = \mathbf{C}I.$$

Consequently the bare candidate

$$\omega^{r \det X} I$$

is only a global phase and is not an internal six-qutrit magic gate. A noncentral operator-valued coupling is required to evade this single-sector no-go.

On the outer-complete doubled carrier $V_1 \oplus V_2$, however,

$$\mathrm{End}_H(V_1 \oplus V_2) \cong \mathbf{C} \oplus \mathbf{C},$$

and the same scalar invariant has a different exact meaning. With

$$z = \mathrm{diag}(\omega, \omega^{-1}), \qquad X_L = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix},$$

the determinant-controlled phase is

$$D_X = \mathrm{diag}(\omega^{\det X}, \omega^{-\det X}) \otimes I_{729} = z^{\det X} \otimes I_{729}.$$

For $\det X \neq 0$ this is a nontrivial *relative* logical phase on the central-character two-level factor, while it remains the identity on the internal 729-state degree of freedom. It is not a new generator: $D_X \in \langle z \rangle \cong C_3$. The outer swap obeys

$$X_L D_X X_L = D_X^{-1},$$

so the nonzero-determinant sector again closes as $C_3{:}C_2 \cong S_3$. The genuinely open intertwiner is the coherent controller operation

$$\sum_X |X\rangle\langle X| \otimes z^{\det X},$$

or an equivalent noncentral Weyl/VOA descendant. If the two central characters are superselected, even this logical interpretation is not operational.

The doubled carrier itself therefore has an exact logical-qubit structure conditional on coherent access to both sectors:

$$Z_L = \frac{z - z^{-1}}{i\sqrt{3}}, \qquad X_L = \text{outer sector swap},$$

with $X_L Z_L = -Z_L X_L$. The symmetry polynomial

$$P_{\text{code}} = \frac{2I - z - z^{-1}}{3}$$

vanishes on a center-trivial $r = 0$ sector and equals one on $r = 1, 2$, giving a genuine leakage check without measuring the logical $r = 1$ versus $r = 2$ information. The certified S_3 control remains finite; a separately available logical basis-changing gate is still required for dense one-qubit control.

Finally, the companion Holotrade branch now contains the first honest even-order gauge embedding replacing the old order-three software boundary. For the standard Z_6-II twist

$$v_6 = (1/6, 1/3, -1/2),$$

the explicit first-E_8 data

$$\begin{aligned} V_6 &= (1/6, 1/3, -1/2, 0, 0, 0, 0, 0), \\ W_2 &= (-1, 1/2, 0, -1, -1, -1/2, -1/2, -1/2), \\ W_3 &= (-2/3, -2/3, 2/3, 0, 2/3, -1/3, -1/3, 0) \end{aligned}$$

have exact lattice orders $6, 2, 3$ and satisfy all six Abelian modular congruences. Exact E_8-root enumeration gives

$$E_6 \longrightarrow A_4 + A_1 \longrightarrow A_2 + A_1$$

along the W_3 then W_2 route. The final $A_2 + A_1$ is contained inside the $A_4 \cong SU(5)$ parent, and the canonical Cartan direction

$$Y = \frac{1}{12}(-1, -1, -1, 5, -7, 3, 3, -5)$$

satisfies

$$Y^2 = \frac{5}{6}, \qquad \boxed{k_Y = 2Y^2 = \frac{5}{3}}.$$

On every $SU(5)$ root the W_2 character equals the character of $(3/5)Y$, with phases 0 and 1/2. This closes the *gauge-embedding* version of the even-order escape.

The first twisted sector can now be pushed one step further without building the full spectrum. The twelve T_1 fixed points have local shifts

$$V_g = V + n_3 W_3 + n_2 W_2 + n_2' W_2', \qquad n_3 = 0, 1, 2, \quad n_2, n_2' = 0, 1.$$

For the present witness $W_2' = 0$, so each of six local shifts occurs twice. At $n_3 = n_2 = 0$ the local algebra is E_6, giving exactly two local E_6 fixed points. Since $\delta c_{T_1} = 11/36$, the unoscillated left-moving mass equation is

$$(P + V_g)^2 = \frac{25}{18}.$$

At either local E_6 point the shifted E_8 lattice contains exactly 27 solutions. Those 27 weights form one transitive orbit under all 72 local E_6 root reflections. Using the standard Z_6-II result that massless T_1 solutions are twist invariant and survive as complete local-GUT multiplets, the witness therefore contains two complete localized 27s.

Restricting one exact 27-weight shell to the globally surviving $SU(3) \times SU(2) \times U(1)_Y$ gives

$$\begin{aligned} 27 = {} & (3, 2)_{1/6} + (\bar{3}, 1)_{-2/3} + 2(\bar{3}, 1)_{1/3} + (3, 1)_{-1/3} \\ & + 2(1, 2)_{-1/2} + (1, 2)_{1/2} + (1, 1)_1 + 2(1, 1)_0. \end{aligned}$$

Thus each local 27 contains one complete Standard-Model family (including ν^c), a vectorlike $5+\bar{5}$ package, and an extra singlet. Two localized family multiplets are therefore closed. The third net family, the other twisted and untwisted sectors, global anomaly accounting, exotic decoupling, flatness and Yukawas remain open; no complete MSSM spectrum is claimed.

Executable certificates are `data/w33_e6_degree2_selected270_bridge.json`, `data/w33_e6_involution_ful` `data/w33_det_phase_scalar_no_go.json`, `data/w33_doubled_central_character_logical_qubit.json`, and `data/w33_det_phase_doubled_logical_reconciliation.json`. The even-order witnesses are frozen in the companion Holotrade repository as `data/w33_z6ii_sm_shape_builder.json`, `data/w33_z6ii_t1_local_e6_shell.json`, and `data/w33_z6ii_t1_two_local_27s.json`.

All statements above are finite group, representation, lattice, or gauge-embedding statements. No claim of a completed MSSM spectrum, observed particle parameters, continuum unification, or experimentally realized logical sector is made.

79.78 Controlled determinant gate and outer-complete coherence

The determinant controller target can now be stated as an exact unitary rather than a verbal missing bridge. Let $X \in \mathfrak{sp}_4(\mathbb{F}_3)$ label the certified ten-qutrit controller basis and let

$$z = \mathrm{diag}(\omega, \omega^{-1})$$

act on the doubled $r = 1, 2$ central-character factor. Define

$$\boxed{U_{\det} = \sum_X |X\rangle\langle X| \otimes z^{\det X}.}$$

This is unitary. Since the determinant assumes all three values in $\mathbb{F}_3$, it is not a product gate. For a controller superposition of one $\det X = 0$ and one $\det X = 1$ basis state and logical $|+\rangle = (|1\rangle + |2\rangle)/\sqrt{2}$, the two logical branches have overlap

$$\langle +|z|+\rangle = -\frac{1}{2},$$

so the output has Schmidt rank two.

The gate is also non-Clifford on the controller. For prime qutrits, a cube-root diagonal Clifford has a quadratic polynomial exponent. The exact adjoint invariant calculation already proves that the only invariant quadratic is $q_2(X) = \mathrm{tr}(X^2)$, while all nine pairs $(q_2, \det) \in \mathbb{F}_3^2$ occur. Hence $\det X$ is not any quadratic function on the controller, and each logical-Z block $\omega^{\pm \det X}$ is non-Clifford.

This does not contradict the single-sector Schur no-go. On a fixed 729-dimensional Schrödinger sector the determinant phase is scalar. The new unitary uses both controller dependence and the doubled logical sector. What remains physically open is an actual VOA/OPE, Hamiltonian, photonic, or fault-tolerant implementation of $U_{\det}$.

The doubled-sector coherence question also closes algebraically. Let $H = 3^{1+12}$ and adjoin the certified outer involution s with $szs^{-1} = z^{-1}$. The two 729-dimensional Schrödinger irreducibles V_1, V_2 have distinct central characters and satisfy

$$V_1^s \simeq V_2 \not\simeq V_1.$$

For the index-two normal extension

$$G = H \rtimes \langle s \rangle,$$

Mackey–Clifford irreducibility therefore gives

$$\boxed{\mathrm{Ind}_H^G V_1 \text{ irreducible}, \qquad \mathrm{Ind}_H^G V_1\big|_H = V_1 \oplus V_2.}$$

Thus the certified 1458-dimensional doubled carrier is one irreducible outer-complete module. The projectors P_1, P_2 onto the two central characters obey

$$sP_1s^{-1} = P_2$$

and are not central projectors of the enlarged representation algebra. Therefore $r = 1$ versus $r = 2$ is not an *intrinsic* superselection label once the outer operation is admitted.

The physical boundary is precise: if the outer coset is not dynamically realizable and the observable algebra is restricted to operations commuting with z, then the two labels remain operationally superselected. The open question is implementation of the outer operation, not representation theory.

Executable certificates: `data/w33_controlled_det_logical_gate.json` and `data/w33_outer_complete_no_`

79.79 Seventeen-term determinant compiler, photonic outer rail, and the corrected heterotic frontier

The controlled determinant gate now has an exact sparse compiler. In the certified ten-coordinate basis of $\mathfrak{sp}_4(\mathbb{F}_3)$,

$$X = \begin{pmatrix} 2x_4 & 2x_8 & x_0 & x_1 \\ 2x_5 & 2x_9 & x_1 & x_2 \\ x_3 & x_6 & x_4 & x_5 \\ x_6 & x_7 & x_8 & x_9 \end{pmatrix}.$$

Direct expansion over $\mathbb{F}_3$ contains exactly 17 nonzero quartic monomials. Exhaustive evaluation on all $3^{10} = 59049$ controller states verifies the identity pointwise. Hence

$$U_{\det} = \sum_X |X\rangle\langle X| \otimes z^{\det X} = \prod_{a=1}^{17} P_{m_a}(c_a),$$

where the diagonal primitives commute and

$$P_m(c)|x, r\rangle = \omega^{r\, c\, m(x)}|x, r\rangle.$$

Thus the nonlinear hardware target is a seventeen-primitive quartic phase compiler rather than a 59049-entry truth table. If the controller is measured classically one may compute $\det X$ digitally and apply $z^{\det X}$, but that fast path does not implement coherent non-Clifford controller dynamics.

The outer logical operation also admits a concrete photonic encoding. Choose two coherent rails for the two central characters,

$$r = 1 \leftrightarrow H \text{ (or path A)}, \qquad r = 2 \leftrightarrow V \text{ (or path B)},$$

and program the $r = 2$ rail with the conjugate qutrit phase convention $Z \mapsto Z^{-1}$. Then the certified outer involution is the rail swap,

$$X_L = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \qquad X_L\, \mathrm{diag}(\omega, \omega^{-1})\, X_L = \mathrm{diag}(\omega^{-1}, \omega).$$

At the encoding layer this is implementable by a polarization swap or path cross-connect. Once coherent access to both rails is available, an ordinary two-mode mixer plus a relative phase gives arbitrary logical $SU(2)$, not only the finite $\langle z, X_L\rangle \cong S_3$ subgroup. The unresolved physical step is the coherent isometry from the native $V_1 \oplus V_2$ carrier into those laboratory rails; representation theory does not construct that interface.

The companion heterotic track also changed materially during this pass. The full T_1 B.3–B.5 oscillator ledger retains the two local E_6 27s but reveals additional states at the other fixed points. Consequently the earlier shorthand that the model had two families plus an untwisted ten and only one missing $\bar{5}$ is withdrawn as a global claim. A first all-sector Z_6-II engine now covers $U, T_1/T_5, T_2/T_4, T_3$, but its anomaly sentinel currently returns $A_{SU(3)^3} = -2$. The engine is therefore quarantined rather than promoted to a physical spectrum. This is an evidence improvement: the remaining projection/chirality convention bug is visible and testable.

Executable certificates are `data/w33_controlled_det_17term_compiler.json` and `data/w33_outer_logical` The heterotic correction is frozen in the companion Holotrade repository as `data/w33_z6ii_t1_full_oscillator_` and `data/w33_z6ii_full_spectrum_engine_v1.json`.

79.80 Optimal determinant compiler, exact rail intertwiner, and the heterotic extension boundary

Three previously open finite-control questions now have exact answers.

First, the seventeen-term determinant compiler is optimal in its native ancilla-free monomial-phase library. Polynomial functions

$$\mathbb{F}_3^{10} \longrightarrow \mathbb{F}_3$$

have unique reduced representatives modulo

$$x_i^3 - x_i, \qquad i = 0, \ldots, 9,$$

with each exponent in $\{0, 1, 2\}$. The reduced determinant polynomial has exactly seventeen nonzero coefficients. Since one native primitive contributes one reduced monomial coefficient to the phase exponent, every circuit in this fixed commuting library needs at least seventeen nontrivial primitives. The existing compiler meets the bound:

$$\boxed{N_{\text{native}}^{\text{ancilla-free}}(U_{\det}) = 17.}$$

Ancillas, nonmonomial analog Hamiltonians, measurement/feedforward and a different basis/library are explicitly outside this optimum.

Second, the native doubled carrier has an exact generator-level rail intertwiner. Choose computational bases $|n\rangle$, $n \in \mathbb{F}_3^6$, for V_1, V_2 so that

$$\rho_1(X_j) = X_j, \quad \rho_1(Z_j) = Z_j, \qquad \rho_2(X_j) = X_j, \quad \rho_2(Z_j) = Z_j^{-1}.$$

The basis map

$$J|r = +1, n\rangle = |0\rangle_{\text{rail}}|n\rangle, \qquad J|r = -1, n\rangle = |1\rangle_{\text{rail}}|n\rangle$$

gives

$$X_j \mapsto I_{\text{rail}} \otimes X_j,$$

$$Z_j \mapsto |0\rangle\langle 0| \otimes Z_j + |1\rangle\langle 1| \otimes Z_j^{-1},$$

$$z \mapsto \operatorname{diag}(\omega, \omega^{-1}) \otimes I_{729}, \qquad s \mapsto X_{\text{rail}} \otimes I_{729}.$$

Thus the algebraic native-sector-to-rail intertwiner is no longer missing. The laboratory obligation is specifically a coherent loading/readout isometry implementing this normal form.

Third, the tempting identification of the W33 outer C_2 with the current heterotic Z_6-II even-order factor is false. The cyclic point group is

$$C_6 = \langle \theta \rangle \cong C_3 \times C_2,$$

so

$$\theta^3 \theta^2 \theta^{-3} = \theta^2.$$

Its C_2 acts trivially on its C_3. The W33 outer involution instead satisfies

$$szs^{-1} = z^{-1},$$

and therefore

$$\langle z, s \rangle \cong C_3{:}C_2 \cong S_3.$$

The two extensions correspond to the trivial and nontrivial homomorphisms $C_2 \to \mathrm{Aut}(C_3)$ and are not equivariantly isomorphic. A genuine heterotic analogue of the W33 inversion would require a non-Abelian S_3/dihedral-type space-group or flavor extension.

The companion Z_6-II spectrum audit also corrected the earlier $SU(3)^3 = -2$ quarantine sentinel. Restoring the published $D_{\gamma=+1,-1} = (1, 2)$ multiplicities and Table-VII T_3 vector right movers gives

$$\boxed{A_{SU(3)^3} = 0}.$$

Hypercharge-related visible anomalies remain nonzero in the current ledger, so the heterotic witness remains quarantined and is not promoted to an MSSM compactification.

Executable certificates: `data/w33_controlled_det_17term_optimality.json`, `data/w33_native_sector_ra` and `data/w33_z6ii_c2_extension_no_go.json`.

79.81 External orbifold benchmark, two-invariant magic compiler, and the correct non-Abelian heterotic target

The heterotic spectrum code now has its first external regression fixture. Using the published Z_6-II model of Buchmüller–Hamaguchi–Lebedev–Ratz, exact $E_8 \times E_8$ root enumeration reproduces

$$A_2 + A_1 \quad (8 \text{ roots})$$

in the visible first E_8 and

$$A_3 + A_1 \quad (14 \text{ roots})$$

in the hidden second E_8, i.e.

$$SU(3) \times SU(2) \times [SU(4) \times SU(2)]$$

before the Abelian factors. At the origin T_1 fixed point, the published visible shell

$$(p + V_6)^2_{\mathrm{obs}} = \frac{23}{18}$$

contains exactly 16 weights, while the hidden shell of norm 1/9 contains one shifted weight, reproducing the local $SO(10)$ sixteen-plet. The published Table 5.1 aggregate spectrum has been frozen as the next row-by-row regression checksum. Full Tables D.2–D.3 reproduction is not yet claimed.

On the W33 controller, the determinant gate admits a much smaller compiler once the hardware library is enlarged from reduced monomial phases to adjoint-invariant phases. For $X \in \mathfrak{sp}_4(\mathbb{F}_3)$, the even characteristic polynomial and Newton identities give

$$\det X = \frac{(\operatorname{tr} X^2)^2 - 2\operatorname{tr} X^4}{8}.$$

Reducing in $\mathbb{F}_3$,

$$\boxed{\det X = 2\left[(\operatorname{tr} X^2)^2 + \operatorname{tr} X^4\right]}.$$

This identity has been verified on all $3^{10} = 59049$ controller states. Hence, if direct invariant-phase primitives are available,

$$\boxed{U_{\det} = P^2_{(\operatorname{tr} X^2)^2}\, P^2_{\operatorname{tr} X^4}},$$

only two commuting nonlinear primitives are required, versus the exact seventeen-primitive optimum in the native reduced-monomial library.

The doubled 1458-state carrier also has a concrete optical packing. Flatten

$$n = (n_0, \ldots, n_5) \in \mathbb{F}_3^6$$

to one mode label

$$m = \sum_{j=0}^{5} n_j 3^j \in \{0, \ldots, 728\}$$

and use a polarization/path rail for $r = \pm 1$. The physical mode count is therefore exactly

$$2 \times 729 = 1458.$$

Each X_j is a permutation of 243 disjoint three-cycles on the comb, each Z_j is a rail-conditioned phase $\omega^{r n_j}$, the center is a relative rail phase, and the outer involution is a rail swap. Declared 99% single-gate planning targets give phase-error budgets of approximately 0.123 rad for the rail phase and 0.142 rad for a qutrit digit phase. A conservative 1% total wrong-mode leakage budget across 728 unwanted modes corresponds to -48.6 dB per wrong mode under an equal-leakage union bound. These are derived engineering targets, not measurements.

Finally, the previous cyclic Z_6-II no-go points to the correct heterotic symmetry class. Konopka's explicit non-Abelian heterotic S_3 orbifold has published generators obeying

$$S_3 = \langle \tau, \sigma \mid \tau^2 = \sigma^3 = (\tau\sigma)^2 = 1 \rangle,$$

so

$$\tau\sigma\tau^{-1} = \sigma^{-1}.$$

The published 6×6 lattice matrices have been checked directly. Therefore the abstract extension law matches W33 exactly under

$$\tau \leftrightarrow s, \qquad \sigma \leftrightarrow z.$$

This is a group-extension bridge only: a geometric heterotic point-group rotation is not thereby identified with the Heisenberg center phase.

Executable certificates: `data/w33_controlled_det_two_invariant_compiler.json`, `data/w33_1458_mode_p` and `data/w33_heterotic_s3_outer_target.json`.

79.82 Five-front plus three-physics closure: unique hypercharge, exact S_3 module, and spectral/commutator probes

The companion heterotic benchmark has now been frozen at row level. The published Buchmüller–Hamaguchi–Lebedev–Ratz Table D.2 visible-state labels close exactly to

$$3Q + 3u^c + 7d^c + 4d + 5\bar{L} + 8L + 8m + 3e^c + 16s^+ + 16s^-,$$

and every Table D.3 row identity is frozen through $s_1, \ldots, s_{69}$, $h_1, \ldots, h_{14}$, $f_1, \ldots, f_4$, $\bar{f}_1, \ldots, \bar{f}_4$, and $w_1, \ldots, w_5$. Reproduction of every published Abelian charge column remains the external fail-closed target.

The explicit witness also has a hypercharge rigidity theorem. Requiring a Cartan vector to reproduce the hypercharge of all 27 exact local-E_6 weights gives

$$Y(t) = \left(t, -2t - \frac{1}{4}, t, \frac{5}{12}, -\frac{7}{12}, \frac{1}{4}, \frac{1}{4}, -\frac{5}{12}\right).$$

Since

$$Y(t)^2 - \frac{5}{6} = \frac{(12t+1)^2}{24},$$

the canonical condition $k_Y = 2Y^2 = 5/3$ uniquely fixes

$$t = -\frac{1}{12}.$$

Thus the canonical Y cannot be continuously repaired by first-E_8 Cartan mixing while preserving the full local-family charges and normalization.

The non-Abelian heterotic bridge is now representation-level rather than only presentation-level. Konopka's defining S_3 matrices

$$\tau = \begin{pmatrix} 1 & -1 \\ 0 & -1 \end{pmatrix}, \qquad \sigma = \begin{pmatrix} 0 & -1 \\ 1 & -1 \end{pmatrix}$$

are conjugate, in the basis

$$v_+ = (-\omega^2, 1)^T, \qquad v_- = (\omega, -1)^T,$$

to

$$\tau \mapsto X_L, \qquad \sigma \mapsto \mathrm{diag}(\omega, \omega^{-1}).$$

Hence the heterotic defining doublet and the W33 central-character logical doublet are isomorphic as complex S_3-modules. The physical operator identification remains open.

Three additional physics consequences follow.

First, for the W33 Laplacian

$$L = 12I - A, \qquad \mathrm{spec}\, L = 0^1 + 10^{24} + 16^{15},$$

an engineered evolution at $gt = \pi/2$ is the exact eigenspace reflection

$$e^{-i(\pi/2)L} = I - 2P_{10} = \frac{A^2 - 8A - 18I}{30}.$$

Only the 24-dimensional $\lambda = 10$ sector changes sign, and the full system revives at $gt = \pi$.

Second, the common S_3 normal form gives the closed commutator loop

$$K = X_L z X_L^{-1} z^{-1} = z.$$

A Ramsey experiment beginning in

$$|+\rangle = (|r=1\rangle + |r=2\rangle)/\sqrt{2}$$

therefore has return probability

$$|\langle +|K|+\rangle|^2 = \frac{1}{4},$$

whereas a commuting $C_3 \times C_2$ null model gives unity.

Third, the determinant magic interaction admits a one-window analog target. Writing

$$A(X) = ((\operatorname{tr} X^2)^2 + \operatorname{tr} X^4) \pmod 3,$$

the Hamiltonian

$$H_{\det} = -\frac{4\pi\hbar}{3T} A(X) \otimes Z_L$$

obeys

$$e^{-iH_{\det}T/\hbar} = U_{\det}.$$

The unresolved problem is microscopic realization of this invariant coupling, not its finite-dimensional synthesis.

Executable certificates are `data/w33_heterotic_s3_defining_irrep_intertwiner.json`, `data/w33_laplaci` `data/w33_s3_commutator_ramsey_witness.json`, and `data/w33_det_single_window_hamiltonian.json`.

79.83 Entangling qutrit Wilson line, canonical $SU(5)$, and the all-q CZ weld

The viable W33-class Z_6-I flagship selects a distinguished order-three class inside its local $A_8 = \mathfrak{su}_9$. Its roots split as

$$72 = 24_0 + 24_1 + 24_2,$$

with neutral root subsystem $A_4 + A_1 + A_1$. Consequently the defining nine-dimensional holonomy has eigenvalue multiplicities $5 + 2 + 2$, and is projectively $SU(9)$-conjugate to the two-qutrit gate

$$CZ_3|x, y\rangle = \omega^{xy}|x, y\rangle.$$

This is the entangling Clifford branch: the corresponding W33 point action is

$$1^4\, 3^{12},$$

with the four fixed points one totally isotropic line. By contrast, a local single-qutrit phase gate has $6 + 3$ fundamental spectrum, adjoint grading $44 + 18 + 18$, and W33 profile $1^{13}3^9$.

The construction extends uniformly to prime q. For

$$CZ_q|x, y\rangle = \zeta^{xy}|x, y\rangle$$

the fundamental phase multiplicities are

$$m_0 = 2q - 1, \qquad m_a = q - 1 \quad (a \neq 0),$$

and the induced $\mathbb{Z}_q$-grading of $\mathfrak{sl}_{q^2}$ obeys

$$\dim \mathfrak{g}_0 = (q+1)(q^2-1), \qquad \dim \mathfrak{g}_a = q(q^2-1) \quad (a \neq 0).$$

The charged dimension is therefore

$$q(q^2-1) = |SL(2,q)|.$$

On the projective two-qudit Pauli geometry $W(3,q)$, the same Clifford has cycle profile

$$1^{\,q+1}\, q^{\,q(q+1)}.$$

Its fixed set is one totally isotropic $PG(1,q)$, and the number of nontrivial projective cycles is

$$q(q+1) = k,$$

the $\mathrm{GQ}(q,q)$ collinearity valency. On all nonzero Pauli vectors the profile is

$$1^{\,q^2-1}\, q^{\,q(q^2-1)},$$

so the number of nontrivial vector cycles equals every nonzero adjoint-grade dimension and $|SL(2,q)|$.

At $q=3$, the CZ_3 zero-phase states are

$$(0,0),(0,1),(0,2),(1,0),(2,0),$$

the zero locus $xy=0$ in $\mathbb{F}_3^2$. Thus its connected centralizer is

$$S(U(5)\times U(2)\times U(2)).$$

The flagship's measured neutral A_4 is consequently the $SU(5)$ acting on this five-dimensional zero-phase block, after the projective conjugation. A $3+2$ split of that block carries the canonical generator

$$Y = \mathrm{diag}\left(-\frac{1}{3},-\frac{1}{3},-\frac{1}{3},\frac{1}{2},\frac{1}{2}\right),$$

with

$$\mathrm{tr}\, Y^2 = \frac{5}{6}, \qquad k_Y = \frac{5}{3}.$$

Thus the same exact entangling qutrit conjugacy class controls the observed $32+24+24$ $SU(9)$ grading and contains the flagship's canonically normalised $SU(5)$ hypercharge block.

This is a conjugacy-class result; no preferred map from the displayed heterotic root basis to the standard qutrit computational basis is claimed.

Executable certificates: `data/w33_allq_cz_orbit_adjoint_weld.json` and `data/w33_cz_zero_phase_su5_h`

79.84 An exact E8 lift of the oriented-Pauli label action, and the parity firewall

The signed-Pauli label action admits an exact lift to the complete 240-root E8 Coxeter fibration. Let $d = c_{\mathrm{Cox}}^5$ be the internal order-six fiber rotation. Transporting the 80-state label permutation $CZ_3(-I)$ through the frozen signed-Pauli map gives a fiber permutation Q, and the phase equations admit

$$L : (x,k) \mapsto (Qx, k+\delta_x) \pmod 6$$

preserving every E8 root inner product. The reversing branch has no solution. The lift commutes with d, has cycle profile $2^3\,6^{39}$, and

$$L^3 = d^3 = -I.$$

With $C = Ld^{-1}$, C has order three, cycle profile $1^{12}3^{76}$, and induces the pure CZ label permutation. Hence

$$\langle d, C\rangle \cong C_6 \times C_3.$$

This is a label-level root-system theorem, not a physical parity identification. The flagship θ^3 holonomy is inner on $\mathfrak{su}(9)$, with fixed algebra $\mathfrak{su}(5)+\mathfrak{su}(4)+\mathfrak{u}(1)$ of dimension 40. The Coxeter half-turn d^3 is global root negation, outer on $\mathfrak{su}(9)$, with fixed algebra $\mathfrak{so}(9)$ of dimension 36. Therefore $40 \neq 36$ forbids identifying d^3 with the physical parity gate.

The remaining physical problem is sharper: construct or rule out an E8/Chevalley realization of the inner 5+4 parity together with the commuting 5+2+2 order-three holonomy. Executable certificate: `data/w33_e8_cz_parity_c6_root_lift.json`.

79.85 Physical inner holonomies in E_8: Chevalley centralizers, triality, and the mod-three charge law

The physical flagship holonomies admit an exact lift to all of E_8 in the correct category: as commuting inner torus automorphisms of the regular $A_8 \cong SU(9)$ subgroup, not as Weyl permutations of the root set. The classical branching is

$$\mathfrak{e}_8 = \mathfrak{sl}_9 \oplus \Lambda^3\mathbf{9} \oplus \Lambda^6\mathbf{9} = 80 + 84 + \overline{84}.$$

The exact fundamental joint multiplicities

$$(0,+),(0,-),(1,+),(1,-),(2,+),(2,-) = 3,2,1,1,1,1$$

propagate to the full adjoint as

$$\boxed{44, 48, 38, 40, 38, 40}.$$

Hence the product C_6 eigenvalue multiplicities are

$$\boxed{44, 40, 38, 48, 38, 40}.$$

Explicit reconstruction of the 240 roots in the A_8 model gives

$$\begin{aligned}
\mathfrak{e}_8^{W_3} &\cong D_7 \oplus \mathfrak{u}_1, && \dim = 92,\\
\mathfrak{e}_8^{\theta^3} &\cong D_8, && \dim = 120,\\
\mathfrak{e}_8^{W_3\theta^3} &\cong D_4 \oplus A_3 \oplus \mathfrak{u}_1, && \dim = 44.
\end{aligned}$$

The last line is the exact neutral algebra $SO(8) \times SU(4) \times U(1)$.

The non-neutral sectors exhibit the full Spin(8) triality triple. Denoting the three eight-dimensional minuscule weight orbits by $8_A, 8_B, 8_C$, which are $8_v, 8_s, 8_c$ in some triality frame, one obtains

$$\begin{aligned}
(0,-) &= (8_A, 6),\\
(1,+) &= (8_B, 4) \oplus (1, 6),\\
(2,+) &= (8_B, \bar{4}) \oplus (1, 6),\\
(1,-) &= (8_C, \bar{4}) \oplus (8_A, 1),\\
(2,-) &= (8_C, 4) \oplus (8_A, 1).
\end{aligned}$$

The residual Cartan generator can be chosen

$$Q = (0, 0, 0, 0, 0, -1, -1, +1, +1),$$

giving the complete branching

$$\begin{aligned} 248 = {} & (28,1)_0 + (1,15)_0 + (1,1)_0 + (8_A,6)_0 \\ & + (8_B,4)_{-1} + (8_C,\bar{4})_{-1} + (1,6)_{+2} + (8_A,1)_{+2} \\ & + (8_B,\bar{4})_{+1} + (8_C,4)_{+1} + (1,6)_{-2} + (8_A,1)_{-2}. \end{aligned}$$

On every E8 root space the order-three Wilson character satisfies the exact continuous-to-discrete law

$$\boxed{a \equiv -Q \pmod 3}.$$

This resolves the earlier parity firewall. The physical parity is an inner Chevalley/torus automorphism with a 120-dimensional D_8 fixed algebra in all of E_8, whereas the Coxeter-fiber antipode is a distinct Weyl/root permutation. No Standard-Model particle assignment or canonical naming of the three triality orbits is inferred.

Executable certificates: `data/w33_physical_holonomy_e8_chevalley_lift.json`, `data/w33_physical_e8_t` and `data/w33_physical_e8_so8_su4_u1_branching.json`.

79.86 The 72-slot packet frame is the full qutrit Hamming frame of the CZ_3 entangler

The punctured-Hesse packet group admits a sharper interpretation at $q = 3$. The nine affine bins are the two-trit computational grid

$$\mathbb{F}_3^2,$$

whose Hamming graph $H(2,3)$ joins basis labels differing in exactly one coordinate. The packet-frame group is

$$\mathbb{F}_3^2 \rtimes D_8 \cong AGL(1,3) \wr C_2 \cong S_3 \wr C_2 = \operatorname{Aut} H(2,3),$$

of order 72. Thus the current $9 \times 2 \times 4$ packet radix is the full local classical relabelling group of the two-qutrit computational basis.

For

$$CZ_3|x,y\rangle = \omega^{xy}|x,y\rangle,$$

the zero-phase support is the five-state cross

$$Z_0 = \{(x,y) : xy = 0\}.$$

Its stabiliser inside the 72-element local-frame group is exactly the linear monomial D_8. The orbit of Z_0 consists of the nine translated crosses

$$Z_{a,b} = \{(x,y) : (x-a)(y-b) = 0\},$$

one centered on each affine Hesse bin. Hence

$$G_3/D_8 \cong \mathbb{F}_3^2$$

is literally the bundle of nine CZ zero-phase frames.

The two retained infinity points of the punctured plane are

$$[1:1:0], \qquad [1:-1:0].$$

For a linear monomial frame change

$$L = \mathrm{diag}(\alpha, \beta)$$

with optional register swap, the CZ phase rescales by

$$xy \longmapsto \chi(L)\, xy, \qquad \chi(L) = \alpha\beta.$$

The infinity slope transforms by β/α (up to inversion under the swap). Because every nonzero element of $\mathbb{F}_3$ is self-inverse,

$$\frac{\beta}{\alpha} = \alpha\beta.$$

Therefore the two infinity points swap if and only if

$$CZ_3 \longleftrightarrow CZ_3^{-1}.$$

The existing runtime alphabet

$$11 = 9 + 2$$

is consequently equivariantly interpretable as nine affine CZ-frame centers plus the two nonzero CZ phase sectors.

Both coincidences are $q = 3$-specific among odd primes: $AGL(1,3) = S_3$, so the affine packet group is the full Hamming automorphism group, and the ratio and product characters on $\mathbb{F}_3^\times$ coincide. The result is an exact finite control/frame theorem, not a claim that current hardware dynamically implements all 72 frame symmetries.

Executable certificate: `data/w33_qutrit_hamming_cz_frame_bundle.json`.

79.87 Scope correction: the holonomy pair fixes the SM nonabelian factor, not the full SM group

The certified joint fundamental multiplicities of the commuting order-three Wilson line and order-two θ^3 holonomy are

$$(3, 2, 1, 1, 1, 1).$$

For a commuting semisimple family with joint multiplicities m_i, the centralizer in $SU(n)$ is $S(\prod_i U(m_i))$ and has dimension $\sum_i m_i^2 - 1$. Hence the full local centralizer here is

$$S(U(3) \times U(2) \times U(1)^4),$$

with Lie algebra

$$\mathfrak{su}(3) \oplus \mathfrak{su}(2) \oplus \mathfrak{u}(1)^5, \qquad \dim = 16.$$

The observable Standard Model algebra has dimension $8 + 3 + 1 = 12$. Thus the exact positive statement is that the pair cuts the Wilson-line $SU(5)$ block as $3 + 2$, yielding the observable $SU(3) \times SU(2)$ factor, with hypercharge one selected $U(1)$. Four further local abelian directions remain and must be removed or lifted by the rest of the heterotic compactification.

This corrects the stronger historical shorthand "the SM gauge group is the joint stabilizer" without changing the measured 25/25 $3 + 2$ split or the 630/2099 background control.

Executable witness: `analysis/w33_holonomy_joint_centralizer_scope.py`; frozen certificate: `data/w33_holonomy_joint_centralizer_scope.json`.

79.88 The physical E8 lift closes only after the local A_8 selector is included

The physical Wilson/parity pair has an exact inner lift to all of E_8, but its common fixed algebra in the full exceptional algebra is larger than the local gauge algebra:

$$\mathfrak{g}^{W_3,\theta^3} = D_4 \oplus A_3 \oplus \mathfrak{u}(1), \qquad \dim = 44.$$

The local $SU(9)$ chart is itself selected by an independent order-three inner automorphism ρ with grading

$$E_8 = A_{8,0} \oplus \Lambda^3(\mathbf{9})_1 \oplus \Lambda^6(\mathbf{9})_2.$$

Among the 36 roots fixed by the physical pair, eight lie in A_8 and twenty-eight lie in the two exterior-power sectors, fourteen in each. Imposing ρ-neutrality therefore removes exactly those twenty-eight roots.

The resulting triple fixed root system has component signatures $(6, 2)$ and $(2, 1)$, hence

$$\mathfrak{g}^{\rho,W_3,\theta^3} = A_2 \oplus A_1 \oplus \mathfrak{u}(1)^5, \qquad \dim = 16.$$

This is exactly the corrected local joint centralizer of the $(3, 2, 1, 1, 1, 1)$ fundamental spectrum. The fixed-algebra chain is

$$\rho : A_8(80), \quad W_3 : D_7{+}u_1(92), \quad \theta^3 : D_8(120),$$

$$W_3 \cap \theta^3 : D_4{+}A_3{+}u_1(44), \qquad \rho \cap W_3 \cap \theta^3 : A_2{+}A_1{+}u_1^5(16).$$

Thus the apparent 44-versus-16 tension is not a contradiction: the A_8 selector is the missing projector from the full E_8 centralizer to the local orbifold gauge algebra.

Executable witness: `analysis/w33_e8_a8_selector_holonomy_triple_intersection.py`; frozen certificate: `data/w33_e8_a8_selector_holonomy_triple_intersection.json`.

79.89 The translated CZ_3 cross bundle has determinant 80

The nine translated CZ_3 zero-phase frames from the Hamming packet theorem form a square incidence operator on $\mathbb{F}_3^2$. For general q, let

$$C_{a,b} = \{(x, y) : x = a \text{ or } y = b\}$$

and define

$$B_q[(a, b), (x, y)] = 1_{(x,y)\in C_{a,b}}.$$

Then

$$B_q = I + A(H(2, q)) = J_q \otimes I_q + I_q \otimes J_q - I_{q^2}.$$

The Hamming spectrum gives

$$\operatorname{spec}(B_q) = \{2q - 1\}^1 \cup \{q - 1\}^{2(q-1)} \cup \{-1\}^{(q-1)^2},$$

and hence

$$\det B_q = (-1)^{(q-1)^2}(2q - 1)(q - 1)^{2(q-1)}.$$

At $q = 3$,

$$\boxed{\det B_3 = 80 = 3^4 - 1 = \dim \mathfrak{sl}_9.}$$

The equality with q^4-1 is unique for integer $q \geq 2$. This is an exact arithmetic lock between the translated-CZ frame incidence and the independently certified nonzero two-qutrit Pauli carrier; it is not by itself an equivariant identification.

The integral Smith form is

$$\mathrm{SNF}(B_3) = \mathrm{diag}(1^5, 2^3, 10).$$

Reducing its row span modulo two gives a binary

$$[9, 5, 3]$$

code with weight enumerator

$$1 + 6z^3 + 9z^4 + 9z^5 + 6z^6 + z^9.$$

Thus the same five-dimensional number that appears as the CZ_3 zero-phase block also appears as the binary rank of the nine-frame incidence, without identifying the corresponding vector spaces.

There is a second $q = 3$ lock in native characteristic. For odd prime q,

$$B_q = -I + N, \qquad N = J_q \otimes I_q + I_q \otimes J_q,$$

and over $\mathbb{F}_q$,

$$N^3 = 0, \qquad \operatorname{rank} N = 2q - 2, \qquad \operatorname{rank} N^2 = 1.$$

Therefore

$$\dim \ker N = (q-1)^2 + 1.$$

This equals the CZ_q zero-support size $2q-1$ precisely when

$$(q-1)(q-3) = 0,$$

so among $q > 1$ it singles out $q = 3$.

Finally the exact inverse lies in the Hamming Bose–Mesner algebra:

$$B_q^{-1} = \frac{3-q}{q-1} I + \frac{1}{q-1} A - \frac{2}{(q-1)(2q-1)} J.$$

At $q = 3$ the explicit identity coefficient vanishes,

$$\boxed{B_3^{-1} = \frac{1}{2} A(H(2,3)) - \frac{1}{5} J.}$$

Thus the nine translated frame sums can be inverted from rook-neighbour sums and one global mean, with no separate identity-channel term in this basis.

Executable witness: `analysis/w33_qutrit_hamming_cross_incidence.py`; frozen certificate: `data/w33_qutrit_hamming_cross_incidence.json`.

79.90 The holonomy group acts on packet18 from the left and right

The packet execution group is

$$G = \mathbb{F}_3^2 \rtimes D_8, \qquad |G| = 72,$$

and the eighteen probe blocks are the homogeneous space

$$X = G/H, \qquad H = \langle R \rangle \cong C_4.$$

The earlier subgroup obstruction remains valid: the physical character group

$$K = C_{3,\rho} \times C_{3,a} \times C_{2,b}$$

is not a subgroup of G. Nevertheless the homogeneous space carries one additional symmetry that is invisible if one looks only inside the left runtime action.

For a transitive G-set G/H,

$$\mathrm{Aut}_G(G/H) \cong N_G(H)/H.$$

Here exhaustive computation gives

$$N_G(H) = \{0\} \times D_8, \qquad N_G(H)/H \cong C_2.$$

The unique nontrivial equivariant automorphism is right multiplication by a reflection. In the packet coordinates

$$t = (\rho, a) \in \mathbb{F}_3^2, \qquad b \in \mathbb{F}_2,$$

it is simply $(t, b) \mapsto (t, b+1)$ and commutes with the entire left G-action.

The left translation kernel $T = \mathbb{F}_3^2$ and this right deck involution therefore generate

$$T_{\mathrm{left}} \times C_{2,\mathrm{deck}} \cong C_3^2 \times C_2,$$

acting regularly on all eighteen packet blocks. Thus the old two-sheet torsor bridge is the restriction of an exact regular action of the full holonomy character group; what remains false is only the stronger claim that this group sits inside the 72-element execution group.

Using $n = 4a + 3b \pmod 6$, the physical C_6 generator $(a, b) = (1, 1)$ becomes one ternary translation plus one deck swap. Its packet18 cycle profile is 6^3. The existing control-plane ABI writes

$$h = 3\rho + a, \qquad \texttt{tick} = 8h + 4b + p,$$

where $p \in \mathbb{Z}_4$ is the probe slot. Hence the same generator compiles lookup-free on the full 72-slot frame as

$$a \mapsto a + 1, \qquad b \mapsto b + 1, \qquad \rho, p \text{ fixed}.$$

It has cycle profile 6^{12}, its cube is the pure deck parity, and its sixth power is the identity.

These statements are control-plane and finite-group theorems. They do not identify an E_8 eigenspace with a hardware packet mode, nor do they claim that address mutation alone implements the microscopic holonomy.

Executable witnesses: `analysis/w33_packet18_external_regular_holonomy_action.py` and `analysis/w33_packet72_physical_c6_address_compiler.py`.

79.91 Executed genus-six surface and computation models

The certificate `w33_genus_six_execution.json` independently checks Lutz's 44-face triangulation on twelve vertices as a connected orientable surface, including every vertex link. A tree–cotree minor of determinant ± 1 gives an integral homology basis. An explicit 66×12 cycle map pulls back its intersection pairing to the previously certified K12 form E. The old singular Reye face table is retained as a rejected control. Tadokoro's periods for $y^2 = x^{13} - 1$ give an alternative marked Jacobian structure preserving E, but not the original Coxeter–Todd metric or its scalar Eisenstein symmetry. This does not contradict the earlier obstruction. A checked connected-sum instruction adds a torus with count change $(\Delta V, \Delta E, \Delta F) = (4, 18, 12)$; its inverse rejects live state and changed

topology. The two Heawood dynamical models have distinct frequencies. Finally, modulo three, E has rank twelve while the tested Gaussian form has rank six and a six-dimensional radical. These are different finite commutation structures, without a derived physical gauge identification. Proof, precision limits and ownership are in `W33_GENUS_SIX_EXECUTED_FIVE.md`.

79.92 Harmonic storage, actual singlets, and testable model boundaries

On the verified Lutz genus-six surface, the declared unit-edge inner product has twelve harmonic one-cycle representatives. Exact rational projection preserves their marked lattice homology classes; a second positive edge metric changes the representatives without changing those classes. Factorization and rational root isolation certify the smallest positive combinatorial Hodge eigenvalue as $2 - \sqrt{2}$. The harmonic projector removes boundary and gradient errors but preserves harmonic errors, which are logical changes. This is a discrete recovery limit, not a measured mass or complete quantum error-correcting scheme. Checked connected-sum instructions transport the original symplectic logical generators and add one pair. Atomic snapshots support recovery with explicit corruption and incomplete-write controls. The oscillator inference process separates two declared response families on synthetic data; actual hardware calibration remains open, and response frequency identifies stiffness divided by mass, not either quantity separately. Holotrade's actual flagship replay identifies the four co-local singlets completing the local nine-weight orbit, computes the one-dimensional local fundamental bilinear invariant space, and verifies momentum-neutral channels for the stored 64 Higgs-mass and 144 triplet-mass coupling rows. These necessary invariant checks do not compute full string amplitudes. Finally, the coarse values 137, 1836, and 3/13 are tested against declared measurement conventions and the frozen formula universe; percentage agreement alone is not agreement at measurement precision or prospective evidence. See `W33_TOE_FIVE_FOLLOWTHROUGHS.md` for certificates and scope.

79.93 Hypercharge as a W33 duad vector and the five-dimensional neutral center cokernel

The flagship global Standard-Model-side root algebra is

$$A_2 + A_1 + \mathfrak{u}(1)^5,$$

and the orthogonal rank-five lattice inside E_8 is exactly A_5. With standard A_5 coordinates

$$Q(A_5) = \{x \in \mathbb{Z}^6 : \sum_i x_i = 0\},$$

the canonical hypercharge vector is

$$Y = -\omega_1 = \frac{1}{6}(-5, 1, 1, 1, 1, 1), \qquad Y^2 = \frac{5}{6}.$$

The existing S_6-duad gauge module admits the normalized intertwiner

$$\Psi(x)_{\{i,j\}} = \frac{x_i + x_j}{2}.$$

Unlike the earlier unnormalized map, Ψ is an isometry: the five simple roots $e_i - e_{i+1}$ have exactly the A_5 Cartan Gram matrix in the fifteen-duad carrier. Hypercharge therefore has the explicit W33-coordinate form

$$\Psi(Y)_{\{0,i\}} = -\frac{1}{3} \quad (i = 1, \ldots, 5), \qquad \Psi(Y)_{\{i,j\}} = \frac{1}{6} \quad (1 \le i < j \le 5).$$

Thus the discriminant generator is a five-versus-ten duad pattern. Every syntheme sum vanishes, $\|\Psi(Y)\|^2 = 5/6$, and

$$6\Psi(Y) = (-2)^5(+1)^{10}$$

in the star/nonstar ordering. Its stabilizer in S_6 is exactly the $S_5 = W(A_4)$ fixing the distinguished vertex.

The hypercharge-orthogonal integral sublattice is

$$A_4 = \{x_0 = 0,\ \sum_{i=1}^{5} x_i = 0\}.$$

Writing

$$y_i = \Psi(x)_{\{0,i\}} = \frac{x_i}{2},$$

this four-dimensional sector is simply

$$\sum_{i=1}^{5} y_i = 0,$$

and all ten nonstar coordinates are reconstructed by

$$\Psi(x)_{\{i,j\}} = y_i + y_j.$$

Hence the four extra Abelian directions in the flagship have an exact W33 realization as zero-sum fluctuations on the five-edge duad star.

Independently, the physical E_8 holonomy bracket tensor gives the neutral sector

$$\dim \mathfrak{g}_{000} = 16, \qquad \operatorname{rank}[\mathfrak{g}_{000}, \mathfrak{g}_{000}] = 11.$$

Its five-dimensional cokernel is therefore precisely the center $\mathfrak{u}(1)^5$. The lattice result refines this as

$$16 = 11 + 1 + 4,$$

namely

$$\mathfrak{su}(3) \oplus \mathfrak{su}(2) \quad + \quad \mathfrak{u}(1)_Y \quad + \quad \mathfrak{u}(1)^4_{A_4}.$$

A hypercharge-preserving singlet vacuum removes all extra Abelian factors only if its charge projections span rank four on this A_4 sector.

There is an important cardinality firewall. The five duads in the hypercharge star have natural stabilizer S_5, whereas the five-state CZ_3 zero-phase cross has classical frame stabilizer D_8. Their equal size does not define a canonical intertwiner.

The executable certificate is `data/w33_hypercharge_duad_center_cokernel.json`.

Exact FI cones, harmonic redundancy and a prospective conditional test

The alternative-field audit in Holotrade extends all fourteen projected rank-four positive circuits to every physical representative and component mixture. Exact Farkas witnesses exclude their fixed type ratios from the full Cartan moment-map cone, including a nonnegative coefficient of the actual anomalous FI ray. The full set of 65 singlets does admit rational Cartan solutions; its sparse positive-FI candidate fails an explicit off-diagonal root moment, while all 34 one-component singlets are FI-infeasible. Other hidden-charged configurations and their full D/F equations remain open. The engine charge trace 200 is a normalization datum, not a measured FI scale.

On the prior local nine-weight carrier, normalized commuting holonomies W, H give explicit projectors

$$P_0 = (I + W + W^2)/3, \qquad P_T = P_0(I + H)/2, \qquad P_D = P_0(I - H)/2.$$

Their ranks are three and two. This constructs a globally permitted endomorphism ansatz, not a string amplitude. The joint-block census is prior work; its associative centralizer has dimension 17 and its traceless Lie algebra dimension 16.

The existing genus-six symplectic marking supports a finite algebraic assignment of six qutrits. Applying the known nine-qutrit Shor construction to each handle across nine carriers yields a $[[54, 6, 3]]_3$ code. Exact checks cover 5329 single-block error pairs and all 2304 weight-two Paulis. This corrects a fault on one carrier copy under the stated tensor-product encoding, whereas the Hodge projector alone preserves harmonic logical errors. Physical quantization and syndrome extraction are not supplied by this mapping.

For the conditional engineered dynamics $M = mI$, $K = kL_1$, one prospective ratio is frozen:

$$\omega^2_{\text{gap,natural}}/\omega^2_{\text{vertex,natural}} = (2 - \sqrt{2})/12.$$

The SI calibration intake and covariance propagation are implemented, but no measured trace or unseen test outcome is available. This tests a declared substrate model, not a universal constant or a completed theory of everything. See `analysis/W33_VACUUM_HARMONIC_PROSPECTIVE.md` for provenance, prior ownership, scope regressions and reproduction.

Physical FI prime shadows: a regular $\mathrm{Alt}(5)$ torsor

The cross-repository heterotic calculation fixes the physical anomalous-$U(1)$ direction in the five hypercharge-star coordinates to

$$v = (-5, 3, 1, -5, 6), \qquad \sum_i v_i = 0.$$

The coordinate Weyl group is S_5. The only equality among coordinates is between the two entries -5, so the S_5 stabilizer is the order-two reflection interchanging those positions. That reflection is odd. Hence

$$\mathrm{Stab}_{\mathrm{Alt}(5)}(v) = 1, \qquad |\mathrm{Alt}(5) \cdot v| = 60,$$

and the sixty integral FI orientations form a regular $\mathrm{Alt}(5)$ torsor.

Factoring out the baseline duplicate value, the four distinct entries are $-5, 1, 3, 6$. Their Vandermonde product is

$$6 \cdot 8 \cdot 11 \cdot 2 \cdot 5 \cdot 3 = 15840 = 2^5 3^2 5\, 11.$$

These are exactly the primes at which extra coordinate collisions occur. Direct exhaustive enumeration gives

p	multiplicities	$\mathrm{Stab}_{\mathrm{Alt}(5)}$	orbit	integral fibre
2	$4 + 1$	A_4	5	12
3	$3 + 2$	S_3	10	6
5	$2 + 2 + 1$	C_2	30	2
11	$3 + 1 + 1$	C_3	20	3

while primes outside this collision set preserve the free sixty-state action. In particular,

$$v \bmod 3 = (1, 0, 1, 1, 0)$$

is a literal $3+2$ partition of the five star coordinates, with ten possible images:

$$10 = \binom{5}{3} = [S_5 : S_3 \times S_2].$$

Each such mod-3 selector has six integral FI lifts.

Scope firewall. This theorem lives in the hypercharge-orthogonal *Abelian* A_4 charge module inside the $u(1)^5$ center. The flagship Wilson-line analysis also contains a non-Abelian $SU(5)$ block, but those are distinct certified objects. The common $S_5/(S_3 \times S_2)$ combinatorics is therefore an intertwiner target, not a proved gauge-breaking identification. Likewise the occurrence of $11 = k-1$, the W33 nonbacktracking branching number, is recorded only as an exact arithmetic coincidence until an operator-level bridge is constructed.

The executable witness is `analysis/w33_physical_fi_alt5_prime_shadow_torsor.py`, with frozen certificate `data/w33_physical_fi_alt5_prime_shadow_torsor.json`.

The physical twin-A_4 factors and the index-five E_8 gluing

The recorded flagship bases contain two distinct type-A_4 root systems in the same physical E_8: the Wilson-line $SU(5)$ root system and the hypercharge-orthogonal A_4 organizing the four extra Abelian directions. Their Gram matrices are both C_{A_4} and their cross Gram matrix vanishes. The combined rank is eight, hence

$$\det(C_{A_4} \oplus C_{A_4}) = 25$$

and, because E_8 is unimodular,

$$\boxed{[E_8 : A_4 \oplus A_4] = 5.}$$

Thus the full-rank overlattice quotient is cyclic of order five.

The executable verifier enumerates all 240 E_8 roots and computes their orthogonal projection norms and discriminant classes (c_C, c_G) in the two A_4 factors. The census is

$$20 + 20 + 50 + 50 + 50 + 50 = 240,$$

with mixed class pairs

$$(1,3), \quad (2,1), \quad (3,4), \quad (4,2),$$

so the gluing is the graph

$$\boxed{c_G = 3c_C \pmod 5.}$$

Since the nonzero A_4 weight classes of norms $4/5$ and $6/5$ are the $5, \bar{5}$ and $10, \overline{10}$ Weyl orbits, respectively, the complete adjoint branching recovered from the physical roots is

$$\boxed{248 = (24,1) + (1,24) + (10,5) + (\overline{10},\bar{5}) + (\bar{5},10) + (5,\overline{10})}.$$

Scope firewall. The complementary A_4 is used by the flagship as an organizer of Abelian charges. The lattice theorem does not assert an unbroken second $SU(5)$ gauge factor, nor does it solve the D/F-flat vacuum equations. It explains why the two physical S_5 structures are parallel while remaining orthogonal.

The executable witness is `analysis/w33_physical_twin_a4_e8_index5_gluing.py`.

The physical FI projection realizes the $E_6 \times A_2$ $\mathbb{Z}_3$ grading

The certified anomalous-$U(1)$ projection into the flagship hypercharge-organizer E_8 factor is

$$t_A = -\frac{5}{3}\alpha_2 - \frac{2}{3}\alpha_3 - \frac{1}{3}\alpha_4 - 2\alpha_5.$$

In standard A_4 diagonal coordinates this is

$$h = (-5/3, 1, 1/3, -5/3, 2), \qquad 3h = (-5, 3, 1, -5, 6),$$

so the physical five-star FI vector is recovered exactly. Modulo phases, the order-three exponential has defining multiplicities $3 + 2$. Its organizer A_4 root grading is

$$8_0 + 6_{1/3} + 6_{2/3},$$

with neutral root system $A_2 + A_1$.

On the complete E_8 root system the same physical Cartan projection gives

$$\boxed{240 = 78_0 + 81_{1/3} + 81_{2/3}.}$$

The 78 neutral roots split into nonorthogonal connected components of sizes and ranks

$$(72, 6) \quad \text{and} \quad (6, 2),$$

hence

$$\boxed{\Phi_0 = E_6 \sqcup A_2.}$$

Adding the eight Cartan directions yields the standard adjoint branching

$$\boxed{248 = (78, 1) + (1, 8) + (27, 3) + (\overline{27}, \overline{3})}.$$

Thus the physical FI projection supplies an explicit Cartan representative for the repository's pre-existing abstract $E_6 \times A_2$ root refinement.

Scope firewall. The full anomalous generator also has a nonzero component in the other E_8. This theorem concerns the certified organizer-factor projection t_A. Exponentiating a charge generator defines an exact Lie-theoretic grading; it does not assert that FI dynamics physically generates a Wilson-line holonomy, and it does not solve the D/F-flat vacuum equations.

The executable witness is `analysis/w33_physical_fi_e6_a2_z3_grading.py`.

The FI three-block is the external A_2; the physical $SU(5)$ lies in E_6

Combining the exact physical twin-A_4 embedding with the FI-induced $E_6 + A_2$ grading gives an objectwise root-set routing. Of the eight FI-neutral roots inside the hypercharge-orthogonal organizer A_4, the six roots belonging to its three-block are exactly the six-root external A_2 component. The remaining two roots form an A_1 lying inside the 72-root E_6 component. All 20 roots of the physical Wilson-line $SU(5)$ A_4 also lie in that same E_6 component.

Hence, at root-system level,

$$A_4^{\text{gauge}} + A_1^{\text{FI}} \subset E_6, \qquad A_2^{\text{FI}} = A_2^{\text{external}},$$

with the two internal factors orthogonal and of combined rank five. This is compatible with the standard $SU(5) \times SU(2) \times U(1) \subset E_6$ chain, while the FI three-block is the external $SU(3)$ factor.

Scope firewall. The repository also contains separately constructed W33/affine $SU(3)_{\text{family}}$ actions. The theorem above identifies an exact physical E_8 root A_2, but does not identify it with those canonical family actions without an explicit Weyl/intertwiner map.

The executable witness is `analysis/w33_physical_fi_factor_routing_e6_a2.py`.

Q_ψ matter parity extends to the $E_8 \supset D_8$ involution

The exact E_6 charge decomposition

$$27 = 16_1 + 10_{-2} + 1_4$$

shows that matter parity on the complete 27 is simply

$$P_M = (-1)^{Q_\psi}.$$

The repository's certified Q_ψ spectrum on all 240 E_8 root channels reduces modulo two to

$$240 = 112_{\text{even}} + 128_{\text{odd}}.$$

With the eight Cartan generators fixed, the even Lie algebra has dimension 120. An independent standard-coordinate E_8 reconstruction identifies the 112 even roots with D_8,

$$\{\pm e_i \pm e_j\},$$

and the 128 odd roots with the chiral half-spinor shell. Therefore

$$\boxed{248 = 120 + 128}$$

is the canonical $E_8 \supset SO(16)$ involution branching.

The same parity is respected by every exact E_6 cubic. The 45 cubic triads have only

$$40 \times (-2, 1, 1), \qquad 5 \times (-2, -2, 4)$$

as Q_ψ patterns, so every cubic is matter-parity even. This explains the cross-repository heterotic observation that a dangerous matter-odd MSSM operator can occur in an invariant coupling only after another odd factor, such as the measured odd singlet insertion, is included.

Scope firewall. The 240-channel Q_ψ histograms are owned by the existing E8 metadata pipeline. The lightweight verifier proves the resulting involution class and independently reconstructs the standard D_8/spinor split; it does not yet supply a coordinatewise Weyl map between the archived metadata basis and the standard D_8 gauge.

The executable witness is `analysis/w33_qpsi_matter_parity_e8_d8_bridge.py`.

The FI Z_3 and matter-parity Z_2 form the physicalized Z_6 quotient of the old E_8 Z_{12}

The certified Kummer Z_4 grading restricts to the exact $E_6 \to SO(10) \times U(1)_\psi$ charge

$$27 = 16_1 + 10_{-2} + 1_4.$$

Hence its square is

$$(Z_4^{\text{Kummer}})^2 = (-1)^{Q_\psi} = P_M,$$

the matter-parity involution. The independently measured heterotic FI projection realizes the $E_8 \to E_6 + A_2$ Z_3 factor. Therefore the old $Z_{12} = Z_4 \times Z_3$ common refinement has a physically interpreted $Z_6 = Z_2 \times Z_3$ quotient.

Merging the exact $Z_4 \times Z_3$ joint table by Z_4 parity gives

	0	1	2
$P_M = +$	54	33	33
$P_M = -$	32	48	48

and CRT residue order $0, \ldots, 5$ gives

$$\boxed{248 = 54 + 48 + 33 + 32 + 33 + 48.}$$

The fixed root system is $D_5 + A_2$ with one residual Cartan direction, so

$$\boxed{\mathfrak{g}_0 = \mathfrak{so}_{10} \oplus \mathfrak{sl}_3 \oplus \mathfrak{u}_1}, \qquad \dim \mathfrak{g}_0 = 54.$$

Holonomy firewall. This structural Z_6 is not the flagship physical order-six holonomy. Their adjoint eigen-dimensions are respectively

$$(54, 48, 33, 32, 33, 48) \quad \text{and} \quad (44, 40, 38, 48, 38, 40),$$

with trace-power fingerprints

$$(248, 37, 5, -8, 5, 37) \quad \text{and} \quad (248, -2, 14, -8, 14, -2).$$

They share only their cube conjugacy class: both cubes are D_8 involutions of trace -8. Equality of order six is therefore explicitly not an identification with the Z_6-I compactification holonomy.

The executable witness is `analysis/w33_physical_fi_matter_parity_z6_quotient.py`.

Objectwise parity, the physical family A_2, and explicit D_8 conjugacy

The native cubic-surface carrier independently realizes the matter-parity split. Relative to one cubic line, the other 26 lines divide into the ten meeting lines and sixteen skew lines, hence

$$27 = 1 + 10 + 16.$$

With $Q_\psi(1, 10, 16) = (4, -2, 1)$, matter parity is precisely skewness to the reference line. The 45 tritangents split objectwise as

$$45 = 5(1, 10, 10) + 40(10, 16, 16),$$

so every cubic is parity even.

The physical FI-selected six-root A_2 has now been matched to the canonical CE2/family A_2 by an explicit E_8 Weyl element. In the frozen simple-root gauge one reduced word is

$$(3, 2, 5, 7, 1, 2, 3, 4, 8, 2, 1, 3, 2, 4, 5, 6, 7, 1, 8, 2, 3, 4, 5),$$

using one-based simple-reflection labels. It intertwines the complete $78 + 81 + 81$ root grading grade-for-grade.

The nonzero FI–parity sectors now have objectwise carriers:

$$48 = 16 \times 3, \qquad 33 = (10 + 1) \times 3 = 30 + 3.$$

For the grade-zero odd sector, each of the sixteen 16_1 minuscule weights differs from the unique 1_4 weight by an actual E_6 root of $Q_\psi = -3$; adjoining the negative roots gives

$$32 = 16_{-3} + \overline{16}_{+3}.$$

Finally, the physical θ^3 parity and Q_ψ matter parity are not merely two involutions with fixed algebra D_8. After an exact $SU(9)$-to-standard-E_8 root-lattice identification, the Weyl word

$$(1, 4, 3, 2, 5, 4, 3, 6, 5, 4)$$

maps all 112 physical-even roots to the 112 Q_ψ-even roots and all 128 odd roots to odd roots. Thus the two involutions are explicitly Weyl-conjugate. Their order-six extensions remain distinct, as proved by the different adjoint trace fingerprints already frozen in the preceding section.

Executable witnesses are `analysis/w33_objectwise_matter_parity_cubic_incidence.py`, `analysis/w33_fi_family_a2_weyl_intertwiner.py`, `analysis/w33_z6_objectwise_33_48_32_carrier.py`, and `analysis/w33_physical_theta3_qpsi_d8_weyl_conjugator.py`.

The two physicalized order-six actions are distinct affine-E_8 Kac classes

The structural FI $\times$ matter-parity quotient and the flagship physical holonomy both define certified inner order-six actions on the E_8 adjoint, but their eigenspace fingerprints differ:

$$(54, 48, 33, 32, 33, 48) \qquad \text{versus} \qquad (44, 40, 38, 48, 38, 40).$$

Using the affine highest-root marks in the repository's frozen simple-root ordering,

$$(a_0, \ldots, a_8) = (1, 4, 6, 5, 4, 3, 2, 2, 3),$$

an exhaustive Cartan–Kac classification of all normalized exact order-six inner diagrams finds exactly twenty candidates and selects uniquely

$$\boxed{s_{\mathrm{FI}\times\mathrm{P_M}} = (2, 0, 0, 0, 1, 0, 0, 0, 0)}$$

and

$$\boxed{s_{\mathrm{hol}} = (0, 0, 0, 0, 1, 0, 0, 1, 0)}.$$

Their power ladders are therefore

	g	g^2	g^3
FI $\times$ P_M	$D_5 + A_2 + \mathfrak{u}_1$	$E_6 + A_2$	D_8
holonomy	$D_4 + A_3 + \mathfrak{u}_1$	$D_7 + \mathfrak{u}_1$	D_8.

The fixed dimensions are respectively

$$(54, 86, 120) \qquad \text{and} \qquad (44, 92, 120).$$

Thus the previously certified common D_8 cube is the exact intersection of the two power ladders, while the square already separates the conjugacy classes. Equivalently, both Kac diagrams use the same mark-four finite node; the remaining Kac weight two is carried by the affine node in the structural class and by a finite mark-two node in the holonomy class.

This is the standard Cartan–Kac torsion classification (see M. Reeder, *Enseign. Math.* 56 (2010), 3–47). The executable witness is `analysis/w33_e8_order6_kac_classification.py`.

Scope firewall. This is an exact conjugacy-class theorem inside complex E_8. It neither proves a matter-parity-preserving heterotic D/F-flat vacuum nor identifies the two distinct order-six classes with one another or with additional spacetime orbifold data.

The structural and holonomy Z_6 classes differ by one mark-two coweight phase

In the common affine-E_8 Kac gauge, let

$$S = (2, 0, 0, 0, 1, 0, 0, 0, 0)$$

denote the structural FI $\times$ matter-parity class and

$$H = (0, 0, 0, 0, 1, 0, 0, 1, 0)$$

the flagship holonomy class. Only the eight finite Kac labels determine root phases. Their quotient is therefore the single finite mark-two node, normalized to exact order six as

$$\boxed{R = (4, 0, 0, 0, 0, 0, 0, 1, 0)}.$$

The full 240-root census proves

$$\boxed{\deg_H(r) = \deg_S(r) + \deg_R(r) \pmod 6}$$

for every root, hence in the common maximal torus

$$\boxed{H = S\,R}.$$

The three eigenspace fingerprints are

$$d(S) = (54, 48, 33, 32, 33, 48),$$

$$\boxed{d(R) = (92, 64, 14, 0, 14, 64)},$$

and

$$d(H) = (44, 40, 38, 48, 38, 40).$$

The difference element has power ladder

$$R:\ D_7 + \mathfrak{u}_1, qquad R^2:\ D_7 + \mathfrak{u}_1, qquad R^3:\ D_8,$$

with fixed dimensions $92, 92, 120$, and adjoint trace powers

$$(248, 142, 14, -8, 14, 142).$$

Thus the two physicalized order-six structures share the same mark-four Kac component; one additional mark-two fundamental-coweight phase accounts for their complete root-space difference.

Scope firewall. This is an exact factorization of inner automorphisms in the common complex E_8 Cartan gauge. It does not imply that the heterotic FI dynamics generates the compactification holonomy and does not solve D/F flatness.

The executable witness is `analysis/w33_twin_z6_single_node_difference.py`.

One integer Q_ψ charge generates the E_8 Z_2, Z_3, Z_4, Z_6, and Z_{12} layers

The certified E_8 adjoint charge histogram is

$$Q_\psi: \quad (-4)^3,\ (-3)^{16},\ (-2)^{30},\ (-1)^{48},\ 0^{54},\ 1^{48},\ 2^{30},\ 3^{16},\ 4^3,$$

with the eight Cartan generators included in the neutral count. Reducing this single integer charge gives all of the previously separate discrete gradings:

reduction	adjoint sector dimensions
Q_ψ mod 2	$(120, 128)$
Q_ψ mod 3	$(86, 81, 81)$
Q_ψ mod 4	$(60, 64, 60, 64)$
Q_ψ mod 6	$(54, 48, 33, 32, 33, 48)$
Q_ψ mod 12	$(54, 48, 30, 16, 3, 0, 0, 0, 3, 16, 30, 48)$.

The mod-three statement is channelwise: the neutral E_6 roots have charges $0, \pm 3$, the external A_2 has charge zero, the 81-dimensional grade-one sector has charges $1, -2, 4$, and the grade-two sector has charges $-1, 2, -4$. Hence the canonical $E_6 + A_2$ grading is exactly Q_ψ mod 3. Since the physical FI projection is already Weyl-intertwined with that grading, matter parity is Q_ψ mod 2, and the Kummer grading is Q_ψ mod 4, the Chinese-remainder refinements collapse to one charge law:

$$\boxed{Z_6 = Q_\psi \bmod 6, \qquad Z_{12} = Q_\psi \bmod 12.}$$

Equivalently,

$$g_6 = \exp(2\pi i Q_\psi/6), \qquad g_{12} = \exp(2\pi i Q_\psi/12).$$

This charge spectrum agrees with the standard $E_8 \supset SO(10) \times SU(3) \times U(1)$ adjoint branching.

The executable witness is `analysis/w33_qpsi_mod12_unification.py`.

Scope firewall. This unifies the E_8 Lie/representation gradings. It does not by itself identify the resulting Z_{12} with the independent photonic μ_{12} scalar phase group, and it does not prove a matter-parity-preserving heterotic D/F-flat vacuum.

The E_8 Q_ψ grading has an explicit faithful μ_{12} character

The old E_8 Z_{12} theorem deliberately stopped at equality of orders with the independent qutrit-Clifford scalar phase group μ_{12}. The single-charge theorem now closes the character half of that boundary. Choose a primitive twelfth root ζ_{12} and define

$$\chi: \mathbb{Z}/12\mathbb{Z} \longrightarrow \mu_{12}, \qquad \chi([q]) = \zeta_{12}^q.$$

Because the E_8 grading is exactly Q_ψ mod 12, this is a faithful generator-preserving isomorphism. Its adjoint phase multiplicities are

$$(54, 48, 30, 16, 3, 0, 0, 0, 3, 16, 30, 48),$$

exactly the certified Z_{12} grading dimensions.

The same character turns the exact E_6 cubic charge law into scalar-phase conservation. The 45 cubics occur only with

$$40 \times (-2, 1, 1), \qquad 5 \times (-2, -2, 4),$$

and both charge triples sum to zero. Hence every cubic obeys

$$\chi(q_1)\chi(q_2)\chi(q_3) = 1.$$

Independently, Pass 2799 proves that the scalar phase group of the n-qutrit Clifford group is μ_{12} for every n. Thus the equality of orders has been upgraded to an explicit faithful cyclotomic character.

The executable witness is `analysis/w33_e8_z12_clifford_mu12_character_bridge.py`.

Intertwiner firewall. This is not yet a Hilbert-space/root-space representation intertwiner. Clifford μ_{12} acts as a global scalar center on a qutrit Hilbert space, whereas the E_8 character assigns relative eigenphases to distinct Q_ψ sectors. A physical identification still requires an explicit carrier map conjugating the two actions.

The external A_2 contains two inequivalent order-three E_8 actions

The physical FI grading and the Pass 1147 colour cycle both arise from the same external type-A_2 factor, but they are not the same inner automorphism.

For

$$248 = (78,1) + (1,8) + (27,3) + (\overline{27},\overline{3}),$$

the physical FI element is the central $SU(3)$ phase ωI_3. It acts trivially on the two adjoint blocks and by ω, ω^2 on the two matter blocks, so its adjoint eigendimensions are

$$\boxed{86 + 81 + 81},$$

and its fixed algebra is $E_6 + A_2$.

Pass 1147 instead uses the Weyl Coxeter three-cycle of the same A_2. In the defining triplet its eigenvalues are $1, \omega, \omega^2$, while on the A_2 adjoint they occur with multiplicities $2, 3, 3$. Hence its full E_8 adjoint spectrum is

$$\boxed{134 + 57 + 57},$$

with fixed reductive algebra $E_7 + \mathfrak{u}(1)$.

An exhaustive affine-Kac sweep in the repository's frozen E_8 gauge finds exactly four normalized inner order-three spectra,

$$80 + 84 + 84, \qquad 86 + 81 + 81, \qquad 92 + 78 + 78, \qquad 134 + 57 + 57.$$

The two actions therefore select distinct conjugacy classes. Their unique Kac coordinates in the repository ordering are respectively

$$(0,0,0,0,0,1,0,0,0), \qquad (1,0,0,0,0,0,1,0,0).$$

The executable witness is `analysis/w33_e8_a2_center_vs_coxeter_order3.py`.

Carrier firewall. The Pass 1147 module $81_- \otimes \mathbb{C}[C_3]$ has rank 243 and is not the physical 81-dimensional E_8 grade-one root sector. The two C_3 actions may coexist inside one A_2, but they cannot be substituted for one another.

The measured FI Z_3 is the center character of the qutrit H_{27}

Passes 5727/5730 already realize on the E_8 family multiplicity factor the qutrit Schrödinger pair

$$X|j\rangle = |j+1\rangle, \qquad Z|j\rangle = \omega^j|j\rangle, \qquad ZX = \omega XZ,$$

so $\langle X, Z\rangle = H_{27}$ and

$$[Z, X] = \omega I_3$$

generates its order-three center.

The physical-FI theorem independently proves that the measured organizer-E_8 FI projection acts on

$$248 = (78,1) + (1,8) + (27,3) + (\overline{27},\overline{3})$$

as $1, 1, \omega, \omega^2$. The single-charge theorem identifies the same grading with Q_ψ mod 3. Hence, on the certified family multiplicity factor and its conjugate,

$$\boxed{z_{H_{27}} = z_{\mathrm{FI}} = \exp(2\pi i Q_\psi/3).}$$

The executable witness is `analysis/w33_physical_fi_is_h27_center.py`.

Scope firewall. This identifies the finite central character only. It does not identify the older affine Lie $su(3)$ construction with the full physical family $SU(3)$ Lie algebra, prove a D/F-flat vacuum, or assign observed generations.

The Q_ψ character has an objectwise two-qutrit frame-bundle carrier

Holotrade supplies an exact object dictionary for the E_6 minuscule 27: the 27 complete factorisation frames of two qutrits realize

$$27 = 1_4 + 10_{-2} + 16_1$$

relative to a chosen reference frame. Define

$$D_{12}|F\rangle = \zeta_{12}^{Q_\psi(F)}|F\rangle.$$

Its phase multiplicities are

$$(\zeta_{12}^4)^1, \qquad (\zeta_{12}^{-2})^{10}, \qquad (\zeta_{12})^{16},$$

so D_{12} has exact order twelve.

The 45 factorisation-octet/tritangent triples have only the two exact charge patterns

$$40 \times (-2,1,1), \qquad 5 \times (-2,-2,4),$$

hence every cubic has phase product one.

Each frame is a tensor factorisation of a two-qutrit Hilbert space $\mathcal{H}_F \cong \mathbb{C}^9$. Since the two-qutrit Clifford scalar center is μ_{12}, the formal frame bundle

$$\mathcal{H}_{\mathrm{bundle}} = \bigoplus_{F=1}^{27} \mathcal{H}_F \cong \mathbb{C}^{27} \otimes \mathbb{C}^9$$

carries the explicit fibrewise Clifford-scalar operator

$$\boxed{D_{\mathrm{bundle}} = \bigoplus_F \zeta_{12}^{Q_\psi(F)} I_9.}$$

Single-fibre firewall. One scalar on one $\mathbb{C}^9$ has one eigenphase and therefore cannot realize the three relative frame phases above. The theorem is a frame-bundle/controlled-phase carrier. A noncentral single-two-qutrit Clifford intertwiner remains open.

The physical external A_2 carries an explicit H_{27}

The physical FI theorem selects

$$E_8 \supset (E_6 \times SU(3))/Z_3$$

and identifies its measured order-three FI character with the central $SU(3)$ phase. Pass 1147 supplies the Weyl Coxeter three-cycle of the same external A_2. The remaining qutrit clock can now be isolated directly in the frozen E_8 root gauge.

Search all 3^8 toral $\mathbb{F}_3$ characters, requiring that the character be trivial on all 72 E_6 roots and that its commutator with the A_2 Coxeter shift equal the physical FI center. Exactly three solutions survive:

$$(0,0,0,k,2,2,0,0), \qquad k = 0,1,2.$$

They differ by multiplication by the three FI-center scalars. Hence a pure clock is unique modulo the physical center; choose

$$\boxed{f_Z = (0,0,0,0,2,2,0,0) \pmod 3.}$$

Its adjoint spectrum is $134 + 57 + 57$, and each physical matter shell splits

$$\boxed{81 = 27 + 27 + 27}.$$

For one Coxeter orientation $X = s_\alpha s_\beta$, the complete 240-root check gives

$$XZX^{-1}Z^{-1} = Z_{\mathrm{FI}}.$$

The inverse orientation is the Pass 5727 convention

$$ZX = \omega XZ.$$

Since

$$Z_{\mathrm{FI}} = \exp(2\pi i Q_\psi/3),$$

the shift, clock, and measured FI center generate

$$\boxed{H_{27} = 3_+^{1+2}}$$

inside the same external $SU(3)$ carrier of the certified E_8 embedding.

Scope firewall. This is a finite subgroup/representation theorem. It does not prove that the external $SU(3)$ survives as a low-energy family gauge group, solve D/F flatness, or derive observed masses and mixings.

The regular E_6 H_{27} does not central-product with the physical external H_{27}

The tempting arithmetic

$$27 \cdot 27/3 = 243 = 3^{1+4}$$

would require the central C_3 of the Pass 369/371 Heisenberg group on the E_6 minuscule 27 to equal $Z(E_6)$. It does not.

The Pass 369 group acts regularly on the 27 minuscule weights. Hence every nonidentity element, including its central generator, acts fixed-point-freely and has nontrivial Weyl projection. By contrast a central element of E_6 has trivial Weyl projection and acts by a scalar on the irreducible 27. Therefore

$$Z(H_{27}^{\text{Pass369}}) \neq Z(E_6).$$

Consequently this particular internal H_{27} cannot be glued through the diagonal Z_3 kernel of $(E_6 \times SU(3))/Z_3$ to the center of the physical external-A_2 Heisenberg group. Conditional on an honest order-27 lift of the Pass 369 Weyl subgroup, the intersection with $Z(E_6)$ is trivial, so the two commuting factors generate

$$\boxed{H_{27} \times H_{27}}$$

of order 729, not an extraspecial group of order 243.

Remaining opening. This excludes the already-certified regular Pass 369 torsor from the center-gluing construction. It does not exclude a different $H_{27} \subset E_6$ whose center is literally $Z(E_6)$.

The physical external-A_2 qutrit normalizer is the W33 point stabilizer

The physical external-A_2 theorem supplies

$$H_{27} = \langle X, Z, \omega I \rangle, \qquad ZX = \omega XZ, \qquad \omega I = \exp(2\pi i Q_\psi/3).$$

Pass 5730 gives the standard Fourier and quadratic-phase normalizer actions. On $H_{27}/Z(H_{27}) \cong \mathbb{F}_3^2$ in the basis (X, Z) they are

$$F = \begin{pmatrix} 0 & 2 \\ 1 & 0 \end{pmatrix}, \qquad P = \begin{pmatrix} 1 & 0 \\ 1 & 1 \end{pmatrix}.$$

They generate all of $SL(2,3)$, of order 24, so the finite normalizer has order

$$27 \cdot 24 = 648.$$

Pass 1054 independently computes the selected W33 point stabilizer, extracts its normal extraspecial H_{27}, and records the complete conjugation image of an $SL(2,3)$ complement on the quotient. Re-running that witness yields literally the same set of 24 determinant-one matrices, including the two generators above. Therefore the physical external-A_2 qutrit normalizer and the W33 point stabilizer agree at the exact quotient-action level:

$$\boxed{\text{Stab}_{W33}(p) \cong H_{27} : SL(2,3).}$$

Boundary. No particular 3×3 complex conjugating matrix to the W33 permutation model is serialized here, and the theorem makes no low-energy gauge or hardware claim.

The 81-root matter shell is 27 complete frames times one external qutrit

The exact $E_8 \to E_6 \times A_2$ coordinate decomposition gives

$$81 = 27_{E_6} \times 3_{A_2}$$

root by root. Independently, the two-qutrit frame theorem identifies the cubic-surface 27 with the 27 complete tensor-factorisation frames.

In one frozen matter chart, an anchored complement-Schläfli isomorphism assigns every root a unique label

$$\boxed{(F, a), \qquad F \in \{0, \ldots, 26\}, \quad a \in \mathbb{F}_3.}$$

The cubic law factorizes exactly. The 27 projected weights have 45 zero-sum tritangents. For each tritangent all 3^3 phase assignments are tested; exactly six lift to zero-sum E_8 triples, namely the six permutations of the three distinct phases. Hence

$$\boxed{270 = 45 \cdot 3!}$$

zero-sum matter triples occur, and every one of the 81 roots lies in

$$\boxed{10 = 5 \cdot 2}$$

of them. Cubic root addition therefore enforces the external-qutrit selection rule: one of each phase.

Scope firewall. This is an object-set/root-incidence theorem in a fixed coordinate gauge, not a Hilbert-space factorization of the full adjoint, a Yukawa coefficient, or a vacuum construction.

Trinification supplies the internal H_{27} needed for the two-qutrit Pauli group

The hostile-control theorem excludes the regular Pass 369 Weyl H_{27} from a center-gluing construction, because its center is not $Z(E_6)$. A different internal Heisenberg group is supplied by trinification:

$$E_6 \supset (SU(3)_1 \times SU(3)_2 \times SU(3)_3)/\Delta Z_3,$$

with

$$27 = (3, \bar{3}, 1) \oplus (1, 3, \bar{3}) \oplus (\bar{3}, 1, 3).$$

For center exponents (a, b, c), the three nonets acquire phases

$$(a - b,\ b - c,\ -a + c) \pmod 3.$$

The diagonal $(1, 1, 1)$ is the quotient kernel, while

$$\boxed{z_{E_6} \sim (2, 1, 0)}$$

acts as $(1, 1, 1)$ and therefore as the same scalar ω on the full 27.

With the qutrit convention $ZX = \omega XZ$, define

$$X_{\text{int}} = (X, X, I), \qquad Z_{\text{int}} = (Z^2, Z, I).$$

Then

$$[Z_{\text{int}}, X_{\text{int}}] = (\omega^2 I, \omega I, I) = z_{E_6},$$

so these generate an internal H_{27} whose center is literally $Z(E_6)$.

The physical external-A_2 theorem supplies a second H_{27} with center

$$z_{\text{ext}} = z_{\text{FI}} = \exp(2\pi i Q_\psi/3).$$

The subgroup

$$(E_6 \times SU(3)_{\text{ext}})/\langle (z_{E_6}, z_{\text{ext}}^{-1})\rangle \subset E_8$$

identifies these centers. Since the two factor groups commute before quotienting, their images form

$$\boxed{H_{27} \circ H_{27} = 3_+^{1+4}}, \qquad \boxed{|\cdot| = 243}.$$

The explicit quotient verifier checks exponent 3, center and derived subgroup of order 3, and projective quotient $\mathbb{F}_3^4$ of order 81.

Scope firewall. This is an exact finite subgroup theorem. It does not prove a D/F-flat vacuum, observed family assignment, or hardware implementation.

The explicit E_8 Pauli subgroup projectivizes to canonical $W(3,3)$

The trinification/external-A_2 construction gives

$$G = H_{27}^{\text{int}} \circ H_{27}^{\text{ext}} = 3_+^{1+4} \subset E_8.$$

In the basis

$$v = (b_{\text{int}}, b_{\text{ext}}, a_{\text{int}}, a_{\text{ext}}) \in \mathbb{F}_3^4$$

of $G/Z(G)$, direct commutator evaluation gives

$$[g(v), g(w)] = z^{-\omega(v,w)},$$

where

$$\omega(v,w) = b_{\text{int}} a'_{\text{int}} - a_{\text{int}} b'_{\text{int}} + b_{\text{ext}} a'_{\text{ext}} - a_{\text{ext}} b'_{\text{ext}}.$$

Projectivizing the 80 nonzero quotient vectors gives 40 rays. Two rays are collinear exactly when their original Pauli representatives commute. The resulting graph is

$$\text{SRG}(40, 12, 2, 4)$$

and its maximal commuting classes are exactly 40 isotropic lines of size four. The point table and form agree literally with the repository's canonical two-qutrit W33 verifier.

Hence

$$\boxed{E_8 \supset 3_+^{1+4} \to \mathbb{F}_3^4 \to W(3,3)}$$

is now objectwise in an E_8-derived generator gauge.

All 648 physical qutrit Clifford elements are materialized in the W33 point stabilizer

Fix the Heisenberg lift gauge by

$$X_{\text{phys}} \mapsto x, \qquad Z_{\text{phys}} \mapsto y, \qquad z_{\text{phys}} \mapsto z_{\text{Hess}}^{-1}.$$

For physical normal coordinates $Z^a X^b z^c$, the exact Pass 1054 Hessian coordinates are

$$\boxed{(a, b, c) \mapsto (b, a, -ab - c) \pmod 3}.$$

This map is checked on all 27^2 Heisenberg products.

For each of the 24 matrices in $SL(2, 3)$, choose the unique element of Pass 1054's deterministic split complement with that quotient action. The resulting $27 \times 24 = 648$ normal forms are mapped bijectively to the selected W33 point stabilizer. For every element the degree-40 W33 permutation and degree-27 affine Hessian permutation are serialized. The verifier checks all

$$648^2 = 419904$$

products and hashes the complete multiplication table.

Thus the earlier quotient-action match is upgraded to a complete finite group-element dictionary in a fixed split-complement gauge.

The matter 81 is nine Schrödinger modules, not the Pauli phase space

For the trinification realization of the E_6 minuscule representation, the internal Heisenberg shift has nine three-cycles on the 27 weight rays and the clock supplies the corresponding qutrit phases. Thus

$$27 \downarrow H_{27}^{\text{int}} = 9\,\mathcal{H}_3.$$

Tensoring with the external physical qutrit gives

$$\boxed{(27, 3) \downarrow 3_{+}^{1+4} = 9\,\mathcal{H}_9}.$$

The exact character is

$$\chi(1) = 81, \quad \chi(z) = 81\omega, \quad \chi(z^2) = 81\omega^2,$$

and vanishes on all 240 noncentral elements.

On projective matter weight rays the Pauli subgroup has nine orbits of size nine. By contrast its quotient

$$G/Z(G) \cong \mathbb{F}_3^4$$

is a regular 81-element translation set. Therefore the two appearances of 81 are not equivariantly identical:

$$\boxed{81_{\text{matter}} = 9\,\mathcal{H}_9, \qquad 81_{\text{operators}} = \mathbb{F}_3^4.}$$

The E8-derived Pauli representation has full $Sp(4,3)$ Clifford normalizer

The explicit central-product Pauli subgroup inherits the projective basis

$$(X_{\text{int}}, X_{\text{ext}}, Z_{\text{int}}, Z_{\text{ext}})$$

of $\mathbb{F}_3^4$. Four exact symplectic transvections generate

$$\boxed{|Sp(4,3)| = 51840}.$$

In the same coordinate gauge the phase-specified two-qutrit Clifford lifts satisfy

$$U_T D_x U_T^\dagger = D_{Tx}$$

for all 81 Weyl labels. The verifier checks all four generators, hence 324 conjugation identities, and their projective actions preserve the same 40 rays of the certified E8-to-W33 bridge.

Thus the representation-level normalizer is

$$\boxed{3_+^{1+4} : Sp(4,3)}.$$

Embedding firewall. The Pauli subgroup itself is constructed inside E_8. The present theorem proves the full $Sp(4,3)$ normalizer of its Schrödinger representation and projective phase space; it does not prove that every Clifford lift lies in compact E_8, nor identify $N_{E_8}(3_+^{1+4})$.

The address and operator H_{27} roles are distinct and executable

In physical normal form $Z^a X^b \omega^c$, the regular address Heisenberg group has five distinguished order-three directions

$$\langle \omega \rangle,\ \langle \omega X \rangle,\ \langle \omega Z \rangle,\ \langle ZX \rangle,\ \langle \omega^2 ZX^2 \rangle.$$

Their 45 right cosets form

$$\text{SRG}(27, 10, 1, 5) = GQ(2,4)$$

and map exactly to the 45 tritangents on the complete-factorisation-frame carrier.

After adjoining the external phase C_3, slopes ± 1 over each base direction give ten directions in $H_{27} \times C_3$. Their 270 right cosets are exactly the lifted matter cubics,

$$270 = 45 \cdot 3!,$$

with one of each external phase. The physical Clifford-648 preserves this address geometry, with line orbits $9 + 36$ and, when phase labels are fixed, instruction orbits

$$27 + 27 + 216.$$

The center-correct trinification Heisenberg group has a different role. On

$$27 = (3, \bar{3}, 1) + (1, 3, \bar{3}) + (\bar{3}, 1, 3)$$

there is a basis chart (m, q) with

$$X_{\text{int}}|m,q\rangle = |m, q+1\rangle, \qquad Z_{\text{int}}|m,q\rangle = \omega^q |m,q\rangle.$$

Tensoring the external qutrit gives

$$\boxed{\mathbb{C}^{81} \cong \mathbb{C}^9_{\text{mult}} \otimes \mathbb{C}^3_{\text{int}} \otimes \mathbb{C}^3_{\text{ext}}.}$$

The central-product Pauli group acts as $I_9 \otimes \mathcal{H}_9$, so its generated algebra and commutant are

$$\boxed{I_9 \otimes M_9(\mathbb{C})}, \qquad \boxed{M_9(\mathbb{C}) \otimes I_9}.$$

The two H_{27} actions are not permutation-isomorphic: the center of the address action is fixed-point-free, while the operator center is scalar and fixes all basis rays projectively.

The Clifford gauge uniquely fixes the H_{27} lift and the Q_ψ clock leaves only its center

The preceding address/operator H_{27} certificate fixes five direction subgroups and the matter factorization $\mathbb{C}^{81} \cong \mathbb{C}^9 \otimes \mathbb{C}^3 \otimes \mathbb{C}^3$. An independent replay agrees with every shared count. It also removes the remaining direction-lift ambiguity. In addresses $(a, b, c) = Z^a X^b \omega^c$, the fixed physical $H_{27} : SL(2, 3)$ dictionary has complement suborbits

$$1, 1, 1, 8, 8, 8.$$

Exactly one of the three eight-orbits, after adjoining the two nonidentity central elements, gives $\mathrm{SRG}(27, 10, 1, 5) = GQ(2, 4)$. It uniquely selects the five direction lifts

$$\langle \omega \rangle, \quad \langle \omega X \rangle, \quad \langle \omega Z \rangle, \quad \langle ZX \rangle, \quad \langle \omega^2 ZX^2 \rangle.$$

This is a uniqueness statement relative to the fixed split-complement gauge, not an absolute choice without gauge data. The selected lines and lifted cubics independently replay the landed $9 + 36$ and $27 + 27 + 216$ orbit counts. Even after anchoring the address identity at frame zero, there are exactly $1920 = |W(D_5)|$ incidence isomorphisms to the frozen frame carrier. Selecting the first map is deterministic bookkeeping, not a canonical physical root-gauge intertwiner.

For the landed execution algebra $\mathcal{A}_{\text{exec}} = I_9 \otimes M_9(\mathbb{C})$ with commutant $\mathcal{A}'_{\text{exec}} = M_9(\mathbb{C}) \otimes I_9$, the E_6 charge multiplicities $1_4 + 10_{-2} + 16_1$ give an additional exact test. For $D_{12} = \exp(2\pi i Q_\psi/12)$, exhaustive multiplicity checks give

$$\langle D_{12} \rangle \cap \mathcal{A}'_{\text{exec}} = \langle D_{12}^4 \rangle \cong C_3,$$

the FI/common-H_{27} center; the order-two and order-four shadows lie outside the certified commutant.

Scope firewall. The uniqueness is an address-permutation result with the external phase label held fixed. The nine-dimensional factor is noiseless only relative to the certified Pauli-243 algebra. A full H_{27}-equivariant change of basis is impossible: its rank is at most 9 on the 27-dimensional carriers. On the full scheduler/execution modules every $(H_{27} \times C_3)$-equivariant compiler has rank at most 27 in dimension 81. A subsequent explicit permutation in K-Fourier coordinates preserves 27 operator-compatible coordinates and retypes exactly 54, saturating the $81 - 27$ lower bound. The remaining frontier is to materialize the frozen-root/address-to-Fourier analysis matrix, compose it with the operator chart, and realize those 54 retypings dynamically. The subsequent complete Steiner-chart audit nevertheless closes the monomial normalizer question uniformly: among all 51840 compatible charts, only $D_{12}^{0,4,8}$ normalize the execution algebra.

The Q_ψ clock is compiled by one $GQ(2,4)$ anchor

Let A be the adjacency matrix of the 27-point cubic-surface meet graph. For any anchor a, define

$$\boxed{q_a(i) = 1 + 3\delta_{ai} - 3A_{ai}.}$$

The anchor has charge 4, its ten neighbours have charge -2, and its sixteen nonneighbours have charge 1. Thus every anchor gives

$$27 = 1_4 + 10_{-2} + 16_1.$$

The five tritangents through a have pattern $(-2,-2,4)$. By the generalized quadrangle axiom, each of the other forty tritangents contains exactly one neighbour of a and has pattern $(-2,1,1)$. Hence all 45 cubics conserve Q_ψ directly from incidence.

The six simple reflections generate $W(E_6)$ of order 51840 and act transitively on these 27 clocks. The five reflections fixing the highest-weight anchor have the D_5 Cartan matrix and generate its complete order-1920 stabilizer:

$$\boxed{W(E_6)/W(D_5) = 27.}$$

Consequently, choosing the $SO(10)\times U(1)_\psi$ chart is precisely choosing one minuscule weight/cubic-surface line.

On the address register this gives the executable clock

$$D_{12}(a)|i,p\rangle = \zeta_{12}^{1+3\delta_{ai}-3A_{ai}}|i,p\rangle,$$

using only equality and adjacency predicates. The formula does not select an anchor physically. A full H_{27}-equivariant change of basis to the trinification execution factor is impossible by the sharp rank-9 bound; on Matter81 the corresponding $H_{27}\times C_3$ bound is rank 27. A physical compiler cannot preserve the full symmetry. A subsequent exact K-Fourier-coordinate permutation preserves 27 coordinates and retypes the minimum possible 54; its frozen-root composition and physical realization remain the frontier. The subsequent complete Steiner-atlas audit independently closes the finite monomial normalizer question over all 51840 compatible charts.

The regular address H_{27} and operator H_{27} admit no invertible equivariant basis change

The two landed order-27 Heisenberg actions are not merely different as permutation actions; they are non-isomorphic complex modules. The regular address module decomposes as

$$\mathbf{C}[H_{27}] \cong \bigoplus_{\chi\in\widehat{H_{27}/Z}} \chi \oplus 3V_\omega \oplus 3V_{\omega^2},$$

whereas the center-correct trinification action on the E_6 minuscule 27 is

$$27 \downarrow H_{27}^{\mathrm{op}} = 9V_\omega.$$

Consequently

$$\dim \mathrm{Hom}_{H_{27}}(\mathbf{C}[H_{27}], 9V_\omega) = 27,$$

but every equivariant map has

$$\boxed{\mathrm{rank}\, T \le 9.}$$

The bound is sharp, so no invertible 27×27 H_{27} intertwiner exists.

Equivalently, the address center acts with eigenvalue multiplicities $9+9+9$, while the operator center is scalar on all 27 dimensions. Automorphism twisting cannot remove the obstruction because the center is characteristic.

Scope firewall. This rules out an H_{27}-equivariant frozen-root basis conjugacy between the two landed actions. It does not rule out a non-equivariant coordinate dictionary, a smaller common subgroup, or an enlarged correspondence.

The full 81-state scheduler compiler has equivariant rank ceiling 27

Let

$$K = H_{27}^{\text{address}} \times C_3^{\text{external}}, \qquad |K| = 81.$$

The address chart is the regular K-module on the frozen labels $((a,b,c),p)$. On the operator side, restricting the landed matter-81 carrier to the internal trinification H_{27} and the external qutrit shift gives

$$(9V_\omega) \otimes \mathrm{Reg}(C_3).$$

For each of the three external C_3 characters the regular scheduler supplies three copies of V_ω, while the operator carrier requires nine. Therefore

$$\dim \mathrm{Hom}_K = 3(3 \cdot 9) = 81, \qquad \boxed{\operatorname{rank} T \le 3\big(3\min(3,9)\big) = 27.}$$

No invertible 81×81 K-equivariant compiler exists.

The same obstruction is visible from the characteristic commutator subgroup

$$[K,K] = Z(H_{27}) \times \{0\} \cong C_3.$$

Its nontrivial generator has eigenspaces $27 + 27 + 27$ on the regular address module but is scalar on the operator matter module.

Consequence. The root-address compiler must change symmetry: it can be non-equivariant, equivariant only under a proper common subgroup, or formulated after replacing or enlarging one of the two actions. This theorem does not decide which such compiler is physically selected.

The complete Steiner atlas excludes non-FI Q_ψ normalizers

Let C be the 45×27 support matrix of the Cartan cubic. Exact row reduction over $\mathbb{F}_3$ gives

$$\operatorname{rank} C = 21, \qquad \dim \ker C = 6.$$

Thus $\ker C$ is a ternary $[27,6,12]_3$ conservation code, with exact weight enumerator

$$1 + 72z^{12} + 510z^{18} + 144z^{21} + 2z^{27}.$$

This is distinct from the earlier binary $[27,6,12]_2$ double-six incidence code. Among its $3^6 = 729$ words, 510 have content $9{+}9{+}9$. They split as 240 words with eighteen monochromatic and twenty-seven rainbow cubic terms, and 270 words with twelve monochromatic and thirty-three rainbow terms. After the six colour relabellings these give forty and forty-five partitions, respectively.

The constant word lies in the code. Projectivizing its quotient gives

$$\mathbb{P}(\ker C/\langle \mathbf{1} \rangle) = PG(4,3), \qquad \boxed{121 = 36 + 40 + 45}.$$

The induced order-51840 $W(E_6)$ action preserves a nondegenerate five-dimensional quadratic form. Direct support comparison identifies its norm classes objectwise:

$$Q = 2:\ 36\ \text{double}-\text{sixes}, \qquad Q = 0:\ 40\ \text{Steiner triads}, \qquad Q = 1:\ 45\ \text{tritangents}.$$

The weight-twelve supports are exactly the double-sixes. The forty eighteen-monochromatic partitions are exactly the classical Steiner triads already owned by Part MCCCXCVI and Pass 4870. For each of the other forty-five partitions, its twelve monochromatic cubics are exactly the star of one tritangent. Pass 4863 already owned the abstract $40, 45, 36$ norm-class sizes and the 36-class identification; the common code and the objectwise 40- and 45-class identifications are the increment here. The transpose has nullity 24, so the point-charge six-space and the prior line-holonomy twenty-four-space are the two kernels of the same cubic incidence matrix.

Each partition has six sector assignments and 6^3 shared-factor coordinate labellings. Hence the complete incidence-defined monomial atlas contains

$$40 \cdot 6 \cdot 6^3 = 40 \cdot 1296 = 51840$$

distinct trinification charts. The exact $W(E_6)$ action on one chart has this whole atlas as its orbit with trivial chart stabilizer. Equivalently, the atlas is a regular $W(E_6)$-torsor, while an unordered partition has stabilizer order 1296.

In any chart write a weight as (m, q), with nine-valued multiplicity address m and internal qutrit q; the external qutrit p is unchanged by Q_ψ. A diagonal normalizer of $I_9 \otimes M_9(\mathbb{C})$ must factor across its multiplicity and active registers. Therefore D_{12}^k normalizes precisely when its 9×3 exponent table is additively separable modulo twelve, or equivalently when every anchored additive 2×2 minor vanishes. Exhaustion of all charts gives, for $k = 0, \dots, 11$,

$$(51840, 0, 0, 0, 51840, 0, 0, 0, 51840, 0, 0, 0).$$

Thus

$$\boxed{\langle D_{12} \rangle \cap N(I_9 \otimes M_9) = \langle D_{12}^4 \rangle \cong C_3,}$$

and matter parity D_{12}^6 is not a normalizer in any compatible monomial chart.

The obstruction is nevertheless sharply local. The Hamming distances of the 51,840 parity tables to the 2048 separable binary tables have census

$$1^{5760}\, 5^{34560}\, 6^{11520}.$$

In a best chart only one (m, q) phase cell must be corrected; on Matter81 it is repeated over the three values of p, so the diagonal correction has support three. This finite theorem neither selects a physical chart or vacuum nor proves that the correction is dynamically available. Separate sharp rank bounds exclude an invertible H_{27}-equivariant change of basis ($9 < 27$) and an invertible $H_{27} \times C_3$-equivariant Matter81 compiler ($27 < 81$). A subsequent exact K-Fourier-coordinate permutation preserves 27 coordinates and retypes exactly 54, attaining the lower bound. The remaining frontier is its explicit composition with the frozen root/address and operator bases and a dynamical realization of those retypings.

The maximal address–operator common symmetry is a qutrit plane, with 36 Hesse–Pappus choices

Let

$$K = H_{27}^{\text{address}} \times C_3^{\text{ext}}, \qquad D = [K, K] = Z(H_{27}) \times \{0\}.$$

The regular address character and the landed matter-81 operator character restrict identically to a subgroup $L \leq K$ exactly when $L \cap D = 1$. Such an L injects into $K/D \cong \mathbf{F}_3^3$ as a totally isotropic subspace for the rank-two commutator form, so

$$\boxed{|L| \leq 9.}$$

Exhaustion gives 49 order-nine subgroups, of which exactly

$$\boxed{36}$$

avoid D. All 13 maximal order-27 subgroups contain D, so the bound is sharp and global.

In the fixed physical Clifford lift gauge, the twelve possible noncentral H_{27} cyclic lifts are symplectic-dual to the twelve affine lines of $AG(2,3)$ through

$$\langle d, v\rangle_{\mathrm{symp}} = c - c_0(d).$$

Each safe plane has one of three center lines complementary to D, hence the maximal compiler choices form a 12×3 three-sheet Hesse controller. The fixed-center automorphism image has order 216 and orbit split $12 + 12 + 12$.

There is a second exact incidence theorem. The 36 noncentral C_3 subgroups of K, incident with the 36 maximal safe planes by containment, form a cubic bipartite graph on 72 vertices. It has four connected components of size 18, and every component is the Pappus graph. On one projective direction this is simply

$$c = \alpha + \beta p$$

on nine points $(c, p) \in \mathbf{F}_3^2$: $AG(2,3)$ with one parallel class deleted.

Scope firewall. This is not an identification with the classical 36 doily/double-six carrier: the safe-plane order-three-intersection graph is 17-regular, whereas the established E6/double-six graph is SRG$(36, 20, 10, 12)$. The earlier Witting-packet Pappus theorem also lives on a different carrier (affine-foliation leaf incidence). The result is a finite compiler-symmetry theorem; it selects no physical plane, vacuum, continuum limit, or hardware realization.

The two $36 = 12 \times 3$ Hesse carriers differ only at order three, and Q_8 repairs them

The ordinary Payne/Hesse 36 and the maximal compiler-safe 36 are both invariant under the exact common physical split complement $SL(2,3)$ of order 24, but they are not the same $SL(2,3)$-set. Their orbit splits are

$$36_{\mathrm{ordinary}} = 24 + 4 + 4 + 4, \qquad 36_{\mathrm{safe}} = 8 + 8 + 8 + 4 + 4 + 4.$$

More sharply, their permutation characters agree on every element-order stratum except order three:

$\mathrm{ord}(g)$	1	2	3	4	6
$\lvert C\rvert$	1	1	8	6	8
$\chi_{\mathrm{ordinary}}(g)$	36	12	3	0	3
$\chi_{\mathrm{safe}}(g)$	36	12	9	0	3

so the obstruction is concentrated exactly on the qutrit order-three shear/transvection class.

Restricting to the normal quaternion subgroup

$$Q_8 \triangleleft SL(2,3)$$

removes that class. Both 36-sets then decompose as

$$\boxed{8 + 8 + 8 + 4 + 4 + 4.}$$

The 8-orbits are regular Q_8 torsors and the 4-orbits are copies of $Q_8/Z(Q_8)$. Hence an objectwise Q_8-equivariant bijection exists. One deterministic frozen-gauge bijection is constructed and checked on all $8 \cdot 36 = 288$ action pairs.

The repair is not canonical:

$$\boxed{(3!\,8^3)(3!\,4^3) = 1{,}179{,}648}$$

distinct Q_8-equivariant bijections exist.

Compiler consequence. The address/operator bridge already has an exact quaternionic objectwise core. The remaining obstruction is purely the ternary order-three extension. A future compiler should therefore complete a Q_8-equivariant seed by an order-three phase/shear rule rather than remap the other symmetry sectors. No physical selector among the 1,179,648 gauges is claimed here.

The order-three defect closes by a three-character Fourier compiler

Let $G = SL(2,3)$ be the common physical split complement. The two 36-state carriers decompose as

$$36_{\text{ordinary}} = 4 + 4 + 4 + 24, \qquad 36_{\text{safe}} = 4 + 4 + 4 + 8 + 8 + 8.$$

The three 4-orbits have the same order-six stabilizer and pair objectwise. The ordinary 24-orbit is the regular G-set, while all three safe 8-orbits have the same stabilizer $H \cong C_3$. Hence

$$\boxed{\mathrm{Reg}(G) \cong \bigoplus_{\chi \in \widehat{H}} \mathrm{Ind}_H^G \chi.}$$

The executable compiler realizes this identity directly. For each of the eight right cosets rH and the three characters $j = 0, 1, 2$,

$$|r, j\rangle \longmapsto \sum_{k=0}^{2} \omega^{-jk} |rh^k\rangle.$$

The three safe 8-orbits carry the characters $1, \chi, \chi^2$, with monomial phase

$$g|r, j\rangle = \omega^{jm(g,r)} |r', j\rangle, \qquad gr = r' h^{m(g,r)}.$$

The resulting 36×36 matrix has entries in $\mathbf{Q}(\omega)$, exact rank 36, and 84 nonzero entries. Its columns are exactly orthogonal, with squared norms

$$1^{12} \oplus 3^{24}.$$

All $24^2 \cdot 36 = 20{,}736$ twisted-target representation-law checks and all 24 intertwining identities pass exactly. The order-three target trace moves from 9 before twisting to 3 after twisting, matching the ordinary carrier; the order $1, 2, 4, 6$ character strata were already identical.

Architecture reading. Twelve states compile objectwise. The remaining 24 are eight C_3 fibers whose three Fourier modes are the three character-labelled safe sheets. Thus the finite $SL(2,3)$ representation-level compiler closes after one explicit ternary character twist.

Scope firewall. Multiplying the Fourier columns by $1/\sqrt{3}$ gives the usual complex-unitary normalization. This finite intertwiner does not prove that E8 dynamics, a heterotic vacuum, or a photonic device physically selects the twist.

The Hesse compiler closes on all 270 cubic instructions, while the 81-root lift has a classified eight-dimensional complement

The full physical qutrit Clifford group

$$G = H_{27}^{\text{address}}{:}SL(2,3), \qquad |G| = 648,$$

acts transitively on the ordinary Hesse 36 with stabilizer H_{18}. The safe carrier is three 12-orbits with common stabilizer H_{54}, where

$$H_{18} \triangleleft H_{54}, \qquad H_{54}/H_{18} \cong C_3.$$

The quotient generator is the address center $z = (0,0,1)$. Hence

$$\operatorname{Ind}_{H_{18}}^{G} \mathbf{1} \cong \bigoplus_{\chi \in \widehat{C_3}} \operatorname{Ind}_{H_{54}}^{G} \chi,$$

and the exact 36-state compiler is twelve independent F_3 transforms, with

$$T_{36}^{*} T_{36} = 3 I_{36}.$$

The full cubic-instruction layer splits as

$$45 = 9 + 36, \qquad 270 = 54 + 216,$$

and the compiler lifts exactly as

$$\boxed{T_{270} = I_{54} \oplus (T_{36} \otimes I_6)}.$$

Thus $\operatorname{rank} T_{270} = 270$, its Gram matrix is $I_{54} \oplus 3I_{216}$, and the four Pappus components lift to twenty-four phase-decorated components.

The root-basis lift is different. The ordinary 81×216 cubic-incidence matrix has rank 73, and adding all 54 fiber cubics leaves

$$\boxed{\operatorname{rank}(81 \times 270) = 73}.$$

Its eight-dimensional left kernel is a $K = H_{27} \times C_3$ submodule with exact decomposition

$$\boxed{D_8 \cong \chi_{\text{ext}} \oplus \chi_{\text{ext}}^{2} \oplus V_{\omega} \oplus V_{\omega^2}}, \qquad 8 = 1 + 1 + 3 + 3.$$

Therefore an invertible 81-root compiler must supply precisely these four missing irreducible sectors; cubic rephasings alone cannot do so.

The 1,179,648 Q_8-equivariant objectwise bijections and the six full-Clifford character-to-sheet assignments count different object types; there is no subset reduction between them. The full-Clifford intertwiner space has dimension seven. Inside the induced/Fourier ansatz, the certified sheets $\beta = 0,1,2$ admit six assignments and then the conjugate pair $(0,1,2)$ and $(0,2,1)$ after fixing the neutral sheet. The physical E8 root gauge already fixes

$$z = Z_{\text{FI}} = \exp(2\pi i Q_{\psi}/3) = \omega I.$$

Relative to that frozen orientation the compiler assignment is therefore $(0, 1, 2)$; the other survivor is the complex-conjugate/opposite-Coxeter convention. This is gauge-coordinate closure, not a dynamical chirality or vacuum-selection theorem.

Finally, the exact Clifford compiler lowers to twelve balanced photonic F_3 mixers. With the current inventory of nine tritters it schedules as $9+3$ over two waves, with one active mixer traversal per logical channel. The existing visibility and leakage falsifiers remain unchanged; insertion loss, process fidelity, and the non-Clifford M_{36} injection threshold remain open.

The rank-73 root chart completes as 73 cubic modes plus an exact Fourier–magic dark eight

The eight-dimensional complement of the full 81×270 cubic-incidence transform is

$$D_8 \cong \chi_{\text{ext}} \oplus \chi_{\text{ext}}^2 \oplus V_\omega \oplus V_{\omega^2}.$$

The two one-dimensional summands are the nontrivial external-C_3 Fourier characters. The two three-dimensional summands admit a sharper description. For the four selected noncentral Hesse directions

$$\omega X, \quad \omega Z, \quad ZX, \quad \omega^2 ZX^2,$$

the stacked matrices

$$I + \rho(d) + \rho(d)^2$$

have exact rank two. Their unique common multiplicity ray is

$$\boxed{m = (1, -\omega, 0)^T}.$$

If $|S\rangle = (0, 1, -1)^T$ denotes the repository's qutrit Strange reference, then

$$\boxed{m = ZX^2|S\rangle}.$$

Thus the V_ω dark multiplicity direction is a Clifford image of qutrit Strange magic, and the V_{ω^2} direction carries its complex conjugate. This is a single-qutrit statement and is not the distinct `M36_Q4_RAW` ququart/two-qubit resource.

A deterministic set of 73 pivot columns from the 270 cubic instructions, together with the two external Fourier characters and six Strange/conjugate-Strange matrix-coefficient columns, forms an exact 81×81 matrix over $\mathbf{Q}(\omega)$ with

$$\boxed{\text{rank} = 81}.$$

The dark columns are Hermitian-orthogonal to every cubic-incidence column and have Gram diagonal

$$81,\ 81,\ 54,\ 54,\ 54,\ 54,\ 54,\ 54.$$

Hence the frozen matter/address carrier has the complete hybrid coordinate law

$$\boxed{81 = 73_{\text{cubic}} + 8_{\text{Fourier/magic}}}.$$

The completed chart also makes the address–operator mismatch quantitative. Under the abstract $K = H_{27} \times C_3$ identification, the visible 73-space can map equivariantly to at most 24 operator dimensions and the dark eight to at most 3. Hence

$$\boxed{\text{rank}_{K\text{-equivariant}} \le 27, \qquad 81 - 27 = 54.}$$

Of the dark eight, only the V_ω summand is operator-compatible in the frozen central orientation; χ_{ext}, χ_{ext}^2, and V_{ω^2} lie outside the operator irrep support. Thus the remaining compiler must convert representation type on a 54-dimensional deficit. The equality with the separate 54 fiber-instruction count is recorded only as a count collision, not an objectwise identification.

Scope firewall. This is an invertible coordinate chart on the root/address carrier. It is not an equivariant address–operator conjugacy; the earlier H27 and $H_{27} \times C_3$ rank obstructions still forbid that interpretation. The remaining problem is to match this complete hybrid chart to the $C_{\mathrm{mult}}^9 \otimes C_{\mathrm{int}}^3 \otimes C_{\mathrm{ext}}^3$ trinification operator chart by an explicitly symmetry-changing compiler.

The ramified Clifford compiler lifts to a ternary $[45, 12, 6]_3$ cubic-holonomy code

Let T_{36} be the exact full-Clifford Hesse compiler. Over $\mathbf{Q}(\omega)$ it is a direct sum of twelve three-point Fourier transforms and satisfies

$$T_{36}^* T_{36} = 3I_{36}.$$

Reduce its Eisenstein coefficients at the ramified prime $\pi = 1 - \omega$. Since

$$\mathbf{Z}[\omega]/(1-\omega) \cong \mathbf{F}_3, \qquad \omega \longmapsto 1,$$

each Fourier block collapses to an all-ones matrix. The reduced compiler $\overline{T}_{36}$ has

$$\operatorname{rank}_{\mathbf{F}_3} \overline{T}_{36} = 12, \qquad \dim\ker \overline{T}_{36} = \dim\ker \overline{T}_{36}^T = 24, \qquad \overline{T}_{36}^T \overline{T}_{36} = 0.$$

Its twelve distinct column supports are triples which partition the ordinary 36 tritangents, three triples in each of the four noncentral Hesse directions.

The compiler nullity is on safe-plane coordinates and is not identified with the independent 24-dimensional line kernel of the 27×45 Cartan-cubic incidence matrix. The exact bridge uses only $\operatorname{im} \overline{T}_{36}$. In the frozen Clifford gauge this 12-space lies in the ordinary-36 projection of the cubic line kernel. The incidence submatrix on the distinguished fiber nine has rank nine, so every reduced Fourier triple admits a unique fiber correction.

The twelve corrected relations each contain three ordinary and three fiber tritangents. They span

$$\boxed{R_{12} \subseteq \ker_{\mathbf{F}_3} C_{27\times 45}, \qquad R_{12} \cong [45, 12, 6]_3.}$$

Exhaustion of all $3^{12} = 531441$ words proves that the minimum shell consists of exactly the 24 nonzero scalar multiples of the twelve generator hexads. Every ordinary tritangent occurs once across the basis and every fiber tritangent occurs four times. The generator Gram matrix has rank three and, after grouping by Hesse direction, is

$$(J_4 - I_4) \otimes J_3.$$

More precisely, the fiber nine is the affine plane $H_{27}/Z(H_{27}) \cong AG(2,3)$ and the twelve correction supports are all twelve affine lines, with coefficient 2 on each line. The ordinary parts are disjoint triples, so after permuting coordinates

$$G = \left[, 2A_{AG(2,3)} \;\middle|\; I_{12} \otimes (1,1,1) \right], \qquad \mathrm{wt}(cG) = 3\,\mathrm{wt}(c) + \mathrm{wt}(cA_{AG(2,3)}).$$

This formula independently reproduces the complete enumerator.

Scope firewall. This is a finite arithmetic bridge in a fixed Clifford gauge. The two dimension-24 kernels remain different objects; no $W(E_6)$-invariance, physical noise process, particle assignment, or global coding-theory novelty is claimed. In particular, the parameters $[45, 12, 6]_3$ also occur in a published split-local-ring Gray-image code; equivalence with that unrelated construction has not been tested.

The hybrid matter chart extends to a root-ordered graded E_8 vector atlas

The physical FI element gives the exact grading

$$E_8 = \mathfrak{g}_0 \oplus \mathfrak{g}_1 \oplus \mathfrak{g}_2, \qquad 248 = 86 + 81 + 81,$$

with branching

$$(78, 1) \oplus (1, 8) \oplus (27, 3) \oplus (\overline{27}, \overline{3}).$$

Let B_{81} be the exact hybrid chart consisting of seventy-three cubic pivots and the eight Fourier/magic dark modes. The landed address certificate orders the grade-one roots by the same $K = H_{27} \times C_3$ addresses used by B_{81}. Negating those roots fixes the grade-two row order, and field conjugation fixes its coefficients. Hence the graded vector-space atlas is

$$\boxed{I_{86} \oplus B_{81} \oplus \overline{B}_{81}}, \qquad \text{rank} = 248.$$

Its FI-center trace is

$$86 + 81\omega + 81\omega^2 = 5.$$

The certificate stores all eighty-one addresses and both ordered root lists, so the conjugate block is no longer merely a formal copy.

Scope firewall. This closes the graded vector-space row ordering. The neutral I_{86} block is still relative to the prior $E_6 + A_2$ grading basis, and the Chevalley maps $\mathfrak{g}_1 \times \mathfrak{g}_1 \to \mathfrak{g}_2$, $\mathfrak{g}_2 \times \mathfrak{g}_2 \to \mathfrak{g}_1$, and $\mathfrak{g}_1 \times \mathfrak{g}_2 \to \mathfrak{g}_0$ have not yet been transported. Thus this is not yet a full Lie-algebra compiler and does not select a physical CP orientation.

Subsequent executable transport. The signed current-H27 Chevalley compiler now evaluates all six graded bracket products using explicit source permutations, phases, and a labeled neutral basis. This separate coordinate convention is recorded in its certificate; it is not silently identified with the negated-root row convention above.

The ramified cubic code is a 12-trit affine-holonomy encoder

Let A be the 12×9 line–point incidence matrix of $AG(2, 3)$. After permuting coordinates, the ramified cubic code has generator

$$\boxed{G_{45} = [\, , 2A \mid I_{12} \otimes (1, 1, 1)\,]}.$$

Thus twelve line trits are encoded into nine affine-point holonomy checks and twelve private three-copy payload blocks. For every $c \in \mathbf{F}_3^{12}$,

$$\mathrm{wt}(cG_{45}) = 3\,\mathrm{wt}(c) + \mathrm{wt}(cA).$$

The full code is $[45, 12, 6]_3$. Puncturing two copies in each private block gives

$$G_{21} = [\, , 2A \mid I_{12}\,], \qquad [21, 12, 4]_3.$$

The dual code is $[45, 33, 2]_3$. Its seventy-two weight-two words generate a canonical 24-dimensional sum of twelve local private-triple difference codes; the remaining nine check dimensions are affine point-holonomy checks. The Euclidean hull of the full code has dimension nine.

The minimum shell also determines the complete coordinate-permutation group. Its coordinate degrees recover the intrinsic $9 + 36$ split. Exhaustion of all 9! point permutations gives the full affine-plane incidence group $AGL(2, 3)$ of order 432, while every private triple has an independent S_3 kernel. Consequently

$$\boxed{\mathrm{Aut}_{\mathrm{perm}}(C) \cong S_3^{12} : AGL(2, 3), \qquad |\,\mathrm{Aut}_{\mathrm{perm}}(C)| = 940369969152.}$$

Scope firewall. This is a classical ternary virtual-machine encoder and checker. Its two-error correction and five-error detection statements are exact Hamming guarantees, not a stochastic threshold, hardware benchmark, or quantum-code claim.

Minimal symmetry change, full E_8 atlas, nonlinear cubic transduction, and three physics closures

The address/operator obstruction now has an explicit optimal finite solution in group-Fourier coordinates. Writing the regular $K = H_{27} \times C_3$ module as

$$27\,L \;\oplus\; 27\,S_\omega \;\oplus\; 27\,S_{\omega^2},$$

the operator target is $9V_\omega \otimes \mathrm{Reg}(C_3)$. A deterministic permutation of the Fourier coordinates preserves the 27 S_ω-coordinates and retypes the remaining 54. Thus

$$\boxed{81 = 27_{\text{equivariant}} + 54_{\text{symmetry change}}},$$

and the change is minimal because the exact equivariant-rank ceiling is 27.

The numerical equality with the 54 phase-decorated fiber instructions does not survive representation theory. The fiber sector is the sum of two 27-point quotient permutation modules and has

$$\mathrm{tr}_{54_{\text{fiber}}}(z) = 0,$$

whereas the symmetry-change sector has

$$\mathrm{tr}_{54_{\text{deficit}}}(z) = -27\omega.$$

Their maximum common equivariant rank is only 27.

The completed matter chart also extends to the full physical FI grading:

$$\boxed{248 = 86 + 81 + 81, \qquad A_{248} = I_{86} \oplus B_{81} \oplus \overline{B}_{81}.}$$

The FI-center trace is

$$86 + 81\omega + 81\omega^2 = 5.$$

This is a vector-space atlas; the Chevalley bracket has not yet been transported into these hybrid coordinates.

The dark qutrit resource is operationally distinct from both the qutrit T-state and the ququart M_{36} resource. With

$$|D\rangle = (1, -\omega, 0)^T, \qquad |S\rangle = (0, 1, -1)^T,$$

one has exactly

$$|D\rangle = ZX^2|S\rangle, \qquad XZ^2|D\rangle = |S\rangle.$$

The runtime therefore types a separate `DARK_STRANGE_Q3_RAW` handoff and refuses cross-casts to `HESSE_T_RAW` and `M36_Q4_RAW`.

On the photonic side the 12 Fourier fibers admit a coherent $9 + 3$ serialization: wave zero is post-held and wave one is pre-held, so every one of the 36 channels experiences exactly one F_3 and one matched storage interval. The symbolic coherent path loss is uniformly

$$L_{\mathrm{TRI}} + L_{\mathrm{HOLD}},$$

while physical insertion loss and hold-phase noise remain calibration inputs.

Three further physics tests sharpen the interpretation. First, the H27 representation ring obeys

$$V_\omega \otimes V_{\omega^2} = \bigoplus_9 \chi, \qquad V_{\omega^2} \otimes V_{\omega^2} = 3V_\omega,$$

and cubic Schrodinger products contain three singlets precisely when the external C_3 charges sum to zero. Thus the E6 cubic/Yukawa layer is representation-theoretically capable of crossing a linear symmetry-type boundary, although no nonlinear unitary compiler is yet asserted.

Second, the dark eight is not the external A_2 adjoint: its physical-center trace is -1, not 8. After restricting to H27 it is

$$1 + 1 + 3 + \bar{3},$$

which exactly matches the $SU(3)$ branching of $1+7$ for a G_2 fundamental seven. This is a branching shadow only, not a constructed G_2 action.

Third, the full hybrid E_8 atlas has an exact anti-linear involution

$$C : g_1 \leftrightarrow g_2, \qquad \omega \leftrightarrow \omega^2, \qquad C^2 = 1,$$

with

$$CZ_{\mathrm{FI}}C^{-1} = Z_{\mathrm{FI}}.$$

It exchanges the two compiler orientations and the Strange/conjugate-Strange dark rays. This is a finite charge-conjugation scaffold, not a derivation of observed CP violation.

Signed cubic transport, full hybrid E_8 bracket, Golay Strange lane, G_2 no-go, and process calibration

The canonical signed E_6 cubic now transports objectwise into the current $H_{27} \times C_3$ matter chart through an explicit 27-point gauge conjugacy. The raw Pass1103 Heisenberg coordinate table is not identified with the later physical-Clifford gauge: the un-conjugated 45-line systems overlap in ten triads, including all nine firewall fibers, while the explicit bridge maps all 45 triads and all nine fibers exactly. In the canonical $SU(3)$ phase gauge,

$$[e_{i,a}, e_{j,b}] = d_{ijk}\epsilon_{abc}\,\bar{e}_{k,c}.$$

The 45 signed E_6 triads have sign split $22 + 23$, generate exactly 810 nonzero unordered $g_1 g_1 \to g_2$ root channels, and contain exactly 162 channels on the nine firewall fibers. Every input root has

degree 20 and every conjugate-matter root occurs as output ten times. If B_{81} is the completed $73+8$ hybrid basis, the complete cubic tensor is

$$T_{\mathrm{hyb}} = \overline{B}_{81}^{-1}\, T_{\mathrm{root}}\,(B_{81}\otimes B_{81}).$$

Each root-basis tangent map $D_v(x)=[v,x]$ has rank 20, while the collective image span of all 81 such maps is the full 81-dimensional g_2 block. Thus the Jacobian family reaches all 54 previously identified retyped slots, without claiming that a single root background has rank 54.

The full 248-dimensional finite Lie-algebra compiler is likewise exact. With the source-locked W33-discrete Chevalley table and the archived root/sign gauge,

$$A = I_{86} \oplus (P_1 G_1 B_{81}) \oplus (P_2 G_2 \overline{B}_{81})$$

is invertible over $\mathbb{Q}(\omega)$ and

$$[x,y]_{\mathrm{hyb}} = A^{-1}[Ax, Ay]_{E_8}.$$

All six $\mathbb{Z}_3$ grade products are therefore executable. The source Jacobi verifier exhausts

$$\binom{248}{3} = 2\,511\,496$$

basis triples; exact change of basis transports Jacobi identically to the hybrid atlas.

The dark Strange resource also lands on an internally reconstructed quantum Golay code. The W33 local construction gives $G_{11}=[11,6,5]_3$, and

$$\dim G_{11}^{\perp} = 5, \qquad G_{11}^{\perp} \subset G_{11},$$

so $H_X = H_Z = G_{11}^{\perp}$ gives

$$\boxed{[[11,1,5]]_3}.$$

This is precisely the code type used by the published ternary-Golay Strange-state protocol. The runtime chain is

$$\texttt{DARK_STRANGE_Q3_RAW} \xrightarrow{XZ^2} \texttt{STRANGE_Q3_RAW} \longrightarrow [[11,1,5]]_3.$$

Code algebra is closed, but calibrated input noise, protected syndrome extraction, circuit-level fault coverage, decoder integration and protected non-Clifford injection remain fail-closed physical gates.

The earlier G_2 branching shadow does not extend to a commuting $G_2 \times C_3^{\mathrm{ext}}$ action. The dark external-C_3 spectrum is

$$1^6 + \omega + \omega^2.$$

After choosing either external-charge singlet as the G_2-fixed line, the candidate irreducible seven sees either $1^6+\omega$ or $1^6+\omega^2$, which is non-scalar. This contradicts Schur's lemma for the irreducible complex G_2 seven. A noncommuting larger envelope is not ruled out.

Finally the coherent $9+3$ photonic retimer now has a quantitative design target. For declared normalized process target $F_\star = 0.99$, use

$$F_{\mathrm{model}} \geq F_{\mathrm{TRI}} \cos^2\phi_{\max}\, \mathrm{sech}^2\!\left(\frac{\ln 10}{20} L_{\max}^{\mathrm{dB}}\right).$$

Equal allocation gives

$$F_{\mathrm{TRI}} \geq 0.996655493413, \qquad |\delta\phi| \leq 3.315362654681^\circ, \qquad |\delta L| \leq 0.502880974035 \text{ dB}.$$

These are sufficient component gates, not measurements. The final one-device acceptance test is the reconstructed 36×36 complex transfer matrix

$$F_{\mathrm{HS}}(M) = \frac{|\operatorname{Tr}(U_{\mathrm{ideal}}^{\dagger} M)|^2}{36 \operatorname{Tr}(M^{\dagger} M)} \geq 0.99,$$

together with the previously frozen visibility and radial-leakage falsifiers.

A single cubic background reaches rank 78

For the canonical signed E_6 cubic on the matter block,

$$[e_{i,a}, e_{j,b}] = d_{ijk} \epsilon_{abc}\, \bar{e}_{k,c}, \qquad D_v(x) := [v, x],$$

the Jacobian $D_v : g_1 \to g_2$ is represented, after the paired root-label identification, by an 81×81 skew-symmetric integer matrix and satisfies $D_v v = 0$.

Exact fraction-free elimination gives

v	$\operatorname{rank} D_v$	$\dim \ker D_v$
e_0	20	61
$(1, \ldots, 1)$	54	27
$(1, 2, \ldots, 81)$	54	27
$(1^2, 2^2, \ldots, 81^2)$	78	3

in the canonical $(e6id, \text{external phase})$ coordinate ordering.

Hence one explicit superposed matter background already supplies cubic tangent rank 78, exceeding by 24 the independently proved 54-dimensional symmetry-retyping requirement. Raw nonlinear rank is therefore no longer the obstruction. What remains is the sharper alignment problem: the rank-78 image has not yet been identified with, or projected surjectively onto, the specific 54 Fourier coordinates that must change representation type.

The repeated value 54 for the uniform and linear backgrounds is not promoted to an intertwiner statement: equality with the independent equivariance deficit is presently a dimension collision only.

The cubic interaction covers all 54 retyped Fourier directions

The canonical E_6-id cubic labels are first transported through the explicit 27-point gauge conjugacy to the current physical-Clifford H_{27} address chart. This bridge maps all 45 canonical cubic triads to the current five-direction right-coset system and all nine firewall fibers to the current center spread.

The source regular module decomposes as

$$\operatorname{Reg}(K) = S_1^{(27)} \oplus S_2^{(27)} \oplus L^{(27)},$$

with S_1 the unique operator-compatible isotypic sector. Thus the minimal compiler must access the quotient

$$\operatorname{Reg}(K)/S_1, \qquad \dim = 54.$$

For $D_v(x) = [v, x]$, the correct alignment criterion is

$$\operatorname{rank}(S_1 + \operatorname{Im} D_v) = 81,$$

not merely $\operatorname{rank} D_v \geq 54$.

Constructing the 27 canonical S_1 matrix coefficients from the frozen *qutrit* Schrödinger representation and reducing the resulting $\mathbb{Z}[\omega]$ matrices at both split primes 103 and 109 gives

v	$\operatorname{rank} D_v$	$\operatorname{rank}(S_1 + \operatorname{Im} D_v)$	$\operatorname{rank}_{\text{quotient}}$	$\dim(S_1 \cap \operatorname{Im} D_v)$
e_0	20	47	20	0
$(1, \ldots, 1)$	54	63	36	18
$(1, 2, \ldots, 81)$	54	72	45	9
$(1^2, 2^2, \ldots, 81^2)$	78	81	54	24

at both primes.

Because an 81×81 minor remains nonzero after reduction, it was already nonzero over $\mathbb{Q}(\omega)$. Hence for the explicit quadratic background

$$v_n = (n+1)^2$$

the projection

$$\operatorname{Im} D_v \longrightarrow \operatorname{Reg}(K)/S_1$$

is surjective of rank 54. The finite tangent-level alignment obstruction is therefore closed: one cubic background accesses every Fourier direction that must change representation type.

This does not assert $\operatorname{Im} D_v = S_2 \oplus L$; the image intersects S_1 in dimension 24. Nor does it select the quadratic background as a physical vacuum or exponentiate the tangent map into a hardware gate.

The diagonal phase weld unlocks the full 54-dimensional compiler quotient

After applying the explicit canonical-E_6-id to current physical-Clifford H_{27} gauge bridge, write the scheduler address as

$$K = H_{27} \times C_3^{\text{ext}}, \qquad h = (a, b, c) = Z^a X^b \omega^c,$$

with external phase $p \in \mathbb{F}_3$. The two external slopes of the pure central direction are

$$g_+ = ((0, 0, 1), 1), \qquad g_- = ((0, 0, 1), 2).$$

The diagonal phases

$$\tau_- = c - p, \qquad \tau_+ = c + p \pmod 3$$

are constant on right cosets of g_+ and g_-, respectively.

For the three-level backgrounds

$$v_\pm = 1 + \tau_\pm \in \{1, 2, 3\},$$

each amplitude occurs 27 times. Exact cubic-Jacobian ranks together with the 54-dimensional Fourier-quotient projections are

v	$\operatorname{rank} D_v$	$\operatorname{rank}(\operatorname{Im} D_v \to \operatorname{Reg}(K)/S_1)$
$1 + c$	36	36
$1 + p$	54	36
$1 + (c + p)$	66	54
$1 + (c - p)$	66	54

where the quotient ranks are certified at both split Eisenstein primes 103 and 109.

Thus neither factor by itself supplies the required representation conversion, but either diagonal center–external weld does:

$$\operatorname{rank}(S_1 + \operatorname{Im} D_{v_\pm}) = 81.$$

The missing compiler capacity therefore appears specifically in the *correlation* between the H_{27} center and the external qutrit phase. Neither factor alone is quotient-surjective, while either diagonal weld is.

This is a finite tangent-level weld theorem. It does not select $v_\pm$ as a physical vacuum, determine a coupling coefficient, or infer which conjugate orientation is dynamically preferred.

The canonical cubic and current H_{27} compiler gauges are explicitly conjugate

The canonical signed E_6 cubic and the later physical-Clifford H_{27} address chart use two independently anchored coordinate gauges. Their raw 45-line label sets are not identical: they overlap in only ten triads, although all nine firewall center fibers lie in that overlap.

Fix the bridge by requiring

$$e6id\ 0 \longmapsto (0,0,0) \in H_{27}$$

and by sending the canonical bad-nine spread to the current pure-center spread generated by $(0,0,1)$. Deterministic minimum-remaining-values propagation on the colored $\mathrm{GQ}(2,4)$ incidence graph then fixes a 27-point bijection in 27 search nodes. Under this permutation,

$$\{45 \text{ canonical cubic triads}\} = \{45 \text{ current five-direction } H_{27} \text{ cosets}\},$$

and the nine firewall fibers map exactly to the nine current center cosets.

Consequently every Fourier/compiler statement below uses this explicit bridge before applying the current H_{27} Schrödinger representation. The older Pass1103 coordinate table remains an exact historical Heisenberg gauge, but the two gauges are not conflated.

79.94 Affine-holonomy hull and a quantum-distance obstruction

For the already certified private-triple encoder $G = [2A \mid I_{12} \otimes (1,1,1)]$, where A is the line–point incidence matrix of $\mathrm{AG}(2,3)$, the ternary Gram matrix is

$$GG^{\mathsf{T}} = (J_4 - I_4) \otimes J_3.$$

Its radical consists of coefficient vectors with equal sums in the four parallel classes. The corresponding Euclidean hull is exactly $[45, 9, 12]_3$. Exhaustive enumeration of its 3^9 words finds twenty-four minimum words, precisely the signed differences of parallel-line generators. The three-dimensional nondegenerate quotient has four projective isotropic points, identified with the four affine directions. The punctured encoder's dual is $[21, 9, 5]_3$, with eighteen signed point-star minimum words.

Using the self-orthogonal hull as both CSS check spaces produces $[[45, 27, 2]]_3$. No hull column is zero, excluding dual weight one, while a private-triple difference supplies a dual weight-two word outside the hull. Thus this construction detects but does not correct an arbitrary single qutrit error. These are finite coding statements; no physical noise threshold or spacetime dynamics follows. The witness is `analysis/w33_affine_holonomy_hull.py`; classical Hesse geometry and parent-code parameter prior art are cited in its accompanying report.

Anti-linear conjugation completes the Hessian group and exposes a four-ray finite null cone

The projective one-qutrit Clifford/Hessian symmetry is the already-certified central quotient

$$648/C_3 = 216, \qquad G_{216} \cong \mathbb{F}_3^2 : \mathrm{SL}(2,3).$$

In the frozen normal form $Z^a X^b \omega^c$, coefficient conjugation acts as

$$(a,b,c) \longmapsto (-a,b,-c).$$

Consequently its action on $H_{27}/Z(H_{27}) \cong \mathbb{F}_3^2$ is the determinant-minus-one reflection $\mathrm{diag}(-1,1)$. Adjoining this reflection gives

$$\mathbb{F}_3^2 : \mathrm{GL}(2,3) = \mathrm{AGL}(2,3), \qquad |\mathrm{AGL}(2,3)| = 432,$$

exactly the affine factor independently recovered from the ramified $[45,12,6]_3$ VM code.

On the four affine direction classes

$$(1,0),\ (0,1),\ (1,1),\ (1,2),$$

the determinant-one subgroup has image A_4, while conjugation supplies the odd transposition exchanging the last two classes. The extended image is therefore all of S_4.

Independently, the nine-dimensional hull has a three-dimensional nondegenerate quotient over $\mathbb{F}_3$ with Gram matrix

$$Q = \begin{pmatrix} 0 & 1 & 1 \\ 1 & 0 & 1 \\ 1 & 1 & 0 \end{pmatrix}.$$

Its four projective isotropic rays are

$$[1,0,0],\ [0,1,0],\ [0,0,1],\ [1,1,1].$$

Direct exhaustion gives $|O(Q)| = 48$ and $|SO(Q)| = 24$; the special orthogonal group acts faithfully as S_4 on those four rays. Under the dictionary

$$(1,0) \leftrightarrow [1,0,0], \quad (0,1) \leftrightarrow [0,1,0], \quad (1,1) \leftrightarrow [0,0,1], \quad (1,2) \leftrightarrow [1,1,1],$$

its ray permutations equal the full $\mathrm{GL}(2,3)$ direction permutations.

Thus the four Hesse parallel classes are exactly the projective isotropic set of the affine-hull quotient, and the missing factor two from 216 to 432 is realized by anti-linear qutrit orientation reversal.

This is a finite orthogonal geometry over $\mathbb{F}_3$. It does not supply a continuum Lorentz metric, causal cone, CPT theorem, or measured CP observable.

The executable hybrid algebra carries the split real form $E_{8(8)}$

On the committed source Chevalley basis define

$$\Theta(h_i) = -h_i, \qquad \Theta(e_\alpha) = e_{-\alpha}.$$

The complete root-phase consistency system has 6840 equations of rank 232 on 240 sign variables, and the all-positive root gauge solves it. Direct evaluation of all

$$\binom{248}{2} = 30628$$

unordered basis-pair brackets verifies

$$\Theta([x, y]) = [\Theta x, \Theta y]$$

exactly. Since all source structure constants are integral, composing with Eisenstein conjugation gives an anti-linear involutive Lie automorphism

$$J = \Theta \circ \overline{(\cdot)}.$$

Put $\delta = 1 + 2\omega$, so that $\bar{\delta} = -\delta$ and $\delta^2 = -3$. The J-fixed Cartan directions are δh_i, while each opposite-root pair contributes the fixed real plane

$$e_\alpha + e_{-\alpha}, \qquad \delta(e_\alpha - e_{-\alpha}).$$

The exact source Killing form has a positive-definite Cartan block and

$$K(e_\alpha, e_{-\alpha}) = \begin{cases} +60, & 64 \text{ opposite-root pairs}, \\ -60, & 56 \text{ opposite-root pairs}. \end{cases}$$

Consequently the fixed real form has inertia

$$\boxed{(128_+, 120_-)},$$

and Killing signature +8. It is therefore the split real form

$$\boxed{E_{8(8)}}.$$

The dimensions agree with the classical Cartan decomposition $\mathfrak{e}_{8(8)} = \mathfrak{so}(16) \oplus \mathbf{128}$, but the frozen Chevalley root gauge must not be confused with the standard D_8/spinor root partition. The exact pair census is

	$K = +60$	$K = -60$
D_8-type	32	24
half-spinor	32	32

so the compact $\mathfrak{so}(16)$ appears after taking the fixed real linear combinations, not by retaining one coordinate root type.

Transport to the hybrid atlas also corrects the earlier labelwise charge-conjugation scaffold. All 81 grade-one roots pair with their exact grade-two negatives, but 39 of the frozen row signs differ. Hence the true matter involution is

$$J_{12}(x) = \bar{B}^{-1} D \bar{B}\, \bar{x}, \qquad D = \mathrm{diag}(s_1 s_2),$$

rather than a pointwise grade swap. The neutral block similarly uses Cartan sign reversal and root negation.

This is an exact real-form theorem for the finite Lie-algebra compiler; it does not derive a physical $E_{8(8)}$ gauge theory, gravity, spacetime signature, vacuum, spectrum, or CP observable.

The Hesse directions are the projective nilpotent cone of an explicit $\mathfrak{sl}_2(\mathbf{F}_3)$ quadratic module

The preceding Clifford–Hessian certificate identified the permutation action on the four affine/Hesse directions with the S_4-action on the four isotropic rays of the three-dimensional affine-hull quotient. That statement now has an explicit linear lift.

Write

$$X(a,b,c) = \begin{pmatrix} a & b \\ c & -a \end{pmatrix}, \qquad q_{\mathfrak{sl}_2}(a,b,c) = -\det X = a^2 + bc,$$

and let

$$B = \begin{pmatrix} 2 & 0 & 0 \\ 0 & 0 & 1 \\ 0 & 1 & 0 \end{pmatrix}, \qquad Q = \begin{pmatrix} 0 & 1 & 1 \\ 1 & 0 & 1 \\ 1 & 1 & 0 \end{pmatrix}.$$

The executable witness finds

$$P = \begin{pmatrix} 1 & 1 & 0 \\ 1 & 0 & 2 \\ 2 & 0 & 0 \end{pmatrix}, \qquad \boxed{P^T Q P = 2B}.$$

For $g \in GL(2,3)$, with affine directions treated in the repository's normal-covector convention, define

$$\boxed{\rho(g) = P\ \mathrm{Ad}(g^{-T})\, P^{-1}}.$$

Exhaustion of all 48 elements proves

$$\rho(g)^T Q \rho(g) = Q, \qquad \det \rho(g) = 1, \qquad \ker \rho = \{\pm I_2\},$$

and

$$\boxed{\mathrm{im}\,\rho = SO(Q), \qquad |\,\mathrm{im}\,\rho| = 24.}$$

The $SL(2,3)$ restriction has image of order 12 and induces the existing A_4 direction action; the full $GL(2,3)$ quotient induces the existing S_4 action.

More strongly, the nilpotent-cone parametrisation

$$\nu(u,v) = (-uv, u^2, -v^2)$$

reproduces the certified dictionary without relabeling:

$$(1,0) \mapsto (1,0,0), \quad (0,1) \mapsto (0,1,0), \quad (1,1) \mapsto (0,0,1), \quad (1,2) \mapsto (1,1,1).$$

Thus the four Hesse directions are concretely the four projective nilpotent directions of the determinant form transported to the hull quotient.

There is one useful parity guardrail. The anti-linear phase-space reflection $\kappa = \mathrm{diag}(-1,1)$ has determinant -1 in dimension two and induces the odd four-ray transposition already certified, but its adjoint lift satisfies $\det \rho(\kappa) = +1$. Hence odd permutation parity on the four null rays is not determinant -1 in the three-dimensional orthogonal module.

Parallel real-form boundary. A parallel certificate identifies the exact 248-dimensional anti-linear compiler involution with the split real form $E_{8(8)}$. That characteristic-zero Lie-algebra theorem is separate from this finite $\mathbf{F}_3$ module; no homomorphism or spacetime identification between them is asserted here.

Evidence boundary. This is finite quadratic geometry over $\mathbf{F}_3$. It does not identify the hull quotient with Lorentzian spacetime or derive a continuum spin structure, $Spin(3,1)$, CPT, CP violation, or a physical metric. The executable witness is `analysis/w33_hesse_nullcone_adjoint_intertwiner.py`.

The missing C_2 is the spinor norm

The explicit adjoint lift resolves the apparent parity mismatch between the two-dimensional qutrit phase-space action and the three-dimensional hull orthogonal action. For

$$q(v) = \frac{1}{2} v^T Q v, \qquad Q = \begin{pmatrix} 0 & 1 & 1 \\ 1 & 0 & 1 \\ 1 & 1 & 0 \end{pmatrix}$$

over $\mathbf{F}_3$, enumerate all nine projective orthogonal reflections and all 24 elements of $SO(Q)$. Every $SO(Q)$ element is a product of two reflections, and all reflection decompositions give the same spinor square-class.

For the explicit lift

$$\rho : GL(2,3) \longrightarrow SO(Q)$$

from the preceding theorem, the executable certificate proves

$$\boxed{\theta_{\mathrm{spin}}(\rho(g)) = \det(g) \pmod{(\mathbf{F}_3^{\times})^2}}$$

for all 48 elements $g \in GL(2,3)$. Consequently

$$\rho(SL(2,3)) = \Omega(Q) \cong A_4, \qquad \rho(GL(2,3)) = SO(Q) \cong S_4.$$

In particular, the anti-linear qutrit reflection

$$\kappa = \mathrm{diag}(-1, 1)$$

has $\det \kappa = -1$, while its three-dimensional lift has determinant $+1$ but nontrivial spinor norm. Explicitly,

$$\rho(\kappa) = r_{(1,1,0)} r_{(1,2,0)}, \qquad q(1,1,0) = 1, \quad q(1,2,0) = 2.$$

Thus the correct finite invariant carried by the factor-two extension is the spinor norm, not the determinant of the three-dimensional orthogonal matrix.

Evidence boundary. This is the finite-field spinor norm of an orthogonal group. It does not by itself supply physical fermionic spin, a continuum $Spin/Pin$ structure, Lorentz symmetry, CPT, or spacetime parity.

The complete Hesse affine group carries the spinor-parity bit

The determinant/spinor-norm identity extends over the translation layer. For an affine symmetry

$$x \longmapsto gx + t, \qquad t \in \mathbf{F}_3^2, \quad g \in GL(2,3),$$

define

$$\boxed{\chi(t,g) = \det(g) = \theta_{\mathrm{spin}}(\rho(g)).}$$

Exhaustion of all $432^2 = 186624$ ordered products proves that χ is a surjective homomorphism

$$AGL(2,3) \longrightarrow C_2$$

with

$$\boxed{\ker \chi = \mathbf{F}_3^2 : SL(2,3) = ASL(2,3), \qquad |\ker \chi| = 216.}$$

Hence the projective one-qutrit Clifford/Hessian group is exactly the trivial spinor-parity half of the full Hesse affine group, while the other 216 elements form the determinant-minus-one/anti-linear coset. The nine translations lie in the kernel.

Under the orthogonal lift, the 432 affine elements map in fibers of size $18 = 9 \cdot 2$ onto $SO(Q)$: nine translations times the central pair $\{\pm I_2\}$. Thus

$$\boxed{\chi = \det_{\mathbf{F}_3^2} = \text{spinor norm on } SO(Q)}$$

after pullback.

Central-lift guardrail. The repository separately certifies a nonsplit central C_3 lift of the 216-group of order 648, and records an extended-with-center count 1296. Several distinct 1296-carriers exist in the repository, so no specific 1296 permutation stabilizer is identified with this semilinear extension without an explicit central-extension intertwiner.

Evidence boundary. This is a finite compiler/group character. It is not physical spatial parity, fermion parity, CPT, or a continuum $Pin/Spin$ structure.

The 1296-element point stabilizer is the extended qutrit Clifford group

The central-lift boundary can be closed on the point/Hessian side of the $W(3,3)$ geometry. Adjoin to the native $PSp(4,3)$ point action the multiplier-2 symplectic similitude

$$D = \mathrm{diag}(2,1,2,1).$$

The resulting projective group has order 51840, and the stabilizer of the selected W33 point has order 1296. Inside it, the certified extraspecial Heisenberg subgroup $H_{27} \cong 3_+^{1+2}$ remains normal, and the executable witness constructs a disjoint complement of order 48 whose conjugation action on $H_{27}/Z(H_{27})$ is the complete $GL(2,3)$. Every stabilizer element has a unique $H_{27} \cdot GL(2,3)$ normal form. Hence

$$\boxed{G_{\text{ext}} \cong 3_+^{1+2} : GL(2,3), \qquad |G_{\text{ext}}| = 1296.}$$

The determinant-one half is the already certified one-qutrit Clifford group

$$\boxed{G_{\text{Cliff}} \cong 3_+^{1+2} : SL(2,3), \qquad |G_{\text{Cliff}}| = 648.}$$

There is an important semantic correction at the phase center. If $Z(H_{27}) = \langle z \rangle \cong C_3$, then the 648-group centralizes z, whereas every determinant--1 linear operation acts by

$$\boxed{z \mapsto z^2 = z^{-1}.}$$

Thus this C_3 remains normal in the 1296-group but is not central; indeed the full point stabilizer has trivial center.

Quotienting the normal phase subgroup gives the exact affine groups

$$\boxed{G_{\mathrm{Cliff}}/C_3 \cong ASL(2,3), \qquad G_{\mathrm{ext}}/C_3 \cong AGL(2,3).}$$

The second identification is checked permutation-by-permutation on the nine phase-space points, not inferred from order.

Finally, the finite spinor-parity character lifts through the phase extension:

$$\boxed{\chi(n,g) = \det(g) = \theta_{\mathrm{spin}}(\rho(g)), \qquad \ker\chi = G_{\mathrm{Cliff}}.}$$

Its two fibers have sizes $648 + 648 = 1296$. Thus the same exact C_2 separates the unitary and anti-linear halves at the 216/432, 648/1296, and A_4/S_4 levels.

Side-selection guardrail. This is the W33 point/Hessian stabilizer with extraspecial normal 3^{1+2}. The nonconjugate W33 line/dual stabilizer has elementary-abelian normal 3^3 and is not identified with the physical qutrit Clifford extension.

Evidence boundary. This closes a finite compiler/group boundary. It does not by itself produce physical CPT, continuum parity, a Lorentz *Pin*/*Spin* structure, or particle chirality.

Qutrit Clifford symmetry uniquely saturates the Heisenberg bulk at $p = 3$

The parallel point-stabilizer theorem identifies the full local W33 stabilizer as

$$3^{1+2}_{+} : GL(2,3)$$

of order 1296, with determinant-one Clifford half

$$3^{1+2}_{+} : SL(2,3)$$

of order 648. An independent coordinate audit now welds that statement directly to the older Pass-408 Heisenberg bulk automorphism theorem.

Write the qutrit Pauli normal form as

$$Z^a X^b \omega^c \leftrightarrow (a,b,c),$$

so that

$$(a,b,c)(A,B,C) = (a + A, b + B, c + C - bA) \pmod 3.$$

The gauge

$$\boxed{u = (a,b), \qquad z = c + 2ab}$$

turns this into the alternating-voltage Heisenberg law

$$(u,z)(v,w) = (u + v, z + w + \omega(u,v)),$$

with precisely the Pass-408 form

$$\omega((x,y),(x',y')) = yx' - xy'.$$

Consequently every $M \in GL(2,3)$ acts by

$$(u,z) \longmapsto (Mu, \det(M)z),$$

and composing with left Heisenberg translation gives

$$\boxed{(u,z) \longmapsto \big(Mu + a, \det(M)z - \omega(Mu,a) + c\big),}$$

exactly the frozen Pass-408 graph-automorphism formula. The verifier compares all $1296 \cdot 27 = 34992$ vertex images and obtains the identical complete permutation set.

This comparison exposes an all-odd-prime selection theorem. Pass 408 gives

$$\mathrm{Aut}(\Gamma_p) = H_p : GL(2,p)$$

for every odd prime p, whereas the unitary/anti-unitary extended Clifford normalizer uses

$$ESL(2,p) = \{M \in GL(2,p) : \det M = \pm 1\}.$$

Thus, retaining the Pauli phase centre,

$$\mathrm{ExtCliff}_p = H_p : ESL(2,p).$$

Because the determinant map onto $\mathbb{F}_p^\times$ has equal fibres,

$$\boxed{[\mathrm{Aut}(\Gamma_p) : \mathrm{ExtCliff}_p] = \frac{p-1}{2}.}$$

Hence

$$\boxed{\mathrm{ExtCliff}_p = \mathrm{Aut}(\Gamma_p) \quad \Longleftrightarrow \quad p = 3.}$$

Equivalently, $\mathbb{F}_3^\times = \{\pm 1\}$, so at the qutrit prime every linear similitude is already symplectic or anti-symplectic. At $p = 5$, for example, the determinant classes 2 and 3 supply genuine graph automorphisms outside the extended Clifford group, giving index 2.

Evidence boundary. The Pass-408 full graph group and the current qutrit Clifford action are matched by an explicit coordinate/permutation intertwiner, not by order alone. The odd-prime saturation criterion is a finite symmetry theorem. Treating that criterion as a physical selection law would be an additional assumption; it does not by itself derive particle generations, spacetime dimension, CPT, the Standard Model, or a measured coupling.

The extended qutrit 1296-group is not Shephard–Todd G_{26}

The order alone suggests a tempting comparison with the three-dimensional Hessian complex-reflection group G_{26}, also of order 1296. The comparison is now ruled out by an exact group invariant.

The retained-phase extended qutrit Clifford group certified above is

$$G_{\mathrm{ext}} \cong H_{27} : GL(2,3), \qquad |G_{\mathrm{ext}}| = 1296,$$

with

$$\boxed{Z(G_{\mathrm{ext}}) = 1.}$$

Its determinant-minus-one coset inverts the normal Pauli phase subgroup C_3, so that subgroup is no longer central in the full extension.

By contrast, the standard Shephard–Todd classification gives

$$\boxed{G_{26} \cong C_2 \times \left(3^{1+2}_{-} \cdot SL(2,3)\right),}$$

again of order 1296. In particular G_{26} contains an explicit central involution. Therefore

$$\boxed{G_{\text{ext}} \ncong G_{26}.}$$

The natural quotient pictures also separate: the qutrit group's normal phase-C_3 quotient is $AGL(2,3)$ of order 432, whereas the scalar collineation quotient of G_{26} is the classical Hessian group of order 216.

Boundary. This no-go concerns the full 1296-element anti-linear extension only. It does not rule out the separately known Hessian/G_{25} relationship of the determinant-one 648-element core. Equal orders are not being used as identifications in either direction.

Reversible-quantum saturation, the literal Hessian qutrit, and three physics probes

The extended-Clifford saturation criterion now has a direct quantum-mechanical derivation. In a Weyl–Heisenberg representation,

$$ZX = \omega XZ.$$

A graph similitude with central multiplier m sends the commutator phase by $\omega I \mapsto \omega^m I$. Unitary conjugation fixes scalar phases, while antiunitary conjugation complex-conjugates them. Hence reversible Hilbert-space implementation forces

$$\boxed{m = \pm 1.}$$

Thus the finite saturation principle is precisely that every combinatorial automorphism of the Heisenberg information geometry be realizable as a unitary or antiunitary quantum symmetry.

For the determinant-one core the remaining Hessian comparison is also literal. In one qutrit Hilbert basis, the standard G_{25} reflections are

$$R_1 = P = \operatorname{diag}(1,1,\omega), \qquad R_3 = ZP = \operatorname{diag}(1,\omega,1),$$

and

$$R_2 = F \operatorname{diag}(\omega,1,1) F^{-1},$$

where

$$F = \frac{1}{1+2\omega} \begin{pmatrix} 1 & 1 & 1 \\ 1 & \omega & \omega^2 \\ 1 & \omega^2 & \omega \end{pmatrix}$$

is a global-phase choice of the qutrit Fourier transform. Exact arithmetic gives

$$FXF^{-1} = Z, \qquad PXP^{-1} = XZ.$$

Together with the existing faithful G_{25} enumeration, this identifies the retained-phase Clifford-648 realization with the Hessian reflection matrix group, not merely with an equal-order abstract group.

The local anti-linear involution

$$Z^a X^b Z_{\text{FI}}^c \longmapsto Z^{-a} X^b Z_{\text{FI}}^{-c}$$

also reaches the exact E_8 Lie compiler. The certified anti-linear real structure

$$J = \theta \circ (\omega \mapsto \omega^2), \qquad \theta(h_i) = -h_i, \quad \theta(e_\alpha) = e_{-\alpha},$$

preserves all 30,628 checked basis-pair brackets and obeys $J^2 = 1$. On the external A_2 Heisenberg carrier, root negation leaves Weyl reflections unchanged while coefficient conjugation inverts the qutrit clock and the FI center. Hence the local determinant/spinor C_2 is the restriction of this exact anti-linear E_8 involution. Its fixed real form is the already-certified split form $E_{8(8)}$.

A finite mismatch action can then be defined without fitting. For $q = p^f$, let

$$\psi(z) = \exp\left(\frac{2\pi i}{p} \operatorname{Tr}_{\mathbb{F}_q/\mathbb{F}_p}(z)\right).$$

Average the squared phase mismatch of a multiplier m against the nearer of the two reversible branches $\psi(z)$ and $\psi(-z)$. Additive-character orthogonality gives

$$E(m) = \begin{cases} 0, & m = \pm 1, \\ 2, & m \neq \pm 1. \end{cases}$$

Therefore

$$\boxed{S(q) = \sum_{m \in \mathbb{F}_q^\times} E(m) = 2(q-3),}$$

so the action has a unique odd-prime-power zero at $q = 3$.

The prime-power extension remains exact after Frobenius is included. With basis states indexed by $x \in \mathbb{F}_q$,

$$U_\sigma |x\rangle = |x^p\rangle$$

is a permutation unitary, and trace invariance yields

$$U_\sigma X_u U_\sigma^{-1} = X_{u^p}, \qquad U_\sigma Z_v U_\sigma^{-1} = Z_{v^p}.$$

Thus the reversible semilinear quantum group is

$$H_q : \big(ESL(2,q) : \mathrm{Gal}(\mathbb{F}_q/\mathbb{F}_p)\big),$$

while the graph has $H_q : \Gamma L(2,q)$. Their index is still

$$\boxed{\frac{q-1}{2}},$$

and therefore saturation among all odd prime powers occurs only for

$$\boxed{q = 3.}$$

Outside-box probe 1: a formal Hodge completion. The exact W33 clique complex has cell vector

$$(40, 240, 160, 40)$$

and Betti vector

$$(1, 81, 0, 0),$$

so no internal Hodge star exists. Adjoining the reversed dual chain complex gives

$$K \oplus K^{\vee}: \qquad (C_0, C_1, C_2, C_3) = (80, 400, 400, 80)$$

and

$$(b_0, b_1, b_2, b_3) = (1, 81, 81, 1).$$

The Euler characteristic vanishes and the primal/dual sector swap provides a formal $C_k \leftrightarrow C_{3-k}$ carrier. This does not create a physical metric star by fiat; it identifies a mathematically clean place where the missing electric/magnetic partner sector could live.

Outside-box probe 2: a literal μ_{12} Floquet qutrit. The three Hessian/qutrit reflections form the stroboscopic drive

$$U_F = R_1 R_2 R_3.$$

Exact $\mathbb{Q}(\omega)$ arithmetic gives

$$U_F^{12} = I$$

with no smaller positive period and characteristic polynomial

$$\boxed{\lambda^3 - \omega\lambda^2 + \omega^2\lambda - 1.}$$

Its eigenphases are

$$\boxed{\frac{1}{12}, \quad \frac{4}{12}, \quad \frac{7}{12}}$$

of a full turn. The recurring μ_{12} frame therefore has a concrete three-kick qutrit Floquet representative. This is an internal control clock, not a derivation of physical time.

Outside-box probe 3: a holonomy falsifier. For $p = 5$, a Weyl commutator loop with unit trace phase carries ζ_5. A determinant-2 graph similitude predicts ζ_5^2, whereas a unitary can only preserve ζ_5 and an antiunitary can only produce ζ_5^{-1}. In a balanced reference interferometer

$$P_0(\phi) = \frac{1 + \cos\phi}{2},$$

the reversible branches give approximately 0.654508, while the forbidden multiplier-2 branch gives approximately 0.095492, an absolute contrast about 0.559017. This supplies a direct experimental falsifier of the saturation principle in a higher-dimensional control system.

Evidence boundary. The new results are exact finite group, matrix, Lie-algebra, and chain-complex statements plus one proposed interferometric experiment. They do not derive the Standard Model, gravity, spacetime dimension, observed generations, masses, couplings, CPT, or a physical vacuum. The mismatch functional $S(q)$ and doubled-Hodge construction are candidate physical principles whose necessity remains to be established.

Self-dual Hodge completion, information obstruction, and the global μ_{12} clock

The original W33 clique complex still has

$$(C_0, C_1, C_2, C_3) = (40, 240, 160, 40), \qquad (b_0, b_1, b_2, b_3) = (1, 81, 0, 0),$$

so it does not possess an internal degree-reversing Hodge star. Adjoining its named formal dual gives the self-dual completion

$$\widetilde{K} = K \oplus K^{\vee}$$

with

$$\boxed{C(\widetilde{K}) = (80, 400, 400, 80), \qquad b(\widetilde{K}) = (1, 81, 81, 1).}$$

Giving every paired primal/dual basis cell unit positive weight defines a local algebraic star with one nonzero per row and column,

$$*^2 = 1,$$

and the exact adjoint identity

$$\boxed{\delta_k = *^{-1} d^{\vee}_{3-k} * = B_k = d^{\mathsf{T}}_{k-1}.}$$

This closes the algebraic Hodge carrier but not yet a geometric circumcentric DEC metric: physical primal/dual cell volumes remain to be derived.

The proposed multiplier mismatch

$$E(m) = 0 \quad (m = \pm 1), \qquad E(m) = 2 \quad (m \neq \pm 1)$$

does *not* generate the earlier

$$S(q) = 2(q - 3)$$

as an equilibrium free energy. Its literal canonical partition function is

$$\boxed{Z_q(\beta) = 2 + (q - 3)e^{-2\beta},}$$

with

$$U_q(\beta) = \frac{2(q-3)e^{-2\beta}}{2 + (q-3)e^{-2\beta}}, \qquad F_q(\beta) = -\beta^{-1} \log Z_q(\beta).$$

Instead,

$$\boxed{S(q) = (q - 1)U_q(0),}$$

so the linear defect is the unnormalised infinite-temperature mismatch moment. The simple equilibrium-free-energy selection hypothesis is therefore *refuted*.

A cleaner invariant emerges from the exact group index

$$[G : H] = \frac{q - 1}{2},$$

where G is the full Heisenberg graph symmetry and H the reversible unitary/antiunitary semilinear subgroup. The uniformly distributed obstruction coset has entropy

$$\boxed{H_{\text{obs}} = \log \frac{q - 1}{2}.}$$

Equivalently, if P_Q is uniform on the quantum multipliers $\{\pm 1\}$ and P_G uniform on $\mathbb{F}_q^\times$, then

$$\boxed{D_{\mathrm{KL}}(P_Q \| P_G) = \log \frac{q-1}{2}.}$$

Its total-variation distance is $1 - 2/(q-1)$, and ideal Landauer erasure of the coset label costs

$$\boxed{W_{\min} = k_B T \log \frac{q-1}{2}.}$$

All four obstruction measures vanish simultaneously iff $q = 3$.

The order-twelve Hessian/qutrit Floquet operator also admits a complete E_8 phase census. Its fundamental qutrit phase exponents are

$$(1, 4, 7) \pmod{12}.$$

Using

$$248 = (78, 1) + (1, 8) + (27, 3) + (\overline{27}, \overline{3}),$$

the full exponent histogram is

$$\boxed{0^{80},\ 1^{27},\ 3^2,\ 4^{27},\ 5^{27},\ 6^2,\ 7^{27},\ 8^{27},\ 9^2,\ 11^{27}.}$$

The exact trace sequence $\operatorname{Tr} U^t$, $t = 0, \ldots, 11$, is

$$\boxed{248, 51, 105, 132, 5, 51, 24, 51, 5, 132, 105, 51,}$$

and the fixed-space dimensions for $t = 1, \ldots, 12$ are

$$\boxed{80, 82, 134, 86, 80, 136, 80, 86, 134, 82, 80, 248.}$$

Most importantly,

$$\boxed{U^4|_{\mathfrak{g}_0} = 1, \qquad U^4|_{\mathfrak{g}_1} = \omega, \qquad U^4|_{\mathfrak{g}_2} = \omega^2.}$$

Thus U^4 is exactly the already-certified physical FI/Q_ψ center action.

A falsifiable $p = 5$ control experiment. A unit-trace Weyl commutator at $p = 5$ produces ζ_5. Reversible quantum conjugation permits only $\zeta_5^{\pm 1}$, while a determinant-two graph similitude demands ζ_5^2. In a balanced reference interferometer the ideal port probabilities are

$$0.6545084972 \quad \text{versus} \quad 0.0954915028.$$

Using a design target of visibility 0.965, background 0.01, phase calibration error 1°, visibility uncertainty 0.005, and background uncertainty 0.002, the remaining conservative contrast is approximately 0.51738. The worst-binomial-variance normal proxy requires 94 detected events for 5σ; a proposed engineering target of 128 detected events per setting gives a proxy significance about 5.85σ. These are design calculations, not experimental data.

Outside-box result I: central-character completion. For each nontrivial central character of H_q, finite Stone–von Neumann theory supplies one q-dimensional Schrödinger irrep. Inducing the Heisenberg–Weil representation from

$$H_q : SL(2,q)$$

to

$$H_q : GL(2,q)$$

produces a unitary carrier of dimension

$$\boxed{q(q-1)}$$

containing all $q-1$ nontrivial central-character sectors once. General determinant similitudes are then represented by permutations of these sectors. A charge-conjugate matter/antimatter pair contains only χ and χ^{-1}, hence dimension $2q$. Consequently

$$q(q-1) = 2q \quad \Longleftrightarrow \quad \boxed{q = 3}.$$

The qutrit is therefore uniquely the odd field dimension in which ordinary charge-conjugate doubling already closes the full similitude orbit.

Outside-box result II: a doubled Kramers structure. An antiunitary $T = UK$ with $T^2 = -I$ requires

$$U\overline{U} = -I.$$

Taking determinants makes this impossible in odd complex dimension. Hence a single qutrit and the single 81-dimensional matter grade cannot carry such a structure. On

$$\mathbb{C}^{81} \oplus \overline{\mathbb{C}^{81}},$$

however, define

$$\boxed{T(v,w) = (-\overline{w}, \overline{v}).}$$

Its linear part

$$S = \begin{pmatrix} 0 & -I \\ I & 0 \end{pmatrix}$$

is unitary and obeys $S^2 = -I$, so $T^2 = -I$ exactly on dimension 162. This is a possible quaternionic/Kramers structure on the doubled carrier, not an identification with the already-certified E_8 real involution $J^2 = +1$ or with observed physical time reversal.

Outside-box result III: four Floquet ticks equal one FI step. The qutrit Floquet exponents $(1,4,7)$ obey

$$4(1,4,7) \equiv (4,4,4) \pmod{12},$$

hence

$$\boxed{U_F^4 = \omega I_3.}$$

On the full E_8 branching,

$$\boxed{U_F^4 = 1^{86} \oplus \omega^{81} \oplus (\omega^2)^{81},}$$

exactly reproducing the physical FI/Q_ψ grading. Thus four internal Floquet ticks equal one finite FI-center step and twelve ticks close. This is an exact internal-control identity, not a derivation of physical time.

Evidence boundary. The self-dual completion is algebraic rather than an embedded circumcentric dual; the Landauer reading assumes ideal reversible erasure; the Floquet spectrum is an internal finite-order action; the $p = 5$ experiment is a design protocol without data; and the Kramers and all-character completions are finite representation-theoretic possibilities rather than observed particle, spacetime, gravity, or CPT claims.

Geometric Hodge metric, minimal similitude completion, E8 Kramers no-go, FI pulse compiler, and profiled p=5 likelihood

The formal doubled Hodge carrier can now be given an exact $\mathrm{Aut}(W(3,3))$-invariant piecewise-Euclidean metric. For adjacency matrix A, the normalized rank-24 spherical Gram matrix is

$$\boxed{G = \frac{5A + 20I - 2J}{18},}$$

so adjacent vertices have inner product $1/6$, nonadjacent vertices $-1/9$, and every edge has

$$\boxed{a^2 = \frac{5}{3}}.$$

The symplectic transvection generators act transitively on all 240 edges, so an invariant edge metric has one scale. Every clique-line is a regular tetrahedron. The exact circumcentric Hodge weights at the spherical normalization are

$$\boxed{\left(\frac{5\sqrt{30}}{108}, \frac{\sqrt{30}}{72}, \frac{\sqrt{30}}{15}, \frac{18\sqrt{30}}{25}\right),}$$

all strictly positive. The topology nevertheless remains non-manifold: every triangle and every edge has only one tetrahedral coface, while each vertex lies in four tetrahedra. Thus the result is a positive piecewise-Euclidean circumcentric metric, not a smooth-manifold theorem.

The full Heisenberg similitude group can also be unitarized explicitly once all nontrivial central-character sectors are retained. On

$$\mathcal{H}_{\mathrm{full}} = \bigoplus_{t \in \mathbb{F}_q^\times} \mathcal{H}_t, \qquad \dim \mathcal{H}_{\mathrm{full}} = q(q-1),$$

the finite Fourier and quadratic-chirp generators act blockwise, while a primitive determinant a is represented by

$$\boxed{D_a |t, x\rangle = |a^{-1}t, x\rangle.}$$

This gives

$$(u, v, z) \mapsto (u, av, az).$$

The matrices were materialized at $q = 5$ and $q = 9$, in dimensions

$$\boxed{20 \quad \text{and} \quad 72},$$

with maximum covariance residuals below 6×10^{-15}. The dimensions are minimal: determinant surjectivity makes $\mathbb{F}_q^\times$ act transitively on the $q - 1$ nontrivial center characters, while finite Stone–von Neumann uniqueness assigns each an inequivalent q-dimensional Schrödinger irrep. Hence every full similitude unitary extension obeys

$$\boxed{\dim \mathcal{H} \geq q(q-1)}.$$

The ordinary conjugate pair has dimension $2q$, so it already saturates this completion iff $q = 3$.

The proposed doubled Kramers structure does *not* extend the exact E_8 bracket. Its square would act as $+I$ on $\mathfrak{g}_0$ and $-I$ on both matter grades. But for nonzero $[x, y] \in [\mathfrak{g}_1, \mathfrak{g}_1] \subset \mathfrak{g}_2$,

$$A[x, y] = -[x, y], \qquad [Ax, Ay] = [-x, -y] = [x, y].$$

The committed structure constants contain

$$\boxed{810\ \mathfrak{g}_1\mathfrak{g}_1 \to \mathfrak{g}_2 \quad \text{and} \quad 810\ \mathfrak{g}_2\mathfrak{g}_2 \to \mathfrak{g}_1}$$

nonzero source pairs, giving exactly

$$\boxed{1620}$$

sign violations. Therefore $T^2 = -1$ may only be an independently imposed state-space/Hamiltonian symmetry; it cannot be a Lie automorphism or anti-automorphism of the certified E_8 bracket. The existing $J^2 = +1$ real involution remains bracket-compatible.

The exact FI fourth-root identity also lowers to the existing Holonet qutrit vocabulary. With

$$R_1 = \mathrm{diag}(1, 1, \omega), \qquad R_3 = \mathrm{diag}(1, \omega, 1),$$

and

$$R_2 = F_3\, \mathrm{diag}(\omega, 1, 1) F_3^\dagger,$$

one physical tick of $U_F = R_1 R_2 R_3$ is, right-to-left,

$$\mathrm{phase}_1(120^\circ), \quad F_3^\dagger, \quad \mathrm{phase}_0(120^\circ), \quad F_3, \quad \mathrm{phase}_2(120^\circ).$$

Four ticks therefore require eight $F_3/F_3^\dagger$ traversals and twelve ternary phase masks. Adjacent diagonal masks merge to give seventeen hardware layers. Exact multiplication verifies

$$\boxed{\|U_F^4 - \omega I\| < 2 \times 10^{-15}, \qquad \|U_F^{12} - I\| < 6 \times 10^{-15}.}$$

Because U_F^4 is an isolated-qutrit global phase, readout requires a bypass/reference or controlled-Ramsey arm. A sufficient nearest-Z_3 classification budget is

$$\boxed{12\epsilon_{\mathrm{mask}} + 8\epsilon_{F_3} < 60^\circ.}$$

However, the repository's current symbolic leakage envelopes do not certify the sequence. If the 10% F_3 and 2% phase-mask bounds were independently saturated, four-tick survival would be only

$$\boxed{0.3378}.$$

A uniform twenty-primitive budget giving 90% survival would require per-primitive leakage below approximately

$$\boxed{0.00525}.$$

The hardware admission result is therefore explicitly fail-closed.

Finally, the $p = 5$ holonomy experiment now has a nuisance-profiled count likelihood rather than a Gaussian separation proxy. With

$$p(\phi, V, b, \delta) = \frac{1 + V(1 - b)\cos(\phi + \delta)}{2},$$

the two-port Poisson model profiles to a binomial likelihood after the common rate is removed. The nuisance model is

$$V = 0.965 \pm 0.005, \qquad b = 0.010 \pm 0.002, \qquad \delta = 0 \pm 1^\circ,$$

profiled over the full $\pm 3\sigma$ box. An exact search finds the first detected-event count for which both worst box tails lie below the one-sided 5σ level:

$$\boxed{N_{\min} = 87}.$$

At $N = 87$, the profile rule is

$$\boxed{k \geq 31 \Rightarrow H_A},$$

with worst declared nuisance-box misclassification tails

$$\boxed{1.70 \times 10^{-7}, \qquad 2.15 \times 10^{-7}.}$$

At $N = 128$ those tails fall below 10^{-9}. A deterministic 10^5-trial nuisance-mixture Monte Carlo is retained only as an ordinary power cross-check; rare-tail significance comes from the exact binomial calculation, not Monte Carlo extrapolation.

Evidence boundary. The Hodge metric is piecewise Euclidean on a non-manifold complex; the added similitude sectors are finite representation sectors rather than observed particles; the Kramers extension is ruled out as an E_8 bracket symmetry; the FI pulse program currently fails accumulated-leakage admission; and the $p = 5$ likelihood is a preregisterable design calculation rather than laboratory evidence.

Metricized Maxwell spectrum, all-prime-power similitudes, and generalized anti-linear Z_3 symmetry

The exact circumcentric Hodge weights obtained from the rank-24 spherical embedding are

$$w_0 = \frac{5\sqrt{30}}{108}, \qquad w_1 = \frac{\sqrt{30}}{72}, \qquad w_2 = \frac{\sqrt{30}}{15}, \qquad w_3 = \frac{18\sqrt{30}}{25}.$$

Their adjoint ratios are

$$\boxed{\frac{w_1}{w_0} = \frac{3}{10}, \qquad \frac{w_2}{w_1} = \frac{24}{5}, \qquad \frac{w_3}{w_2} = \frac{54}{5}.}$$

Using the already-certified orthogonal Hodge decomposition of the W33 clique complex therefore gives the weighted spectra

$$L_0 : 0^1 + 3^{24} + (24/5)^{15},$$

$$\boxed{L_1 : 0^{81} + 3^{24} + (24/5)^{15} + (96/5)^{120},}$$

$$L_2 : (96/5)^{120} + (216/5)^{40}, \qquad L_3 : (216/5)^{40}.$$

Across all cochain degrees,

$$\boxed{D^2 : 0^{82} + 3^{48} + (24/5)^{30} + (96/5)^{240} + (216/5)^{80}.}$$

After quotienting the 39 exact gauge directions in C^1, the metricized Maxwell carrier consists of 81 harmonic zero modes and one 120-fold coexact band at

$$\boxed{\lambda_{\text{Maxwell}} = 96/5}.$$

Thus geometric metricization preserves the 81-dimensional topological sector while separating it from a single finite propagating band.

For every odd prime power $q = p^f$, let $\mathcal{H}_t$ be the q-dimensional Schrödinger irrep of the finite Heisenberg group with nontrivial central character $t \in \mathbb{F}_q^\times$. The complete similitude carrier is

$$\boxed{\mathcal{H}_{\text{full}} = \bigoplus_{t \in \mathbb{F}_q^\times} \mathcal{H}_t, \qquad \dim \mathcal{H}_{\text{full}} = q(q-1).}$$

On basis $|t, x\rangle$,

$$X_u|t, x\rangle = |t, x + u\rangle, \qquad Z_v|t, x\rangle = \psi(\mathrm{Tr}(tvx))\,|t, x\rangle,$$

and a determinant-a similitude is represented by

$$\boxed{D_a|t, x\rangle = |a^{-1}t, x\rangle.}$$

Frobenius acts by

$$U_\sigma|t, x\rangle = |t^p, x^p\rangle,$$

so the same carrier realizes the semilinear $H_q : \Gamma L(2, q)$ action.

Restricted to H_q, the exact character is

$$\boxed{\chi(1) = q(q-1), \qquad \chi(0, 0, z \neq 0) = -q, \qquad \chi(u, v, z) = 0 \text{ for } (u, v) \neq (0, 0).}$$

The $q - 1$ central-character sectors are pairwise inequivalent and multiplicity-free, hence

$$\dim \mathrm{End}_{H_q}(\mathcal{H}_{\text{full}}) = q - 1.$$

Because determinant similitudes act transitively on those sectors,

$$\boxed{\mathrm{End}_{H_q : GL(2,q)}(\mathcal{H}_{\text{full}}) = \mathrm{End}_{H_q : \Gamma L(2,q)}(\mathcal{H}_{\text{full}}) = \mathbb{C}.}$$

Thus the full carrier is irreducible. Surjectivity of $\det : GL(2, q) \to \mathbb{F}_q^\times$ and finite Stone–von Neumann uniqueness force the lower bound

$$\boxed{\dim \mathcal{H} \geq q(q-1),}$$

which is attained. Since

$$q(q-1) = 2q \quad \Longleftrightarrow \quad q = 3,$$

ordinary charge-conjugate doubling already supplies the entire minimal similitude carrier only for the qutrit.

Let

$$C = Z_{\text{FI}}$$

be the physical Z_3 grading automorphism on $\mathfrak{g}_0 \oplus \mathfrak{g}_1 \oplus \mathfrak{g}_2$. Coefficient conjugation K is anti-linear with

$$K^2 = 1, \qquad KCK^{-1} = C^{-1}.$$

The certified root-opposition automorphism θ obeys

$$\theta^2 = 1, \qquad \theta C \theta^{-1} = C^{-1}.$$

Hence the split-real involution

$$J = \theta K$$

commutes with C and has $J^2 = 1$.

Any anti-linear automorphism normalizing $\langle C \rangle$ lies in one of the two cosets

$$\boxed{G_0 K \quad \text{or} \quad G_0 J,}$$

where G_0 is the grade-zero complex centralizer. In the more restrictive neutral-fixed scalar-twist subclass, bracket closure gives

$$\beta = \alpha^2, \qquad \alpha\beta = 1, \qquad \alpha^3 = 1.$$

Therefore the six canonical maps are

$$K,\ CK,\ C^2K,\ J,\ CJ,\ C^2J.$$

Their squares are

$$\boxed{K^2 = (CK)^2 = (C^2K)^2 = J^2 = 1,}$$

and

$$\boxed{(CJ)^2 = C^2, \qquad (C^2J)^2 = C.}$$

The last two are anti-linear order-6 symmetries. Thus the exact bracket-compatible replacement for the failed Kramers square $-I$ is an anti-linear generator whose square is the physical finite Z_3 center.

The FI-center implementation also admits exact constant folding. Expanding four explicit Hessian/Floquet ticks uses eight $F_3/F_3^\dagger$ traversals and twelve selective ternary phase masks. But once the target

$$U_F^4 = \omega I_3$$

is certified, its optimal phase-referenced implementation is simply

$$\boxed{0 \text{ mixers} + 1 \text{ uniform signal-arm } 120^\circ \text{ phase.}}$$

Zero mixers is the absolute lower bound. This compression implements the certified target; an experiment intended to verify the four-tick identity must still compare the original long path against the compressed reference.

Finally, the multiplier-obstruction experiment extends sequentially beyond $q = 5$. The hidden label entropy is

$$H_q = \log_2 \frac{q-1}{2}.$$

At the nominal visibility/background model used previously, deterministic posterior-threshold simulations with 5000 trials give mean detected-event counts approximately

$$\boxed{22.58\ (q = 5), \qquad 50.53\ (q = 7).}$$

For

$$\mathbb{F}_9 = \mathbb{F}_3[\alpha]/(\alpha^2 + 1),$$

the quotient

$$\boxed{\mathbb{F}_9^\times/\{\pm 1\} = \mathbb{P}^1(\mathbb{F}_3)}$$

has four projective directions. Three trace probes $z = 1, \alpha, 1+\alpha$ assign them the distinct binary signatures

$$LHL,\ HLL,\ LLH,\ LLL.$$

Cycling those probes gives mean stopping count 35.87, while choosing the next probe by maximum expected posterior entropy reduction lowers the mean to

$$\boxed{16.90}.$$

Thus the log-index is the entropy of the hidden symmetry label, not a universal photon-count law: experimental sample complexity also depends on the measurement-channel KL geometry.

Three outside-box consequences. First, the geometric Dirac-square spectrum contains the exact ladder

$$\boxed{\left\{\frac{24}{5}, \frac{96}{5}, \frac{216}{5}\right\} = \frac{24}{5}\{1^2, 2^2, 3^2\}.}$$

Second, the E_8 matter pair has

$$\boxed{162 = 81 + 81 = 27 \times 6 = 27 \times [3(3-1)],}$$

and its two FI/H27 center characters are exactly ω and ω^2, i.e. every nontrivial qutrit central-character sector required by the minimal full-similitude family carrier. Third, the anti-linear order-6 maps CJ and C^2J satisfy

$$(CJ)^2 = C^2, \qquad (C^2J)^2 = C,$$

providing an exact Z_3-valued semilinear square rather than a Kramers $-I$ square.

Evidence boundary. The weighted spectrum is finite and dimensionless until a physical scale is derived. The all-character carrier is representation theory, not a particle census. The anti-linear normalizer has continuous G_0 dressing; the six maps above are the neutral-fixed scalar subclass. The zero-mixer target implementation does not replace experimental certification of the four-tick identity. The sequential results are simulated nominal optical models, not laboratory significance.

Geometric Dirac modules, qutrit realification, and Z_3-graded antiunitary pairing

For a regular tetrahedron of edge length a, the circumcentric Hodge ratios are

$$\frac{w_1}{w_0} = \frac{1}{2a^2}, \qquad \frac{w_2}{w_1} = \frac{8}{a^2}, \qquad \frac{w_3}{w_2} = \frac{18}{a^2}.$$

Combining these with the relevant unweighted incidence-square eigenvalues $16, 4, 4$ gives

$$\boxed{\frac{8}{a^2}\{1, 4, 9\}.}$$

At the W33 spherical normalization $a^2 = 5/3$ this is exactly

$$\boxed{\left\{\frac{24}{5}, \frac{96}{5}, \frac{216}{5}\right\} = \frac{24}{5}\{1^2, 2^2, 3^2\}.}$$

A fresh GAP decomposition of the signed simplicial chain action gives

$$C_0 = \chi_1 + \chi_7 + \chi_{10},$$

$$C_1 = \chi_7 + \chi_{10} + \chi_{11} + \chi_{16} + \chi_{17} + \chi_{20},$$

$$C_2 = \chi_2 + \chi_3 + 2\chi_{11} + \chi_{16} + \chi_{17}, \qquad C_3 = \chi_2 + \chi_3 + \chi_{11},$$

in the frozen GAP character-table order. Here

$$\boxed{H^1 = \chi_{20}, \qquad \dim H^1 = 81,}$$

and the 120-dimensional coexact carrier is

$$\boxed{M_{120} = \chi_{11} \oplus \chi_{16} \oplus \chi_{17}, \qquad 30 + 45 + 45 = 120.}$$

The same degree-30 constituent χ_{11} occurs in both the 96/5 and 216/5 bands on different cochain degrees. Therefore the $1 : 4 : 9$ spacing is not a function only of a $PSp(4,3)$ Casimir: the finite group controls the multiplicities, while the circumcentric/cochain geometry controls the rung spacing.

Correction: canonical retained-phase Weil lift. The first version of this insert independently normalized each Clifford generator to determinant one. That projective gauge is inadmissible for a retained-phase finite-group identification: cube roots of the determinant insert ninth roots of unity and change the central extension. The corrected finite Weil section is generated by

$$X, \quad Z, \quad e^{i\pi/6}F_3, \quad N = \mathrm{diag}(1, \omega, \omega),$$

up to multiplication by the physical scalar C_3. It closes at order

$$\boxed{648}$$

with Frobenius–Schur indicator zero on its irreducible complex 3-carrier. Coefficient conjugation completes it to the certified

$$\boxed{3_+^{1+2} : GL(2,3), \qquad |G| = 1296.}$$

The full 6D character is irreducible of real type, has

$$\boxed{\nu_6 = +1}, \qquad \boxed{\chi_6(G) \subset \{-3, -2, -1, 0, 1, 2, 3, 6\}},$$

and the group has no elements of order 18. In the rational real basis $q = \sqrt{3}\,\mathrm{Im}\, v$, every $M = A + i\sqrt{3}B$ acts as

$$\boxed{R(M) = \begin{pmatrix} A & -B \\ 3B & A \end{pmatrix} \in GL_6(\mathbb{Q}),}$$

and preserves the positive form

$$\boxed{Q_6 = \mathrm{diag}(3, 3, 3, 1, 1, 1).}$$

The earlier conductor-9 traces and order-18 classes belong to the phase-twisted group produced by the invalid independent $SU(3)$ normalization; they are not characters of the W33 point stabilizer. The separate repository ζ_9 Galois phase-cycle construction remains a distinct arithmetic object.

Let $C = Z_{\mathrm{FI}}$ denote the physical Z_3 grading and let T be antiunitary with

$$[H, C] = 0, \qquad HT = TH, \qquad TC = CT, \qquad T^2 = C^r, \quad r = 1, 2.$$

If $C\psi = \omega\psi$, anti-linearity implies

$$C(T\psi) = T(C\psi) = \bar{\omega}\, T\psi = \omega^2 T\psi.$$

Hence T maps the ω and ω^2 sectors into one another. These sectors are orthogonal because C is unitary, and the two states have equal energy because $HT = TH$. Therefore

$$\boxed{\mathrm{Spec}(H|_{\mathfrak{g}_1}) = \mathrm{Spec}(H|_{\mathfrak{g}_2})}$$

for any Hamiltonian genuinely respecting the certified grading and one of the order-six anti-linear symmetries CJ or C^2J. No Kramers degeneracy is forced in the neutral $C = 1$ sector, where $T^2 = 1$. This is a graded pairing theorem, not ordinary $T^2 = -1$ Kramers theory.

FI reference-arm compiler. The existing frequency-bin packet already contains three 120° Hesse bins, $H1, H4, H7$. With 30 packet frames and two sector sidebands, this provides

$$\boxed{180}$$

120° calibration opportunities per mirror atlas and

$$\boxed{4320}$$

per 24-atlas supercycle. Introduce one phase-referenced primitive

`FI_REFERENCE_ARM_PHASE`

and analyzer phases $0°, 90°, 180°, 270°$. With

$$d_\theta = \frac{N_+ - N_-}{N_+ + N_-},$$

use

$$X = \frac{d_0 - d_{180}}{2}, \qquad Y = \frac{d_{90} - d_{270}}{2},$$
$$\hat{V} = \sqrt{X^2 + Y^2}, \qquad \hat{\phi} = \mathrm{atan2}(Y, X).$$

For the effective two-path phase/dephasing channel,

$$F_e = \frac{1 + V\cos\delta}{2}.$$

The fail-closed design gate

$$F_e \geq 0.99, \qquad |\delta| \leq 2.5°$$

requires

$$\boxed{V \geq 0.9809336315}.$$

The prior $V = 0.965$ benchmark does not meet that gate and is not bench data. The Fisher design requires about 5620 detected events at $V = 0.965$, or 5211 at the admission-floor visibility, so one-detection-per-opportunity operation requires two supercycles.

Nuisance-adaptive multiplier discrimination. A 175-particle nuisance grid over visibility, background, and phase was marginalized online. In 5000 deterministic-seed trials per case, the mean stopping counts were

$$\boxed{22.8716\ (q=5), \qquad 50.8004\ (q=7), \qquad 17.0438\ (q=9).}$$

For $q = 9$,

$$\mathbb{F}_9^\times/\mathbb{F}_3^\times = \mathbb{P}^1(\mathbb{F}_3),$$

and the three trace probes give signatures

$$010, \quad 100, \quad 001, \quad 000.$$

The first three hypotheses each have nominal controlled information

$$D^* = 1.2124412603,$$

while the all-low point has

$$D^* = 0.7469076417.$$

A 0.05° RMS phase random walk per shot changes the simulated mean only to

$$17.0156.$$

Thus the q9 advantage over q7 survives this declared drift model: sample cost is controlled by the available KL/Chernoff information geometry, not hidden label entropy alone.

Three additional finite-physics identities. First, every positive weighted Hodge eigenvalue cancels in the alternating heat trace:

$$\boxed{\mathrm{Str}(e^{-tL}) = \chi(K) = 40 - 240 + 160 - 40 = -80}$$

for every t. Second, the determinant-odd qutrit completion simultaneously realifies the complex Clifford irrep and, in the corrected canonical Weil lift, has a rational character. The previously reported conductor-9 field is a superseded phase-lift artifact. Third, the FI center is exactly a ternary frame symbol $0^\circ, 120^\circ, 240^\circ$; after local phase calibration it can reuse the already-certified optimal 7-tick W33 frame-broadcast tree over all 80 point/line nodes, while the existing gather-plus-broadcast all-reduce costs 14 ticks.

Evidence boundary. The spectral ladder and McKean–Singer identity are finite-complex statements, not a continuum Kaluza–Klein or supersymmetric field theory. The 6D realification is a finite point-stabilizer representation, not an observed particle multiplet. The graded pairing theorem applies only to Hamiltonians that actually respect both symmetries. The FI packet contains no measured counts, and the sequential study is a seeded design simulation rather than a laboratory significance claim.

One diagonal phase correlation switches the Lie closure from 24 dimensions to all of E_8

Lift the four current-H27 three-level backgrounds

$$v_c = 1 + c, \quad v_p = 1 + p, \quad v_+ = 1 + (c + p \bmod 3), \quad v_- = 1 + (c - p \bmod 3)$$

to the signed grade-one and paired signed grade-two root charts of the frozen Chevalley E_8. Closing each pair under the two adjoint generators gives

$g_1 \backslash g_2$	v_c	v_p	v_+	v_-
v_c	24	24	248	248
v_p	24	24	248	248
v_+	248	248	248	248
v_-	248	248	248	248

modulo 103. Every full-rank entry therefore lifts to dimension 248 over $\mathbb{Q}$: the independent modular iterated brackets lift to independent rational Lie words, and the ambient algebra has dimension 248. A matched diagonal pair and both one-sided diagonal orientations replay at the independent prime 109.

The four pure center/external controls were closed with exact rational arithmetic. They generate the same 24-dimensional subalgebra, with inherited grading $24 = 6 + 9 + 9$. Hence a diagonal correlation on either the matter or the antimatter generator is sufficient; matching the two diagonal orientations is not required.

This is an explicit generating-pair theorem for the rational/complex Chevalley algebra. The numerical match $24 = \dim A_2^3$ is now ruled out: an independent exact center/Killing/radical audit gives center dimension one, Killing rank nine, and a 15-dimensional two-step nilpotent radical. The full Levi/module identification and compact-real two-control construction are kept in their separate packets; a physical vacuum and laboratory normalization remain open.

Corrected qutrit Weil lift, all-q Hodge tower, and E_6 extension

The retained-phase qutrit Clifford section must not be obtained by independently normalizing every projective generator to determinant one. That operation can adjoin ninth roots of unity and change the finite central extension. A canonical finite Weil section is generated by

$$X, \quad Z, \quad e^{i\pi/6} F_3, \quad N = \mathrm{diag}(1, \omega, \omega),$$

up to the physical scalar C_3. It closes at order 648. Coefficient conjugation completes it to a 1296-element group with element-order census

$$\boxed{1^1 2^{117} 3^{98} 4^{54} 6^{450} 8^{324} 9^{144} 12^{108}},$$

and no order-18 elements.

The full six-dimensional character is irreducible of real type and rational:

$$\boxed{\chi_6(G) \subset \{-3, -2, -1, 0, 1, 2, 3, 6\}}, \qquad \nu_{FS}(\chi_6) = +1.$$

Writing $M = A + i\sqrt{3}B$ and $q = \sqrt{3}\,\mathrm{Im}\, v$ gives the rational realification

$$\boxed{R(M) = \begin{pmatrix} A & -B \\ 3B & A \end{pmatrix}},$$

which preserves the positive form

$$\boxed{Q_6 = \mathrm{diag}(3,3,3,1,1,1)}.$$

The previously reported conductor-9 cubic character field is therefore a phase-lift artifact of the superseded independent-$SU(3)$ normalization.

For the E_8 grading $86 \oplus 81 \oplus 81$, imposing

$$[H, C] = 0, \qquad HT = TH, \qquad T^2 = C^r, \quad r = 1, 2,$$

puts the Hamiltonian in the normal form

$$\boxed{H = H_0 \oplus H_+ \oplus \overline{H_+}}, \qquad H_0 \in \mathrm{Sym}_{86}(\mathbb{R}), \quad H_+ \in \mathrm{Herm}_{81}(\mathbb{C}).$$

Hence

$$\boxed{P_H(E) = P_0(E) P_+(E)^2},$$

with generic spectrum 86 neutral singlets plus 81 forced matter doublets. The real parameter count falls from 20518 under the Z_3 grading alone to

$$\boxed{\frac{86 \cdot 87}{2} + 81^2 = 10302}$$

after the anti-linear symmetry is imposed.

For the clique complex of $W(q, q)$ with regular simplex edge length a, define

$$\lambda_* = \frac{2(q^2+1)}{(q+1)a^2}, \qquad \lambda_n = \frac{2(q+1)n^2}{a^2}.$$

Then the complete circumcentric Hodge spectrum contains the universal ladder

$$\boxed{\lambda_n = \frac{2(q+1)}{a^2} n^2, \qquad 1 \le n \le q}.$$

Thus the $q = 3$ square ladder is not unique; it is the three-rung member of an all-q theorem. The positive bands cancel pairwise in alternating degree, so

$$\boxed{\mathrm{Str}(e^{-tL}) = 1 - q^4}$$

for every t.

The FI reference-arm decoder was upgraded to a fail-closed Monte Carlo including Poisson counts, dark gates, EOM jitter, efficiency and loss calibration, and three-sigma confidence bounds. The admission condition includes

$$V - 3\sigma_V \ge 0.98093363146, \qquad |\delta| + 3\sigma_\delta \le 2.5^\circ.$$

At 80000 detected events per analyzer quadrature the seeded design accepts a declared good device with probability 0.9969 and accepts none of the five deliberately bad devices in 20000 trials each; the conservative schedule is 80 existing Holonet supercycles.

Finally, GAP identifies the corrected rational matrix group with the certified Pass-408 point stabilizer $3_+^{1+2} : GL(2,3)$ and with the index-40 maximal subgroup $3_+^{1+2} : 2S_4$ of

$$W(E_6) \cong U_4(2).2.$$

The point-stabilizer outer automorphism group has quotient C_3, and the three rational six-dimensional local characters form one outer orbit. Both six-dimensional $W(E_6)$ characters restrict into this orbit. Therefore the corrected qutrit six-carrier extends to the global Weyl representation after an actual outer phase-frame automorphism of the local stabilizer.

Evidence boundary. These statements concern finite groups, finite DEC spectra, and seeded engineering simulations. They do not by themselves derive a continuum Hamiltonian, particle masses, or measured optical performance.

Compact-E_8 control and the trialitarian cubic-Jacobi boundary

Let σ_c be the compact anti-linear conjugation of the committed Chevalley basis:

$$\sigma_c(h_i) = -h_i, \qquad \sigma_c(e_\alpha) = -\operatorname{sgn} K(e_\alpha, e_{-\alpha}) e_{-\alpha}.$$

All 30628 unordered basis-bracket identities hold exactly. For either diagonal H27 background x, the controls

$$A = x + \sigma_c(x), \qquad B = i(x - \sigma_c(x))$$

generate the compact real form $\mathfrak{e}_{8(-248)}$.

This compact-conjugate architecture needs exactly eight root channels. The support

$$\{16, 19, 23, 31, 153, 190, 216, 228\}$$

with amplitudes $(3, 2, 1, 2, 1, 3, 1, 1)$ closes to all 248 dimensions over $\mathbb{Q}$, and its root matrix has determinant -1. Fewer than eight roots cannot generate Cartan rank eight, so

$$\boxed{k_{\min} = 8}.$$

The non-diagonal branch is instead

$$L_{24} \cong \left(\operatorname{Res}_{K/\mathbb{Q}} \mathfrak{sl}_2(K)\right) \ltimes \mathfrak{h}_7,$$

with $\mathfrak{h}_4 \subset \mathfrak{h}_7$ and

$$K = \mathbb{Q}(\theta), \qquad \theta^3 - \theta^2 - 53\theta - 120 = 0, \qquad \operatorname{Disc} K = 94557 = 3 \cdot 43 \cdot 733.$$

This exact Levi–radical structure rules out an A_2^3 trinification identification.

Writing $W_8 = \mathfrak{h}_4/Z$ and $U_6 = \mathfrak{h}_7/\mathfrak{h}_4$, characteristic-zero commutants and associative envelopes give

$$U_6 \cong \operatorname{Res}_{K/\mathbb{Q}}(K^2), \qquad W_8 \cong \operatorname{TensorInd}_{K/\mathbb{Q}}(K^2).$$

The latter is the cubic tensor-induction, or Asai-cube, representation. The actual bracket form supplies the symplectic orthogonal decomposition

$$\mathfrak{h}_7/Z \cong \operatorname{TensorInd}_{K/\mathbb{Q}}(K^2) \mathbin{\widehat{\oplus}} \operatorname{Res}_{K/\mathbb{Q}}(K^2).$$

All 54 rational Levi actions preserve the six-dimensional complement exactly, every cross-bracket with W_8 vanishes, and the resulting 15-vector phase basis has a pivot minor of determinant -1. Hence

$$\mathfrak{h}_7 \cong \mathfrak{h}_4 *_Z \mathfrak{h}_3.$$

This is an exact finite virtual-hardware ABI: the eight-coordinate tensor-induction data lane and six-coordinate restricted-standard control lane commute while sharing one central phase register.

Over a splitting field the Levi is $\mathfrak{sl}_2^3$ and $W_8 = (2, 2, 2)$. The D_4 contact grading has root counts $1, 8, 6, 8, 1$, semisimple grade-zero part A_1^3, and grade-minus-one weights $(\pm 1, \pm 1, \pm 1)$. Together

with the cubic tensor induction and its unique invariant alternating form, this identifies the 18-dimensional core as the abstract derived contact parabolic of the trialitarian D_4 form attached to K. A coordinate conjugating matrix to a chosen rational Chevalley presentation remains open.

The squarefree discriminant makes $3, 43, 733$ the exact bad-reduction locus. At each ramified prime, the centroid has a dual-number factor and the nine-dimensional Levi reduction acquires a three-dimensional square-zero ideal; its Killing rank drops from nine to six.

For the corrected local Weil carrier ρ_6 of the W33 point stabilizer,

$$\mathrm{Ind}_H^{W(E_6)} \rho_6 = 10 \oplus 60 \oplus 80 \oplus 90,$$

while the signed edge module is

$$15 \oplus 24 \oplus 30 \oplus 81 \oplus 90.$$

Their unique common constituent is realized over $\mathbf{F}_{103}$ by an invertible 90×90 matrix T satisfying

$$M_{\mathrm{ind}}(g)T = TM_{\mathrm{edge}}(g)$$

for every frozen $W(E_6)$ generator. The local qutrit fibre therefore has an explicit equivariant route to the global degree-90 constraint sector.

Finally, the rank-optimal eight-root frame has exact chromatic number three for each control. One full cycle requires

$$\boxed{3A + 3B = 6 \text{ microframes} = 432 \text{ ticks}}.$$

Five cycles fill the existing 2160-tick E_8 Coxeter bus.

Boundary. These are exact finite Lie-algebra, arithmetic, representation, and scheduling results. The term Asai cube names cubic tensor induction; no automorphic L-function is asserted to be physically realized. The packet does not derive a continuum action, Standard-Model parameters, black-hole entropy, or laboratory pulse calibration.

79.95 Pass 10941: triality VM five-front closure

The requested rational conjugation of the 18-dimensional core to the *split* D_4 contact parabolic does not exist. Its Levi centroid is the cubic field $K = \mathbb{Q}[\theta]/(\theta^3 - \theta^2 - 53\theta - 120)$, whereas the split A_1^3 centroid is $\mathbb{Q}^3$; their idempotents differ. Two independent rational charts into the correct trialitarian presentation agree on all 103 nonzero brackets and all 5832 ordered Jacobi checks.

The central product $\mathfrak{h}_7 = \mathfrak{h}_4 *_Z \mathfrak{h}_3$ compiles to a seven-mode symplectic ABI. Twenty-four lane-local transvections have Lie closure $\mathfrak{sp}_8 \oplus \mathfrak{sp}_6$ of dimension 57; one bridge transvection gives $\mathfrak{sp}_{14}$ of dimension 105, exactly at both $p = 3$ and $p = 103$. With Heisenberg translations this is the seven-qutrit Clifford/stabilizer instruction set. Universal quantum computation still requires a non-stabilizer resource, but the ideal logical instruction path is now explicit. Every listed transvection lowers exactly into the F_i, P_i, CZ_{ij} alphabet furnished by the fixed ancilla–memory interaction. The programmed branch

$$K_m = 3^{-1/2} X^{-m} FT, \qquad T = \mathrm{diag}(1, \zeta_9, \zeta_9^{-1}),$$

therefore adds T on any of the seven modes, giving approximately universal seven-qutrit Clifford+T. Moreover its analyzer kets obey the exact identity $|b_m\rangle = Z^{-m}|M_T^*\rangle$ for $|M_T\rangle = T|+\rangle$; analyzer programming relocates the ninth-root magic resource rather than erasing it. This is an ideal-resource compiler theorem. A protected analyzer or endogenous magic factory, the physical photon–memory interaction, and a fault-tolerance threshold remain open. Rank-one stabilizer outputs are not used.

The common W_{90} also lifts beyond the earlier $\mathbb{F}_{103}$ witness. On the signed-edge lattice the primitive integral central operator A satisfies

$$A^2 = 48A, \qquad \operatorname{tr}(A) = 4320, \qquad \operatorname{rank}_{\mathbb{Q}} A = 90.$$

Thus $A\mathbb{Z}^{240}$ is a $W(E_6)$-stable integral target lattice. Its ranks modulo $2, 3, 5, 7, 103$ are respectively $14, 25, 90, 90, 90$, exposing the bad-prime boundary without a characteristic-zero obstruction.

At each ramified prime $3, 43, 733$, the centroid word becomes $(a, \dot{a}, c) \in \mathbb{F}_p[\epsilon]/(\epsilon^2) \times \mathbb{F}_p$. Exact opcodes implement addition, multiplication, inversion, Horner evaluation, and composition; 192 polynomial and 192 chain-rule checks pass. Finally, the Killing-normalized compact-root schedule has microframe weights $(4, 5, 5, 4, 5, 5)$. For the declared reference area $\theta_0 = \pi/2$, the Duhamel bound gives $\|\widetilde{U} - U\| \le \exp(28\theta_0\rho) - 1$; a one-percent target requires $\rho \le 2.2623490581 \times 10^{-4}$. The separate declared survival target is 0.90 per cycle. These are falsifiable engineering requirements, not device measurements or predictions.

79.96 Pass 10942: the dark Strange ray opens a metaplectic universal port

The certified dark H27 ray is Clifford-equivalent to the canonical qutrit Strange state $|S\rangle = (|1\rangle - |2\rangle)/\sqrt{2}$. An exact replay of the two stabilizer reductions in the repository's Pauli convention gives

$$|S\rangle^{\otimes 2} \xrightarrow[1/2]{Z_1 Z_2 = 1} |N\rangle, \qquad |N\rangle^{\otimes 2} \xrightarrow[1/4]{\omega X_1 X_2 = 1} X^2 |U_Z(\pi/3, 2\pi/3)\rangle.$$

The Pauli correction $X^2 Z$ yields $|R\rangle = R|+\rangle = (|0\rangle + |1\rangle - |2\rangle)/\sqrt{3}$ for $R = \operatorname{diag}(1, 1, -1)$. A pure four-Strange batch succeeds with probability $1/16$; buffering successful Norell intermediates costs 32 Strange states per R state on average.

Controlled-X^2 injection has exact branches $K_m = 3^{-1/2} R X^{-m}$. Pauli tracking gives the three conjugate reflections $X^m R X^{-m}$, whose projective closure has order four. Repeat until the desired branch succeeds consumes three R resources on average. Hence the buffered logical cost is 96 Strange states per injected R gate. The gate is non-Clifford and $|R\rangle$ has maximum stabilizer fidelity $7/9$. Adding `R_INJECT(mode)` to the Pass 10941 $F/P/CZ$ compiler gives approximately universal seven-qutrit Clifford+R on every mode.

This converter is not a distiller. For $\rho_S(p) = (1-p)|S\rangle\langle S| + pI/3$, the exact output-equivalent error is

$$q(p) = \frac{4p(3p^2 - 7p + 6)}{(p+1)(5p^2 - 10p + 9)} = \frac{8}{3}p + O(p^2),$$

and $q(p) - p > 0$ for $0 < p < 1$. A protected or pre-distilled Strange source must precede the circuit.

Finally, finite stabilizer processing preserves projective amplitude ratios in $\mathbb{Q}(\zeta_{12})$, of degree four. The Pass 10941 T state requires ζ_9, of degree six, so exact stabilizer-only Strange-to-T conversion is impossible. The internal Strange lane closes algebraic universality through R rather than secretly supplying the ninth-root analyzer resource. Physical population of the dark ray, a distillation threshold, and a laboratory implementation remain open.

79.97 Pass 10943: protected metaplectic supply and a null-direction resource selector

Composing the ternary-Golay Strange-state map with the exact Pass 10942 Strange-to-R converter gives

$$\delta_{\text{out}} = \frac{55}{18}\delta^3 + O(\delta^4), \qquad q_R(\delta) = \frac{220}{27}\delta^3 + O(\delta^4).$$

The first nonzero fixed point of the composite map is $\delta_* = 0.2715245018525886$. The exact $[[11,1,5]]_3$ replay has $|C| = 243$, $|C^\perp| = 729$, $d(C) = 6$, and $d(C^\perp \setminus C) = 5$, so the logical converter and repeat-until-success R injection correct any two physical qutrit errors, subject to a still-open circuit-level syndrome and malignant-pair audit.

An independent preparation target uses $L_0 = \sqrt{\gamma}|S\rangle\langle 0|$ and $L_N = \sqrt{\gamma}|S\rangle\langle N|$. Its unique steady state is $|S\rangle\langle S|$ and its Liouvillian gap is $\gamma/2$. This specifies the required reservoir; it does not show that the current Holonet hardware realizes it.

The four-mode M36 ROM supplies a second exact route. Deleting each ray's known dark mode maps 27 of the 36 rays into the qutrit R-magic Clifford orbit and the remaining nine into the stabilizer set. A selected family therefore costs one M36 state per R state and three per successful R injection. The same family label is already the affine null direction, Hesse striation, and temporal E_8 A_2-component label. Each family has six origin/orientation choices for the exact parabolic dimensions $2{+}27{+}54{+}82{+}54{+}27{+}2$, with positive bracket growth $54 \to 81 \to 83$. In the canonical optical phase gauge three selector values are resource lanes and one is a stabilizer calibration lane. Since $\mathrm{AGL}(2,3)$ treats the four striations equivalently, this $3+1$ split is a programmable gauge assignment rather than an intrinsic preferred temporal direction.

Finally, exact Clifford+R is a strict subset of Clifford+T. The known borrowed-qutrit construction uses 39 T gates for $R \otimes I$, while exact T cannot be synthesized from any number of Clifford+R qutrits. The native R lane is cheaper precisely when a T resource costs more than $32/13$ distilled-Strange units. Component noise, a fabricated mode interface, and a physical fault-tolerance threshold remain open.

79.98 Pass 10944: a cubic universal opcode and the exact 54-dimensional obstruction

The positive parabolic 54 and the Fourier quotient are not isomorphic H_{27}-modules. Their multiplicities are respectively

$$P : (\chi_{u,v}^2, V_\omega^6, V_{\omega^2}^6), \qquad S_2 + L : (\chi_{u,v}^3, V_\omega^0, V_{\omega^2}^9),$$

where the exponent denotes multiplicity and (u,v) ranges over nine linear characters. Hence an equivariant map has rank at most $9\min(2,3) + 3\min(6,0) + 3\min(6,9) = 36$; an invertible intertwiner is impossible. Exact elimination over $\mathbb{Q}(\omega)$ constructs the optimal symmetry-changing quotient basis from 36 positive-grade and 18 opposite-grade coordinates.

The signed E_6 cubic nevertheless supplies a reversible instruction

$$t \longmapsto t + sN(x) \pmod 3, \qquad N(x) = \sum d_{ijk} x_i x_j x_k.$$

Phase kickback is a product of 45 signed qutrit CCZ gates. On one supported triad, Clifford copying, a fixed trit, and the inverse tick implement $t \mapsto t + 1 - x^2$, the $|0\rangle$-controlled qutrit X. Together with the already compiled qutrit Fourier gate this is approximately universal by the odd-prime controlled-X universality theorem.

Building on the previously certified common $\mathrm{PGL}(2,3) \cong S_4$ direction action (with affine kernel 18), the M36 three-resource/one-calibration coloring has image stabilizer S_3 and affine preimage order 108; explicit movers make its calibration assignment movable rather than geometrically preferred. Extending the previously certified $[[11,1,5]]_3$ code and logical ABI, a 66-location transversal Golay syndrome-plus-injection core corrects all 2212 fault subsets of size at most two when conditioned on clean accepted encoded inputs, giving the independent-noise bound $P_{\mathrm{fail}} \le 1 - \sum_{j=0}^{2} \binom{66}{j} p^j (1-p)^{66-j}$.

Finally, the family partial isometries W_f delete the exact dark mode and satisfy $W_f W_f^\dagger = I_3$. A sufficient 99% conditional interface budget is core fidelity 0.9966554934, phase error at most 0.057864 radians, and differential loss at most 0.502881 dB, with dark-port leakage reported separately and bounded by 10^{-3} (30 dB extinction). These are engineering falsifiers; no fabricated device or measured rate is asserted.

79.99 Pass 10947: cubic VM lowering and the coloring-phase anomaly

The signed E_6 cubic zero-controlled-X compiler now lowers to four modes of the seven-qutrit VM. With two clean ancillas, the exact word uses three Heisenberg translations, four Fourier operations, two controlled phases and one native cubic tick. It has ten operations in seven parallel layers, uses only the existing $(0, 1)$ pair edge, and returns both ancillas to zero.

Building on the code and logical-core certificates in `analysis/w33_dark_strange_golay11_ft_lane.py` and `analysis/PASS10944_RESERVATION.md`, the ternary Golay $[[11, 1, 5]]_3$ lane's three logical input supports are constructed explicitly from the cosets $C, C + \mathbf{1}, C + 2\mathbf{1}$. Two verified syndrome rounds per block plus the 66-location core give 552 locations in the declared coordinate-local model. Exact enumeration finds 2,576,205 malignant fault triples and the bound

$$P_{\text{fail}} \le 2{,}576{,}205 p^3 (1-p)^{549} + \Pr[\mathrm{Bin}(552, p) \ge 4],$$

whose conservative crossing with p is 0.000531703523611593.

The Fourier quotient is canonically $18 + 18 + 18$; the parabolic $36 + 18$ projector has discrete centralizer $H_{27} \times S_2$ of order 54 inside $H_{27} \times S_3$. Its linear commutant dimensions are 162 with only H_{27} retained and 54 with the external clock C_3 retained.

The ideal M36 interface is synthesized by a three-switch star with mode 3 as dump. Its four active-switch counts are $(1, 1, 1, 0)$, improving the adjacent-chain counts $(3, 2, 1, 0)$ while reproducing all 36 partial isometries exactly.

Finally, the order-108 M36 coloring stabilizer lifts to the signed cubic only projectively. Its support lift is $H_{27}{:}B$ of order 324, with central kernel C_3; every support permutation has a 2^6 affine set of diagonal-sign lifts, so the full monomial signed lift has order 20,736. The C_3 extension is nonsplit: every lift of the two affine translation generators has the same nontrivial central commutator. Selector relabeling must therefore track the central qutrit phase and sign gauge. These are finite logical and engineering specifications, not device measurements.

79.100 Pass 10948: the clock tetracode is a reciprocal negacyclic hyperbolic pair

The exact oriented clock code from Pass 10946,

$$C = \{(a, b, a + b, b - a) : a, b \in \mathbb{F}_3\},$$

is not negacyclic in its frozen orientation. However, flipping either the second or the fourth projective-ray representative gives the two codes

$$C_+ = (x^2 + x - 1), \qquad C_- = (x^2 - x - 1) \subset \mathbb{F}_3[x]/(x^4 + 1),$$

where

$$x^4 + 1 = (x^2 + x - 1)(x^2 - x - 1).$$

Thus the two standard negacyclic gauges are precisely the two reciprocal irreducible factors of Φ_8 modulo 3.

For the negacyclic shift

$$N(c_0, c_1, c_2, c_3) = (-c_3, c_0, c_1, c_2)$$

one has $N^4 = -I$ and $N^8 = I$ on both sectors, so the algebraic clock has exact order eight. Each sector is a self-dual $[4, 2, 3]_3$ tetracode. They meet only at zero and pair perfectly across one another: in polynomial bases (g_+, Ng_+) and (g_-, Ng_-) the cross Gram matrix is

$$\begin{pmatrix} 1 & 1 \\ 2 & 1 \end{pmatrix}, \qquad \det = 2 \pmod 3.$$

Cyclotomic inversion $x \mapsto x^{-1} = -x^3$ exchanges the two sectors.

Exhaustive signed-coordinate enumeration gives eight distinct tetracode images under the order-384 signed permutation group. Exactly two images are standard negacyclic; each has 48 presentations, hence 96 of the 384 signed gauges yield negacyclicity. This 48 is the same monomial stabilizer scale already attached to the clock tetracode.

The mechanism is objectwise compatible with the older Pass 9961–9984 Φ_8 split branch: that pass uses the same reciprocal factors to obtain two conjugate $\mathbb{F}_9$ spaces with vanishing restricted forms and nondegenerate cross-pairing. Pass 10948 therefore identifies the four-ray clock code as the rank-one finite shadow of that reciprocal-prime mechanism, not merely a repeated factor count.

This is a reversible coding/cyclotomic statement. The order-eight negacyclic shift is not a thermodynamic arrow and does not by itself promote the finite clock to physical time.

79.101 Pass 10949: the tick line's Freudenthal system, the quasiconformal cone, and the Lorentzian clock form

On the committed Chevalley basis, the Hesse striation's $|3|$-grading is the α_7 coefficient and its positive tick line's contact grading is the α_8 coefficient. The contact layer $\mathfrak{g}_{-1}$ (56 roots) sits at clock degrees $0, -1, -2, -3$ with sizes $1, 27, 27, 1$, while the clock layer (54 roots) meets it in exactly one 27: the count $54 + 2 = 56$ is not an objectwise statement. The poles are $e_{-\alpha_8}$ (the A_1 of the $|3|$ Levi) and $e_{-(\theta-\alpha_8)}$ (a clock-doublet vector).

The bracket $[x_i, x_j] = \Omega_{ij} e_{-\theta}$ is a unimodular signed matching pairing X_k with Y_k of the same history label. The quartic $Q(x) = \frac{1}{6} \operatorname{coeff}_{e_{-\theta}} \operatorname{ad}_x^4 e_\theta$ has 1036 monomials, is exactly E_7-invariant, and equals

$$Q = (\alpha\beta + T(X, Y))^2 - 4\beta N(X) - 4\alpha N(Y) + 4T(X^\#, Y^\#),$$

where N is the repository's signed 45-triad E_6 cubic, with no sign repair. That cubic satisfies $(X^\#)^\# = N(X)X$, and its 45 triads are exactly the strongly orthogonal root triples (coordinate Jordan frames).

With $v_p = \exp(\operatorname{ad}(X + \tau e_{-\theta}))e_\theta$ one has $N(X, \tau) = Q(X)/4 - \tau^2$, the Heisenberg law $(X_1, \tau_1)(X_2, \tau_2) = (X_1 + X_2, \tau_1 + \tau_2 + \frac{1}{2}\Omega(X_1, X_2))$, and the Weyl inversion i satisfies $D(i(p), i(p')) = D(p, p')/(N(p)N(p'))$, where $D(p, p') = N(X - X', \tau - \tau' - \frac{1}{2}\Omega(X', X))$: the Günaydin–Koepsell–Nicolai quasiconformal light cone, objectwise.

The Killing form obeys $K(e_\alpha, e_{-\alpha}) = -60(-1)^{\operatorname{ht}\alpha}$, so the certified split involution is the compact one twisted by $\exp(i\pi\rho^\vee)$. The three tick lines give three commuting $E_{8(-24)}$ involutions with $E_8 = 80 + 56 + 56 + 56$; the clock twist restricts to $E_{7(-25)}$ on the contact Levi, the height twist to $E_{7(7)}$. In the clock form the Hermitian Jordan triple $\{x, y, z\} = -[[x, \sigma_c y], z]$ on 27 roots yields a Euclidean Jordan algebra (trace form $(27, 0)$) with Peirce split $1 + 16 + 10$ and a Lorentzian $(1, 9)$ Peirce-0 determinant; the committed split cubic gives $(5, 5)$. Signature is a real-form datum invisible over $\mathbb{F}_3$. This is finite Lie and Jordan algebra, not a derivation of physical spacetime.

79.102 Pass 10950: the clock Albert algebra carries so(1,9), a Weyl spinor, and matter parity as a 2π rotation

The Euclidean Albert algebra A of the clock real form (Pass 10949) has $\mathrm{Der}(A) = [L_A, L_A]$ of dimension 52 with negative-definite trace form (compact F_4), and $\mathrm{str}_0(A)$ of dimension 78 with trace-form inertia $(26, 52)$, i.e. $E_{6(-26)}$. For a frame idempotent c with $u = e - c$, the stabiliser $\mathrm{Der}_c(A)$ is 36-dimensional and compact, and together with the nine boosts L_y ($y \in A_0$, $y \perp u$) it spans a 45-dimensional algebra acting faithfully on the Peirce 10 and preserving its $(1, 9)$ determinant: this is $\mathfrak{so}(1, 9)$. Its commutant on the Peirce 16 is one-dimensional, so the 16 is the Majorana–Weyl spinor. Splitting off time u, the frame direction $e_{g_2} - e_{g_3}$ and a Hermitian complex line of J_{23} leaves $\mathfrak{so}(1, 3) \oplus \mathfrak{so}(6)$ (dimension 21) with a complex-structure commutant on the 16: $16 = (2, 4) \oplus \overline{(2, 4)}$.

The repository's charge $27 = 16_1 + 10_{-2} + 1_4$ with triad pattern $40 \times (-2, 1, 1) + 5 \times (-2, -2, 4)$ is $Q = 6L_c - 2$ for every coordinate idempotent. Matter parity $(-1)^Q$ is the Peirce symmetry U_{2c-e}, an automorphism acting as $+1$ on $A_1 \oplus A_0$ and -1 on the 16, and it equals $\exp(2\pi D)$ for a single-plane rotation $D \in \mathfrak{spin}(9)$. In this real form the singlet, Higgs 10 and matter 16 of the grand-unified reading are the scalar, Lorentz vector and Weyl spinor of $\mathrm{Spin}(1, 9)$, and matter parity is the spinor sign. This is an idempotent stabiliser inside $E_{6(-26)}$, not a derivation of physical spacetime or gauge dynamics.

79.103 Pass 10951: four clock ticks are the central spin sign

The two negacyclic clock gauges of Pass 10948 have unique lifts in $GL(2, 3)$,

$$g_- = \begin{pmatrix} 0 & 1 \\ 1 & 1 \end{pmatrix}, \qquad g_+ = -g_-,$$

with minimal polynomials $x^2 - x - 1$ and $x^2 + x - 1$. Both have determinant -1 and order eight, project to the same four-cycle of the clock rays, and satisfy

$$g^2 \in Q_8 \subset SL(2, 3), \qquad g^4 = -I, \qquad g^8 = I.$$

An explicit all-products isomorphism identifies $SL(2, 3)$ with the binary tetrahedral group $2T \subset \mathrm{Spin}(3)$ and sends $-I$ to quaternion -1. Thus the determinant character is the finite Pin-component/Hesse-spinor-norm bit, whereas the central $-I$ is the distinct 2π spin sign.

Under the standard inclusion $\mathrm{Spin}(3) \subset \mathrm{Spin}(9)$, that central sign is the same one that Pass 10950 proves to be matter parity on the Peirce 16. Hence four algebraic clock ticks reach the spin central sign while eight return to the identity. This identifies only the central character; no full determinant-minus-one tick action on the Albert spinor, continuum Pin structure, or physical time evolution is claimed.

79.104 Pass 10952: the order-eight clock has a complete-positivity grading

The Pass-10951 determinant-odd clock element has an explicit qutrit extended-Clifford lift $A = U_S K$. On density operators one tick is

$$\Theta(\rho) = U_S \rho^T U_S^\dagger.$$

Its Choi operator has inertia $(6, 3, 0)$, so the map is positive and trace preserving but not completely positive. All eight clock powers obey the exact parity rule

$$n \text{ even}: \ (1, 0, 8) \text{ Choi inertia}, \qquad n \text{ odd}: \ (6, 3, 0).$$

Hence the bare-qutrit operational clock is the even subgroup: two algebraic ticks give one unitary Clifford step, and those steps form a projective C_4.

The four-tick qutrit unitary has phase-space action $-I$ but is non-scalar, with $|\operatorname{tr}|/3 = 1/3$; the Spin central sign of Pass 10951 and the qutrit parity Clifford are therefore different representations of the same abstract group element. The full order-eight clock becomes unitary on $\mathcal{H}_3 \oplus \overline{\mathcal{H}}_3$ via $D = \left(\begin{smallmatrix} 0 & U_S \\ U_S^* & 0 \end{smallmatrix}\right)$, with $D^2 = \operatorname{diag}(V, V^*)$. This is an operational channel firewall, not a derivation of physical time or a thermodynamic arrow.

79.105 Pass 10953: the minimal doubled Pin clock has an exact visibility word

The order-eight clock of Pass 10952 has a minimal complex-linear unitary carrier

$$\mathcal{H}_\omega \oplus \mathcal{H}_{\omega^{-1}}, \qquad \dim = 3 + 3 = 6.$$

Indeed the determinant-odd tick inverts the Heisenberg centre, so a linear implementer must biject the three-dimensional ω and ω^{-1} eigenspaces. On the minimal carrier $\Gamma = \operatorname{diag}(I_3, -I_3)$ anticommutes with the tick D, so odd powers swap conjugate sectors and even powers preserve them.

The unitary spectrum is $\{\zeta_8^k : k = 0, 1, 3, 4, 5, 7\}$ and $D^6 - D^4 + D^2 - I = 0$. Its normalized trace–Choi visibility is

$$\frac{|\operatorname{Tr} D^n|}{6} = (1, 0, \tfrac{1}{3}, 0, \tfrac{1}{3}, 0, \tfrac{1}{3}, 0).$$

The physical bare-qutrit even subgroup has $|\operatorname{Tr} V^n|/3 = (1, \frac{1}{3}, \frac{1}{3}, \frac{1}{3})$; its generator is in the order-four Fourier symplectic class and, in the frozen lift, Clifford-conjugate to a Pauli-displaced F_3. Thus the clock lands objectwise in the repository's existing 1/3 Bell-qutrit visibility calibration. The doubled sector is a conjugate-representation register, not an identification with literal past/future or physical chirality.

79.106 Pass 10954: the regular C_8 clock lives on the oriented A_2^4 cover

The minimal doubled Pin clock of Pass 10953 has C_8 character exponents $\{0, 1, 3, 4, 5, 7\}$, so it is exactly the regular C_8 representation with the $k = 2, 6$ modes, $\{+i, -i\}$, deleted. Restoring those two modes gives trace character $[8, 0, 0, 0, 0, 0, 0, 0]$ and eight mutually orthogonal clock positions.

The completion is already present objectwise in the repository. Before the Pass 7409 quotient $\mathbb{F}_2^4/\langle 1111\rangle$, the sixteen oriented A_2^4 sign states split under the exact clock generator into two disjoint eight-cycles. Four ticks act as the global-complement deck transformation $x \mapsto x + 1111$, and eight ticks return to the identity. Quotienting the deck map produces the already-certified two four-cycles on the eight Eisenstein $W(3, 3)$ leaves.

An explicit unitary intertwiner embeds the six-dimensional Pin clock into either regular eight-cycle with precisely the $k = 2, 6$ Fourier modes removed. Those two missing modes are deck-even, not orientation-odd. Exhausting all 48 elements of $GL(2, 3)$ further gives an exact shared character: determinant $+1$ preserves the Fano-hinge orientation bipartition and determinant -1 swaps it. This is the same determinant C_2 that separates unitary from antiunitary extended-Clifford actions and grades the clock's CP/non-CP powers. No continuum time, past/future, or temporal-chirality identification is inferred.

79.107 Pass 10955: the clock determinant exchanges the two D_4 half-spin sheets

The tetracode clock group $GL(2, 3)$ has a faithful four-dimensional signed permutation representation obtained directly from its frozen monomial action. All 48^2 products are checked, and every image preserves the standard D_4 root shell $\{\pm e_i \pm e_j\}$.

The sixteen orientation signs split as the two eight-weight half-spin demicubes S_+ and S_-, according to even or odd sign parity. Every determinant-$+1$ element preserves the vector, S_+ and S_- weight sets separately; every determinant--1 element fixes the vector set and exchanges $S_+ \leftrightarrow S_-$. Thus the outer image is the single transposition inside $\mathrm{Out}(D_4) \cong S_3$, not a triality three-cycle.

For the exact clock generator, one tick exchanges the two half-spin sheets, two ticks preserve them, four ticks equal $-I_4$, and eight ticks return to the identity; on $S_+ \cup S_-$ there are two eight-cycles. Consequently the extended-Clifford/complete-positivity grading, the Pass 10954 Fano orientation grading, and the D_4 half-spin-sheet grading are the same determinant character on the shared $GL(2,3)$. This is a finite root/weight theorem, not an identification with observed fermion chirality or continuum spin geometry.

79.108 Pass 10956: the Albert Peirce 16 contains the same D_4 half-spin transposition

Inside the executable compact $\mathfrak{spin}(9)$ of Pass 10950, the stabiliser of the spatial Peirce-0 direction $s_0 = e_{g_2} - e_{g_3}$ has dimension 28. On the Peirce 16 its exact commutant has dimension two. The non-scalar generator rescales to an involution

$$\mathrm{X}^2 = I_{16}, \qquad \mathrm{tr}\,\mathrm{X} = 0, \qquad 16 = 8_+ \oplus 8_-,$$

and each eight-dimensional eigenspace has scalar commutant, with no intertwiner between the two. Thus the certified Spin(9) spinor restricts objectwise as $8_s \oplus 8_c$ under Spin(8).

For a spatial vector $z \perp s_0$, the derivation $D = [L_{s_0}, L_z] \in \mathfrak{spin}(9)$ generates a half-turn that sends $s_0 \mapsto -s_0$, normalises the same unoriented Spin(8), and conjugates $\mathrm{X} \mapsto -\mathrm{X}$, exchanging the two eight-dimensional projector images. Its square is $-I_{16}$, the already-certified 2π Spin(9) matter-parity sign of Pass 10950.

This realizes on the actual Albert spinor the same D_4 outer transposition found for the finite clock in Pass 10955. It does not yet identify the full order-eight $GL(2,3)$ clock generator with this order-four Spin(9) half-turn; the shared structure is the half-spin transposition and central sign.

79.109 Pass 10957: a μ_4 determinant phase converts the two S_4 Schur cocycles

A deterministic section of the frozen central quotient $GL(2,3) \to PGL(2,3) \cong S_4$ gives a binary cocycle c_+, verified on all 24^3 triples and mapped objectwise back to all 48^2 products of the original clock group. Its extension has 13 involutions, the $2^+S_4 \cong GL(2,3)$ profile.

If ϵ is permutation parity, then

$$c_-(\sigma,\tau) = c_+(\sigma,\tau) + \epsilon(\sigma)\epsilon(\tau) \pmod 2$$

is again a cocycle. Its extension has one involution and the 2^-S_4 / binary-octahedral order spectrum. After enlarging central phases from μ_2 to μ_4, however,

$$b_\pm(\sigma) = (\pm i)^{\epsilon(\sigma)}$$

satisfies

$$\delta b_\pm(\sigma,\tau) = (-1)^{\epsilon(\sigma)\epsilon(\tau)}.$$

Thus the two nonisomorphic double covers become cohomologous as complex projective cocycles under this determinant-phase gauge.

On the projective clock C_4, the two missing Pass 10954 characters are exactly the two square roots $\bar{g} \mapsto \pm i$ of permutation sign. This resolves the plus/minus lifting mismatch between the finite clock and the Pass 10956 Albert half-turn at cocycle level, but no carrier-level matrix intertwiner is yet asserted.

79.110 Pass 10958: the missing μ_4 clock modes embed exactly in the Albert spinor

The Pass-10956 Albert half-turn is exactly rational: $U = R/2$ with $R^2 = -4I_{16}$, hence $U^2 = -I_{16}$ and $U^4 = I_{16}$. Over $\mathbb{Q}(i)$ its characteristic polynomial is $(x^2+1)^8$, so the Peirce 16 has eight $+i$ modes and eight $-i$ modes. The exact Spin(8) chirality involution X anticommutes with U, pairing the two eigenspaces.

Let $A_2 = \mathrm{diag}(i, -i)$ be the two-mode module formed by the missing Pass-10954 clock characters $k = 2, 6$. The producer constructs an explicit rank-two embedding W_2 and an invertible 16×16 matrix W such that

$$UW_2 = W_2 A_2, \qquad \mathrm{X}W_2 = W_2 \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix},$$

and, globally, U is eight copies of A_2 while chirality is eight copies of the swap matrix. Thus the Albert Peirce 16 is exactly eight copies of the missing μ_4 clock module over $\mathbb{Q}(i)$. Its square $U^2 = -I_{16}$ is the Pass-10950 2π Spin(9) matter-parity sign. This is a cyclic-module intertwiner only; no full $GL(2,3)$ embedding into Spin(9) is claimed.

79.111 Pass 10959: one Albert 16 cannot carry the full clock; $32 = 16 + 16$ is minimal

Restricting every irreducible complex character of $GL(2,3)$ to the frozen clock $C_8 = \langle g \rangle$ gives an exact central-odd law: if the central $-I$ acts as scalar -1, then the odd Fourier multiplicities obey

$$m_1 = m_3, \qquad m_5 = m_7.$$

The exact Albert half-turn U of Pass 10958 has only two distinct admissible μ_8 phase-lift spectra compatible with $g^4 = -I$: eight copies of $\{1, 5\}$ or eight copies of $\{3, 7\}$. Exhausting all 25 central-odd degree-16 character combinations proves that neither spectrum extends to a full $GL(2,3)$ representation.

The minimal completion is dimension 32. Combining the two conjugate Albert phase lifts gives multiplicity eight on each odd C_8 character, exactly the restriction of eight copies of the faithful four-dimensional signed D_4 representation from Pass 10955. Over $\mathbb{Q}(\zeta_8)$ an explicit invertible 32×32 matrix J intertwines

$$\mathrm{diag}(\zeta_8^{-1} U, \zeta_8 U) \quad \text{with} \quad R_4(g)^{\oplus 8},$$

so transporting $R_4^{\oplus 8}$ supplies a faithful full $GL(2,3)$ action on the doubled Albert vector space. This is a finite complex-representation result; no Spin(9), Spin(10), Jordan-product, or physical Dirac identification is claimed.

79.112 Pass 10960: the FI term forces a $B - L = \pm 1$ condensate — exhaustive matter-even D-flat closure

The raw orbifolder spectra of all 215 $\mathbb{Z}_6$ Standard Models of the $W(3,3)$ twist were recovered and frozen as an exact-rational left-chiral ledger, and the Holotrade closure contract was executed without sampling. With $B - L = x_0 + Nt$ ranging over its full rational solution set, none of the

88 models with a $B-L$ direction admits a D-flat, FI-cancelling singlet direction condensing only matter-even singlets: 64 have no D-flat direction at all (exact Farkas vector), 23 are excluded by one Farkas vector on the singlets that are even for *some* t, and one ($\mathbb{Z}_6$-II, 3334 exact extreme rays, 304 FI-cancelling) by a Smith-normal-form parity obstruction on every FI-cancelling ray. The singlets that are never even carry $3(B-L)=\pm 3$ fixed by the Standard Model itself: every D-flat vacuum must condense a $B-L=\pm 1$ (right-handed-sneutrino-type) field, which is exactly the case in which matter parity cannot survive (Martin's criterion). An independent scan of all 1024 $\mathbb{Z}_2$ characters of the charge lattice that are odd on q, u^c, d^c, e^c gives no even D-flat direction either. The exact machinery reproduces the prior census of $23+105$ D-flat models and 88 $B-L$ models. Scope: singlet directions; hidden nonabelian composite directions remain the one loophole.

79.113 Pass 10961: exact Albert $Cl(9)$, doubled $Cl(10)$, and the clock grade obstruction

The nine spatial Peirce-zero Jordan multiplication operators act on the Albert Peirce 16 as exact rational Euclidean Clifford generators:

$$\{\gamma_i, \gamma_j\} = 2\delta_{ij} I_{16}.$$

Their bivectors span dimension 36. On two copies of the Albert 16, the block matrices

$$\Gamma_i = \begin{pmatrix} 0 & \gamma_i \\ \gamma_i & 0 \end{pmatrix}, \qquad \Gamma_{10} = \mathrm{diag}(I_{16}, -I_{16})$$

satisfy $\{\Gamma_a, \Gamma_b\} = 2\delta_{ab} I_{32}$ and have a 45-dimensional bivector span, giving an explicit $Cl(10)$ Dirac system.

For the minimal doubled clock $G = \mathrm{diag}(\zeta_8^{-1} U, \zeta_8 U)$,

$$G^2 = i\Gamma_{10}, \qquad G^4 = -I_{32},$$

but one tick obeys $G\Gamma_i G^{-1} = -i\Gamma_{10} \sum_j (C_9)_{ji} \Gamma_j$ while fixing Γ_{10}. Thus nine Clifford vectors are sent to mixed bivectors; the vector space and its one-tick image span dimension 19 and intersect only in Γ_{10}. The full order-eight clock is therefore not a Spin(10)/Pin(10) vector normalizer in this canonical Albert extension. Two ticks do return to the vector normalizer, acting as $\mathrm{diag}(-I_9, +1)$ on the ten Clifford vectors.

79.114 Pass 10962: the hidden sector does not rescue matter parity

Pass 10960's one loophole — Standard-Model singlets charged under the hidden gauge group, whose parity a hidden gauge element can compensate — is closed in tiers. Tier A (exact, every hidden direction): a parity-preserving vacuum is D-flat for the hidden maximal torus with component parities $3(B-L)\cdot q + 2\eta \cdot w$, t and η free; for 32 of the 88 models the ever-even components carry an exact Farkas vector. Tier B (exact over explicit generators): by Luty–Taylor and Kempf–Ness a parity-preserving D-flat vacuum exists iff an FI-cancelling product of matter-even hidden invariants does; over singlets, all quadratic invariants, $SU(N)$ baryons and $SU(5)$ cubics, 55 more models close by exact Farkas vectors (completeness of the generators is not claimed). Tier C: in the last model all 2846 FI-cancelling rays of 62,309 are parity-obstructed (Smith normal form). The four anomaly-free models admit no matter parity at all. A pilot scan shows that $\mathbb{Z}_{12}$-I also carries the $W(3,3)$ twist (1167 modular-invariant shifts, all with Z3 part $(A_8, D_7{+}U_1)$) and hosts Standard Models, whose first spectra fail the same test.

79.115 Pass 10963: Clifford-grade stabilizers recover the tetrahedral $S_4 \to S_3$ chain

Let V_{10} be the ten-dimensional $Cl(10)$ vector packet from Pass 10961 and let P_{19} be its enlargement by the nine mixed bivectors $\Gamma_{10}\Gamma_i$. For the frozen clock

$$g = \begin{pmatrix} 0 & 1 \\ 1 & 1 \end{pmatrix}$$

and the involution

$$b = \begin{pmatrix} 1 & 0 \\ 1 & -1 \end{pmatrix}$$

in $GL(2,3)$, exact multiplication gives $bgb = g^3$. The exact packet stabilizers are

$$\mathrm{Stab}(V_{10}) = \langle g^2, b\rangle \cong D_8, \qquad \mathrm{Stab}(P_{19}) = \langle g, b\rangle \cong QD_{16},$$

and $QD_{16} = N_{GL(2,3)}(\langle g\rangle)$ is the clock normalizer. Their cores in $GL(2,3)$ are the central C_2 and Q_8 respectively, so the induced packet actions are

$$GL(2,3)/C_2 \cong S_4, \qquad GL(2,3)/Q_8 \cong S_3.$$

The six conjugate V_{10} packets are equivariantly the six edges of the tetrahedron K_4, while the three conjugate P_{19} packets are the three perfect matchings, or opposite-edge pairings. Each P_{19} contains exactly the two V_{10} packets belonging to one opposite pair. Numerically replaying the exact committed matrices gives literal intersection dimensions $0^{12}, 1^3$ for the six vector packets and 8^3 for the three 19-packets; the corresponding cross-Gram ranks are $9^{12}, 1^3$ and 9^3. Both full packet orbits generate the same 33-dimensional operator hull. Thus the clock-grade ladder closes through the exact chain

$$D_8 < QD_{16} < GL(2,3),$$

with a six-edge S_4 cover and a three-matching S_3 quotient. The resulting S_3 has the same permutation degree as D_4 triality, but no triality intertwiner is asserted here.

79.116 Pass 10964: one E6-shaped U(1) forces the sneutrino

In each of the 23 $W(3,3)$ $\mathbb{Z}_6$-I models with FI-cancelling D-flat singlet directions there is an exact canonical certificate $f = sQ_{\mathrm{anom}} + \lambda \cdot Q_{\mathrm{nonanom}}$ with $f = \frac{24}{5}\mu$ on every q, u^c, e^c, $f = \frac{8}{5}\mu$ on every d^c, ℓ, $\mu > 0$, and $f \geq 0$ on every singlet that can be matter-even. On Standard-Model singlets f/μ takes only the values $-8, 0, 8$, on Higgs-type doublets $-\frac{48}{5}, -\frac{8}{5}$, and the $f < 0$ singlets are exactly forced $B - L = +1$ ones at -8. On the families $f/\mu = 4Q_\psi - \frac{4}{5}Q_\chi$ with $Q_\chi = 4Y - 5(B-L)$; the value -8 at $(B-L, Y) = (1, 0)$ means $Q_\psi = -3$: the right-handed-sneutrino direction of the matter-odd $16_{-3} \subset 78$ of E_6. The anomalous $U(1)$ acts on singlets like the E_6 generator $5Q_\psi - Q_\chi$, and only that sneutrino can balance it.

79.117 Pass 10965: baryon triality is structurally impossible

Baryon triality $B_3 = \exp(2\pi i(B - 2Y)/3)$ would protect the proton without matter parity. As a gauge symmetry it must be a $\mathbb{Z}_3$ character of the $U(1)$ charge lattice equal to B_3 on every q, u^c, d^c, e^c up to a hypercharge rotation; over GF(3) this is inconsistent in all 215 $W(3,3)$ $\mathbb{Z}_6$ models (zero-target control consistent in all 215). The obstruction is $SU(5)$: in 214 models single copies obey $Q(u^c) + Q(e^c) = 2Q(q)$ exactly, on which B_3 is 2 and every hypercharge shift is 0 mod 3; the last model has an explicit integer relation with the same property. Only an R-symmetry such as the anomaly-free $\mathbb{Z}_4^R$ remains as a route to proton stability.

79.118 Pass 10967: the FI vacuum regenerates R-parity violation

(A) The most general matter parity. Any element of the gauge $U(1)$ torus times the space-group non-R discrete group (point-group $\mathbb{Z}_6$, $\mathbb{Z}_3$, and in $\mathbb{Z}_6$-II the $\mathbb{Z}_2 \times \mathbb{Z}_2$ fixed-point rules) that is -1 on q, u^c, d^c, e^c and $+1$ on the condensing singlets, other fields unrestricted, is decided exactly by a Smith normal form. Such an element exists in exactly the 88 $B-L$ models; 87 close by one Farkas vector, $\mathbb{Z}_6\mathrm{II}_{23}$ by obstructing all 304 FI-cancelling rays: 0/215. *(B)* 290 of the 302 forced singlets obey, with single copies, $Q(n) = -Q(u^c d^c d^c) = -Q(q\,l\,d^c) = -Q(l\,l\,e^c)$ — the $SO(10)$ invariant $\mathbf{16}^4$ at ν^c — so they are odd under every matter parity. *(C)* With all orbifolder selection rules, in the 23 D-flat $\mathbb{Z}_6$-I models no cubic R-parity-violating coupling is allowed, yet all 9 forced singlets of every model appear in allowed quartics $n\,u^c d^c d^c$, $n\,q\,l\,d^c$, $n\,l\,l\,e^c$; $\mathbb{Z}_6\mathrm{II}_{23}$ has $q\,l\,d^c$, $l\,l\,e^c$ at order 3 and $u^c d^c d^c$ at order 5. The FI term therefore regenerates all three operators with strength $\langle n\rangle/M_s$, which closes b81ef8c's condition.

79.119 Pass 10969: harmless R-parity violation versus the Higgs quartic

The FI-forced condensate regenerates dimension-four R-parity violation with $\lambda' \sim \lambda'' \sim \langle n\rangle/M_s \approx 0.19$–$0.39$. Heavy squarks make it harmless only if $\tilde{m} \gtrsim 6 \times 10^{14}$–$1.2 \times 10^{15}\,\mathrm{GeV}$ ($|\lambda'\lambda''| \lesssim 10^{-27}(\tilde{m}/100\,\mathrm{GeV})^2$). Two-loop Standard-Model running from NNLO matching (control: $\lambda(M_{\mathrm{Pl}}) = -0.0150$ against the three-loop fit -0.0143) puts the zero of the Higgs quartic at $3.2 \times 10^{10}\,\mathrm{GeV}$ for $m_t = 172.57\,\mathrm{GeV}$. MSSM matching with colour-breaking-safe stop mixing needs $\lambda(M_S) \geq 0$, so $M_S \geq 10^{15}\,\mathrm{GeV}$ requires $m_t \leq 171.00\,\mathrm{GeV}$, 5.4σ below the measured value on the experimental error alone. The same running refutes $\lambda_h(\mathrm{GUT}) = +1/40$ (BT475), which would need $m_t \approx 166.9\,\mathrm{GeV}$.

79.120 Pass 10968: plane-rotation R-parity; the flat-or-massive dichotomy

Adding the W-invariant combinations of the $\mathbb{Z}_6^R \times \mathbb{Z}_3^R \times \mathbb{Z}_2^R$ plane rotations of the $\mathbb{Z}_6$-II lattice, matter parity exists in 3 of 128 models; $\mathbb{Z}_6\mathrm{II}_{23}$ alone has parity-preserving FI-cancelling D-flat directions (38 extreme rays; witness invariant on all 1524 orbifolder-allowed couplings; selection rules reproduce the orbifolder's 144 order-5 $u^c d^c d^c$ couplings exactly). In the 38 the exotic masses $u\,u^c$, $d\,d^c$, $e\,e^c$ are forbidden to all orders. Two certified larger vacua break the remnant: 68 directions (exotics full rank by order 5, Higgs rank 6) and 23 directions (exotics full rank, Higgs rank 5/6 at all orders, no outside linear term), each with one parity element and an exact positive D-flat vector; neither has $W|_S = 0$. A branch search reached 202 sub-vacua with $W|_S \equiv 0$ (71 fully flat): the exotic d mass matrix has rank 0 in all 202. $\mathbb{Z}_{12}$-I: 14 of 289 SMs reach a parity-viable vacuum and fail the exotic mass test (5 robustly, 9 with tentative R rules). $\mathbb{Z}_2 \times \mathbb{Z}_6$-I: 29 SMs, 0 survive.

79.121 Pass 10974: the established R-rules close the plane-rotation door

The per-plane R-charge rule used by orbifolder 1.2 holds only on prime planes of factorizable orbifolds; on non-prime planes the γ-phase contributes (Bizet et al.). Keeping only the established $\mathbb{Z}_3^R$, $\mathbb{Z}_2^R$ of the $\mathbb{Z}_6$-II lattice, and separately adding the γ-corrected G2-plane charge, all 304 FI-cancelling directions of $\mathbb{Z}_6\mathrm{II}_{23}$ break the parity: $\mathbb{Z}_6$-II is 0/128. The new $\mathbb{Z}_3 \times \mathbb{Z}_6$ family (5 SMs) has no parity; $\mathbb{Z}_2 \times \mathbb{Z}_6$-I (29) and $\mathbb{Z}_6 \times \mathbb{Z}_6$ (10; two models open only under uncorrected R-rules admit no MSSM-viable parity even then) have none that survives; $\mathbb{Z}_2 \times \mathbb{Z}_6$-II yields no Standard Model in 51 000 tries. The 9 $\mathbb{Z}_{12}$-I verdicts that used per-plane rules become undetermined.

79.122 Pass 10978: the E6 lattice fixes the admissible R-rule of $\mathbb{Z}_{12}$-I

The $\mathbb{Z}_{12}$-I twist on the E_6 lattice is the Coxeter element c. Generating $W(E_6)$ (51 840 elements) exactly gives $C_W(c) = \langle c\rangle$ and $-1 \notin W(E_6)$, so the lattice symmetries commuting with the twist are $\langle c\rangle \times \langle -1\rangle$, and $-c^6$ is a π-rotation of the order-3 plane only: the single admissible R-symmetry is $\mathbb{Z}_2^R$ on that plane. Bracketing every verdict between the weakest rules and this one, all 14 parity-viable $\mathbb{Z}_{12}$-I vacua are decided: 11 keep exotic d-triplets massless (non-negative monomials, all orders), one has no light Higgs, one fails at both ends, and $\mathbb{Z}_{12}\mathrm{I}_{1063}$ — exotics massive, one Higgs pair protected at all orders — has an outside singlet entering linearly at order 4, and absorbing any low-order linear singlet lifts the protected pair. The Pass 10967 statement on $u^c d^c d^c$ in $\mathbb{Z}_6\mathrm{II}_{23}$ survives every rule set.

79.123 Pass 10979: the $W(3,3)$ twist on the prime orbifolds $T^6/\mathbb{Z}_3$ and $T^6/\mathbb{Z}_3\times\mathbb{Z}_3$

With the unique A_8 modular-invariant Kac pair, $T^6/\mathbb{Z}_3$ gives no Standard Model in 64 000 Wilson-line draws, corroborating the cyclic order-three law; $T^6/\mathbb{Z}_3 \times \mathbb{Z}_3$ gives 13 (12 distinct spectra). All planes are prime, so every R-rule is established: parity exists in 4, and 3 keep it on FI-cancelling D-flat rays — the first such family. On all 36 MSSM-viable minimal supports the exotic d-triplet is massless to all orders and $W|_S \equiv 0$, while outside singlets enter W linearly at order 3–4; absorbing them gives 28 vacua with joint MSSM-viable parity, massive exotics and full-support FI-cancelling D-flatness (Higgs massless to all orders in 22). F-flatness with every field nonzero needs $\sum_k (c_k m_k) e_k = 0$, i.e. linearly dependent exponent vectors: enumerating every allowed monomial to degree 14, they are independent through degree 11 in all 28 (through 14 in 12). No supersymmetric vacuum exists through degree 11 for any couplings; the first balance, cubic against degree 12, needs $c_{12}/c_3 \sim (M_s/\langle\phi\rangle)^9$ — a worldsheet-instanton question left open.

79.124 Pass 10980: flavour structure does not hide the regenerated R-parity violation

At the Higgs-quartic ceiling $\tilde{m} \approx 3\times10^{10}$ GeV the proton needs $|\lambda'_{1jk}\lambda''_{11k}| \lesssim 10^{-10}$. In the 23 D-flat $\mathbb{Z}_6$-I vacua, with gauge and space-group rules (which over-permit, so every coupling is an upper bound), first-generation projections through the up-Yukawa give 2×10^{-3}–0.34; no suppression mechanism appears, and the vacua fail independently of proton decay: 7 have no light H_u and 16 keep two exotic d-triplets massless.

79.125 Pass 11024: the $\mathbb{Z}_3 \times \mathbb{Z}_3$ parity vacua are supersymmetric, and carry massless fractional charges

On each of the 28 Pass 10979 vacua the monomials invariant under the continuous charges form a free monoid on $k \in \{1,2\}$ composites p_i (disjoint products of 3 or 4 fields, lattice index 1), and p^a is allowed in W iff $a_1+\cdots+a_k \equiv 1 \pmod 3$, checked on a full period, hence to all orders: $W|_S = F(p)$ with $F(\omega p) = \omega F(p)$. With every field nonzero $F_\phi = 0 \iff \nabla_p F = 0$, which has the Bézout number of roots; every root lifts to an exact $F = D = 0$ point with the FI term cancelled and every field nonzero (28/28), at $\max|\phi| \approx 0.8$–$1.07\,M_s$ for $O(1)$ couplings. A hidden-representation-refined index then shows 48 chiral states of charge $\pm\frac{1}{3}$, six of them hidden singlets, massless in every vacuum preserving the hidden $SU(4) \times SU(3)'$; both are infrared free ($b = -7, -16$ and $-4, -13$), and no single $SU(4)$ meson condensate added to any vacuum pairs the fractional class. Breaking one factor at a time shows the index vanishes iff the hidden $SU(4)$ is broken; a Luty–Taylor census of every FI-cancelling ray containing a quadratic $SU(4)$ condensate finds 54 parity vacua $(39+15)$,

all supersymmetric with aligned parity, and in every one at least 120 fractional multiplets stay massless at all orders, most of them protected by an unbroken discrete symmetry, a 3-group of order 3^4 or 3^6 (the torsion of the charge lattice modulo the vacuum's). An exact lattice solver (Smith normal form, LLL, congruence-free residual program, rational re-verification) reproduces every integer-program result of Passes 10978–10980 with 0 differences.

79.126 Pass 11086: "flat-or-massive" is an unbroken R-symmetry, not a law

With the exact lattice solver, every parity vacuum with a decided exotic spectrum is classified by whether $W|_S$ is forbidden by an exact unbroken symmetry of the vacuum (integer exponents of any sign fail) or only by holomorphy, and likewise for the exotic $d\bar{d}$ masses. Where both vanish ($\mathbb{Z}_3 \times \mathbb{Z}_3$ minimal supports 36/36, $\mathbb{Z}_{12}$-I under $\mathbb{Z}_2^R$ 12/14), W is always forbidden by an unbroken discrete R-symmetry, which in 46 of the 48 cases also forbids the exotic masses (the other 2 are holomorphy-only). But neither implies the other: under $\mathbb{Z}_2^R$ two $\mathbb{Z}_{12}$-I vacua (one is $\mathbb{Z}_{12}\mathrm{I}_{1063}$) have W forbidden and the exotics massive, and under the weakest rules eleven have $W \neq 0$ and the exotics massless.

One fixed W33 perfect gate compiles every two-qutrit Clifford

Let $H = (\mathrm{SL}(2,3) \times \mathrm{SL}(2,3)){:}C_2$ be the order-1152 stabilizer of one of the 45 W33 tensor factorizations, and let p be the order-four symplectic tetracode perfect gate. Exact double-coset enumeration and objectwise word replay give

$$\mathrm{Sp}(4,3) = H \sqcup HpH \sqcup Hph_*pH$$

for one fixed $h_* \in H$. The three pieces have sizes $1152, 13824, 36864$ and optimal p-depths $0, 1, 2$ respectively. In particular, every two-qutrit Clifford uses at most two copies of the same perfect interaction, and the standard qutrit SUM gate has a frozen exact word Lph_*pR of minimal depth two.

On the 45 factorizations, if A is the perfect-relation adjacency matrix,

$$A^2 = 12I + 3A + 3(J - I - A), \qquad \mathrm{Spec}(A) = \{12^1, 3^{20}, (-3)^{24}\}.$$

This rank-three Hecke identity is the compiler algebra: graph diameter two is the depth bound. The fixed gate remains Clifford. Approximate universality uses the separate signed-E_6 cubic zero-controlled-X resource already certified in Pass 10944; no physical implementation is claimed.

The same walk is exactly lumpable on the Pass 11185 decomposition of the 45 cubic monomials into 5 terms of type $1 \cdot 10 \cdot 10$ and 40 of type $16 \cdot 16 \cdot 10$. Its neighbour quotient and stochastic form are

$$\begin{pmatrix} 4 & 8 \\ 1 & 11 \end{pmatrix}, \qquad P = \begin{pmatrix} 1/3 & 2/3 \\ 1/12 & 11/12 \end{pmatrix}.$$

The stationary weights are $(1/9, 8/9)$ and the transient mode decays by $1/4$ per perfect step. This is an exact dynamics on Yukawa-term labels, not a computation of Yukawa amplitudes, masses or mixing angles. The tetracode carrier itself is prior (Passes 10946, 10954–10955, 10970, 11035 and 11164); the increment here is the optimal two-qutrit word theorem and its exact E_6 sector quotient.

80 Overture: the machine is the geometry is the carrier

In plain language. *The claim of this paper in one section: the shape, the machine and the light are not three things connected by engineering but one thing described three ways. Everything after this is either a consequence of that or a limit on it.*

Classical architecture separates three things: the processor that acts, the program that directs, and the network that connects. The thesis of this paper is that at the level of a single photon on a finite symplectic geometry the three are one object, and that this is not a metaphor but a chain of theorems.

Principle 80.1 (Identity of the three layers)**.** *Transporting the photon through the mesh* is *applying a gate* is *routing a packet. One physical process; three descriptions.*

Rosetta stone of the $q = 3$ substrate (read this first). This paper has two halves: the *machine* (the architecture, below) and the *world* it computes (§C). Both are the one $q = 3$ Eisenstein object — the Witting polytope $3\{3\}3\{3\}3\{3\}3$ (240 vertices = E8 roots), its symmetry ST#32 (order $155520 = 3|\mathrm{Aut}(W(3,3))|$), equivalently the degree-two cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\} = \{13, 10, 7\}$ at $q = 3$ — seen from *seven faces*: **(1) selection** ($q = 3$ forced: $\Phi_4 = q^2 + 1$ factors the de Sitter cubic and $v = (q{+}1)\Phi_4 = 40$), **(2) constants** (the Witting degrees $\{12, 18, 24, 30\} = \{k, h(E_7), c{=}f, h(E_8)\}$), **(3) gauge** ($\dim \mathrm{SU}(3)^3 = 24 = c$, $\dim \mathrm{SM} = 12 = k$, $\sin^2\theta_W = 3/8$), **(4) neutrino** ($\Phi_3/q^2 = 13/9$, PMNS $1/\Phi_3$), **(5) code** (the GKP tower $A_2{<}D_4{<}E_8$), **(6) demonstrator** (contextual fraction $1/\Phi_4 = 1/10$, pump Chern $\lambda = 2$), and **(7) cosmology** ($N = 2(v{-}\Phi_4) = 2h(E_8) = 60$ e-folds; $n_s = 29/30$, $r = k/N^2 = 1/300$). The faces share integers — $k{=}12, \Phi_4{=}10, \Phi_3{=}13, c{=}f{=}24, v{=}40$ each serve ≥ 3 faces (Table 1) — which is why they are one object (Fig. 9). *No free integer parameter*: every geometric integer is a cyclotomic value, GQ count, or Witting degree, and even the moonshine ceiling closes — the Leech kissing number factors as $196560 = 6\mu q^2\Phi_3\Phi_4\Phi_6$, so the Monster (196883), $\tau = \mu q^2\Phi_6 = 252$, and the fine-structure integer $1/\alpha = 137 = \Phi_3\Phi_4 + \Phi_6$ are all $\{\mu, q, \Phi_3, \Phi_4, \Phi_6\}$ arithmetic; the lone non-integer input is the 0.036 of 137.036 (QED running). *The one experiment to run first*: the benchtop, calibration-free contextual fraction $1/\Phi_4 = 1/10$, which tests three faces at once.

The identification rests on seven exact pillars, each proved by explicit computation in the project repository (every theorem below carries its witness script):

1. **Operator–operand duality** (§81.1): the same $W(3,3)$ is drawn by the photon's *states* (orthogonality of the 40 Witting rays in $\mathbb{C}^4$) and by its *operators* (commutation of the 40 two-qutrit Pauli classes on $\mathbb{C}^9$).

2. **Routing–gate identity** (§83): the mesh is an atlas of 540 three-dimensional hypercube charts whose native XOR routing moves are exactly the register operations, glued along the 1620 apartments of the Tits building of $\mathrm{Sp}(4, \mathbb{F}_3)$.

3. **Parabolic address–route duality** (§81.3): the point parabolic supplies two 648-slot address sheets, whereas the Bell-line parabolic decodes the compass fabric by the complete prefix code $0, 10, 110, 111$; its cache quarter is an exact D_8-over-81 four-state address fiber. Address and route are the two nodes of the same C_2 building, while the separate ternary transport extension carries temporal state.

4. **Dual-torsor state–program compilation**: the Steinberg memory restricts to both canonical order-27 shell groups as three regular copies. Bell-shell programs use commuting $\mathbb{F}_3^3$ coordinates; point-shell states use Heisenberg 3^{1+2} coordinates; both compile into the same 81 logical qutrits.

5. **Mirror middleware** (§84): the cyclic selector clock and the mirror transport bus are different 2160 worlds. The photon is clocked by the C_{12} side but routed by the D_{12} side, whose full Clifford lift is the exact product $24 \cdot 45 \cdot 48$.

6. **Universality from optics** (§85.5): the photon's own beam-splitting elements generate the complete Clifford group (symplectic closure = 51840, exact), and its matter shell is precisely its magic supply.

7. **Fractal holonet scaling** (§86): recursively replacing every site by a fresh $W(3,3)$ core gives a universal computer/network with exact 40^n leaves and logarithmic reversible routing.

And the machine is not separate from the world it computes. The second half of the paper (§C) shows that the *same* $q = 3$ Eisenstein structure that fixes this architecture — the Witting polytope, its symmetry ST#32, the cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\}$ — is also the selection of $q = 3$, the substrate constants, the Standard-Model gauge group, the neutrino masses, the error-correcting code, the benchtop experiment, and inflationary cosmology. These seven faces, and the single object behind them, are laid out in §C.1 (Fig. 9); the reader who wants the unifying picture before the engineering may read that subsection first.




Figure 1: The photonic holonet as an engineering stack. The same photon is data, instruction, and packet; the same finite geometry supplies the network, middleware, and runtime.

81 The substrate

Definition 81.1 ($W(3,3)$)**.** *Let $V = \mathbb{F}_3^4$ with the alternating form $\langle u, v\rangle = u_1v_3 - u_3v_1 + u_2v_4 - u_4v_2$. The points of $W(3,3)$ are the 40 projective points of V; the lines are the 40 totally isotropic projective lines. Each point lies on 4 lines and each line carries 4 points; collinearity defines the strongly regular graph* $\mathrm{SRG}(40, 12, 2, 4)$.

Three related symmetry groups occur, and their roles are different:

$$\underbrace{\mathrm{Sp}(4,3)}_{\text{2·PSp(4,3), Clifford double cover}}, \qquad \underbrace{\mathrm{PSp}(4,3)}_{\text{25920, faithful projective action}}, \qquad \underbrace{W(E_6) \cong \mathrm{PSp}(4,3){:}2}_{\text{51840, outer Weyl extension}}.$$

The first and third groups both have order 51840 but are not the same extension: the center of $\mathrm{Sp}(4,3)$ acts trivially on projective points and lines, while the outer involution in $W(E_6)$ acts

nontrivially. The projective group acts with permutation rank 3. The ATLAS index-40 subgroups are the two building parabolics $3^{1+2}{:}2A_4$ and $3^3{:}S_4$ [21]. The substrate primitives are

$$q = 3, \quad \lambda = 2, \quad \mu = 4, \quad k = 12, \quad f = 24, \quad g = 15, \quad \Phi_6 = 7, \quad \Phi_4 = 10, \quad \Phi_3 = 13,$$

and every numerical claim in this paper reduces to arithmetic in these.

Formal grounding (the master formalism). In the master manuscript [1] the whole structure is forced by one Diophantine seed: the *master equation* $q! = 2q$ has the unique positive-integer solution $q = 3$, and the SRG quadratic $x^2 - q!\,x + 2^q = (x-2)(x-4)$ then delivers $\lambda = 2$, $\mu = 4$ and the full parameter closure ($k = 2^q + q + 1$, $v = 40$, multiplicities $f = 24$, $g = 15$, cyclotomic ladder $\Phi_3 = 13$, $\Phi_6 = 7$, $\Phi_{12} = q^4 - q^2 + 1 = 73$, $\Theta = q^2 + 1 = 10$). Two of those closure constants reappear in this paper as *spectral field discriminants*: the chart-web's irrational eigenvalue pairs $1 \pm \sqrt{10}$ and $(-1 \pm \sqrt{73})/2$ (§83) live precisely in $\mathbb{Q}(\sqrt{\Theta})$ and $\mathbb{Q}(\sqrt{\Phi_{12}})$ — the machine's transport spectrum speaks the same cyclotomic dialect as the physics tier ladder.

81.1 The two carriers and the operator–operand duality

Theorem 81.2 (Two realizations, one geometry)**.** (i) *The* 40 *Witting rays in* $\mathbb{C}^4$ *(the photon's path* $\otimes$ *polarization space) have orthogonality graph isomorphic to the collinearity graph of* $W(3,3)$*.* (ii) *The* 40 *projective classes of two-qutrit Pauli displacements* $D(v) = X^a Z^b \otimes X^c Z^d$ *on* $\mathbb{C}^9$ *(the photon's past* $\otimes$ *future time-bin space) have commutation graph equal to the same* $W(3,3)$*, via* $D(u)D(v) = \omega^{\langle u,v\rangle} D(v)D(u)$*.* Witnesses: `bt817_self_entangled_photon_atlas.py`, `bt821_operator_operand_duality.py`.

Thus a point of the substrate is simultaneously a pure state the photon can occupy and a unitary the photon can enact; a line is simultaneously a measurement context (orthonormal tetrad) and a stabilizer group (maximal commuting Pauli set with its 9-state joint eigenbasis). The $360 = 40 \times 9 = f \cdot g$ two-qutrit stabilizer states are the joint eigenbases of the forty lines.

81.2 The five vacua and the Schläfli geography

Every maximal subgroup class of $\mathrm{PSp}(4,3)$ decomposes the substrate in its own canonical way; the maximal indices are the classical inventory of the 27 lines on a cubic surface.

index	subgroup	points	lines	vacuum	cubic surface
27	$2^4{:}A_5$	$[40]$	$[40]$	homogeneous (icosahedral)	27 lines
36	S_6	$[40]$	$[10,30]$	spread fibration	36 double-sixes
40	parabolic	$[1,12,27]$	$[4,36]$	holonet point vacuum	trihedra I
40	parabolic	$[4,36]$	$[1,12,27]$	dual line vacuum	trihedra II
45	$(2T{\times}2T){:}2$	$[8,32]$	$[16,24]$	binary polar	45 tritangents

The physical decomposition $40 = 1 + 12 + 27$ (self + gauge shell + matter shell) is the *choice of the point-parabolic vacuum* among five inequivalent readings; the icosahedral vacuum sees a featureless substrate. The platonic ladder threads the table: the binary tetrahedral group $2T$ (the 24-cell) lives in every polar-pair stabilizer, the real octahedral group O_h ($= S_4 \times \mathbb{Z}_2$, order 48) is the chart symmetry of §83, and the binary icosahedral group $2I = \mathrm{SL}(2,5)$ (the 600-cell) is the core of every spread stabilizer, with point orbits $[20,20]$ and line orbits $[10,30]$ echoing the Boerdijk–Coxeter decomposition $600 = 20 \times 30$. *Witnesses:* `bt808–bt813`.

81.3 The parabolic router: address and route are dual

In plain language. *In this machine a destination and the path to it are the same kind of object, so routing is not a search. That duality is what removes the routing table, and this section makes it precise.*

The two index-40 parabolics are not duplicate descriptions of one local neighborhood. They execute different halves of a packet protocol. This becomes visible only after the compass census: there are two 216-element classes of icosahedral A_5 cores, and exactly $1296 = 216 \cdot 6$ cross-class pairs meet in D_{10}.

Theorem 81.3 (Bell–compass parabolic router)**.** *Fix an isotropic Bell line. Its projective Siegel parabolic* $3^3{:}S_4$ *has four orbits on the* 1296 *incident compass pairs:*

$$162_L + 162_R + 324 + 648.$$

They are distinguished objectwise by the Bell line lying in the pentad core's 5_L*,* 5_R*,* 10*, or* 20 *line orbit. The normalized orbit sizes satisfy the Kraft equality*

$$2^{-3} + 2^{-3} + 2^{-2} + 2^{-1} = 1,$$

so they admit the complete prefix decoder

$$110 \mapsto \textit{left cache}, \quad 111 \mapsto \textit{right cache}, \quad 10 \mapsto \textit{schedule}, \quad 0 \mapsto \textit{dark mirror}.$$

The outer Weyl involution fuses exactly the two 162 *cache orbits, leaving* $324_{\text{cache}} + 324_{\text{schedule}} + 648_{\text{mirror}}$*. By contrast, the dual point parabolic has two regular projective orbits of size* 648*; the outer extension preserves rather than fuses these address sheets.* Witness: `bt859_bell_compass_parabolic_router.py`.

The equality case of Kraft–McMillan means the routing words fill a binary decision tree with no unused branch [22]. Here the code lengths were not optimized from assumed traffic probabilities: they were read from exact group orbits. A packet first asks whether its Bell line is in the dark mirror half; if not, whether it is in the common schedule quarter; only the remaining cache quarter needs the third, chiral bit. The decoder is self-delimiting and constant-depth, with expected word length

$$\frac{1}{2}(1) + \frac{1}{4}(2) + 2 \cdot \frac{1}{8}(3) = \frac{7}{4}$$

under the invariant uniform measure on the 1296 compass pairs.

orbit	Bell-line position	prefix	engineering action
648	dark 20-orbit	0	enter mirror bus
324	common schedule 10-orbit	10	timetable-local route
162	absolute pentad 5_L	110	left cache
162	absolute pentad 5_R	111	right cache

This theorem also closes an honesty boundary. The Bell stabilizer and the compass incidence set both have cardinality 1296, but they are not a regular G-set identification. Projectively, the Bell stabilizer has order 648 and the orbit stabilizers are $1, 2, 4$. The useful result is stronger than the count: a hierarchical decoder and a persistent address bit are forced by the two parabolic actions.




Figure 2: The two C_2 parabolics implement a dual protocol. Point localization selects one of two address torsors; Bell-line localization decodes a complete variable-length route word.

81.4 The incidence transceiver and the route-dark lattice

In plain language. *How a message gets from one machine to another. "Incidence" means the sender and receiver share a point of the geometry; the transceiver is the optical hardware that exploits it. The second half of the title is the failure mode: some routes are dark — structurally unreachable — and this section maps them rather than assuming a fully connected network.*

Pass 173 turns the address/route distinction into an exact signal law. For the line–point incidence matrix N, the centered operator

$$T = N - \frac{1}{10}J$$

has rank 24 and satisfies

$$TA_P = A_L T, \qquad T^{\mathsf{T}}T = 6E_{24}^{P}, \qquad TT^{\mathsf{T}} = 6E_{24}^{L}.$$

Thus $T/\sqrt{6}$ is a lossless transceiver on the shared gauge sector, while the unmatched address and route dark sectors remain type-protected. Every one of the 480 local-axis selector vectors produces a 40-channel analyzer word with histogram $\{-3^1, -1^9, 0^{20}, 1^9, 3^1\}$ and exact decoder $x = N^{\mathsf{T}}(Nx)/6$.

The two dark lattices are not interchangeable. The address lattice $\ker_{\mathbb{Z}} N$ has minimum shell 90 at norm 8 and binary code $[40, 15, 8]$; the route-dark lattice $\ker_{\mathbb{Z}} N^{\mathsf{T}}$ has minimum shell 432 at norm 10 and code $[40, 15, 10]$. Its 216 projective supports are exactly the pentad cores already used by the router: each is $K_{5,5}$ minus a perfect matching, and the deleted matchings double-cover the 540 skew-line chart atlas. The signed shell splits into the two chiral 216-orbits. Hence the old compass carrier is not merely count-compatible with the route layer; it is its complete minimum-energy integral dark shell.

The two 25-dimensional context duals are locally indistinguishable at their first two nonzero shells: both have $A_4 = 40$ and $A_6 = 240$. They first separate at the third shell,

$$A_8^{\text{address}} = 5085, \qquad A_8^{\text{route}} = 3645.$$

Moreover only the address code is self-orthogonal; the route code has binary Gram rank 6. Thus the Pass-164 $O^+(10, 2)$ quotient is address-chiral and cannot be silently reused as a route codec.

This also corrects the architecture vocabulary. At odd $q = 3$, $W(3,3)$ and its dual $Q(4,3)$ have equal $40 + 40$ counts and cospectral concurrence graphs, but are not incidence-self-dual. The lossless identification exists only on the shared 24-sector. The statement is an algebraic analyzer-ROM/control-codec theorem until a specified optical amplitude implementation of T is supplied. (Witness: `analysis/w33_pass173_incidence_transceiver_route_dark_lattice.py`.)

Pass 174 supplies the missing protected subcodec. Although the full route code $R = [40, 15, 10]$ is not self-orthogonal, its route-code hull is

$$H = R \cap R^{\perp} = [40, 9, 16], \qquad W_H = 1 + 135z^{16} + 240z^{20} + 135z^{24} + z^{40}.$$

The all-ones word is a fixed radical and $H/\langle \mathbf{1} \rangle$ is a plus-type 8-space with the exact $1 + 135 + 120$ native group orbits. Its 255 nonzero words reconstruct the symplectic graph $\mathrm{SRG}(255, 126, 61, 63)$ and its two quadratic subconstituents $\mathrm{SRG}(135, 70, 37, 35)$ and $\mathrm{SRG}(120, 63, 30, 36)$. So one route codec now supplies the complete finite stack

$$432 \text{ signed pentads} \to 216 \text{ cores} \to [40, 9, 16] \to 255 = 135 + 120.$$

The order-eight control rail is also less obstructed than the previous cohomology wording claimed. On both address and route discriminants, $[\tau(h) - h] = 0$ while $[\tau(h) - 5h] = [4h] \neq 0$. Thus a $q(h) = 11/8$ fixed order-eight rail exists; the nonzero class forbids only a pure scalar-5 normal form. This is a finite control-label theorem, not yet a fabricated phase rail. (Witness: `analysis/w33_pass174_dual_discriminant_fixed_rail.py`.)

Pass 176 removes the remaining abstract quotient choice. If $C = \ker_{\mathbb{F}_2} N$ and $R = \ker_{\mathbb{F}_2} N^{\mathsf{T}}$, the unique nonzero fixed isotropic class $f \in C^{\perp}/C$ is sent by incidence to the all-ones route word, and

$$f^{\perp}/\langle f \rangle \xrightarrow{N} (R \cap R^{\perp})/\langle \mathbf{1} \rangle$$

is an exact native-$\mathrm{PSp}(4,3)$ quadratic isometry. All 512 quadratic identities and 8192 generator/object commuting squares are checked. The 240 weight-six address words become the two explicit sheets over the 120 anisotropic route states and map bijectively to the 240 weight-20 hull words. This is an executable codec map; it still does not specify an optical transfer matrix, loss budget, or detector model.

Pass 177 then locates the first address/route classification depth in the *dual* context lattices. Both begin

$$1 + 720q^2 + 15360q^3,$$

where the 720 is coordinate doubles plus sign-lifts of lines on the address side and point stars on the route side. They first split at

$$q^4: \qquad 1350960 - 982320 = 368640.$$

Thus firmware may share the first two dual-shell tables, but must retain the type bit before admitting weight-eight sectors. Separately, the sentinel/context theta regression has an exact normalization because $A^{\vee} = \frac{1}{2}B$ and $\mathrm{covol}(A) = 2^{25}$; finite shell sums are regression checks only. Finally, $\ker_{\mathbb{Z}} N^{\mathsf{T}}$ is the point-trade lattice of the nonisomorphic dual $Q(4,3)$, whose span size is 2 versus 4 for $W(3,3)$. A route generator with $q = 11/8$ exists, but $3/8$ occurs on the other fixed-generator orbit, so no invariant $11/8$ hardware phase is inferred. (Witnesses: `analysis/w33_pass176_incidence_fixed_line_e8_bridge.py`, `analysis/w33_pass177_address_route_dual_theta_split.py`, and `analysis/w33_pass179_poisson_modular_pair.py`.)

Passes 188–192 refine the local controller geometry. The 432 route minima contain 36 exact double-six crowns: each is $K_{6,6}$ minus a matching, assembled from one K_6 in each of the two chiral

shell orbits, with faithful S_6 component symmetry. The naive homogeneous-product scheduler is ruled out:

$$(120 \text{ axes}) \times (36 \text{ double-sixes}) = 3240 + 720 + 360 = 120(27 + 6 + 3).$$

Thus a packet carrying an axis/double-six pair needs a three-valued relation-type tag; the 4320 pairs are not one native group orbit. The positive replacement is local: an axis stabilizer of order 216 acts on its distinguished three double-sixes through full S_3 with kernel 36, giving a genuine S_3/C_2 completion fibre.

Restoring signs gives an even sharper codec. The three positive octads of each signed second-shell trade contain a unique two-point edge of its matched four-point line; the three negative octads contain the complementary edge. Hence

$$240 \text{ signed trades} \longleftrightarrow 40 \text{ lines} \times 6 \text{ edge addresses},$$

with sign reversal implemented by edge complement. The line stabilizer satisfies $1 \to C_3^3 \to H_{\text{line}} \to S_4 \to 1$: its six signed states carry the tetrahedral-edge S_4 action, while complement-pairing gives the unframed S_3/C_2 axis action. Firmware must therefore not identify the six edge states with a regular S_3 clock merely because both sets have size six. (Witnesses: `analysis/w33_pass188_icosahedron_test.py`, `analysis/w33_pass191_supercycle_pullback.py`, and `analysis/w33_pass192_signed_trade_edge_s4.py`.)

Passes 209–212 close the global controller carrier without undoing that local warning. A route-shell double-six D now determines its timetable intrinsically:

$$\Sigma(D) = \{\ell : \ v_\ell = 0 \text{ for every signed minimum } v \in D\}.$$

The ten lines in $\Sigma(D)$ are pairwise skew and cover all 40 points; the 36 double-sixes recover all 36 spreads, equivariantly and bijectively. On the crossing-pair six-set of D, its ten silent lines are the ten unordered $3+3$ bisections, by a unique S_6-equivariant atlas. The associated doily is the derived duad–syntheme geometry on that six-set, not a literal incidence subgeometry on the twelve crown vertices.

This bridge gives the controller an exact two-stratum ABI. For a silent spread incidence (Σ, ℓ), the common stabilizer has order 72 and shape $(S_3 \times S_3){:}C_2$; its line-clock image is C_2 with kernel $S_3 \times S_3$. For an active pair $\ell \notin \Sigma$, the stabilizer is S_4, faithful on the four points of ℓ, and its line-clock quotient is $S_4/V_4 \cong S_3$. Thus the silent and active rows require an explicit stratum bit: they are two equivariant clock modes, not one direct-product clock.

Most importantly, the previously numerical 4320-carrier coincidence is now a canonical $\mathrm{PSp}(4,3)$-equivariant bijection. Let

$$X = \{(\Sigma, L, p) : L \notin \Sigma,\ p \in L\}, \qquad |X| = 1080 \cdot 4 = 4320.$$

For (Σ, L, p), let M be the unique line of Σ through p and let N be the unique line meeting M, disjoint from L, whose four Σ-owner lines equal those of L. Then

$$(\Sigma, L, p) \longmapsto (L, M, N)$$

is the required bijection to ordered nonlocal two-paths; the inverse chooses the unique such Σ and returns $p = L \cap M$. The path has three quadrangle completions, canonically indexed by the other three points of L, so the complete incidence surface is

$$1080 \cdot 4 \cdot 3 = 12960.$$

In the full $\mathrm{PGSp}(4,3)$ supercycle the path stabilizer is the split group $S_3 \times C_2$ of order 12: S_3 permutes the three completions, its central kernel has order two, and fixing one completion leaves V_4. That V_4 is an exact four-element branch carrier, but it is *not* a regular four-probe address on the completion line: the four points have orbits $1+1+2$. Firmware must supply any semantic probe-role labelling separately rather than infer it from group order. (GAP witnesses: `analysis/w33_pass209_silent_spread_two_clock.g`, `analysis/w33_pass210_s6_route_atlas.g`, `analysis/w33_pass211_pgsp_controller_clifford.g`, and `analysis/w33_pass212_4320_carrier_equivariant_bijection.g`.)

Passes 214–218 now separate the remaining controller sheets before any optical interpretation. The four points of the *source* line do carry a regular V_4 action: after choosing the source point, the identity fixes that port and the three nonidentity double transpositions address the other ports through their intrinsic pair-partition labels. This is the exact four-way switching algebra that the completion line lacked, but the residual S_3 still permutes the three nonidentity labels. A photonic controller must calibrate semantic port names; geometry supplies the torsor, not the laboratory naming convention.

The same carrier sheet selects the local-axis endpoint formed by the external line and its unique spread owner through the source point. GAP verifies the uniform tower

$$4320 \xrightarrow{18:1} 240 \xrightarrow{2:1} 120,$$

where endpoint complement is a fixed-point-free C_2 deck operation central in the extended order-103680 action. Via Pass 123's chosen chamber gauge it can be represented by an E_8 root sign; it is not a measured optical phase. Moreover the transitive W33-code action and the standard $E_6 \times A_2 < E_8$ branching action are nonconjugate and have different root-orbit fingerprints, so choosing rational E_8 coordinates remains a chamber calibration rather than a symmetry-forced device frame.

Incidence duality also changes the schedule type. $W(3,3)$ has 36 spreads and no ovoids, while $Q(4,3)$ has no spreads and 36 ovoids; the duality-odd checksum is therefore $\Delta_{SO} = \#\text{spreads} - \#\text{ovoids} = \pm 36$, not an Euler characteristic. The surviving Q carrier is the ovoid tower $4320 = 36 \cdot 15 \cdot 2 \cdot 4$ with stabilizers $S_6 > C_2 \times S_4 > S_4 > S_3$. It is the incidence-dual typing of the same controller, not a second independent optical channel, and its central mate swap is not an absolute handedness observable.

The construction is also special to field order three. At the tested odd anchors the regular-spread owner router covers the path carrier with degree $(q-1)/2$: $1, 2, 3$ at $q = 3, 5, 7$, so only $q = 3$ is lookup-free and bijective. The module backend changes at the same anchors: the $q = 5$ binary 24 is the $\mathbb{F}_2$ restriction of an $\mathbb{F}_4$ Weil 12, while the $q = 7$ 48 is the split dual pair $24 \oplus 24^*$. These are representation and control-plane constraints, not claims of fabricated modes or measured coherence. (GAP witnesses: `analysis/w33_pass214_source_line_v4_torsor.g`, `analysis/w33_pass215_carrier_double_six_signed_e8.g`, `analysis/w33_pass216_q43_dual_ovoid_carrier.g`, `analysis/w33_pass217_w3q_owner_spread_uniqueness.g`, and `analysis/w33_pass218_weil_shadow_split.g`.)

82 The carrier: how to self-entangle a photon

Entanglement is a relation between tensor factors; nothing requires the factors to be distinct particles. Self-entanglement is entanglement between one photon's own registers.

82.1 Stage A: spatial (one element)

A diagonal photon meets a polarizing beam splitter: $\frac{1}{\sqrt{2}}(|H\rangle + |V\rangle) \mapsto \frac{1}{\sqrt{2}}(|H,a\rangle + |V,b\rangle)$. Path and polarization are now maximally entangled *within* the photon; this two-qubit $\mathbb{C}^4$ is the Witting carrier of Theorem 81.2(i).

82.2 Stage B: temporal (two Clifford gates)

A tritter (symmetric 3-port coupler) *is* the qutrit Fourier gate F_3; a three-bin delay ladder $(0, \tau, 2\tau)$ defines past and future registers; one electro-optic modulator applies $\mathrm{CX}_{p\to f}$ conditioned on bin index. The temporal Bell qutrit

$$|\Omega\rangle \;=\; \mathrm{CX}_{p\to f}\,(F_3 \otimes I)|0\rangle_p|0\rangle_f \;=\; \frac{1}{\sqrt{3}}\sum_{j=0}^{2}|j\rangle_p|j\rangle_f$$

is verified exactly; the photon is entangled with its own future. Inserting any U in the future arm, the recombination visibility is the *trace–Choi witness*

$$V(U) \;=\; \frac{|\mathrm{Tr}\,U|}{3}, \qquad V(F_3) = \tfrac{1}{3}, \quad V(X) = V(Z) = 0,$$

so the photon implements the Choi–Jamiołkowski isomorphism on itself: it measures channels against its own past. *Witness:* `bt820_self_entanglement_protocol.py`.




Figure 3: Preparation schematic. One photon, four registers. The PBS entangles path with polarization (Stage A); the tritter–delay–EOM chain prepares the temporal Bell qutrit $|\Omega\rangle$ (Stage B); the dashed loop is the irrational Boerdijk–Coxeter drive of §90.

83 The network: atlas, building, and routing

Theorem 83.1 (The hypercube atlas)**.** *$W(3,3)$ contains exactly* 540 *skew line pairs. For each pair the non-collinearity graph on its* 8 *points is the cube graph Q_3, with full symmetry group O_h of order* 48 *(these are the only order-*48 *stabilizers; the binary $2O$ does not occur). Each chart admits an exact $\mathbb{F}_2^3$ Gray-code addressing in which chart edges are unit XOR moves and the antipode of a vertex is its unique collinear partner. Every $W(3,3)$ nonedge is a chart edge in exactly $12 = k$ charts; every edge is an antipode pair in exactly $9 = q^2$.* Witnesses: `bt773`, `bt777`, `bt778`.

83.1 Hypercube networking, not hypercube decoration

In plain language. *A warning against a tempting shortcut. The network's addresses look like the corners of a hypercube, which invites reusing standard hypercube routing — and that would be wrong here, because the geometry constrains which moves are legal in a way a hypercube does not. This section shows where the two diverge.*

The cube is not only a picture for one chart. It is the local interconnect primitive. A chart gives eight simultaneously valid addresses

$$000,\ 001,\ 010,\ 011,\ 100,\ 101,\ 110,\ 111 \in \mathbb{F}_2^3,$$

and the elementary network instruction is the dimension-order hypercube hop

$$a \longmapsto a \oplus e_i, \qquad i \in \{1,2,3\}.$$

This is the standard e-cube rule of hypercube networks: compare source and target, flip one differing coordinate at a time, and finish in at most three local hops [13]. In the holonet that same XOR flip is also a register operation, because the chart address is a finite "which-register" word on the photon's self-entangled carrier. The local routing primitive is therefore simultaneously

$$\text{bit flip} \quad = \quad \text{qutrit-frame update} \quad = \quad \text{optical path choice.}$$

A packet in the photonic holonet is not merely a payload. The natural packet header is

$$\mathcal{P} = (\text{payload},\ \text{Pauli frame},\ \text{chart word},\ \text{apartment hop},\ \text{mirror slot},\ \text{clock phase}).$$

The payload is the quantum state or teleported gate; the Pauli frame is the two-trit feedforward record; the chart word is the $\mathbb{F}_2^3$ route inside the current cube; the apartment hop selects the next chart; the mirror slot chooses the D_{12} transport bus of §84; and the clock phase is the cyclic C_{12} interrupt that keeps the selector coherent. This is why the same object can be called a computer architecture and a network architecture. A node never sends data to a processor: the act of transport is the processor's gate action.


Theorem 83.2 (The fabric is the building)**.** *The chart-adjacency web (*540 *nodes, two charts adjacent when one's axis is a disjoint transversal pair of the other) is* 6*-regular with exactly* 1620 *edges, and these edges are in canonical bijection with the* 1620 *apartments of the Tits building of* $\mathrm{Sp}(4,\mathbb{F}_3)$*. The web has diameter* 5*; its adjacency module contains the Steinberg representation twice and presses against the Ramanujan bound only on a* 15*-dimensional sentinel eigenspace.* Witnesses: `bt777`, `bt779`, `bt744`.

Routing a packet means choosing XOR moves inside charts and apartment hops between them; since chart moves *are* register operations (§85), routing is computation. At scale the recursion is the holonet ladder: 40^n cores at level n, the same $\mathrm{SRG}(40,12,2,4)$ at every level, with the level-0 chart's $1+12+27$ degree split realized as self pole, gauge shell, and matter shell of each node.

Corollary 83.3 (Two-plane routing bound)**.** *Inside a chart the worst route length is* 3*, the diameter of* Q_3*. Between charts the worst route length is* 5*, the diameter of the apartment web. One recursive digit of a holonet address therefore costs at most*

$$3+5=8$$

reversible transport moves. BT827 globalizes this to $8n = 8\log_{40} N$ *for* $N = 40^n$ *photonic leaves.*



one chart: Q_3, XOR routing, antipode = collinear partner

the web (sketch): 540 charts, 6-regular, 1620 links = apartments, diameter 5

Figure 4: Network schematics. Left: a single chart with its $\mathbb{F}_2^3$ addressing (XOR routing native). Center: the 540-chart web whose links are the apartments of the Tits building (sketched as a circulant fragment). Right: the two-level routing stack.

84 The middleware: tomotope mirrors and the runtime bus

In plain language. *The layer between the geometry and the running program — the part that would be an operating system in a conventional machine. It routes, schedules and checks, and it is built from the same object as everything below it rather than being written on top.*

Definition 84.1 (Tomotope packet)**.** *In this paper the tomotope is used in the only way the finite calculation currently justifies: as a local middle-layer incidence packet. A tomotope packet has four vertex carriers, twelve local edge axes, sixteen triangular face labels, and forty-eight edge–face incidence blocks. The doubled base/shadow fiber gives* 192 *flags. Thus the tomotope is the durable packet format sitting between the fast cube router and the global mirror bus; it is not introduced as an ambient continuous torus, and it is not identified with the rectangle clock.*

The atlas contains two different 2160-element boundary worlds. They must not be collapsed. The rectangle side is cyclic: its stabilizer is C_{12} and it supplies the selector's phase clock. The chart-transversal side is dihedral: its stabilizer is D_{12} and it supplies the mirror transport bus. Equal cardinality is the red herring; different stabilizer structure is the theorem.

Theorem 84.2 (The D_{12} mirror bus)**.** *The* 540 *cube charts carry exactly four common-transversal slots each, so the global chart-transversal space has* $540 \cdot 4 = 2160$ *slots. The map*

$$(\textit{chart},\ \textit{common transversal line}) \longmapsto (\textit{chart},\ \textit{antipode pair cut out by that transversal})$$

is an equivariant bijection onto the atlas antipode-slot space. Its projective stabilizer has order 12 *and GAP identifies it as* D_{12}*, not* C_{12}*.* Witness: `bt815_global_2160_transversal_gset.py`.

Locally, a skew-line chart has four common isotropic transversals. Read those four transversals as the four vertex carriers of the tomotope middle layer. Each transversal is a K_4, and each K_4 has three opposite-edge axes and four triangular faces. Thus the chart carries

$$4 \text{ vertices}, \qquad 4 \cdot 3 = 12 \text{ edge labels}, \qquad 4 \cdot 4 = 16 \text{ face labels},$$

and the middle incidence packet has

$$4 \cdot 3 \cdot 4 = 48$$


edge–face blocks, with the doubled base/shadow fiber restoring 192 flags. This is the local $\langle r_0, r_3 \rangle$ tomotope block layer, not an analogy to a toroidal polyhedron. *Witness:* `bt814_tomotope_middle_layer_from_residual_tetrahedra.py`.

Theorem 84.3 (Photonic mirror middleware)**.** *The full optical Clifford runtime factors as*

$$|\mathrm{Sp}(4, \mathbb{F}_3)| = 51840 = 24 \cdot 2160 = 24 \cdot 45 \cdot 48.$$

Here $24 = f$ *is the full* $\mathrm{Sp}(4, 3)$ *lift of the projective* D_{12} *mirror-slot stabilizer,* 45 *is the hyperbolic polar-pair/tritangent geography, and* 48 *is the local tomotope edge–face middle layer (also the order of the chart group* O_h*). Equivalently, the photon is clocked by the cyclic selector side and routed by the dihedral mirror side; the complete Clifford group is the lift of that mirror bus through the tomotope middle carrier.* Witness: `bt826_photonic_mirror_middleware.py`.

This is the architectural closure missing from a bare universality claim. The tritter, phase plate, and controlled delay generate the whole Clifford group, but the group is *organized* as a middleware stack: full slot stabilizer, global mirror bus, polar vacuum geography, and tomotope local block. In software terms, C_{12} is the clock interrupt, D_{12} is the mirror router, 48 is the local packet format, and $24 \cdot 45 \cdot 48$ is the finite runtime.



fast XOR routing is committed through the tomotope middle layer and reflected by the mirror bus.

Figure 5: Middleware schematic. The cube is the reversible local router; the tomotope is the edge–face packet format; the D_{12} bus is the global mirror transport object.

84.1 Product-grid closure ABI v2

The 12 closure strands are modeled as

$$C_3 \times V_4, \qquad V_4 = C_2 \times C_2,$$

rather than as a bare C_{12}. The C_3 coordinate is the Szilassi/Fano channel and qutrit phase axis; the V_4 coordinate is the four-triangle E6 gauge-shell/D4 branch axis.

The E6 firewall square is now upstream in the claim DAG through the exact nodes

$$36 \to 72, \qquad 72 + 6 = 78, \qquad 72 + 9 = 81.$$

This supports the exact finite ABI/CSS branch while leaving blocked formula and physics claims downstream of the transcription gate.

The closure packet ABI is upgraded to v2. Each packet carries C_3 channel, V_4 branch, active/-guard outputs, 72-row sector metadata, the nine-mode firewall gap, and claim-DAG dependencies.

84.2 ABI v2 consumer, E6 claim table v2, and D4/V4 branch audit

The closure ABI v2 is executable. It regenerates 12 packets, 48 events, and 72 rows while preserving the dual-axis metadata. The three C_3 channels each carry 24 rows, and the four V_4 triangles each carry 18 rows.

The E6-merged claim DAG now produces a table with explicit E6 provenance for the 72-sector, the 81 closure, and the $C_3 \times V_4$ grid. Blocked formula and physical claims remain downstream.

On branch classes, D4 shear fixes each V_4 triangle, while τ_4 acts as an order-two translation preserving the triangle partition as a set. The two operations still fail to commute on full branch/phase states, so retwining remains part of the exact decoder rule.

84.3 BT1486–BT1488 ABI v2 retwined CSS and splice manifest

BT1486 reruns the CSS join from the ABI v2 consumer output. The result is not just the old 72-row count: every row satisfies the retwined X- and Z-syndrome checks, while the C_3 channel profile remains $P_0 = P_1 = P_2 = 24$ rows and the V_4 triangle profile remains $T_0 = T_1 = T_2 = T_3 = 18$ rows.

BT1487 classifies the branch symmetries behind those four triangles. The full triangle-partition stabilizer is S_4 of order 24, giving the Fano point reading $7 \cdot 24 = 168$. The physically used square subgroup is D_4 of order 8, giving the Fano flag reading $21 \cdot 8 = 168$. Thus the active detector-bin count is Fano-native, not merely an optical count.

BT1488 updates the splice cascade: the E6 claim table v2 from BT1484 supersedes the BT1472 table as the preferred paper table, and the preferred exact finite insert packet is now BT1474, BT1480, BT1482, BT1484, BT1486, and BT1487. The Golden Quartic/Moebius-ball equation fill remains blocked pending rendered formula transcription; no public source-code repository is assumed.

84.4 BT1489–BT1491 row symmetry and Fano–E6 square

BT1489 lifts the S_4, D_4, and V_4 branch actions from triangle labels to the actual ABI v2 row layer. All 24 elements of S_4, all 8 elements of the square D_4 subgroup, and all 4 V_4 translations act as honest permutations of the 72 active/guard value rows. The lift preserves the C_3 channel, row kind, qutrit value, guard slot, and column formula, so the branch symmetry is now a decoder-row symmetry.

BT1490 is the new finite-geometry lock:

$$24 = 4 \cdot 6 = 3 \cdot 8, \qquad 72 = 3 \cdot 24, \qquad 168 = 7 \cdot 24 = 21 \cdot 8, \qquad 81 = 72 + 9.$$

The shared 24-state fiber is V_4 branch times six row-value slots on the ABI side, and three local Fano arms times the D_4 flag stabilizer on the Fano side. Thus the same finite fiber feeds the E6/CSS 72-sector, the 81-closure after adjoining the $q^2 = 9$ firewall gap, and the Fano-native 168 active-bin bus.

BT1491 makes the paper splice idempotent. The main holonet paper now imports the BT1480–BT1491 exact finite packet through one controlled block; rerunning the splicer replaces that block rather than duplicating it. The claim firewall remains intact: this is an exact finite ABI and incidence statement, not a detector calibration, optical-layout claim, or imported Golden Quartic/-Mobius particle interpretation.

84.5 BT1492–BT1494 canonical Fano fiber and pulse release lock

BT1492 removes the last arbitrary index from the 24-state bridge. In the Fano plane, $\mathrm{GL}(3,2)$ has order 168. Fixing one point leaves a point stabilizer of order 24, and this stabilizer acts as the full S_4 on the four Fano lines not through that point. Fixing one incident flag leaves an order-8 flag stabilizer with the D_4 order profile. Therefore the shared fiber is canonical:

$$24 = 3 \cdot 8,$$

namely three Fano lines through the anchor point times the D_4 flag stabilizer.

BT1493 compiles those row symmetries down to the existing physical holonet interfaces. A row action first selects a BT1411 detector slot, then hands that slot to the BT1374 rule mirror_slot mod 4, and finally occupies the matching BT1407 Hesse epilogue lane for its C_3 channel and row-value slot. All 24 S_4 actions compile across all 72 rows, while the order-8 D_4 square subgroup is the native square-pulse layer.

BT1494 repairs the broad photonic-QEC release lock. The legacy tests expected selected `PART_*` artifacts at the repository root, while the preserved copies lived under `manuscripts/parts`. The repair restores those root release-lock targets and regenerates the live scheduler, harmonic bus, fusion splice, and projective screen/bulk/QEC artifacts.

85 The software: braids, teleported gates, universality

85.1 Exact braid words

In the anyonic Fibonacci representation $\sigma_1 = \mathrm{diag}(\zeta^4, -\zeta^2)$ ($\zeta = e^{i\pi/5}$) one has *exactly* $\sigma_1^5 = Z$ and $\sigma_1^{10} = I$ — not merely projectively (verified in the cyclotomic ring $\mathbb{Z}[\zeta_{10}]$). In the dual ($\pm$) encoding of the local $K_{3,3}$ cycle code $\mathbb{F}_2^4$ this makes every register bit-flip an exact five-letter braid word, and the flat global register (the unique connected gluing with trivial holonomy across the atlas) carries the action coherently: a zero-Berry-phase memory. *Witnesses:* `bt740`, `bt741`.

85.2 The photon is its own gate

A gate U is stored as the self-entangled state $(I \otimes U)|\Omega\rangle$; Bell-projecting an input register against the photon's *past* register outputs U (times a known Pauli correction) on the *future* register — verified for all nine outcomes. The machine's gate library is a library of self-entangled states; executing software means interfering the photon with its own history. *Witness:* `bt821`.

85.3 Instruction set architecture

The practical instruction set is finite:

$$\mathcal{I}_{\mathrm{holo}} = \{F_p, F_f,\ S_p, S_f,\ \mathrm{CX}_{p\to f},\ \sigma^5 = Z,\ D_{12}\text{-mirror},\ M_{36}\text{-magic}\}.$$

F and S generate single-qutrit Clifford frame changes; CX couples past to future; $\sigma^5 = Z$ gives exact braid-register flips; the D_{12} mirror operation moves a packet through the atlas without confusing it with the cyclic selector clock; and M_{36} denotes injection from the thirty-six magic rays of §88. The Clifford part normalizes Pauli frames and is efficiently classically trackable; it is not universal by itself. Universality starts only when the Clifford runtime can consume the intrinsic magic sector. This is the engineering meaning of "matter equals magic": the same thirty-six rays that appear as the matter shell are the non-Clifford fuel for the processor.

85.4 The minimal classical shadow

The smallest classical headline compatible with the substrate is the pair

$$(\lambda, q) = (2, 3).$$

This is the same two-state, three-symbol signature made famous by the Wolfram–Smith weakly universal Turing machine. The present paper does not use that result as the proof of quantum universality; the proof is the Clifford closure plus magic/contextuality [17, 16]. The point is sharper: the classical shadow of the photonic holonet lands on the same minimality boundary. The quantum machine has forty rays and an $81 = q^4$ protected register, but its smallest visible finite-state control alphabet is already the substrate pair $2, 3$.

85.5 The Universality Theorem

Theorem 85.1 (Clifford completeness from optics)**.** *The symplectic images of the photon's physical elements — the tritter F_3 on either register, the quadratic phase plate S, and the delay-conditioned* CX *— generate all of* $\mathrm{Sp}(4, \mathbb{F}_3)$ *(closure of order* 51840*, exact). Hence tabletop optics realize the complete two-qutrit Clifford group modulo Paulis and phases.* Witness: `bt825_universality_theorem.py`.

Theorem 85.2 (Conditional universality criterion)**.** *Clifford completeness, together with a fault-tolerant preparation and injection of a distillable qutrit magic state, gives a universal gate set. The finite substrate certifies the Clifford closure and a nonclassical contextuality obstruction. It does not, from those facts alone, certify that the thirty-six distinguished rays are physically preparable magic states or that a single photon supplies a protected injection circuit.*

Evidence boundary. Contextuality is a resource diagnostic, not a compiled optical protocol. Promoting the conditional criterion to a hardware universality theorem requires an explicit state preparation, injection gadget, decoder, and noise threshold for the chosen photonic encoding. Accordingly, later "matter equals magic" and unit-premium statements are architectural hypotheses unless they name those missing maps; the exact finite results do not establish them.

86 Fractal scaling: the computer is the network

The single-core theorem is not the end of the architecture. The substrate is self-similar: any node may be replaced by a fresh copy of the same forty-node holonet, with the parent line/point incidence becoming the routing grammar for the child layer.

Definition 86.1 (Recursive holonet)**.** *Let $\mathcal{H}_0$ be one self-entangled photonic qutrit. Define $\mathcal{H}_n$ recursively by replacing each point of one copy of $W(3, 3)$ with a copy of $\mathcal{H}_{n-1}$. Thus $\mathcal{H}_1$ is the single-core machine of this paper and $\mathcal{H}_n$ is a* 40*-ary fractal computer/network.*

Theorem 86.2 (BT827 holonet scaling law)**.** *A level-n holonet has*

$$N_n = 40^n$$

photonic leaf cores and

$$I_n = 1 + 40 + \cdots + 40^{n-1} = \frac{40^n - 1}{39}$$

total $W(3,3)$ instances. Its total edge-qutrit slots are $240I_n$, its directed transport slots are $480I_n$, its chart routers are $540I_n$, its apartment links are $1620I_n$, its mirror slots are $2160I_n$, and its local Clifford runtime atoms are $51840I_n$. Worst-case reversible routing across the recursive address uses at most

$$8n = 8\log_{40} N_n$$

moves, where $8 = 3 + 5$ is one in-chart hypercube diameter plus one chart-web apartment diameter. Durable commits use the distinct Császár/tomotope clock

$$T(0) = 1, \qquad T(g) = 4(7^g - 1) \quad (g \geq 1).$$

Witness: `bt827_holonet_fractal_architecture.py`.

level n	leaves 40^n	$W(3,3)$ instances	mirror slots	runtime atoms	route bound
1	40	1	2160	51840	8
2	1600	41	88560	2125440	16
3	64000	1641	3544560	85069440	24
4	2560000	65641	141784560	3402829440	32




Figure 6: Fractal scaling schematic. The drawn fans show only a few children; the rule is exact substitution of forty child holonets at each substrate point. Routing grows logarithmically in the number of photonic leaves because each recursive digit costs at most eight reversible moves.

This resolves the computer-engineering question. A conventional machine grows by adding processors connected by a separate network. The holonet grows by adding copies of the same object; each copy contains its own processor, router, memory, clock, and packet format. There is no von Neumann bus to saturate. At every scale, the edge set is both communication bandwidth and entangling-gate availability, the chart atlas is both routing table and instruction decoder, and the Steinberg 81-sector is both protected memory and fault-tolerant logical space.

87 Runtime closure: compile, monitor, commit

The architecture now has an executable operating-system loop.

address word $\longrightarrow$ packet route $\longrightarrow$ sentinel monitor $\longrightarrow$ durable tomotope commit.

BT828–BT831 make each arrow finite and testable.

Theorem 87.1 (BT828 packet compiler)**.** *A recursive address word with digits in* $\{0,\dots,39\}$ *compiles to a sequence of digit packets*

$$(Q_3\text{-XOR hops},\ \text{apartment hops},\ D_{12}\ \text{mirror slot},\ C_{12}\ \text{phase},\ \text{tomotope block}).$$

Each digit uses at most three XOR hops and at most five apartment hops, hence at most eight reversible moves. The stress route

$$(0,7,14,21,28,35) \longrightarrow (39,32,25,18,11,4)$$

compiles to 47 *reversible moves, below the level-six bound* 48. Witness: `bt828_holonet_packet_compiler.py`.

Theorem 87.2 (BT829 sentinel monitor)**.** *The projector onto the* $g = 15$ *adjacency sector of* $W(3,3)$ *has exact entry profile*

$$P_{-4}(x,x) = \frac{3}{8}, \qquad P_{-4}(x,y) = \begin{cases} -\frac{1}{8}, & x \sim y, \\ \frac{1}{24}, & x \nsim y. \end{cases}$$

Consequently a full context line K_4 *is sentinel-invisible, while localized, mirror, and shell faults activate the sentinel with exact energies:*

fault	*energy*	*normalized fraction*
single point	3/8	5/13
adjacent edge	1/2	5/19
nonedge mirror pair	5/6	25/57
gauge shell $N(x)$	6	5/7
matter shell	27/8	5/13

The immune system is therefore not generic noise detection: it is blind to legal context-line traffic and tuned to off-context routing and shell congestion. Witness: `bt829_fault_sentinel_monitor.py`.

Theorem 87.3 (BT830 two-phase commit clock)**.** *The runtime has two clocks. The reversible prepare phase finishes in at most* $8n$ *moves. The durable commit phase waits for*

$$T(n) = 4(7^n - 1).$$

For $1 \le n \le 24$, $T(n)$ *is always divisible by* 24 *and by* 8*, so it is aligned with both the local runtime stabilizer and the single-digit route window. But it is not always divisible by the full* $8n$ *route epoch: the first desynchronization is* $n = 5$*, with remainder* $24 = f$*. Thus the commit layer is deliberately slower and cover-like; it is not merely the route clock renamed.* Witness: `bt830_two_phase_commit_clock.py`.

87.1 The infinite-cover warning

The tomotope contributes a harder boundary than the earlier packet picture showed. Monson, Pellicer, and Williams prove that the tomotope has infinitely many distinct minimal regular covers; for coprime odd $p, q > 1$ there are minimal covers R_p, R_q of the tomotope such that neither covers the other, and neither covers the special R_2 cover [20]. They also record the toroidal cover arithmetic

$$|\mathrm{Mon}(Q_k)| = 36864\,k^6, \qquad Q_k : \ (4,24,32,8,4)k^3$$

for vertices, edges, triangles, tetrahedra, and octahedra.

Architecturally this is a big correction. The 48-block tomotope middle layer is a stable local ABI, but the global regular cover is not unique. Durable storage must therefore carry a *cover index* k as an implementation gauge. Fast routes compile to the same invariant packet, while persistent storage may choose one minimal cover family without invalidating the other non-comparable families. *Witness:* `bt831_tomotope_minimal_cover_architecture.py`.

87.2 Cover-indexed storage, rerouting, and guard bands

In plain language. *Where data physically sits and what happens when part of the machine fails. Storage locations are indexed by the geometry rather than by an address counter, which means a failure has a shape: the states lost when one component dies are a geometrically describable set, and rerouting can be planned against it in advance.*

The infinite-cover warning would be useless as engineering unless it changed the runtime. BT832–BT834 make it operational. The principle is that the local tomotope packet is the ABI and the chosen regular cover is the storage backend.

Theorem 87.4 (BT832 cover-indexed durable storage)**.** *For every supported cover index k, durable storage is the lifted packet space*

$$\{0,\dots,47\}\times\mathbb{Z}_k^3, \qquad |slots| = 48k^3,$$

with projection back to the fast-route ABI by forgetting the $\mathbb{Z}_k^3$ coordinate. The kernel to the base tomotope packet has order

$$k^6 = (k^3)^2,$$

matching the Monson–Pellicer–Williams toroidal cover law $|\mathrm{Mon}(Q_k)| = 36864k^6$. Changing k changes durable capacity and kernel size, but not the packet program seen by the compiler. Tested cover gauges $k = 3, 5, 7, 11, 13$ all reduce exactly to the same 48-block ABI, and larger k reduces the load fraction of the same stress program. Witness: `bt832_cover_indexed_durable_storage.py`.

Theorem 87.5 (BT833 sentinel-aware packet rerouting)**.** *The BT829 projector supplies a compiler-visible cost function. Before the durable commit, each digit route may insert up to two W33 waypoint points and minimize*

sentinel energy first, reversible move count second.

The extra reversible moves are charged to the slower BT830 commit phase, not to the BT827 fast $8n$ route bound. In the level-six stress program the direct route uses 47 moves and total sentinel energy 4; the sentinel-aware route uses 58 moves, still far below the 470592-tick commit window, and lowers the total sentinel energy to 2. Each tested digit route strictly lowers its own $g = 15$ energy; adjacent endpoints can be context-completed to zero, and nonedge mirror pairs drop below their direct 5/6 activation. Witness: `bt833_sentinel_aware_packet_rerouter.py`.

Theorem 87.6 (BT834 desynchronization guard-band arithmetic)**.** *The two-phase clock has an exact number-theoretic boundary. Full route-epoch synchronization is*

$$8n \mid T(n) = 4(7^n - 1),$$

equivalently

$$2n \mid 7^n - 1.$$

For every odd prime power $p^a \mid n$ with $p \neq 7$, this requires $\mathrm{ord}_{p^a}(7) \mid n$; if $7 \mid n$, synchronization is impossible because the base is not coprime. The first failure is $n = 5$: $\mathrm{ord}_5(7) = 4 \nmid 5$, and the remainder is

$$T(5) \bmod 40 = 24 = f.$$

Thus the first cover-index where durable storage and the full route epoch separate is not empirical drift; it is the $f = 24$ guard band of the tomotope-backed runtime. Witness: `bt834_desync_guard_band_arithmetic.py`.

Theorem 87.7 (BT838 tomotope Wythoff runtime ladder)**.** *The Grünbaum–Coxeter/tomotope operation tables give the local tomotope counts*

$$\textit{original, rectified, truncated, maximal expanded, omnitruncated} \quad = \quad 4,\ 12,\ 24,\ 48,\ 96.$$

These are exactly the runtime packet-growth layers:

$$4 = \mu \quad (\textit{vertex carriers}), \qquad 12 = k \quad (\textit{edge axes}), \qquad 24 = f \quad (D_{12}\ \textit{lift}),$$

$$48 = 2f \quad (\textit{BT814 packet ABI}), \qquad 96 = 4f \quad (\textit{half-flag boundary}).$$

The doubled omnitruncated boundary gives the verified full packet flags, $2 \cdot 96 = 192$. After a cover lift this becomes

$$48k^3 = \textit{BT832 lifted packet capacity}, \qquad 192k^3 = |W_k|,$$

the W_k order already recorded in the tomotope cover architecture. Thus the Wythoff operations are not decorative variants; they are the compiler's packet expansion states:

$$\textit{carrier} \to \textit{edge-axis} \to \textit{mirror lift} \to \textit{packet ABI} \to \textit{flag boundary}.$$

Witness: `bt838_tomotope_wythoff_runtime_ladder.py`.

88 The fuel: matter = magic

Theorem 88.1 (The triality)**.** *In the photon's two-qubit reading, exactly the 4 basis rays are stabilizer states and all 36 ω-rays are magic (no stabilizer state has support 3). Consequently three classifications coincide exactly, on rays $[4, 36]$ and on contexts $\{4{:}1,\ 1{:}12,\ 0{:}27\}$: the holonet vacuum split, the Schmidt (self-entanglement) strata, and the magic strata.* The matter shell is the machine's non-classical resource sector. Witness: `bt822`.

Theorem 88.2 (Three grades and the cube inside)**.** *Stabilizer fidelity splits the 36 magic rays into grades*

$$\underbrace{8}_{2^q}\ \textit{deep}\ \left(F = \tfrac{2+\sqrt{3}}{6}\right), \qquad \underbrace{24}_{f}\ \textit{mid}\ \left(F = \tfrac{5+2\sqrt{3}}{12}\right), \qquad \underbrace{4}_{\mu}\ \textit{shallow}\ \left(F = \tfrac{3}{4} = \tfrac{q}{\mu}\right),$$

the shallow grade sitting exactly at the Werner decoherence threshold. The 8 deep rays are precisely the point set of a hyperbolic polar pair (the 24-cell vacuum axis), and the 27 fully-magic contexts stratify by grade signature as $1+8+12+6$ — the cell census of the cube. Witnesses: `bt822`, `bt823`.

Theorem 88.3 (Exact contextuality budget)**.** *The maximum number of contexts a classical* $\{0,1\}$ *valuation can satisfy exactly-once is exactly* $36 = (q!)^2$ *(complete branch-and-bound over all* 2^{40} *markings): classicality saturates at the spread count, the deficit is exactly* $\mu = 4$*, and the contextual fraction is exactly* $1/10 = 1/\Phi_4$*. A perfect valuation would be an ovoid, and* $W(3,3)$ *has none: the true independence number is* $\alpha = 7 = \Phi_6$*, attained only by the beacon heptads of §91, against the Lovász bound* $\vartheta = 10$ *— the* $\vartheta - \alpha$ *gap* $3 = q$ *is the combinatorial face of Kochen–Specker.* Scope, added after Pass 4800: both identifications are exact at $q = 3$ and neither extends. Exhaustive computation gives $\alpha(W(3,5)) = 18$, whereas $\Phi_6(5) = 21$ and the gap is $26 - 18 = 8 \neq q$. What survives at every q tested is the parity statement: $W(3,q)$ attains its bound if and only if q is even, and the odd-q failure widens with q rather than closing. Witnesses: `bt818`, `bt823`.

Theorem 88.4 (Conditional matter-equals-magic architecture)**.** *The exact finite inputs are the* $36 = (q!)^2$ *distinguished rays, their* $8 + 24 + 4 = \{2^q, f, \mu\}$ *grading, the contextual fraction* $1/\Phi_4 = 1/10$*, and the qutrit Strange state's mana* $\log(5/3)$ *(stabilizer states have mana* 0*). Separately, the homological register is the* $[[240, 81, 3]]_3$ *Steinberg code, equivalently* $[[240, 81, 4, 3]]_3$ *in the ordered convention* $[[n, k, d_Z, d_X]]_3$*. If a protected encoding and injection map identifies prepared copies of the distillable state with the distinguished-ray sector of that register, then one hardware layer could serve both error correction and non-Clifford injection. The counts and contextuality witness do not construct that map, prove replenishment, or remove a distillation factory.* Witness: `analysis/w33_magic_economy.py`.

Exact resource boundary from the QR branch (Passes 361–367). The theorem above is an architectural proposal for the qutrit/GKP branch; a count of contextual rays is not by itself a compiled injection circuit or a threshold theorem. The independently certified binary QR-137 branch makes that distinction concrete. Its one-block simple lift supplies only logical H; the multi-block construction supplies the real Clifford tower $O^+(2m, 2)$; and the first named phase lift is the weight-137 Clifford rotation $\exp(-\pi i \bar{Z}/4)$. That operator normalizes the exact stabilizer but is not yet transversal, local, low-weight, or proved fault-tolerant. Consequently the QR witnesses do not establish $P = 1$ or remove magic-state distillation. Doing so requires an explicit protected resource-state preparation/injection circuit, decoder, and noise-threshold analysis for the chosen physical branch.

The conditional resource accounting. Define the non-Clifford premium $P = \text{cost(non-Clifford)}/\text{cost(Clifford)}$. In the surface-code baseline a non-Clifford gate needs a distilled magic state, so $P \sim O(d^3)$ (the distillation factory, $\sim 10^3$–10^4 qubit-rounds at useful code distances d, occupying 30–90% of the device — the dominant cost of fault tolerance). In the proposed shared-layer implementation, $P = 1$ is a design target: it would require a protected injection to cost one correction cycle. Neither the equality nor an $O(d^3)$ saving follows until that injection, decoder, and threshold are supplied. (Witness: `analysis/w33_magic_resource_accounting.py`.)

What the irrational clock does and does not prove. The Boerdijk–Coxeter twist $\theta = \arccos(-2/3)$ — the $q = 3$ simplex angle, $-2/3 = -(q-1)/q$ — has θ/π *irrational* (Niven, since $\cos\theta = -2/3 \notin \{0, \pm\frac{1}{2}, \pm 1\}$), so the stroboscopic phases $\{n\theta \bmod 2\pi\}$ never repeat, are Weyl-equidistributed (star discrepancy $\to 0$), obey the Steinhaus three-gap law, and never land exactly on a stabilizer angle $2\pi k/q$. This proves aperiodicity, not gate type: an irrational phase sequence need not implement a cubic Hamiltonian, a distillable state, or a protected non-Clifford injection. Establishing replenishment requires an explicit driven Hamiltonian/control map and a classification of its logical action. (Witness: `analysis/w33_clock_magic_renewal.py`.)

And the code is holographic. The matter shell is not just a code but a *holographic* one. From any pole the 40 rays split $1 + 12 + 27 =$ self + gauge boundary + matter bulk, and every bulk ray is screened by exactly $\mu = 4$ boundary rays. That strongly-regular screening multiplicity is a combinatorial redundancy, not the full CSS distance: the edge code has $d_X = 3$, $d_Z = 4$, and hence $d = 3$. It therefore corrects one arbitrary qutrit error or two known-location arbitrary erasures. The $\mu = 4$ neighbourhood by itself does not prove recovery from three arbitrary erasures; an operational bulk-reconstruction map would be additional data. The causal diameter is 2 (every bulk ray one hop from the boundary, two from the pole), the RT-like depth; and the logical register H_1 is the irreducible Steinberg module (dim $81 = q^4$), so there is no local logical operator — logical information lives only nonlocally on the boundary. Boundary redundancy, an RT-like causal depth, and no local logical representative are the proposed holographic signature: the "holo" in holonet is earned. (Witness: `analysis/w33_holographic_code.py`.)

Theorem 88.5 (Conditional self-fueling holographic-memory proposal)**.** *The exact finite inputs are the Steinberg-code dimensions and distances* $(k, d_X, d_Z) = (81, 3, 4)$*, screening multiplicity* $\mu = 4$*, the* 36*-ray contextual sector, the fraction* $1/10$*, the irrational angle* $\arccos(-2/3)$*, and the graph-cut counts* 12*,* 4*, and* $108 = 4 \cdot 27$*. Calling these one self-fueling holographic memory requires three additional maps: a bulk–boundary recovery channel, a protected resource-state injection, and a logical clock action that actually produces that resource. The current witnesses certify the finite inputs, not those identifications; in particular they do not prove* $P = 1$ *or eliminate distillation. (Witnesses:* `analysis/w33_self_fueling_memory.py`*,* `analysis/w33_holographic_rt.py`*.)*

Theorem 88.6 (Finite-curvature/de Sitter analogy and conditional cost model)**.** *The collinearity graph* $W(3, 3)$ *has positive Ollivier–Ricci curvature — computed by optimal transport,* $\kappa = 1 - W_1(m_x, m_y) = 1/6 = 2/k$ *— the discrete finite identity* $E\,\kappa = 240 \cdot \frac{1}{6} = 40 = v$ *(Face 1). These exact facts motivate a de Sitter analogy; they do not identify the graph with spacetime, its cuts with horizons, or its clock with cosmological time. (Witness:* `analysis/w33_memory_is_desitter.py`*.)*

Conditional cost model. *If the missing protected injection consumes resource states at the contextual-fraction rate* $1/\Phi_4 = 1/10$ *per cycle, then a circuit with non-Clifford fraction* $f \le 1/10$ *would avoid rate throttling, while* $f > 1/10$ *would require the model factor* $10f$ *in time or parallel cores. The finite fraction is exact; the replenishment law, factory removal, and claimed hardware saving remain conditional on the unbuilt compiler and threshold. (Witness:* `analysis/w33_self_fueling_cost.py`*.)*

89 Memory, protection, and the immune system

In plain language. *How the machine stores information without losing it. Quantum states decay, so a useful memory has to notice damage and repair it before the damage accumulates — the reason for the biological metaphor. What makes this section unusual is that the code doing the protecting is not designed and then bolted on: it is already present in the geometry, as the shape's own hole structure.*

Theorem 89.1 (The code register is the Steinberg module)**.** *The companion paper's CSS code* $[[240, 81, 3]]_3$*, with asymmetric distances* $(d_X, d_Z) = (3, 4)$*, stores its* 81 *logical qutrits in* H_1 *of the* $W(3, 3)$ 2*-complex (*40 *vertices,* 240 *edges,* 160 *in-line triangles). Complete character computation over all* 25920 *group elements gives*

$$\langle \chi_{H_1}, \chi_{H_1} \rangle = 1.$$

Therefore $H_1 \otimes \mathbb{C}$ *is* irreducible *of dimension* 81*, hence equal to the unique* 81*-dimensional irreducible — **the Steinberg module** — with* $\chi_{H_1}(g) = \#\text{fixflags} - \#\text{fixpoints} - \#\text{fixlines} + 1$ *(the Solomon–Tits alternating sum) verified for every* g*. The QECC logical space and the Schur-protected register below are one object: any equivariant logical error is a scalar, so only symmetry-breaking noise can touch the code, and the sentinel/clock layers are exactly the symmetry monitors. The homological dictionary then completes:* H_0 *is trivial (the vacuum pole),* H_1 *is Steinberg (the register), and* H_2 *(dim* 40*, one tetrahedron-boundary* 2*-cycle per line) is the* sign-twisted *line module — a fixing symmetry acts on a line's* 2*-cycle by the parity of its induced* S_4 *action (verified for all* 25920 *elements;* not *the plain permutation module): the top homology is the* oriented *timetable carrier, feeding the chirality ledger.* Witnesses: `bt861_code_register_is_steinberg.py`, `bt862_h2_is_the_line_module.py`.

Corollary 89.2 (Three generations from Steinberg vanishing)**.** $\chi_{\mathrm{St}}(g) = 0$ *iff* $3 \mid \mathrm{ord}(g)$ *(verified for all* 25920 *elements). Hence* any *order-*3 *symmetry of the substrate splits the matter register into eigenspaces of exactly* $27 + 27 + 27$ *— the three-generation decomposition is forced for every choice of triality element, not selected — and every order-*9 *element (*5760 *of them) refines it into nine* 9*-dimensional sub-generations. In the code's own characteristic the parameters survive:* $\mathrm{rank}_3 \partial_0 = 39$*,* $\mathrm{rank}_3 \partial_1 = 120$*,* $\dim H_1(\mathbb{F}_3) = 81$*, so the logical dimension of* $[[240, 81, 3]]_3$ *is exact over* $\mathbb{F}_3$*. The number of fermion generations is the defining-characteristic degeneracy of the protected register.* Witness: `bt863_generations_from_steinberg_vanishing.py`.

Theorem 89.3 (The dual-torsor Steinberg compiler)**.** *Let* $H_{27} = 3_+^{1+2}$ *be the canonical Heisenberg* O_3 *of the point parabolic and let* $A_{27} = \mathbb{F}_3^3$ *be the canonical translation* O_3 *of the Bell-line parabolic. Their* 27*-point and* 27*-line shells are regular torsors (BT858). On the protected register,*

$$\mathrm{St}{\downarrow_{H_{27}}} = 3\,\mathbb{C}[H_{27}], \qquad \mathrm{St}{\downarrow_{A_{27}}} = 3\,\mathbb{C}[A_{27}],$$

because both restricted characters are exactly $\{81^1, 0^{26}\}$*. The statement survives in the code's own field and is constructive:*

$$H_1(W(3,3); \mathbb{F}_3){\downarrow_{H_{27}}} \cong \mathbb{F}_3[H_{27}]^{\oplus 3}, \qquad H_1(W(3,3); \mathbb{F}_3){\downarrow_{A_{27}}} \cong \mathbb{F}_3[A_{27}]^{\oplus 3}.$$

For each torsor the verifier finds three cycle seeds whose 27 *group translates add* $27 + 27 + 27$ *independent classes modulo the* 120*-dimensional boundary space. Thus the same logical memory has a flat program basis and a curved state basis:* A_{27} *is the commuting three-trit address compiler, while* H_{27} *is the noncommuting qutrit-phase compiler.*

The center $Z(H_{27}) = \langle z \rangle \cong C_3$ *selects a canonical triality. Over* $\mathbb{C}$ *its central-character blocks are*

$$H_1 = H_{1,1} \oplus H_{1,\omega} \oplus H_{1,\omega^2}, \qquad \dim H_{1,j} = 27.$$

The trivial block contains the nine linear characters with multiplicity 3*; the two nontrivial blocks contain the conjugate* 3*-dimensional Schrödinger representations with multiplicity* 9*. Over* $\mathbb{F}_3$*, where* $x^3 - 1 = (x-1)^3$*, the phases coalesce into a canonical unipotent flag. With* $N = z - I$*,*

$$(\mathrm{rank}\, N, \mathrm{rank}\, N^2, \mathrm{rank}\, N^3) = (54, 27, 0),$$

so

$$0 \subset \ker N \subset \ker N^2 \subset H_1, \qquad \dim = (0, 27, 54, 81),$$

has three successive quotients of dimension 27*. Equivalently,* z *acts by* 27 *Jordan blocks of length* 3*. Complex generations are phase sectors; native qutrit generations are the three layers of one depth-*3 *memory stack.*




Figure 7: The dual-torsor compiler. Flat program translations and noncommutative state translations give two free rank-3 module coordinates on one Steinberg-protected register. The Heisenberg center reads as three phase sectors over $\mathbb{C}$ and as a three-step unipotent memory flag over $\mathbb{F}_3$.

The freeness is canonical, but the displayed orbit bases are not: H_{27} and A_{27} are nonisomorphic, and a basis-to-basis matrix still requires a chosen point, line, shell origin, and cycle seeds. No canonical intertwiner is claimed. Witness: `bt865_dual_torsor_steinberg_compiler.py`.

Theorem 89.4 (Steinberg memory)**.** *The Levi-graph cycle space and the chart-overlap* 81*-sector are both irreducible and equal to the Steinberg representation of* $\mathrm{PSp}(4,3)$ *— the Solomon–Tits homology of the building, whose canonical basis is the* 81 *apartments through any chamber. Schur's lemma then forces the uniqueness of the chart–cycle bridge. Restricted to a Sylow* 3*-subgroup the module is free of rank one: the protected memory is one free generator over the substrate's ternary symmetry.* Witnesses: `bt742`, `bt744`.

Corollary 89.5 (The oriented timetable spectrum)**.** *Let $P = 3^3{:}S_4$ be the index-*40 *line parabolic. The ordinary line permutation module and the oriented top-homology module are the two inductions of its two linear characters:*

$$\mathrm{Ind}_P^{\mathrm{PSp}(4,3)}(1) = 1 \oplus 15 \oplus 24, \qquad H_2 = \mathrm{Ind}_P^{\mathrm{PSp}(4,3)}(\mathrm{sign}_{S_4}) = 5_\omega \oplus 5_{\omega^2} \oplus 30.$$

The two 5-dimensional characters are complex conjugates over $\mathbb{Q}(\zeta_3)$; the 30 is rational. Under the outer extension $W(E_6) = U_4(2){:}2$, the conjugate pair is the restriction of one irreducible 10-dimensional representation, whereas the 30 has two inequivalent extensions. Thus the oriented timetable header reads as a Weyl-visible chiral channel 10 *plus a payload $30^{\pm}$ whose outer parity is not fixed by the projective module alone.*

The completed homology spectrum is

$$H_0 = 1, \qquad H_1 = \mathrm{St}_{81}, \qquad H_2 = 5_\omega \oplus 5_{\omega^2} \oplus 30,$$

and resolves the Euler charge representation by representation:

$$1 - 81 + (5 + 5 + 30) = -40 = -v.$$

BT867 resolves the tempting cache comparison negatively: neither 162*-cache branch is one of the two 5-dimensional sectors. The branches are isomorphic copies with identical character overlaps; the outer involution acts on their multiplicity label. The possible identification of the two 30-extensions with BT857's local gauge bit remains open.* Witness: `analysis/bt866_h2_oriented_irreducible_decomposition.py`.

Theorem 89.6 (The cache/transport extension boundary)**.** *Let $H = 3^3{:}S_4$ be the order-*648 *Bell-line parabolic. The two* 162*-slot BT859 cache branches have conjugate cyclic stabilizers and are therefore isomorphic transitive H-sets,*

$$\mathcal{C}_L \cong H/C_4 \cong \mathcal{C}_R.$$

Their permutation characters are equal. In particular, their scalar products with the restrictions of the three BT866 characters $(5_\omega, 5_{\omega^2}, 30)$ are both $(1, 1, 8)$: each cache sees both conjugate 5-sectors equally. "Left" and "right" are copy labels, not internal spectral chiralities.

The parabolic contains one conjugacy class of 81 *cyclic C_4 subgroups, and*

$$N_H(C_4) = D_8, \qquad H/C_4 \longrightarrow H/D_8, \qquad 162 \longrightarrow 81$$

is the canonical free two-sheet cache cover. Both copies cover this same stabilizer base. On their union GAP computes

$$C_{\mathrm{Sym}(324)}(H) \cong D_8, \qquad 324 = 81 \times 4 = 81 \times 2_{\mathrm{deck}} \times 2_{\mathrm{cache}},$$

with exactly 81 *commutant orbits of size four. Thus the four-state fiber carries the symmetry of a square, not merely a numerical pair of bits.*

This cache carrier is not the older ternary 162*-sector. On one cache fiber the deck swap and its two projectors are*

$$D = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \qquad P_\pm = \frac{I \pm D}{2}, \qquad \mathbb{F}_3^2 = \operatorname{im} P_+ \oplus \operatorname{im} P_-.$$

Since 2 *is invertible in $\mathbb{F}_3$, the cache splits; indeed $(D - I)^2 = D - I$. By contrast, packet transport uses*

$$N = \begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix}, \qquad N^2 = 0, \qquad (I + N)^3 = I,$$

and tensors this indecomposable fiber with the 81*-register to obtain the non-split sequence* $0 \to 81 \to 162 \to 81 \to 0$*. No change of basis can identify the idempotent cache difference with the nilpotent transport shift. The architecture therefore separates a reversible* address/control plane *from a memory-bearing ternary* temporal data plane *by extension class, not by convention.* Witness: `analysis/bt867_cache_split_transport_nonsplit_boundary.py`.

The error layer is native: the $[[240, 81, 3]]_3$ CSS code on the edge qutrits has $(d_X, d_Z) = (3, 4)$; the dual Császár/Szilassi cross-check supplies parity-free error detection; and the web's unique non-Ramanujan eigenspace — dimension $15 = g$ — is the spectral sentinel where drift appears first. At the classical boundary-image layer, Pass 373 gives the exact $[240, 120, 3]_3$ code and a complete 481-entry radius-one syndrome table, so one edge-symbol fault has a fully enumerated decoder. Pass 374 adds a separate controller constraint: the 51840 nonzero minimal logical X/Z vector pairings occupy four invariant 12960-state sheets under the natural $W(E_6)$ action, with stabilizer $C_2 \times C_2$. A runtime using those scalar representatives must therefore retain the two deck-sign bits; geometry does not collapse them to one Weyl torsor. Pass 375 sharpens the controller law: the fixed pairing character reduces the four-state sheet normalizer from abstract S_4 to the phase-compatible D_8, with no order-three operation. The split controller $W(E_6) \times V_4$ has no regular 51840-state complement. A future sheet fusion must therefore be a genuinely coupled transport, not an appended commuting phase register.




Figure 8: The local cache cell and the split/non-split boundary. The D_8 square fiber chooses a reversible address over one of 81 routes; the independent ternary nilpotent updates state while retaining temporal memory. Equal 162-dimensional counts do not imply equivalent modules.

90 Time: three clocks and a quasicrystal

Theorem 90.1 (Clock trichotomy)**.** *Of the program's three natural clocks, exactly one is internal:* $\mathbb{Z}_{12}$ *(the rectangle clock,* $12 \mid 51840$*) runs the selector and duo machinery, while* $\mathbb{Z}_7$ *(Császár) and* $\mathbb{Z}_{13}$ *(Singer) do not divide the group order and act as external references — both with decimal period* $6 = q!$*, so the digit expansion of* $1/7$ *is literally the internal clock's shadow modulo its duo bit.* Witnesses: `bt774`, `bt803`, `bt807`, `bt819`.

Theorem 90.2 (The Boerdijk–Coxeter time quasicrystal)**.** *Driving the loop by the BC twist* $\theta = \arccos(-2/3)$ *per round trip yields a stroboscopic orbit that provably never repeats (Niven), with the Steinhaus three-distance signature at all substrate step counts and — the substrate's signature moment — exactly* two *gap lengths at* $n = 30 = h(E_8)$*, the BC ring length, where closure happens in* S^3 *(the* 600*-cell) rather than the phase circle (deficit* 0.0158*). This is the photonic sibling of the Fibonacci-drive dynamical topological phase.* Witness: `bt820`.

Corollary 90.3 (The machine's clock is the universe's clock)**.** *The same BC clock is the de Sitter beat of inflation (Face 7). Its twist* $\cos\theta = -(q-1)/q$ *is the discrete de Sitter angle, its ring length is the beat* $30 = h(E_8)$ *(the* 600*-cell's* 20 *rings of* 30*), and the inflationary cosmology reads off that beat: the e-fold number is* $N = 2(v - \Phi_4) = 2\,h(E_8) = 60$*, exactly twice the beat, and the CMB spectral tilt is*

$$1 - n_s \;=\; \tfrac{2}{N} \;=\; \tfrac{1}{30} \;=\; \tfrac{1}{h(E_8)} \;=\; \tfrac{1}{\textit{(clock beat)}},$$

so the deviation of the primordial spectrum from scale invariance is the inverse of the clock's period. The two structures even match in kind: the clock is a time quasicrystal *(nearly periodic, never exact) just as inflation is* quasi–de Sitter *(nearly exponential, never exact) — both broken de Sitter by* $q = 3$*, the clock's aperiodicity being the cosmology's tilt. The architecture's time and the universe's expansion are one quasicrystal.* Witness: `analysis/w33_clock_cosmology.py`.

Corollary 90.4 (A falsifiable clock fingerprint in the CMB)**.** *If the clock couples to the inflaton, its quasiperiodicity imprints a* quasi-periodic *modulation on the primordial spectrum: peaks at log-period* $2\pi/\theta \approx 2.73$ *in* $\ln k$ *(with* $\theta = \arccos(-2/3)$*) whose spacings obey the Steinhaus* three-gap *law (two gap lengths near the BC ring* $n = 30$*) — the time-quasicrystal fingerprint, distinct from smooth slow roll (no peaks) and from single-frequency resonant inflation (a uniform comb, one gap). The log-frequency and the three-gap shape are fixed by* $q = 3$*; only the amplitude (the coupling) is*

free. A CMB feature search (Planck, LiteBIRD, CMB-S4) can detect the three-gap comb, bound the coupling, or — finding a clean single-frequency comb — disfavour the clock. (Witness: `analysis/w33_cmb_clock_signature.py`*.)*

Theorem 90.5 (The arrow of time)**.** *Without its two-trit feedforward record, the photon's self-configuration loop is the completely depolarizing channel with unique fixed point I/q — exactly the Bell marginal; with the record it is unitary. Decoherence is self-forgetting, priced at $\log_3 q^2 = 2$ trits per cycle.* Witness: `bt823`.

91 Synchronization: beacons and schedules

In plain language.*How separated machines agree on the time. The trick is to find sets of optical states that are all equally distinguishable from one another — so that no member of the set is a special case — and use them as a shared reference. This section counts how many such sets exist, which turns out to be exactly determined by the geometry rather than chosen, and then builds a schedule from them.*

The maximum classically coherent constellations are the *beacon heptads*: seven states with all pairwise overlaps exactly $1/3 = 1/q$ — a complete K_7 interference mesh, the Császár toroidal node realized in light. There are exactly 2880 heptads in a single transitive family; each has a $\mathbb{Z}_3 \times \mathbb{Z}_3$ symmetry fixing a unique *master beacon* and cycling two triads ($7 = 1 + 3 + 3$), and single-beacon swaps connect the family into its own exchange network: the reference frames of the network form a network. The measurement timetable is rigid: there exist exactly 36 complete schedules (partitions of the 40 states into 10 contexts) — an exhaustive result that simultaneously proves every spread of $W(3,3)$ is regular — with each context appearing in exactly 9 schedules. *Witnesses:* `bt817`*,* `bt819`*.*

Theorem 91.1 (Schedule-overlap law)**.** *Two distinct schedules share exactly* 1 *or exactly* $4 = \mu$ *contexts: each schedule has* 15 near *partners (overlap* 4*) and* 20 far *partners (overlap* 1*), the two relation classes of the double-six diagonal* $[1, 15, 20]$*, with the exact counting identity* $1 \cdot 20 + 4 \cdot 15 = 80 = 10 \times (9 - 1)$*. Operationally: a cheap timetable switch preserves* 4 *of* 10 *calibrated contexts and a far switch only* 1*, so a controller hopping among near partners re-calibrates* 6 *contexts per hop — the timetable library is itself a metric space whose geometry is the double-six relation.* Witness: `bt835_schedule_overlap_theorem.py`.

The Grünbaum–Coxeter cells. Each schedule also has an internal shape. The full schedule stabilizer S_6 is 2-homogeneous on the 10 contexts, but its icosahedral core A_5 — the 600-cell level of the platonic ladder, and *exactly* the automorphism group of the hemi-dodecahedron $\{5, 3\}_5$ — splits the $\binom{10}{2} = 45$ context pairs as $45 = 15 + 30$, and the 15-orbit graph on the 10 contexts is the **Petersen graph**: the edge skeleton of the hemi-dodecahedron, the cell of Coxeter's exceptional 57-cell. Dually, the hidden 6-set of the S_6 action realizes the hemi-icosahedron $\{3, 5\}_5$ — the cell of Grünbaum's 11-cell — with incidence count $(6, 15, 10)$: six hidden points, fifteen duads, ten triple-splits = the contexts themselves. The exceptional polytopes' groups do not embed in $\mathrm{Sp}(4, \mathbb{F}_3)$, but they are substrate arithmetic ($|\mathrm{PSL}(2, 11)| = 660 = k \cdot N_{\text{eff}}$, $|\mathrm{PSL}(2, 19)| = 3420 = k \cdot g \cdot 19$, Heawood genus $H(19) = 20 =$ the BC ring count, and $11 = k - 1$ is the Ihara prime of the zeta critical circle $|u| = 1/\sqrt{11}$): the full 11-cell and 57-cell live elsewhere, yet their *cells* are carried by every measurement timetable of this machine, glued by the substrate's own group instead of $\mathrm{PSL}(2, p)$. *Witness:* `bt836_gc_hemicells_in_spreads.py`*.*

Theorem 91.2 (The library is a classical geometry)**.** *The timetable library carries its own rank-3 geometry, and the hemicell structure fibers over it with perfect uniformity: (i) every skew line pair lies in exactly* 3 *schedules, so the* (schedule $\supset$ pair) *flag count is* $36 \times 45 = 1620$ *— the apartment count of the Tits building — and* 540×3*; (ii) the near-partner graph on the* 36 *schedules is strongly regular* $\mathrm{SRG}(36, 15, 6, 6)$*, the* other *classical rank-3 graph of* $U_4(2) \cong \mathrm{PSp}(4, \mathbb{F}_3)$*, so the control plane (timetables) and the data plane (*$W(3, 3) = \mathrm{SRG}(40, 12, 2, 4)$*) are the two rank-3 geometries of one group; (iii) each schedule stabilizer contains exactly* 6 *icosahedral* A_5 *cores (*$216 = 6^3$ *in all, each marking its unique schedule via its* $[10, 30]$ *line orbits) giving* 6 *distinct Petersen splits; each internal pair is a Petersen edge under exactly* 2 *of the* 6 *cores, hence every skew pair of* $W(3, 3)$ *has exactly* $6 = 3 \times 2$ *hemi-dodecahedral homes (*$3240 = 540 \times 6$ *Petersen flags).* Witness: `bt837_schedule_library_geometry.py`.

Theorem 91.3 (Two compasses, twelve Petersens, $4 \cdot K_{10}$)**.** $\mathrm{PSp}(4, \mathbb{F}_3)$ *has exactly two conjugacy classes of* A_5*, both with normalizer* S_5 *and* 216 *conjugates, unfused by the outer automorphism, and* both fiber over the same 36 schedules*: every schedule stabilizer contains* $12 = 6 + 6$ *icosahedral cores —* 6 duad *cores (line signature* $[10, 30]$*, the Theorem-91.2(iii) cores) and* 6 pentad *cores (signature* $[5, 5, 10, 20]$*: transitive on the schedule, plus two distinguished* pentads *of* 5 *pairwise-disjoint lines outside it). The two* 216*-sets are non-isomorphic* G*-sets (rank* 10 *suborbits* $[1, 5, 10, 10, 20, 20, 20, 30, 40, 60]$ *vs* $[1, 5, 10, 10, 20, 20, 30, 30, 30, 60]$*); the Petersen flags form the coset geometry* $\mathrm{PSp}(4, \mathbb{F}_3)/D_4$ *(*3240 *flags, dihedral stabilizer). There are* 432 *distinct pentads in* two chiral orbits *of* 216 *(stabilizer order* 120*); every core pairs one LEFT with one RIGHT pentad, and each pentad serves exactly one core. Pentads are* maximal partial spreads*: no schedule contains one. The two pentads of one core interlock as* $K_{5,5}$ *minus a perfect matching — mutual disjointness is* forbidden *by the overlap law (it would create a* 0*-overlap schedule) — and the deleted matching consists of* 5 skew *pairs, i.e. five hypercube charts; over the* 216 *cores these matchings cover the* 540*-chart atlas* ***exactly twice*** *(*$1080 = 540 \times 2$*): the routing fabric is readable off the pentad compasses, five charts per needle. Finally,* all twelve *cores split the* 45 *internal pairs as Petersen* 15*-orbits, and the twelve Petersen edge-sets cover every pair exactly* $\mu = 4$ *times:*

$$4 \cdot K_{10} \;=\; 12 \text{ Petersens.}$$

Schwenk's classical obstruction (no edge-partition of K_{10} *into* 3 *Petersen graphs) dissolves at the substrate multiplicity* μ*. The numerical coincidence* $3240 = \#\{\text{triangles of } Q\}$ *is refuted at the* G*-set level (orbits* $[360, 2880]$ *vs transitive).* Witnesses: `bt843_icosahedral_compass.py`, `bt844_double_five_and_six_petersens.py`, `bt845_pentad_exchange_and_chart_double_cover.py`.

Theorem 91.4 (The amalgamation ladder)**.** *The* 11*-cell and* 57*-cell are* universal *abstract polytopes: the unique ones with hemi-icosahedral facets and hemi-dodecahedral vertex figures (group* $L_2(11)$*, no proper quotients) and vice versa (*$L_2(19)$*). Their incidence is icosahedral-subgroup geometry: each of* $L_2(11)$*,* $L_2(19)$*,* $U_4(2)$ *has exactly two conjugacy classes of* A_5*, and in all three the distinguished incidence is* intersection in D_{10} *with valency* 6 *— the* 11*-cell's vertex–facet relation, the* 57*-cell's facet adjacency (the Perkel graph), and the substrate's compass incidence (*$216 + 216$*, bipartite* 6*-regular,* $216 \times 6 = 1296 = 6^4$ *incident pairs =* 36 *schedules ×* 36 *core pairs). The closures of one amalgam* $A_5 *_{D_{10}} A_5$ *(GAP):*

$$\langle A, B \rangle = \begin{cases} L_2(9) \cong A_6 \ (360) & \text{in } U_4(2)\text{: inside exactly one schedule stabilizer,} \\ L_2(11) \ (660) & \text{the 11-cell,} \\ L_2(19) \ (3420) & \text{the 57-cell.} \end{cases}$$

One local icosahedral amalgam, a PSL(2)*-ladder of completions over* $9 = q^2$*,* $11 = k - 1$ *(the Ihara prime),* 19 *(Heawood,* $H(19) = 20$*). Universality plus Lagrange (*$11, 19 \nmid 25920$*) shows the substrate carries the* complete local data *of both exceptional polytopes while their rank-*4 *amalgamation is arithmetically forbidden inside* $\mathrm{Sp}(4, \mathbb{F}_3)$*: the GC polytopes are the substrate's sibling completions, not subobjects. One step up the universal ladder (*$\{\{5,3\},\{3,5\}_5\}$*,* 10006920 *facets) the completion group is* $J_1 \times L_2(19)$ *— the first sporadic Janko group, whose involution centralizer* $2 \times A_5$ is *the compass datum. Finally, the compass Petersen* 15*-orbit carries exactly* 12 *pentagons splitting under the compass into two* 6*-orbits, each covering every edge exactly twice: two* chiral fully-faced *hemi-dodecahedra per needle, not merely skeletons. The dark sector closes the calculus: its* 190 *line pairs split* $[10, 30, 30, 30, 30, 60]$ *under the core into a perfect matching of* 10 dark charts*, two chiral* $5 \times K_4$ *partitions into skew tetrads, the two dark dodecahedra, and a* 6*-regular meeting frame; the dark matching is* schedule-shadow pairing *(each dark line meets exactly* 4 *schedule lines; matched lines share their shadow), and in* K_5 *terms the ten shadows are exactly the ten "edge + opposite triangle" configurations — a canonical bijection dark chart* $\leftrightarrow$ K_5 *edge* $\leftrightarrow$ *schedule line. The timetable is stored three ways (lit-chart transversals,* K_5 *edges, dark shadows): built-in erasure redundancy. Each chiral tetrad's four distinguished edges form a* K_5 star*, the five tetrads of each partition marking the five lit charts exactly once:* K_5 *vertices are stored three ways (lit charts, left/right tetrads), edges two ways (schedule lines, dark charts) — every* A_5*-orbit structure of the pentad core except the dodecahedra and the meeting frame is a* K_5 *element — and those two fold in as well: each chiral dark dodecahedron is the* antipodal double cover *of the Petersen (Kneser) graph on the* 10 *dark charts, with deck transformation the shadow matching (antipode = shadow partner, verified), and the meeting frame is the doubled Johnson graph* $T(5)$*. The* K_5*-relation census is constant on every orbit (matching = same edge, tetrads and meeting = adjacent, dodecahedra = disjoint): the dark sector is the canonical* 2:1 *cover of the* K_5 *edge-world, with the Petersen graph appearing three ways in one needle (schedule skeleton, dark Kneser quotient, doubled chiral covers).*

Theorem 91.5 (The dark charts are the mirror bus)**.** *The* (core, dark chart) *slot space —* 216 *pentad cores* $\times$ 10 *dark charts =* 2160 *slots, with every skew pair occurring as a dark chart in exactly* 4 *cores (*$2160 = 540 \times 4$*, the repair-atlas factorization) — is* ***G-set isomorphic to the*** 2160***-slot*** D_{12} ***mirror bus*** *of the middleware: the slot stabilizer has order* 12 *with the* D_{12} *profile* $\{1{:}1, 2{:}7, 3{:}2, 6{:}2\}$ *and is* conjugate in $\mathrm{PSp}(4, \mathbb{F}_3)$ *to the antipode-slot stabilizer (direct search over all* 25920 *elements). The multiplicity-*4 *agreement is canonical: a dark chart's transversal tetrad is its schedule shadow, so the* 4 *host cores' schedules all contain the pair's* 4 *transversals. Hence the compass layer* generates *the middleware — timetables from its lit side (reconstruction), the transport bus from its dark side — and the mirror bus acquires a hardware identification: one slot = one needle's dark chart.* Witnesses: `bt856_dark_mirror_bus.py`; further: `bt853_dark_orbit_zoo.py`, `bt854_dark_chart_transversal_duality.py`, `bt855_dark_sector_k5_complete.py`.

Witnesses: `bt848_universal_amalgam_ladder.py`, `.tmp/gap_bt848*.g`; cf. Hartley's classification (17 universal rank-4 locally projective polytopes, 441 quotients) and Hartley–Leemans on $\{5, 3, 5\}$.

The barren rung and the maniplex workaround. Relaxing polytopes to *maniplexes* (flag graphs without the intersection property; the tomotope middleware of this machine is a uniform 4-polytope whose monodromy $18432 = 96 \times 192$ fails that property, giving it *infinitely many* distinct minimal regular covers — the canonical rank-4 cover pathology) does not lift the obstruction: exhaustive search shows $U_4(2)$ admits *no* rank-4 regular maniplex with a 5 in its type, and the amalgam closure $A_6 = L_2(9)$ admits no regular maniplex at any rank — it is the *barren rung* of the PSL(2) ladder, whose populated rungs are exactly the 11-cell (q=11), the 57-cell (q=19), and

Leemans–Toledo's degenerate single-facet $\{5,5,5\}$ family (our control search rediscovers all of them, including both exceptional polytopes). This is why the Grünbaum–Coxeter content of the substrate is *delocalized* over the 36 schedules — Petersen splits, chiral pentads, chart covers, dark dodecahedra — rather than crystallized in one flag object, and why the machine's runtime uses the tomotope: it is the flag structure that survives the obstruction. The tomotope's symmetry type is now exact: $|\mathrm{Aut}| = 96$ (independent centralizer computation on the 192 flags), two flag orbits $[96, 96]$, **class** $2_{\{0,1,2\}}$ — only the cell-color crosses orbits, and the orbits are precisely "flag in a tetrahedron" vs "flag in a hemioctahedron": the middleware *alternates spherical and projective cells*, the exact situation the classical "locally X" taxonomy cannot name, and the setting of Mochán's 2-orbit polytopality theory. Moreover the tomotope is a **Cayley maniplex over** $V_4 = \mathbb{Z}_2 \times \mathbb{Z}_2$ (vertex action = full S_4 with a regular Klein subgroup; edge and face actions faithful and transitive): the middleware's vertex layer is a free $\mathbb{F}_2^2$-torsor, so register XOR-addressing extends from the chart atlas into the runtime with no added structure. Reading Hartley's full classification (seventeen universal locally projective rank-4 polytopes) against the substrate adds three facts: Aut(**tomotope**) **is itself a universal polytope group** — isomorphic to $\Gamma(\{\{4,3\}_3, \{3,4\}_3\})$, the quotient-free doubly-projective $\{4,3,4\}$ universal built from hemicubes and hemicrosses (the tomotope's own projective cell type), with the case-10 group $= C_2 \times \mathrm{Aut}$ of order 192 = the flag count; the mixed $\{3,5,3\}$ amalgam (icosahedral facets, hemi-dodecahedral vertex figures) *does not exist* — the construction closes into the 11-cell — while the dodecahedral mix is the J_1 giant; and the chart–compass universal $\{\{4,3\}, \{3,5\}_5\} = 2^{\mathcal{I}}$ (cube facets $= Q_3$ charts, hemi-icosahedral vertex figures = compass cells, vertices $= \mathbb{F}_2^6$ on the hidden 6-set) has order $3840 \nmid 25920$: blocked like the rest of the ladder. *Witnesses:* `bt849_maniplex_barren_rung.py`, `bt850_tomotope_two_orbit_class.py`, `bt851_tomotope_cayley_test.py`, `bt852_seventeen_universals.py`, `.tmp/gap_bt849*.g`, `.tmp/gap_bt852*.g`.

Reconstruction, the chart K_5, and the dark dodecahedra. The pentad core's full signature $[5,5,10,20]$ (lines), $[20,20]$ (points) is rigid: both chiral pentads cover the *same* 20-point orbit (lit/dark halves of the substrate), the five matching charts' common-transversal bundles overlap to exactly the 10 schedule lines — **a pentad pair generates its timetable** — and the line $\to$ chart-pair map is a bijection onto the $\binom{5}{2} = 10$ edges of K_5: the schedule *is* a K_5 on its own charts (4 transversals per chart, 2 charts per line). The 20 dark lines complete the $\{5,3\}$ family: their 190 pairs split $[10,30,30,30,30,60]$ under the core, and exactly two of the 30-orbits are **dodecahedron skeletons** (3-regular, girth 5, diameter 5) — a chiral pair of genuine dodecahedra beneath every compass needle, one level under the hemi-dodecahedral Petersen splits of the schedule itself. *Witnesses:* `bt846_pentad_core_anatomy.py`, `bt847_dark_dodecahedron.py`.

Theorem 91.6 (BT839 GC operation Euler/flag audit)**.** *Treating the full Grünbaum–Coxeter note as a data table gives a second invariant. The base tables for the* 11*-cell,* 57*-cell, tomotope partial a, and tomotope partial b are all Euler-neutral:*

$$V - E + F - C = 0.$$

But every Wythoff operation table has a fixed family charge:

$$\chi_{\mathrm{op}}(11\text{-}cell) = -11, \qquad \chi_{\mathrm{op}}(57\text{-}cell) = -57, \qquad \chi_{\mathrm{op}}(tomotope) = -4.$$

The omnitruncated rows are full-flag carriers:

$$660 = |\mathrm{PSL}(2,11)| = 11 \cdot A_5 = kN_{\mathrm{eff}},$$

$$3420 = |\mathrm{PSL}(2,19)| = 57 \cdot A_5 = k \cdot g \cdot 19,$$

and the tomotope has 96 *half-flags, whose double is the verified* 192*-flag BT814 packet. The* 57*-cell also locks to the W33 timetable library: BT837 gives* 3240 *Petersen homes, and*

$$3240 + k \cdot g = 3240 + 180 = 3420.$$

Thus one $k \cdot g$ *sentinel sheet completes the W33 Petersen-home carrier to the* 57*-cell flag count.*

The regular-polychoron alignment supported by the cell/symmetry data is

$$11\text{-}cell \to 600\text{-}cell, \qquad tomotope \to 24\text{-}cell, \qquad 57\text{-}cell \to 120\text{-}cell.$$

The $57 \to 120$ *link is direct at the dodecahedral cell level; the* $11 \to 600$ *link is weaker but real, through hemi-icosahedral local structure and the quotient* $2I \to A_5$ *rather than through a direct tetrahedral-cell match. The swapped* 11/57 *orientation is recorded as a lower-scoring dual/vertex-figure hook, not discarded.* Witness: `bt839_gc_operation_euler_flag_audit.py`.

Theorem 91.7 (BT840–BT842 carrier closure)**.** *The three unresolved carriers in the Grünbaum–Coxeter paragraph are now explicit objects.*

(i) The 180 ***sentinel sheet.*** *The verified Clifford* L/R *boundary has* 36 *cells arranged as a* 6×6 *rook grid. Its zero-overlap relation is not a numerical afterthought: it is the union of the* 6 *row fibres and* 6 *column fibres, each fibre carrying the duads of a six-set. Hence*

$$12 \cdot \binom{6}{2} = 12 \cdot 15 = k \cdot g = 180.$$

This is exactly the sheet missing from BT837:

$$3240 + 180 = 3420 = |\mathrm{PSL}(2,19)|.$$

Equivalently, the timetable library gives 216 *Petersen cores (*$216 \cdot 15 = 3240$*), and the rook boundary supplies the missing* 12 *six-set fibres (*$12 \cdot 15 = 180$*).*

(ii) The 660 ***carrier.*** *At an apex cell* (r, c) *of the same* 6×6 *grid, remove the incident row and column. The apex plus the five nonincident rows and five nonincident columns gives*

$$11 = 1 + 5 + 5.$$

Crossing these eleven labels with the verified 60*-element Clifford* A_5 *selector gives*

$$11 \cdot A_5 = 11 \cdot 60 = 660 = kN_{\mathrm{eff}}.$$

This is a carrier theorem only: it does not assert an internal $\mathrm{PSL}(2,11)$ *action on* $W(3,3)$*.*

(iii) The 96 ***tomotope half-flags.*** *In the* D_4*-root model of the* 24*-cell, every edge lies in a unique central hexagon plane. The two endpoint axes determine the third, missing axis in that plane, so each edge maps to a Reye incidence* $(\mathit{missing\ axis}, \mathit{hexagon\ plane})$*. Each of the* 48 *Reye incidences has exactly two edge lifts:*

$$96 = 2 \cdot 48.$$

Thus the tomotope omnitruncated half-flag count is literally the 24*-cell edge lift of the common tomotope/Reye spine.*

The hexagon clue supplies the conceptual bridge to the 11*-cell. Each central* 24*-cell hexagon is a six-root cycle* C_6*. Completing that cycle to a full* K_6 *gives* 15 *duads, exactly the hemi-icosahedral skeleton count of the* 11*-cell cell. Across the* 16 *central hexagons,*

$$16\binom{6}{2} = 16 \cdot 15 = 240,$$

the W33 edge count and the E_8 *root count. The tested dot profile of these* 240 *duad slots is*

$$96_{\langle x,y\rangle=1} \;+\; 96_{\langle x,y\rangle=-1} \;+\; 48_{\langle x,y\rangle=-2},$$

namely live 24*-cell edges, mirror pairs, and repeated opposite-axis Reye incidences.* Witnesses: BT840, BT841, and BT842; executable scripts are in `analysis/`.

92 Build sheet and falsifiable witnesses

Components (all standard quantum optics): one heralded single-photon source; one polarizing beam splitter; one symmetric 3-port coupler (tritter); a $0/\tau/2\tau$ delay ladder; one bin-synchronous electro-optic modulator; one polarization rotator set to $\arccos(-2/3)$ in the recirculation loop; single-photon detectors.

Witnesses (kill criteria, all parameter-free):

witness	predicted value	substrate form
trace–Choi visibility of F_3	$1/3$	$1/q$
trace–Choi visibility of X, Z	0	—
Kochen–Specker classical budget	$36/40$	$(q!)^2/v$
beacon-mesh pair visibility	$1/3$ (all 21 pairs)	$1/q$
Werner separability threshold	$3/4$	q/μ
BC-drive gap census at n=30	2 gap lengths	$h(E_8)$ ring
Hashimoto transport phases (one tick)	$\arctan\sqrt{10},\ \pi - \arctan(\sqrt{7}/2)$	Φ_4, Φ_6; $\lvert u\rvert^2 = 11$
key-agreement rate	$13/40$	Φ_3/v
D_{12} mirror-slot stabilizer	order 12	projective bus
runtime factorization	$24 \cdot 45 \cdot 48$	$\lvert\mathrm{Sp}(4, \mathbb{F}_3)\rvert$
one recursive route digit	≤ 8 reversible hops	$3 + 5$
level-n leaves	40^n	v^n
level-n $W(3,3)$ instances	$(40^n - 1)/39$	geometric tower
durable commit clock	$4(7^g - 1)$ ticks	tomotope/Csaszar
compiled stress route	$47 < 48$ moves	BT828 level six
cover-lifted packet capacity	$48k^3$ slots	BT832 storage gauge
Bell–compass prefix router	$648 + 324 + 162 + 162$	code $0, 10, 110, 111$
sentinel-aware stress energy	$4 \to 2$	BT833 reroute
full route sync criterion	$2n \mid 7^n - 1$	BT834 guard band
tomotope Wythoff runtime ladder	$4, 12, 24, 48, 96$	BT838 packet growth
GC operation Euler charges	$-11, -57, -4$	BT839 table audit
sentinel projector trace	15	g sector
first full-route desync	$n = 5$ remainder 24	f guard band
tomotope cover ABI	48 blocks / 192 flags	cover-invariant

A measured deviation in any row falsifies the corresponding layer.

93 Implications, corrections, and the ethos

This section states what the architecture means — for physics, for computing, for networking, and beyond the laboratory. Every claim below is either (i) a theorem with an executable witness in this paper's ledger, or (ii) an implication of such a theorem, flagged as such. Nothing here floats free of the verification chain.

93.1 Physics

In plain language. *What has to be true of the world for this architecture to work, separated from what has to be true of the mathematics. The mathematics is checked; the physics is a set of requirements on materials, loss rates and detector performance that current technology meets in some cases and not in others. Each requirement below says which.*

The vacuum is a gauge choice among five. The decomposition $40 = 1 + 12 + 27$ (self, gauge, matter) that organizes the entire Standard-Model derivation is *one of five* maximal decompositions, indexed by the Schläfli inventory of the cubic surface: 27 registers, 36 schedules, $40 + 40$ building parabolics, 45 polar pairs. The five vacua are connected by an explicit 5×5 double-coset transition matrix. Physically: what looks like "the" vacuum is a parabolic gauge choice, and the theory knows its own alternative phases and the exact combinatorial cost of moving between them. No continuum field theory has this property; here it is finite, exact, and enumerated.

Matter is magic, with three octane grades. The machine's non-classical resource (magic, in the resource-theoretic sense) coincides *exactly* with its matter sector: the 36 entangled Witting rays are the matter shell, and the 27 matter contexts stratify $[1, 8, 12, 6]$ — the cube's cell census. The three magic grades — deep $(2 + \sqrt{3})/6$ on $8 = 2^q$ rays, mid $(5 + 2\sqrt{3})/12$ on $24 = f$, shallow $3/4 = q/\mu$ (the Werner threshold) on $4 = \mu$ — mean that "what matter is" and "what fuels quantum advantage" are one census. A physicist reads this as a structural identification of the fermionic sector with the non-stabilizer sector; an engineer reads the same integers as a fuel gauge. Both readings are forced by the same double cosets.

The Standard-Model spine: one transvection. The preceding paragraphs assemble into a single statement, verified end-to-end in one pass (`bt886_standard_model_spine.py`): *from the pair* $(W(3,3),\ R)$ *— the symplectic quadrangle and one long-root transvection — the discrete Standard Model follows with zero free parameters.* The transvection R fixes the 13-point gauge perp-plane and acts freely (nine orbits) on the 27 matter shell; its centralizer $C(R)$ (order 648) is the gauge group, with module $\mathbf{1} \oplus \mathbf{3} \oplus \mathbf{8} = U(1) \times SU(2) \times SU(3)$; its centre $Z(C(R)) = \langle R \rangle = \mathbb{Z}_3$ is the three generations; its normalizer gives the flavor group S_3 and charge-conjugation; the W/Q duality gives parity; the matter shell grades 9+9+9 with the $\mathbb{Z}_3$ Yukawa rule; and the connection is flat $(\mathbb{Z}_3^2)$ along collinear edges, $2T$-curved on the matter graph Q with a quaternionic field strength. The gauge group, the generations, the flavor symmetry, the Yukawa texture, chirality, parity, and the gauge dynamics are not separate inputs — they are the centralizer, centre, normalizer, duality, grading, and commutator structure of one element of $\mathrm{Sp}(4, \mathbb{F}_3)$, replicated over the 40 points. The gauge group even carries its color/electroweak split: $C(R) = 3^{1+2} : SL(2,3) = 27{:}24$, with the normal Heisenberg radical (order $q^q = 27$, the color part) fixing the electroweak $\mathbf{1} \oplus \mathbf{3}$ pointwise (the $W/Z/\gamma$ are color-blind, constant on the four lines through p_0) and acting on the gluon octet $\mathbf{8}$,

and the Levi $SL(2,3)$ (order $f = 24$, the electroweak part) carrying the $\mathbf{1}\oplus\mathbf{3}$ — color $\rtimes$ electroweak as a parabolic, with substrate orders q^q and f. And the color radical is *the same* Heisenberg group $3^{1+2} = O_3$ that acts simply transitively on the 27 matter shell (the matter torsor): **color is the matter-shell Heisenberg group**, so matter carries color precisely because the 27-shell is a torsor under the color group — color rotations and matter-shell motions are one action of $q^q = 27$. Under the full gauge group the matter shell is the homogeneous space $27 = C(R)/SL(2,3)$ (gauge group over the electroweak Levi): $C(R)$ is transitive with point-stabiliser the electroweak $SL(2,3)$, rank 6 (suborbits $[1,1,1,8,8,8]$), module $\mathbb{C}[27] = \mathbf{1}\oplus\mathbf{6}\oplus\mathbf{8}\oplus\mathbf{12}$, and the three electroweak-fixed points form a color-singlet (lepton-like) 3-set while the three color-8 suborbits carry the colored (quark-like) content ($27 = 3 + 24$). One generation's fermion multiplets are the $C(R)$-module structure of the 27.

Three generations, matter-blind and gauge-visible. Because the matter register is the Steinberg module (Corollary, §89) and the Steinberg character vanishes on every 3-singular element, *any* order-3 symmetry of the substrate splits matter into exactly $27 + 27 + 27$: the three generations carry identical matter/Steinberg structure — they are indistinguishable to the protected register, which is why generations share gauge charges. Yet the four order-3 conjugacy classes *are* distinguished in the gauge (40-point) sector: the transvections grade it $22+9+9$ and fix a whole $\mathrm{PG}(2,3)$ plane of $13 = \Phi_3$ points, while the regular classes grade it $16+12+12$ and fix only $\mu = 4$ points. The *physical* texture triality (Pillar 68's Yukawa map R) is identified exactly: it is the long-root transvection (a 40-class element = the centre of the point-parabolic's Heisenberg radical), fixing the 13-point gauge perp-plane $p_0^\perp$ pointwise and acting on the 27-point matter shell with 9 free orbits of 3 — the canonical "fix the gauge, stir the matter" generator. Its eigengrading of $\mathbb{C}[27]$ is $9\oplus 9\oplus 9$, and $\mathbb{Z}_3$ Clebsch–Gordan then *forces* the Pillar-68 Yukawa selection rule $T[a,b,v] = 0$ unless the three grades sum to 0 mod 3 (exactly 9 of 27 grade-triples survive); the matter coupling lives on the 36 within-shell tritangent triples (Pillar 69's Heisenberg-twisted triads, $45 = 9 + 36$). And the gauge side closes it: the centralizer $C(R) = \mathrm{Stab}(p_0)$ of order 648 (the gauge group is what commutes with generation-cycling) acts on the $12 = k$ gauge neighbours with permutation rank 3, decomposing the gauge module as

$$\mathbb{C}[12] = \mathbf{1}\oplus\mathbf{3}\oplus\mathbf{8} = U(1)\oplus SU(2)\oplus SU(3),$$

the Standard-Model gauge group adjoint (the $\mathbf{1}$+$\mathbf{3}$ from the A_4 action on the four lines through p_0, the $\mathbf{8}$ the within-line gluon octet). So R fixes the gauge sector ($12 = 8$+3+1, generation-blind) and grades the matter sector ($27 = 9$+9+9, three generations): the gauge group and the generations are the two eigen-data of one long-root transvection. The gauge sector even carries a parity statement: $C(R)$ acts on the four lines through p_0 as A_4 inside PSp, but as the full S_4 in $\mathrm{PGSp}(4,\mathbb{F}_3) = W(E_6)$ — the odd (parity-violating) 4-line permutations are *exactly* the anti-symplectic W/Q-duality coset, so gauge parity is the duality/chirality $\mathbb{Z}_2$ and lives only in the full $W(E_6)$. The flavor sector even has its charge conjugation: $N_{W(E_6)}(\langle R\rangle)/C(R) = \mathbb{Z}_2$, so there is an element C with $CRC^{-1} = R^{-1}$ that fixes generation grade-0 and swaps grade-1 $\leftrightarrow$ grade-2 — the discrete shadow of CP, conjugating the generation $\mathbb{Z}_3$ exactly as the temporal Bell qutrit's CPT conjugates $\omega \mapsto \bar\omega$. The full Standard-Model discrete flavor/parity data — gauge group $1\oplus 3\oplus 8$, three generations $\mathbb{Z}_3$, generation C, matter chirality, gauge parity — is the normalizer geometry of one long-root transvection. The grading R and its conjugation C together generate the **flavor group** S_3 ($\langle R, C\rangle$, order 6, non-abelian — the minimal non-abelian flavor symmetry of BSM model-building), under which the matter shell decomposes as $\mathbb{C}[27] = 6\cdot\mathbf{1}\oplus 3\cdot\mathbf{1}'\oplus 9\cdot\mathbf{2}$, the standard doublet appearing $q^2 = 9$ times. And the flavor–gauge relationship is exact: R is central in the gauge group

$C(R)$, with $Z(C(R)) = \langle R \rangle \cong \mathbb{Z}_3$ — **the three generations are the centre of the gauge group**, acting trivially on the adjoint exactly as the $\mathbb{Z}_3$ centre of colour $SU(3)$ acts on the gluon octet (so the $SU(3)$ centre *is* the generation $\mathbb{Z}_3$). Globally there are 40 such local gauge groups — one per point, a single conjugacy class (homogeneous spacetime) — and the 40 generation-centred long-root $\mathbb{Z}_3$'s generate all of $\mathrm{PSp}(4, \mathbb{F}_3)$: **the** 40 **points of** $W(3,3)$ **are the space of local gauge groups**, each $SU(3) \times SU(2) \times U(1)$ with its generation centre, and the global symmetry is the closure of the local generation symmetries. The connection between adjacent local gauge groups is exact: for collinear points the generation centres commute ($\langle R_p, R_{p'} \rangle = \mathbb{Z}_3 \times \mathbb{Z}_3$), so the gauge connection is **flat along the** 240 **edges**; for non-collinear points $\langle R_p, R_{p'} \rangle = SL(2,3) = 2T$ (the binary tetrahedral / 24-cell group), so it is **curved across the** 27**-per-point matter shell**. Gauge curvature lives exactly on the matter graph Q — flat = collinearity, curved = non-collinearity = matter, with holonomy the 24-cell group. The curvature 2-form $F(p,q) = [R_p, R_q]$ makes this quantitative: it vanishes on collinear (causal) directions and is an *order*-4 *quaternion unit* of $2T$ (one of $\pm i, \pm j, \pm k$, with $F^2 = -I$ the centre) on every matter pair — an **su**(2)**-valued field strength supported exactly on the matter graph** Q. Flat causality, quaternionic curvature on matter. The integrated flux (Wilson loop $R_a R_b R_c$) confirms it: all 160 collinear triangles carry order-3 abelian flux (the flat $\mathbb{Z}_3$ line grading), while the 3240 matter triangles of Q carry non-abelian flux of orders $\{2, 4, 6, 12\}$ (counts $180, 180, 1440, 1440$) up to $12 = k$ — gauge energy lives on the matter graph. The matter register (Steinberg) couples to this flux only through its non-3-singular part: by Steinberg vanishing, $\chi_{\mathrm{St}}(W) = 0$ on every order-$3, 6, 12$ loop (3040 triangles, matter-invisible) and is nonzero only on the order-2 loops ($\chi_{\mathrm{St}} = +q^2 = 9$, the polar-pair chirality involution of BT869) and order-4 loops ($\chi_{\mathrm{St}} = -q = -3$); the total coupling $\sum \chi_{\mathrm{St}}(W) = 180 \cdot 9 - 180 \cdot 3 = 1080 = 540 \cdot 2$ is exactly the chart double-cover count — gauge dynamics and the routing fabric meet at 1080. This is the Standard-Model pattern as a representation- theoretic theorem: generations are identical in gauge charge (matter-blind) and differ only through gauge-sector–visible couplings (the Yukawa/mass structure), here the eigenvalue degeneracy of an order-3 symmetry rather than a modeling input. *Witnesses:* *bt863_generations_from_steinberg_vanishing.py*, *bt864_triality_census.py*. Order-6 symmetries see *both* internal gradings at once: an order-6 element factors as g^2 (generation, order 3) times g^3 (chirality, order 2 — the sign-twisted carrier of H_2), and since χ_{St} vanishes on every 3-singular power, its $\mathbb{Z}_6 = \mathbb{Z}_3 \times \mathbb{Z}_2$ eigengrading factors cleanly: each chirality half $(81 \pm \chi(g^3))/2$ carries 3 equal generations. For the dominant involution type ($\chi(g^3) = q^2$) the chirality split is $\mathbf{45 + 36}$ — the substrate's own tritangent and double-six counts — so the left/right matter split is tied to Schläfli geometry; the other type gives $39 + 42$. Generation $\times$ chirality $= 3 \times 2 = 6 = q$!. The dominant chirality involution is identified exactly: $\mathrm{PSp}(4, \mathbb{F}_3)$ has just two involution classes, and the 45-class (eight fixed points carrying the cube Q_3, centralizer $2T \times 2T$ of order 576) is the *central involution of a hyperbolic polar pair* $L \leftrightarrow L^{\perp}$ — so the left/right split of matter, $45 + 36$, is sized by the substrate's own tritangent-plane and double-six counts, and the matter chirality $\mathbb{Z}_2$ *is* the 24-cell polar-pair swap. *Witnesses:* *bt868_joint_generation_chirality_grading.py*, *bt869_involution_chirality_classes.py*.

Time has three hands and an irrational escapement. The internal $\mathbb{Z}_{12}$ rectangle clock, the external $\mathbb{Z}_7$ (Császár) and $\mathbb{Z}_{13}$ (Singer) references, and the Boerdijk–Coxeter drive $\arccos(-2/3)$ together realize a discrete time quasicrystal: a drive that never repeats yet has exactly bounded gap structure (two gap lengths at $n = 30 = h(E_8)$). The arrow of time appears as the unique self-loop fixed point I/q with its two-trit forgetting cost: irreversibility is priced, not postulated. Implication: any laboratory system realizing this architecture is also a clock whose long-term stability is protected by a number-theoretic irrationality rather than by feedback.

The exceptional polytopes are the theory's siblings, not its parts. The Grünbaum–Coxeter arc (Theorems 91.2–91.4) shows the substrate carries the complete local geometry of the 11-cell and 57-cell — hemi-icosahedra and hemi-dodecahedra in every schedule, with exact incidence — while universality plus Lagrange forbid their global crystallization inside $\mathrm{Sp}(4,\mathbb{F}_3)$. The same local amalgam $A_5 *_{D_{10}} A_5$ closes as $L_2(9)$ (the substrate's schedule core), $L_2(11)$ (the 11-cell), $L_2(19)$ (the 57-cell), with $J_1 \times L_2(19)$ — a sporadic group — atop the universal ladder. The physical moral is delocalization: the substrate *cannot* host a "GC condensate," so the icosahedral order is necessarily spread over the 36 schedules as compass structure. This is the same mathematical mechanism by which frustrated phases in condensed matter refuse local order parameters — realized here exactly, with the obstruction an integer $(11, 19 \nmid 25920)$.

Spectral ghosts. The primes that refuse to divide the group still govern its analysis: $11 = k - 1$ is the Ihara prime of the zeta critical circle $|u| = 1/\sqrt{11}$, 19 enters through the Heawood genus $H(19) = 20 =$ the BC ring count, and the chart-web eigenvalue fields are $\mathbb{Q}(\sqrt{\Theta})$ and $\mathbb{Q}(\sqrt{\Phi_{12}})$ ($\Theta = 10$, $\Phi_{12} = 73$, both parameter-closure constants). A spectroscopist's summary: the machine's transport spectrum speaks the tier-ladder dialect of the physics paper, and the forbidden primes appear as poles of the zeta function rather than as symmetries.

Gravity counts the matter register. The discrete gravitational bridge is the Matrix-Tree action $S = \frac{M_P^2}{2} \ln \tau(G)$, τ the spanning-tree count, and for the substrate it is exact: the Laplacian spectrum $\{0, 10^{24}, 16^{15}\}$ gives

$$\tau(W(3,3)) = \frac{10^{24} \cdot 16^{15}}{40} = 2^{81} \cdot 5^{23},$$

where the exponent of 2 is $81 = q^4 =$ the matter-sector (Steinberg) dimension, the base $5 = F_5$ is the tier-ladder prime ($r = 27/80$), and the exponent $23 = f - 1$. The complement matter graph $Q = \mathrm{SRG}(40, 27, 18, 18)$ gives $\tau(Q) = 2^{66} \cdot 3^{39} \cdot 5^{23}$ with 3-exponent $39 = q\Phi_3 =$ the gauge-sector dimension. So the discrete-gravity partition function carries the Standard-Model sector sizes as its prime-exponent charges — matter (q^4) in the power of 2, gauge ($q\Phi_3$) in the power of 3, cosmological (F_5) shared — and the entropy of the spanning-tree ensemble *counts the registers*. This is not a separate fact from the transport spectrum: the Ihara zeta $\zeta^{-1}(u) = (1-u^2)^{200}(1-u)(1-11u)(1-2u+11u^2)^{24}(1+4u+11u^2)^{15}$ (verified directly by the 480×480 Hashimoto operator) has its non-trivial zeros on the graph-RH circle $|u| = 1/\sqrt{11}$ (the transport sector, $p_{\mathrm{Ih}} = k - 1 = 11$) and its Perron zero at $u = 1$, where the Bass matrix $I - A + 11I = 12I - A$ *is* the Laplacian, so the Matrix-Tree leading coefficient $10^{24}16^{15} = 2^{84}5^{24} = v \cdot \tau$ recovers exactly the gravity count. Transport and gravity are the off-critical and critical behavior of one zeta: the prime 11 is the transport critical norm, the matter dimension $q^4 = 81$ is the gravity entropy. The substrate is in fact a *pair* of zetas: the complement matter graph $Q = \mathrm{SRG}(40, 27, 18, 18)$ has its own Ihara prime $26 = 2\Phi_3$ (Hashimoto Perron, all complex eigenvalues on $|u| = 1/\sqrt{26}$) and its Perron-point gravity $\tau(Q) = 2^{66}3^{39}5^{23}$ puts the *gauge* dimension $39 = q\Phi_3$ where $W(3,3)$ puts the matter dimension — complementation (collinearity $\leftrightarrow$ non-collinearity) swaps the matter and gauge entropies, with the cosmological charge 5^{23} shared. The non-backtracking walk census confirms the dynamics: $N_3 = \mu|E| = 960$, $N_5 = |E|\, q^q\, n_{\mathrm{even}} = 181440$, $N_n \sim 11^n$. *Witnesses:* ***bt870_spanning_tree_gravity.py***, ***bt872_ihara_zeta_spanning_bridge.py***, ***bt873_dual_zeta_walk_census.py***.

Falsifiability is retail, not wholesale. Each physics reading above is pinned to a tabletop witness with an exact rational value: trace–Choi visibility $1/3 = 1/q$ exactly (not approximately);

Kochen–Specker budget $36/40 = (q!)^2/v$ exactly, with deficit μ; contextual fraction $1/10 = 1/\Phi_4$; Werner threshold $3/4 = q/\mu$; two gap lengths — not three — at drive step 30. A single wrong integer kills the corresponding layer. This is a stronger falsifiability posture than parameter-fitting physics can offer, because there are no parameters to refit.

93.2 Computing

What the machine is. One photon carries a 4-dimensional path–polarization register (states) and a 9-dimensional past–future time-bin register (operators), realizing the same $W(3,3)$ geometry twice; the operator–operand duality makes program and data literally the same incidence object. Universality is a two-ingredient theorem: three passive optical elements (tritter, phase plate, EOM) generate the full 51840-element Clifford symplectic closure — *exactly*, not approximately — and the matter shell supplies the magic states that promote Clifford to universal. There is no cryostat, no vacuum chamber, no trapped ion: the exotic resource is geometry.

What it costs. The build sheet is a heralded single-photon source, one polarizing beam splitter, one symmetric tritter, a three-rail delay ladder, one electro-optic modulator, one recirculation loop with a fixed irrational rotation, and single-photon detectors. Every component is catalog optics. The machine's benchmarks are integer-valued: a laboratory can certify the Clifford layer by counting to 51840 and certify the fuel by hitting 36/40. Self-testing is native because the specification is arithmetic.

The software stack exists and is finite. Programs are braid words (with $\sigma^5 = Z$ exact); the instruction set is the BT828 compiler ABI; the operating system is the timetable library (36 schedules; overlap law 1-or-4 with switching cost 6); synchronization is the beacon-heptad mesh (2880 frames, themselves forming an exchange network); memory protection is the Steinberg sector ($81 = q^4$, a single irreducible — protected by Schur's lemma, the strongest no-leakage statement representation theory can make). The state/program compiler makes that register directly addressable: $\mathbb{F}_3^3$ supplies three commuting copies of the 27-slot program shell, H_{27} supplies three noncommuting copies of the state shell, and its center supplies the native generation flag $27 \subset 54 \subset 81$. The oriented timetable header above that memory splits as $5_\omega + 5_{\omega^2} + 30$: the full Weyl runtime fuses the handed pair into a 10-channel and leaves one 30-channel with an outer parity choice. Cache lookup is a distinct split layer: two copies of H/C_4 share an 81-route H/D_8 base, and their 324 slots form 81 four-state D_8 address fibers. The non-split ternary transport operator then updates the selected state; address choice and temporal memory cannot alias because their minimal polynomials differ. The watchdog is the BC loop. Each layer is a theorem; the stack compiles because double cosets compose.

Redundancy is built in, not bolted on. The newest results sharpen the fault story: each pentad core stores its timetable *three independent ways* (lit-chart transversals, the K_5 edge labeling, dark-sector shadows), every skew pair has six Petersen homes and two matching covers, and the dark sector carries its own chart matching and two chiral tetrad partitions (Theorem 91.4 block). Erasure of any single description leaves the schedule reconstructible — redundancy appears as a counting identity, not as an engineering allowance. The middleware's two packet phases (tetrahedral/hemioctahedral, the tomotope's $2_{\{0,1,2\}}$ class) confine phase changes to cell hops, which is where the commit boundaries already sit, and the runtime's vertex layer is a free $\mathbb{F}_2^2$-torsor (the Cayley structure), so address arithmetic is XOR end to end.

What it is not. No claim is made here of asymptotic speedups over error-corrected gate-model machines, of fault-tolerance thresholds, or of scalability beyond the fractal substitution rule (40^n leaves, diameter $8n$, commit clock $T(n) = 4(7^n - 1)$) — those are stated as exact combinatorial scaling laws, and their physical realization at depth $n > 2$ is an open engineering problem with its first hard boundary already computed (the $n = 5$ desynchronization with remainder $24 = f$). The honest claim is narrower and stranger: a complete, finite, self-verifying computational architecture exists inside one photon's worth of quantum optics, with zero adjustable parameters.

93.3 Networking

The network is the computer, twice over. The thesis is not rhetorical: the atlas's transport groupoid and the register's gate groupoid are the same groupoid, so moving a packet and applying a gate are one operation. The new library-geometry theorem (Theorem 91.2) doubles the statement at the control plane: the 36 timetables form $\mathrm{SRG}(36, 15, 6, 6)$, the *other* rank-3 geometry of the same group, so the control plane and the data plane ($\mathrm{SRG}(40, 12, 2, 4)$) are the two classical geometries of one symmetry. Configuration management inherits strongly-regular guarantees: any two timetables, near or far, have exactly six common near-neighbors — worst-case reconfiguration paths are bounded by the geometry itself.

Routing, addressing, switching. Local routing is e-cube XOR on Q_3 charts (540 of them; the atlas is glued along the 1620 apartments of the Tits building, diameter 5). Addresses are Gray-coded $\mathbb{F}_2^3$ words; the antipode map is bit complement. Timetable switching obeys the overlap law: cheap hops preserve $4 = \mu$ of 10 calibrated contexts, the switch graph is the $U_4(2)$ rank-3 geometry, and every skew pair lies in exactly 3 schedules, 6 Petersen homes, and 2 pentad-matching covers — the router's spare-path inventory is an exact census, not a provisioning estimate.

Synchronization without a master. The beacon heptads (2880 complete K_7 interference meshes, all pairwise overlaps 1/3) are reference frames that form their own exchange network — the network's clock distribution is itself a network, with no distinguished master node. External discipline comes from the $\mathbb{Z}_7/\mathbb{Z}_{13}$ clocks (both decimal period 6) and the BC quasicrystal drive; internal phase order from C_{12}. A distributed-systems reader will recognize the structure: consensus by geometry, where the "leader election" problem dissolves because the frame family is a single transitive orbit.

Security posture (implication, flagged). Three structural facts have security readings, stated here as directions rather than theorems. (i) Contextuality is tamper-evidence: the KS budget 36/40 is exact, so any channel intervention that classicalizes measurement statistics moves an integer and is detectable in principle. (ii) Gate teleportation stores a unitary in the photon's self-entanglement and applies it by Bell projection against its own past — a store-and-forward primitive for quantum repeaters that never exposes the gate classically. (iii) The timetable redundancy (three independent reconstructions) is an erasure-code posture against denial: losing a description class does not lose the schedule. Turning these into security proofs requires adversary models this paper does not supply.

Scaling. The fractal holonet substitutes a full 40-node substrate for each leaf: 40^n leaves, $(40^n - 1)/39$ substrate instances, reversible diameter $\leq 8n = 8 \log_{40} N$, durable commit clock $T(n) = 4(7^n - 1)$, with the first guard band an arithmetic necessity at $n = 5$. Because every child inherits the

same finite protocol, scaling adds no new control logic — the protocol stack is depth-invariant. This is the architectural property that datacenter fabrics approximate statistically and this geometry has exactly.

93.4 The physics-to-architecture dictionary

In plain language. *A translation table. Each row pairs a physical quantity — an optical mode, a phase, a loss rate — with the architectural role it plays, so a physicist and an engineer reading the same later section can tell they are discussing the same object. Where a row has no entry on one side, that gap is the honest state of the design.*

The dictionary is the deepest implication: one set of integers reads simultaneously as physics and as engineering, because both readings are projections of the same incidence theorems.

object	physics reading	architecture reading
$1 + 12 + 27$ split	Bell line + meeting + disjoint	pole / I-O ports / fuel+store
240 edges	interaction qutrits	bandwidth = memory
$81 = q^4$ Steinberg	protected sector (Schur)	logical register
dual O_3 restrictions	Heisenberg state phases	state/program compiler
$H_2 = 5 + \bar{5} + 30$	oriented context chirality	timetable header $10 + 30^{\pm}$
$324 = 81 \times 4$, commutant D_8	split cache multiplicity	four-state address fiber
$0 \to 81 \to 162 \to 81 \to 0$	ternary temporal extension	non-split state update
36 spreads	measurement bases	timetable OS
$\mathrm{SRG}(36, 15, 6, 6)$	basis-overlap law	control-plane fabric
five vacua	phases of the theory	boot modes
magic strata 8+24+4	fermion shell grading	fuel octanes
540 skew pairs	two-fold null systems	hypercube charts
1620 apartments	Weyl frames	inter-chart trunks
2880 heptads	equiangular frames	sync beacons
BC drive $\arccos(-2/3)$	quasicrystal time	watchdog clock
compasses (216+216)	icosahedral order, delocalized	needle registers
pentads (chiral 216+216)	maximal partial spreads	F_5 chart caches
dark sector zoo	hidden-half structure	erasure store
tomotope ($2_{\{0,1,2\}}$, Cayley/V_4)	sphere/projective alternation	packet middleware
11-cell, 57-cell, J_1	universal completions (blocked)	the covers the hardware refuses

The first row carries the deepest identification, drawn from the companion paper *Universal Quantum Computation Through a Single Photon*: the split $1 + 12 + 27$ is not merely the local SRG anatomy of a point — it is the **Bell-line shell** of the photon's own self-entanglement seed. The temporal Bell qutrit $|\Omega\rangle$ stabilizes one line of $W(3, 3)$; the 40 lines then decompose as 1 (the Bell line itself) $+12$ (lines meeting it — the gauge sector) $+27$ (lines disjoint from it — the matter sector), with substrate reading $1 + k + q^q$. The vacuum decomposition that organizes the Standard-Model derivation is literally the photon's view of its own now-context: *self = the seed of self-entanglement.* The Bell-line stabilizer has order $51840/40 = 1296 = \mu^2 q^{q+1}$ — the same $1296 = 6^4$ that counts the compass D_{10}-incidence pairs of Theorem 91.4 (36 schedules $\times$ 36 core pairs), but Theorem 81.3 proves that this is not a regular-action identification. Instead, the projective Bell stabilizer resolves the incidence carrier as 648+324+162+162, the exact mirror/schedule/left-cache/right-cache prefix decoder, while the point parabolic supplies two persistent 648 address sheets. The two cache words

110 and 111 are now resolved more finely by Theorem 89.6: they name two copies of the same H/C_4 cache, not two inequivalent internal chiral modules. Both double-cover one canonical H/D_8 base of 81 routes, and the complete cache quarter is an exact D_8-over-81 square bundle. This reversible address plane is provably not the non-split $81 \to 162 \to 81$ transport plane, despite their common 162 count. The companion also supplies the master equation at Hilbert-space level ($q^2 = q+q!$: the 9-dimensional past⊗future space splits into 3 diagonal "now" histories and $6 = q!$ context-changing ones), and a ledger identity: temporal gate teleportation consumes exactly 2 classical trits of memory — the same 2-trit cost that prices the arrow of time in the self-loop fixed point of §90. Storing a state for one's future self and forgetting one's past cost the same two trits. The 27 itself now has a dual decoding: the 27 non-collinear *points* form a torsor under the genuine Heisenberg group (the normal 3_+^{1+2} of the point parabolic, acting simply transitively), whose invariant relations reconstruct the whole classical 27-zoo — the 9-triangle fibration, $\mathrm{GQ}(2,4) = \mathrm{SRG}(27,10,1,5)$, and the Schläfli graph $\mathrm{SRG}(27,16,10,8)$ of the E_6 27-lines world — while the 27 disjoint *lines* of the Bell shell form a torsor under elementary $\mathbb{F}_3^3$ (the line parabolic's O_3), a flat 3-trit register cube carrying *no* invariant strongly regular graph. Curvature for states, flatness for programs: the matter sector is a Heisenberg manifold on the state side and a ternary address space on the operational side. The register reading is exact: assigning each Bell-shell context its 3-trit address, the four pair relations $[4,4,6,12]$ are the difference-vector classes, and the geometry is a function of register arithmetic alone — meeting contexts (±-paired 4-classes) share exactly 1 transversal onto the Bell line, near-skew (12) exactly 2, far-skew (6) exactly 0: base-3 register incidence for matter contexts, twin to the charts' base-2 Gray arithmetic. *Witnesses:* `bt858_heisenberg_shell_torsors.py`, `bt860_bell_shell_register_arithmetic.py`.

Three rows deserve emphasis. The *Steinberg row* is the strongest protection statement available: the register is one irreducible representation, so *any* equivariant leakage operator is zero by Schur's lemma — protection by symmetry, not by redundancy. The *compass rows* say that what physics sees as delocalized icosahedral order, engineering sees as a navigation instrument: 12 needles per schedule, each carrying Petersen addressing, five-chart caches, and a dark-sector mirror. The *universal-polytope row* states the program's sharpest structural lesson: the hardware keeps the local physics of the exceptional objects and refuses their global rigidity; the refusal (an integer non-divisibility) is precisely why the architecture is distributed.

93.5 Beyond the laboratory

A different contract between theory and experiment. Every layer of this machine is specified by integers and verified by scripts that re-derive those integers from first principles in seconds. The cultural implication is a publishing model in which papers *run*: a claim is not a sentence but a reproducible computation, and a correction is a commit. This program has already operated under that contract (see the ethos below) — twice it corrected its own published claims at the source, and the corrected values were more natural than the originals. If the broader physics literature adopted executable claims at even a small scale, entire classes of irreproducibility would become type errors.

Quantum hardware without a building. Architectures that need millikelvin cryostats centralize by economics: only institutions can own them. A universal architecture whose parts list is catalog optics — source, splitters, delay fiber, modulator, detectors — decentralizes by the same economics. The realistic near-term role is not supremacy-class computation but *certified* small-scale quantum information: teaching laboratories that can verify 51840 and 36/40 on a bench; metrology nodes whose clock is protected by an irrational rotation; network testbeds where gates

and routes are the same hardware. A machine whose benchmarks are exact integers is also the natural pedagogical machine: a student can check the whole specification.

Communication and computation stop being separate utilities. In this architecture there is no boundary at which computation hands off to networking — the gate groupoid and the transport groupoid coincide, and the fractal substitution makes the computer/network identity scale-invariant. The long-run implication, if any physical system realizes this pattern at depth, is infrastructural: bandwidth and compute become one provisioned quantity, scheduling becomes group theory, and the spectrum-allocation problem for the network's measurement contexts is solved by a finite library (36 timetables with a known switching metric) rather than by auction or contention.

Society-scale stakes of a zero-parameter physics. Separately from the machine, the substrate program's physics claims — 54+ observables, 14 falsifiable predictions, no adjustable parameters — carry a specific societal meaning: they are maximally exposed. A theory with no dials cannot retreat; the 2027 neutrino-hierarchy determination, the proton-decay window, the CMB measurements will each either hit the predicted integers or end the corresponding pillar. Public trust in fundamental science is built by exactly this posture — predictions that can die — and the machine half of the program extends the posture to hardware: the device specification is its own audit.

What could go wrong, said plainly. The architecture is exact; its physical realization is not yet demonstrated beyond the component level. The fractal scaling laws are combinatorial theorems, not engineering schedules. The security readings are directions, not proofs. And the identification of the substrate with fundamental physics stands or falls with the prediction table, not with the elegance of the mathematics. This paragraph exists because the program's ethos (below) requires the failure modes to be listed next to the claims.

93.6 The ethos

Several pre-existing corpus claims failed under exact computation and were corrected at their sources during this program: the independence number of $W(3,3)$ is 7, not 10 (no ovoid exists; the "perfect graph" block is withdrawn); the Kochen–Specker optimum is 36/40, not 34/40; the pentad-sharing count of BT844 was corrected by the chiral-orbit census of BT845 within one working session; and the tomotope's framing was corrected from "non-polytopal maniplex" to "uniform polytope with non-polytopal minimal covers" when the literature was read precisely; and the "$\mathbb{Z}_3$ Berry phase as a discrete second Chern class" was corrected (BT871) — the uniform Berry 2-cochain is a coboundary over $\mathbb{F}_3$, so the physical $\mathbb{Z}_3$ is the order-3 action on the Steinberg register, not a curvature class. In every case the corrected value is *more* substrate-natural than the claim it replaced ($\alpha = \Phi_6$; budget $= (q!)^2/v$; $432 = 216 + 216$ chiral; infinitely many covers as the actual pathology; the $\mathbb{Z}_3$ as a group action rather than a cocycle) — the pattern a real structure shows when probed honestly. The program treats corrections as first-class results: they are committed, logged, and cited like theorems, because a corpus that cannot heal is a corpus that cannot be trusted.

A Verification ledger

Every theorem above is backed by an executable script in `analysis/` with results in `data/`; the chain BT739–BT839 was developed and pushed incrementally with exact arithmetic (GF(p) elimination, cyclotomic integers, complete branch-and-bound, GAP witnesses for group-theoretic facts).

layer	primary witnesses
duality / carriers	bt817, bt820, bt821
atlas / building / web	bt773, bt777, bt744, bt779
mirror middleware / tomotope runtime	bt814, bt815, bt826
braids / registers	bt740, bt741
vacua / geography / transitions	bt808–bt813, bt816
fuel / contextuality	bt818, bt822, bt823
memory / Steinberg	bt742, bt744
clocks / quasicrystal / arrow	bt774, bt819, bt820, bt823
sync / schedules / overlap law	bt817, bt819, bt835
Grünbaum–Coxeter hemicells / library geometry	bt836, bt837, bt839
two compasses / $4 \cdot K_{10} = 12$ Petersens / chart double cover	bt843–bt845
pentad anatomy / schedule reconstruction / dark dodecahedra	bt846, bt847
amalgamation ladder / universality / J_1	bt848
maniplex barren rung / class $2_{\{0,1,2\}}$ / Cayley over V_4	bt849–bt851
seventeen universals / Aut(tomotope) universal	bt852
dark orbit zoo / shadow bijection / K_5-complete dark sector	bt853–bt855
dark charts = mirror bus (G-set iso)	bt856
Heisenberg/$\mathbb{F}_3^3$ shell torsors, Schläfli decoding	bt858
Bell-shell register arithmetic ($[4, 4, 6, 12]$ named)	bt860
code register = Steinberg ($[[240, 81, 3]]_3$, $d_X = 3, d_Z = 4$)	bt861
H_2 = sign-twisted lines (homological dictionary)	bt862
three generations = Steinberg vanishing	bt863
triality census (matter-blind, gauge-visible)	bt864
joint generation × chirality grading	bt868
chirality = polar-pair involution $(45 + 36)$	bt869
spanning-tree gravity $\tau = 2^{81}5^{23}$	bt870
Berry-phase correction ($\mathbb{Z}_3$ is the Steinberg action)	bt871
Ihara zeta = spanning-tree gravity bridge	bt872
two-zeta duality / walk census	bt873
texture triality = long-root transvection	bt874
Yukawa rule = $\mathbb{Z}_3$ grade conservation	bt875
gauge group $1 \oplus 3 \oplus 8$ from $C(R)$	bt876
gauge parity = duality ($A_4 \to S_4$)	bt877
generation charge-conjugation ($N/C = \mathbb{Z}_2$)	bt878
flavor group S_3 ($\mathbb{C}[27] = 6{\cdot}1 + 3{\cdot}1' + 9{\cdot}2$)	bt879
generations = centre of the gauge group	bt880
spacetime = space of 40 local gauge groups	bt881
gauge connection flat on edges, $2T$-curved on Q	bt882
curvature 2-form (quaternionic, on Q)	bt883
gauge flux (Wilson loops, $\mathbb{Z}_3$/lines, $\leq 12/Q$)	bt884
YM–matter coupling $\sum \chi_{\mathrm{St}} = 1080$	bt885
SM spine (one transvection, master theorem)	bt886
gauge group = color : electroweak (27:24)	bt887
color = the matter-shell Heisenberg group	bt888
fermion content $27 = C(R)/SL(2, 3)$ (lepton/quark)	bt889
dual-torsor Steinberg compiler / native generation flag	bt865
oriented H_2 irreducible spectrum / outer lift	bt866
cache D_8-over-81 fibration / split–non-split boundary	bt867
chirality bookkeeping / Bell–compass parabolic router	bt857, bt859
universality	bt825
fractal computer/network	bt827
runtime compiler / sentinel / commit / cover boundary	bt828–bt834, bt838
corpus corrections	bt818, bt823, bt824

B Architecture Completeness and the Three Physical Residuals

In plain language. *What remains unspecified. Three physical questions are not answered by the geometry and must be settled by measurement or by a fabrication choice; this section names them rather than leaving them implicit. A design that cannot say what it does not determine is not complete in any useful sense.*

The holonet machine is now specified end to end: the 40-point substrate register and its $W(3,3)$ commuting-projector Hamiltonian; the $[[240, 81, 3]]_3$ Steinberg code as the native error-correcting register; the local gate set and transversal/holonomy operations; the gauge connection (flat along the 240 edges, curved on the matter graph with binary-tetrahedral $2T$ holonomy) as the physical wiring of multi-qubit interaction; and the discrete dynamics, in which the physical on-shell states are exactly the harmonic forms $\ker D$ (vacuum $\oplus$ Steinberg matter $\oplus$ line module $= 1 \oplus 81 \oplus 40$) — the least-action ground space of the finite spectral action $\mathrm{Tr}\, f(D^2)$, whose value reproduces the spanning-tree gravity invariant. *As a universal computer the architecture is complete*: universality, the code, the gate set, and the runtime compiler are established (cf. the substrate ledger above).

What remains is not computational but *physical*, and the three residuals of the master manuscript's completeness boundary (`w33_paper.tex`) are now each resolved or reduced:

- **(R1) the gauge-lattice embedding — resolved.** The machine's symmetry register carries the canonical symplectic $E_8/2E_8$ datum mod 2, and that datum admits a *unique* $\mathrm{PSp}(4,3)$-invariant quadratic refinement, of plus type; hence $\mathrm{PSp}(4,3) \subset O_8^+(2) = \mathrm{Aut}(E_8/2E_8)$, and the canonical positive-definite lift is E_8 (up to a central $\{\pm 1\}$). The gauge lattice is fixed.

- **(R2) the symmetry / matter register — datum supplied, bridge built.** The quintic moonshine traces $\mathrm{Tr}(2A|V_5) = 74428120$, $\mathrm{Tr}(2B|V_5) = 184024$ are computed; and the matter register is realized as a finite spectral triple (a Hilbert–Schmidt bimodule of dimension 81, first-order condition verified, gauge content $\mathbf{1} \oplus \mathbf{3} \oplus \mathbf{8}$). The residual is now the explicit physical fermion-multiplet assignment, a representation- selection task.

- **(R3) the emergent-spacetime limit — theorem-governed.** On a shape-regular (edge-wise) refinement tower the full gravity-plus-matter spectral action converges term by term to the continuum Einstein–Hilbert + Standard-Model action — by Cheeger–Müller–Schrader (curvature), higher-order Regge (higher-derivative), classical lattice gauge, and the exact finite moments $\{440, 1920, 16320\}$; the spectral action is moreover continuous for Latrémolière's spectral propinquity. The emergent-spacetime limit is thus the *application* of established convergence theorems, not an open analytic obstruction.

None of the three is a gap in the machine's *operation* — the holonet runs, corrects, and computes universally as specified — and none is now an open problem in principle: a fixed gauge lattice (E_8), a matter register awaiting only its physical labelling, and an emergent spacetime with a theorem-governed continuum limit. This is the precise sense in which the architecture is complete: a finite, exact, universal machine whose physics closes onto the Standard Model and general relativity through results that are now either proved or reduced to the application of known theorems.

Reading guide for what follows. The remaining subsections develop the architecture in four movements, each a chain of witnessed theorems. *(A) The logical layer is substrate-forced*: the machine is the substrate's symplectic continuum (the oscillator representation), its fault-tolerant

code is the lattice tower $A_2 \subset D_4 \subset E_8$, its universal gate set is the degree-2 symplectic plus degree-3 cubic invariants, the gate group equals the code's logical Clifford group $\mathrm{Sp}(4,3)$, and the code lattices sit on the $E_8 \to$ Leech $\to$ Monster moonshine ladder. *(B) The physical carrier is one massless self-protected photon*: the demonstrator versus the fault-tolerant machine, gates as geometric ($2T$) holonomies, self-error-correction from the substrate-fixed quasicrystal drive (topological, $|C| = q-1$), why the primitive must be a single massless photon (zero proper time, Wigner helicity λ), and the carrier as its own geon inside a fractal of nested shells. *(C) The physics and the computer are one object*: the quantum power is the gauge curvature on the matter graph, that discrete curvature is a finite-group lattice gauge theory whose continuum limit is the spectral action's gauge-plus-gravity field equations (with an exact mass gap f), the whole network has a finite holographic-code analogue — its screen multiplicity $\mu = 4$ agrees with the one-sided distance $d_Z = 4$, while the full CSS distance is $d = 3$; that finite equality alone derives neither black-hole entropy nor a continuum AdS/CFT. The runtime adds a separate typed finite control ABI: binary Q_3 address toggles lower to header flags and then to Q6 pulse transitions. Its spectral displacement $\sqrt{\lambda} = \sqrt{2}$ and its 51840-frame accounting do not by themselves supply a mass scale, group action, or continuum realization. *(D) It is testable now*: a parameter-free near-term falsification protocol on the single-photon demonstrator. Throughout, one substrate number recurs — $q - 1 = \lambda = 2$ sets the drive angle, the topological protection, and the photon's transverse helicity count — and no constant is fitted.

B.1 The architecture is the substrate's symplectic continuum

There is a structural reason the machine and the spacetime are different objects built from the same $W(3,3)$: the substrate has *two* continuum limits. The arithmetic tower $W(3,q)$ (the symplectic quadrangle over $\mathbb{F}_q$, $q = 3^n$) is spectrally rigid — exactly three eigenvalues at every q, no Weyl law — so it never becomes a smooth spacetime; the metric continuum needs the external $K3$ seed (the physics side, `w33_paper.tex`, Prop. on the two continua). The *intrinsic* continuum of $W(3,3)$ is instead *symplectic*: its Heisenberg matter shell 3^{1+2} carrying the $\mathrm{Sp}(4,3)$ action is a Weil-representation datum, whose $q \to \infty$ limit is the metaplectic (oscillator) representation of $\mathrm{Sp}(4,\mathbb{R})$ on $L^2(\mathbb{R}^2)$ — precisely the continuous-variable, Fock/oscillator computation this paper realizes. So the holonet *is* the symplectic continuum of the substrate, exactly as the spacetime is its metric continuum: the universal computer and the universe are the two faces of one finite geometry's continuum limit. (Witness: `analysis/w33_two_continua_symplectic_metric.py`.)

B.2 The fault-tolerant layer is the substrate's lattice tower [Face 5]

Because the holonet's logical layer is a continuous-variable (CV) oscillator computation, its canonical fault-tolerant encoding is the Gottesman–Kitaev–Preskill (GKP) code, which embeds a qudit in an oscillator. A *multimode* GKP code *is* a symplectic lattice in phase space: stabilisers are displacements by lattice vectors, and error correction is closest-point decoding in the symplectic dual lattice. The code quality is set entirely by the lattice, and the established optima are exceptional lattices: the *hexagonal* lattice A_2 for one mode, the densest 4-dimensional lattice D_4 for two modes (strictly better than any product of one-mode codes), and E_8 for four modes [23, 24].

This is not a free design choice for the holonet: the substrate *fixes* the lattice at every scale. The machine is two qutrits, hence two oscillator modes ($L^2(\mathbb{R}^2)$, phase space $\mathbb{R}^4$), so its optimal GKP code lattice is D_4 — and D_4 is exactly the substrate's matter shell, with $|W(D_4)| = 192$ the tomotope/flag symmetry and D_4 triality the three-generation structure. The single-mode optimum A_2 is the $q = 3$ (hexagonal, $SU(3)$) lattice of a single qutrit, and two modes stacked, $D_4 \oplus D_4$,

sit primitively inside E_8 — the substrate's mod-2 homology lift (R1), which is also the $K3$ gauge lattice. Thus the tower

$$A_2 \subset D_4 \subset E_8$$

is *simultaneously* the optimal 1-, 2-, 4-mode GKP code lattices (the architecture's quantum error-correction layer) and $W(3,3)$'s physical lattice tower (single-qutrit $SU(3)$, matter shell, gauge E_8). The error correction of the computer and the gauge structure of the universe are one and the same lattice tower; the QEC code is not chosen, it is the substrate. (Witness: `analysis/w33_gkp_lattice_architecture.py`, verifying the kissing numbers $6, 24, 240$ and the embedding $D_4 \oplus D_4 \subset E_8$.)

This also fixes the lattice part of the fault-tolerance threshold. The substrate lattices are *isodual* (symplectically self-dual — the balanced-GKP condition, $\hat{q}$ and $\hat{p}$ protected equally) and densest in their dimensions, so they maximise the nominal coding gain $\gamma = d_{\min}^2/\det^{1/n}$ among symplectic lattices of that rank:

$$\gamma_{\mathrm{dB}}(A_2) = 0.6, \qquad \gamma_{\mathrm{dB}}(D_4) = 1.5, \qquad \gamma_{\mathrm{dB}}(E_8) = 3.0$$

(and 6.0 for the Leech lattice). So the holonet's two-mode code D_4 already buys ~ 1.5 dB, and the four-mode code $E_8 \sim 3$ dB, of squeezing-margin over the trivial square code, for free. The absolute threshold still needs the noise model, the finite-squeezing GKP-state quality and the syndrome-extraction protocol — which we do not fix here — but the lattice contribution, the part that depends only on the code, is the substrate's and is optimal. (Witness: `analysis/w33_gkp_coding_gain.py`.)

B.3 The universal gate set is degree two plus degree three

The code fixes the fault-tolerant layer; the gate set completes the architecture, and it too is substrate-forced. The continuous-variable universality theorem [25] states that the Gaussian unitaries — those generated by Hamiltonians at most *quadratic* (degree 2) in the mode operators: beamsplitters, phase shifters, squeezers, i.e. the CV Clifford group $\mathrm{Sp}(2n,\mathbb{R})$ — are *not* universal, but adjoining any single generator of degree ≥ 3 (canonically the cubic phase gate $e^{i\gamma\hat{q}^3}$) generates the full unitary group on the oscillators. A universal CV machine thus needs exactly

$$\underbrace{\text{degree 2}}_{\text{Gaussian / Clifford}} \quad + \quad \underbrace{\text{degree 3}}_{\text{cubic, non-Gaussian}} \quad .$$

The substrate supplies precisely these, as its two lowest matter invariants and no others below degree three: the *degree*-2 symplectic form on $\mathbb{F}_3^4$ that $\mathrm{Sp}(4,3)$ preserves — whose oscillator-rep limit is the Gaussian group $\mathrm{Sp}(4,\mathbb{R})$ that the photon's tritter, phase plate and modulator already realise (§85.5) — and the *degree*-3 E_6 Cartan cubic on the matter $27 = 3 \otimes 3 \otimes 3$, the ε-cubic preserved by $\mathfrak{sl}(3,\mathbb{F}_3)^3$ (`w33_paper.tex`, the 27-cubic and its 45 triads). So the paper's earlier statement that "the matter shell supplies the magic" is, in the CV picture, exact: the magic is the degree-3 E_6 cubic, the minimal non-Gaussian element, matching the Lloyd–Braunstein criterion on the nose. The substrate's invariant degrees $\{2,3\}$ *are* the universal CV generating set $\{\text{Gaussian}, \text{cubic}\}$. Together with the lattice tower $A_2 \subset D_4 \subset E_8$ this closes the architecture: $W(3,3)$ fixes both the fault-tolerant code and the universal gate set, leaving no free choice in the logical layer. (Witness: `analysis/w33_cv_universality_cubic.py`.)

Finally, the code and the gate set are not two independent facts: they are welded by a single group. The logical Clifford group of a GKP code on n qudits of dimension d is the symplectic group $\mathrm{Sp}(2n, \mathbb{Z}/d)$ over the logical phase space. For the holonet ($n = 2$, $d = 3$) this is

$$\mathrm{Sp}(4, \mathbb{Z}/3) = \mathrm{Sp}(4,3), \qquad |\mathrm{Sp}(4,3)| = 51840,$$

which is *exactly* $\mathrm{Aut}(W(3,3))$, the 2-qutrit Clifford group mod Pauli, and the Clifford group the photon's own tritter, phase plate and modulator already generate (§85.5, "symplectic closure = 51840"). So the substrate's symmetry group, the machine's realised gate group, and the GKP code's logical gate group are *one group*: the gates act on the code by construction. The code-preserving (transversal) Gaussian gates are the lattice automorphisms $\mathrm{Aut}(D_4) = W(F_4)$ of order $192 \cdot 6 = 1152$, whose S_3 factor is D_4 triality — the three-generation structure — and the remaining $[\mathrm{Sp}(4,3) : \mathrm{Aut}(D_4)] = 45$ logical Cliffords are teleported using the cubic resource. The logical layer of the holonet is thus a single coherent object, every part of it fixed by $W(3,3)$. (Witness: `analysis/w33_gkp_clifford_coherence.py`.)

B.4 The code lattices are the moonshine ladder [Face 5]

The same lattices carry one last structure that ties the machine to the deepest arithmetic of the substrate. The holonet's modes are free bosons, and a GKP code is a free-boson theory compactified on its stabiliser lattice; an even lattice Λ of rank r is in turn the lattice vertex operator algebra (VOA) V_Λ of central charge $c = r$ (Frenkel–Kac–Segal), while the stabiliser code itself fixes the corresponding (Narain) code CFT [26, 27]. The holonet's GKP code lattices are the substrate tower A_2, D_4, E_8 of ranks $2, 4, 8$, hence the lattice VOAs of central charge

$$c(A_2) = 2, \qquad c(D_4) = 4, \qquad c(E_8) = 8.$$

The top rung, the E_8 VOA at $c = 8$, is exactly the base of the moonshine ladder that $W(3,3)$ already realises on the physics side,

$$V_{E_8}\ (c = 8) \ \longrightarrow\ V_{\Lambda_{24}}\ (c = 24) \ \longrightarrow\ V^\natural\ (c = 24,\ \mathrm{Aut} = \mathbb{M}),$$

with $V^\natural$ the Frenkel–Lepowsky–Meurman Monster module (24 free bosons on the Leech torus, $\mathbb{Z}/2$-orbifolded), and $\Lambda_{24} \supset E_8^3$ the gauge lattice thrice. So the *same* E_8 is the holonet's optimal 4-mode GKP code, the substrate's homology/gauge lattice, and the $c = 8$ chiral VOA that begins moonshine; and the top central charge $c = 24 = f = \chi(K3)$ is the $W(3,3)$ matter count. The computer's error-correcting code and the Monster module are one vertex-algebra tower — the architecture and the moonshine residual (R2) are the bottom and top of a single ladder of substrate lattices. (Witness: `analysis/w33_gkp_voa_bridge.py`.)

B.5 What is physically needed: demonstrator versus fault-tolerant machine [Face 6]

It is worth being exact about what we are building, because the design is now complete but the *physical* realisation has two genuinely different layers. The single self-entangled photon of the build sheet — polarisation + time-bin qutrits, a tritter (F_3), a delay ladder and an EOM, read out by single-photon detectors — realises the *ideal, un-encoded* logical layer: the $\mathrm{Sp}(4,3)$ gate set, the routing network, and every parameter-free witness. It is buildable with today's quantum optics and it demonstrates the *logic*. But a single photon has fixed photon number; it cannot carry a GKP grid state (a many-photon quadrature lattice). So the photonic demonstrator is not, and cannot be, fault-tolerant.

Fault tolerance is the standard two-layer continuous-variable stack — and here both layers are substrate-fixed, with nothing left to choose:

$$\underbrace{240 \text{ squeezed modes}}_{\text{physical}} \to \underbrace{120\ D_4 \text{ GKP pairs}}_{\substack{\text{inner: analog}\to\text{digital} \\ \text{gain } 1.5\,\text{dB}}} \to 240 \text{ GKP qutrits} \to \underbrace{[[240, 81, 3]]_3}_{\substack{\text{outer: Steinberg} \\ d_X{=}3,\ d_Z{=}4}} \to 81 \text{ logical qutrits}.$$

The inner code is the GKP code on the matter-shell lattice D_4 (converting continuous displacement noise into discrete qutrit errors, with the 1.5 dB coding gain that eases the squeezing budget); the outer code is the $[[240, 81, 3]]_3$ Steinberg code, with $(d_X, d_Z) = (3, 4)$, on the substrate's 240 edges. What remains is purely physical, and it is the *universal* CV fault-tolerance bottleneck, not a $W(3, 3)$-specific one:

1. squeezed light at threshold ($\sim$ 10 dB; protocol-dependent, 7–20 dB in the literature), lowered by the D_4/E_8 coding gain (1.5/3.0 dB);
2. GKP qutrit *state generation* — measurement-based breeding from squeezed/cat states with photon-number-resolving detection, or matter-assisted preparation: the hard step;
3. the cubic non-Gaussian resource — the degree-3 E_6 "matter-shell magic" — via a $\chi^{(3)}$ medium or magic-state injection;
4. a programmable beamsplitter/phase/squeeze network implementing the $\mathrm{Sp}(4, 3)$ Clifford (mature integrated photonics);
5. homodyne detection for GKP and Steinberg syndrome readout.

This is the precise, honest statement of what the holonet is and what it still needs: a concatenated $\mathrm{GKP}(D_4) \circ \mathrm{Steinberg}\,[[240, 81, 3]]_3$ continuous-variable qutrit computer in which $W(3, 3)$ fixes *both* code layers, the gate set ($\mathrm{Sp}(4, 3)$ Gaussian + E_6 cubic) and the network — leaving *zero design freedom above the hardware*. The only open problem is the same one the entire CV fault-tolerance field faces, GKP-state generation at threshold squeezing, and the substrate's optimal lattices ease rather than remove it. (Witness: `analysis/w33_holonet_physical_stack.py`.)

B.6 The gates are geometric: holonomic Clifford from the gauge connection

There is a third, gate-level layer of robustness that the substrate supplies for free, and it explains the name. The substrate gauge connection is flat along the 240 edges and curved on the matter graph, with binary-tetrahedral $2T$ holonomy. That holonomy group is not arbitrary:

$$2T \;\cong\; \mathrm{SL}(2, 3) \;=\; \mathrm{Sp}(2, \mathbb{Z}/3), \qquad |2T| = 24,$$

the centre being $\{\pm I\}$ and the quotient $2T/\{\pm I\} = A_4$; and $\mathrm{Sp}(2, \mathbb{Z}/3)$ is precisely the single-qutrit Clifford group modulo Pauli. So the gauge connection's holonomy *is* the qutrit Clifford group, and the gates may be realised as *non-abelian holonomies* (Wilczek–Zee geometric phases) traced in the connection [4, 5]. Holonomic gates depend only on the geometric path, not on pulse timing or shape, so they are intrinsically robust to control error: this is fault tolerance at the *gate* level, complementary to the GKP code (analog level) and the Steinberg/color outer code (logical level). The full two-qutrit Clifford $\mathrm{Sp}(4, 3)$ (order 51840) is generated by the matter-graph holonomy on each qutrit together with the entangling network.

The deeper point is the identity of the connection. The *same* connection whose *curvature* furnishes the substrate's gauge fields furnishes, through its *holonomy*, the computer's gates: the gauge interactions of the physics and the logic gates of the machine are one and the same non-abelian holonomy. This is the literal content of "holo-net". (Witness: `analysis/w33_holonomic_gates.py`, constructing $\mathrm{SL}(2, 3)$ and verifying order 24, symplecticity, centre $\{\pm I\}$, quotient A_4, and the order spectrum $\{1, 1, 8, 6, 8\}$ of $2T$.)

B.7 The quantum power is the gauge curvature

Read together with the physics tier (§93: the gauge connection is flat on the 240 collinear edges and $2T$-curved on the matter graph Q, with curvature $F(p,q) = [R_p, R_q]$ a quaternion unit), the holonomic identification sharpens into a single statement: *the gates are the gauge generators, and the entangling power is the curvature.* The 40 long-root transvections R_p — one per point, each the generation-$\mathbb{Z}_3$ source of the Standard-Model spine — are exactly the elementary gates (Wilson loops of the substrate connection), and they generate the whole gate group:

$$\langle R_p : p \in W(3,3)\rangle = \mathrm{Sp}(4,3), \qquad |\cdot| = 51840.$$

Each point has $12 = k$ *flat* (collinear, causal) neighbours, where $[R_p, R_q] = I$ and $\langle R_p, R_q\rangle = \mathbb{Z}_3 \times \mathbb{Z}_3$ is abelian and classically simulable, and $27 = q^q$ *curved* (matter-graph Q, non-collinear) neighbours, where the curvature $F = [R_p, R_q]$ is an order-4 quaternion unit and $\langle R_p, R_q\rangle = 2T = \mathrm{SL}(2,3)$ is non-abelian. So the non-Clifford/entangling resource sits *exactly* on the curved directions: a flat pair gives only the abelian $\mathbb{Z}_3 \times \mathbb{Z}_3$ (classically simulable), and the per-gate non-abelian content requires curvature. Quantitatively, a triangle $p{\to}q{\to}r{\to}p$ carries a Wilson loop $W = R_pR_qR_r$ whose order is the discrete curvature flux: the 160 collinear triangles all carry the uniform abelian flux of order 3, while the 3240 matter triangles of Q carry non-abelian flux of orders $\{2,4,6,12\}$ (counts $180, 180, 1440, 1440$, up to $12 = k$), and the discrete Yang–Mills action $S = \sum_{\triangle}\big(1 - \frac{1}{\mathrm{ord}\,W}\big)$ concentrates $\approx 96\%$ on the matter graph. In the physics reading the same curvature on Q is the $su(2)$ field strength and, through its $\mathbb{Z}_3$ Yukawa grading, the fermion-mass texture — so on the matter graph,

$$\text{curvature} \;=\; \text{entanglement} \;=\; \text{magic} \;=\; \text{mass},$$

all one object, while flatness is causality. *(Honest scope: this is a field-strength statement. Both the flat and the curved Wilson-loop* sets *generate all of* $\mathrm{Sp}(4,3)$ *— the order-3 flat loops are genuine gates — so the curved/flat split is the per-plaquette curvature and the location of the Yang–Mills action, not a global classical-vs-quantum partition of the group.)* The machine's quantum advantage is not added to the substrate; it lives in the curvature of the Standard-Model gauge field. (Witnesses: `analysis/w33_gauge_curvature_is_computation.py` (40 order-3 transvections, 12 flat / 27 curved per point, curvature order 4 on Q, $\langle R_p\rangle = \mathrm{Sp}(4,3)$); `analysis/w33_yang_mills_computation.py` (Wilson-loop census, the 96% matter-graph action).)

B.8 The fuel is contextuality: the register is a Wigner phase space and magic is its negativity

There is a second, resource-theoretic answer to "where does the quantum power come from," and it is exact on the substrate. Howard, Wallman, Veitch and Emerson proved that for odd-prime-dimensional qudits *contextuality* — equivalently, negativity of the Gross discrete Wigner function — is the necessary resource that lifts Clifford computation to universal quantum computation by magic-state injection [10]. The qutrit $d = q = 3$ is the smallest, cleanest case, and the substrate realizes the whole picture geometrically. The discrete phase space of two qutrits is $\mathbb{Z}_3^4$ with $3^4 = 81 = q^4$ points — *exactly* the logical register $H_1 = 81$ of the $[[240, 81, 3]]_3$ code (irreducible under $\mathrm{PSp}(4,3)$); the Wigner function lives on the same 81 points the machine computes on. The 40 vertices of $W(3,3)$ are the $(81-1)/2 = 40$ nonzero rays of that phase space — the two-qutrit Pauli operators up to phase — so the substrate *is* the two-qutrit Pauli geometry. The Clifford group acts as $\mathrm{Sp}(4,3) = \mathrm{Aut}(W(3,3))$, permuting phase points and preserving Wigner-positivity (the classically simulable sector, Gottesman–Knill). And the non-Clifford states the holonet injects — the Hesse/cubic/T-type magic of the universal gate set — are exactly the Wigner-*negative* states:

a stabilizer state such as $|0\rangle$ or $|+\rangle$ has $W \geq 0$, while the qutrit "strange" state $(|1\rangle - |2\rangle)/\sqrt{2}$ has $\min W = -\frac{1}{3}$ and mana $\ln \frac{5}{3} > 0$. So the machine is quantum precisely where the substrate's Wigner function goes negative; the magic it spends is the contextuality of the geometry, and the corpus already measures the geometry's contextual fraction as $4/40 = 1/\Phi_4$. Curvature (the gauge picture) and Wigner-negativity (the resource picture) are two readings of the same fuel. (Witness: `analysis/w33_contextuality_is_the_fuel.py`.)

B.9 From the matter-graph lattice to continuum Yang–Mills: the loop closes

The discrete curvature of the previous subsection is not a metaphor for a gauge theory — it *is* one, and its continuum limit is the gauge sector of the physics. Each matter edge carries the curvature $F = [R_p, R_q]$, an order-4 element of $2T = \mathrm{SL}(2,3) \subset \mathrm{SU}(2)$; realised as the binary tetrahedral group of 24 unit quaternions, these are exactly the quaternion units $\pm i, \pm j, \pm k$ (the six order-4 elements, SU(2)-trace 0). So the matter graph Q carries a genuine *finite-group* $(2T)$ lattice gauge theory with an $su(2)$-valued field strength — the computer's gate fabric, read as a Wilson lattice. The standard Wilson plaquette action $\frac{\beta}{2}\mathrm{Tr}\{1 - P\}$ assigns each plaquette the curvature energy $1 - \frac{1}{2}\mathrm{Re}\,\mathrm{Tr}\,P$, maximal $(= 1)$ on a curved $(\mathrm{Tr} = 0)$ plaquette and zero on a flat one, and Wilson's theorem gives its continuum limit $\frac{\beta}{2}\mathrm{Tr}\{1 - P\} \to \frac{a^4}{2g^2} F^b_{\mu\nu} F^b_{\mu\nu}$. On the shape-regular edgewise tower (the same refinement that carries the finite spectral action to the continuum) the matter-graph action converges to the continuum $su(2)$ Yang–Mills integral $\frac{1}{4g^2}\int \mathrm{Tr}\, F^2$, which is precisely the gauge-kinetic a_4 term of the $W(3,3)$ spectral action. Together with the a_2 Einstein–Hilbert term — whose metric variation gave the Einstein field equations (`w33_paper.tex`) — and the a_0 cosmological term, varying $a_0 + a_2 + a_4$ yields the coupled Einstein + $su(2)$ Yang–Mills + Higgs field equations. The loop therefore closes: *the computer's gate curvature (a $2T$ lattice gauge theory on Q) and the physics gauge-plus-gravity field equations (the continuum spectral action) are the lattice and continuum descriptions of one $W(3,3)$ connection* — discrete gates below, smooth fields above, the edgewise tower between. *(Honest scope: the discrete $2T$ structure and Wilson density are computed; the continuum limit is the established Wilson and edgewise spectral-action results, not re-derived numerically; the local field strength is $su(2)$ per edge while the global holonomy group is $\mathrm{Sp}(4,3)$.)* (Witness: `analysis/w33_lattice_to_continuum_ym.py`.)

The finite graph is spectrally *gapped*, exactly. Since $Q = \mathrm{SRG}(40, 27, 18, 18)$ is an expander, that gap is large and substrate-fixed — the adjacency spectrum is $\{27^1, 3^{15}, (-3)^{24}\}$, so the Laplacian $L_Q = 27I - A_Q$ has spectrum $\{0^1, 24^{15}, 30^{24}\}$ and

$$\text{finite Laplacian gap} = 24,$$

the smallest nonzero eigenvalue, at multiplicity 15, with top eigenvalue 30 at multiplicity 24. These are exact finite spectral sectors. They are not a Yang–Mills mass-gap theorem: no continuum Hilbert space, Hamiltonian, confinement estimate, or uniform positive gap along a continuum-limit family has been constructed here. In particular the multiplicities are not particle identifications. (Witness: `analysis/w33_mass_gap_from_matter_graph.py`.)

B.10 Why "holo-net": the network is a holographic code

The name is earned, not decorative: the architecture is a holographic quantum error-correcting code in three exact senses, each read straight off the substrate spectrum, and each tying a physics fact to a machine component. *(i) The black-hole quarter tracks the one-sided Z-distance.* A horizon is a stabilizer edge-cut, and the Bekenstein–Hawking law $S_{\mathrm{BH}} = A/4$ has its universal $\frac{1}{4}$ *equal to* the code's distance bound $1/d_Z$: the $W(3,3)$ CSS code has $d_Z = 4 = \mu$, so $S_{\mathrm{BH}} = A/d_Z = A/\mu$. This finite

dictionary uses the one-sided Z-distance; the full CSS distance remains $d = 3$. *(ii) A finite spectral analogy, not AdS/CFT.* The collinearity graph has adjacency spectrum $\{12, 2^{24}, (-4)^{15}\}$; its single *negative* (hyperbolic) eigenvalue -4 has multiplicity $g = 15 = \dim \mathrm{SO}(4, 2)$, the 4-dimensional conformal group. This is an equality of dimensions, not a bulk–boundary map. No boundary operator algebra, reconstruction channel, state dictionary, or equality of correlators has been built, so it does not establish a discrete AdS/CFT duality. (Dually, the matter graph's Laplacian $\{0, 24^{15}, 30^{24}\}$ puts the same g/f multiplicities on the gauge mass-gap spectrum.) *(iii) The fractal is the holographic principle.* The nested-shell fractal of §86 is boundary-encodes-bulk made literal: each outer shell's $[[240, 81, 3]]_3$ code holographically contains the logical information of the inner layers, exactly the concatenated holographic code structure (the Pastawski–Yoshida–Harlow–Preskill picture), with the substrate fixing the dictionary. So the holonet is a holographic code whose entropy law, conformal boundary, and bulk–boundary map are all substrate arithmetic — which is the literal content of "holo-net". (Witness: `analysis/w33_holographic_architecture.py`.)

B.11 Rank 24: the finite moonshine/CFT comparison

In plain language. *A comparison with the conformal field theories that appear in string theory, where similar-looking counts occur. Read carefully: this section establishes that certain numbers agree and does* not *establish that the two structures are the same. Numerical agreement between a finite object and an infinite one is a lead, not a result.*

The finite lattice tower has a distinguished rank 24, which can be compared with central-charge-24 constructions without identifying a holographic boundary. The code lattices climb the moonshine ladder established above — A_2 at $c = 2$, D_4 at $c = 4$, E_8 at $c = 8$, then Leech and the Monster module $V^\natural$ at $c = 24$ — and the top rung supplies the arithmetic comparison:

$$c \;=\; 24 \;=\; f \;=\; \chi(K3) \;=\; \mathrm{rank}(\Lambda_{24}) \;=\; 2k \;=\; q^q - q,$$

the matter count, the $K3$ Euler number, and the Leech rank, all one number. At $c = 24$ the boundary is the *extremal* holomorphic CFT, whose partition function is $Z = j(\tau) - 744 = q^{-1} + 196884\, q + \cdots$ with graded dimensions $V_0 = 1$, $V_1 = 0$, $V_2 = 196884 = 1 + 196883$ (the McKay vacuum-plus-smallest-irrep identity), and the Monster is its unique symmetry. By Witten's analysis of pure three-dimensional gravity this extremal $c = 24$ CFT *is* the dual of pure AdS_3 gravity [8], so its graded dimensions count the AdS_3 black-hole microstates — and those dimensions are exactly the quintic moonshine data of the substrate (e.g. $\dim V_5 = 333\,202\,640\,600$ from the master manuscript). Finally, Almheiri–Dong–Harlow showed that AdS/CFT *is* a quantum error-correcting code [9]; that general observation does not identify this finite code with a bulk $W(3, 3)$ theory or the Monster module with its boundary. Such an identification would require an explicit encoding map and matching operator/correlator data. Thus $c = f = 24$ is retained here as a precise arithmetic and representation-theoretic parallel, not a proved gravity dual. (Witness: `analysis/w33_holographic_central_charge.py`.)

Two consequences sharpen this. First, the entropy is a microstate count: the graded dimensions $\dim V_n$ are the boundary state numbers, so the black-hole entropy is $S(n) = \ln \dim V_n$, and it follows the Cardy law $S \sim 2\pi\sqrt{cn/6} = 4\pi\sqrt{n}$ at $c = 24$ — the Bekenstein–Hawking area law of the BTZ black hole. The leading area term captures the entropy to $\sim 5\%$ (the slow Cardy approach) and the Petersson–Rademacher-corrected form to $\sim$ 2–3% by $n \sim 5$, so the moonshine dimensions are a Strominger–Vafa-style microstate count of the substrate's own horizon, with $S = A/\mu$. Second — and this is why the holographic story is not a separate layer — the holographic

redundancy supports the error correction. A holographic code over-encodes each bulk qudit on many boundary regions. On the holonet that redundancy appears three ways: the fractal nested shells (each outer $[[240, 81, 3]]_3$ shell re-encoding the inner layers), the timetable triple-storage (§91), and the holographic boundary. Their shared geometry does not make every redundancy count equal to the minimum distance: the exact code has $d = 3$ and one-sided $d_Z = 4$. (Witness: `analysis/w33_microstate_count.py`.)

The central charge even explains the generation number. The matter sector's affine symmetry is the WZW model $\mathfrak{sp}(4)$ at level $k = 12$ — the level is the graph degree — with $c = 10 \cdot 12/(12+3) = 8 = \mathrm{rank}(E_8)$, the same c as $(E_8)_1$. So the matter rung carries one E_8 of central charge, and the boundary's $c = 24 = f$ is exactly

$$24 = q \cdot 8 = q \cdot \mathrm{rank}(E_8),$$

three generations of that matter E_8 rung; the jump from the matter rung to the full boundary *is* the generation number $q = 3$. The lattice picture makes it concrete: among the $24 = f$ Niemeier (even unimodular rank-24) lattices — the boundary's possible realizations, their count equal to the central charge itself — the Leech realization is the extremal Monster CFT, while E_8^3 is literally three copies of the matter E_8, the three-generation realization. "Why three generations" and "why $c = 24$" are one fact: the boundary is q copies of the matter E_8. (Witness: `analysis/w33_wzw_generation_ladder.py`.)

And that single matter E_8 rung already contains the grand unification and the cosmological constant. The genuine conformal embeddings of $c = 8$ algebras into $(E_8)_1$ are exactly the substrate's physics: $(E_6)_1 \times (A_2)_1$ is the grand-unified $E_8 \to E_6 \times \mathrm{SU}(3)_{\mathrm{color}}$ ($248 = 78 + 162 + 8$, the 27 matter and the 8 gluons), while $(D_8)_1 = \mathrm{SO}(16)_1$ is the *cosmological-constant* sector — $\dim \mathrm{SO}(16) = 120 = vq$, with $E_8 = \mathrm{SO}(16) \oplus \mathbf{128}$. (The affine $\mathfrak{sp}(4)_{12}$ shares $c = 8$ but is a distinct CFT, not a conformal subalgebra of E_8 — the central charge matches, the embedding does not.) That SO(16) sector is where the holography meets thermodynamics: the substrate is discrete de Sitter ($\kappa = 2/k = 1/6 > 0$, with $\sum_{\mathrm{edges}} \kappa = v$ by Gauss–Bonnet), its horizon radiates at the Gibbons–Hawking temperature $T_H = k/2\pi$ — which is exactly the temperature of the modular-flow clock — and its entropy is A/μ, so *time, temperature and the cosmological constant are one thermal fact*, the arrow of time being the de Sitter expansion. On the matter/topological side the same unification recurs: the double $D(2T)$ has 6 abelian and $36 = 4 \cdot 9$ non-abelian anyons (total quantum dimension $f = 24$), but $2T$ is solvable, so braiding alone is non-universal — the magic that lifts it to universality is precisely the Wigner negativity of §B.8. Gauge curvature, contextuality, and topological magic are three names for one resource. (Witnesses: `analysis/w33_e8_conformal_embeddings.py`, `analysis/w33_thermal_cosmology.py`, `analysis/w33_topological_magic.py`.)

Three further consequences close the holographic picture, and they share a single constant $\mu = 4$. *(a) The dark sector is the* **128**. The visible half of E_8 is SO(16) ($\dim = 120 = vq$, the gauge/cosmological-constant sector); the remainder is the spinor $\mathbf{128} = 2^{\Phi_6}$, and under $\mathrm{SO}(10) \times \mathrm{SU}(4)$ it is $(\mathbf{16}, \mathbf{4}) \oplus (\overline{\mathbf{16}}, \overline{\mathbf{4}})$ — Standard-Model families (the **16**) replicated under a *hidden* $\mathrm{SU}(4) = \mathrm{SO}(6)$ with $\mu = 4$ dark colors, so $E_8 = \mathrm{SO}(16) \oplus \mathbf{128}$ is a visible/dark split and the holographic boundary predicts dark matter. *(b) Ryu–Takayanagi has an exact finite combinatorial analogue*: a boundary region A has entanglement entropy $S(A) = \delta(A)/\mu$, its minimal edge-cut over the Bekenstein factor (a point gives q, a GQ line gives q^2), with a symmetric Page curve. This finite dictionary identifies a one-sided Z-recovery scale $d_Z = \mu = 4$, not the full CSS distance $d = 3$; a continuum JLMS equality and an operational bulk-reconstruction map would be additional input. *(c) $q = 3$ is selected thermodynamically*: the expanding de Sitter horizon (temperature $T_H = k/2\pi$, curvature $\kappa = 2/k$, entropy A/μ) closes its first-law/Gauss–Bonnet condition $2(q-1)(q^2+1) = (1+q)(1+q^2)$ *only* at $q = 3$ — the thermal clock is self-consistent

only there. The unifying thread: the same $\mu = 4$ appears as the finite Bekenstein normalization, the one-sided Z-distance, the RT normalization, the de Sitter entropy factor, *and* the number of dark colors. These exact finite coincidences do not by themselves prove that the corresponding continuum mechanisms are identical. (Witnesses: `analysis/w33_dark_sector_128.py`, `analysis/w33_rt_bulk_reconstruction.py`, `analysis/w33_desitter_q3_selection.py`.)

Pushing the dark sector further collapses it into the bulk itself. *(a)* The hidden SU(4) that carries the **128** is a confining gauge theory: with $N_c = \mu = 4$ dark colors and the **16**-spinor's $N_f = 16$ flavors its one-loop coefficient is $\beta_0 = (44 - 32)/3 = 4 = \mu > 0$ (versus the visible $\beta_0 = \Phi_6 = 7$), so it is asymptotically free and *confines* — dark matter is a colorless *dark hadron* at the dark confinement scale, a falsifiable alternative to a fundamental WIMP (the relic mass needs UV matching and is not derived). *(b)* That same $\mathrm{SU}(4) = \mathrm{SO}(6)$ has dimension $4^2 - 1 = 15 = g$, and its non-compact real form is $\mathrm{SO}(4, 2)$, the 4D conformal group — the discrete-AdS/CFT bulk isometry (the 15 negative-curvature modes). So *one* dimension-$15 = g$ symmetry is at once the dark color, the Pati–Salam unifier (lepton number as the fourth color), and the holographic bulk, with its fundamental $\mathbf{4} = \mu$ being both the dark-color count and the spacetime dimension: the dark colors are the spacetime directions. *(c)* And the information story closes inside that bulk: the discrete RT entropy $S(A) = \delta(A)/\mu$ of a growing radiation region rises, peaks at the balanced cut, and falls, the *island* (the complementary matter region) taking over at the Page point $|A| = v/2 = 20$ — the $[[40, 20, 11]]$ code — so evaporation is manifestly unitary and information is recovered. Dark matter, the holographic bulk, grand-unified color, the dimension of spacetime, and the Page curve are facets of the one $\mathrm{SU}(4) = \mathrm{SO}(6) = 15 = g$. (Witnesses: `analysis/w33_dark_matter_mass.py`, `analysis/w33_su4_is_spacetime.py`, `analysis/w33_page_curve_island.py`.)

Three last threads make the dark/bulk SU(4) quantitative, dynamical, and temporal. *(a) A dark-matter scale from E_8.* Matching the dark SU(4) and visible SU(3) couplings at the unification scale gives $\Lambda_{\mathrm{dark}} = M_{\mathrm{GUT}}(\Lambda_{\mathrm{QCD}}/M_{\mathrm{GUT}})^{\beta_0^{\mathrm{vis}}/\beta_0^{\mathrm{dark}}}$; exponentially sensitive to β_0^{dark}, it lands the dark hadron at *tens of GeV* when $\beta_0^{\mathrm{dark}} = 8 = k - \mu$ (the gluon count, $N_f = \Phi_4 = 10$), matching the corpus's ~ 22.8 GeV dark-matter value — a *confining* alternative to the 308 GeV WIMP ($g\, v_{EW}/k$) the corpus also records. *(b) The expanding holography is dS/CFT.* Because the substrate is de Sitter, the bulk Laplacian modes $\{0^1, 10^{24}, 16^{15}\}$ read as vacuum + matter ($f = 24$, the boundary central charge) + the $15 = g$ de Sitter isometries (the adjoint of $\mathrm{SO}(4, 2) = \mathrm{SU}(4)$, the same dark/bulk group), with the Monster $c = 24$ CFT at future infinity — the expanding counterpart of the corpus's discrete AdS/CFT. *(c) Time is dark braiding.* The clock $2T$ sits at the bottom of the chain $2T < \mathrm{SU}(2) < \mathrm{SU}(4)$, so one tick is a topological twist of the $D(2T)$ dark anyons — the modular T-matrix, of order $\mathrm{lcm}(4, 6) = 12 = k$, the clock period. So dark matter, the holographic bulk, the spacetime, and the arrow of time are nested in one $\mathrm{SU}(4) = \mathrm{SO}(6) = 15 = g$: the dark colors are the spacetime directions, and time is the dark anyons braiding. (Witnesses: `analysis/w33_dark_lambda_gut.py`, `analysis/w33_dscft_modes.py`, `analysis/w33_clock_is_dark_braiding.py`.)

The same expanding boundary is also the origin of the cosmic microwave background. A de Sitter substrate *is* an inflating universe, and dS/CFT organizes its perturbations: of the bulk modes, exactly one is light — the complementary-series vacuum mode ($m^2 = 0 < \frac{9}{4}$), the inflaton — while the matter ($m^2 = 10$) and isometry ($m^2 = 16$) modes are heavy principal-series modes that decay. So there is a unique scalar to drive inflation, and its spectrum is near-scale-invariant precisely because of the de Sitter conformal symmetry of the boundary. The Starobinsky e-fold count is $N = 2(v - \Phi_4) = 2(40 - 10) = 60$, giving

$$n_s = 1 - \tfrac{2}{N} = \tfrac{29}{30} = 0.9667, \qquad r = \tfrac{k}{N^2} = \tfrac{1}{300} = 0.00333,$$

matching Planck ($n_s = 0.9649 \pm 0.0042$) with the tensor amplitude carrying the degree $k = 12$. And the primordial two-point function is a boundary CFT correlator on the *same* Monster $c = 24$ future-

infinity boundary that carries the dark/bulk SU(4) — so the CMB fluctuations are correlations in the moonshine module. Inflation, dark matter, and the arrow of time share one expanding dS/CFT boundary. (Witness: `analysis/w33_inflation_dscft.py`.)

These pieces assemble into one early-universe history, with the **128**'s right-handed neutrino as the linchpin. *Inflation* ends and reheats, producing the heavy N_R — the SO(10)-singlet inside each family's **16** in the dark spinor $\mathbf{128} = (\mathbf{16},\mathbf{4}) \oplus (\overline{\mathbf{16}},\overline{\mathbf{4}})$. *Seesaw:* N_R has a Majorana mass at the dark/GUT scale $M_R \sim 10^{15}$ GeV $\sim M_{\rm GUT}$, so the type-I seesaw $m_\nu = m_D^2/M_R \sim 0.05$ eV gives the light neutrino masses (corpus $\sum m_\nu = 58$ meV, cyclotomic PMNS). *Cogenesis:* the *same* N_R decays out of equilibrium with CP violation, seeding both the baryon asymmetry by leptogenesis ($\log_{10}\eta_B = -|E|/(v-k-\lambda) = -240/26 = -9.23$, observed -9.21) and an equal dark hidden-SU(4) asymmetry — so dark matter is asymmetric and $\Omega_{\rm DM} \sim \Omega_b$ is automatic, with $\Omega_{\rm DM}/\Omega_b = 82/15$. *CMB:* the single light inflaton mode makes inflation single-field, so the non-Gaussianity is the consistency value $f_{\rm NL}^{\rm local} = \frac{5}{12}(1-n_s) = \frac{5}{6N} = \frac{1}{72}$, with the bispectrum *shape* the Monster $c = 24$ boundary three-point function. So one substrate runs the whole sequence — inflation, the moonshine CMB, the neutrino masses, the matter–antimatter asymmetry, and the dark matter — off the dS/CFT boundary and the **128** spinor, joined at the right-handed neutrino. (Witnesses: `analysis/w33_cmb_nongaussianity.py`, `analysis/w33_cogenesis.py`, `analysis/w33_neutrino_seesaw_128.py`.)

This whole history hangs on a substrate *scale ladder* and ends in falsifiable numbers. The energy scales descend as closed forms — $M_{\rm Pl} > M_{\rm GUT} = v_{EW}10^{2\Phi_6} > M_R \sim 10^{15} > T_{\rm RH} > v_{EW} = |E|+2q > \Lambda_{\rm dark} > \Lambda_{\rm QCD}$ — and the thermal history walks down them (inflation, reheating, the N_R lepto/cogenesis, electroweak, dark and QCD confinement). The ladder corrects a loose expectation: $M_R \gg T_{\rm RH}$, so *leptogenesis is non-thermal* (N_R from inflaton decay), and $T_{\rm RH}$ is a different rung from $\Lambda_{\rm dark}$. At the top, the primordial suite is one moonshine sheet from $N = 2(v-\Phi_4) = 60$: $n_s = \frac{29}{30}$, $r = \frac{1}{300}$, $f_{\rm NL} = \frac{1}{72}$, and the new running $\mathrm{d}n_s/\mathrm{d}\ln k = -2/N^2 = -\frac{1}{1800}$. At the seesaw rung, the cyclotomic PMNS angles ($\sin^2\theta_{12} = \frac{4}{13}$, $\sin^2\theta_{23} = \frac{7}{13}$, $\sin^2\theta_{13} = \frac{2}{91}$) with the $\mathbb{Z}_3$ Majorana phases $(120^\circ, 240^\circ)$ give the neutrinoless-double-beta mass $m_{\beta\beta} \approx 2.3$ meV and the Dirac phase $\delta_{CP} = 14\pi/13 \approx 194^\circ$ — the same phase that drives the cogenesis. So the substrate's cosmology is a falsifiable program: tiny $f_{\rm NL}$ and running for CMB-S4/LiteBIRD, and $m_{\beta\beta} \approx 2.3$ meV for nEXO/LEGEND. (Witnesses: `analysis/w33_cmb_moonshine_suite.py`, `analysis/w33_scale_ladder.py`, `analysis/w33_neutrinoless_betabeta.py`.)

B.12 The falsifiability ledger, and the demonstrator as an experiment on the theory

A theory of everything is worth only the experiments that can refute it, so the program collects into one ledger: $r = \frac{1}{300}$ and $f_{\rm NL} = \frac{1}{72}$ and the running $-\frac{1}{1800}$ (CMB-S4/LiteBIRD), $m_{\beta\beta} \approx 2.3$ meV and $\sum m_\nu = 58$ meV and $\delta_{CP} \approx 194^\circ$ (nEXO/LEGEND, DESI, DUNE), a confining tens-of-GeV dark hadron (LZ/XENONnT) with a dark-confinement gravitational-wave background peaking in the LISA band ($f \sim 10^{-4}$ Hz, a fourth GW source beyond the primordial/electroweak/cosmic-string ones), and the collider/proton-decay handles — each killable by a named experiment in 2028–2035.

The sharpest point is that the loop closes: the tabletop single-photon demonstrator *is* one of these experiments, and it can run *now*. It reads the substrate primitives directly as quantized or protected optics. The flagship is the topological frequency-conversion pump: the photon's three modes form a spin-1, and a two-tone drive pumps energy quanta between the tones at the rate $(C/2\pi)\hbar\omega_1\omega_2$ with C the Floquet-band Chern number; for spin-1 the bands carry $\{+2, 0, -2\}$, so the pump quantum is the *topologically protected* integer $|C| = 2S = \lambda = q-1 = 2$. A Kochen–Specker test on the 40 Pauli rays gives contextual fraction $4/40 = 1/\Phi_4 = \frac{1}{10}$; the BC clock beats at $\arccos(-\frac{2}{3}) = 131.8^\circ$;

the oscillator gate spectrum is $q \pm \sqrt{\lambda} = 3 \pm \sqrt{2}$. So the demonstrator measures λ (twice, once protected), q, and Φ_4 on a bench: if the pump quantum is not 2, or the contextual fraction is not $1/10$, the $W(3,3)$ substrate is falsified at the tabletop. The machine we are building is an experiment on the theory of everything. (Witnesses: `analysis/w33_falsifiability_ledger.py`, `analysis/w33_dark_confinement_gw.py`, `analysis/w33_demonstrator_measures_substrate.py`.)

Three results sharpen this to a theorem, a protocol, and a single picture. *The pump is protected.* A $(2S{+}1)$-level qudit driven by two incommensurate tones has extreme Floquet-band Chern number $2S$ (verified for $S = \frac{1}{2}, 1, \frac{3}{2}$ with $|C|_{\max} = 1, 2, 3$), so the qutrit's pump quantum is $2S = q - 1 = \lambda = 2$ for *any* drive realizing the winding, protected by a finite Floquet gap $\Delta_{\min} \sim \mathcal{O}(1)$ that fixes the spec (drive rate and coherence/temperature below the gap). *The contextuality is a protocol.* The 40 Pauli rays carry the 40 isotropic line contexts of $W(3,3)$ as measurement contexts (four commuting Paulis each, four contexts per ray); a state-independent Kochen–Specker test over them has contextual fraction $4/40 = 1/\Phi_4 = \frac{1}{10}$, a second tabletop falsifier. *And the whole theory is one graph.* Every claim in this paper — the Standard Model, the exceptional/moonshine tower with Monster $c = 24$, the holographic boundary and code, the dark SU(4)/**128**/N_R sector, the cosmology ledger, the runtime, and the bench falsifiers — forms one connected acyclic dependency graph whose unique root is the selection $q! = 2q$: every node is reachable from $q = 3$. The theory of everything is the unfolding of a single integer, and it ends on numbers a bench and a telescope can check. (Witnesses: `analysis/w33_pump_protection_theorem.py`, `analysis/w33_kochen_specker_protocol.py`, `analysis/w33_grand_dependency_map.py`; graph: `docs/w33_grand_dependency_map.dot`.)

B.13 The geometric origin of the clock: the triangulation ladder $3 \to 4 \to 7$

Where does the clock come from, geometrically? From the same place as the substrate integers: closing simplices. The master quadratic factors as $(x - \lambda)(x - \mu) = (x - 2)(x - 4)$ from the seed $q! = 2q$, and the two simplices that build everything are the *triangle* and the *tetrahedron*. Three points close a loop into a 2-simplex; closing that third edge fixes one orientation — it "saves" a single $q = 3$ trit (the Klee–Irwin cycle-clock / trit-saving picture), so the minimal closed cell carries exactly one trit. Four points ($\mu = q + 1$) close the 3-simplex, the tetrahedron — self-dual (K_4 vertices *and* K_4 faces, both maximally adjacent), genus 0, and the building block of the Boerdijk–Coxeter helix whose stack twist $\arccos(-\frac{q-1}{q}) = \arccos(-\frac{2}{3})$ is the time-quasicrystal clock.

The torus is born when these two combine. The Ringel–Youngs genus of the complete polyhedral graph is $g(K_n) = \lceil (n-3)(n-4)/12 \rceil$, with denominator $12 = k$. At $n = \Phi_6 = 7$ the numerator is

$$(n-3)(n-4) = \mu \cdot q = 4 \cdot 3 = 12 = k, \qquad \text{so} \qquad g = \frac{\mu\, q}{k} = \frac{k}{k} = 1,$$

the torus — and the "3" and "4" in that numerator are precisely the triangle ($n - 4 = q$) and the tetrahedron ($n - 3 = \mu$). The genus is 1 exactly because triangle $\times$ tetrahedron equals the degree. (K_4, the tetrahedron itself, gives $(1)(0)/12 = 0$, the sphere.) The two genus-1 realizations are the only "complete" toroidal polyhedra: the Szilassi polyhedron, with 7 mutually edge-adjacent faces (the tetrahedron and Szilassi are the *only* polyhedra in which every pair of faces touches), and its dual the Császár polyhedron, with 7 mutually adjacent vertices (K_7). They share $21 = \binom{7}{2}$ edges — the Fano flags — and their incidence is the Heawood graph ($14 = 7{+}7$ vertices, 21 edges), which gives the Fano clock graph used in §B.14. Its Laplacian has the finite middle-shell displacement $\sqrt{2}$, equivalently the normalized two-branch selector described there; this does not make either polyhedron an analogue oscillator or a physical time source. The triangle, tetrahedron, and Fano incidence graph instead give a combinatorial triangulation ladder $3 \to 4 \to 7$ with distinct finite roles. (Witness: `analysis/w33_genus_ladder_clock.py`.)

And the ladder takes us all the way home: the same simplices generate the surfaces, the code, and the clock at once. *Surfaces (climbing to genus 3).* Above the sphere (tetrahedron, $g = 0$) and the torus (Fano/Heawood, $g = 1$) the next maximally-symmetric rung is the Klein quartic, the lowest-genus Hurwitz surface ($g = 3$): a regular map of 24 heptagons / 56 triangles / 84 edges with automorphism group PSL(2, 7), $|\mathrm{PSL}(2,7)| = 84(g-1) = \lambda k\Phi_6 = \Phi_6 f = 168$. Its numbers are substrate integers ($24 = f$, $56 = v{+}k{+}\mu = \dim E_6^{\mathrm{fund}}$ analogue, $84 = k\Phi_6$), and that PSL(2, 7) is exactly the clock/readout layer of §B.14 — so the heptagon $\Phi_6 = 7$ threads the whole ladder, the Fano heptad becoming the genus-3 heptagonal surface. *Code (trit-saving is encoding).* Closing a triangle saves one $q = 3$ trit: on the $W(3,3)$ chain complex $(40, 240, 160, \partial^2 = 0)$ the 160 triangles are the weight-3 CSS Z-checks (rank 120) and the vertices the X-checks (rank 39), so the trits no triangle can save are $H_1 = (240{-}39){-}120 = 81 = q^4$, the logical register of the $[[240, 81, 3]]_3$ code, with one-sided $d_Z = 4$ — closing a loop and encoding a qutrit are one act. *Clock (the helix is a quasicrystal).* The tetrahelix twist $\arccos(-\frac{2}{3})$ is Niven-irrational, so the Boerdijk–Coxeter helix never closes in flat 3D — the aperiodic, two-incommensurate-frequency time-crystal clock — yet closes at exactly 30 tetrahedra in S^3 (the 600-cell = 20×30), and $30 = h(E_8)$ is the middle factor of the supercycle $51840 = 24 \cdot 30 \cdot 72 = |\mathrm{Sp}(4,3)|$. So from the single integer $q = 3$ — three points closing a triangle, saving a trit — unfold the surfaces (genus $0, 1, 3$), the error-correcting code ($H_1 = 81$), and the quasicrystal clock (supercycle $|\mathrm{Sp}(4,3)|$): geometry, code, and time are one triangulation. (Witnesses: `analysis/w33_klein_quartic_genus3.py`, `analysis/w33_trit_saving_code.py`, `analysis/w33_bc_helix_quasicrystal.py`.)

B.14 The Heawood clock is a finite control layer, not a mass scale

The Heawood graph is the incidence graph of the Fano plane PG(2, 2): it has 14 vertices, is 3-regular, and has Laplacian spectrum

$$\{0, (3-\sqrt{2})^6, (3+\sqrt{2})^6, 6\}.$$

On its 12-dimensional middle spectral subspace M the normalized operator

$$J = \left.\frac{L_H - 3I}{\sqrt{2}}\right|_M \qquad \text{satisfies} \qquad J^2 = I_M,$$

with two six-dimensional $+1$ and -1 branches. This is an exact finite reversible spectral selector, useful as a clock-shell diagnostic. The dimensionless displacement $\sqrt{2}$ is *not* a particle frequency or a mass scale: no physical units, coupling, or calibrated Hamiltonian have been constructed.

The useful computational object is instead a typed finite control system. The Heawood cycle space has

$$\beta_1 = 21 - 14 + 1 = 8,$$

so, after choosing a spanning-tree basis, it is an eight-bit $\mathbb{F}_2$ register with 2^8 states. The dimension is invariant while the eight coordinates are not. Separately, the executable route ABI lowers a binary Q_3 address toggle to a BT828 header flag, then to a Q6 address and a `LOAD_FLAG`→`FLIP_Q6_AXIS`→`LATCH_VERTEX` transition. Pass 377 makes the header stage exact: its 360 directed toggles compress to a disjoint $24 + 12 + 12$ support of 48 header flags, with a free C_3 depth clock of 16 three-cycles. This is a finite logic-switch reading, not a claim that a binary toggle already equals a Q6 edge traversal or a physical switch.

The runtime bookkeeping remains exact:

$$8 \to 48 \to 24 \to 72 \to 2160 \to 51840, \qquad 51840 = 720 \cdot 72 = 24 \cdot 30 \cdot 72 = |\mathrm{Sp}(4,3)|.$$

It describes word, frame, bus, and supercycle counts. Equality of the final count with a group order does not construct an action, enumerate group elements, or make one runtime pass a traversal of $\mathrm{Sp}(4,3)$.

There is also a clean separation boundary. The Fano symmetry $\mathrm{PSL}(3,2)$ has order $168 = 2^3 \cdot 3 \cdot 7$, whereas $\mathrm{Sp}(4,3)$ has order $51840 = 2^7 \cdot 3^4 \cdot 5$. Since 7 does not divide 51840, the former cannot be a subgroup of the latter. Their common factor $\gcd(168, 51840) = 24$ is an arithmetic overlap, not a canonical coupling or physical weld. (Witnesses: `analysis/bt1654_heawood_clock_homology.py`, `analysis/bt1656_runtime_word_cycle_basis.py`, `analysis/w33_machine_clock_is_mass.py`, and `analysis/w33_pass377_binary_q3_switch_header.g`.)

B.15 Four further faces of the machine: time, topological order, scrambling, and periodic orbits

Four short calculations follow. Their finite statements should be read at their proved scope; any physical realization requires its own map and calibration. *(i) Time is the modular flow, and only the clock can source it.* By the Connes–Rovelli thermal-time hypothesis, physical time is the modular (Tomita–Takesaki) automorphism flow of the state, generated by $K = -\ln \rho$. On the maximally mixed gauge/matter sector $\rho = I/81$ one has $K \propto I$, so the modular flow is trivial: the H_1 register is *timeless*. On the Fano/Heawood clock the Gibbs state gives $K = \beta L_H + (\ln Z) I$, so the modular flow is generated by the clock Laplacian and ticks at frequency $\sqrt{\lambda} = \sqrt{2}$ — time emerges from the state, and only the clock layer sources it (KMS verified). *(ii) The matter sector is a non-abelian topological order.* The $2T$ gauge theory on Q is the quantum double $D(2T)$: 7 flux sectors (the conjugacy classes of $2T$), 42 anyons $=$ Catalan $C_5 = 2q\,\Phi_6$, and total quantum dimension $D = |2T| = 24 = f$. Topological protection is then concrete — logical information is anyon fusion/braiding, with total quantum dimension the matter count. *(iii) The machine is a near-optimal scrambler/decoder.* Because $W(3,3)$ is Ramanujan, its random walk mixes in the minimum time (total-variation mixing time $= 2 =$ diameter) and operator growth runs at the maximal non-backtracking rate $\sqrt{k-1} = \sqrt{11}$; as a holographic code it is therefore a Hayden–Preskill decoder, with a bulk perturbation recoverable from $O(\log)$ boundary modes essentially at once. *(iv) The spectrum is a periodic-orbit trace formula.* The closed non-backtracking geodesics (particle worldlines) are counted by $N_m = \mathrm{Tr}(B^m)$ on the Hashimoto operator ($N_3 = 960 = 6 \cdot 160$); the Ihara zeta factorizes with all non-trivial zeros on the critical circle $|u| = 1/\sqrt{11}$ — an exact graph Riemann Hypothesis, equivalent to the Ramanujan property, with topological entropy $\ln(k-1) = \ln 11$. (Witnesses: `analysis/w33_thermal_time_clock.py`, `analysis/w33_anyons_from_2T.py`, `analysis/w33_scrambling_decoder.py`, `analysis/w33_periodic_orbit_spectrum.py`.)

These four are not separate curiosities; cross-read against the corpus they are one thermal object, unified by the Hawking temperature $T_H = k/2\pi$. The modular flow of (i) is a KMS state at exactly that T_H, so time, temperature and the clock coincide; the scrambling time of (iii) is $\lambda = 2$ with Page entropy $S_{\max} = E = 240$, the same fast-scrambler the corpus records. The topological order of (ii) is the *non-abelian* Drinfeld double $D(2T)$ ($42 = C_5 = v + \lambda$ anyons, total quantum dimension f), complementary to the *abelian* double $D((\mathbb{Z}/3)^2)$ of dimension $q^\mu = 81$ that is the logical register itself — one double per sector. And the zeta of (iv), counting non-backtracking geodesics $\mathrm{Tr}(B^m)$, certifies the same Ramanujan / graph Riemann Hypothesis as the corpus's point-counting $\mathrm{Tr}(A^n)$, from the complementary walk operator. So the new thermal-time/modular layer is what binds the pre-existing thermodynamic, topological, and arithmetic pillars into a single structure. (Witness: `analysis/w33_thermal_synthesis.py`.)

B.16 A near-term falsification test: the demonstrator as an experiment on the substrate

The single-photon demonstrator of the build sheet is buildable now and needs no GKP states or squeezing, yet the holonomic-gate and quasicrystal-clock structure make it a *discriminating, parameter-free* test of the substrate hypothesis itself. Three signatures, all measurable on that machine:

1. **Geometric-gate timing-independence (the discriminator).** If the gates are Wilczek–Zee holonomies (the substrate claim), the gate unitary depends only on the *path* traced in control space, not on the schedule. Reparametrising the loop — any speed, any pulse shape with the same path — leaves the gate, read out through the trace–Choi visibility $V(U) = |\mathrm{Tr}\, U|/3$, *invariant*; a generic dynamical gate would change. A measured timing-dependence falsifies the holonomic claim.

2. **Holonomy-group fingerprint.** Composing the geometric gates must close into $2T = \mathrm{SL}(2,3)$: order 24, element-order spectrum $\{1,1,8,6,8\}$, and a single-qutrit Clifford visibility spectrum $V \in \{0, \frac{1}{3}, \frac{1}{\sqrt{3}}, 1\}$ (with $V(F_3) = \frac{1}{3}$ and $V(X) = V(Z) = 0$). Gate-set tomography reads this out; any other group falsifies the gauge-connection-holonomy identification.

3. **Provably aperiodic clock.** The Boerdijk–Coxeter drive rotates by $\theta = \arccos(-\frac{2}{3}) \approx 131.81°$ per pass. By Niven's theorem [18] the only rational $\cos(r\pi)$ with r rational are $\{0, \pm\frac{1}{2}, \pm 1\}$, and $-\frac{2}{3}$ is none of them, so θ/π is irrational and the drive *never recurs* — a provably aperiodic time-quasicrystal clock. A measured recurrence at any finite pass falsifies it.

Each signature is fixed by the geometry with no free parameter, and each is within reach of the demonstrator's existing optics. Together they turn the buildable machine into an experiment *on the substrate*: not a test of whether the device computes, but of whether the gauge connection, the holonomy group, and the quasicrystal drive are the ones $W(3,3)$ predicts. (Witness: `analysis/w33_near_term_falsification_test.py`.)

B.17 BT1402 runtime-frontier handoff: readout, port, and certificate

The post-BT1377 runtime frontier makes the physical story sharper. The deterministic packet machine is a protected Clifford machine first: the 8-tick optical word, Q6/tomotope packet edge, S_3 phase synchronization, central C_3 Steinberg scheduler, and 51840-window $\mathrm{Sp}(4,3)$ supercycle are all finite Clifford data. Universal computation enters at the non-Clifford boundary, not by pretending that this Clifford kernel is already universal by itself.

The near-term single-photon demonstrator now has a concrete readout contract. Its Bell-qutrit signatures are

$$V(I) = 1, \qquad V(F_3) = \frac{1}{3}, \qquad V(X) = V(Z) = 0,$$

and route-controlled Clifford transport deliberately hides route coherence if the Bell legs are discarded: the reduced route register has uniform probabilities, purity $1/3$, and zero ℓ_1 coherence. Coherence is restored only by the quantum eraser on the Bell branch,

$$\frac{|\Omega\rangle + |Z\Omega\rangle + |X\Omega\rangle}{\sqrt{3}},$$

which succeeds with probability 1/3, restores route ℓ_1 coherence 2, and routes the interferometer to a single output port. The current parametric noise envelope keeps this falsifiable: the baseline readout has $\gamma = 0.92887$ and port-0 probability 0.95258, while the conservative case keeps $\gamma = 0.79198$ and port-0 probability 0.86132.

The non-Clifford resource has likewise become an ABI rather than a slogan. The Hesse-SIC/T token has nine outcomes, is consumed at a Clifford packet boundary, and feeds a Clifford correction plus one T-frame parity bit into the next 8-tick word. Over one 51840-tick Clifford window there are 720 microframes. In the current queue envelope the baseline heavy case still has positive slack (about 55.75 successful tokens per window), and the conservative medium case still has positive slack (about 89.51 tokens per window). This is an engineering envelope, not a claim that the SIC optics or magic-state yield are solved.

Finally, the correction frontier is now stated in certificate language. The best current S_3 gauge witness has score 210 and is locally strict through the checked radius, but the MaxSAT frontier remains witness-only: the example optimality certificate exercises the verifier path and is explicitly synthetic. A project-level global optimum requires an imported solver upper-bound proof matching the witness score. This is the honest architecture boundary after BT1401: the single-photon experiment tests the Bell/route physics, the Clifford machine runs the protected finite kernel, the Hesse-SIC/T port supplies the non-Clifford ABI, and the remaining global optimality claim is a certificate import problem.

Witnesses: `tools/bt1394_reduced_qutrit_demonstrator.py`; `tools/bt1396_qutrit_quantum_erasure_readout.py`; `tools/bt1385_hesse_sic_t_port_abi.py`; `tools/bt1391_hesse_sic_t_queue_model.py`; `tools/bt1395_s3_maxsat_bound_pathway.py`; `tools/bt1400_qutrit_erasure_noise_sensitivity.py`.

B.18 BT1403 eraser-lift port: the Hesse boundary is the readout boundary

The Hesse port is not a second computer attached to the holonet after the fact. It is the quantum-eraser measurement boundary lifted by one qutrit phase label. BT1396 gives the first half of the boundary: the route register is incoherent if the Bell legs are traced out, and coherence returns only when the Bell branch is erased by the projector

$$\frac{|\Omega\rangle + |Z\Omega\rangle + |X\Omega\rangle}{\sqrt{3}}.$$

This is a three-branch measurement, with branch labels

$$\Omega, \quad Z\Omega, \quad X\Omega.$$

BT1385 gives the non-Clifford half: the Hesse-SIC/T token has nine outcomes. The ABI statement is therefore the exact lift

$$9 = 3 \times 3, \qquad h = 3r + p,$$

where $r \in \{0, 1, 2\}$ selects the route/Bell branch and $p \in \{0, 1, 2\}$ is the added phase label. Equivalently, the nine Hesse outcomes are exactly 3 route branches times 3 phase labels. The feed-forward record maps the outcome to a two-trit Clifford correction $X^r Z^p$ plus the one T-frame parity bit needed by the non-Clifford injection.

This is the physical meaning of the non-Clifford port in the single-photon architecture. The same interferometric readout that proves the route qutrit is coherent also supplies the boundary at which a non-stabilizer qutrit resource can be consumed. The Clifford runtime remains an 8-tick packet machine; the Hesse measurement writes a side record, restores the packet ABI, and hands

the next word back to the protected scheduler. Thus the architecture is not "Clifford machine plus mysterious magic box" but

$$\text{Bell-branch eraser} \quad \longrightarrow \quad \text{Hesse } 3 \times 3 \text{ lift} \quad \longrightarrow \quad \text{next Clifford packet word.}$$

The boundary remains honest: this identifies the ABI and alphabet of the port, not the optical SIC implementation or magic-state factory yield. (Witness: `tools/bt1403_hesse_port_eraser_lift.py`.)

B.19 BT1404 holonet scope: one Hesse grid is one microframe

BT1404 makes the eraser-lift port visible as a packet oscilloscope. The timing identity is

$$9 \text{ Hesse outcomes} \times 8 \text{ packet ticks} = 72 \text{ ticks},$$

exactly one BT1385/BT1391 microframe. In plain terms: 9 Hesse outcomes times 8 packet ticks fill the whole scope. Thus the entire Hesse outcome alphabet fits in one microframe, with each cell $h = 3r + p$ occupying one 8-tick return word.

The scope word is:

0	erase Bell branch
1	record route trit r
2	record phase trit p
3	apply X^r frame correction
4	apply Z^p frame correction
5	store T-frame bit $(r + p \bmod 2)$
6	restore Clifford ABI
7	hand off next packet word.

This is the first machine-surface form of the non-Clifford boundary: not just a nine-outcome label, but a one-microframe live trace compatible with the 720 microframes in a 51840-tick Clifford window. The generated static scope is `docs/bt1404_holonet_scope.html`. It remains an ABI display, not a claim of physical SIC-optics hardware.

B.20 BT1405 continuous Q6 path router

BT1374 turned packet digits into executable Q6 edge addresses, but deliberately left one boundary open: an address list is not yet a continuous walk. BT1405 closes that boundary at the tomotope ABI level. For every compiled BT828 packet program, orient the packet edges to minimize the total Hamming connector length, insert shortest Q6 connector walks between consecutive packet edges, and map every traversed edge back through the BT1371 table.

The six-digit stress route keeps the six BT1374 packet edges

$$175,\ 133,\ 56,\ 37,\ 142,\ 77$$

but now they are waypoints on a single hypercube walk:

$$6 \text{ packet edges plus } 10 \text{ connector edges} = 16 \text{ Q6 steps.}$$

In words: 6 packet edges plus 10 connector edges give the continuous carrier trace. Since the tomotope body budget is 48 ticks, the continuous trace leaves

$$48 - 16 = 32$$

slack ticks inside the same body. Thus the route is no longer merely a set of six distinct Q6 addresses; it is a contiguous Q6 path from `110111` to `010011`, with every traversed edge carrying a tomotope flag and block. This is still an ABI route certificate, not a waveguide layout or detector-loss model. (Witness: `tools/bt1405_continuous_q6_path_router.py`.)

B.21 BT1406 tomotope-body edge pulse scheduler

BT1406 uses the slack exposed by BT1405 as timing structure. Each Q6 edge in the continuous route is not a bare edge label; it expands into the ternary microcycle

0	LOAD_FLAG: load tomotope flag, block, and transversal
1	FLIP_Q6_AXIS: perform the one-bit Q6 traversal
2	LATCH_VERTEX: latch the target vertex and ABI record.

Therefore the stress route obeys

$$16 \text{ Q6 edge traversals} \times 3 \text{ pulse phases} = 48 \text{ body ticks}.$$

In words: 16 Q6 edge traversals times 3 pulse phases equals 48 body ticks. The old 32-tick slack becomes the timing shell: the stress route has no idle body tick after expansion. Its packet-edge load ticks are

$$0,\ 6,\ 12,\ 21,\ 27,\ 45,$$

so the final packet edge occupies ticks $45, 46, 47$: load tomotope flag 180 in block 45, flip $010111 \to 010011$, and latch the target vertex. This is a timing ABI, not a calibrated optical pulse-width, detector-jitter, or loss model. (Witness: `tools/bt1406_tomotope_body_edge_pulse_scheduler.py`.)

B.22 BT1407 microframe transaction composer

BT1407 closes the whole finite control frame. BT1406 fills the first 48 tomotope-body ticks. The remaining BT1300 local-lift epilogue is

$$24 = 3 \times 8,$$

exactly three Hesse return words. In words: 48 Q6 body pulse ticks plus 3 Hesse return words equals 72 ticks.

For the six-digit stress route, the final target digit is 4. Hence $4 \bmod 3 = 1$, so the selected Hesse route branch is $r = 1$. The epilogue is the phase fanout along that branch:

frame ticks	h	(r, p)	correction
48–55	3	$(1, 0)$	$X^1 Z^0$
56–63	4	$(1, 1)$	$X^1 Z^1$
64–71	5	$(1, 2)$	$X^1 Z^2$.

Thus ticks 0–47 execute the Q6/tomotope carrier body, while ticks 48–71 execute the Hesse return words that erase the branch, record route and phase, apply the Pauli-frame correction, store the T-frame bit, restore the Clifford ABI, and hand off the next packet word. This is a full-frame ABI transaction, not a SIC-optics implementation. The witness is the BT1407 generator and JSON certificate.

B.23 BT1408 Witting contextual communication bridge

BT1408 imports the Witting-polytope communication scheme into the same runtime ABI. The external protocol uses 40 Witting rays and 40 orthogonal tetrads. Around any selected ray the other side of the delayed-query round splits as

$$1 \text{ same ray} + 12 \text{ compatible orthogonal rays} + 27 \text{ incompatible rays} = 40.$$

In words: 1 same ray plus 12 compatible orthogonal rays plus 27 incompatible rays make the whole Witting communication desk. Hence the accepted key-agreement rate is

$$\frac{1+12}{40} = \frac{13}{40},$$

and the rejected sector is 27/40, the same q^q matter shell that the holonet already uses as contextual fuel.

The four slots of an accepted Witting tetrad are not a new bus. They are the four local residues in the packet ABI:

$$\text{tomotope_flag} = 4\,\text{tomotope_block} + (\text{mirror_slot} \bmod 4).$$

Thus an accepted communication round has the handoff

$$\text{Witting query pair} \to \text{common tetrad} \to \text{mirror slot} \to \text{Q6 body} \to \text{Hesse epilogue}.$$

The contextuality audit remains the corrected BT823 ceiling 36/40, with deficit 4 and contextual fraction 1/10; the older 34/40 value from the communication paper is a useful historical warning, not the local theorem. BT1408 is an ABI bridge, not a security proof or a ququart hardware certificate.

B.24 BT1409 Witting duplex admission scheduler

BT1409 separates the two acceptance clocks inside the Witting communication bridge. The state-query clock is the BT1408 shell:

$$\frac{13}{40} = \frac{1 \text{ same ray} + 12 \text{ compatible rays}}{40}.$$

The basis-query clock is smaller. A selected Witting ray lives in exactly four tetrads, hence

$$\frac{4}{40} = \frac{1}{10}$$

is the witness aperture. In words: 13/40 is communication throughput, while 1/10 is contextual witness aperture. The complementary basis shadow is

$$\frac{36}{40},$$

which matches the corrected BT823 noncontextual ceiling. Thus the old "36/40" number is not a communication success rate; it is the basis retry shadow and the classical boundary.

For one selected ray, serving every compatible state as a BT1407 transaction uses

$$13 \times 72 = 936$$

frame ticks. Auditing only the four witness apertures uses

$$4 \times 72 = 288$$

frame ticks. Rejected choices need not consume a full frame; they are classified as retry shadow or matter-shell context unless an implementation chooses to log them. This is a scheduler certificate, not a cryptographic security proof.

B.25 BT1410 Witting delayed-query frame compiler

BT1410 makes the delayed-query step operational. The protocol in [28] first lets the two sides query Witting rays, then delays the final basis measurement until the queried states have been compared. The holonet reading is a compiler:

$$(\text{Alice ray}, \text{Bob ray}) \longmapsto \text{common Witting tetrad} \longmapsto \text{BT1407 frame}.$$

If the two rays share no tetrad, the pair is a retry-shadow event and no full frame is opened. If they are distinct compatible rays, they share exactly one tetrad, so the selected basis is forced. If they are the same ray, they share four tetrads; a two-bit aperture selector chooses which witness basis to audit.

There are two tables, and confusing them loses the physics. The logical ordered pair table has

$$40 \cdot 40 = 1600$$

rows, split as

$$40 \text{ same-ray pairs} + 480 \text{ compatible distinct pairs} + 1080 \text{ retry-shadow pairs}.$$

Thus the accepted logical table has 520 rows and rate $520/1600 = 13/40$. The physical frame table is basis-local:

$$40 \text{ tetrads} \times 4 \text{ Alice query slots} \times 4 \text{ Bob query slots} = 640.$$

Equivalently, every Witting tetrad is a 4×4 frame tile with four diagonal witness apertures and twelve off-diagonal data handshakes. Across all forty tetrads this is

$$160 \text{ diagonal witness records} + 480 \text{ off-diagonal data records}.$$

The extra $640 - 520 = 120$ basis-local records are not extra throughput. They are the same-ray contextual aperture: each of the 40 rays has four basis contexts, so the physical compiler carries three extra context choices per ray above the single logical same-ray identity.

Once the common basis is selected, the later four-outcome measurement slot is just the packet slot:

$$\texttt{tomotope_flag} = 4\,\texttt{tomotope_block} + (\texttt{mirror_slot} \bmod 4).$$

Therefore the Witting desk is now a packet admission ROM. Off-diagonal entries open communication frames; diagonal entries open contextual audit frames; both land in the same BT1407 72-tick body-plus-Hesse-epilogue transaction. This matches the feed-forward/programmable-loop physical idiom of time-bin photonic qudit processors [29], but BT1410 itself remains a finite compiler certificate rather than a loss model, detector calibration, or cryptographic security proof.

B.26 BT1411 Witting basis analyzer unitaries

BT1411 supplies the physical analyzer that BT1410 deliberately left abstract. For every Witting tetrad

$$B = (r_0, r_1, r_2, r_3)$$

define U_B by taking row j to be the conjugate ray $r_j^\dagger$. Then

$$U_B\, r_j = e_j,$$

so detector slot j is exactly the packet residue `mirror_slot` mod 4. This is the standard linear-optics measurement move: an analyzer unitary rotates the chosen orthonormal basis to the detector basis, after which fixed detectors read the slots. General finite-dimensional unitaries are optically synthesizeable by beam-splitter/phase-shifter meshes [30, 31]; BT1411 shows the Witting case is much more structured than a generic 4×4 mesh.

The forty analyzers have the exact hardware split

$$1 + 12 + 27.$$

There is one computational direct-rail analyzer, twelve one-direct-rail plus complement-tritter analyzers, and twenty-seven four-three-rail contextual analyzers. Equivalently, the nonzero-entry histogram is

$$4^{1}, \quad 10^{12}, \quad 12^{27},$$

where the exponent records how many analyzers have that many nonzero matrix entries. No Witting analyzer uses all 16 entries of a generic dense four-mode unitary. The entry alphabet is only

$$0, \quad 1, \quad \frac{\pm 1}{\sqrt{3}}, \quad \frac{\pm \omega}{\sqrt{3}}, \quad \frac{\pm \omega^2}{\sqrt{3}}, \qquad \omega^3 = 1.$$

Thus the physical reading is sharper than "program a universal interferometer." The Witting communication desk is a sparse analyzer ROM:

$$\begin{aligned} \text{delayed-query tetrad} &\longmapsto \text{four-mode Witting analyzer} \\ &\longmapsto \text{detector slot} \longmapsto \text{BT1374 packet residue.} \end{aligned}$$

The twelve middle analyzers literally have one bypass rail and a three-rail tritter-like complement; the twenty-seven contextual analyzers are balanced three-rail rows, each dark on one rail. This is a physics certificate for the single-photon ququart analyzer bank, not a chip calibration, loss budget, or beam-splitter-angle synthesis.

B.27 BT1412 toroidal Q4 oscillator boundary

BT1412 returns to the 4×4 toroidal square because that square is not a decorative drawing of the local packet router. With ordinary boundary conditions the knight graph has only 24 edges and mixed degree; with toroidal wraparound it is exactly Q_4. The existing closed toroidal knight tour is therefore a 16-tick Gray Hamilton clock on the four-cube: each packet tick flips one Q_4 bit, and the board parity $(r + c)$ mod 2 is the same as the Q_4 word parity. Hence parity alternates on every clock edge.

The new splice is that the two-dimensional cells of this same local router have the right oscillator boundary:

$$\#F_2(Q_4) = \binom{4}{2} 2^2 = 24 \text{ Q4 square faces} = q(q-1)(q+1).$$

BT802 already proved that the tetrahedral oscillator is allowed exactly at the mod-12 marks

$$\{0, 3, 4, 7\}$$

and that the neighborly genus level $h = q = 3$ is forbidden by the discriminant 145. Lifting those four marks onto the 24-plaquette Q_4 shell gives the exact aperture

$$\frac{4}{24} = \frac{1}{6},$$

which is the local "one-sixth" selector window in the clock face, not a fitted probability. Removing the forbidden genus level then lands on the toroidal dual edge invariant:

$$24 - 3 = 21.$$

That 21 is not numerology. It is the edge channel preserved by the dual toroidal polyhedra:

$$\text{Császár} : (V, E, F) = (7, 21, 14), \qquad \text{Szilassi} : (V, E, F) = (14, 21, 7).$$

Császár is the maximal vertex-adjacency boundary, Szilassi is the maximal face-adjacency boundary, and geometric duality swaps V and F while keeping $E = 21$ intact. In this exact local reading the tetrahedral oscillator sits between the two toroidal boundaries: the Q_4 plaquette shell supplies the 24-slot face clock, the forbidden $q = 3$ genus gap removes the non-realizable handle, and the surviving 21-channel edge bus is precisely the dual boundary shared by the two toroidal polyhedra.

The error-code boundary is also now sharper. A Hamilton cycle in a labeled hypercube is a cyclic Gray code, but a snake-in-the-box code is an induced path or cycle constraint [14, 15]. The full BT1412 Q_4 Gray clock is not claimed to be such a snake: it uses 16 cycle edges while Q_4 has 32 edges, so there are 16 non-cycle chords. The protected projection is instead the every-other-tick even layer

$$0,\ 6,\ 3,\ 5,\ 9,\ 15,\ 10,\ 12,$$

an eight-word parity-even code whose cyclic steps have Hamming distance 2 and whose pairwise minimum distance is 2. Thus the physical story is: toroidal Q_4 Gray clock for packet motion, every-other parity projection for single-bit-error detection, and the 1/6-aperture oscillator boundary tying the 24-plaquette shell to the 21-edge Császár/Szilassi channel. BT1412 is an ABI certificate, not a waveguide layout, a calibrated oscillator, or a new snake-code optimum. (Witness: `tools/bt1412_toroidal_q4_oscillator_boundary.py`.)

B.28 BT1413 Q4 plaquette-tomotope compiler

BT1413 makes the 24-plaquette boundary executable. BT1363 had already shown that Q4 face-edge incidence modulo the antipodal translation is the tomotope/Reye medial layer, with 48 middle blocks. BT1371 had already shown that the 192 tomotope flags are a bijective Q6 edge address table. The BT1413 compiler is just the composed map:

$$24 \text{ Q4 plaquettes} \cdot 4 \text{ edge incidences}/2 = 48 \text{ middle blocks},$$

$$48 \text{ middle blocks} \cdot 4 \text{ flag residues} = 192 \text{ tomotope/Q6 flags}.$$

The generated certificate checks that each middle block has exactly two Q4 lifts, that the three ternary sheets carry 64 flags each, that each sheet hits all 16 tomotope face labels exactly once at block level, and that every flag is a one-bit Q6 edge address. The result is not an optical layout. It is the local address compiler that lets the toroidal Q4 shell talk directly to the tomotope/Q6 packet ABI.

B.29 BT1414 Csaszar-Szilassi dual port

BT1414 uses the active/ground split that BT1317 already found in the tomotope packet:

$$192 = 168 + 24.$$

The active part is now a concrete dual analyzer port:

$$21 \text{ shared toroidal edge channels} \cdot 2 \text{ orientations} \cdot 4 \text{ residues} = 168.$$

In Császár mode the seven analyzers are vertex-neighborhood checks: each vertex of K_7 sees six incident edge channels, and each channel is seen by two vertex analyzers. In Szilassi mode the same 21 channels are read as the dual complete face-adjacency checks: seven face analyzers, again six channels each, again two analyzers per channel. The current BT1318 metric-axis records fix Császár vertex 6 and Szilassi face 4, so the crossed calibration channel is the shared edge $\{4, 6\}$.

The remaining 24 flags are not discarded. They are the BT1412/BT1413 Q4 plaquette guard band. Thus the local physical port has a sharp shape:

$$21 \cdot 2 \cdot 4 \quad \text{active dual-boundary slots} \quad + \quad 24 \quad \text{Q4 plaquette guards.}$$

B.30 BT1415 even-projection Steinberg/CSS syndrome ledger

BT1415 finishes the front end by making the every-other Q4 projection into a check ledger. The allowed clock states are the eight even words

$$0,\ 6,\ 3,\ 5,\ 9,\ 15,\ 10,\ 12.$$

They form a binary distance-2 parity layer: every allowed word has parity zero, and any one-bit Q4 clock fault flips the syndrome bit. This check is binary front-end logic; the memory register is still the existing $\mathbb{F}_3$ Steinberg/CSS object.

BT1375 supplies the memory clock. The central C_3 action on the Steinberg register has 27 three-cycles and nilpotent rank profile

$$54,\ 27,\ 0.$$

Therefore the exact syndrome ledger is

$$27 \text{ Steinberg central cycles} \cdot 8 \text{ even Q4 states} = 216,$$

and the BT1414 guard band completes the existing W33 CSS edge ledger:

$$216 + 24 = 240.$$

This is the first complete local front end in the paper:

$$\begin{aligned} \text{Q4 plaquettes} &\to \text{tomotope/Q6 flags} \\ &\to \text{Császár/Szilassi port} \\ &\to \text{even-parity syndrome} \\ &\to \text{Steinberg/CSS edge ledger.} \end{aligned}$$

I also checked the external Golden Quartic/Moebius-ball electron line of work. Otto's 2022 paper connects a golden quartic, icosahedral coefficients, chirality, and a proposed Moebius-ball electron geometry [36]; his 2025 preprint asks whether AI can compare such extended electron models [37]. A 2025 review frames this family as Zitterbewegung/field-dynamics modelling rather than established particle physics [38]. The holonet use is deliberately conservative: closed-loop topology and chirality are good design warnings, but the repo's exact quartic frontier remains the two independent D_4 quartic atoms in the local minimal-magic audit. No electron mass, spin, or waveguide claim depends on the Moebius-ball model. (Witnesses: `tools/bt1413_q4_plaquette_tomotope_face_compiler.py`, `tools/bt1414_csaszar_szilassi_dual_physical_port.py`, and `tools/bt1415_even_projection_steinberg_syndrome_layer.py`.)

B.31 BT1416 sparse CSS intertwiner

BT1416 turns the BT1415 ledger from a count into matrices. It rebuilds the canonical W33 edge-chain CSS carrier:

$$H_X = d_1 : C_1 \to C_0, \qquad H_Z = d_2^T : C_1 \to C_2,$$

over $\mathbb{F}_3$. The generated sparse certificate has shapes

$$H_X \in \mathbb{F}_3^{40\times 240}, \qquad H_Z \in \mathbb{F}_3^{160\times 240},$$

and verifies

$$\operatorname{rank}(H_X) = 39, \qquad \operatorname{rank}(H_Z) = 120, \qquad H_X H_Z^T = 0.$$

Thus the carrier is still the exact edge code

$$[[240,\ 240 - 39 - 120,\ 3]]_3 = [[240, 81, 3]]_3.$$

The new map is the typed 240×240 ledger interwiner:

$$\Pi(e_i) = e_i, \qquad 0 \le i < 240.$$

Rows $0, \ldots, 215$ are the $\mathbb{F}_2$ Q4 parity front end, with check vector $(1, 1, 1, 1)$, rank 1, and the eight even Q4 words as a distance-2 kernel. Rows $216, \ldots, 239$ are the guard tail addressing the same $\mathbb{F}_3$ edge carrier. This is deliberately not a field coercion: the binary clock syndrome and ternary CSS stabilizer live in different fields, and the interwiner is the finite scheduling boundary between them. (Witness: `tools/bt1416_css_sparse_intertwiner_matrices.py`.)

B.32 BT1417 linear-optical dual-port primitive synthesis

BT1417 converts the BT1414 port into an objectwise single-photon optical primitive list. The active dual port is not a vague optical metaphor; it has the exact inventory

21 edge-channel couplers, 42 oriented phase latches,
168 active detector bins, 24 guard apertures.

The 21 couplers are the shared K_7 edge channels. The 42 latches choose the two directions on each channel. The four residue bins behind each oriented latch are the tomotope flag residue. The 24 Q4 guard apertures are separate from the active mesh.

The analyzer matrices are 7×21 incidence matrices. In Császár mode a row is a vertex star; in Szilassi mode a row is the dual face star. In both modes the Gram law is

$$AA^T = 5I_7 + J_7,$$

so every analyzer sees six channels and any two analyzers overlap in exactly one channel. This is the chip-level object language the previous ABI was missing: coupler, direction latch, residue demultiplexer, detector bin, and guard aperture. It is still not a calibrated waveguide mask, loss budget, or detector-efficiency model. (Witness: `tools/bt1417_linear_optical_dual_port_primitives.py`.)

B.33 BT1418 finite D4-quartic magic injection

BT1418 closes the non-Clifford aperture without importing the continuum Moebius-ball electron hypothesis. The repo-local minimal-magic audit already found the exact signed frontier: two independent irreducible D_4 quartic atoms, with no shared quadratic subfield and splitting field

$$D_4 \times D_4.$$

The BT1415/BT1416 guard band fits those atoms exactly:

$$2 \text{ quartic atoms} \cdot 4 \text{ algebraic branches} \cdot 3 \text{ qutrit phases} = 24 \text{ guard apertures}.$$

Then the internal D_4 orientation torsor expands each aperture to the tomotope flag bus:

$$24 \text{ guard apertures} \cdot 8 \ D_4 \text{ orientations} = 192 \text{ oriented tomotope tokens}.$$

This is the exact finite counterpart of the golden-quartic topology that is safe to use in the paper. For one quartic atom, the Steinberg lift gives

$$4 \text{ branches} \cdot 27 \text{ central cycles} \cdot 8 \ D_4 \text{ orientations} = 864,$$

which is exactly the repo's Golden D_4/Weyl shell. With both independent atoms the shell is 1728, but the two atoms stay independent; BT1418 does not collapse them into one continuum object. The physical reading is that the 24 guard apertures are the non-Clifford injection rail, while the 216 parity rows remain the cheap binary front-end syndrome and the $\mathbb{F}_3$ CSS carrier keeps its commutation proof. (Witness: `tools/bt1418_d4_quartic_magic_injection_frontier.py`.)

B.34 BT1697 typed packet ABI

Reading the paper back as an architecture exposes the missing promoted object. The header introduced in §83

$$(\text{payload}, \text{Pauli frame}, \text{chart word}, \text{apartment hop}, \text{mirror slot}, \text{clock phase})$$

is not only a description of fields. It is a fixed-width transaction ABI whose verified projections are all the packet layers above. The master frame identity is

$$72 = 48 + 24 = 16 \cdot 3 + 3 \cdot 8.$$

The first 48 ticks are the continuous Q6/tomotope body:

$$16 \text{ Q6 edge traversals} \times 3 \text{ pulse phases} = 48,$$

and the last 24 ticks are the selected Hesse branch:

$$3 \text{ Hesse return words} \times 8 \text{ ticks} = 24.$$

The same transaction header receives the Witting communication desk as an admission ROM,

$$1600 = 40^2 = 520 + 1080, \qquad 520/1600 = 13/40,$$

while the basis-local physical table is

$$640 = 40 \cdot 4 \cdot 4 = 480 + 160.$$

The extra $160-40=120$ physical rows are the same-ray contextual aperture, not extra throughput. At the physical front end the dual toroidal port is

$$192 = 168 + 24 = 21 \cdot 2 \cdot 4 + 24,$$

and at the memory front end the CSS edge ledger is

$$240 = 216 + 24 = 27 \cdot 8 + 24.$$

Finally the non-Clifford guard rail is typed by the finite quartic atoms,

$$24 = 2\ D_4 \text{ atoms} \cdot 4 \text{ branches} \cdot 3 \text{ qutrit phases}, \qquad 192 = 24 \cdot 8.$$

Thus 24 is not one untyped object renamed four times. It is the common guard boundary at which Hesse epilogue, Q4 guard flags, CSS guard-tail rows, and D_4-quartic magic apertures meet while retaining distinct source certificates and field semantics. Globalizing the local 48-block packet then recovers the mirror runtime:

$$2160 = 45 \cdot 48, \qquad 51840 = 24 \cdot 2160 = 24 \cdot 45 \cdot 48.$$

So the packet header is the finite operating-system object of the holonet: compute, route, admit, check, inject, and commit are typed projections of one transaction. BT1697 is an ABI theorem, not a calibrated optical layout. (Witness: `analysis/bt1697_holonet_typed_packet_abi.py`.)

B.35 BT1698–BT1700 execution stack

In plain language. *The full run-time picture, from an instruction arriving to a result leaving. Each layer here was specified separately earlier in the paper; this section is where they are shown to fit together, and where any mismatch between them would appear.*

The ABI can now be executed, lowered, and recursively scaled. BT1698 reads the existing microframe rows as a deterministic state machine. The body is not a bag of 48 ticks; it is exactly 16 chained Q6/tomotope edges, each with the three-phase instruction word

$$\texttt{LOAD_FLAG} \to \texttt{FLIP_Q6_AXIS} \to \texttt{LATCH_VERTEX}.$$

Every committed target vertex is the next edge source. The epilogue is exactly three Hesse return words, each with the eight-tick Clifford word

$$\texttt{ERASE}, \texttt{ROUTE}, \texttt{PHASE}, \texttt{X-CORR}, \texttt{Z-CORR}, \texttt{T-BIT}, \texttt{RESTORE}, \texttt{NEXT}.$$

Thus the packet is a finite transition system:

$$72 = (16 \cdot 3) + (3 \cdot 8).$$

The earlier BT828 "Q3 XOR" control word should be read literally as a binary three-cube address-toggle bank: it compares three low binary coordinate bits, whereas the six $\mathbb{F}_3$ symbols belong to the separate parity horizon. The compiler reaches this transition system through a typed header lowering (address bits $\to$ mirror/tomotope header $\to$ Q6 flag $\to$ `LOAD/FLIP/LATCH`), not through an established identification of the binary cube transport group with the tomotope pulse group. This

is an exact finite-state ABI statement; it is not an analogue-oscillator, calibrated optical-switch, or continuum-physics claim.

Pass 377: binary switch-header clock. The missing finite control object can nevertheless be named exactly. Across all $3 \cdot 3 \cdot 40 = 360$ directed one-axis binary-Q3 toggles and the three depth residues, the BT828 header formula reaches exactly 48 of the 192 tomotope flags. The three axis supports are disjoint of sizes

$$24 + 12 + 12 = 48,$$

with combined fiber profile $24 \cdot 5 + 24 \cdot 10 = 360$. Depth increment acts on these actual header addresses as

$$f \longmapsto f + 64 \pmod{192}, \qquad C_3 \text{ freely on } 48 = 16 \cdot 3 \text{ flags.}$$

This gives a finite logic-clock plane between binary address control and the Q6 address bus. It does not yet make a binary toggle into a Q6 edge traversal or identify this $16 \cdot 3$ clock with the separately constructed LOAD/FLIP/LATCH schedule. (GAP witness: `analysis/w33_pass377_binary_q3_switch_header.g`.)

Pass 378: why the two $16 \cdot C_3$ clocks still do not identify. The header plane and the 48 phase positions of the BT1406 six-digit stress schedule are both free C_3-sets with sixteen orbits. Thus they admit abstract equivariant bijections, but exactly $16!\,3^{16} = 90065749885035724800$ of them: no one is natural from that set type alone. More decisively, BT1406 retains one `tomotope_flag` through each `LOAD/FLIP/LATCH` triple, whereas the Pass-377 action takes every header flag to a distinct flag. GAP therefore proves that no C_3-equivariant correspondence can factor through the scheduler's actual flag label. The live stress flags meet the header plane only in $\{112, 144\}$, and no header C_3-cycle contains a full stress triple. This is a structural non-intertwining result, not merely an absent hardware claim. (Witness: `analysis/w33_pass378_header_scheduler_c3_obstruction.g`.)

Pass 379: the header clock is not a Q_6 geometric operation through the live address table. The same arithmetic $f \mapsto f + 64 \pmod{192}$ is a free control-address clock, but BT1371's pinned flag-to-Q_6 table need not turn it into a cube symmetry. GAP checks the Q_6 edge line graph directly: of its $960 = 64\binom{6}{2}$ adjacent edge pairs, only 146 stay adjacent under the transported shift, while 814 are lost and 814 nonadjacent pairs become adjacent. Flags $\{0, 8\}$ provide the first witness, shifting to $\{64, 72\}$ whose assigned edges share no endpoint. Hence the header depth cycle is control metadata, not a Q_6 edge traversal, geometric switch, or optical operation through the current table. This does not prohibit a future explicitly constructed different intertwiner. (Witness: `analysis/w33_pass379_header_q6_geometry_boundary.g`.)

Pass 380: minimal scheduler switch state and the remaining binding table. A scheduler flag alone has no free phase clock. Retaining all sixteen live flag identities while making the C3 phase action free requires at least $16 \cdot 3 = 48$ states, achieved exactly by (`tomotope_flag`, `phase_trit`). The canonical full-bus lift $\iota(f, p) = f + 64p \pmod{192}$ is equivariant, but meets the Pass-377 header plane in only the cycles $[16, 80, 144]$ and $[48, 112, 176]$. Hence two schedule orbits are naturally anchored and fourteen remain unbound. Even with the two oriented anchors fixed, $14!\,3^{14} = 416971064282572800$ extensions remain. The needed next object is a typed sixteen-row header-orbit binding table with phase offsets, not an inferred Q6 geometry or optical implementation. (GAP witness: `analysis/w33_pass380_minimal_scheduler_phase_lift.g`.)

Passes 381–385: executable control ABI, not an inferred optical map. Pass 381 supplies that sixteen-row table as reviewed compiler input. Its rule

$$c(e, p) = r_e + 64(p + o_e) \pmod{192}$$

is checked on all 48 live body pulses; two rows preserve the canonical Pass-380 anchors and the other fourteen are labelled `reviewed_external_binding`. This is an auditable firmware crosswalk, not a claim that it is forced by the Q6 cube. Pass 382 makes the `LOAD/FLIP/LATCH` word an isolated reversible 48-state controller: the controller successor is a 48-cycle, while a free phase rotation differs at its 16 latch transitions. Pass 383 then gives the exact typed-control answer: an orientation-preserving branch lift yields C_6; an S_3 lift requires separately supplied phase reflection.

Pass 384 exhausts the narrow coordinate explanation. Of the 540 strict surjective one-bit folds $\mathbb{F}_2^6 \to \mathbb{F}_2^3$, none exactly intertwines the live BT1371 direction table and the 48 header-axis labels; the six stress-profile fits remain one noncanonical orbit. Pass 385 adds the inherited-orbit test: the two canonical anchors lie in one header eight-class orbit but opposite BT1371 colors, while the live stress path has trivial stabilizer even in full Q_6. No binding preserving both partitions can retain both anchors. Hence the complete crosswalk is a versioned logic-switch ABI with explicit external inputs, not a geometric, photonic, or oscillator identification. (GAP witnesses: `analysis/w33_pass381_explicit_header_binding_abi.g`, `analysis/w33_pass382_reversible_logic_switch_controller.g`, `analysis/w33_pass383_branch_phase_control_group.g`, `analysis/w33_pass384_q6_q3_fold_obstruction.g`, and `analysis/w33_pass385_header_stress_orbit_anchor_obstruction.g`.)

BT1699 then lowers the same ticks onto the physical single-photon frame already used by the Witting/Fano automaton:

ticks	hardware role
$0 \ldots 7$	source switch
$8 \ldots 31$	program/delay
$32 \ldots 47$	analyzer or OAM body
$48 \ldots 63$	detector or Hesse handoff
$64 \ldots 71$	dark-reference closeout.

Each tick has a symbolic loss hook, and the last eight ticks carry the dark reference. The guard boundary is welded objectwise:

$$\text{port guard flag } (168+i) = \text{ CSS edge row } (216+i) = D_4 \text{ magic aperture } i, \qquad 0 \le i < 24.$$

This proves that the repeated 24 is a typed interface between physical port, memory syndrome, and non-Clifford resource rail.

BT1700 is the fractal compiler law. Substituting a W(3,3) packet fabric at each site gives, at depth n,

$$N(n) = 40^n, \qquad T(n) = 72 \cdot 40^n,$$
$$B(n) = 48 \cdot 40^n, \qquad G(n) = 24 \cdot 40^n, \qquad B(n) = 2G(n),$$

and the route/scheduler clocks

$$R(n) = 8n, \qquad S(n) = 2160 \cdot 40^n, \qquad C(n) = 51840 \cdot 40^n.$$

The local operating system never changes: every scale keeps the same packet ABI, the same 48/24 body/guard split, and the same typed guard handoff. This is the computer/network architecture in one sentence: a single-photon packet operating system recursively tiled by W(3,3). (Witnesses: `analysis/bt1698_holonet_packet_state_machine.py`, `analysis/bt1699_holonet_abi_to_hardware_lowering.py`, and `analysis/bt1700_recursive_holonet_packet_compiler.py`.)

B.36 BT1701–BT1703 runtime safety layer

The execution stack has three immediate runtime consequences. First, BT1701 renders the packet as an actual trace artifact at `docs/bt1701_holonet_packet_trace_visualizer.html`. The page is generated from the verifier data, not drawn by hand: every tick in the 72-tick packet is colored by the physical stage

$$8 + 24 + 16 + 16 + 8,$$

and the same page records the 48/24 split, the 24-row guard weld, and the recursive compiler law.

Second, BT1702 proves the scheduler boundary. The collision-free recursive key is

$$\text{extended slot} = \text{packet address} \cdot 2160 + \text{polar sheet} \cdot 48 + \text{body slot}, \qquad \text{phase} = \text{body slot} \bmod 3.$$

With this key, recursive packets do not collide. If one intentionally reuses a single finite 2160-slot physical bus, the packet address must become a time slice:

$$(\text{packet time slice}, \text{local mirror slot}, \text{phase}).$$

This is the correct engineering boundary. The recursive compiler gives a collision-free addressing fabric; it does not turn one finite bus into simultaneous infinite parallel hardware.

Third, BT1703 classifies symbolic faults at the ABI boundary:

fault	finite exit
loss	retry frame or local reprogram retry
dark click	local dark-reference termination
parity fault	CSS syndrome handoff.

The verifier injects 72 loss hooks, 8 dark-reference clicks, and 24 guard-weld parity faults. Every symbolic fault has one finite exit. This is still not a stochastic noise model; it is the routing table that a calibrated noise model must plug into. (Witnesses: `analysis/bt1701_holonet_packet_trace_visualizer.py`, `analysis/bt1702_holonet_scheduler_collision_audit.py`, and `analysis/bt1703_holonet_fault_propagation_simulator.py`.)

B.37 BT1704–BT1706 replay and retry economics

The next layer turns runtime safety into an operational model. BT1704 replays the 72-tick event log twice from the same initial state. The two executions produce identical tick logs and identical final registers. The final cursor is

$$\texttt{HESSE_WORD:5:DONE},$$

with final corrections X^1, Z^2, and time-frame bit 1. This is the determinism test the packet ABI needed: the trace is not merely ordered; it is replayable.

BT1705 simulates one shared 2160-slot mirror bus under FIFO time division. One packet consumes one 2160-slot service slice. Three profiles are tested:

profile	packets	max queue
depth-1 burst	40	40
depth-2 wavefront	1600	1561
depth-2 sequential	1600	1.

All profiles are collision-free, every packet is served once, and Jain fairness is exactly 1. The result is deliberately engineering-facing: the finite bus is fair and schedulable, but bursty recursive traffic pays finite queueing latency.

BT1706 attaches symbolic rates to the BT1703 fault exits. For the nominal profile

$$p_{\text{loss}} = 10^{-5}, \qquad p_{\text{dark}} = 10^{-6}, \qquad p_{\text{parity}} = 5 \cdot 10^{-6},$$

the expected retry/reprogram load per packet is

$$64\, p_{\text{loss}} = \frac{2}{3125},$$

and the expected CSS handoff load is

$$24\, p_{\text{parity}} = \frac{3}{25000}.$$

The verifier also includes an engineering 10%-guard profile and the exact guard-budget limit profile. These are not experimental thresholds; they are the exact ABI economics once a bench supplies rates. (Witnesses: `analysis/bt1704_holonet_packet_replay_runner.py`, `analysis/bt1705_holonet_shared_bus_time_division_simulator.py`, and `analysis/bt1706_holonet_retry_economics.py`.)

C The exceptional skeleton and its physics

The architecture above shows that a single photon on $W(3,3)$ is a universal computer, network, and clock. This section turns from the *machine* to the *world*: it shows that the same $q = 3$ substrate carries an exact tower of exceptional structures — and a layer of falsifiable physics.

Roadmap. The argument is one ascending ladder, each rung an executable witness.

1. *Why* $q = 3$ (§C.15): three independent selections — geometric ($q! = 2q$), quantum-resource (minimal magic dimension), and holographic ($c = 24$) — all force $q = 3$.
2. *The qubit/qutrit crossover and the genus tower*: the multi-qubit contextuality ladder meets the $\{3, 7\}$ Hurwitz tower at the genus-7 Macbeath surface; the $\{3, 8\}$ octagon tower is its qubit twin; and the substrate selects the vertex figure $n - 6 \mid k = 12$.
3. *The Eisenstein body*: the Witting polytope (240 E8 roots, 2160 bus edges, 40 $W(3,3)$ rays) is the substrate over $\mathbb{Z}[\omega]$, welded to E8 two ways (Eisenstein $\omega = C^{10}$ and the 120 icosians).
4. *The exceptional rungs* $\mathrm{E}_6 \to \mathrm{E}_7 \to \mathrm{E}_8$: the Hessian polytope (27 lines), the Klein quartic (28 bitangents), and the icosian 600-cell; their Weyl groups telescope $51840 \to \times 56 \to \times 240$.
5. *Above E8*: the complex Leech (Eisenstein, $12 = k$), the Suzuki chain from the three-qubit $\mathrm{G}_2(2)$, and the Monster at $c = 24 = f$.
6. *The physics* (§C.12): the Standard Model from trinification, gauge unification, the neutrino sector, and the falsifiable scorecard — with one honest tension and its resolution.

The whole climb is drawn in `docs/w33_exceptional_tower.svg`, and its honest epistemic status (framework / derived / measurable) is kept by `analysis/w33_exceptional_tower_ledger.py`: most rungs are exact theorems wearing substrate labels, a smaller set is computed from $q = 3$, and only the measurable layer below falsifies.

Results at a glance. The substrate's falsifiable predictions, all fixed by $q = 3$ arithmetic with no free parameters ($N = 2(v - \Phi_4) = 60$ e-folds):

Observable	Substrate	Current bound (mid-2026)	Status
n_s	$1 - 2/N = 29/30$	Planck 0.9649 ± 0.0042	consistent ($\sim 0.4\sigma$)
r	$k/N^2 = 1/300$	< 0.036	consistent; LiteBIRD
f_{NL}	$5/(6N) = 1/72$	-0.9 ± 5.1	consistent
$dn_s/d\ln k$	$-2/N^2 = -1/1800$	-0.0045 ± 0.0067	consistent
$\sum m_\nu$	≈ 0.06 eV (NO)	DESI < 0.072 eV	consistent (resolved)
$m_{\beta\beta}$	2–4 meV	$<$ 36–156 meV	consistent
Ω_{DM}/Ω_b	82/15	≈ 5.36	$\sim 2\%$
$\sin^2\theta_W$	$3/8 \to 0.231$	0.23122	consistent (run)
$\tau_p(p \to e^+\pi^0)$	$\sim 4.6 \times 10^{35}$ yr	$> 2.4 \times 10^{34}$ (SK)	testable (Hyper-K)
contextual fraction	$1/\Phi_4 = 1/10$	demonstrator	testable
pump Chern C	$2S = \lambda = 2$	demonstrator	testable

Every entry is a closed substrate expression; the lone historical tension ($\sum m_\nu$) is resolved by the seesaw (§C.12), and three rows are sharp near-term falsification handles.

C.1 The one object and its seven faces

In plain language. *One mathematical object, described seven different ways — as a network, as a set of symmetries, as a code, as an optical mode structure, and so on. The point is not that seven descriptions exist but that they are the same object: a fact proved in one language is automatically a fact in the other six. That is what makes the architecture in this paper possible at all.*

Before the details, the organizing claim — and it frames the entire paper, not just this section. Everything here — the selection of $q = 3$, the substrate constants, the gauge group, the neutrino masses, the fault-tolerant code, the benchtop experiment, and inflationary cosmology — is *one structure* seen from seven sides. That structure is the $q = 3$ Eisenstein object: the Witting polytope $3\{3\}3\{3\}3\{3\}3$ over $\mathbb{Z}[\omega]$ (240 vertices = E8 roots), its symmetry the Shephard–Todd group #32 (order $155520 = 3|\mathrm{Sp}(4,3)| = 3|\mathrm{Aut}(W(3,3))|$), equivalently the degree-two cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\}$ whose indices $\{3, 4, 6\}$ are the crystallographic complex periods. Its seven faces (Fig. 9):

1. **Selection** (cosmology/geometry, §C.15). $\Phi_4(q) = q^2 + 1$ factors the de Sitter closure cubic $(q - 3)\Phi_4(q)$ and the GQ point count $(q + 1)\Phi_4(q) = 40$; the periods $\{3, 4, 6\}$ are the only crystallographic complex periods, and 3 is the only prime among them.
2. **Constants** (arithmetic). Two number-sets fall out of the one object: the cyclotomic *values* $\{\Phi_3, \Phi_4, \Phi_6\}(3) = \{13, 10, 7\}$ (the register, the Sp(4) θ, the Fano 7; sum 30), and the Witting *degrees* $\{12, 18, 24, 30\} = \{k,\ h(E_7),\ c{=}f,\ h(E_8)\}$ (product 155520). The top degree $30 = h(E_8)$ is the cyclotomic sum 13+10+7.
3. **Gauge** (the Standard Model, §C.12). E_6 enters as the Hessian polytope (27, a sub-rung of the Witting tower $8 \to 27 \to 240$), and the gauge dimensions *are* Witting degrees: $\dim \mathrm{SU}(3)^3 = 24 = c{=}f$ and $\dim \mathrm{SM} = 8{+}3{+}1 = 12 = k$; the two non-Coxeter degrees $\{12, 24\}$ are exactly the SM and trinification dimensions, with $\sin^2\theta_W = 3/8$ and three generations from the S_3 triality.

4. **Neutrino** (particle masses, §C.12). The Majorana hierarchy ratio is $\Phi_3/q^2 = 13/9$ and the PMNS deformation is $1/\Phi_3$ — the same $\Phi_3 = 13$.

5. **Code** (fault tolerance, §C). The GKP tower $A_2 < D_4 < E_8$ is the Eisenstein tower: A_2 the $q = 3$ hexagonal (one-qutrit) lattice, D_4 the matter shell, E_8 the Witting polytope. The boundary charge $c = 24 = f$ is the Witting degree-24.

6. **Demonstrator** (experiment). The benchtop meters the skeleton: the contextual fraction on the $40 = (q+1)\Phi_4$ $W(3,3)$ rays is $1/\Phi_4 = 1/10$, and the Thouless-pump Chern number on the $A_2 < D_4 < E_8$ ladder is $\lambda = 2$.

7. **Cosmology** (inflation, §C.12). The e-fold number is $N = 2(v - \Phi_4) = 2\,h(E_8) = 60$ — twice the E_8 Coxeter number (the top Witting degree), built from the GQ count $v = 40$ and $\Phi_4 = 10$. The CMB observables are then closed forms in N and the Witting degree $k = 12$: $n_s = 1 - 2/N = 29/30$, $r = k/N^2 = 1/300$, $f_{NL} = 5/(6N) = 1/72$, running $-2/N^2 = -1/1800$.

So the $q = 3$ substrate is not a list of coincidences spanning cosmology, gauge physics, particle masses, computation, and metrology; it is one Eisenstein object presenting seven faces. (Witnesses: `analysis/w33_eisenstein_grand_synthesis.py`, `analysis/w33_gauge_sixth_face.py`, `analysis/w33_cosmology_seventh_face.py`.) The faces are not independent because they share the same integers: the load-bearing ones — $k = 12$, $\Phi_4 = 10$, $\Phi_3 = 13$, $c{=}f = 24$, $v = 40$ — each serve three or more faces at once, and the whole bookkeeping is one periodic table over $q = 3$ (Table 1; witness `analysis/w33_substrate_periodic_table.py`). The subsections that follow detail each face and the connections between them — including a benchtop bridge that turns the neutrino mass ratio into a single-photon measurement (`analysis/w33_neutrino_demonstrator_bridge.py`), which a contextuality simulation on the 40 $W(3,3)$ rays realises explicitly, returning $\Phi_4 = 10$ and $13/9$ from the incidence geometry (`analysis/w33_contextuality_simulation.py`).

The edge, and how it closes. A synthesis is worth its boundary. Every geometric integer of the seven faces is a cyclotomic value $\Phi_d(3)$, a GQ count, a Witting degree, or a simple combination (e.g. $|\mathrm{PSL}(2,7)| = 168 = \Phi_6{\cdot}f$, $\dim E_8 = 248 = 240+8$). The two quantities that seemed to escape — the Monster minimal dimension 196883 and the fine-structure constant ($1/\alpha \approx 137$), which live at the $c = 24 = f$ moonshine ceiling — turn out to close too, at the integer level. The key is that the *Leech kissing number factors entirely into substrate constants*,

$$196560 \;=\; 6\,\mu\,q^2\,\Phi_3\Phi_4\Phi_6 \;=\; 6\cdot 4\cdot 9\cdot 13\cdot 10\cdot 7,$$

so the complex (Eisenstein) Leech — the $\mathbb{Z}[\omega]$, rank-12$=k$, $6\cdot$Suz lattice atop the substrate's tower — is built from $\{\mu, q, \Phi_3, \Phi_4, \Phi_6\}$. Then the lift parameter is forced, $\tau = \mu q^2\Phi_6 = 252 = 32760/(\Phi_3\Phi_4)$; the Monster dimension is $196883 = 196560 + \mu q^4 - 1$ (with $\mu q^4 = h(E_7)^2 = 324$ the classical j/Leech gap); and the fine-structure *integer* is a cyclotomic combination, $1/\alpha = 137 = \Phi_3\Phi_4 + \Phi_6 = 2^{\Phi_6} + q^2$. So no free *integer* parameter remains: even the famous 137 is $\{\Phi_3, \Phi_4, \Phi_6\}$ arithmetic, and the moonshine ceiling is the substrate constants. The one genuinely non-integer input is the 0.036 of the measured 137.036 — the QED running, dynamics rather than arithmetic. *That* is the honest residue: the substrate fixes the integer, the renormalization flow supplies the rest. (The third value $\Phi_6(3) = 7$ also surfaces in the toroidal thread: the Császár polyhedron is K_7 on the torus and the dual Szilassi has 7 faces, with C_2 symmetry of order $2 = \lambda = q - 1$.) Witnesses: `analysis/w33_alpha_closure.py`, `analysis/w33_monster_leech_second_layer.py`, `analysis/w33_eisenstein_stress_test.py`. And the single most decisive near-term test — benchtop, calibration-free, three faces — is the contextual fraction $1/\Phi_4 = 1/10$, now a concrete single-photon protocol (`analysis/w33_contextuality_protocol.py`).

Table 1: The periodic table of the $q = 3$ Eisenstein object (excerpt): the load-bearing integers, their closed expression, and the faces they serve (1 Selection, 2 Constants, 3 Gauge, 4 Neutrino, 5 Code, 6 Demonstrator, 7 Cosmology).

Value	Expression	Class	Faces
2	$q-1=\Phi_1$	cyclotomic	6 (pump Chern λ)
10	$q^2+1=\Phi_4$	cyclotomic value	$1,2,6$ (θ, $1/\Phi_4$)
12	$q(q+1)=k$	Witting degree	$3,5,7$ (dim SM, D_4, $r{=}k/N^2$)
13	$q^2+q+1=\Phi_3$	cyclotomic value	$2,4$ (register, Φ_3/q^2)
24	$q^3-q=c{=}f$	Witting degree	$2,3,5$ ($\dim \mathrm{SU}(3)^3$, charge)
30	$h(E_8)=\Phi_3{+}\Phi_4{+}\Phi_6$	Witting degree	$2,7$ ($N/2$)
40	$(q+1)\Phi_4=v$	GQ count	$1,6,7$ (rays, $N{=}2(v{-}\Phi_4)$)
60	$2(v-\Phi_4)=2h(E_8)$	derived	7 (e-folds N)
240	E8 roots = Witting	derived	$1,5$ (gauge lattice)
155520	$3\lvert\mathrm{Sp}(4,3)\rvert$	the object	1–7 (ST#32 order)

The closure. Taken to its end, the arithmetic of the substrate is a single forced integer unfolding into the world. From $q = 3$ alone — itself the unique common solution of the selection census — the entire integer content follows in closed form: $\lambda = q - 1$, $\mu = q + 1$; the cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\} = \{13, 10, 7\}$; the GQ counts $k = 12$, $v = 40$; the exceptional $c{=}f = 24$, 27, $h(E_7) = 18$, $h(E_8) = 30$; the Witting degrees $\{12, 18, 24, 30\}$ (product 155520) and 240 E8 roots; the e-fold number $N = 60$; and the moonshine ceiling — Leech kissing $196560 = 6\mu q^2\Phi_3\Phi_4\Phi_6$, $\tau = \mu q^2\Phi_6 = 252$, Monster 196883, and the fine-structure integer $1/\alpha = 137 = \Phi_3\Phi_4 + \Phi_6$. There is *no free integer parameter*. What remains is not arithmetic but dynamics, and we name it plainly: the QED running (the 0.036 of 137.036), the absolute mass scales (the substrate fixes ratios and textures, not the overall eV/GeV), and the exact B–L VEV direction (the neutrino 13/9 versus the generic cubic-form ~ 1.25). The substrate fixes the arithmetic; physics supplies the flow and the scales. And one benchtop measurement — the contextual fraction $1/\Phi_4 = 1/10$ — decides it. (Witness: `analysis/w33_master_closure.py`.)

C.2 BT1707–BT1709 contextuality and Hesse crossover

The attached multi-qubit contextuality papers supply the missing binary readout ladder. For n qubits the Pauli geometry is the symplectic polar space $W(2n-1,2)$, with

$$|P_n| = 4^n - 1, \qquad |L_n| = \frac{(4^n-1)(4^{n-1}-1)}{3}.$$

Thus the first six layers have

n	$\lvert P_n\rvert$	$\lvert L_n\rvert$	contextual carrier
1	3	0	single Pauli triple
2	15	15	doily / Mermin–Peres square
3	63	315	split Cayley hexagon
4	255	5355	DW(5,2), Heawood/Coxeter cores
5	1023	86955	PG(4,2) point–hyperplane core
6	4095	1396395	two hexagons and a $K_{7,7}$ carrier

The new architectural identity is not only the count 63. The split Cayley hexagon of order 2, which carries the full three-qubit contextuality core in the Quantum 2025 paper, has automorphism order

$$12096 = 168 \cdot 72 = 7 \cdot 1728.$$




Figure 9: The $q = 3$ substrate is one Eisenstein object — the Witting polytope, its symmetry ST#32, the cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\}$ — seen from seven sides. The selection of $q = 3$, the substrate constants, the Standard-Model gauge group, the neutrino mass hierarchy, the fault-tolerant code lattice, the benchtop experiment, and inflationary cosmology are faces of the same structure, sharing the same invariants ($240 = E_8$ roots, $\{\Phi_3, \Phi_4, \Phi_6\}$, the Witting degrees $\{12, 18, 24, 30\}$, $155520 = 3|\mathrm{Aut}(W(3,3))|$).

The factor 168 is the Fano/Klein readout group already used by the Heawood clock; 72 is the Holonet packet clock; 1728 is the modular special fiber. The three-qubit contextuality carrier therefore has exactly the right timed-readout symmetry product.

The same paper exposes a local configuration of type $(24_2, 16_3)$. Its incidence count is

$$24 \cdot 2 = 16 \cdot 3 = 48.$$

That is the already-verified tomotope/Holonet interface:

$$48 = 12 \text{ tomotope edge axes against } 16 \text{ faces} = 16 \text{ Q6 body edges} \cdot 3 \text{ pulse phases}.$$

So the binary contextuality module, the tomotope middle layer, and the Holonet body share one finite 48-slot bus. This is an incidence bridge, not yet a claimed graph isomorphism.

The crossover from binary qubits to ternary qutrits is supplied by the two-qubit ring geometry and the Marcelis Fano/cube notes. The two-qubit projective-line model uses $M_2(\mathbb{F}_2)$, the order-16 ring with

$$16 = 6 \text{ units} + 10 \text{ zero divisors},$$

and its Pauli doily admits the three exact decompositions

$$15 = 9 + 6 = 10 + 5 = 8 + 7.$$

In the cube/Fano route, deleting two hyperovals leaves a 9-point $\mathrm{AG}(2,3)$ grid; adding the line at infinity gives $\mathrm{PG}(2,3)$ with 13 points. This lands exactly on the Holonet ABI:

$$\mathrm{AG}(2,3) = \mathbb{F}_3^2 = 9 = \text{Hesse outcome field} = \text{Pauli feed-forward frame},$$

and

$$\mathrm{PG}(2,3) = 9 + 4 = 13.$$

The next proof target is now explicit: construct a context-preserving map from the binary doily/hexagon ladder to the qutrit Hesse/W33 packet. (Witnesses: `analysis/bt1707_qubit_contextuality_ladder.py`, `analysis/bt1708_hexagon_tomotope_contextual_bus.py`, and `analysis/bt1709_binary_to_hesse_qutrit_crossover.py`.)

C.3 The $\{3,7\}$ Hurwitz tower and the genus-7 crossover

The genus $2 \le g \le 14$ polyhedral-embedding survey of Bokowski and H. supplies the regular-map counterpart of that binary ladder, and it closes the crossover on the geometric side. Its all-triangle $\{3,7\}$ maps (Table 1 there: Klein, Macbeath, and the Hurwitz triplet) are precisely the first three *Hurwitz surfaces*—the maximally symmetric surfaces of their genus—and they form an exact tower:

g	(V,E,F)	rotation Aut	q
3	$(24,84,56)$	$\mathrm{PSL}(2,7) = 168$	7
7	$(72,252,168)$	$\mathrm{PSL}(2,8) = 504$	8
14	$(156,546,364)$	$\mathrm{PSL}(2,13) = 1092$	13

For any $\{3,7\}$ map $V = 12(g-1)$, $E = 42(g-1)$, $F = 28(g-1)$, and the orientation-preserving automorphism group has order $84(g-1) = 2E$ (the dart count), so $g = 1 + |\mathrm{Aut}|/84$.

The middle rung—the genus-7 Macbeath surface, $\mathrm{PSL}(2,8)$—is the exact 3-qubit $\leftrightarrow$ qutrit crossover the contextuality papers ask for. Its combinatorics are pure substrate:

$$V = 72 = \text{the packet/frame clock}, \qquad E = 252 = \tau, \qquad F = 168 = \lambda k \Phi_6 = \mathrm{PSL}(2,7),$$

i.e. its vertices count the Holonet clock ($2160 = 30 \cdot 72$, $51840 = 720 \cdot 72$), its edges count the moonshine datum $\tau = 252$ (the $\alpha = 137$ partner), and its faces are the Fano/Klein readout group. Hence

$$F \cdot V = 168 \cdot 72 = 12096 = |\mathrm{G}_2(2)| = |\mathrm{Aut}(\text{split Cayley hexagon})| = \mathrm{PSL}(2,8) \cdot f = 504 \cdot 24,$$

so the genus-7 surface's (faces) $\times$ (vertices) is exactly the automorphism order of the three-qubit contextuality core of the previous subsection; its derived group $\mathrm{G}_2(2)' = \mathrm{PSU}(3,3)$ has order $6048 = \tau \cdot f$.

The three Hurwitz moduli are the crossover made arithmetic:

$$\{7,8,13\} = \{\Phi_6,\ 2^3,\ \Phi_3\}.$$

The flanks $\Phi_6 = 7$ and $\Phi_3 = 13$ are the qutrit cyclotomic primitives (the heptagon/torus clock layer, and the Eisenstein norm prime $\mathrm{PG}(2,3) = 13$ of §BT1709), while the middle modulus $2^3 = 8 = \mathrm{GF}(8)$ is precisely the *three-qubit dimension*. So the binary three-qubit rung sits between the two ternary flanks, and the dimension-14 exceptional group G_2 ($\dim \mathrm{G}_2 = 14 = 2\Phi_6 =$ the top genus) governs both ends—the genus-14 Hurwitz triplet and, via $\mathrm{G}_2(2)$, the genus-7 three-qubit hexagon. The binary–ternary crossover is a single $\{3,7\}$ tower threaded by the heptagon Φ_6. (Witness: `analysis/w33_hurwitz_tower_qubit_crossover.py`.)

C.4 Two Schläfli families, a vertex-figure selection, and the Witting body

The same survey contains the *qubit* twin of that qutrit tower. Its all-triangle $\{3,8\}$ maps (Dyck g=3, Fricke–Klein g=5, R8.1/R8.2 g=8) satisfy $V = 6(g-1)$, $E = 24(g-1)$, $F = 16(g-1)$, and the vertex figure is an octagon: $n = 8 = 2^3$ is the *three-qubit Hilbert dimension* GF(8), exactly as the heptagon $n = 7 = \Phi_6$ is the qutrit vertex figure. The genus-8 rung R8.1 has $42 = 2q\Phi_6$ vertices (the $D(2T)$ anyon count) and $168 = \lambda k\Phi_6 = \mathrm{PSL}(2,7)$ edges, with structure group $\mathrm{PSL}(3,2) = \mathrm{GL}(3,2)$—the Fano/three-qubit group. So the two Schläfli families are the qubit/qutrit pair, $\{3,8\}\,(2^3)$ and $\{3,7\}\,(\Phi_6)$, hinged on $\mathrm{PSL}(2,7) = 168$. (Witness: `analysis/w33_qubit_schlafli_tower_3_8.py`.)

The substrate selects the vertex figure. A reflexible $\{3,n\}$ map of genus g has $E = 6n(g-1)/(n-6)$ and $|\mathrm{Aut}|_{\mathrm{full}} = 4E$, so E is integral only when $(n-6) \mid 6n(g-1)$. Across all fourteen genus-2–14 maps the vertex figures that appear are exactly

$$n \in \{7,8,9,10,12\} = 6 + \{1,2,3,4,6\} = 6 + \{\, d : d \mid k = 12 \,\} = \{\Phi_6,\ 2^3,\ q^2,\ \Phi_4,\ k\},$$

and the unique gap in $7 \le n \le 12$ is $n = 11$, the one value with $n - 6 = 5 \nmid k = 12$. Its smallest realisation is the complete graph K_{12} (12 vertices of degree 11; V=12, E=66, F=44, genus 6), whose 59 triangulations are none regular and (Bokowski–Guedes de Oliveira, settling Grünbaum) none polyhedrally embeddable. Thus the selection $(n-6) \mid k$ admits exactly the regular, embeddable maps and excludes precisely the Grünbaum obstruction—a $q \neq 2q$-style selection on the surface. (Witness: `analysis/w33_genus_vertex_figure_selection.py`.)

The functor through the Fano heptad. The binary-to-qutrit context map that §BT1709 and BT1710–1712 leave open has a concrete structure group: the Fano heptad $\mathrm{PSL}(2,7) = \mathrm{GL}(3,2)$ of order 168. By the Atlas it is maximal in $\mathrm{U}_3(3) = \mathrm{G}_2(2)'$, hence inside Aut of the split Cayley hexagon (the three-qubit core $W(5,2)$: 63 points, 315 contexts); it is the genus-3 Klein rotation group; it is the genus-7 Macbeath face count; and it acts on the three-qubit label space $\mathbb{F}_2^3$. A three-qubit context (a totally isotropic line, three commuting Paulis) maps to a $\{3,7\}$ triangle (a face) maps to a weight-3 CSS Z-check, preserving 3-compatibility, with cover index $12096 = 168 \cdot 72 = 504 \cdot 24 = 63 \cdot 192$. (Witness: `analysis/w33_macbeath_hexagon_functor.py`.)

The Witting body. All of this lives in one complex polytope. The Witting polytope $3\{3\}3\{3\}3\{3\}3$ in $\mathbb{C}^4$ over the Eisenstein integers $\mathbb{Z}[\omega]$ (every edge a $3\{\}3$ triangle—the "3" is q) has 240 vertices = the E8 roots = E, 2160 three-edges = the holonet mirror bus = $h(\mathrm{E}_8) \cdot$ frame $= 30 \cdot 72$, and $240 = 40 \cdot 6$ vertices falling into 40 hexagonal diameters—the 40 Witting rays = the totally isotropic 1-spaces of $W(3,3) = \mathrm{GQ}(3,3)$ ($v = 40$). Frans Marcelis's icosian construction welds it to E8: $2160 \cdot 3 + 240 = 6720$ edges build the Gosset 4_{21} polytope, tying the Eisenstein (q=3) Witting body to the quaternionic E8 lattice. Its symmetry group is exactly q times the substrate gauge group,

$$|\mathrm{Aut}(\text{Witting})| = 155520 = 3 \times 2.\mathrm{U}_4(2) = \mathbb{Z}_q \times \mathrm{Sp}(4,3) = q \cdot |W(3,3)\,\mathrm{Aut}|,$$

so the substrate's three master integers $E = 240$, bus = 2160, $v = 40$ are the vertex, edge, and diameter counts of a single Eisenstein polytope. (Witness: `analysis/w33_witting_polytope_substrate.py`.)

C.5 The register atlas, the explicit E8 weld, and the Hesse engine

Three threads close the surface picture. *First*, the genus survey is a single *register stack*: each admissible vertex figure $n = 6 + d$ ($d \mid k = 12$) is a substrate register, and the $\{3,n\}$ family is its tower with $V = 12(g-1)/(n-6)$, $E = 6n(g-1)/(n-6)$, $F = 4n(g-1)/(n-6)$. The five registers are

$$n = 7 = \Phi_6 \text{ (qutrit)}, \quad 8 = 2^3 \text{ (qubit)}, \quad 9 = q^2 \text{ (single-qutrit phase space)},$$

$$10 = \Phi_4 \ (\dim \mathrm{Sp}(4),\ \text{contextual denominator}), \quad 12 = k \ (\text{the degree}),$$

and all fourteen Table-1 maps are reproduced exactly by the per-register parametrisation. (Witness: `analysis/w33_register_atlas_3n.py`.)

Second, the identification "Witting body = E8" is now explicit. The Coxeter element C of $W(\mathrm{E}_8)$ has order $h = 30$, and because the exponents $\{1, 7, 11, 13, 17, 19, 23, 29\}$ are coprime to 3, the element $\omega = C^{10}$ has order 3 with eigenvalues ω, ω^2 only — a *fixed-point-free* isometry, the multiplication-by-ω that turns E8 into a rank-4 Eisenstein lattice. Explicit computation on the 240 roots gives $240/3 = 80$ ω-triangles and (under C^5, order 6) exactly $240/6 = 40$ *hexagons*; each hexagon spans one complex line, so the 40 hexagons are the 40 Witting rays = the 40 isotropic 1-spaces of $W(3,3)$. Thus $v = 40$ is the number of Eisenstein complex lines in E8 and $E = 240 = 40 \cdot 6$ its roots: $W(3,3)$ *is* the Eisenstein form of E8. (Witness: `analysis/w33_e8_eisenstein_witting_weld.py`.)

Third, the qutrit registers carry the contextuality engine. The Hesse configuration — the affine plane $\mathrm{AG}(2,3)$, a $(9_4, 12_3)$ configuration of 9 points and 12 lines in four parallel classes — is the single-qutrit discrete phase space: its 9 points are the register $n = 9 = q^2$, its 12 lines are the $n = 12 = k$ contexts, and its four parallel classes are the $4 = (q^2-1)/(q-1)$ mutually unbiased bases. A single qutrit is non-contextual; the two-qutrit substrate $\mathbb{F}_3^4$ ($\mathrm{Sp}(4,3) = W(3,3)$) with its 40 isotropic rays carries the state-independent contextuality, with contextual fraction $1/\Phi_4 = 1/10$, so the vertex figures $9, 10, 12$ are exactly the qutrit phase space, its contextual denominator, and its context count. (Witness: `analysis/w33_hesse_mermin_contextuality.py`.)

C.6 The Eisenstein tower qutrit $\to$ E6 $\to$ E8, the Golay gap, and the quadrangle ladder

The Witting body extends downward into a complete Eisenstein ladder. The regular complex polytopes over $\mathbb{Z}[\omega]$ nest as face/vertex-figure:

polytope	dim	vertices	symmetry
$3\{3\}3$ (Möbius–Kantor)	2	8	$24 = \lvert 2T\rvert = f$
$3\{3\}3\{3\}3$ (Hessian)	3	27	$648 = 27f$
$3\{3\}3\{3\}3\{3\}3$ (Witting)	4	240	$155520 = q\,\lvert\mathrm{Sp}(4,3)\rvert$

with orders multiplying by the next vertex count ($24 \cdot 27 = 648$, $648 \cdot 240 = 155520$). The middle rung's 27 vertices are the 27 lines on a cubic surface = the minuscule E_6 rep, and its automorphism group is $W(\mathrm{E}_6)$ with $|W(\mathrm{E}_6)| = 51840 = |\mathrm{Sp}(4,3)|$. Thus the single qutrit (Hesse, 9), E_6 (Hessian, 27), and E_8 (Witting, 240) are three rungs of one tower, and 27 is exactly the E_6 matter of $v = 40 = 1 + 12 + 27$. (Witness: `analysis/w33_hessian_polytope_e6.py`.)

The vertex-figure gap $n = 11 = K_{12}$ is not empty algebraically. Its $12 = k$ vertices carry the substrate's natural $q = 3$ code, the *ternary Golay* $[12, 6, 6]_3$: $3^6 = 729$ codewords, weight enumerator $1 + 264x^6 + 440x^9 + 24x^{12}$, minimum distance 6 (verified by enumeration). Its 132 weight-6 hexads are the Steiner system $S(5, 6, 12)$ with Mathieu group M_{12}, and doubling $k = 12 \to f = 24$ gives the binary Golay $[24, 12, 8]$, M_{24}, $S(5, 8, 24)$ — the $c = 24$ Monster charge. The Grünbaum gap is the ternary M_{12} half of the substrate's M_{24}/Golay/Monster structure. (Witness: `analysis/w33_ternary_golay_m12_grunbaum.py`.)

Finally, $W(3,3) = \mathrm{GQ}(3,3)$ sits in a quadrangle ladder 27–40–45. $\mathrm{GQ}(2,4)$ has 27 points = the 27 lines on a cubic (= E_6; intersection graph $\mathrm{SRG}(27, 10, 1, 5)$, collinearity the complement Schläfli graph $\mathrm{SRG}(27, 16, 10, 8)$), with $\mathrm{Aut} = W(\mathrm{E}_6) = 51840 = |\mathrm{Sp}(4,3)|$ — the group of the $D = 5$ E_6 black-hole/qubit entropy. The substrate $\mathrm{GQ}(3,3)$ is $\mathrm{SRG}(40, 12, 2, 4)$, and $\mathrm{GQ}(4,2)$ (the dual, 45 points) is the other flank; the four-qubit $W(7,2)$ carries the same 27/45 split through its 135 $\mathrm{DW}(5,2)$. (Witness: `analysis/w33_generalized_quadrangle_ladder.py`.)

C.7 A guardrail on the 27, and the Klein quartic as the E7 rung

Two honest refinements close this arc. *First, a guardrail.* It is tempting to read $v = 40 = 1+12+27$ as realising the E_6/27-lines Schläfli graph inside $W(3,3)$. It does *not*: fixing a point of GQ(3, 3), the 12 collinear points induce $4K_3$ and the 27 non-collinear points induce an 8-regular graph that is *not* strongly regular — in particular not the 16-regular Schläfli graph SRG(27, 16, 10, 8). So $40 = 1 + 12 + 27$ is an exact count (the matter cone $28 = 1 + 27$), and 27 matches the E_6 representation dimension and the GQ(2, 4) point count, but it is *not* a subgraph embedding. The genuine bridge is group-theoretic: the substrate's projective gauge group and the E_6 group are the same simple group $U_4(2) = PSp(4, 3) = PSU(4, 2)$, of order 25920, with $Sp(4, 3) = 2.U_4(2)$, $W(E_6) = U_4(2){:}2$, and $\mathrm{Aut}(GQ(2, 4)) = U_4(2){:}2$ all order 51840. (Witness: `analysis/w33_27_not_schlafli_group_bridge.py`.)

Second, the E7 rung. The genus-3 Klein quartic $x^3y+y^3z+z^3x$ — the first $\{3, 7\}$ Hurwitz rung — carries E_7. Its automorphism group PSL(2, 7) acts transitively on three distinguished point-sets that are all substrate integers:

$$24 \text{ Weierstrass} = f, \quad 28 \text{ bitangents} = \mu\Phi_6 \ (= 1 + 27), \quad 84 \text{ sextactic} = k\Phi_6.$$

The 28 bitangents are the E_7 datum: the minuscule rep has dimension $56 = 2 \cdot 28 = v + k + \mu$, which is exactly the number of triangular faces of the Klein map. So the exceptional trinity

$$27 \text{ lines (cubic)} \to E_6, \quad 28 \text{ bitangents (quartic)} \to E_7, \quad 120 \text{ tritangents} \to E_8 \ (= 120 \text{ icosians}, \ 240 = 2{\cdot}120),$$

closes the substrate's exceptional ladder, with Weyl orders $|W(E_6)| = 51840 = |Sp(4, 3)|$, $|W(E_7)| = 56 \cdot 51840$, and $|W(E_8)| = 240 \cdot |W(E_7)| = 696729600$ — the multipliers being 56 ($= 2\times$ bitangents) and 240 ($= |E|$ = E8 roots = Witting vertices). The Hessian polytope (E_6), the Klein quartic (E_7), and the Witting body (E_8) are the three exceptional rungs of one qutrit tower. (Witness: `analysis/w33_klein_quartic_e6_e7_trinity.py`.)

C.8 The three exceptional rungs made explicit

Each rung of $E_6 \to E_7 \to E_8$ can now be built and verified. E_6 *as trinification.* The guardrail showed the 27 does not sit in $W(3, 3)$; it sits in GQ(2, 4) — the Schläfli graph SRG(27, 16, 10, 8), group $W(E_6) = U_4(2){:}2$ — and its substrate content is trinification,

$$27 = (3, \bar{3}, 1) + (1, 3, \bar{3}) + (\bar{3}, 1, 3) = 9 + 9 + 9,$$

three bifundamental nonets under $SU(3)^3 \rtimes S_3$. Each nonet is $\mathbb{F}_3 \times \mathbb{F}_3 = AG(2, 3)$, a Hesse single-qutrit phase space, and the S_3 triality permuting them is the three generations. So the 27-lines/E_6 is three Hesse-9s welded by triality. (Witness: `analysis/w33_e6_trinification_schlafli.py`.)

E_7 *as a symplectic space.* The 28 bitangents of the Klein quartic are its 28 odd theta characteristics (Arf = 1) in $\mathbb{F}_2^6$: enumerating the Arf invariant gives 28 odd + 36 even = 64. The group $Sp(6, 2) = W(E_7)/\{\pm 1\}$ (order 1451520, half of $|W(E_7)| = 2903040$) permutes the 28 transitively, and the minuscule $56 = 2 \cdot 28 = v + k + \mu$ — the Freudenthal symplectic double — is the Klein map's 56 faces. (Witness: `analysis/w33_e7_theta_bitangents.py`.)

E_8 *as the icosians.* The trinity's E_8 rung, "120 tritangents," is the 120 icosians: 8 units + 16 half-units + 96 golden even-permutations, all unit quaternions, closed under quaternion multiplication (all 14400 products checked) — the binary icosahedral group $2I$, the 600-cell vertices. The icosian construction gives $240 = 2 \cdot 120$ E8 roots = the Witting vertices, so alongside the Eisenstein weld ($\omega = C^{10} \to 40$ rays) the quaternionic weld gives $E_8 = 2I$-doubled = the Witting body, with the 600-cell the Boerdijk–Coxeter clock. One body, two arithmetics — Eisenstein ($q = 3$) and icosian (golden quaternion). (Witness: `analysis/w33_icosian_e8_witting.py`.)

C.9 The magic square, the complex Leech, and the icosian clock

These exceptional rungs sit inside three larger frames. *The magic square.* $\mathrm{E}_6, \mathrm{E}_7, \mathrm{E}_8$ are the octonion row of the Freudenthal–Tits magic square (dims $78, 133, 248$), and the substrate's two welded arithmetics are its $\mathbb{C}$ and $\mathbb{H}$ columns: Eisenstein ($q = 3$) gives $\mathrm{E}_6 = \mathrm{magic}(\mathbb{O}, \mathbb{C})$ (the Hessian/ trinification 27), the icosian (quaternion) gives $\mathrm{E}_7 = \mathrm{magic}(\mathbb{O}, \mathbb{H})$, and $\mathrm{E}_8 = \mathrm{magic}(\mathbb{O}, \mathbb{O})$. The 27 is the exceptional Jordan algebra $J_3(\mathbb{O}) = 3 + 3 \cdot 8 = q + f$ (three diagonal reals, 24 off-diagonal octonions), whose cubic norm is the $D = 5$ black-hole entropy, and the 56 is its Freudenthal triple. (Witness: `analysis/w33_magic_square_substrate.py`.)

The complex Leech. One level above E_8, the same fixed-point-free order-3 ω that welds E_8 makes the 24-dimensional Leech lattice $12 = k$-dimensional over the Eisenstein integers — the complex Leech, with automorphism group $6.\mathrm{Suz} \leq \mathrm{Co}_0 = 2.\mathrm{Co}_1$. The Suzuki chain $\mathrm{G}_2(2) \to \mathrm{J}_2 \to \mathrm{G}_2(4) \to \mathrm{Suz}$ (on $36, 100, 416, 1782$ points) *starts* at $\mathrm{G}_2(2) = \mathrm{U}_3(3){:}2$, $|\mathrm{G}_2(2)| = 12096 = 168 \cdot 72$ — the split Cayley hexagon, the three-qubit contextuality core — and climbs to Suz, the complex Leech group. So the substrate's $q = 3$ Eisenstein arithmetic threads E_8 (8d) $\to$ complex Leech ($12 = k$ complex $= 24 = f$ real) $\to \mathrm{Co}_0 \to$ Monster ($c = 24 = f$), with the three-qubit hexagon as its first rung. (Witness: `analysis/w33_complex_leech_suzuki_chain.py`.)

The icosian clock. Finally the runtime closes on the 600-cell: its 120 vertices are the gate set $2I$, its 600 tetrahedral cells are 20 rings of 30 (the Boerdijk–Coxeter beat, $30 = h(\mathrm{E}_8)$), its $720 = 6!$ edges are the supercycle width, and its $240 = 2 \cdot 120$ E8 roots/Witting vertices are the mirror-bus addresses — so $2160 = 30 \cdot 72$ and $51840 = 24 \cdot 30 \cdot 72 = 720 \cdot 72 = |\mathrm{Sp}(4, 3)|$ are the polytope's own counts. The machine's clock *is* the icosian 600-cell. (Witness: `analysis/w33_icosian_600cell_runtime.py`.)

C.10 The ceiling, the Suzuki tower, and the G2 thread

The climb tops out, telescopes, and is held together by one group. *The ceiling.* The complex-Leech / Co0 tower ends at the Monster $M = \mathrm{Aut}(V^\natural)$, the $c = 24$ holomorphic CFT, whose graded dimension is $J = j - 744 = q^{-1} + 196884q + \dots$ with the moonshine head $196884 = 1 + 196883$ and $21493760 = 1 + 196883 + 21296876$. Its central charge $c = 24 = f$ is exactly the Holonet holographic boundary charge, so the qutrit machine's boundary CFT is the Monster and $f = 24$ is the tower's moonshine constant. (Witness: `analysis/w33_monster_moonshine_ceiling.py`.)

The Suzuki tower. The chain $\mathrm{G}_2(2) \to \mathrm{J}_2 \to \mathrm{G}_2(4) \to \mathrm{Suz}$ is the automorphism tower of four nested strongly regular graphs, $\mathrm{SRG}(36, 14, 4, 6) \prec \mathrm{SRG}(100, 36, 14, 12) \prec \mathrm{SRG}(416, 100, 36, 20) \prec \mathrm{SRG}(1782, 416, 100, 96)$, in which each valency is the previous vertex count and each λ the previous valency, so the parameters telescope $14 < 36 < 100 < 416 < 1782$. The base $\mathrm{SRG}(36, 14, 4, 6)$ anchors the substrate: its 36 vertices are the *even* theta characteristics of the Klein quartic (the E_7 companion of the 28 bitangents), and its valency $14 = \dim \mathrm{G}_2$. (Witness: `analysis/w33_suzuki_tower_srg.py`.)

The G2 thread. $\mathrm{G}_2 = \mathrm{Aut}(\mathbb{O})$ recurs at every level, keyed by the heptad $\Phi_6 = 7$: its 7-dim rep is the Fano plane (the imaginary octonions); $\dim \mathrm{G}_2 = 14 = 2\Phi_6$ is the genus of the $\{3, 7\}$ Hurwitz triplet; $\mathrm{G}_2(2) = 12096$ is the split Cayley hexagon (the three-qubit core, $\mathrm{SRG}(36, 14)$ valency $= \dim \mathrm{G}_2$); $\mathrm{G}_2(4)$ is the Suzuki rung; and the octonion column gives $\mathrm{E}_8 = \mathrm{magic}(\mathbb{O}, \mathbb{O})$. So one group, keyed by $7 = \Phi_6$, runs Fano $\to$ genus-14 $\to$ three-qubit $\to$ Suzuki $\to \mathrm{E}_8$. (Witness: `analysis/w33_g2_thread.py`.)

C.11 The ledger, the Standard Model, and the tower as one figure

Three closing moves keep the climb honest, turn it toward physics, and draw it. *The ledger.* The tower is a large set of exact mathematical facts wearing substrate labels, and intellectual honesty requires saying which is which: most rungs (the magic square, the trinity, the complex Leech, the Monster) are FRAMEWORK — true theorems annotated with substrate integers, where the annotation is a dictionary, not a derivation; a smaller set (the genus/register formulas, the Eisenstein E_8 weld, the icosian group closure, the ternary Golay, the theta-Arf count, the $W(3,3)$ geometry and its guardrail) is DERIVED — structures literally computed from $q = 3$ and checked; and the falsifiable physics (masses, CMB, contextual fraction, pump Chern) is a separate MEASURABLE layer. *A FRAMEWORK rung being exact confirms a number coincidence is a real theorem; it does not confirm the physics — only the measurable layer can.* (Witness: `analysis/w33_exceptional_tower_ledger.py`.)

The Standard Model. The exceptional E_6 sits at the head of the trinification chain $E_6 \to \mathrm{SU}(3)_C \times \mathrm{SU}(3)_L \times \mathrm{SU}(3)_R \rtimes S_3 \to \mathrm{SU}(3) \times \mathrm{SU}(2) \times \mathrm{U}(1)$, with substrate-clean dimensions: the trinification adjoint is $3 \cdot 8 = 24 = f$ and the Standard-Model gauge dimension is $8+3+1 = 12 = k$. The 27 is one generation ($9 + 9 + 9 =$ quarks/leptons/Higgs) and the three generations are the S_3 triality of the three SU(3) factors — not inserted, but the same triality that permutes the three Hesse nonets. So f and k bookend the breaking from the exceptional 27 to the Standard Model. (Witness: `analysis/w33_standard_model_from_trinification.py`.)

The figure. The whole session is one ascending ladder — $q = 3 \to$ genus/ register tower $\to$ Witting body $\to E_6/E_7/E_8 \to$ complex Leech $\to \mathrm{Co}_0 \to$ Monster ($c = 24$), with a downward branch to the Standard Model — run the full height by three threads (the Eisenstein order-3 ω, $G_2 = \mathrm{Aut}(\mathbb{O})$, and the simple group $U_4(2) = \mathrm{PSp}(4,3)$). It is drawn in `docs/w33_exceptional_tower.dot` and rendered to `docs/w33_exceptional_tower.svg`. (Witness: `analysis/w33_exceptional_tower_synthesis.py`.)

C.12 The measurable layer: a scorecard and a unification [Faces 2, 3, 7]

Following the ledger's rule that only the measurable layer falsifies, two quantitative tests. *The scorecard.* With $N = 2(v - \Phi_4) = 60$ e-folds the substrate's cosmological predictions are $n_s = 1 - 2/N = 29/30$, $r = k/N^2 = 1/300$, $f_{NL} = 5/(6N) = 1/72$, running $-2/N^2 = -1/1800$, together with $\Omega_{DM}/\Omega_b = 82/15$, $m_{\beta\beta} \approx 2.3\,\mathrm{meV}$, and $\sum m_\nu \approx 0.101\,\mathrm{eV}$. Against mid-2026 data these are mostly CONSISTENT (n_s at $\sim 0.4\sigma$ of Planck; r below the BICEP/Keck bound and testable by LiteBIRD), but one is in honest TENSION: $\sum m_\nu \approx 0.101\,\mathrm{eV}$ satisfies Planck ($< 0.12\,\mathrm{eV}$) yet exceeds the DESI 2024 bound ($< 0.072\,\mathrm{eV}$) — a genuine falsification handle, not a confirmation. (Witness: `analysis/w33_measurable_scorecard_2026.py`.)

The unification. The same S_3 triality that gives the three generations unifies the gauge couplings: it forces $g_C = g_L = g_R$ at the trinification scale, and the GUT hypercharge normalization $g_1^2 = \frac{5}{3} g'^2$ then fixes

$$\sin^2 \theta_W = \frac{g'^2}{g^2 + g'^2} = \frac{3/5}{1 + 3/5} = \frac{3}{8}$$

at unification — the canonical SU(5)/SO(10)/E_6 value — running to the measured ≈ 0.231 at M_Z (with the usual $\sim 10\%$ one-loop non-SUSY gap that the trinification thresholds must close). So the three generations and coupling unification are one triality. (Witness: `analysis/w33_trinification_unification.py`.)

C.13 Three live tests, scrutinised

The neutrino tension, both ways. The scorecard's one red flag deserves honest scrutiny. Externally, $\sum m_\nu \approx 0.10\,\text{eV}$ is in $\sim$1.5–2σ tension with the tight DESI-2024 ΛCDM bound ($< 0.072\,\text{eV}$) but *consistent* with the looser w_0w_aCDM bound ($\lesssim 0.16\,\text{eV}$) that DESI's own data prefer — so whether the theory is falsified here depends on the dark-energy model. Internally, a naive geometric mass cascade ($r = 0.5225$) predicts $\Delta m^2_{21}/\Delta m^2_{31} = 0.21$ against the observed 0.030, a factor ~ 7 too large, so the substrate's neutrino masses are *not* a simple geometric cascade and that model must be revisited. Both flags are recorded, not smoothed. (Witness: `analysis/w33_neutrino_desi_scrutiny.py`.)

Unification, honestly. Minimal one-loop SM running does not unify — the couplings meet pairwise at $\sim 10^{13}, 10^{14}, 10^{17}\,\text{GeV}$, a $\sim$4-order spread. The two-step chain $\text{E}_6 \to \text{SU}(3)^3 \to \text{SM}$ inserts one intermediate scale, giving two free scales that fit the two low-energy constraints ($\sin^2\theta_W$ and α_s); so trinification unifies, with $\sin^2\theta_W = 3/8$ the exact boundary, at the price of predicting M_I and M_{GUT} — the honest status of every non-SUSY GUT. (Witness: `analysis/w33_trinification_two_step_unification.py`.)

The demonstrator as a meter. The benchtop layer makes two substrate constants directly measurable: the contextual fraction of a two-qutrit Kochen–Specker measurement on the 40 $W(3,3)$ rays is $1/\Phi_4 = 1/10$ (reading out $\Phi_4 = 10$), and the Thouless-pump Chern number on the qutrit GKP ladder is $C = 2S = \lambda = 2$ (reading out λ). Both are integer/unit-fraction — robust, calibration-free — so a measured 1/10 and 2 confirm the substrate's contextuality and topology, and any deviation falsifies them on a table. (Witness: `analysis/w33_demonstrator_substrate_constants.py`.)

C.14 Fixing the neutrino, predicting the proton, and the balance sheet

The neutrino, fixed. The DESI tension was a model artifact. The geometric cascade mismatched the Δm^2 hierarchy (0.21 vs 0.030) and forced $\sum m_\nu \approx 0.10\,\text{eV}$; the substrate's type-I seesaw with a hierarchical Dirac Yukawa instead *squares* the hierarchy, driving the lightest mass small. For strong normal ordering ($m_1 \lesssim 0.009\,\text{eV}$) the spectrum is fixed by oscillation data and $\sum m_\nu \approx 0.06\,\text{eV}$ — below the DESI bound, so the tension is *resolved* — with $m_{\beta\beta} \approx$ 2–4 meV. The corrected prediction is $\sum m_\nu \approx 0.06\,\text{eV}$ (strong NO), not 0.10. (Witness: `analysis/w33_neutrino_seesaw_texture.py`.)

The proton. The two-step fit gives $M_{\text{GUT}} \sim 10^{16}\,\text{GeV}$, so $\tau_p \sim (1/\alpha^2_{\text{GUT}})M^4_{\text{GUT}}/m^5_p \approx 4.6 \times 10^{35}\,\text{yr}$ via $p \to e^+\pi^0$ — above the Super-Kamiokande bound ($2.4 \times 10^{34}\,\text{yr}$, which already requires $M_{\text{GUT}} \gtrsim 10^{15.7}\,\text{GeV}$) and within Hyper-Kamiokande's reach. A sharp falsifiable GUT-scale prediction. (Witness: `analysis/w33_proton_lifetime_gut_scale.py`.)

The balance sheet. After building, auditing, applying, testing, and scrutinising the tower: the cosmological and electroweak predictions are CONSISTENT; the one DESI tension is FIXED; proton decay, the contextual fraction 1/10, and the pump Chern 2 are TESTABLE near-term handles; the $q = 3 \to$ Monster tower is exact FRAMEWORK (a magnificent dictionary, not a confirmation of physics); and the open problems are the precise neutrino texture, the GUT scales, and — above all — the bridge from the framework to why these numbers are the physical world, which is the program's defining task. (Witness: `analysis/w33_state_of_the_theory.py`.)

C.15 Why $q = 3$, and one triality for the neutrino [Faces 1, 4]

The bridge: $q = 3$ is triply forced. The defining task — why is the $q = 3$ substrate the physical world? — has a sharp answer in the form of a convergence. Three independent first-principles

selections each return $q = 3$: (i) *geometric*, the master equation $q! = 2q$ is equivalent to $(q-1)! = 2$, whose unique solution is $q = 3$; (ii) *quantum-resource*, discrete Wigner negativity = contextuality = magic (the resource for quantum advantage) needs *odd prime* dimension, and the minimal odd prime is 3 (qubits are stabilizer-positive); (iii) *holographic*, a self-correcting holographic code needs the Monster boundary at $c = 24 = f = 8q$, which closes at $q = 3$. Geometry, quantum resource theory, and holography agree: the substrate is not one choice among many but the unique common solution. (Witness: `analysis/w33_q3_triple_selection.py`.)

One triality, the whole neutrino sector. The S_3 triality that permutes the three SU(3) factors — the three generations, and the unification condition $g_C = g_L = g_R$ giving $\sin^2\theta_W = 3/8$ — is, as a flavour symmetry, exactly the group producing tri-bimaximal PMNS mixing, $\sin^2\theta_{12} = 1/3$, $\sin^2\theta_{23} = 1/2$, $\sin^2\theta_{13} = 0$, close to the observed $0.304, \sim 0.5, 0.022$ (the small θ_{13} the Φ_3-scale deformation). The hierarchical seesaw then sets the scale (strong normal ordering, $\sum m_\nu \approx 0.06\,\text{eV}$). So generations, gauge unification, and neutrino mixing are one triality. (Witness: `analysis/w33_neutrino_tbm_s3.py`.)

The proton signature. The two-step fit gives $M_I \sim 10^{13.5}\,\text{GeV}$ and $M_{\text{GUT}} \sim 10^{16}\,\text{GeV}$; non-SUSY gauge-mediated decay makes $p \to e^+\pi^0$ the dominant channel (branching $\sim$ 30–60%, with $p \to \bar{\nu}K^+$ suppressed for lack of superpartners), and $\tau_p \approx 4.6 \times 10^{35}\,\text{yr}$ sits squarely in the Hyper-Kamiokande window. (Witness: `analysis/w33_proton_branching_two_scale.py`.)

C.16 Pass 1 — three closures: the neutrino matrix, the selection census, the threshold number

In plain language. *Three separate questions that closed in the same pass, grouped because they closed together and not because they are related. Read them independently; the neutrino material in particular is a numerical relation and not a derivation, and says so.*


Reading the next four subsections. They make four passes over three of the five faces of §C.1 — the **neutrino** (Face 3), the **selection** and its constants (Faces 1–2), and the **code** (Face 4) — each pass sharper than the last: closure (Pass 1), invariant (Pass 2), skeleton (Pass 3), and the cubic form / Witting degrees / measured curve (Pass 4). The same three threads run through all four; the fifth face, the demonstrator, ties them together at the end (§C.12 and the bridge witness).

Three sharper statements close gaps left open above.

(1) The neutrino texture, pinned to one matrix. The mixing pattern (§C.15) and the mass scale were established separately; an earlier single-parameter geometric cascade gave $\Delta m^2_{21}/\Delta m^2_{31} = 0.21$, about 7× the observed 0.030 — recorded honestly as a wrong-model flag. That flag is now closed by a *single* matrix. The S_3 triality forces the Majorana mass matrix into μ–τ-symmetric + *magic* (constant row-sum) form, whose eigenvectors are exactly the tri-bimaximal columns, so the angles are fixed by symmetry rather than fitted; crucially that form carries *two* independent mass scales, so it fits *both* Δm^2 where the one-scale cascade could not. Diagonalising the exact TBM matrix numerically returns $\sin^2\theta = (1/3, 1/2, 0)$ and $\Delta m^2_{21}/\Delta m^2_{31} = 0.030$ to machine precision; adding the substrate $\Phi_3 = 13$ deformation moves the angles to $(4/13, 7/13, 2/91)$, close to the observed $(0.307, 0.546, 0.0220)$, with the ratio unchanged. (Honest: the two scales are fixed by the two measured Δm^2, so this is the unique substrate-symmetric matrix consistent with the data — a closure demonstration, not an absolute-mass prediction. Witness: `analysis/w33_neutrino_texture_pinned.py`.)

The ratio as a partial prediction. The closure above fixes the two mass scales from the two measured Δm^2; the ratio can instead be *predicted*. Feeding the substrate's own mild Yukawa

hierarchy — up-type singular values $10:5:1$ (Pillar 68), with $Y_\nu = Y_{\text{up}}$ at the GUT scale — into a type-I seesaw with a minimal flat S_3-symmetric M_R, with *no* neutrino-sector input, the seesaw squares the hierarchy and returns $\Delta m^2_{21}/\Delta m^2_{31} \approx 0.062$: the right strong-normal-ordering order of magnitude, a factor ~ 2 from the observed 0.030; the down-type ratios $6:2:1$ give 0.012, so the observed value is *bracketed* (against the 0.21 — a factor 7 — of the geometric cascade). The residual factor ~ 2 is named, not removed: the M_R texture and $Y_\nu \neq Y_{\text{up}}$ running. So the strong ordering and order of magnitude are predicted from the substrate hierarchy. (Witness: `analysis/w33_neutrino_seesaw_prediction.py`.)



two independent mass scales ⇒ fits *both* Δm^2: $\Delta m^2_{21}/\Delta m^2_{31} = 0.030$ (observed), *not* the 0.21 of the one-scale cascade

Figure 10: The neutrino sector closed by one matrix. The S_3 triality forces the mass matrix into μ–τ-symmetric + magic form, whose eigenvectors are the tri-bimaximal columns; because that form carries two independent mass scales it fits both Δm^2 (the one-scale geometric cascade could not). The $\Phi_3 = 13$ deformation moves the angles onto the observed values.

(2) The $q = 3$ selection census. The bridge is a convergence, and it is overdetermined: *five* independent first-principles selections return $q = 3$ by genuinely different mathematics — geometric $(q-1)! = 2$ (a forcing equation), minimal odd prime (a minimality fact), holographic $c = 24 = 8q$ (a charge match to the Monster ceiling), thermodynamic de Sitter closure $2(q-1)(q^2+1) = (1+q)(1+q^2) \Leftrightarrow (q-3)(q^2+1) = 0$ (a cubic, a *different* polynomial from the factorial, so not one equation in disguise), and a new *Eisenstein complex-polytope* selection: the regular complex polytopes with order-3 reflections over $\mathbb{Z}[\omega]$ form the exceptional tower Möbius–Kantor $3\{3\}3$ (8 vertices, $2T$) → Hessian $3\{3\}3\{3\}3$ (27 = lines on a cubic = E_6) → Witting $3\{3\}3\{3\}3\{3\}3$ (240 = E_8 roots), with Witting symmetry the Shephard–Todd group #32 of order $155520 = 3 \times |\mathrm{Sp}(4,3)|$. The symplectic orders were verified directly in GAP: $|\mathrm{Sp}(4,3)| = 51840$, $|\mathrm{PSp}(4,3)| = 25920 = |U_4(2)|$, and $3 \times 51840 = 155520$. (Witness: `analysis/w33_q3_selection_census.py`.)

The Eisenstein selection is forced, and it equals the magic-dimension selection. The polytope entry can be upgraded from a realization to a forcing intersection. The crystallographic restriction $\phi(p) = 2$ admits exactly the genuinely-complex periods $p \in \{3, 4, 6\}$ (Eisenstein 3, 6 over $\mathbb{Z}[\omega]$, Gaussian 4 over $\mathbb{Z}[i]$); requiring the reflection order to be *prime* — the minimal-magic / clean-qudit condition of the resource selection — leaves $p = 3$ uniquely, since $4 = 2^2$ and $6 = 2 \cdot 3$ are composite. So the geometric lattice condition and the quantum-resource prime condition, independent in origin, intersect at a single $p = 3$: two of the five census selections collapse into one forcing statement, realized by $\mathbb{Z}[\omega]$ and the Witting polytope. (GAP-verified: $\phi^{-1}(2) \cap [3, \infty) = \{3, 4, 6\}$, prime part $\{3\}$. Witness: `analysis/w33_eisenstein_forcing.py`.)

(3) The fault-tolerance threshold as a lab number. The architecture's hardest residual — the absolute FT threshold — becomes concrete once the substrate-fixed code lattice meets the measured square-GKP threshold. The best reported square-GKP + surface-code threshold is 9.9 dB of squeezing (Noh–Chamberland 2022; 11.2 dB under minimum-weight matching), and 9.5 dB has already been demonstrated in hardware. The substrate code is *not* the square code: its single-mode lattice is hexagonal A_2 (coding gain 0.6 dB), its natural two-mode code is D_4 (1.5 dB), and its four-mode code is E_8 (3.0 dB), so the threshold shifts down to $\sim 9.3/8.4/6.9$ dB respectively — all at or below the 9.5 dB already reached. Universality needs only the minimal Lloyd–Braunstein set, Gaussian (degree-2, the $\mathrm{Sp}(4,3)$ Weil rep) plus one cubic gate (degree-3, E_6), with cubic-phase




Figure 11: The $q = 3$ selection census: five first-principles selections, each a different kind of mathematics (two forcing equations of distinct degree, a minimality fact, a holographic charge match, and the Eisenstein complex-polytope tower $2T \to E_6 \to E_8$), all return $q = 3$. The substrate value is overdetermined.

magic states the sole distilled resource. The falsifiable target: a D_4-GKP photonic demonstrator should cross fault tolerance near 8–9 dB; no threshold at the coding-gain-reduced squeezing, or no D_4 advantage over $\mathbb{Z}^4$, falsifies the substrate-code claim. (Honest: the single-mode A_2 shift is exact; the multimode numbers are nominal upper bounds pending a full circuit-level FT simulation. Witness: `analysis/w33_holonet_ft_threshold_budget.py`.)




Figure 12: The fault-tolerance threshold as a lab number. The measured square-GKP + surface-code threshold (9.9 dB, Noh–Chamberland 2022; 11.2 dB under minimum-weight matching) is lowered by the substrate lattices' coding gains to $\sim$ 9.3/8.4/6.9 dB for $A_2/D_4/E_8$ — all at or below the 9.5 dB squeezing already demonstrated in hardware. (Multimode D_4/E_8 values are nominal upper bounds; the single-mode A_2 shift is exact.)

C.17 Pass 2 — sharper: a Majorana invariant, a cyclotomic merge, a code curve

Each of the three closures admits a sharper statement.

The neutrino factor of two closes on a substrate invariant. In the tri-bimaximal basis the seesaw gives $m_i = y_i^2/r_i$ with y_i the Dirac and r_i the Majorana eigenvalues. The substrate Dirac hierarchy $(1, 5, 10)$ with a flat M_R overshoots the mass-squared ratio by the factor ~ 2 above. The Majorana

eigenvalue ratio the seesaw needs is $r_2/r_3 = 1.45$ — which is the substrate number $\Phi_3/q^2 = 13/9 = 1+1/q+1/q^2$, the same $\Phi_3 = 13$ that deforms the PMNS angles. Fixing $r_2/r_3 = \Phi_3/q^2$ (not fitted) gives $\Delta m^2_{21}/\Delta m^2_{31} = 0.030$, $m_2 = 8.6\,\text{meV} = \sqrt{\Delta m^2_{21}}$, and $\sum m_\nu \approx 59\,\text{meV}$ — the observed strong ordering. (Honest: this Majorana ratio is substrate-motivated and gives exact agreement, but it is an input here; deriving it from the $\mathbb{Z}_3$-graded Majorana coupling is the open step. Witness: `analysis/w33_neutrino_majorana_texture.py`.)

Two of the selections are one cyclotomic structure. The de Sitter and the crystallographic/Eisenstein selections are not independent. The de Sitter closure cubic factors as $(q-3)\,\Phi_4(q)$ with $\Phi_4(q) = q^2+1$ (complex roots $\pm i = \zeta_4$, the Gaussian period); the crystallographic periods $\{3,4,6\}$ are exactly the three degree-two cyclotomics $\{\Phi_3, \Phi_4, \Phi_6\}$; and Φ_4 already factors the $\mathrm{GQ}(q,q)$ point count $v = (q+1)\Phi_4(q)$ ($= 40$ at $q = 3$). So the census's "five independent" selections are honestly *four* independent plus one cyclotomic refinement, and $q = 3$ is the unique real prime the structure admits — a tighter convergence, not a weaker one. (Witness: `analysis/w33_desitter_crystallographic_unify.py`.)

The D_4 code as a measured curve. The threshold number has an explicit code and curve behind it. The D_4 stabilizer lattice $\{x \in \mathbb{Z}^4 : \sum x_i \text{ even}\}$ (generators $\times\sqrt{\pi}$) has exact invariants $d^2_{\min} = 2$, $\det = 4$, kissing 24, coding gain 1.5 dB; under iid displacement noise the logical-error curve $P_L(s)$ is the square-code curve shifted left by exactly that 1.5 dB (Fig. 13), so D_4 reaches any target error at up to 1.5 dB less squeezing and the surface-GKP threshold 9.9 dB becomes ~ 8.4 dB — below the 9.5 dB already demonstrated. The relative D_4-versus-square advantage is the falsifiable handle. (Honest: the lattice quantities are exact and the 1.5 dB is the low-error *asymptote*; a real closest-point decoder shows the finite-error advantage is smaller — see §C.18. Witness: `analysis/w33_d4_gkp_error_curve.py`.)




Figure 13: The D_4-GKP logical-error curve as a spec. Logical error P_L versus GKP squeezing for the substrate D_4 code (dashed) and the trivial square code (solid), in the union-bound effective-distance model. The D_4 curve is the square curve shifted left by its *asymptotic* 1.5 dB coding gain. This idealised constant shift is corrected by a real decoder in §C.18 (Fig. 14): the actual advantage is error-rate dependent and smaller at realistic error rates.

C.18 Pass 3 — deeper: a cyclotomic skeleton, a projective Majorana ratio, a decoder correction

Digging beneath the three closures turns up one structure, one geometric meaning, and one honest correction.

The substrate constants are degree-two cyclotomics, and they do double duty. The selections that pick $q = 3$ and the constants that the substrate runs on are the same object. The three degree-two cyclotomic polynomials, evaluated at the selected field, are

$$\Phi_3(3) = 13, \qquad \Phi_4(3) = 10, \qquad \Phi_6(3) = 7, \qquad 13 + 10 + 7 = 30 = h(E_8),$$

i.e. the substrate's core invariants (register $\Phi_3 = 13$, the Sp(4) $\theta = 10$, the Fano/Hurwitz 7), summing to the E_8 Coxeter number. The same $\{\Phi_3, \Phi_4, \Phi_6\}$ skeleton *selects* $q = 3$: its indices $\{3, 4, 6\}$ are the crystallographic periods, and $\Phi_4(q) = q^2{+}1$ factors both the de Sitter cubic $(q{-}3)\Phi_4$ and the GQ point count $(q{+}1)\Phi_4 = 40$. So the census is honestly one deep cyclotomic object (which both selects $q = 3$ and generates $\{13, 10, 7\}$) plus three genuinely independent confirmations — the factorial $(q - 1)! = 2$, the minimal odd prime, and the central charge $c = 24 = q^3 - q = |2T|$ — which reference $q = 3$ but do not reduce to the cyclotomics. (Witness: `analysis/w33_cyclotomic_skeleton_census.py`.)

The Majorana ratio is projective over affine. The neutrino number $\Phi_3/q^2 = 13/9$ has a geometric meaning. A single-grade B–L breaking VEV forces, by the $\mathbb{Z}_3$ grade rule, the Majorana texture $M_R = [[A, 0, 0], [0, 0, C], [0, C, 0]]$ with eigenvalues $\{A, \pm C\}$ — exactly degenerate, so it cannot give the observed non-degenerate neutrinos; a splitting is mandatory. The splitting that works is $r_2/r_3 = |\mathrm{PG}(2, 3)|/|\mathrm{AG}(2, 3)| = 13/9$: the democratic (trivial-rep) right-handed neutrino couples to all $\Phi_3 = 13$ projective points, the others to the $q^2 = 9$ affine ones. Since $\Phi_3 = 13 = \Phi_3(3)$, the neutrino hierarchy is fixed by the very cyclotomic skeleton that selects $q = 3$. (Honest: the degeneracy is exact and 13/9 now has a geometric meaning, but identifying M_R's eigenvalues with these counts from the cubic form is still open. Witness: `analysis/w33_majorana_grade_derivation.py`.)

A real decoder corrects the threshold advantage. Replacing the union-bound shift with an actual Conway–Sloane closest-point decoder over sampled Gaussian noise (both codes at equal density) shows the D_4-versus-square advantage is *error-rate dependent*: it grows from ~ 0.6 dB at logical error 3×10^{-2} to ~ 0.9 dB at 10^{-3}, tracking the union bound *with* kissing numbers (D_4's 24 versus the square's 8 suppresses the finite-error gain) and reaching the nominal 1.5 dB only asymptotically. So the constant-1.5 dB curve was the low-error limit; the honest near-threshold advantage is ~ 0.7–1.0 dB, with the full coding gain realised deep below threshold. The qualitative claim — D_4 beats the square code and the threshold shifts down — survives; its size is error-dependent. (Witness: `analysis/w33_d4_decoder_montecarlo.py`.)

C.19 Pass 4 — deepest: the cubic form, the Witting degrees, and the measured curve

Pushed to the limit, each result either closes part-way or reveals a single deeper object.

The cubic form proves the degeneracy and bounds the rest. Computing the Majorana mass from the actual E_6 cubic invariant $c(\psi_a, \psi_b, \langle v \rangle)$ on the H_{27} profiles (Pillar 68), a grade-0 (S_3-symmetric) B–L VEV gives, with real substrate numbers $A = 0.0017$, $C = 0.0442$, the texture $M_R = [[A, 0, 0], [0, 0, C], [0, C, 0]]$ whose generation-$(1, 2)$ block is *exactly* degenerate — so the "a splitting is mandatory" step is now *proven* from the cubic form, not assumed. A grade-1/2 VEV lifts it to a genuine non-degenerate spectrum, and the natural symmetric VEVs give eigenvalue ratios ~ 1.25 — near, but not equal to, $\Phi_3/q^2 = 1.444$; the exact 13/9 needs a particular B–L

direction. So the qualitative claim is proven and the answer is bounded, while the exact 13/9 stays a structural interpretation. (Witness: `analysis/w33_majorana_cubic_form.py`.)

The substrate constants are the Witting degrees. The cyclotomic skeleton has a companion: the Witting complex reflection group (Shephard–Todd #32, the $q = 3$ Eisenstein polytope's symmetry, $|G| = 155520 = 3|\mathrm{Sp}(4,3)|$) has the four invariant degrees $\{12, 18, 24, 30\}$, whose product is $|G|$, and these are

$$12 = q(q{+}1) = k, \quad 18 = h(E_7), \quad 24 = q^3{-}q = |2T| = f = c, \quad 30 = h(E_8) = \Phi_3(3){+}\Phi_4(3){+}\Phi_6(3).$$

So the GQ degree, the E_7 and E_8 Coxeter numbers, and the holographic central charge are the Witting degrees, and the largest is the cyclotomic sum. In particular the holographic $c = 24$ is *not* an independent selection — it is the degree-24 of the Witting group, fixed by the same $q = 3$ Eisenstein structure. The census's honestly-independent arithmetic shrinks to two (the factorial and the primality) on top of one deep Eisenstein object. (Witness: `analysis/w33_witting_degrees_unify.py`.)

The advantage is a curve, measured to 10^{-6}. Variance-scaling importance sampling (validated against brute force at 10^{-3} to 0.0%) pushes the real Conway–Sloane decoder deep below threshold. The D_4-versus-square advantage grows $0.48 \to 0.74 \to 0.92 \to 1.03 \to 1.11 \to 1.17$ dB as the logical error falls $10^{-1} \to 10^{-6}$ (Fig. 14), tracking the union bound and reaching only ~ 1.2 dB even at 10^{-6} — the full 1.5 dB is realised only at far lower error. So the honest engineering spec is a curve: D_4 buys ~ 0.7 dB near threshold, ~ 1.2 dB at 10^{-6}, the full coding gain only asymptotically. (Witness: `analysis/w33_d4_advantage_curve.py`.)




Figure 14: The measured D_4-versus-square advantage as a function of target logical error, from a real Conway–Sloane closest-point decoder (importance-sampled below 10^{-3}, validated against brute force). The advantage is error-rate dependent — ~ 0.7 dB near threshold (10^{-2}), ~ 1.2 dB at 10^{-6} — approaching the nominal 1.5 dB coding gain (dashed) only asymptotically, because D_4's larger kissing number suppresses the finite-error gain. This corrects the constant-shift idealisation of Fig. 13.

C.20 Self-error-correction and why the primitive is one

The carrier is a single photon — not two, not a pack — and that is structural, not economical. Two ingredients explain why the universe's primitive is one.

Self-entanglement instead of inter-particle entanglement. A photon carries several internal registers (polarization, path, time-bin, frequency, transverse mode), and entanglement among them needs no second particle. Two ternary internal registers already give $\mathbb{C}^3 \otimes \mathbb{C}^3 = \mathbb{C}^9$ — the entire two-qutrit substrate register *inside one photon*. The geometry is realised within a single indivisible quantum, which is exactly the operator–operand self-duality of §81.

Self-error-correction, and no-cloning as a feature. A multi-photon code spreads one logical amplitude over many quanta that decohere *independently*; its redundancy is also its leak. A single photon cannot be cloned — and here that is the asset, not the obstacle: the logical amplitude is one indivisible excitation, with no independent copies to dephase against each other. Correction is then *internal* (a code among the photon's own registers) and *dynamical*, supplied by the drive. The Boerdijk–Coxeter loop (§90) is not a periodic clock but a genuine *time quasicrystal*: its twist $\theta = \arccos(-\frac{2}{3})$ is substrate-fixed — at $q = 3$, $-\frac{2}{3} = -(q-1)/q = 2 \cdot (-1/q)$, the pairwise vertex dot of the regular q-simplex (the tetrahedron = the q=3 simplex) — and the stroboscopic orbit $\{n\theta \bmod 2\pi\}$ obeys the Steinhaus three-gap law at every N (exactly two gaps at $n = 30 = h(E_8)$), is Weyl-equidistributed, and never recurs (Niven). It therefore carries two incommensurate frequencies $(\,2\pi,\ \theta\,)$, a pure-point spectrum: the quasiperiodically-driven (Fibonacci-type) setting whose emergent dynamical symmetry topologically protects an edge mode [6, 11]. The photon self-protects its logical qutrit through its own substrate-fixed drive — no copies, no external apparatus. And the protection is concrete, not merely analogical: two incommensurate drives realise *topological frequency conversion* [7], with energy pumped between the round-trip and twist drives at a quantised, dissipationless, perturbation-robust rate $\dot{W} = (C/2\pi)\,\omega_1\omega_2$ set by a Chern integer C. We compute it. Because the BC twist is a rotation (the holonomy group $2T \subset \mathrm{SU}(2)$), the qutrit carrier transforms as the spin-1 representation, and the spin-1 two-tone pump has band Chern numbers

$$(C_-, C_0, C_+) = (+2,\ 0,\ -2)$$

throughout the topological regime $0 < m < 2$ (computed by the Fukui–Hatsugai–Suzuki method; trivialising past the gap-closing at $m = 2$). The qutrit carrier therefore enjoys $|C| = 2$ — *double* the protection of a qubit ($|C| = 1$, also computed) — and the substrate fixes the two frequencies (round-trip and BC twist) squarely into this topological class. More generally a dimension-q carrier is spin $\frac{q-1}{2}$, so its extremal band Chern is $|C|_{\max} = q - 1 = \lambda$ (verified for $q = 2, 3, 4$: extremal $\pm 1, \pm 2, \pm 3$). The architecture does not choose q; it inherits $q = 3$ from the substrate physics ($q! = 2q$, KO-dimension $2q = 6$) and reaps the enhanced protection as a consequence. The *same* number $q - 1 = \lambda$ then wears three faces — it sets the BC drive ($\cos\theta = -(q-1)/q$), the self-protection ($|C| = q - 1$), and the photon's transverse helicity count ($2 = \lambda$). *(The quasicrystal structure — three-gap, incommensurate frequencies, non-recurrence — and the band Chern numbers are computed; the residual is only the realisation choice: the rotation drive gives $|C| = 2$, and a Heisenberg–Weyl clock-shift drive re-sorts the bands but stays in the nonzero topological class — the protection is generic, its strength $|C| = 2$ is the rotation realisation.)* (Witnesses: `analysis/w33_self_correction_quasicrystal.py`, `analysis/w33_topological_pump_test.py`, `analysis/w33_qutrit_topological_pump.py`.)

C.21 Why the primitive is one *massless* photon

One more layer answers *why a photon* and not some other quantum. Wheeler's one-electron universe (relayed to Feynman in 1940) imagined every electron as a single worldline weaving forward and backward through time. The holonet is the photonic version — one carrier, self-entangled past↔future — but masslessness makes it sharper, and the substrate *forces* the masslessness. Three facts lock together.

Null worldline, zero proper time. A massless carrier moves on $ds^2 = 0$, so its proper time $\tau = t\sqrt{1-\beta^2} \to 0$: its entire worldline is one proper-time instant, and its past and future are proper-time-*simultaneous*. That is exactly what lets a single photon entangle its past and future registers — a relation at one proper-time point. Wheeler's massive electron must literally weave; the massless photon is all-at-once. Self-reference wants masslessness.

Gauge invariance forces it. The photon is the gauge boson of the substrate connection of §85 — the one whose holonomy is the Clifford gates ($2T = \mathrm{SL}(2,3)$) and whose curvature is the gauge fields. The substrate gauge symmetry is unbroken (the holonomy is the full Clifford group), and gauge invariance forces an unbroken gauge boson to be massless, removing the longitudinal mode (Wigner's classification).

The helicity count is the substrate's. A massless vector has Wigner little group ISO(2) and exactly *two* transverse helicities ± 1; a massive vector has SO(3) and *three*. The carrier therefore has $2 = \lambda = q - 1$ polarisations — precisely the paper's photon-polarisation count λ — and only a massless carrier gives it. (Its clock is then the optical frequency: $\tau = 0$ but the phase $\phi = \omega t$ still accrues, so the time-bin/frequency registers — the very degrees of freedom that self-entangle — are the photon's internal clock. A testable corollary: in vacuum the self-entanglement carries no proper-time decoherence, i.e. its visibility is worldline-length independent up to lab-frame loss and dispersion.)

So self-reference (zero proper time), the substrate's unbroken gauge structure (masslessness), and the polarisation count ($\lambda = q-1$) all demand a single massless carrier. The universe's primitive is one photon. (Witness: `analysis/w33_why_one_massless_photon.py`.)

C.22 The single carrier, the geon, and the fractal of nested shells

This section records three architecture readings. The exact content of (i) is limited to finite group generation; the physical readings in (ii)–(iii) remain proposals requiring their own implementation evidence. *(i) Abstract switch generation.* The gate group $\mathrm{Sp}(4,3)$ has order 51840 and is 2-generated. A finite search over named symplectic generators finds 13 generating pairs, including $\langle F_2,\ F_1 \cdot CZ \rangle$, while the naive pair $\langle F_1, CZ \rangle$ generates only a subgroup of order 108. Here a "switch" is an abstract selected group generator: the result supplies a candidate control alphabet and distinguishes a successful pair from a failed one. It does not by itself compile either pair into an optical braid, a junction layout, or a calibrated control pulse.

The word-metric evidence is narrower and exact: a separate symmetric-BFS calculation checks four selected generating pairs and obtains diameter 14 for each, with mean word lengths 10.407 or 10.596. It does not establish that all 13 generating pairs have the same metric. A distinct eight-gate four-transvection set also has diameter 14, but that numerical agreement is not an identification of the two gate alphabets. The 72-tick ABI is likewise logically separate: it sequences, records, and checks finite packet transitions, whereas a switch word selects a group operation. An explicit hardware braid, loss model, and compiler from this abstract switch alphabet to a device remain additional construction problems. (Witness: `analysis/w33_hardware_compilation.py`.)

(ii) The carrier as its own self-contained shell. A single carrier recirculating in the closed loop is the informational analogue of Wheeler's *geon* (a self-bound electromagnetic field, a standing wave of two counter-propagating components held in a closed toroid): self-sourced energy, bent into a closed loop, recirculated *dissipationlessly* by the topological protection (the Chern $|C| = 2$ pump is the "superconducting" losslessness, the substrate lattice the "tilings"). A lossless reversible loop does unbounded computation on finite recirculated energy (Landauer: only erasure costs energy), which is the honest content of a "self-powered" carrier — unbounded *work*, with energy conserved, eternal from the null frame. (A single optical photon is ~ 56 orders from a literal *gravitational*

geon; that forms at the Planck scale, where the substrate's derived Einstein equations govern.)

(iii) The network is a fractal of nested shells. Replacing every one of the $v = 40$ sites by a fresh $W(3,3)$ core gives, at depth n, 40^n leaves and $(40^n - 1)/39$ nested $W(3,3)$ shells. Reading each shell as a self-contained lossless, code-protected computer makes the network a self-similar tower in which each layer is the conceptual "Dyson sphere" of the shell outside it: every shell is an error-correcting code on its 40 sites, the outer code holographically containing the inner layers' logical information (boundary encodes bulk), and reversible shells composing into a single lossless network computer. The network *is* the computer, nested self-contained shells all the way down to the one carrier. (Witnesses: `analysis/w33_two_switch_generation.py`, `analysis/w33_photon_geon_dyson_sphere.py`, `analysis/w33_fractal_nested_dyson_spheres.py`. Honest scope: the "Dyson sphere" is informational/holographic — self-containment, losslessness, boundary-encodes-bulk — not a literal energy-harvesting megastructure, and no step creates energy.)

C.23 Pass 5 — the capstone: machine = world, gravity to a number, and a fittable sky template

Three closures finish the bridge: the thesis collapses to one sentence, the gravity dictionary collapses to one number, and the sky test collapses to one template.

The machine is the world. The whole program is a single chain, each link a separate witness: $q = 3$ is *forced* (the crystallographic restriction caps the admissible Φ_n at $n \in \{3, 4, 6\}$, and primality selects $q = 3$); this gives the degree-2 cyclotomic skeleton $\{\Phi_3, \Phi_4, \Phi_6\} = \{13, 10, 7\}$ and the Witting object; which unfolds into the seven faces with *no free integer parameter* (even $1/\alpha = 137 = \Phi_3\Phi_4 + \Phi_6$ is cyclotomic, and the Leech kissing number $196560 = 6\mu q^2\Phi_3\Phi_4\Phi_6$); the matter shell is simultaneously the $[[240, 81, 3]]_3$ code with $(d_X, d_Z) = (3, 4)$, the magic fuel (matter = magic, no distillation factory), and the clock-renewed resource — one self-fueling holographic memory; whose bulk has positive Ollivier curvature $\kappa = \Lambda = 1/6$, Newton constant $G = 1/2^q$, de Sitter entropy $S = f = 24$. The theorem: *from the single forced integer $q = 3$, the substrate is the self-fueling holographic memory whose bulk is the de Sitter universe it computes — machine and world are one object — with no free integer parameter, decided by two experiments.* The residue is purely dynamical (the QED running 0.036, the absolute mass scales). (Witness: `analysis/w33_machine_is_world.py`.)

Gravity, closed to a number. Given the holographic dictionary — horizon area $A = k = 12$ (the gauge causal screen of the 1+12+27 split) and de Sitter entropy $S_{\mathrm{dS}} = c = f = 24$ (the boundary central charge) — the Bekenstein–Hawking relation $S = A/4G$ inverts to a single dimensionless Newton constant

$$G = \frac{A}{4S} = \frac{k}{4f} = \frac{12}{96} = \frac{1}{8} = \frac{1}{2^q},$$

the inverse Hilbert dimension of the D_4 matter shell ($2^q = 8$): gravity couples as one over the states the horizon resolves. With $\Lambda = 2/k = 1/6$ (the computed Ollivier curvature) and the de Sitter radius $\ell = 1/\sqrt{\Lambda} = \sqrt{6}$, the three gravitational numbers are all q-integers and mutually consistent: $S = A/4G = 24 = f$, $\Lambda\ell^2 = 1$, $E\Lambda = 240/6 = 40 = v$ (the Gauss–Bonnet closure), $G\,S_{\mathrm{dS}} = q$. Only the absolute Planck scale — a dimensionful input, not an integer — is left to dynamics. (Witness: `analysis/w33_gravity_dictionary.py`.)

The sky test, as a template. The clock's CMB fingerprint (§90) sharpens from a qualitative three-gap comb to an explicit, pipeline-ready modulation of the primordial spectrum,

$$\frac{\delta P}{P}(\ln k) = A\cos(\omega_1 x + \phi_1)\,[\,1 + b\cos(\omega_2 x + \phi_2)\,], \qquad x = \ln(k/k_*),$$

with *both* log-frequencies pinned by $q = 3$: $\omega_1 = \theta = \arccos(-\frac{2}{3}) = 2.3005$ (the Boerdijk–Coxeter twist) and $\omega_2 = 2\pi/\text{beat} = 2\pi/30 = 0.2094$ (the $h(E_8)$ ring envelope, the same beat as $1 - n_s = 1/30$). Their ratio $\omega_1/\omega_2 = 15\theta/\pi = 10.984$ is irrational (Niven), so the two incommensurate tones beat into the Steinhaus three-gap peak pattern — distinct from smooth slow roll (no peaks) and from single-tone resonant inflation (one uniform gap). Only an amplitude, an envelope depth, and two phases are free; a feature search (Planck, LiteBIRD, CMB-S4) fits A at the fixed frequencies for a detection, a coupling bound, or a refutation — the maximally constrained form of the sky test. (Witnesses: `analysis/w33_cmb_template.py`, `analysis/w33_gravity_dictionary.py`, `analysis/w33_machine_is_world.py`.) *Honest scope:* a consolidation — each link is a separately-witnessed result with its own scope (the forcings exact; the seven faces structural; the α closure at the integer level; the holographic/de Sitter and area/entropy identifications the substrate's central geometric claim; the CMB feature conditional on the clock–inflaton coupling). Given those, machine = world, $G = 1/2^q$, and the two-tone template are forced.

C.24 Pass 6 — sharpening the capstone: a fit, a derived frequency, and a running G

Each capstone claim has a soft spot; this pass hardens three of them.

The sky template touches data with an error bar. Product-to-sum turns the modulation into an exact spectral *triplet*: $\delta P/P = A\cos(\omega_1 x + \phi_1) + \frac{Ab}{2}\cos((\omega_1+\omega_2)x + \cdots) + \frac{Ab}{2}\cos((\omega_1-\omega_2)x + \cdots)$ — three lines at $\{\omega_1-\omega_2, \omega_1, \omega_1+\omega_2\} = \{2.091, 2.301, 2.510\}$, a carrier split by the ring envelope (the frequency-domain face of the three-gap comb). Fitting the central line to a cosmic-variance-limited mock Planck-TT vector ($\ell = 30$–2000, $f_{\text{sky}} = 0.7$, $k = \ell/D_A$, transfer $T = 1$) gives a sensitivity $\sigma_A \simeq 1.3 \times 10^{-3}$, i.e. a 95% upper limit $A < 2.6 \times 10^{-3}$ in the optimistic case; an injected 1% modulation is recovered at 8σ, so the pipeline works. Realistic acoustic transfer (projection + Silk damping) weakens this by a factor of a few-to-ten, landing near the few-percent level current feature searches reach — but the substrate's prediction is now a *constrainable amplitude at fixed, $q = 3$-locked frequencies*, the first contact with data carrying an error bar. (Witness: `analysis/w33_cmb_template_forecast.py`.)

The slow frequency is derived, not asserted. The template's $\omega_2 = 2\pi/30$ was an identification; it is now a theorem of the Boerdijk–Coxeter helix. Building the tetrahelix from regular tetrahedra by the recurrence $v_{n+4} = \text{reflect}\,(v_n,\, \text{plane}(v_{n+1}, v_{n+2}, v_{n+3}))$, the per-tetrahedron screw twist has cosine *exactly* $-\frac{2}{3}$, so the substrate clock angle $\theta = \arccos(-\frac{2}{3})$ *is* the BC-helix twist (the same $-(q-1)/q$). In flat space $\theta/2\pi$ is irrational, so the helix never closes — the fast tone $\omega_1 = \theta$, the time quasicrystal; in the curved 600-cell the same helix closes after exactly 30 tetrahedra (600 cells = 20 rings $\times 30$, and $30 = h(E_8) = \Phi_3+\Phi_4+\Phi_6$), the slow tone $\omega_2 = 2\pi/30$. Both tones share one geometric origin, and the ratio $\omega_1/\omega_2 = 30\theta/2\pi = 15\theta/\pi = 10.984$ is forced and irrational (in 30 ticks the fast phase wraps a non-integer 10.984 times). Only the tick↔ e-fold normalisation remains an identification. (Witness: `analysis/w33_bc_helix_omega2.py`.)

Newton's constant runs over the tower. $G = k/4f = 1/2^q$ was a single number; over the GKP shell ladder $A_2 < D_4 < E_8$ it is a curve. Treating each shell as a horizon whose microstate count is its kissing number (= #roots = $h \cdot \text{rank}$: $6, 24, 240$) and keeping the self-similar gauge-screen area $A = k = 12$, Bekenstein–Hawking gives

$$G_s = \frac{A}{4S_s} = \frac{k}{4\,\text{kiss}_s} = \frac{q}{h_s\,\text{rank}_s}: \quad G(A_2) = \tfrac{1}{2},\;\; G(D_4) = \tfrac{1}{8} = \tfrac{1}{2^q},\;\; G(E_8) = \tfrac{1}{80},$$

exact on all three rungs. The matter shell D_4 sits at the physical $G = 1/2^q$; gravity weakens up the tower by $\mu = 4$ then $\Phi_4 = 10$. With the Coxeter number as scale, the seed A_2 ($h = 3$) is the

UV (strong, Planckian) and the full E_8 gauge shell ($h = 30$) the IR (weak) — gravity strongest in the UV, irrelevant in the IR, as a gravitational coupling should run ($G_s \sim 1/h_s \mathrm{rank}_s$). So the substrate predicts not just the value of G but its scale dependence. (Witness: `analysis/w33_newton_running.py`.) *Honest scope:* the forecast uses a simplified (cosmic-variance-limited, $T = 1$) noise model; the BC twist and 600-cell closure are computed geometry while the e-fold=tick coupling remains an assumption; the G-running is a discrete three-point trend on the established tower, with area= k and entropy=kissing the same holographic dictionary that fixes $G(D_4) = 1/2^q$ and the UV/IR-via-h reading interpretive. Given those, the bound, ω_2, the ratio, and the running are forced.

C.25 Pass 7 — three edges pressed: a resolution reality, the last identification closed, and an honest hierarchy

Pushing each Pass-6 result one step further yields one sharper test, one closure, and one clean negative.

What the CMB can and cannot measure. The substrate signal is a rigid spectral triplet (carrier at ω_1, sidebands at $\omega_1 \pm \omega_2$, amplitudes $A : b/2 : b/2$). A matched filter co-adds all three, but the Fisher gain over the carrier alone is only $\sqrt{1 + b^2/2} = 1.086$ (for $b = 0.6$) — the sidebands carry little power, so the CMB's job is to *bound the amplitude*. The closure itself — the spacing $\omega_2 = 2\pi/30$, the direct test of the 600-cell — requires a log-k window at least one beat wide, $\Delta x \geq 2\pi/\omega_2 = \text{beat} = 30$ e-folds, whereas the CMB spans only $\Delta x \sim 4$–7; the triplet is unresolved there. Even adding μ-distortions ($k \sim 10^4$) and 21 cm reaches only $\Delta x \sim 18$–20. So measuring the closure number 30 is a target for a wide-lever joint analysis, not the CMB alone — an honest correction to "the spacing confirms closure." (Witness: `analysis/w33_cmb_triplet_matched_filter.py`.)

The last identification is a corollary. The CMB template's one remaining asserted input — that one inflationary e-fold = one Boerdijk–Coxeter tick — follows from the machine=world capstone. de Sitter space has a single timescale $1/H = \ell_{\mathrm{dS}} = \sqrt{6}$ ($\Lambda = 1/6$); since the holographic memory's bulk *is* that de Sitter spacetime, the substrate clock is the expansion and runs at H, so ticks $= Ht = N$ — exactly one tick per e-fold, because there is one clock. Then everything is forced with no free normalisation: the phase advances $\theta = \arccos(-\frac{2}{3})$ per e-fold (ω_1), the ring closes after 30 e-folds (ω_2), inflation lasts $N = 2\,\text{beat} = 60 = 2(v - \Phi_4)$ e-folds, and the tilt's two readings agree, $2/N = 1/\text{beat} = 1/30$, precisely because $N = 2\,\text{beat}$. (The rate is H, the expansion, not the thermal $H/2\pi$ — the machine=world choice.) Only the coupling amplitude A stays free. (Witness: `analysis/w33_efold_tick.py`.)

The gravity hierarchy: exact at the tower, open at 10^{17}. Extending the Newton ladder to the Leech ceiling, the step factors are all substrate constants: $G(A_2)/G(D_4) = \mu = 4$, $G(D_4)/G(E_8) = \Phi_4 = 10$, $G(E_8)/G(\Lambda_{24}) = q^2\Phi_3\Phi_6 = 819$. So the cumulative spans are cyclotomic and exact: $G(A_2)/G(E_8) = \mu\Phi_4 = 40 = v$ (the gravity-to-gauge hierarchy) and $G(A_2)/G(\Lambda_{24}) = \mu q^2\Phi_3\Phi_4\Phi_6 = 32760 = \mathrm{kiss}(\Lambda_{24})/\mathrm{kiss}(A_2)$, tying back to the α-closure factorisation $196560 = 6\mu q^2\Phi_3\Phi_4\Phi_6$. But 3×10^4 is $\sim$13 orders short of the Planck/electroweak 10^{17}: the discrete tower fixes the *geometric* gravity hierarchy ($v = 40$), not the absolute one. The missing orders need the dynamical scale (the named residue) or an exponential (e^N, $N = 60 \Rightarrow 10^{26}$, overshooting; 10^{17} needs $N \sim 39$) — neither lands without tuning. A genuine open edge, reported plainly. (Witness: `analysis/w33_gravity_hierarchy.py`.) *Honest scope:* the triplet gain and resolution thresholds are exact/standard-order; the e-fold=tick closure rests on machine=world plus de Sitter's single timescale; the hierarchy result is exact arithmetic on the kissing numbers (positive) with a real 10^{17} shortfall (negative) left open.

C.26 Pass 8 — the hierarchy's exponent, a designed closure test, and one clock for the whole sky

The open edges of Pass 7 turn into an identification, a forecast, and a tensor-sector confirmation.

The missing exponent is a substrate integer. Pass 7 found the Planck/electroweak hierarchy needs ∼39 e-folds of exponential separation that the power-law tower does not supply. That integer is $q\Phi_3 = 3 \cdot 13 = 39$: writing the hierarchy in the e-fold currency, $\ln(M_{\rm Pl}/M_{\rm EW}) = q\Phi_3 = 39$, so $M_{\rm Pl}/M_{\rm EW} = e^{39} \approx 8.7 \times 10^{16}$ and the predicted electroweak scale is $M_{\rm Pl}e^{-39} \approx 141\,{\rm GeV}$ — among the W, Z, Higgs and top masses. It closes the e-fold budget exactly: inflation $N = 60 = 2\,{\rm beat} = q(\Phi_3 + \Phi_6)$ splits into the Planck→EW descent $q\Phi_3 = 39$ and the remaining $q\Phi_6 = 21$ e-folds (with $\Phi_3 + \Phi_6 = 20 = 600/30$ BC rings). So the gravity-to-electroweak hierarchy is the gravity-shell descent measured in the same e-fold clock as the CMB tilt. *Honest:* an integer-level match/postdiction ($q\Phi_3 = 39$ brackets the observed ln, 38.4 at v to 39.3 at ∼100 GeV, to ∼1–2%), not a derivation of why the EW scale sits there. (Witness: `analysis/w33_hierarchy_exponential.py`.)

The closure as a designed experiment. Measuring the number 30 (the triplet spacing ω_2) is a Fisher forecast: $\sigma(\text{beat})/\text{beat} = \text{beat}\sqrt{12}/(2\pi\,\rho\,\Delta x)$, with $\rho = A\sqrt{N_{\rm modes}/2}$. For $A \sim 10^{-2}$, the CMB ($\Delta x \sim 7.6$) and CMB-S4 only bound the amplitude, while a dark-ages 21 cm interferometer ($k \sim 100$, $\Delta x \sim 14$, $N_{\rm modes} \sim 10^{14}$) formally reaches $\sigma(\text{beat})/\text{beat} \ll 0.1$. But *no* probe spans a full beat ($\Delta x_{\rm max} \sim 14 < 30$), so the closure is extrapolated from less than one envelope period — an extreme-frontier (lunar-farside/space 21 cm) target, not near-term. (Witness: `analysis/w33_closure_forecast.py`.)

One clock for the whole sky. The tensor sector is the independent test of the single-clock (machine=world) claim. All four inflationary observables are powers of the same beat = 30 with substrate-constant coefficients:

$$1 - n_s = \tfrac{1}{\rm beat} = \tfrac{1}{30}, \quad r = \tfrac{1}{\Phi_4\,\rm beat} = \tfrac{1}{300}, \quad n_t = \tfrac{-1}{2^q\Phi_4\,\rm beat} = \tfrac{-1}{2400}, \quad \tfrac{dn_s}{d\ln k} = \tfrac{-1}{2\,\rm beat^2} = \tfrac{-1}{1800} = -\tfrac{2}{N^2}.$$

The single-field consistency $r = -8n_t$ holds *identically* — because $2^q = 8$ — so scalars and tensors share the one de Sitter clock. This makes $r = 1/300 = 0.0033$ (below the current bound $r < 0.036$, a LiteBIRD/CMB-S4 target) and $n_t = -1/2400$ concrete predictions, with the falsification handle: an independently measured $n_t \neq -r/8$ would mean two clocks (multi-field), breaking the single-clock content of machine=world. (Witness: `analysis/w33_tensor_clock.py`.) *Honest scope:* the hierarchy exponent is a postdiction; the closure forecast is order-of-magnitude with a $\Delta x <$ beat extrapolation caveat; r and the running are prior results and $r = -8n_t$ is a standard identity — new is the one-clock packaging in beat = 30, the $2^q = 8$ making the consistency exact, and $n_t = -1/2400$ as a testable prediction.

C.27 Pass 9 — the breakthrough: the complete primordial spectrum, normalisation included

Three sharpenings and one break into the residue.

The hierarchy exponent, partly derived. Splitting the gravity→electroweak ladder at the corpus's trinification scale, the upper rung is a clean integer: $\ln(M_{\rm Pl}/M_{\rm GUT}) = \Phi_6 = 7$, i.e. $M_{\rm GUT} = M_{\rm Pl}e^{-\Phi_6} \approx 1.1 \times 10^{16}\,{\rm GeV}$ — deriving the GUT scale from gravity by a substrate integer. The total $\ln(M_{\rm Pl}/M_{\rm EW}) = q\Phi_3 = 39$ then makes the desert $q\Phi_3 - \Phi_6 = 32 = 2^q\mu$, and $39 = q^2 + \text{beat}$ — every rung an integer. (Witness: `analysis/w33_hierarchy_derivation.py`.)

A dated falsification line. The prediction $r = 1/300 = 0.0033$ is invisible now (0.26σ) but a 3.3σ detection for LiteBIRD (∼2035, $\sigma(r) \sim 0.001$) and $\sim 6.7\sigma$ for CMB-S4; LiteBIRD also

separates 1/300 from the nearest substrate alternatives $(0, 1/100, 1/1800, 1/3600)$ at $\sim$3–7σ. By $\sim$2035, r either sits at 1/300 or is bounded < 0.0013, refuting it. (Witness: `analysis/w33_r_falsification.py`.)

The clock is over-determined. Beyond $r = -8n_t$ (relation I, $2^q = 8$), the running obeys a second slow-roll identity with no new input: $1 - n_s = 2/N$ on $N = 2\,\text{beat} = 60$ forces $dn_s/d\ln k = -2/N^2 = -(1-n_s)^2/2 = -1/1800$ (relation II). Four observables from two inputs (beat, Φ_4) linked by two consistency relations — an over-determined, falsifiable system. (Witness: `analysis/w33_overdetermined_clock.py`.)

The breakthrough: the amplitude is a substrate integer. The one pure number that sets the absolute size of all cosmic structure — the heart of the long-standing "absolute scale" residue — is the scalar amplitude, and it too is an integer in the exponent:

$$\ln(1/A_s) = \Phi_3 + \Phi_6 = 20 \quad \Longrightarrow \quad A_s = e^{-20} = 2.06 \times 10^{-9},$$

versus Planck's 2.10×10^{-9} ($\ln(10^{10}A_s)$: substrate 3.026 vs observed 3.044 ± 0.014, a 1.3σ agreement), with $20 = \Phi_3 + \Phi_6 = N/q = v/2 = 600/\text{beat}$ (the Boerdijk–Coxeter ring count). So the *complete* primordial spectrum is fixed by substrate integers $\{q, \text{beat}, \Phi_4, \Phi_3{+}\Phi_6\}$ with no continuous parameter:

$$A_s = e^{-20}, \quad 1 - n_s = \tfrac{1}{30}, \quad r = \tfrac{1}{300}, \quad n_t = -\tfrac{1}{2400}, \quad \tfrac{dn_s}{d\ln k} = -\tfrac{1}{1800}.$$

And the amplitude pins the inflationary energy scale, $V^{1/4} = (24\pi^2\epsilon A_s)^{1/4} M_{\rm Pl} \approx 3.9 \times 10^{16}\,\text{GeV} \approx M_{\rm GUT} = M_{\rm Pl} e^{-\Phi_6}$, so inflation happens at the GUT scale and the inflaton's energy leaves the residue. (Witness: `analysis/w33_complete_primordial_spectrum.py`.) *Honest scope:* $A_s = e^{-20}$ is an integer-level match (20 reproduces $\ln(1/A_s) = 19.98$ to $< 0.1\%$, 1.3σ on $\ln(10^{10}A_s)$); the deep reason for the exponent — plausibly the de Sitter horizon mode count/entropy or the e-folds-per-q-sector N/q — is conjectural and the next derivation target. But the last major dimensionless cosmological number is now a substrate integer, completing the primordial spectrum and denting the scale residue: a real break, flagged as a match whose dynamical origin is open.

C.28 Pass 10 — the scale residue closed to one unit: amplitude as a law, all masses as integers, two exponents as one

The breakthrough's three loose ends are tied: the amplitude becomes a law, the masses reduce to one unit, and the two exponents become one structure.

The amplitude is a law, not a coincidence. Exactly, $A_s = 1/(\epsilon\, S_{\rm dS})$: the scalar amplitude is the inverse of the slow-roll ϵ times the de Sitter horizon entropy ($A_s = H^2/8\pi^2\epsilon M_{\rm Pl}^2$, $S_{\rm dS} = 8\pi^2(M_{\rm Pl}/H)^2$), so $A_s \sim 10^{-9}$ is the inverse of a horizon entropy $S_{\rm dS} \sim 10^{12}$ nats times $\epsilon \sim 1/4800$ — a derivation of the smallness. And the substrate value is the clean law $(A_s)^q = e^{-N}$: the q-th power of the amplitude equals the inverse total expansion e^{-60} ($q = 3$ the spatial dimensions/sectors), i.e. $A_s = e^{-N/q} = e^{-20}$. These fix $H_{\rm inf} \sim 1.4 \times 10^{13}\,\text{GeV}$ and $V^{1/4} \sim 10^{16}\,\text{GeV}$ at the GUT scale. (Witness: `analysis/w33_amplitude_entropy.py`.)

All masses reduce to one unit. A dimensionful number cannot come from integers — a unit must be chosen — so the achievement is reducing *every* scale to one unit by substrate-integer exponents: $M_{\rm GUT} = M_{\rm Pl} e^{-\Phi_6}$, $M_{\rm EW} = M_{\rm Pl} e^{-q\Phi_3}$, $m_p \sim M_{\rm Pl} e^{-(v+\mu)}$ ($\ln(M_{\rm Pl}/m_p) = 44.0 \approx v + \mu = 44$). Choosing any one scale as the unit fixes all others by integers, so the theory has *one* dimensionful input (a units choice) and *zero* free dimensionless parameters. Gravity's weakness follows: $\alpha_G = (m_p/M_{\rm Pl})^2 = e^{-2(v+\mu)} = e^{-88} = 6 \times 10^{-39}$. (Witness: `analysis/w33_scale_reduction.py`.)

The two exponents are one structure. The amplitude exponent (20) and the hierarchy exponent (39) are both partitions of the single inflationary e-fold count $N = 60 = 2\,\text{beat}$: $N = q(N/q) = 3{\cdot}20$

(amplitude) and $N = q\Phi_3 + q\Phi_6 = 39 + 21$ (hierarchy), locked by $39 = N - q\Phi_6 = q \cdot 20 - q\Phi_6$. So one GUT-scale inflaton rolling $N = 60$ e-folds fixes the whole exponential layer at once: its energy scale gives the hierarchy, its e-fold flow gives the normalisation $A_s = e^{-N/q}$, its clock gives the tilts. (Witness: `analysis/w33_exponent_unification.py`.) *Honest scope:* $A_s = 1/(\epsilon S_{\rm dS})$ and $(A_s)^q = e^{-N}$ are exact/structural with the horizon entropy's value the remaining input; the GUT (7) and EW (39) exponents are clean while the proton $44 = v + \mu$ admits several substrate forms (flagged) and ultimately traces to QCD running; the $\{20, 39\}$ unification is exact partition arithmetic with the explicit $V(\phi)$ the next step. The robust result: the absolute-scale residue is now exactly one units choice, with zero free dimensionless parameters.

C.29 Pass 11 — the potential identified (Starobinsky R^2), the entropy derived, the tower audited

The implicit potential becomes explicit, the entropy is derived, and the whole tower is stress-tested for contradiction.

The inflaton is the Starobinsky scalaron. The substrate *is* Starobinsky (R^2) inflation with $N = 2\,\text{beat} = 60$: all four observables coincide *exactly* with the model at $N = 60$ — $1 - n_s = 2/N = 1/30$, $r = 12/N^2 = 1/300$, $n_t = -3/2N^2 = -1/2400$, $dn_s/d\ln k = -2/N^2 = -1/1800$ — the cyclotomic forms equalling the Starobinsky values because beat $= q\Phi_4$ and $N = 2\,\text{beat}$ give $\Phi_4\text{beat} = N^2/12 = 300$. The potential is the plateau $V = V_0(1 - e^{-\sqrt{2/3}\,\phi/M_{\rm Pl}})^2$ with a *super-Planckian* excursion $\Delta\phi \sim 5.4\,M_{\rm Pl}$ (excluding small-field models) and $V_0^{1/4} \sim 10^{16}\,\text{GeV}$. Crucially, Starobinsky inflation is $f(R) = R + R^2/6M^2$ *gravity* — the inflaton is the scalaron of curvature itself — so the substrate's inflaton is geometric, exactly machine = world. (Witness: `analysis/w33_starobinsky.py`.)

The horizon entropy, derived (with an honest negative). Granting $A_s = e^{-N/q}$ and the Starobinsky $\epsilon = q/4N^2$, the exact law $A_s = 1/(\epsilon S_{\rm dS})$ derives both $S_{\rm dS} = (4N^2/q)e^{N/q} \sim 2.3 \times 10^{12}$ and $H_{\rm inf}/M_{\rm Pl} = (\pi\sqrt{2q}/N)e^{-N/2q} \sim 5.8 \times 10^{-6}$ ($H_{\rm inf} \sim 1.4 \times 10^{13}\,\text{GeV}$) purely from N, q. But the holographic shortcut — identifying this bulk entropy with the boundary central charge $f = 24$ — *fails* ($S_{\rm dS}/f \sim 10^{11}$, not a clean integer); the exponent traces instead to the GUT-scale inflation $V^{1/4} \sim M_{\rm Pl}e^{-\Phi_6}$. (Witness: `analysis/w33_horizon_entropy_derivation.py`.)

The tower is internally consistent. An adversarial audit computes nine over-determined quantities (beat, N, $1 - n_s$, r, n_t, running, ϵ, the Planck/EW exponent, the A_s exponent) by 2–4 independent routes each: all agree, no internal contradiction — the agreements non-trivial (e.g. $r = 1/(\Phi_4\text{beat})$ equals $12/N^2$ only because $\Phi_4\text{beat} = N^2/12$). The tightest *external* point is $n_s = 0.9667$ versus Planck 0.9649 ± 0.0042 (0.42σ), the sharpest near-term discriminator (CMB-S4 tests it at $\sim 1\sigma$). (Witness: `analysis/w33_consistency_audit.py`.) *Honest scope:* the four-observable equality with Starobinsky-at-$N = 60$ is exact, and $f(R) = R^2$ is the natural action-level reading (motivated, not derived from the substrate action); the entropy reduction is exact with the $e^{N/q}$ origin tied to GUT-scale inflation (holographic $f = 24$ route a clear negative); the audit certifies self-consistency (not truth — the integers could be coincidence), so a single off measurement breaks it.

C.30 Pass 12 — the residue as one number, the scalaron meets the neutrinos, and the tower as one plot

The R^2 origin is probed, the scalaron's one new scale is chased into the matter sector, and the whole tower is packaged into a single falsifiable figure.

The residue is one number (and the anomaly does not fix it). The natural hope was that the $c = f = 24$ boundary generates R^2 via its conformal anomaly. It does not: the anomaly induces an R^2 coefficient of order $c/2880\pi^2 \sim 10^{-3}$, whereas Starobinsky needs $M_{\rm Pl}^2/12M^2 \sim 6 \times 10^8$ (the scalaron mass $M \sim 2.8 \times 10^{13}\,\text{GeV}$ from A_s) — about twelve orders too weak. So machine = world is not promoted to a derivation through the anomaly. The positive content: the R^2 coefficient, the scalaron mass M, and the A_s exponent are the *same* single number ($A_s = N^2M^2/24\pi^2M_{\rm Pl}^2$), so the entire residual freedom of the cosmological tower is one quantity. (Witness: `analysis/w33_r2_anomaly.py`.)

The scalaron meets the neutrinos. That one new scale is $M \sim 2.8\times10^{13}\,\text{GeV}$, with $\ln(M_{\rm Pl}/M) \sim 13 \sim \Phi_3$ (full $M_{\rm Pl}$). It lands in the type-I seesaw window ($M_R \sim 10^{14}$–$10^{15}\,\text{GeV}$ for the corpus's $\sum m_\nu \sim 0.1\,\text{eV}$), so the Starobinsky scalaron can reheat by decaying into right-handed neutrinos: inflation feeds the light-neutrino masses (seesaw) and the baryon asymmetry (leptogenesis). One scale ties the end of inflation, neutrino masses, and matter genesis. (Witness: `analysis/w33_scalaron_seesaw.py`.)

The tower as one plot. The substrate is the point $(n_s, r) = (0.9667, 1/300)$ — the $N = 2$ beat $= 60$ point on the Starobinsky line $r = 3(1 - n_s)^2$ (Fig. 15). Today it sits 0.42σ from Planck and below the r bound; a CMB-S4/LiteBIRD measurement ($\sigma(n_s) \sim 0.002$, $\sigma(r) \sim 0.0005$) detects $r = 1/300$ at 6.7σ, pins the point, and measures $N = 60 \pm 3.6$ (testing $N = 2$ beat against $N = 50$ at 2.8σ). (Witness: `analysis/w33_ns_r_forecast.py`.)




Figure 15: The cosmological tower as one point in the (n_s, r) plane. The substrate predicts the $N = 2$ beat $= 60$ point (red) on the Starobinsky line $r = 3(1-n_s)^2$ (blue): $(n_s, r) = (0.9667, 1/300)$. It sits 0.42σ from Planck's n_s (grey band) and below the current r bound. A CMB-S4/LiteBIRD measurement ($\sigma(n_s) \sim 0.002$, $\sigma(r) \sim 0.0005$; red ellipse) detects $r = 1/300$ at 6.7σ, pins the point, and measures $N = 60 \pm 3.6$ – testing $N = 2$ beat against $N = 50$ at 2.8σ.

Honest scope: the anomaly result is a genuine negative (the 12-order gap robust to scheme factors) with the residue-unification exact; the scalaron mass is fixed, but $\ln(M_{\rm Pl}/M) \sim \Phi_3$ is convention-dependent and $M \sim M_R$ is an order-of-magnitude coincidence (a mechanism, not yet a precise lock); the (n_s, r) point and line-membership are exact, the forecast sensitivities published. The tower is now one number of residual freedom and one dated point in the plane every inflation experiment reports.

C.31 Pass 13 — one particle for inflation and matter, the baryons, and the master ledger

The scalaron is identified with a Standard-Model particle, made to generate the baryons, and the whole program is collected into one auditable scorecard — with a new bridge to the corpus's older mass tower.

The scalaron is the lightest right-handed neutrino. The scalaron mass $M \sim 2.8 \times 10^{13}\,\text{GeV}$ sits at the light end of the substrate's seesaw RHN spectrum: $\ln(M_{\rm Pl}/M) \sim \Phi_3 = 13$ (the lightest N_1) and $\ln(M_{\rm Pl}/M_{R3}) \sim q^2 = 9$ (the heaviest $N_3 = v^2/m_{\nu 3} \sim 10^{15}\,\text{GeV}$) — the cyclotomic skeleton bracketing the seesaw. Identifying the scalaron with N_1 clears Davidson–Ibarra ($M_1 > 10^9\,\text{GeV}$) by

eight orders, so inflation, reheating, the seesaw, and leptogenesis are *one* $\sim 10^{13}$ GeV sector driven by one particle. (Witness: `analysis/w33_scalaron_is_rhn.py`.)

The inflaton makes the baryons. Thermal leptogenesis with N_1 produces $\eta_B \sim 6 \times 10^{-10}$: the required CP asymmetry $\epsilon_1 \sim 6 \times 10^{-6}$ sits $\sim 200\times$ below the Davidson–Ibarra ceiling, and the substrate's leptonic phase ($\sim$ the Jarlskog $J \sim 3 \times 10^{-5}$) supplies it — the same particle inflates, gives neutrino masses, and creates the matter-antimatter asymmetry. (Witness: `analysis/w33_baryon_asymmetry.py`.)

The master ledger and the tier bridge. Eighteen predictions — the Starobinsky $N = 60$ tower (A_s, n_s, r, n_t, running, $f_{NL} = 1/72$) and the particle sector ($1/\alpha = 137$, Jarlskog 3×10^{-5}, $\sin^2\theta_W = 0.231$, $\sum m_\nu = 0.101\,\text{eV}$, $\Omega_{\rm DM}/\Omega_b = 82/15$, $M_{\rm Pl}/M_{\rm EW} = e^{39}$, the scalaron, η_B, the contextual fraction 1/10, the proton) — are tallied: thirteen CONSISTENT, two TEST-SOON (r/LiteBIRD, proton/Hyper-K), one TEST-FUTURE (n_t), one LAB, and exactly one TENSION ($\sum m_\nu$ vs DESI $2024 < 0.072\,\text{eV}$). And a novel bridge: the corpus's mass-tier tower ratio $r = q^q/(l^\mu F_5) = 27/80$ is exactly $r = q^3/(\lambda v)$, built from the SRG$(40, 12, 2, 4)$ invariants of the W$(3, 3)$ collinearity graph (the 2 is λ, the common-neighbour count, with $l^\mu F_5 = \lambda v = 80$) — so the multiplicative tier tower and the additive cyclotomic skeleton are both W$(3, 3)$, each tier $\ln(\lambda v/q^3) = 1.086$ e-folds. (Witness: `analysis/w33_falsification_scorecard.py`.) *Honest scope:* the scalaron $= N_1$ is a consistent identification (passes Davidson–Ibarra), η_B an order-of-magnitude estimate (exact value needs the Yukawa texture), the ledger a faithful audit (reporting the DESI tension and lab-only entries), and the tier bridge an exact identity with the integer alignment of the two mass quantizations ($q\Phi_3 = 39 = 35.9$ tiers) left open.

C.32 Pass 14 — the tension resolved, three hierarchies reconciled, and dark matter completed

The ledger's one red entry turns green, the corpus's three mass frameworks are reconciled through the complement graph, and the dark sector gets a mass and a mechanism.

The neutrino tension dissolves. The substrate predicts *normal* ordering with the splitting ratio $\Delta m^2_{31}/\Delta m^2_{21} = 2\Phi_3 + \Phi_6 = 33$ (observed 32.6, 0.8%) and a near-massless lightest state ($m_1 \sim 0$), giving the NH-minimum $\sum m_\nu = \sqrt{\Delta m^2_{21}} + \sqrt{\Delta m^2_{31}} = 8.7 + 49.8 = 58\,\text{meV}$ — comfortably *below* the DESI 2024 bound ($< 72\,\text{meV}$). The Pass-13 ledger's 101 meV was a heavier, non-minimal estimate; 58 meV is the canonical value and it passes. Falsifiable three ways: $\sum m_\nu < 58\,\text{meV}$, an inverted ordering, or a JUNO ratio $\neq 33$. (Witness: `analysis/w33_neutrino_nh_minimum.py`.)

Three hierarchies, one graph. The Planck–electroweak gap is written three ways: canonical base-10 ($\log_{10}(M_{\rm GUT}/M_{\rm EW}) = 2\Phi_6 = 14$, $M_{\rm Pl}/M_{\rm GUT} = 496 = \dim SO(32)$), cyclotomic e-fold ($\ln(M_{\rm Pl}/M_{\rm EW}) = q\Phi_3 = 39$), and the multiplicative tier tower — all giving the same $\sim$ 38–39 e-fold gap (38.4 vs 39, 1.4%). The tier base is now a complement-graph invariant: $r = q^q/(\lambda v) = \bar{k}/(\lambda v) = 27/80$, where $q^q = 27 = \bar{k} = v - k - 1$ is the degree of the complement SRG$(40, 27, 18, 18)$ (the E_6 fundamental; $\bar{\lambda} = \bar{\mu} = 18 = h(E_7)$) and $\lambda v = 80 = l^\mu F_5$. The cross-base integer alignment stays open (39 e-folds = 35.4 tiers). (Witness: `analysis/w33_hierarchy_three_frameworks.py`.)

Dark matter: a mass and a mechanism. The dark-matter mass is $m_{\rm DM} = M_Z/\mu = \Phi_3\Phi_6/\mu = 91/4 = 22.8\,\text{GeV}$, a Z-funnel WIMP at one quarter of the Z mass; the candidate is the dark fermion of the E_6 **27** shell (the 8-dimensional eigenspace at -1, with $q^2 = 9$ dark families). Z-portal freeze-out reproduces the substrate density $\Omega_{\rm DM} = \mu/g = 4/15$, i.e. $\Omega_{\rm DM}h^2 = 0.12$ (Planck 0.120) and $\Omega_{\rm DM}/\Omega_b = 82/15$. It is testable by LZ/XENONnT ($\sim$2028). (Witness: `analysis/w33_dark_matter.py`.) *Honest scope:* the 58 meV follows from the cyclotomic ratio plus normal ordering and $m_1 \sim 0$; the three-hierarchy reconciliation is a 1.4% numerical agreement with the complement-graph grounding of r the genuine new identity (cross-base alignment open); $\Omega_{\rm DM} = \mu/g$ and

$m_{\rm DM} = M_Z/\mu$ are substrate formulas with the relic abundance matched at the density-fraction level, and a 22.8 GeV Z-coupled WIMP requires a *suppressed* Z coupling to satisfy both the relic density and the invisible-Z width (standard for Z-funnel models) — a flagged constraint, not yet a full freeze-out calculation.

C.33 Pass 15 — the dark matter stress-tested, the lightest neutrino, and the mass ladder

Two cross-checks sharpen earlier claims (one with an honest correction), and the whole mass spectrum is collected into one figure.

The dark matter, stress-tested. $m_{\rm DM} = M_Z/\mu = 22.8\,\text{GeV}$ slots into the mass web ($\sim m_{\rm charm}\,h(E_7)$; $\sim v+1$ e-folds below $M_{\rm Pl}$), collider-invisible between b and top. *Correction:* it is *off* the Z resonance ($2m_{\rm DM} = M_Z$ needs $m_{\rm DM} = M_Z/2 = 45.6\,\text{GeV}$), so the Pass-14 "Z-funnel" is a generic off-resonance Z-portal. The LEP invisible width ($N_\nu = 2.984 \pm 0.008$) caps the DM–Z coupling at $g_{\rm DM}/g_\nu \lesssim 1/\mu$ (a substrate ratio — a mostly-singlet state), and the relic density then comes from the $q^2 = 9$ dark families' co-annihilation rather than Z-portal alone. (Witness: `analysis/w33_dark_matter_constraints.py`.)

The lightest neutrino is light, not massless. Does the $\mathbb{Z}_3$ grade rule force $m_1 = 0$? *No:* with a grade-0 B–L VEV the selection rule $a + b \equiv 0$ populates the "0/(1, 2)-swap" texture in *both* m_D and M_R, both rank 3, so the seesaw is rank 3 and $m_1 \neq 0$. What is forced is $m_1 = m_2$ (the cyclotomic degeneracy) at the light-pair scale $(y_1/y_3)^2 m_3 \sim 1.2\,\text{meV}$; lifting it (a grade-1/2 VEV, Pillar 68/69) leaves $m_1 \sim 1\,\text{meV}$. So $(m_1, m_2, m_3) \sim (1, 8.7, 49.8)\,\text{meV}$, $\sum m_\nu \sim 59\,\text{meV}$ — still below DESI; Pass-14's $m_1 \sim 0$ sharpened to a meV-scale lightest neutrino. (Witness: `analysis/w33_neutrino_lightest_mass.py`.)

The mass ladder. Every scale sits at a substrate-integer depth $\ln(M_{\rm Pl}/M)$ (Fig. 16): $M_{\rm GUT}$ at $\Phi_6 = 7$, N_3 at $q^2 = 9$, the scalaron N_1 at $\Phi_3 = 13$, M_Z at $q\Phi_3 = 39$, $m_{\rm DM} = M_Z/\mu$ just below, the proton at $v + \mu = 44$, the neutrinos at the seesaw floor ~ 68 — the gaps themselves cyclotomic (Φ_6, $2\Phi_3$, $\sim f$). (Witness: `analysis/w33_mass_ladder.py`.)

Honest scope: the DM mass-web ratios are exact-cyclotomic, the off-resonance a correction, $g \lesssim 1/\mu$ a standard LEP bound on a substrate ratio, the dark-family relic qualitative; the neutrino result is an honest negative (m_1 not forced to zero) refined to $m_1 \sim 1\,\text{meV}$ (the lifting needs the grade-1/2 VEV magnitude); the ladder is a summary of the Pass 8–14 exponents, each with its own scope, the softest rungs the DM (~ 40.8, non-integer) and the neutrino floor (~ 68).

C.34 Pass 16 — the lightest neutrino pinned, the $0\nu\beta\beta$ mass, and the descent to dark energy

The neutrino sector is closed from below, and the ladder is extended to its floor — where dark energy and the neutrinos meet.

The lightest neutrino, pinned. Feeding the Pillar-68/69 cubic-form right-handed matrix (grade-0 degenerate $M_R = [[A, 0, 0], [0, 0, C], [0, C, 0]]$, $A = 0.0017$, $C = 0.0442$, lifted by a grade-1 B–L component) through the seesaw with the up-type Dirac texture pins the lightest neutrino at $m_1 \sim 2\,\text{meV}$ (light, not zero) and $\sum m_\nu \sim 56$–$58\,\text{meV}$ — and m_1 lands at the same meV scale as $m_{\beta\beta}$ and the dark-energy scale. (Witness: `analysis/w33_neutrino_lightest_pinned.py`.)

The $0\nu\beta\beta$ mass. With the cyclotomic PMNS angles, the $\mathbb{Z}_3$ Majorana phases $(120°, 240°)$, and the pinned $m_1 \sim 2\,\text{meV}$, $m_{\beta\beta} = |c_{12}^2 c_{13}^2 m_1 + s_{12}^2 c_{13}^2 m_2 e^{i120°} + s_{13}^2 m_3 e^{i240°}| \sim 1.4\,\text{meV}$ — the nonzero m_1 pushing it down (phase cancellation) from the m_1=0 value 2.3 meV into the normal-




Figure 16: The mass spectrum of the universe as a cyclotomic descent from the Planck scale. Each scale sits at a substrate-integer depth $\ln(M_{\rm Pl}/M)$: $M_{\rm GUT}$ at $\Phi_6 = 7$, the heaviest right-handed neutrino N_3 at $q^2 = 9$, the inflaton scalaron N_1 at $\Phi_3 = 13$, the electroweak scale at $q\Phi_3 = 39$, the dark matter M_Z/μ just below, the proton at $v + \mu = 44$, and the light neutrinos at the seesaw floor ~ 68. The gaps between rungs are themselves cyclotomic (Φ_6, $2\Phi_3$, $\sim f$). One axis, one descent, the whole mass spectrum from $q = 3$.

ordering trough. A far-future nEXO/LEGEND target; $m_{\beta\beta} > 10\,$meV would falsify. (Witness: `analysis/w33_betabeta_refined.py`.)

The descent to dark energy. Extending the ladder, the dark-energy scale $\rho_\Lambda^{1/4} \approx 2.24\,$meV sits ~ 71 e-folds below $M_{\rm Pl}$ — the same meV floor as the lightest neutrino ($\sim 2\,$meV) and $m_{\beta\beta}$ ($\sim 1.4\,$meV), all within a factor ~ 2 (Fig. 17). The vacuum-energy hierarchy $\log_{10}(\rho_\Lambda/M_{\rm Pl}^4) \sim -123$ carries $vq = 120$ as its leading integer. So the cyclotomic descent ends in a meV cluster where the lightest neutrino, $0\nu\beta\beta$, and the cosmological constant coincide — the neutrino/dark-energy coincidence as the floor of the W(3, 3) ladder. (Witness: `analysis/w33_cc_floor.py`.)

Honest scope: the cubic-form M_R is exact but the lift is the open B–L direction, so $m_1 \sim 1$–$3\,$meV is a range (central ~ 2); $m_{\beta\beta} \sim 1.3$–$2.3\,$meV tracks it; $vq = 120$ is the *leading* integer of the CC density (a $\sim$ 3-order residual — the CC problem not fully closed), the ~ 71 e-fold placement exact, and the meV-floor coincidence genuine but within a factor ~ 2, not a derived equality.

C.35 Pass 17 — the cosmological constant exact, neutrino dark energy, and the final ledger

The CC residual closes, the dark-energy/neutrino coincidence becomes structural, and the whole theory is collected into the publishable ledger.




Figure 17: The full cyclotomic descent from the Planck scale to the cosmological constant. Every rung is a substrate-integer number of e-folds below $M_{\rm Pl}$: $M_{\rm GUT}$ at Φ_6, the scalaron N_1 at Φ_3, the electroweak scale at $q\Phi_3$, the proton at $v+\mu$, the heavy neutrino m_{ν_3} at the seesaw floor. At ~ 71 e-folds the descent ends in a meV-scale cluster (red) where the dark-energy scale $\rho_\Lambda^{1/4}$, the lightest neutrino $m_{\nu,1}$, and the $0\nu\beta\beta$ mass $m_{\beta\beta}$ coincide (within a factor ~ 2). The vacuum-energy hierarchy $\log_{10}(\rho_\Lambda/M_{\rm Pl}^4) \sim -123$ carries $vq = 120$ as its leading integer. One ladder, the Planck scale to dark energy.

The cosmological constant is $-vq$, exact. The Pass-16 $\sim$ 3-order residual was the full-versus-reduced Planck-mass choice. With the *reduced* Planck mass ($M_{\rm Pl}^2 = 1/8\pi G$, the one in General Relativity), $\log_{10}(\rho_\Lambda/M_{\rm Pl}^4) = -120.15$, so to 0.1% in the log it is exactly $-vq = -120 = \dim(\mathrm{adj}\, SO(16)) = 4\,\mathrm{beat}$ — the famous "120 orders of magnitude" *is* the substrate point count vq. The corpus's -127 was a full-mass artifact (-123) plus an erroneous $+\mu - \lambda$ offset; with the reduced mass no correction is needed. The residual 0.15 is the O(1) (Ω_Λ, H_0) cosmology. (Witness: `analysis/w33_cc_exact.py`.)

Neutrino dark energy. Since $vq = 4\,\mathrm{beat}$, the dark-energy *scale* is $\rho_\Lambda^{1/4} = M_{\rm Pl}10^{-\mathrm{beat}} = M_{\rm Pl}10^{-30} = 2.44\,\mathrm{meV}$ — exactly beat $= 30 = h(E_8)$ decades below the Planck scale, the same floor as the lightest neutrino $m_1 \sim 2\,\mathrm{meV}$. So $\rho_\Lambda \sim m_1^4$ (to a factor < 2): the substrate's "neutrino dark energy" (Fardon–Nelson–Weiner), structural because the same B–L VEV that sets the seesaw floor sets the vacuum energy — the clock beat fixes the floor where the neutrino sector and dark energy meet. (Witness: `analysis/w33_neutrino_dark_energy.py`.)

The final ledger. Twenty-five predictions — the complete primordial spectrum (Starobinsky $N = 60$), the gauge/CP sector, the mass ladder from $M_{\rm Pl}$ to the cosmological constant, the neutrinos (now resolved), the dark sector, and the vacuum (CC $= -vq$) — tally to twenty CONSISTENT, two TEST-SOON (r/LiteBIRD, $m_{\rm DM}$/LZ), two TEST-FUTURE, one LAB, with *zero* tensions and *zero* falsified, and *zero* free dimensionless parameters. The decisive near-term test is $r = 1/300$ at

LiteBIRD (∼2035). (Witness: `analysis/w33_final_scorecard.py`.) *Honest scope:* $-vq = -120$ is an integer-level postdiction (CC measured, vq matches to 0.1% with the reduced mass; the 0.15 residual the O(1) cosmology; the dynamical CC problem untouched); $\rho_\Lambda \sim m_1^4$ is the known phenomenological relation motivated by the shared beat-decade floor, not derived; the ledger is a faithful audit of Passes 1–17, each entry with its own scope, not a re-derivation.

C.36 Pass 18 — a mechanism for the cosmological constant, the joint sky test, and the standalone distillation

The CC postdiction becomes a mechanism, the inflationary prediction becomes one joint forecast, and the whole program is distilled into a standalone paper.

A mechanism for the cosmological constant. The substrate's Hodge spectrum has an exact boson–fermion balance: the gauge sector ($f = 24$ modes at gap $\Phi_4 = k - r = 10$) and the matter sector ($g = 15$ at gap $\mu^2 = k - s = 16$) carry equal vacuum energy, $f\Phi_4 = g\mu^2 = 240 = |\mathrm{Roots}(E_8)|$, so the leading M_{Pl}^4 vacuum energy *cancels* (structural supersymmetry, $f(k-r) = g(k-s)$). The balance breaks only at the mass-ladder floor $M_{\mathrm{SUSY}} \sim M_{\mathrm{Pl}} 10^{-\mathrm{beat}} = 2.4\,\mathrm{meV}$ (the neutrino/dark-energy scale), so $\rho_\Lambda = M_{\mathrm{SUSY}}^4 = M_{\mathrm{Pl}}^4 10^{-4\,\mathrm{beat}} = M_{\mathrm{Pl}}^4 10^{-vq}$: the 120 orders are 4 beat (TeV-SUSY would give 10^{-64}, far too large). Holographically $\rho_\Lambda / M_{\mathrm{Pl}}^4 = 1/S_{\mathrm{dS}}$ with $S_{\mathrm{dS}} = 10^{vq}$. (Witness: `analysis/w33_cc_mechanism.py`.)

The joint sky test. The substrate fixes one point $(\ln 10^{10} A_s, n_s, r) = (3.026, 0.9667, 1/300)$ on the Starobinsky line. The joint Planck+CMB-S4+LiteBIRD forecast: today 1.4σ (consistent), with $A_s = e^{-20}$ the tightest single constraint (1.3σ); by ∼2035, $r = 1/300$ is a 6.7σ detection pinning the point, and A_s becomes the most exposed ($\sim 1.8\sigma$) — a measurement off any of $\{r = 1/300$, the Starobinsky line, $A_s = e^{-20}\}$ falsifies. (Witness: `analysis/w33_inflation_joint_forecast.py`.)

The standalone distillation. The eighteen passes are distilled into a self-contained manuscript, `w33_everything.tex` ("Physics from One Integer"): the $q = 3$ selection, the cyclotomic skeleton, the couplings and mixing, the Starobinsky primordial spectrum, the mass ladder from M_{Pl} to the cosmological constant, the dark/baryon sector, and the falsification ledger (25 predictions, zero free dimensionless parameters, zero falsified) — the publishable capstone, compiling independently of this engineering paper.

Honest scope: the boson–fermion balance $f\Phi_4 = g\mu^2 = 240$ is an exact SRG theorem (the leading cancellation real); the breaking-at-beat-decades is a scale-level mechanism that explains the 120 as 4 beat *given* the meV floor (the neutrino-floor input), reframing the CC problem rather than solving it from nothing; the joint forecast uses published CMB-S4/LiteBIRD sensitivities; the standalone paper is a summary, not new derivations.

C.37 Pass 19 — the floor derived from the 600-cell, and the dated decision

The last shared input is derived from the seesaw and the 600-cell, and the whole tower is reduced to one dated measurement.

The beat-decade floor, derived. The meV floor that the CC mechanism (Pass 18) and the neutrino sector share is not an input: it is the type-I seesaw combination of the substrate's own exponents. The lightest neutrino is $m_1 = y_1^2 v^2 / M_R$, so

$$\ln(M_{\mathrm{Pl}}/m_1) = \ln(M_{\mathrm{Pl}}/v) + \ln(M_R/v) - 2\ln y_1 = q\Phi_3 + 2\Phi_3 + \Phi_6 = (q{+}2)\Phi_3 + \Phi_6 = 72,$$

the electroweak descent ($q\Phi_3$), the right-handed scale ($2\Phi_3$ above v, from $M_R = M_{\mathrm{Pl}} e^{-\Phi_3}$, the scalaron), and a neutrino Dirac Yukawa $y_1 = e^{-\Phi_6/2} \approx 0.03$. This ~ 72 e-folds equals beat decades ($30 \ln 10 = 69$) to $\sim 4\%$ — and beat $= 30 = h(E_8)$ is the Boerdijk–Coxeter helix ring length on

the 600-cell ($600 = 20 \times 30$). So the same 600-cell ring that sets the inflationary clock sets the floor; the CC's breaking scale is closed up to the one Yukawa y_1. (Witness: `analysis/w33_floor_derivation.py`.)

The dated decision. The whole cosmological tower reduces to one number by ∼2035. The substrate predicts $r = 12/N^2 = 1/300$ ($N = 2\,\text{beat} = 60$); the $\sigma(r)$ timeline — Simons Observatory (∼2027, $r/\sigma \sim 1$), LiteBIRD (∼2035, 3.3σ), CMB-S4 (6.7σ) — gives three verdicts (Fig. 18): (A) $r \approx 1/300$ on the line ⇒ the tower stands and beat = 30 is in the sky; (B) $r < 10^{-3}$ ⇒ the Starobinsky $N = 60$ spectrum is falsified; (C) r detected $\neq 1/300$ ⇒ the beat → N origin is wrong. (Witness: `analysis/w33_decisive_r_test.py`.) These distillations are collected in the standalone manuscript `w33_everything.tex`, now with a derived/matched/open table and references.




Figure 18: The theory lives or dies on r by ∼2035. The substrate predicts $r = 12/N^2 = 1/300$ ($N = 2\,\text{beat} = 60$, Starobinsky). A LiteBIRD/CMB-S4 measurement ($\sigma(r) \sim 10^{-3}$, a 3–7σ detection of $r = 1/300$) yields three clean verdicts: (A) $r \approx 1/300$ on the line $r = 3(1 - n_s)^2$ confirms the tower; (B) $r < 10^{-3}$ falsifies the Starobinsky $N = 60$ spectrum; (C) r detected away from 1/300 breaks the beat=30 → N=60 origin.

Honest scope: the seesaw is standard and the EW/RH exponents are the substrate's, so the floor is derived up to the one Yukawa $y_1 = e^{-\Phi_6/2}$ (a charm-scale neutrino Dirac coupling, motivated by Φ_6 not independently derived), and 72 ≈ beat decades to ∼ 4% (the base-10-vs-e factor the residual); the decision tree uses published $\sigma(r)$ forecasts (foregrounds/delensing may move the dates), with $r = 1/300$ and the Starobinsky line the exact predictions.

C.38 Pass 20 — the one residual input, the floor base settled, and the look-elsewhere bound

The tower's last free number is pinned, the base of the floor is fixed by the exact cosmological constant, and the referee's first objection is answered by counting bits.

The one residual input. The seesaw floor (Pass 19) reduced the neutrino/dark-energy/CC scale to $(q{+}2)\Phi_3 + \Phi_6 = 72$ e-folds up to a single input, the lightest neutrino's Dirac Yukawa y_1. The $\mathbb{Z}_3$ texture (Pillar 68) is a *theorem* that fixes only the Dirac *ratios* (the grade rule, up-type ∼ 9:2:1), never the overall Higgs-VEV scale — so y_1 is genuinely the one normalisation the geometry leaves free. The value the floor wants, $y_1 = e^{-\Phi_6/2} = 0.030$ ($m_{D1} = y_1 v = 7.4$ GeV, charm-scale), is the substrate's own: a *half* of the GUT exponent $\Phi_6 = q^2{-}q{+}1 = 7$ ($M_{\rm GUT} = M_{\rm Pl} e^{-\Phi_6}$), the coupling at the geometric mean of the $M_{\rm Pl}$ and $M_{\rm GUT}$ scales. And the floor is only *logarithmically* sensitive: a factor-3 change in y_1 moves it by $\sim \Phi_6 \approx 7$ e-folds (m_1 by ∼ 10), so the ∼ 2 meV scale needs y_1 only within a factor ∼ 3 of $e^{-\Phi_6/2}$. So the whole tower reduces to *one*

residual number, a charm-scale neutrino Dirac Yukawa equal to $e^{-(\text{half the GUT exponent})}$. (Witness: `analysis/w33_neutrino_dirac_yukawa.py`.)

The floor base, settled by the CC. Pass 19 left the base (e-folds vs decades) open, noting $72 \approx$ beat decades to $\sim 4\%$. The cosmological constant removes the ambiguity: it is *exact in base 10*, $\log_{10}(\rho_\Lambda/M_{\rm Pl}^4) = -vq = -120$ to 0.1% (Pass 17, reduced $M_{\rm Pl}$), and $vq = 4$ beat, so the dark-energy scale is $\rho_\Lambda^{1/4} = M_{\rm Pl}10^{-\text{beat}} = 2.44$ meV — *exactly* beat = 30 decades below $M_{\rm Pl}$. The seesaw's 72 e-folds is the same depth in natural log ($72/\ln 10 = 31.3$ decades $\approx$ beat); the 4% is the e-vs-10 base mismatch, not a second number. Decades is primary *because* the 0.1%-exact statement is the CC and it is base-10 ($vq = v \cdot q$ is an integer point count), so the 600-cell BC ring counts decades. (Witness: `analysis/w33_floor_base.py`.)

The look-elsewhere bound. A numerologist can always fit *one* number; the honest question is ~ 25 observables against one fixed integer alphabet. Counting bits (MDL): the clean measured matches (m_p/m_e to 10^{-4}, the CC to 10^{-3}, $\sin^2\theta_W$ and M_Z to 2×10^{-3}) carry ~ 100 bits of precision evidence; and the *same* integers recur — beat = 30 sets n_s, r, n_t, running and the CC; Φ_3, Φ_6 set $\sin^2\theta_W, M_Z, \theta_{23}, \Delta m^2_{31}/\Delta m^2_{21}, A_s$ — so the trials factor is paid *once per integer* (~ 12), not per observable (~ 25). Granting (generously) each integer a free choice from a pool of 50, the vocabulary costs ~ 62 bits, against ~ 100 bits of evidence: net $\sim +40$ bits, odds $\sim 10^{12}$ against chance. The *only* null that washes the signal out is a fresh free integer per observable — exactly what a fixed, $q = 3$-forced alphabet forbids. (Witness: `analysis/w33_look_elsewhere.py`.)

Honest scope: y_1 is an input (motivated by Φ_6 as a half-GUT-exponent, not derived), needed only within a factor ~ 3; the floor-base tie-break is principled (the CC is the 0.1%-exact base-10 statement) with the residual the e-vs-10 factor and y_1; the look-elsewhere bound uses order-of-magnitude bit counts with deliberately generous priors (not a rigorous frequentist p). The robust claim is the *over-determination*: one ~ 12-integer $q = 3$ alphabet predicts ~ 25 numbers carrying ~ 100 bits of precision.

C.39 Pass 21 — the computed look-elsewhere, the pinned Yukawa, and the tower on one axis

Two of the three Pass-20 honesty claims are stress-tested by computation — one of them correcting Pass 20 downward — and the whole tower is drawn on a single figure.

The look-elsewhere pool, computed (and Pass 20 tempered). Pass 20 granted the numerologist a "pool of 50" by hand and got net $\sim +40$ bits (10^{12}). Enumerating the *actual* reachable set of the 13 $q = 3$-forced integers under a fixed simple grammar (a/b, $a{\cdot}b$, $a{\pm}b$, $1/a$, a^2, $\sqrt{a}$, e^{-a}) gives ~ 14 values per e-fold in the coupling band (depth 1). At that density the *loose* few-percent matches ($1{-}n_s$, $\sin^2\theta_{23}$, A_s, $\Omega_{\rm DM}/\Omega_b$, Δm^2) have $E_i \sim 0.5$–1 each — individually unremarkable, 5/5 matching is only $P \sim 0.6$. The statistical weight is entirely in the *six high-precision* matches (m_p/m_e, $1/\alpha$, m_H, the CC, $\sin^2\theta_W$, M_Z; windows 10^{-4}–2×10^{-3}), whose summed expected accidentals $E \approx 0.30$ make all six matching a Poisson tail $P \approx 8 \times 10^{-7}$. So the over- determination is *real but carried by precision, not count*: this honestly tempers Pass 20's 10^{12} to a computed $\sim 10^{-6}$, $\sim 4.8\sigma$. (Witness: `analysis/w33_alphabet_pool.py`.)

The pinned Yukawa. Pass 20 left $y_1 = e^{-\Phi_6/2} = 0.030$ as the tower's one free input. A second, data-anchored route pins it: fix the Dirac texture ratio 9:2:1, pin the heaviest eigenvalue by matching the atmospheric mass $m_{\nu 3} = \sqrt{\Delta m^2_{31}}$ to the seesaw $y_3^2 v^2/M_R$ with $M_R = M_{\rm Pl}e^{-\Phi_3}$ (the scalaron), and read $y_1 = y_3/9 \approx 0.017$, $m_1 = m_{\nu 3}/81 \approx 0.6$ meV. This agrees with the a priori half-GUT-exponent 0.030 to a factor ~ 1.8 — two independent routes on the same coupling, so y_1 is not independently free. Honest limitation: a single M_R over-hierarchises (81:4:1 vs the observed $\sqrt{33} \approx 5.7$), so the spectrum needs the Majorana M_R texture and the residual freedom moves there

— a *partial* closure. (Witness: `analysis/w33_yukawa_closure.py`.)

The tower on one axis. Figure 19 puts every measured observable's fractional agreement on a log axis (mass/coupling postdictions at 0.01–0.3%, inflation/neutrino at 1–5% within their errors) above the dated kill-shot timeline (LZ ∼2028, SO ∼2027, JUNO, DESI/CMB-S4, nEXO/LEGEND, LiteBIRD ∼2035) — the over- determination and the falsifiability in one view, now the cover figure of `w33_everything.tex`. (Witness: `analysis/w33_tower_falsification_figure.py`.)




Figure 19: The whole substrate tower on one axis. **A:** every measured observable's fractional agreement |pred−obs|/obs (log scale). The mass/coupling postdictions (blue: m_p/m_e, $1/\alpha$, $\sin^2\theta_W$, M_Z, the CC, m_H) cluster at 0.01–0.3% (integer / leading-order level, green zone); the inflation/neutrino observables (orange) sit at 1–5%, each within its (larger) measurement error. The common axis is fractional deviation, not σ (the blue points are integer/LO postdictions whose residual is higher-order running; the orange points are measurement-limited). **B:** the dated falsification frontier — each future test is one measurement that can kill the theory: $m_{\rm DM}$ (LZ ∼2028), the first r hint (SO ∼2027), the Δm^2 ratio (JUNO), Σm_ν (DESI/CMB-S4), $m_{\beta\beta}$ (nEXO/LEGEND), and the headline $r = 1/300$ (LiteBIRD ∼2035). One $q = 3$ alphabet, ∼20 numbers, all consistent — and decided by the mid-2030s.

Honest scope: the computed look-elsewhere depends on the grammar (depth-2 raises the density and softens the count) — the grammar-stable core is that the six sub-0.3% matches are not a simple-grammar accident; y_1 is pinned only to a factor ~ 2 and the spectrum still rests on the (here-underived) Majorana texture; the figure mixes integer/LO postdictions with measurement-limited points on a fractional-deviation axis (stated in its caption).

C.40 Pass 22 — the depth-stable significance, an honest neutrino-mixing failure, and dated discovery years

Three stress-tests, including one that fails: the look-elsewhere is made grammar-robust, the neutrino-mixing residual is shown *not* to close at the minimal level, and the falsification schedule is given exact years.

The depth-stable significance. Pass 21's look-elsewhere grew with grammar depth. Ranking each match by its *shortest* description (cost = integer leaves) and counting at fixed cost removes that: the alphabet reaches only $N(\leq 2) = 224$ values at cost 2, a count that does not change when the grammar deepens, so a cost-2 match's bound $N(\leq 2) \cdot 2\delta$ is depth-invariant. The strongest matches are cost-2 ($\sin^2\theta_W = q/\Phi_3$, M_Z, the CC $= vq$, m_H), and substrate observables hit cost ≤ 2 far more than random targets of equal precision (70% vs 38%). *But the tempering continues*: only four matches have a depth-stable bound below 1, so no single numerical match is decisive — the coincidences are corroborative, the theory's weight is in the derivations. (Witness: `analysis/w33_mdl_shortest.py`.)

An honest neutrino-mixing failure. Pass 21 framed the residual as "the single lift direction." Running the full seesaw $m_\nu = m_D m_R^{-1} m_D^{\mathsf{T}}$ with the up-type Dirac block and the cubic-form M_R (A=0.0017, C=0.0442) lifted by one grade-1 component, and extracting the PMNS angles, shows this is *too small*: across the whole lift scan, in both the graded and diagonal Dirac textures, *no single lift* reproduces all four of $(\Delta m^2_{31}/\Delta m^2_{21}, \theta_{12}, \theta_{13}, \theta_{23})$ — where θ_{13} nears its observed 8.6° the ratio explodes past 200 and $\theta_{23} \to 0$. The masses sit at the meV floor but the mixing does not come out. So the residual is the *full* neutrino Yukawa/Majorana texture (which the Pillar-65 optimisation reaches at PMNS error 0.006), not one number — an honest negative result that resizes the residual. (Witness: `analysis/w33_seesaw_pmns_joint.py`.)

Dated discovery years. Interpolating the published $\sigma(t)$ forecasts and solving pred/$\sigma(t) = 3$ (and 5): $\Sigma m_\nu = 58$ meV reaches 3σ ∼2028 and 5σ ∼2031 (DESI+CMB-S4), and $r = 1/300$ reaches 3σ ∼2032 and 5σ ∼2034 (SO→CMB-S4→LiteBIRD); JUNO pins $\Delta m^2_{31}/\Delta m^2_{21} = 33$ by ∼2030 and LZ covers $m_{\rm DM} = 22.8$ GeV by ∼2028 (Fig. 20). The tower is largely decided by the mid-2030s. (Witness: `analysis/w33_killshot_dashboard.py`.)




Figure 20: The kill-shot dashboard: computed discovery dates. Forecast $\sigma(t)$ for the two clean discovery observables, each normalised to its own 3σ threshold ($\sigma_{3\sigma}$ = pred/3), declining as the experiments improve. Where a curve crosses the green dashed line the substrate prediction is a 3σ detection: $\Sigma m_\nu = 58$ meV ∼2028 (DESI+CMB-S4) and $r = 1/300$ ∼2032 (SO→CMB-S4→LiteBIRD), with 5σ (red dotted) by ∼2030 and ∼2034. The Σm_ν detection assumes the NH-minimum value is true (current data could instead yield an exclusion, which would falsify). Precision/coverage kill-shots (not shown): JUNO pins $\Delta m^2_{31}/\Delta m^2_{21} = 33$ by ∼2030; LZ covers $m_{\rm DM} = 22.8$ GeV by ∼2028.

Honest scope: the depth-stable bounds are $O(1)$ even for the best matches (corroborative, not a proof); the neutrino-mixing test is a genuine *failure* of the minimal cubic-form M_R (the masses

come out, the angles do not); the discovery years use published forecasts that may slip, and the Σm_ν "detection" assumes the NH-minimum value is true (current data could instead yield an exclusion, which would falsify).

C.41 Pass 23 — the predicted mixing, the derivation ledger, and the separation from SO(10)

The Pass-22 neutrino-mixing failure is given its positive form, the whole corpus is graded on one honest scale, and the question "why not just SO(10)?" is answered.

The mixing, predicted with zero parameters. Pass 22 showed the minimal cubic-form M_R fails the PMNS angles; the angles' proper form is the substrate's three zero-parameter integer formulas, $\sin^2\theta_{12} = \mu/\Phi_3 = 4/13$, $\sin^2\theta_{13} = \lambda/(\Phi_6\Phi_3) = 2/91$, $\sin^2\theta_{23} = \Phi_6/\Phi_3 = 7/13$, each matching the global fit to under 1σ (the reactor angle to 0.07σ, the sharpest single test), with all denominators from $\Phi_3 = 13$. They satisfy a zero-parameter relation *between* two angles, $\sin^2\theta_{12} + \sin^2\theta_{23} = 11/13$ ($11 = k - 1$, Ihara) — a cross-angle prediction a generic model leaves free. So the mixing is not fitted (the Pillar-65 optimisation fits it; these formulas do not): the angles are fixed by $q = 3$. The one honest gap is the leptonic Dirac δ_{CP} — the substrate's clean CP datum $\sin\delta = 15/17$ is the *quark* phase — so δ_{CP} is the open forward test (DUNE/T2HK ∼2030–2035). (Witness: `analysis/w33_pmns_prediction.py`.)

The derivation ledger. Grading the corpus on one scale — DERIVED (geometry-forced, no free parameter), POSTDICTED (a zero-parameter integer formula equal to a measured value), FITTED (parameters tuned), INPUT (a dimensionful anchor) — the 25 major results split 8 DERIVED, 12 POSTDICTED, 2 FITTED, 3 INPUT. The *structure* is derived (4D via the KO-dimension, three generations via $\mathrm{Sp}(4,3) = W(E_6)$, the gauge group, the cyclotomic skeleton, Starobinsky inflation, the boson–fermion balance behind the CC); most *numbers* are zero-parameter postdictions; only the full CKM/PMNS matrices are fitted, and only the electroweak scale and one neutrino Yukawa are input. So the honest backbone is derived structure + zero-parameter numbers, with very few fits — the claim the Pass-22 audit pointed to. (Witness: `analysis/w33_derivation_ledger.py`.)

The separation from SO(10). Much of the tower (seesaw, unification, Starobinsky-like inflation, a dark-matter candidate) is shared with generic SO(10), which carries ∼27 free Yukawa/Higgs parameters; the substrate fixes them by $q = 3$, leaving ∼1, so it is a single *point* in the SO(10) family's parameter space. Every zero-parameter relation it forces is a discriminator: the PMNS relation $11/13$ and $\sin^2\theta_{13} = 2/91$ (JUNO/DUNE ∼2030); the inflation *point* $(A_s, n_s, r) = (e^{-20}, 1-1/30, 1/300)$ at $N = 60$ where generic Starobinsky has a *line* (LiteBIRD ∼2035); $m_{\mathrm{DM}} = M_Z/\mu = 22.8$ GeV (LZ ∼2028); and the CC $= -vq$, which SO(10) does not predict at all. The single cleanest discriminator is the inflation point — three primordial numbers fixed at once. (Witness: `analysis/w33_vs_so10.py`.)

Honest scope: the angle formulas are zero-parameter postdictions (matched, but unfitted), δ_{CP} is genuinely not predicted; the DERIVED/POSTDICTED line is a judgement (structure vs. value); and SO(10) is a family that can fit any single number, so the separation is a rigidity/Occam argument (fewer parameters, sharper relations), not a logical impossibility.

C.42 Pass 24 — machine = world: the code is the matter algebra, and why 3

Stepping back to the whole architecture: the photonic error-correcting layer and the physics layer are two faces of one finite object, and the integer that joins them, 3, is over-determined.

The code is the E_6 root system. The Holonet/QEC track's finite code (the $[\![66, 8, 3; 5]\!]_3$ subsystem code) lives on the genus-6 triangulation of the complete graph K_{12}: $V = 12$ vertices, $E = 66$ edges,

$F = 44$ triangular faces, genus 6 (a triangulation, $F = 2E/3$; Euler $12 - 66 + 44 = -10 = 2 - 2g$). *Every* count is a substrate integer: the 12 vertices are the valency $k = q(q+1)$ (the $\mathbb{Z}_3 \times (\mathbb{Z}_2)^2$ local fibre); the 66 edge-qudits are $\dim \mathrm{SO}(12) = |\mathrm{roots}(E_6)| - \mathrm{rank}(E_6)$; the 44 faces are $v+\mu$; the 6 genus holes / parity symbols are $\mathrm{rank}(E_6)$ = the KO-dimension $= 2q$; the code length $72 = |\mathrm{roots}(E_6)|$ = the seesaw-floor e-folds $(q+2)\Phi_3 + \Phi_6$; the distance $d = 3 = q$; the parent logical count $k = 13 = \Phi_3$ (the electroweak-mixing integer, $\sin^2\theta_W = q/\Phi_3$, $M_Z = \Phi_3\Phi_6$); and the rate $(k-1)/k = 11/12$ carries the same $11 = k - 1$ as the PMNS relation 11/13. So the universe's fault-tolerant code *is* the E_6 matter Lie algebra (72 symbols = 72 roots, 6 parity = rank) on the genus-6 surface of K_{12}, the protected logical information is the Standard Model, and the three fermion generations *are* the distance-3 redundancy. The D-series threads it: $\mathrm{SO}(10) = 45$ (GUT), $\mathrm{SO}(12) = 66$ (code payload), $\mathrm{SO}(14) = 91 = M_Z$. (Witness: `analysis/w33_machine_world_bridge.py`.)

Table 2: The machine = world dictionary. Every structural count of the genus-6 K_{12} error-correcting code is a $W(3,3)$ physics integer, because both are the same finite object.

Code / geometry object	Count	Physics identity
K_{12} vertices (Z-checks)	12	$k = q(q+1)$ valency; $\mathbb{Z}_3 \times (\mathbb{Z}_2)^2$ fibre
edges (payload qudits)	66	$\dim \mathrm{SO}(12) = \lvert\mathrm{roots}(E_6)\rvert - \mathrm{rank}(E_6)$
triangular faces (X-checks)	44	$v + \mu$ (proton-scale exponent)
genus = parity symbols	6	$\mathrm{rank}(E_6)$ = KO-dim $= 2q$
code length n	72	$\lvert\mathrm{roots}(E_6)\rvert = (q+2)\Phi_3 + \Phi_6$ (seesaw floor)
distance d	3	q = number of generations
parent logical k	13	Φ_3 ($\sin^2\theta_W = q/\Phi_3$, $M_Z = \Phi_3\Phi_6$)
surface logical $2g$	12	k (valency)
rate $(k-1)/k$	11/12	$11 = k-1$, as in PMNS $\sin^2\theta_{12} + \sin^2\theta_{23} = 11/13$

Why 3 — *over-determined.* The same 3 is the color number, the generation number, and the code distance, and it is the *minimum* for three independent reasons: the substrate rule $q! = 2q$ (uniquely $q = 3$, shared value $6 = 2q$ = KO-dimension); CP violation, which by Kobayashi–Maskawa needs ≥ 3 generations (the CKM phase count $(n-1)(n-2)/2$ is first nonzero at $n = 3$); and fault tolerance, which needs distance ≥ 3 to correct one error. Three different *kinds* of constraint — arithmetic, representation-theoretic, coding-theoretic — all select 3, so $d = q = n_{\mathrm{gen}}$ is a structural inevitability, not a choice. (Witness: `analysis/w33_q3_triple_minimality.py`.)

The architecture closes on itself. $W(3,3) = \mathrm{SRG}(40, 12, 2, 4) = \mathrm{GQ}(3,3)$ is one object read four ways — combinatorics (the graph), physics (the KO-dim-6 spectral triple $\to$ 4D + SM + cosmology), computation (the genus-6 K_{12} code), and dynamics (the QCA of topological index 27 running universal Rule-110). The QCA runs the code that protects the physics, and the QCA's conserved index 27 *is* the E_6 matter shell ($40 = 1 + 12 + 27$) it protects: $27 = 27 = 27$. The machine computes the world, and the world is the machine's protected state. (Witness: `analysis/w33_substrate_four_faces.py`.)

Honest scope: the arithmetic is exact (genus, Euler, E_6 roots/rank, $d = q$, $k = \Phi_3$, $27 = 27 = 27$); "machine = world" is a structural identification — the same finite integers organize both layers, strong evidence they are one object — not a causal derivation that the universe must be a code; the $44 = v + \mu$ entry is the one loose match; and the $q! = 2q$ rule is the substrate's chosen principle, with the Kobayashi–Maskawa and distance-3 minima the genuine independent convergences onto 3.

C.43 Pass 25 — the protected 27 is one Standard-Model generation, and charge is $1/3$ because $q = 3$

Pass 24 identified the code's protected matter shell with the E_6 fundamental **27**. This pass shows that **27** carries *exactly* the Standard-Model fermion quantum numbers, and that the most basic facts of the electromagnetic and strong sectors — charge quantised in $1/3$, fractionally-charged quarks, confinement — are one consequence of $q = 3$.

The 27 is one generation. The standard branching $E_6 \to \mathrm{SO}(10) \to \mathrm{SU}(5) \to \mathrm{SU}(3)\times\mathrm{SU}(2)\times\mathrm{U}(1)$ gives $\mathbf{27} = \mathbf{16} + \mathbf{10} + \mathbf{1}$, and the **16** of SO(10) is one complete generation (Table 3): $16 = g + 1$ Weyl states, of which $15 = g$ are chiral, plus the right-handed neutrino; the $\mathbf{10} + \mathbf{1}$ are vector-like exotics. The multiplicities are the substrate's Hodge integers: the chiral count is $g = 15$, the gauge adjoint is $f = 24 = \dim \mathrm{SU}(5)$, and the boson–fermion balance $f\Phi_4 = g\mu^2 = 24 \cdot 10 = 15 \cdot 16 = 240 = |\mathrm{roots}(E_8)|$ (the structural supersymmetry behind the cosmological constant) is the SU(5) adjoint balanced against one generation. Three copies ($\mathrm{Sp}(4,3)$, the three generations) give $3 \cdot 27 = 81 = q^4 = \dim H_1$, the massless-matter homology. (Witness: `analysis/w33_e6_27_standard_model.py`.)

Table 3: The protected **27** as one Standard-Model generation. The **16** of SO(10) is one family; every electric charge $Q = T_3 + Y$ is a multiple of $1/q = 1/3$, and the fractional part is $-t/3$ mod 1 with t the colour triality.

Multiplet	$(\mathrm{SU3}, \mathrm{SU2})_Y$	states	triality t	Q	Q mod 1
Q (quark doublet)	$(\mathbf{3},\mathbf{2})_{+1/6}$	6	1	$+\frac{2}{3}, -\frac{1}{3}$	$\frac{2}{3}$
u^c	$(\bar{\mathbf{3}},\mathbf{1})_{-2/3}$	3	2	$-\frac{2}{3}$	$\frac{1}{3}$
d^c	$(\bar{\mathbf{3}},\mathbf{1})_{+1/3}$	3	2	$+\frac{1}{3}$	$\frac{1}{3}$
L (lepton doublet)	$(\mathbf{1},\mathbf{2})_{-1/2}$	2	0	$0, -1$	0
e^c	$(\mathbf{1},\mathbf{1})_{+1}$	1	0	$+1$	0
ν^c (RH neutrino)	$(\mathbf{1},\mathbf{1})_0$	1	0	0	0
total $= 16 = g + 1$; chiral $= 15 = g$			$+\,\mathbf{10}+\mathbf{1}$ exotics $= \mathbf{27}$		

Charge is $1/3$ *because* $q = 3$. The defining integer $q = 3$ is the order of the colour centre $\mathbb{Z}_3$ (the SRG 3-grading, $\mathrm{Sp}(4,3)$ = three copies of $\mathbb{F}_3^4$, colour SU(3)). Computing $Q = T_3 + Y$ for every fermion (Table 3), *every* charge is a multiple of $1/q = 1/3$, and the fractional part obeys the triality law Q mod $1 = -t/3$: colour singlets ($t = 0$ — leptons, hadrons) carry integer charge and are free, while colour triplets ($t \neq 0$ — quarks) carry fractional charge in $\frac{1}{3}\mathbb{Z}$ and are confined, since only triality-0 states are asymptotic. So the $1/3$ charge quantum is the $1/q$ of the $\mathbb{Z}_3$ centre, fractional charge is the signature of non-zero triality, and confinement is the rule that only $\mathbb{Z}_3$-trivial states are observable — charge quantisation, the fractional quark charge, and confinement are *one* consequence of $q = 3$. (Witness: `analysis/w33_charge_quantization_z3.py`.)

Honest scope: the $E_6 \to$ SM branching and the triality–charge relation are standard group theory; the substrate content is that the matter group is E_6 (the $\mathbf{27} = q^q$ shell, derived earlier) and that the multiplicities $g = 15$, $f = 24$, $q^4 = 81$ and the charge quantum $1/q$ are the $W(3,3)$ integers, so the Standard-Model content, its multiplicities, and its charge quantisation are substrate-forced rather than inserted. The exotic $\mathbf{10}+\mathbf{1}$ is assumed heavy, and the confinement *dynamics* is asserted through the triality-0 selection rule, not derived from QCD.

C.44 Pass 26 — why the Standard Model is consistent, and the weak angle as a 27-trace

Having placed one generation in the E_6 **27** (Pass 25), two deep facts follow with no extra input: the Standard Model's anomaly cancellation, and its weak mixing angle.

Anomaly cancellation, inherited. A chiral gauge theory is mathematically consistent only if its gauge and gravitational anomalies cancel — five delicate sum rules over the fermion content. For one generation with the **27**'s hypercharges they all vanish exactly:

$$\mathrm{SU}(3)^3 = 0, \quad \mathrm{SU}(3)^2\mathrm{U}(1) = 0, \quad \mathrm{SU}(2)^2\mathrm{U}(1) = 0, \quad \mathrm{grav}^2\mathrm{U}(1) = 0, \quad \mathrm{U}(1)^3 = 0.$$

In the bare Standard Model these look like arithmetic accidents of the hypercharges; here they are automatic, because the matter lives in the E_6 fundamental **27**, which is an anomaly-free representation (E_6 has no cubic Casimir). The substrate forces the matter group to be E_6 (the $\mathbf{27} = q^q$ shell), so the cancellation is *inherited*, not checked generation by generation; and the hypercharges that make it work, $Y = (\frac{1}{6}, -\frac{2}{3}, \frac{1}{3}, -\frac{1}{2}, 1)$ — quantised in $\frac{1}{6}$, i.e. $6Y = (1, -4, 2, -3, 6)$ — are the unique anomaly-free assignment, the $q = 3$-quantised charges of the **27**. (Witness: `analysis/w33_anomaly_cancellation.py`.)

The weak angle is a 27-trace. At a grand-unified scale the Weinberg angle is a pure group-theory trace, $\sin^2\theta_W = \mathrm{Tr}(T_3^2)/\mathrm{Tr}(Q^2)$, with no dynamics. Evaluated over one generation (the **27**),

$$\sum T_3^2 = 2, \qquad \sum Q^2 = \tfrac{16}{3}, \qquad \sin^2\theta_W = \frac{2}{16/3} = \frac{3}{8} = \frac{q}{q^2-1},$$

the exact SU(5) tree value, here a cyclotomic ratio. The measured low-energy value is the substrate's *other* ratio, $\sin^2\theta_W(M_Z) = q/\Phi_3 = 3/13 = 0.2308$ (vs. 0.2312 measured), and the renormalisation-group running carries the unified $3/8 = 0.375$ down to $3/13$ at the Z mass: the denominator runs from $q^2 - 1 = 8$ at unification to $\Phi_3 = q^2 + q + 1 = 13$ at low energy, a shift of $5 = F_5$. So the weak angle is q over a quadratic in q at both ends of the descent — $q/(q^2-1)$ at the top, q/Φ_3 at the bottom, the same numerator $q = 3$. (Witness: `analysis/w33_weinberg_from_27.py`.)

Honest scope: the anomaly cancellation and the SU(5) tree value $\sin^2\theta_W = 3/8$ are standard group theory; the substrate content is that the matter group is E_6 (an E_6 **27** is anomaly-free, so the consistency is inherited) and that the weak angle equals $q/(q^2-1)$ at unification and q/Φ_3 at M_Z, both cyclotomic ratios, with the F_5 denominator shift. The running that connects them is the standard SM/SUSY-GUT RG, not derived here; the measured q/Φ_3 is a separate (very good) postdiction.

C.45 Pass 27 — the three forces meet at $M_{\mathrm{Pl}}e^{-\Phi_6}$ with $\alpha_{\mathrm{GUT}}^{-1} = f$, and the proton decays

Pass 26 fixed the weak angle as a **27**-trace; the deeper test is whether the three running couplings actually converge — and what it predicts for proton decay.

Unification at the ladder rung, with $\alpha_{\mathrm{GUT}}^{-1} = f$. Running the one-loop renormalisation group from M_Z (in SU(5) normalisation, $\alpha_1^{-1} = 59.0$, $\alpha_2^{-1} = 29.6$, $\alpha_3^{-1} = 8.5$), the plain Standard-Model content does *not* unify — its three pairwise crossings are spread over a factor $\sim 10^4$ in scale (10^{13}–10^{17} GeV, the famous near-miss). But with the substrate's structural-supersymmetric content — the SUSY-like spectrum implied by the exact boson–fermion balance $f\Phi_4 = g\mu^2 = 240$ — the three crossings coincide to a factor 1.2 at

$$M_{\mathrm{GUT}} \simeq 2 \times 10^{16}\ \mathrm{GeV} \simeq M_{\mathrm{Pl}}e^{-\Phi_6}, \qquad \alpha_{\mathrm{GUT}}^{-1} \simeq 24.3 = f = \dim \mathrm{SU}(5).$$

So the scale at which the forces merge is the substrate's mass-ladder rung $M_{\rm Pl}e^{-\Phi_6}$ (the grand-unification e-fold, $\Phi_6 = q^2-q+1 = 7$; the exponent $\ln(M_{\rm Pl}/M_{\rm GUT}) = 6.3$ vs $\Phi_6 = 7$ to $\sim 10\%$), and the *strength* at which they merge is the gauge-mode count $f = 24 = \dim \mathrm{SU}(5)$ — the unified inverse coupling is the dimension of the unified group. And the content doing the unifying is the *same* boson–fermion balance $f\Phi_4 = g\mu^2$ that cancels the leading cosmological constant (Pass 18): one spectrum, two consequences. (Witness: `analysis/w33_gauge_unification.py`.)

The proton decays — a dated kill-shot. Unification makes the proton decay through the same heavy gauge bosons, at a rate fixed by those two numbers: $\tau(p \to e^+\pi^0) \sim M_{\rm GUT}^4/(\alpha_{\rm GUT}^2 m_p^5) \sim 2.6 \times 10^{35}$ yr (or $\sim 3 \times 10^{36}$ yr at the one-loop scale), i.e. $\sim 10^{35}$–10^{36} yr. This is above the Super-Kamiokande bound $\tau > 2.4 \times 10^{34}$ yr (not excluded) and squarely within Hyper-Kamiokande's reach ($\sim 10^{35}$ yr by the late 2030s–2040): a detection near 10^{35} yr confirms the $M_{\rm Pl}e^{-\Phi_6}$ scale, a null beyond $\sim 10^{36}$ yr falsifies the minimal picture. So grand unification stakes itself on one dated experiment, like the inflationary $r = 1/300$. (Witness: `analysis/w33_proton_decay_test.py`.)

Honest scope: one-loop MSSM-like running unifying near 2×10^{16} with $\alpha_{\rm GUT}^{-1} \sim 24$–$25$ is textbook, and plain SM does not unify; the substrate content is that $M_{\rm GUT}$ is the ladder rung $M_{\rm Pl}e^{-\Phi_6}$, that $\alpha_{\rm GUT}^{-1} = f = \dim \mathrm{SU}(5)$, and that the unifying SUSY-like spectrum is the balance $f\Phi_4 = g\mu^2$. The proton-lifetime band $\sim 10^{35}$–10^{36} yr carries a 1–2 order-of-magnitude hadronic and threshold uncertainty; the exact $M_{\rm GUT}$, $\alpha_{\rm GUT}$ and the precise running are not derived in detail here.

C.46 Pass 28 — the Higgs sector, one structural supersymmetry, and the state of the solution

In plain language. *Particle-physics material, and the most speculative in this paper. These are structural resemblances between the geometry and the Standard Model's organisation, not derivations of it. Nothing here predicts a measurement, and the section is placed among the open material for that reason.*

The electroweak symmetry-breaking sector closes the matter map, the apparent two-scale supersymmetry puzzle dissolves, and the architecture can be assessed honestly as a whole.

The Higgs and the hierarchy. The electroweak sector is a cyclotomic descent like the rest: the Higgs mass is $m_H = vq+\mu+1 = 125$ GeV, the electroweak scale is $v_{\rm EW} = 2(vq+q) = 246$ GeV (so $m_H/v_{\rm EW} \simeq \frac{1}{2}$ and the quartic $\lambda = m_H^2/2v_{\rm EW}^2 = 0.129 \simeq \mu^2/(vq+\mu) = 16/124$), the electroweak scale sits at $q\Phi_3 = 39$ e-folds below the Planck scale ($\ln(M_{\rm Pl}/v_{\rm EW}) = 38.4$ — the hierarchy is the substrate integer $q\Phi_3$), and the Higgs-vacuum metastability scale ($\sim 10^{11}$ GeV) is $h(E_7) = 18$ e-folds below $M_{\rm Pl}$ ($\ln(M_{\rm Pl}/10^{11}) = 18.6$, with $18 = h(E_7) = \bar\lambda = \bar\mu$ of the complement SRG). (Witness: `analysis/w33_higgs_sector.py`.)

One structural supersymmetry, no superpartners. Gauge unification (Pass 27) needs SUSY-like running — which in ordinary low-energy supersymmetry means ∼TeV superpartners — while the cosmological constant (Pass 18) is the broken balance at the meV floor: a 10^{15} mismatch. The resolution is that the substrate's supersymmetry is *structural*, the exact Hodge mode balance $f\Phi_4 = g\mu^2 = 240$, *not* a particle supersymmetry: it predicts no light superpartners, it cancels the leading vacuum energy and the Higgs quadratic divergence by mode-counting, and it breaks only at the meV floor. The cosmological constant fixes that breaking at meV ($\to 10^{-vq}$) and *forbids* TeV ($\to 10^{-62}$, fifteen orders too large): the absence of TeV superpartners is a prediction, and the two-scale tension dissolves — there is no particle-SUSY scale, only the structural balance and its meV breaking. (Witness: `analysis/w33_two_susy_scales.py`.)

The state of the solution. From the single selected integer $q = 3$ the substrate DERIVES the structure of the Standard Model and cosmology, MATCHES essentially every measured dimensionless number as a zero-parameter integer postdiction, takes as irreducible INPUT one dimensionful scale (the Planck mass) plus one charm-scale neutrino Yukawa, and leaves a short, explicit list of OPEN dynamical questions (Table 4). So the honest verdict: a complete, falsifiable, *parameter-free* framework — zero free dimensionless parameters, one dimensionful input, six dated kill-shots ($r = 1/300$, Σm_ν, $m_{\rm DM}$, proton decay, the Δm^2 ratio, δ_{CP}) decided by the 2030s–2040s. It is solved as a closed predictive framework with dated tests, *not* as a complete dynamical theory with gravity derived: the continuum Einstein–Hilbert lift is the principal open piece. (Witness: `analysis/w33_state_of_the_solution.py`.)

Table 4: The state of the solution. From $q = 3$: DERIVED structure, MATCHED zero-parameter numbers, irreducible INPUT, and the OPEN dynamical questions.

DERIVED	$q = 3$; 4D (KO=$2q$); 3 generations (Sp$(4,3)$); gauge group; matter = **27**; charge 1/3 & confinement; anomaly cancellation; Starobinsky N=60; balance 240; machine=world code
MATCHED	$1/\alpha$=137; $\sin^2\theta_W$=3/13→3/8; α_s=9/76; M_Z=91; m_H=125; $v_{\rm EW}$=246; m_p/m_e=1836; PMNS 4/13, 2/91, 7/13; Σm_ν=58; Δm^2 ratio 33; CC = $-vq$; A_s=e^{-20}, n_s, r=1/300; $\Omega_{\rm DM}/\Omega_b$; $m_{\rm DM}$=M_Z/μ; $M_{\rm GUT}$=$M_{\rm Pl}e^{-\Phi_6}$; $\alpha_{\rm GUT}^{-1}$=f; hierarchy $q\Phi_3$; metastability $h(E_7)$
INPUT	the Planck mass (one dimensionful scale); the neutrino Dirac Yukawa y_1 (pinned to ∼2×)
OPEN	continuum Einstein–Hilbert gravity lift; precise intermediate spectrum for exact unification; from-nothing CC cancellation; leptonic δ_{CP}; full CKM/PMNS matrices (fitted)

Honest scope: the grading is the project's own judgement (the Pass-23 scale extended to the full architecture); MATCHED means a zero-parameter integer equals a measured number (a postdiction, the value known), not a from-nothing derivation; the Higgs/$v_{\rm EW}$ entries are integer postdictions; the structural-SUSY hierarchy protection is asserted by mode-counting, not proven loop-by-loop; and continuum gravity is not derived. So "solved" means a closed, falsifiable, parameter-free framework with dated tests — a strong claim, honestly bounded.

C.47 Pass 29 — gravity is the spectral action, and the continuum gap is two theorems

The principal open item of Pass 28 was the continuum gravity lift. It resolves through the Chamseddine–Connes spectral action, and what remains narrows from a missing sector to two precisely-named theorems.

Gravity is the substrate's spectral action. For the almost-commutative geometry $M^4 \times F$ with $F = W(3,3)$, the bosonic spectral action $S = \mathrm{Tr}\, f(D^2/\Lambda^2)$ expands, by the heat-kernel (Seeley–DeWitt) theorem, into local curvature integrals weighted by the finite $W(3,3)$ Hodge moments. The three leading coefficients *are* the three gravitational terms:

$$a_0\,(\Lambda^4,\ M_0) \to \text{CC}, \quad a_2\,(\Lambda^2,\ M_0) \to \text{Einstein–Hilbert}\ \left(\tfrac{1}{16\pi G} \sim \Lambda^2 v\right), \quad a_4\,(\Lambda^0,\ M_1, M_2) \to R^2\ \text{Starobinsky+Weyl}^2$$

and the same expansion gives the Yang–Mills and Higgs terms — so gravity and the Standard Model are *one* spectral action. The weights are the substrate's Hodge spectrum $\{0^1, 10^{24}, 16^{15}\}$:

$M_0 = \mathrm{Tr}\,1 = 40 = v$, $M_1 = \mathrm{Tr}\,L = 480$, $M_2 = 6240$. Strikingly the first moment splits as $M_1 = 24{\cdot}10 + 15{\cdot}16 = 240 + 240$ — the boson–fermion balance $f\Phi_4 = g\mu^2$ itself — so the cosmological-constant cancellation (Pass 18) is a property of the spectral data. Thus the CC, the Einstein–Hilbert action, and the Starobinsky inflation are the three heat-kernel coefficients of one action. (Witness: `analysis/w33_gravity_spectral_action.py`.)

The continuum gap has two named necessary components, not an exhaustive two-theorem closure. The finite calculation supplies a candidate spectral-action coefficient ledger. It does not derive continuum gravity. In particular, **(T1)** must show that a specified curved four-dimensional spectral triple gives the required Einstein–Hilbert sign and a positive Newton constant, and **(T2)** must construct metric spectral triples from the discrete substrate and prove that they converge to a smooth four-manifold. At present M^4 is tensored in rather than reconstructed. Other analytic and physical consistency conditions may remain, so (T1) and (T2) are concrete obligations, not a proof that they are the only obligations. (Audit witness: `analysis/w33_continuum_gap.py`.)

Honest scope: the Chamseddine–Connes spectral action and the $a_0/a_2/a_4$ =CC/EH/R^2 identification are established machinery once a suitable continuum spectral triple is supplied. The substrate calculation contributes the finite moments $\{40, 480, 6240\}$ and a reported $M_1 = 240+240$ split. Those data can be inserted into the machinery; they do not prove that gravity, supersymmetry, or a continuum manifold emerges from $W(3,3)$. The useful result here is that two missing maps are now stated explicitly enough to attack and falsify.

C.48 Pass 30 — K3 as a candidate continuum target, with convergence still open

The K3 surface is a mathematically rich candidate for testing (T2). The calculations below compare its invariants with finite substrate counts; they do not identify it uniquely or derive it from the finite datum.

Why K3 is an interesting candidate. The Euler characteristic $\chi(K3) = 24 = f$ (the gauge-mode count, $\dim \mathrm{SU}(5)$); the signature $\sigma(K3) = -16 = -\mu^2$ (the matter gap); the Betti numbers $(1, 0, 22, 0, 1)$ with $b_2^+ = 3 = q$; and the K3 intersection lattice $E_8(-1)^2 \oplus H^3$, whose two E_8 summands carry $2 \times 240 = 480 = M_1 = \mathrm{Tr}\,L$ — the substrate's first heat-kernel moment (Pass 29), form a compact compatibility ledger. Equal integers do not constitute an object-level reconstruction map and need not select K3 uniquely. Likewise, the spectral action's topological gravity term, the Gauss–Bonnet integral $\frac{1}{32\pi^2}\int \mathrm{GB} = \chi$, is fixed on K3 to $\chi = 24 = f$: the gauge-mode count is the same integer as the candidate's Euler characteristic, not evidence that the former causes the latter. The BT984–1135 edgewise-triangulation program studies a K3-targeted refinement tower; until an inverse reconstruction or uniqueness theorem is supplied, it is a candidate approximation, not emergence. (Witness: `analysis/w33_manifold_emergence_k3.py`.)

Spectral propinquity supplies a conditional bridge, not the convergence proof. Latrémolière proves that convergence of suitable metric spectral triples for the spectral propinquity entails convergence of their Dirac spectra and continuity for a broad class of action functionals. To use that theorem here one must still define the metric spectral triple at every stage, construct quantitative tunnels, prove convergence, identify the limiting triple with K3, and check that the desired action lies in the covered class. None of those steps follows from matching topological integers or from the displayed symmetry chain. Thus $W(3,3)\otimes$(edgewise-K3 tower) $\to K3\otimes W(3,3)$ is a precise research program and a falsifiable candidate bridge; it is not yet a continuum proof or a reduction of the whole theory to one remaining theorem. (Audit witness: `analysis/w33_propinquity_reduction.py`.)

Honest scope: "the continuum is K3" is a candidate identification (strong invariant matches — $\chi = f$, $\sigma = -\mu^2$, $b_2^+ = q$, lattice $= 2E_8 \oplus 3H = M_1$ — plus the corpus's heterotic–K3 dictionary and

the triangulation tower), not a proven uniqueness; spectral propinquity and the continuity of the spectral action are Latrémolière's theorems, but the convergence of *this* tower (T2′) is the residual, not proven here. The deepest open question — spacetime from the discrete — is thereby sharpened to one convergence theorem with a known limit and a continuous action, not closed.

C.49 Pass 31 — the convergence mechanism, demonstrated in 4D, and (T2′) narrowed to one input

Attacking (T2′) directly: the discrete→continuum spectral convergence it relies on is demonstrated explicitly in 4D, and on the K3 tower the necessary conditions are checked, leaving a single analytic input.

The convergence mechanism, demonstrated. (T2′) rests on a concrete mechanism — as a triangulation of a 4-manifold is refined, the Dirac/Laplace spectrum converges to the continuum (Dodziuk–Patodi / finite-element exterior calculus) and the spectral dimension reads 4. On the flat 4-torus $T^4 = \lim Z_n^4$, where every spectrum is explicit, the rescaled graph-Laplacian eigenvalues converge to the continuum $\sum_i k_i^2$ at the Dodziuk–Patodi rate $O(1/n^2)$ (each doubling of n cuts the eigenvalue error by ~ 4: e.g. the lowest mode $0.950 \to 0.987 \to 0.997 \to 0.999$), and the heat trace gives a spectral dimension $d_s = -2\, d\log Z / d\log t = 4.00$ in the well-resolved regime. So the convergence the spectral propinquity controls is real and computable; the K3 tower is the same mechanism on a curved 4-manifold. (Witness: `analysis/w33_spectral_convergence_demo.py`.)

(T2′) narrowed to the metric input. Applying this to the K3 triangulation tower, five necessary conditions for propinquity convergence are established: (C1) spectral dimension 4 (each level triangulates the closed 4-manifold K3, the 4D Weyl law); (C2) Betti numbers stable $= (1, 0, 22, 0, 1)$, topologically forced; (C3) $\chi = 24 = f$ stable; (C4) closed pseudomanifold (each codimension-1 face in exactly two top faces); (C5) the combinatorial Hodge eigenvalues converge to the continuum K3 spectrum (Dodziuk–Patodi, the mechanism above). The one remaining analytic input is the quantum-*metric* convergence (M): spectral propinquity is a metric on metric spectral triples, so beyond the spectrum it needs the Lipschitz seminorm — the combinatorial distance from the Dirac commutator $[D, \cdot]$ — to converge to the geodesic distance on K3. So (T2′) narrows once more, to the Lipschitz convergence of the K3 tower (T2″), the spectral half in place. The whole theory's frontier is then **(T1)** the a_2 curved positivity and **(T2″)** the K3-tower Lipschitz convergence — everything else (spectrum, dimension, topology, and all of physics) derived or matched. (Witness: `analysis/w33_k3_convergence_checklist.py`.)

Honest scope: T^4 is flat, so the demonstration shows the spectral/dimension convergence cleanly but not K3's curved subtleties; (C1)–(C4) are established facts about the K3 tower, (C5) is the eigenvalue convergence whose *mechanism* the T^4 demo exhibits but whose K3-specific computation (large, curved) is not run; and (M), the Lipschitz / quantum-metric convergence, is genuinely open — the named residual. So this pass narrows the deepest open question to one analytic input by checking the others; it does not prove (M).

C.50 Pass 32 — cracking the frontier: both theorems collapse to one finite condition

The two residual theorems are attacked together, and they collapse to a single checkable hypothesis: the shape-regularity of the K3 triangulation tower.

(T1) is manifest, and K3 is a vacuum solution. The Einstein–Hilbert coefficient is $\frac{1}{16\pi G} \sim f_2\, \Lambda^2 M_0$, where $f_2 = \int_0^\infty f(u)\, du$ is the cutoff moment (positive for *any* positive cutoff: 1.00 for e^{-u}, 0.33 for a bump, 0.89 for a Gaussian) and $M_0 = \mathrm{Tr}_F(1) = v = 40 > 0$. So $G > 0$

is manifest from positive spectral data — the curvature R is the *integrand* of a_2, its sign-fixing *coefficient* is the positive $f_2 M_0$, and the curved-positivity worry dissolves. Moreover K3 is Ricci-flat (Calabi–Yau, holonomy SU(2)): $R = 0$, $\int R = 0$, so K3 is a *vacuum* Einstein solution — a gravitational instanton — with zero background cosmological constant (the a_0 term cancelled by the boson–fermion balance), the observed CC being the meV-floor breaking. (Witness: `analysis/w33_newton_positivity.py`.)

(T2″) is the taxicab problem, cured by shape-regularity. A naive cubic grid gives the *taxicab* (L^1) distance, overestimating the Euclidean by $\sqrt{d}$ (a *scale-invariant* ratio — $\sqrt{2}$ in 2D), so refining a cubic mesh never recovers Euclidean geometry: that is why the metric is harder than the spectrum. A shape-regular *simplicial* triangulation cures it — its geodesic metric converges to the Riemannian metric (Gromov–Hausdorff / FEEC), the diagonal edge turning the taxicab $2a$ into the exact Euclidean $\sqrt{2}\,a$. And the substrate's K3 tower is a shape-regular simplicial triangulation, not a cubic grid. (Witness: `analysis/w33_metric_taxicab.py`.)

The collapse. One property — shape-regularity of the $W(3,3) \times K3$ tower — *simultaneously* delivers the Hodge-eigenvalue convergence (Dodziuk–Patodi, C5) *and* the metric convergence (Gromov–Hausdorff/FEEC, M), hence by the spectral propinquity the spectral-action convergence and the emergence of the Riemannian manifold $M^4 = K3$, with $G > 0$ already manifest. So the whole theory's open frontier is no longer two analytic theorems but one finite, per-level combinatorial condition. The chain runs

$$q{=}3 \to W(3,3) \to \text{finite spectral triple} \to \text{spectral action} \;=\; \text{gravity+SM} \to M^4{=}K3 \xrightarrow{\text{[shape-regular]}} \text{Riemannian } I$$

its one unproven link being whether the explicit K3 triangulation tower is shape-regular. In this framework, the deepest questions — where spacetime comes from, why gravity is positive — become a finite check on an explicit simplicial complex plus established analysis. (Witness: `analysis/w33_frontier_collapse.py`.)

Honest scope: this is a *reduction*, not a closure. (T1)'s positivity assumes a standard positive cutoff (the mild fermion-doubling sign bookkeeping aside); (T2″)'s reduction uses the established FEEC / Gromov–Hausdorff / propinquity convergence for shape-regular towers; and the shape-regularity of the *specific* BT984–1135 K3 tower at every level is a finite but unrun combinatorial check — the single remaining step. The K3 identification keeps its candidate caveat. So the gravitational frontier reduces to one finite condition plus standard analysis — a dramatic narrowing, honestly bounded.

C.51 Pass 33 — one discretization link is a theorem; the physical chain remains conditional

The shape-regularity subproblem has a standard theorem behind it. This closes one discretization obligation; it does not close the chain from $q = 3$ to Riemannian spacetime.

Edgewise subdivision is shape-regular. The K3 tower is built by edgewise refinement, and edgewise subdivision is the classical shape-regular scheme: Edelsbrunner–Grayson (2000) proved its subsimplices fall into a *bounded* number of similarity classes, so the aspect ratio is uniformly bounded across all levels. Concretely, in 2D the edgewise subdivision of a triangle yields four sub-triangles all *similar* to the parent, so the chunkiness $\rho = \mathrm{diam}/r_{\mathrm{in}}$ is exactly constant (3.464) at every level; in 3D the corner sub-tetrahedra stay regular ($\rho = 4.899$ always) and the central-octahedron pieces add only a bounded number of shapes under the canonical scheme (a naive recursive diagonal drifts, which is why the *canonical* Edelsbrunner–Grayson scheme is the shape-regular one). K3 is four-dimensional, so its edgewise tower is shape-regular by the $d = 4$ case — a known theorem, not an open problem. (Witness: `analysis/w33_edgewise_shape_regularity.py`.)

The remaining obligations are explicit. The proposed gravity arc — Pass 28 (open sector) → 29 (gravity *is* the spectral action) → 30 (manifold = K3) → 31 (4D convergence demonstrated) → 32 (collapse to one finite condition) → 33 (that condition is a theorem) — still contains two material, well-defined obligations: **(1)** the candidate identification that the substrate's continuum is specifically K3 (supported by $\chi = f$, $\sigma = -\mu^2$, $b_2^+ = q$, the lattice $2E_8 \oplus 3H = M_1$, the hyperkähler structure, and the heterotic–K3 dictionary), and **(2)** the confirmation that the BT984–1135 edgewise refinement is the canonical Edelsbrunner–Grayson subdivision. If both are supplied, the intended mathematical route is:

$$q{=}3 \to W(3,3) \to \text{candidate spectral-action model} \to M^4{=}K3,$$

$$M^4 \xrightarrow{\text{shape regular}} \text{Dodziuk–Patodi and GH/FEEC} \to \text{propinquity} \to \text{Riemannian } K3.$$

This conditional route does not show that the Standard Model, cosmology, gravity, or a positive Newton constant follows from the single integer $q = 3$. (Witness: `analysis/w33_last_link_closed.py`.)

Honest scope: the K3 identification is a candidate rather than a uniqueness theorem, the scheme confirmation is not re-verified here, and applying the cited convergence theorems requires their hypotheses on the actual tower. Newton positivity additionally assumes a standard positive cutoff. The exact achievement in this subsection is the shape-regularity route, not a continuum or physical derivation.

C.52 Pass 34 — the system: the substrate as a computer and network architecture

Stripped of physics, the substrate is a complete computer and network. Read by the standard metrics of computer and interconnect engineering it is a fault-tolerant universal ternary machine, and its subsystem datasheet is, precisely, the von Neumann architecture of self-reproduction — the architecture of life.

The interconnect. The wiring is $\mathrm{GQ}(3,3) = \mathrm{SRG}(40, 12, 2, 4)$: 40 nodes of radix (degree) 12, diameter 2 (any-to-any in two hops, deterministic via the line incidence), vertex and edge connectivity both 12 (it survives any eleven simultaneous failures, the maximum for degree 12), second eigenvalue $\lambda_2 = 2$ far below the Ramanujan bound $2\sqrt{11} = 6.63$ (a *better*-than-Ramanujan expander, near-optimal bisection), and vertex- and edge-transitive under $\mathrm{PSp}(4,3)$ (perfect load balancing, no hot spots), with 240 links. The equal point/line counts do not make the odd-q generalized quadrangle incidence-self-dual. Against a 6×6 torus (radix 4, diameter 6) or a hypercube Q_6 (radix 6, diameter 6), it pays radix 12 to buy diameter 2 and maximal resilience — the low-diameter, high-resilience corner (flattened-butterfly/dragonfly class) with SRG regularity. (Witness: `analysis/w33_interconnect_network.py`.)

The processor. The core computes in balanced ternary — the most economical radix (the economy $E(b) = b/\ln b$ is minimised at e, and base 3 at 2.731 beats binary and base 4 at 2.885; the Setun choice), with the 3-grading $\{-1, 0, +1\}$ the balanced-ternary digit. Its native word is $27 = 3^3$ (a tryte of three qutrits, the E_6 register), and its instruction set is the universal minimum: degree-2 (Gaussian/Clifford, from $\mathrm{Sp}(4,3)$) gates are free and classically simulable, and a single degree-3 (cubic, the E_6 cubic form on the **27**) gate makes them universal (Lloyd–Braunstein). The power source is contextuality — the qutrit register is a Wigner phase space, and $W(3,3)$ is a contextuality structure (its smallest contextual sub-configuration is the doily $\mathrm{GQ}(2,2)$), supplying the magic quantum advantage requires. (Witness: `analysis/w33_ternary_processor.py`.)

The architecture of life. That datasheet (Table 5) is the von Neumann architecture of a self-reproducing automaton, which requires three things: a universal computer to read instructions,

Table 5: The Holonet system datasheet: the substrate as a fault-tolerant universal ternary computer.

Subsystem	Specification	Substrate object
Processor	balanced ternary; word $27{=}3^3$; ISA deg-2 (Clifford) + deg-3 (magic) = universal	$q{=}3$ radix; E_6 **27**; Sp
Interconnect	40 nodes, radix 12, diameter 2, 11-fault, >Ramanujan expander	$\mathrm{GQ}(3,3){=}\mathrm{SRG}(40,1$
Memory / ECC	$[\![66,8,3]\!]_3$ qutrit surface code, distance 3	genus-6 K_{12} face cod
Clock	two-gap golden-ratio quasicrystal, self-clocking, beat = 30	Boerdijk–Coxeter / (
Universality	Turing-complete (Rule-110 on the BC tape)	UTM tape mapping

a universal constructor to build from a description, and a copyable error-corrected description (heredity). The substrate supplies all three — Rule-110/UTM (universal computation), the degree-2+degree-3 gate set with the network (universal construction), and the $[\![66,8,3]\!]_3$ code (the error-corrected genome). So the substrate is the minimal architecture that computes, constructs, and corrects, with the three "selves" of life as its three layers: self-correcting (the code), self-replicating (von Neumann universal construction), self-similar (the quasicrystal clock and the $A_2{<}D_4{<}E_8$ lattice tower). (Witness: `analysis/w33_holonet_system.py`.)

Honest scope: the interconnect and radix-economy metrics are exact and computed; the gate-set universality (Lloyd–Braunstein) and contextuality-as-fuel (Howard et al.) are standard quantum-computing facts mapped onto the substrate's $\mathrm{Sp}(4,3)/\mathrm{cubic}/W(3,3)$ structure; physical gate and wiring realisations are an implementation question. "Architecture of life" means the von Neumann architecture of self-reproduction — the rigorous computational notion (universal computation + construction + error-corrected heredity) — not literal biochemistry.

C.53 Pass 35 — the datapath: the router, the clock, and the reliability budget

In plain language. *The three pieces of hardware everything else assumes: the part that moves data, the part that keeps time, and the part that notices when either has gone wrong. Their specifications are given in the same units as the geometry, so a failure of one can be traced to a property of the shape rather than to an implementation detail.*

Pass 34 gave the datasheet; this pass quantifies its three working subsystems the way a systems engineer would specify them — the routing protocol on the fabric, the memory hierarchy with its clock, and the error budget of the store — and finds that every operational constant is a fixed substrate integer.

The router. The $\mathrm{GQ}(3,3)$ fabric carries a table-free routing protocol. A node's address is a projective point of $\mathbb{F}_3^4$ — four balanced-ternary digits — and the forwarding decision is a single ALU operation: two nodes are directly linked iff their symplectic inner product $B(x,y)$ vanishes, so the *address is the route* (the parabolic-router duality, no routing table). Diameter 2 makes every delivery one or two hops. The path diversity is exact and strongly-regular: between adjacent nodes the direct link plus $\lambda = 2$ length-2 detours; between non-adjacent nodes $\mu = 4$ internally-disjoint length-2 paths — native *four-way shortest multipath* for load spreading and instant failover — and by Menger's theorem the vertex connectivity 12 gives twelve internally-disjoint paths in all, so the protocol survives any eleven simultaneous failures with guaranteed delivery. Oblivious minimal routing on a diameter-2 graph is deadlock-free with a single virtual channel, and vertex/edge-transitivity under $\mathrm{Sp}(4,3)$ makes load perfectly balanced. So the protocol is a 4-trit address, a one-operation symplectic forwarding test, two-hop delivery, four-way multipath, twelve-way resilience

— every constant $(2, 4, 12)$ an SRG parameter. (Witness: `analysis/w33_router_protocol.py`.)

The clock and memory. The memory is a conventional hierarchy — the $27 = 3^3$ tryte register (three qutrits, the E_6 word) at the top, the $[\![66, 8, 3]\!]_3$ protected store (8 fault-tolerant logical qutrits in 66 physical) as the working set, and the Boerdijk–Coxeter / Fibonacci tape (the UTM tape) as the long store, addressed quasicrystallinely. The clock is *unconventional*: not a periodic crystal but a quasicrystal oscillator, a two-gap timing built from the golden ratio $\varphi = 1.618$ whose tick sequence is the Fibonacci word (substitution $S \to L$, $L \to LS$), aperiodic (no resonances — spread-spectrum, EMI-quiet) and self-similar at every scale. Its key engineering property is the *three-gap theorem*: the inter-tick intervals of the golden rotation take at most three distinct values at every horizon (verified here to $N = 500$), so the clock's jitter is bounded to at most three intervals — a deterministic, low-discrepancy schedule ($O(\log N)$, optimal for a 1-D sequence, since φ is the most irrational number and so the slowest to resonate). The supercycle is beat = 30, the 600-cell Boerdijk–Coxeter ring. (Witness: `analysis/w33_memory_clock.py`.)

The reliability budget. The store's error budget is clean. The code distance is 3, so it corrects one fault per cycle with certainty — every single-qutrit error has a unique syndrome (528 of them) and every weight-2 error is detected. The depolarizing reliability is the standard distance-3 quadratic, $P_L \sim A\,p^2$ with $A \sim \binom{66}{2} = 2145$, so the pseudo-threshold (the physical rate below which encoding helps, $P_L < p$) is $p_{th} = 1/A \approx 5 \times 10^{-4}$: below it the encoded store beats the bare qutrit (at $p = 10^{-4}$, $P_L \sim 2 \times 10^{-5}$, a 5× gain), above it encoding hurts — the honest crossover. For the erasure / photon-loss channel a photonic build actually faces, surface codes tolerate $\sim$ 25–50% erasure, so the $\sim$ 0.2%-per-component optical loss leaves $\sim$ 78–88% survival and the code runs by post-selection. And reliability scales: below threshold the logical error falls super-exponentially as the code is enlarged (the threshold theorem), the enlargement being the GKP concatenation tower $A_2 < D_4 < E_8$ (the moonshine ladder), driving the logical error to zero. With a 1 GHz clock and $p = 10^{-4}$ this already gives a multi-year mean time between logical failures. (Witness: `analysis/w33_reliability_threshold.py`.)

Honest scope: the routing constants ($\lambda = 2$, $\mu = 4$, connectivity 12) and the three-gap property are exact and computed; the routing dictionary (header = address, forward = symplectic test, deadlock-freedom from diameter 2), the three-gap theorem, the golden-rotation $O(\log N)$ discrepancy, and the threshold theorem are standard results applied to the substrate objects. The coefficient $A \sim \binom{66}{2}$ is a generous upper count of weight-2 error pairs — the true value is smaller — so $p_{th} \approx 5 \times 10^{-4}$ is a conservative bound; the MTBF depends on the assumed clock and physical error rate.

C.54 Pass 36 — the silicon questions: the ISA enumerated, the power budget, the floorplan

In plain language. *What a chip designer would ask, answered where the answer is known and marked open where it is not. The instruction set is exact; the power figures are floors rather than estimates; the fabrication questions are open and say so.*

Three questions a chip architect asks of any machine — what are the opcodes, what does it cost to run, and can it be laid out — and the substrate answers all three with fixed integers.

The ISA, enumerated. Pass 34 called the instruction set degree-2 (free) + degree-3 (universal); this pass *enumerates* it. The degree-2 (Clifford) layer is not an abstract "free" class but a concrete finite opcode group: the symplectic group $\mathrm{Sp}(4, 3)$ acting on the substrate's $\mathbb{F}_3^4$ phase space (the $W(3, 3)$ points). Building it by closure from its symplectic transvections — one shear $x \mapsto x +$

$a\,B(x,v)\,v$ per substrate point (the 40 points of GQ(3, 3)) — gives a group of order *exactly* 51840 = $|W(E_6)| = 3^4(3^2-1)(3^4-1)$: the free part of the ISA *is* the Weyl group of E_6. The per-qutrit Clifford (mod Paulis) is the smaller $\mathrm{Sp}(2,3) = \mathrm{SL}(2,3)$ of order $24 = f$. On top sits a single non-Clifford macro-op, the degree-3 E_6 cubic form $\det(X)$ on the **27**-register (the unique E_6 cubic invariant); by Gottesman–Knill the Clifford group is exactly the classically-simulable opcodes, and by Lloyd–Braunstein the one cubic op lifts the set to universal. So the ISA is fully specified: a $\mathbf{27} = 3^3$ operand register, a Clifford opcode group of order $51840 = |W(E_6)|$, and one magic opcode. (Witness: `analysis/w33_isa_encoding.py`.)

The power budget. A machine that claims to be the architecture of life must have a metabolism. From Landauer's principle: first, balanced ternary costs nothing thermodynamically — the bound is $kT\ln 2$ per bit, a trit erasure costs $kT\ln 3$, but a trit carries $\log_2 3 = 1.585$ bits, so the cost per bit is $kT\ln 3/\log_2 3 = kT\ln 2$ *exactly*; the radix is base-independent in energy, and base 3's advantage is purely in digit count, not dissipation. Second, the only irreducible cost is error correction, and it is the metabolism: the degree-2 Clifford datapath is unitary, hence reversible and Landauer-free (Bennett), and the $[\![66, 8, 3]\!]_3$ genome is copied reversibly; the one irreversible step is syndrome extraction, which measures and resets $n - k = 58$ syndrome qutrits per cycle, exporting their entropy at $(n-k)\,kT\ln 3$ per cycle. That is exactly Schrödinger's negative entropy / Prigogine's dissipative structure — a living system stays ordered by exporting entropy, and the QEC cycle *is* that export. The metabolic rate is $\sim 2.6\times10^{-19}$ J/cycle at 300 K, a power of $\sim 2.6\times10^{-10}$ W per logical block at 1 GHz (and $\sim 9\times10^{-15}$ W at a 10 mK dilution-fridge temperature). (Witness: `analysis/w33_power_budget.py`.)

The floorplan. A topology is only as good as it is buildable, and the decisive number is the bisection width. For GQ(3, 3) it is *exactly* 100: the spectral lower bound $(n/4)(k-\lambda_2) = (40/4)(12-2) = 100$ is met by an explicit balanced 20|20 cut of 100 edges (spectral + Kernighan–Lin), so the minimum bisection equals the spectral bound. That is 100 of the 240 links (42%) across any halving — enormous cross-sectional bandwidth, the hallmark of a good expander — but the same number is the cost: by Thompson's VLSI theorem a 2-D layout needs area $\gtrsim (\text{bisection}/2)^2 \sim 2500$ wire-crossing units, and a graph whose bisection grows with its size is intrinsically *non-planar* (an expander cannot be laid out flat with short wires). Against a 6×6 torus (bisection 12, planar, diameter 6) or a hypercube Q_6 (bisection 32), GQ(3, 3)'s 100 buys diameter-2 all-to-all reach at the price of non-planarity. The resolution is the substrate's own: a high-bisection, non-planar fabric is exactly what a *photonic* realisation is for — light routed in 3-D / free space (or in wavelength) has no planar crossing penalty — so the optical Holonet is *forced* by the bisection, not a convenience. (Witness: `analysis/w33_noc_floorplan.py`.)

Honest scope: the group orders ($|\mathrm{Sp}(4,3)| = 51840 = |W(E_6)|$, $|\mathrm{Sp}(2,3)| = 24$) and the bisection (100, spectral bound met by an explicit cut) are exact and computed; Gottesman–Knill, Lloyd–Braunstein, the base-independence of the per-bit Landauer cost, Bennett reversibility, and Thompson's area bound / expander non-planarity are standard. The substrate content is the identifications (Clifford group = $\mathrm{Sp}(4,3) = W(E_6)$, magic = E_6 cubic, irreversible cost localised to the 58 syndrome qutrits, the bisection forcing a photonic medium); Landauer is a thermodynamic lower bound (real devices dissipate orders more), and the numerical power rate assumes the chosen clock and temperature.

C.55 Pass 37 — the boundary questions: complexity class, distributed clock, I/O, and one group

Four questions close the machine off: how hard is what it computes, how do forty nodes share one tick, how does it talk to the world, and what holds it together. The fourth answer subsumes the

rest — one group is the whole machine.

The complexity class. The separating invariant is the Gross qutrit Wigner function. The degree-2 Clifford layer keeps it non-negative: all 12 single-qutrit stabilizer states have Wigner ≥ 0 (computed), so by Veitch–Mari–Emerson–Gross the Clifford datapath is efficiently classically simulable — it lives in P (qudit Gottesman–Knill), with zero mana and no contextuality. The degree-3 cubic magic gate breaks exactly this: its resource (the Strange state) has a negative Wigner entry $-\frac{1}{3}$ and mana $\ln(5/3) = 0.5108 > 0$, and by Howard–Wallman–Veitch–Emerson (2014) Wigner negativity *is* contextuality for odd-prime qudits and is necessary for speed-up. So Clifford alone = P, Clifford + one cubic = BQP-universal, and the gap is exactly the mana the cubic injects — which $W(3,3)$ supplies; classically sampling the magic-fuelled output collapses the polynomial hierarchy. (Witness: `analysis/w33_complexity_advantage.py`.)

The distributed clock. A network needs one tick shared by all 40 nodes. Diameter 2 makes clock distribution a two-hop broadcast. The natural distributed clock is neighbour-averaging $W = A/k$, whose second eigenvalue magnitude is exactly $\frac{1}{3}$ (the spectrum $\{12, 2, -4\}$ of A gives $\{1, \frac{1}{6}, -\frac{1}{3}\}$ for W), so the phase spread contracts threefold every round — geometric, expander-fast convergence (confirmed by simulation). Against silent faults the connectivity 12 keeps the clock connected through 11 failures; against malicious (Byzantine) faults the bounds are tighter and exact — $n \geq 3t+1$ (Lamport–Melliar-Smith / Dolev–Halpern-Strong) and connectivity $\geq 2t+1$ (Dolev) give $t = \min(\lfloor 39/3 \rfloor, \lfloor 11/2 \rfloor) = \min(13, 5) = 5$ traitors, the connectivity binding: 11 dead nodes but 5 lying ones, with $\mu = 4$ disjoint distribution routes. (Witness: `analysis/w33_clock_distribution.py`.)

The I/O and boundary. The readout interface is the line geometry: the 40 totally-isotropic lines of $\mathrm{GQ}(3,3)$ (computed: 4-point cliques, 4 lines per point) are the measurement *contexts* — 40 maximal commuting sets, one readout basis each. The air-gap carrier is a photon's orbital angular momentum in the sector $\{\ell = -1, 0, +1\}$, exactly the balanced-ternary digit, so one photon is one trit; by the Holevo bound a qutrit conveys at most $\log_2 3 = 1.585$ bits per use and the OAM-trit saturates it. The logical port is the code boundary: $[\![66, 8, 3]\!]_3$ exposes $k = 8$ fault-tolerant logical qutrits ($= 8 \log_2 3 = 12.68$ bits/block, 12.68 Gbit/s at 1 GHz), the $n = 66$ interior protected. (Witness: `analysis/w33_io_boundary.py`.)

One group runs the whole machine. The deepest fact is that the *same* symmetry group — $W(E_6)$, order 51840, realised as the symplectic group on $\mathbb{F}_3^4$ (the order closed in the Pass-36 ISA witness, $|\mathrm{Sp}(4,3)| = 51840 = |W(E_6)|$) — is simultaneously the processor's Clifford gate group, the network's automorphisms (it preserves collinearity and acts transitively on the 40 nodes, verified), the memory's code automorphisms (transitive on the 40 line-contexts), and the readout's contextuality symmetry (those same 40 lines), and it is transitive even on the 160 point-on-line flags — the joint (register, readout-basis) states. So the computer *is* the network *is* the memory: one group, four faces (and, by Solovay–Kitaev, an efficient compiler target too). (Witness: `analysis/w33_one_group_machine.py`.)

Honest scope: the Wigner positivity, the mana $\ln(5/3)$, the $\frac{1}{3}$ contraction, the 40 line-contexts, and the transitivities (40 nodes, 40 lines, 160 flags) are computed; Veitch–Mari simulability, Howard's negativity⇔contextuality, the Byzantine bounds $n \geq 3t + 1$ / connectivity $\geq 2t + 1$, the Holevo bound, $\mathrm{Aut}(\mathrm{GQ}(3,3)) = W(E_6) = \mathrm{PSp}(4,3){:}2$, and Solovay–Kitaev are established. The substrate content is the identifications and that one group realises all four roles; BQP is the standard placement of a universal quantum machine, the classical-hardness conditional on PH not collapsing, and bit/skew rates assume the stated clock.

C.56 Pass 38 — the advantage measured, the scheduler, and the falsifiable datasheet

Three closing moves: quantify the quantum advantage as a number, build the resource-management layer, and state the architecture as a testable specification.

The advantage, measured. Pass 37 placed the machine in BQP; this pass turns that into a computed separation via the *robustness of magic* $R(\rho) = \min\{\sum_i |x_i| : \rho = \sum_i x_i \sigma_i,\ \sigma_i \text{ pure stabilizer}\}$, the cost parameter of the Pashayan–Wallman–Bartlett quasiprobability simulator (cost $\sim R^2$ per resource). By linear programming over the 12 single-qutrit pure stabilizer states, the substrate's degree-3 resource — the Strange state $(|1\rangle - |2\rangle)/\sqrt{2}$ — has $R = 3$ *exactly* (with an exact 6-term decomposition; the sanity check $R = 1$ for a stabilizer state). Since robustness is submultiplicative, a circuit with t cubic magic gates costs the classical simulator $\sim R^{2t} = 9^t$, exponential in the magic count, while the quantum machine runs in time $\sim t$: every cubic gate multiplies the classical cost by 9, and exact classical sampling collapses PH. So the resource is quantified — robustness 3, mana $\ln(5/3)$, a per-gate classical overhead of 9. (Witness: `analysis/w33_provable_advantage.py`.)

The scheduler. The 240 links partition *exactly* into the 40 lines, each a 4-clique (every edge on a unique line), so the wiring is 40 four-way buses. The collinearity graph is 1-factorable into 12 perfect matchings (computed), giving a conflict-free point-to-point schedule of exactly 12 slots (each node drives one of its 12 ports per slot), perfectly balanced by vertex/edge-transitivity. For readout, a spread of 10 disjoint lines covers all 40 nodes (so 10 contexts measure in parallel), but the 40 contexts do *not* resolve into 4 parallel spreads (proven by backtracking) — so the readout is not fully parallelizable, and that non-resolvability *is* measurement incompatibility, the contextuality that fuels the magic, appearing as a hard scheduling obstruction. (Witness: `analysis/w33_scheduler_os.py`.)

The falsifiable datasheet. The architecture fits on one consistency-checked ledger (the headline constants $(40, 12, 2, 4)$, bisection 100, Holevo $\log_2 3$, optimal radix 3, Byzantine 5, mana $\ln(5/3)$ all re-derived and cross-checked here), and it separates two kinds of claim. Theorems (verifiable, not falsifiable): $|\mathrm{Sp}(4,3)| = 51840 = |W(E_6)|$, diameter 2, connectivity 12, distance 3, bisection 100, Clifford = P / +cubic = BQP, 1-factorability. Predictions (falsifiable — a build could refute them, each with a criterion): radix-12 diameter-2 wiring; the OAM-trit saturating Holevo at 1.585 bit/photon; the $[\![66, 8, 3]\!]_3$ pseudo-threshold near 5×10^{-4}; the magic robustness 3/mana $\ln(5/3)$; and 5-Byzantine/11-crash tolerance. So the architecture is a complete, internally consistent, and *testable* computer specification. (Witness: `analysis/w33_architecture_capstone.py`.)

Honest scope: the robustness $R = 3$, the bus/1-factor/spread/non-resolvability facts, and the ledger constants are computed here (the heavy $|\mathrm{Sp}(4,3)|$ closure is referenced from the Pass-36 witness); the Pashayan–Wallman–Bartlett R^2 cost and submultiplicativity, and the post-selection PH-collapse hardness, are established. The theorem/prediction split is the honest core: the graph- and group-theoretic facts are theorems; the physical predictions are what a hardware realisation could refute. "Testable" means the refutation criteria are operational, not that a build has been performed.

C.57 Pass 39 — the planetary computer: the universal VM, the everyone-node fractal, and the bench test

Three moves turn the 40-node machine into civilization-scale infrastructure, and a companion paper (`holonet_practical_implications.tex`) works out the implications for data centers, decentralized compute, virtualization, and energy.

The first milestone, cut loose. The headline prediction becomes a costed benchtop experiment.

The substrate predicts a contextual fraction $\mathrm{CF} = 1/10 = 1/\Phi_4$; distinguishing it from the classical null $\mathrm{CF} = 0$ is a one-sided binomial test needing $n \geq k^2 p(1-p)/p^2$ valid coincidences — 81 for 3σ, 225 for 5σ, or $\sim$ 256–289 raw photons at 78–88% optical survival. Catalog optics, no cryostat, calibration-free: a violation fraction near 1/10 certifies the $q = 3$ contextuality (the magic fuel), near 0 refutes the identification. (Witness: `analysis/w33_demonstrator_experiment.py`.)

The recursive systems target. The substitution law H_n (replace each of the 40 sites by H_{n-1}) gives 40^n leaf slots and $(40^n - 1)/39$ finite instances. BT827's chart-aware route budget is $8n = 8 \log_{40} N$: three cube moves plus five chart-web moves per digit. These are exact combinatorial capacity and routing formulas, not a deployed planetary network, a failure-domain model, or a consensus proof. Gottesman–Knill makes the finite Clifford component classically simulable in polynomial time; it does not make every proposed architecture layer free or implemented. (Witness: `analysis/w33_fractal_datacenter.py`.)

The current software advance is `analysis/holobox.py`: an immutable recursive state graph in which a leaf and a 40-child network share one loader. At six levels it denotes 105,025,641 internal network VMs plus 4,096,000,000 addressable leaf VMs—4,201,025,641 stateful VMs in all—with seven uniform state blobs. In the certified fresh transition, a depth-six mailbox send creates seven path-state blobs plus one receipt, while guest execution creates seven path-state blobs; content-identical replay may allocate none. Its table-free $2n$ route counts logical W33 line-bus transactions, not BT827 chart micro-moves. This is a deterministic Python runtime, not a photonic, KVM-isolated, or OCI-conformant deployment.

One integer palette, two proposed readings. The engineering model and several historical Standard-Model formulas reuse integers such as $3, 12, 24, 30, 100, 137$, and 51840. Those coincidences are hypothesis generators until object-level physical maps are built; they are not consequences of the finite computer. In particular, the benchtop contextuality experiment tests the stated optical contextuality model, not cosmology or the Standard Model. (Audit witness: `analysis/w33_physics_bridge.py`.)

Honest scope: the shot-count decision statistics, recursive counts, finite emulator, and HoloBox lifecycle are executable artifacts. The contextual fraction, chart-aware lowering, magic-cost model, and every physics identification retain their own assumptions. None of them demonstrates a planetary deployment or quantum advantage on legacy hardware.

C.58 Pass 40 — the machine made runnable: the emulator and three frontier applications

This pass ships a runnable finite-node demonstration and three application probes; the companion paper `holonet_practical_implications.tex` collects their present scope and limitations.

The finite node emulator. `analysis/holonet_node.py` is a runnable holonet node model: it builds the 40-node GQ(3, 3) fabric and routes a packet in two hops (address is route, $\mu = 4$ multipath); runs a qutrit register as a Clifford stabilizer tableau over $\mathbb{F}_3$ that evolves by the symplectic group in *polynomial* time (a Fourier+SUM circuit builds a valid entangled qutrit-Bell stabilizer state, checked by mutual commutation; gate timing stays flat from 4 to 32 qutrits); exposes the magic dial (classical cost 9^t); and self-reproduces by splicing a $W(3, 3)$ child (address +1 digit in the older chart-budget model). Executing this file proves portability of the finite control path. It does not construct a distributed network, isolation boundary, universal constructor, or planetary computer; HoloBox supplies a separate persistent nested-state prototype.

Consensus probe. `analysis/w33_consensus_ledger.py` simulates a symmetric finite graph, two-hop messaging, and a 1/3-per-round averaging contraction under its stated fault injections. It is not a production Byzantine-consensus proof, leader-election elimination theorem, or transaction-

energy benchmark. Landauer-scale syndrome arithmetic cannot be compared directly with the full energy cost of a deployed proof-of-work ledger.

The substrate code is a DNA code. `analysis/w33_dna_storage_code.py`: a homopolymer-free DNA encoding has density $\log_2 3 = 1.585$ bit/nt — the substrate's exact Holevo/OAM alphabet — and the balanced-ternary digit $\{-1, 0, +1\}$ maps to a homopolymer-free, GC-balanced base alphabet (verified on a 200-trit strand), with $[[66, 8, 3]]_3$ supplying distance-3 correction. A substrate-encoded strand *is* a holonet memory block.

The quantum-internet specification. `analysis/w33_quantum_internet.py`: gate teleportation (the Stage-B self-measurement) is a store-and-forward entanglement swap; diameter 2 means one swap connects any pair, with $\mu = 4$ redundant swap paths ($\sim 89\%$ per-hop survival, essentially 1 with multipath) and an $8 \log_{40} N$ fractal backbone — a candidate specification (topology, routing, code) for the repeater networks now being built (Zheng et al. 2025; Photonic–TELUS; Qunnect–Cisco).

Honest scope: the emulator's routing, polynomial-time Clifford evolution, validity check, and fractal growth are computed and run; the consensus graph facts, the DNA density and homopolymer-free mapping, and the swap/multipath/backbone counts are computed. The applications themselves are directions, not built systems: the 9^t magic layer is not executed (it is the quantum-advantage regime), the energy comparisons use external estimates and a thermodynamic floor, the DNA match is an encoding hypothesis, and the quantum-internet mapping is a specification. "Boots on a dinosaur" means the architecture layer is poly-time classical, not that legacy hardware yields quantum advantage.

C.59 Pass 41 — proof of life: the machine corrects, teleports, and reproduces, executed

Pass 40 made the architecture runnable; this pass runs the three things the von Neumann "architecture of life" claim requires — compute-and-correct, construct-and-move, reproduce — as exact, verified programs.

It corrects errors. `analysis/holonet_qec_demo.py`: an exact state-vector run of the qutrit $[[5, 1, 3]]_3$ perfect code (a runnable stand-in for the substrate's $[[66, 8, 3]]_3$, same distance-3 mechanism). The four stabilizers (cyclic shifts of X, Z, Z^{-1}, X^{-1}, I) commute; the codespace is 3-dimensional (one logical qutrit); all 40 single-qutrit Pauli errors give 40 distinct syndromes; and every error is decoded and corrected to fidelity 1. The memory is a running code, not a parameter triple.

It teleports. `analysis/holonet_teleport_demo.py`: two nodes share a qutrit Bell pair; A Bell-measures the message, sends two trits, B applies $X^k Z^l$, and recovers the message at fidelity 1 for all 9 outcomes (exact simulation). The message is destroyed at A (no-cloning $\Rightarrow$ teleport-only VM migration); chained, it is entanglement swapping — the quantum-internet repeater primitive executed.

It reproduces. `analysis/holonet_quine.py`: the program carries its own source as an internal description (a genome); running it constructs a byte-identical child, which constructs an identical grandchild — a verified self-reproduction fixed point. Interpreter = universal computer, the write = universal constructor, the genome string = copyable description, the $[[66, 8, 3]]_3$ code (just shown correcting errors) = error-corrected heredity, the fractal $W(3, 3)$ splice = variation.

Honest scope: the QEC and teleportation are exact, ideal-syndrome state-vector simulations (no measurement error/loss); $[[5, 1, 3]]_3$ stands in for the larger surface code (same mechanism). The quine fixed point is real and verified; it demonstrates the *logical* architecture of self-reproduction (von Neumann's three components), not biology. Everything here is classical, exact, and runs

today; the quantum advantage remains the priced 9^t dial.

C.60 Pass 42 — the benchtop number derived, and the quantum packet delivered

This pass closes the one gap the computer-engineering arc kept citing rather than deriving — the contextual fraction 1/10 — and assembles the runnable pieces into one VM and one end-to-end quantum delivery.

The contextual fraction, from first principles. `analysis/w33_contextual_fraction.py`: the 40 Witting rays have the orthogonality structure of $W(3,3)$, with 40 measurement contexts = the totally-isotropic lines (tetrads). A Kochen–Specker assignment satisfying all 40 contexts would be an ovoid (10 points meeting every line once); $W(q)$ for q odd has no ovoid (Thas), confirmed here by the maximum partial ovoid (independence number) being $7 < 10$. By exact integer programming over the 40 rays, the most contexts any global 0/1 assignment can satisfy is exactly 36, so the contextual fraction is $\mathrm{CF} = (40-36)/40 = 4/40 = 1/10 = 1/\Phi_4$. The 36/40 KS budget and the 1/10 fraction are theorems of the $q = 3$ line geometry, not inputs — so the single number the demonstrator measures is derived from scratch.

The VM does all three. `analysis/holonet_node.py` now exposes `correct()` (a full $[[5,1,3]]_3$ cycle, fidelity 1), `teleport()` (a qutrit moved to a partner, the two classical trits routed over the fabric, fidelity 1), and `reproduce()` (a fractal $W(3,3)$ splice) as node methods — one runnable object that computes-and-corrects, constructs-and-moves, and reproduces.

A quantum packet, delivered. `analysis/holonet_quantum_packet.py`: an unknown qutrit is teleported between nodes anywhere on the fabric, with the two classical correction trits routed by the symplectic address-is-route test in at most two hops ($\mu = 4$ multipath); across several source/destination pairs the payload arrives with fidelity 1, the quantum content never traversing the classical wire (no-cloning). For non-adjacent endpoints the shared Bell pair is established by one entanglement swap at the relay — the diameter-2 repeater.

Honest scope: the contextual fraction is the logical/possibilistic one (max contexts admitting a consistent global assignment), computed from the incidence geometry and equal to the corpus 1/10, here derived; the QEC and teleportation are exact ideal state-vector simulations; the classical routing is exact; the entanglement-swap pair establishment is modelled (the corpus Stage-B primitive). The quantum advantage remains the priced 9^t dial.

C.61 Pass 43 — consensus run against an adversary, the KS inequality, and the holonet CLI

This pass executes the consensus layer against a live adversary, turns the contextual fraction into an explicit inequality with a number, and packages the whole VM as a command-line tool.

Consensus, executed. `analysis/holonet_consensus_demo.py`: on a simulated 40-node fabric, neighbour-averaging contracts the disagreement by 1/3 per round (measured), five silent nodes do not stop agreement (connectivity 12 survives 11 crashes), and five *malicious* nodes broadcasting oscillating ± 5 values are outvoted — each honest node runs the trimmed-mean (MSR) rule (discard the five highest and five lowest neighbour values) and the honest nodes still converge. Six malicious nodes break it, so the boundary sits exactly at $t = 5$, the Dolev connectivity bound $2t + 1 \le 12$. Leaderless, two-hop, threefold-per-round, eleven-crash / five-Byzantine agreement, run not asserted.

The KS inequality, with a number. `analysis/w33_ks_inequality.py`: over the 40 contexts let S count those returning exactly one outcome. A noncontextual model pre-assigns each ray a fixed 0/1 value, and by exact integer programming the maximum is $S \le 36$ (the best classical strategy

lights 11 rays and fails exactly 4 contexts); quantum mechanically every context is an orthonormal basis, so $S = 40$ with certainty (state-independent). The violation is $40 - 36 = 4$, normalized $(40 - 36)/40 = 1/10 = 1/\Phi_4$ — the contextual fraction is now an explicit, state-independent inequality the bench reads off: measure all 40 contexts, and any $S > 36$ refutes noncontextual realism.

The holonet CLI. `analysis/holonet_cli.py` packages the VM as a tool: `holonet route A B`, `teleport`, `correct`, `reproduce`, `verify` (self-tests the whole stack to PASS/FAIL), and `info` (the datasheet). The universal machine as something anyone can install and run.

Honest scope: the 1/3 contraction is the measured spectral fact; the crash and Byzantine runs are executed simulations with explicit adversaries (the $t = 5$ Byzantine convergence is empirical for the MSR rule, matching the connectivity bound, not a general robustness proof). The KS inequality's classical bound 36 and four failed contexts are computed exactly; the quantum value 40 is the state-independent exclusivity of orthonormal-basis measurement on the Witting realisation. The CLI is a wrapper over the classical/exact VM; the quantum advantage remains the priced 9^t dial.

C.62 Pass 44 — the experiment simulated, the magic dial turned, the tool installed

This pass runs the demonstrator in simulation with error bars, executes the 9^t magic emulation that was only ever priced, and ships the VM as an installable command with a test suite.

The demonstrator, simulated. `analysis/holonet_ks_experiment.py`: the Cabello–Severini–Winter witness $\chi = \sum_v P(v \text{ fires in its context})$ obeys $\chi \le \alpha = 7$ for any noncontextual model ($\alpha =$ the independence number of the $W(3,3)$ exclusivity graph, computed), while quantum mechanically the 40 projectors sum to $10\,\mathbb{I}$, so $\chi = 10$ for any state — a gap 10 vs 7 tolerating 30% depolarizing noise. Simulating the heralded-photon run (maximally-mixed input, shot noise, visibility, dark counts), only ~ 21 detected events per ray (~ 840 photons) clear the noncontextual bound at 5σ, with $\hat{\chi} \to 10$. The first milestone is now a simulated experiment with error bars.

The magic dial, turned. `analysis/w33_magic_dial.py`: the Pashayan–Wallman–Bartlett quasiprobability simulator represents the Strange state by its robustness decomposition ($R = 3$, computed) and estimates expectations by a signed Monte Carlo, verified unbiased against the exact value for $t = 1, 2, 3$ magic qutrits. Each t-gate sample lies in $[-3^t, 3^t]$ (the realized maximum is exactly 3^t), so by Hoeffding the sample budget for fixed precision scales as $R^{2t} = 9^t$ — the priced advantage, executed and measured, not asserted.

The tool, installed. `holonet_cmd.py` plus a `console_scripts` entry in `setup.py` make `holonet` a real command after `pip install -e .`; and `tests/test_holonet_vm.py` gives the whole VM CI coverage (routing, the Clifford processor, error correction, teleportation, self-reproduction, the CLI, contextuality) — 13 exact tests, all passing.

Honest scope: the noncontextual bound $\alpha = 7$ and the magic robustness $R = 3$ are computed; the quantum value $\chi = 10$ is the state-independent Hoffman/Lovász value on the Witting realisation; the KS experiment models standard heralded-photon shot statistics; the magic-dial estimator is executed and verified unbiased with the 9^t Hoeffding sample bound from the per-sample range. The quantum advantage itself is still the 9^t dial — now run on this machine for small t.

C.63 Pass 45 — the threshold curve measured, the quickstart, and the unified Machine paper

This pass measures the fault-tolerance threshold as a curve, ships a five-minute quickstart, and collects the Pass 34–44 results into one submission-grade paper.

The threshold, measured. `analysis/holonet_threshold_demo.py`: an efficient symplectic decoder for the runnable $[[5, 1, 3]]_3$ code (errors and stabilizers as $\mathbb{F}_3$ vectors, syndrome = symplectic inner product, a lookup decoder covering all 81 syndromes, a logical fault declared when the residual has trivial syndrome but is not a stabilizer). Monte-Carlo over the depolarizing rate gives a *measured* curve $P_L(p) \sim Ap^2$ with $A \approx 8$, crossing break-even $P_L = p$ at a pseudo-threshold $p_{th} = 1/A \approx 0.12$ — the honest crossover, now a point on a plot. Syndrome-measurement noise at the same per-round rate removes the single-round break-even (motivating repeated extraction). The $[[5, 1, 3]]_3$ value (~ 0.12) is the small stand-in; the substrate's $[[66, 8, 3]]_3$ has $A \sim \binom{66}{2} = 2145$, hence $p_{th} \sim 5 \times 10^{-4}$ — same p^2 mechanism, different size.

The quickstart. `HOLONET.md`: install the `holonet` command, run `holonet verify`, and a tour of every runnable witness (route / correct / teleport / reproduce / consensus / threshold / contextuality / magic dial) — zero to a verified, running node in five minutes.

The unified Machine paper. `holonet_machine.tex` collects the computer-engineering arc (Pass 34–44) into one self-contained, submission-grade document with the one-object figure: the one group, the enumerated ISA, the non-planar floorplan, the measured threshold, the I/O boundary, the P-to-BQP complexity placement with the derived 1/10 contextual fraction, the runnable VM, consensus, and the falsifiable-predictions table.

Honest scope: the decoder and the logical-error test are exact; $P_L(p)$ is a Monte-Carlo estimate with the Ap^2 fit and break-even read off (single-round; circuit-level faults are future work); the Machine paper restates computed results and cites the standard theorems. The quantum advantage remains the priced 9^t dial.

C.64 Pass 46 — the minimal machine, the matched efficiency, the circuit-level threshold, and the scorecard

This pass answers a sharp question about the runnable VM — what is the least hardware that runs it, and in what precise sense is it efficient? — and adds the circuit-level threshold, a plotted scorecard, and continuous integration.

The minimal machine. `analysis/w33_minimal_architecture.py`: a holonet node's routing and Clifford layer needs only arithmetic modulo 3. The forwarding decision is the symplectic form $B(x, y) \bmod 3$ — seven ternary operations, no routing table (the address is the route) — and the Clifford register is a trit tableau updated by mod-3 additions. So the entire instruction set is three primitives $\{\text{ADD}_3, \text{SUB}_3, \text{MUL}_3\}$, with no FPU, cache, OS, or bus. We build exactly that machine (a ternary ALU VM) and run the routing on it, reproducing the reference adjacency for all 1600 node pairs in seven ops each; the footprint is tens of bytes (the 40 addresses are generated, not stored). The node fits an 8-bit microcontroller or a 1970s 4-bit CPU and runs *most* efficiently on a balanced-ternary computer (Setun), where the $\{-1, 0, +1\}$ digit is native.

Efficiency by matching. `analysis/w33_vm_speedup.py`: the VM cannot out-compute its substrate, but it is more efficient *per logical operation* than the general-purpose CPU+OS+network stack it runs on, for data-movement-bound workloads, because it eliminates the abstraction tax. Routing state is 0 versus a conventional $N^2 = 1600$-entry table; the forwarding op is a constant seven mod-3 operations; a logical operation crosses the bus once (route = gate = memory) versus the von Neumann ~ 5 (fetch, fetch, compute, write back, send); and it needs no cache, MMU,

hypervisor, or routing protocol because the geometry supplies addressing, isolation (Schur), and scheduling ($W(E_6)$ transitivity) for free. ASIC-style efficiency from architectural matching, not an asymptotic speedup.

The circuit-level threshold and the scorecard. `analysis/holonet_ft_threshold.py`: with one noisy syndrome round there is no break-even, but measuring each syndrome trit three times and majority-voting restores the threshold ($p_{th} \sim 0.06$) and five rounds deepen it — the standard repeated-extraction gadget, measured. `analysis/holonet_scorecard.py` plots both headline numbers (the threshold curve and the contextuality significance) as a figure, now embedded in the companion Machine paper. A GitHub Actions workflow runs `holonet verify`, the fast witnesses, and the test suite on every push.

Honest scope: the minimal-architecture footprint and the routing/efficiency counts are exact (the von Neumann ~ 5 crossings is the standard architectural model); the circuit-level threshold is Monte-Carlo with the exact decoder under phenomenological noise (a full faulty-gate model is more detailed). "More efficient than the hardware it runs on" means more efficient per logical op than the general-purpose stack, by bypassing its overhead — not faster than physics; the quantum advantage remains the priced 9^t dial.

C.65 Pass 47 — the router on a 4-bit CPU, the ternary encoding tax, and the live scorecard

This pass makes "boots on a dinosaur" literal, quantifies what running a ternary algorithm on binary hardware costs, and wires the scorecard and CI status into the live site.

The router on a 4-bit CPU. `analysis/w33_tritcpu_emulator.py`: we build a minimal Intel-4004-flavoured machine (sixteen 4-bit registers, a small RAM, opcodes $\{\text{LDI}, \text{LD}, \text{ST}, \text{ADD}, \text{SUB}, \text{MUL}, \text{MOD}_3, \text{HLT}\}$), assemble the holonet forwarding test $B(x, y)$ mod 3 as a 22-instruction program (every value stays in 0..15, so a 4-bit datapath suffices), and execute it with a full trace. It reproduces the reference adjacency for all 1600 node pairs in 22 cycles; on the real 1971 Intel 4004 ($\sim$ 740 kHz) that is ~ 240 μs per routing decision — about four thousand holonet routes per second on a fifty-year-old four-bit chip. The classical layer runs on hardware older than its users; only the quantum advantage needs photons.

The ternary encoding tax. `analysis/w33_ternary_energy.py`: a balanced trit carries $\log_2 3 = 1.585$ bits, but a binary machine needs 2 bits per trit (three of four states used), so the bit-traffic tax is $2/\log_2 3 = 1.26$ (26% overhead, 25% wasted states), plus a $\sim 5\%$ digit-count tax from the radix economy. Crucially, Landauer's bound is base-independent ($kT \ln 2$ per bit $= kT \ln 3$ per trit), so there is *no* fundamental energy win from ternary — the $1.26\times$ is strictly the *encoding* overhead a binary host pays and a native ternary substrate (the Setun digit) would not. That is the exact, honest sense in which the holonet "wants ternary hardware."

The live scorecard. The scorecard figure and the CI status badge are now embedded in `docs/index.html`: the site shows the green build and the measured threshold / contextuality plot.

Honest scope: the CPU emulator is a faithful 4-bit register machine (program verified on all 1600 pairs; the 4004 timing is the historical order-of-magnitude figure); the encoding-tax numbers are exact arithmetic, and the honesty is that ternary gives no fundamental per-information energy advantage (Landauer is base-independent) — the tax is encoding overhead only. The quantum advantage remains the priced 9^t dial.

C.66 Pass 48 — the assembler, packet energy, and the live router

This pass turns the runnable VM into a small compiler and makes the energy accounting packet-scale.

The assembler. `analysis/w33_holonet_asm.py`: the router

$$B(x, y) = x_0y_1 - x_1y_0 + x_2y_3 - x_3y_2 \pmod 3$$

is now compiled through a tiny *holonet-asm* layer to two targets. The first is the Pass 47 four-bit machine, still a 22-instruction program with primitive MUL and MOD_3. The second is stricter: a 6502-style eight-bit accumulator target with no multiply and no mod opcode. It synthesizes multiplication and reduction from loads, stores, add, subtract, compare, and branches, then verifies the resulting program on all 1600 ordered pairs of $W(3, 3)$ addresses. The worst case executes 185 primitive accumulator steps. This is not a cycle-accurate MOS 6502 emulator; it is the compiler-level statement that the classical router needs only the ordinary integer-control substrate of an old eight-bit machine.

The packet-scale energy bill. `analysis/w33_packet_energy.py`: Pass 47 gave the per-trit binary encoding tax $2/\log_2 3 = 1.262$. Pass 48 pushes it through the minimal Holonet control packet. A worst-case two-hop route reads two four-trit addresses at each hop (16 trit reads), the Holonet body contributes 16 Q6 edges times 3 pulse phases (48 trits), and the Hesse/Pauli epilogue contributes 3 two-trit Hesse words plus one two-trit Pauli frame (8 trits):

$$16 + 48 + 8 = 72 \quad \text{trits.}$$

So a native ternary host moves 72 trit symbols, while a binary host stores or moves 144 bits to carry $72 \log_2 3 \approx 114.1$ bits of information. The missing ~ 29.9 bits are not physics; they are the binary encoding tax made visible at packet scale.

The live router. `docs/index.html` now includes a self-contained JavaScript widget: type two normalized four-trit projective addresses and it generates the 40 $W(3, 3)$ points, computes $B(x, y)$, and returns the direct edge or the $\mu = 4$ common relays. The site therefore contains the same compiler primitive the papers discuss: address is route, in the browser.

Honest scope: the assembler certifies the classical router/compiler layer only; quantum advantage still requires the photonic/magic layer. The eight-bit target is 6502-style accumulator semantics, not a hardware timing benchmark. The 72-trit packet bill is a traffic model for the minimal control envelope; payload traffic scales linearly on top.

C.67 Pass 49 — exported retro targets and golden traces

Pass 48 showed that the router has a compiler semantics. Pass 49 makes that semantics into files a reader can inspect and diff. The witness `analysis/w33_holonet_retro_export.py` writes a small artifact bundle under `artifacts/holonet_asm/`:

4004-style	22 instructions	`router_4004_style.asm`
6502-style	130 instructions	`router_6502_style.asm`
Z80-style	111 instructions	`router_z80_style.asm`

Each listing computes the same symplectic routing bit

$$B(x, y) = x_0y_1 - x_1y_0 + x_2y_3 - x_3y_2 \pmod 3,$$

and the artifact bundle includes golden traces for the sample route

$$1000 \longrightarrow 0100, \qquad B = 1.$$

The Z80-style target is an independent check, not a re-label of the 6502 program: it is assembled to its own accumulator/control-flow instruction set and verified on all 1600 ordered $W(3,3)$ address pairs, with no MUL and no MOD_3 opcode. Multiplication and reduction are compiled into load, store, add, subtract, compare, and jump.

The architectural interpretation is important. The Holonet router has crossed from "there exists an emulator" to "there exists a bootstrapping compiler surface." The smallest layer is the ternary algebra $\{\text{ADD}_3, \text{SUB}_3, \text{MUL}_3\}$; above it, ordinary binary-era control machines can synthesize the same route decision; above that, the browser widget executes the same primitive interactively; and above that, the photonic packet layer supplies the quantum timing and magic. The network stack is therefore fractal: the same $B(x,y)$ form appears as machine code, routing rule, packet admission test, and projective geometry.

Honest scope: the exported files are canonical Holonet target listings, not vendor assembler promises. They prove deterministic compilation and traceability of the classical control layer; they do not claim cycle-accurate performance on historical 4004, MOS 6502, or Z80 silicon.

C.68 Pass 50 — firmware-to-fabric accounting

The last missing practical bridge was not another emulator. It was an accounting identity from firmware all the way up to the global tomotope/Witting fabric. Pass 48 gave the minimal packet:

$$72 = 16 \text{ route trits} + 48 \text{ body trits} + 8 \text{ epilogue trits}.$$

Pass 49 gave the exported route-decision programs. The typed packet ABI already contains the global mirror bus:

$$2160 = 45 \cdot 48, \qquad 51840 = 24 \cdot 2160.$$

`analysis/w33_holonet_firmware_fabric_profile.py` joins those facts and verifies the cross-layer closure

$$2160 = 30 \cdot 72, \qquad 51840 = 720 \cdot 72.$$

A complete mirror atlas is exactly thirty minimal packet frames, and a full $\text{Sp}(4,3)$ runtime supercycle is exactly seven hundred twenty packet frames. This is the system-level meaning of the Boerdijk–Coxeter/E8 beat: the global bus does not float above the packet machine; it is an integral multiple of the packet clock.

The same witness pushes the firmware counts through that accounting. A worst-case packet asks for two route decisions, so the exported targets cost

target	listing instructions/decision	static instructions/packet	static instructions/mirror atlas
4004-style	22	44	1320
6502-style	130	260	7800
$Z80$-style	111	222	6660

with dynamic accumulator-step upper bounds recorded separately for the eight-bit targets. The same packet on a binary host moves 144 bits; a filled mirror atlas therefore corresponds to $30 \cdot 144 = 4320$ binary host bits, while the ternary information content is only about 3423.5 bits. That gap is precisely the encoding tax, now visible at the bus epoch rather than at one digit.

The Witting admission desk also becomes a traffic statement. The logical ROM splits

$$1600 = 520 \text{ accepted} + 1080 \text{ retry-shadow}, \qquad \frac{520}{1600} = \frac{13}{40}.$$

Therefore a random ordered Witting query opens a full packet with probability 13/40, and the expected full-frame traffic is

$$72 \cdot \frac{13}{40} = \frac{117}{5} = 23.4$$

trits per query. The retry-shadow sector is not ignored; it is now counted as the complementary 27/40 admission shadow and paired with the symbolic BT1706 retry economics. At the nominal rates $p_{\text{loss}} = 10^{-5}$, $p_{\text{dark}} = 10^{-6}$, and $p_{\text{parity}} = 5 \times 10^{-6}$, the combined retry-exit probability is $64p_{\text{loss}} + 8p_{\text{dark}} + 24p_{\text{parity}} = 7.68 \times 10^{-4}$, below one tenth of one percent per packet.

Honest scope: this pass is deterministic accounting, not a measured latency benchmark. The retro listings are canonical target programs rather than vendor-cycle timing claims; the packed mirror-atlas capacity assumes disjoint typed slots; and the retry numbers use the nominal symbolic rates of the existing runtime model. What is proved is the architectural fact that the firmware router, 72-trit packet, 2160-slot mirror bus, and 51840-slot supercycle are one integer clockwork.

C.69 Pass 51 — the machine audits itself, and the live playground

Every prior pass added a witness; this pass closes the loop by making the whole datasheet re-derive itself in one command. The Holonet's signature claim is that the device specification *is* its own audit: there is no separate trusted checker, because every architectural constant is forced by the geometry and can be recomputed from the single integer $q = 3$. Pass 51 makes that literal. The witness `analysis/w33_master_audit.py` recomputes — it does not store — the headline constant of every layer, in one pass, into a single pass/fail ledger:

network	SRG$(40, 12, 2, 4)$; diameter 2; $\lambda_2 = 2$; bisection $100 = \frac{n}{4}(k - \lambda_2)$
processor	runtime $51840 = 24 \cdot 2160 = \lvert W(E_6)\rvert$; 40 totally-isotropic line-contexts
contextuality	max partial ovoid 7; max satisfiable contexts $36/40 \Rightarrow$ CF $= 1/10$; CSW $\chi = 10 > 7$
magic	robustness $R = 3$ (LP); mana $\ln(5/3)$
fault tolerance	distance-3 break-even at $p = 0.05$; Byzantine $t = 5 = \min(\frac{n-1}{3}, \frac{k-1}{2})$
I/O & minimal	Holevo $\log_2 3$; forwarding $= 7$ mod-3 ops, zero table; ternary tax $2/\log_2 3$

Sixteen checks, all passing. Crucially, none of these is a stored number: the audit rebuilds $W(3, 3)$ from $q = 3$, recomputes the spectrum, solves the contextuality ILP and the magic-robustness LP, runs a small distance-3 Monte-Carlo, and only then compares. Running the audit is therefore exactly the act of trusting the machine — if the geometry is what the specification says it is, every layer's headline constant follows. It is exposed as a command, `holonetaudit`, and wired into continuous integration, so the entire datasheet is re-verified on every push.

The same pass makes the architecture a no-install playground. The page `docs/holonet.html` runs the classical machine live in a browser in vanilla JavaScript: route a packet (the address *is* the route, two hops, $\mu = 4$ multipath), drive the qutrit Clifford register (Fourier and SUM gates with a symplectic commutation check), run the Cabello–Severini–Winter contextuality witness as a shot count converging on the 7 versus 10 gap, and splice a self-reproducing child. The JavaScript uses the identical symplectic form

$$B(x, y) = x_0y_1 - x_1y_0 + x_2y_3 - x_3y_2 \pmod 3$$

that the Python witnesses verify against, so the browser demonstration and the audited specification are the same arithmetic.

Honest scope: fifteen of the sixteen audit checks are exact recomputations; the distance-3 break-even check is a small Monte-Carlo and is therefore statistical, and the heavy $|\mathrm{Sp}(4, 3)| =$

51840 closure is checked here through its arithmetic factorization $24 \cdot 2160 = |W(E_6)|$ rather than re-enumerated (the full closure remains in `analysis/w33_isa_encoding.py`). The physics identifications and the quantum-advantage values are re-stated, not re-measured, by the audit; they keep their own witnesses and the priced 9^t dial. What Pass 51 proves is the self-auditing property: one command, the whole datasheet, re-derived and checked from $q = 3$ alone.

C.70 Pass 52 — the parity law, and the performance face

Pass 51 made the datasheet re-derive itself from $q = 3$. Pass 52 asks the two questions that audit invites: *is $q = 3$ forced*, and *how fast does the machine run*.

The parity law (is $q = 3$ forced?). The witness `analysis/w33_audit_qscan.py` runs the same audit across the sister geometries $W(q) = \mathrm{GQ}(q, q)$ for $q = 2$ and $q = 3$ and verifies that every layer constant moves with q exactly as its closed form predicts:

$n = (q+1)(q^2+1)$	$k = q(q+1)$	$\lambda = q - 1$
$\mu = q + 1$	$\lambda_2 = q - 1$	points/line $= q + 1$
$\lvert\mathrm{Sp}(4,q)\rvert = q^4(q^2-1)(q^4-1)$	Hoffman $= q^2 + 1$	lines $= n$

giving $(n, k, \lambda, \mu) = (15, 6, 1, 3)$ at $q = 2$ and $(40, 12, 2, 4)$ at $q = 3$, and $|\mathrm{Sp}(4, 2)| = 720$ against $|\mathrm{Sp}(4, 3)| = 51840$. The headline is the contextuality. By Thas's theorem $W(q)$ possesses an ovoid — a set of $q^2 + 1$ pairwise non-collinear points meeting every line once — *if and only if q is even*. An ovoid is precisely a Kochen–Specker 0/1 assignment satisfying all n contexts, so the audit finds, computationally:

$$q = 2 \text{ (even)}: \text{ ovoid of 5 exists } \Rightarrow \text{ CF} = 0 \text{ (classical)},$$

$$q = 3 \text{ (odd)}: \text{ no ovoid, max partial ovoid } 7 < 10 \Rightarrow \text{ CF} = \tfrac{1}{10} \text{ (contextual)}.$$

The contextual power that drives the whole machine is therefore not inserted by hand: it is forced by the parity of the field, and $q = 3$ is the smallest odd prime that supplies it. The audit exhibits, side by side, the $q = 2$ ovoid that kills contextuality and the $q = 3$ obstruction that creates it.

The performance face. Where `holonetaudit` certifies the machine is *correct*, `analysis/holonet_bench.py` (the command `holonetbench`) certifies it is *cheap*, and it separates two kinds of number honestly. The deterministic operation counts — 7 mod-3 ALU operations per routing decision, ≤ 2 hops per packet, $\mu = 4$ multipath, four syndromes per error-correction cycle — are properties of the geometry and are identical on any computer. The wall-clock timings — route latency, correction-cycle time, teleport time, audit time, and the derived throughputs — are reported as medians over fixed, seeded workloads, but are host-relative. On ordinary Python on ordinary hardware the classical layer routes on the order of 10^5 packets per second and applies Clifford gates at a similar rate; these are a floor, not a ceiling, since a compiled or ASIC realization of the same op counts would be far faster.

The audit, live in the browser. Finally `docs/holonet.html` now renders the audit ledger client-side: thirteen of the sixteen rows are recomputed live in the reader's browser from $q = 3$ (the page rebuilds $W(3, 3)$, counts the fabric, derives λ_2 and the line-contexts, and checks the arithmetic), with the three solver rows — the contextual fraction, the magic robustness, and the code threshold — marked as verified by the Python witness. The same symplectic form $B(x, y)$ drives the browser page and the audited specification.

Honest scope: the q-scan is an exact recomputation per q (scipy MILP for the max-satisfiable count, NETWORKX for the independence number) and $q \in \{2, 3\}$ are prime, so F_q is integers mod q; it is a property test of the audit, not a new physical claim. The bench times the *classical* emulation only — the priced 9^t magic dial is excluded by construction — and its absolute times are host-relative.

C.71 Pass 53 — parity not primality, a falsifiable prediction, and the table-free win

Pass 52 established the parity law on two data points, $q = 2$ and $q = 3$, both prime. Pass 53 closes the obvious loophole and turns the law into an experiment.

Parity, not primality. The scan in `analysis/w33_audit_qscan.py` now reaches $q = 4 = \mathrm{GF}(4)$, built over the genuine field $F_2[x]/(x^2 + x + 1)$ rather than the integers modulo 4, and optionally $q = 5$. The geometry $W(4)$ is $\mathrm{SRG}(85, 20, 3, 5)$ with $|\mathrm{Sp}(4, 4)| = 979200$, and it possesses an ovoid of $17 = q^2 + 1$ points, so its contextual fraction is *zero*. Because 4 is even but *composite*, this rules out a "contextuality requires prime order" reading: the cause is the parity of q, full stop. Across the scan the contextual fraction takes the exact closed form

$$\mathrm{CF}(q) = \begin{cases} 0, & q \text{ even}, \\ \dfrac{1}{q^2 + 1}, & q \text{ odd}, \end{cases}$$

measured as $0,\ \frac{1}{10},\ 0,\ \frac{1}{26}$ for $q = 2, 3, 4, 5$. The Holonet sits at $q = 3$, the smallest order with nonzero CF, and its value $1/10$ is the $q = 3$ instance of this one-line law.

A falsifiable prediction. This makes the construction testable by a contrast rather than a single number. The same photonic Kochen–Specker test, laid out on an *even*-order symplectic fabric — $W(2)$ with 15 rays or $W(4)$ with 85 rays — must return *zero* contextuality, because an explicit ovoid assignment reproduces every measurement outcome noncontextually. Observing contextuality on an even-order fabric, or failing to observe $\mathrm{CF} = 1/10$ on the $q = 3$ fabric, refutes the model. The contextual fraction is not a tunable parameter; it is pinned to the field order, and the even-versus-odd contrast is the discriminating measurement.

The table-free win, measured. Finally `holonetbench--compare` quantifies the claim that "the address is the route". It builds a classical all-pairs forwarding table explicitly: a next hop for each of the $n(n-1) = 1560$ ordered destination pairs, $\lceil \log_2 40 \rceil = 6$ bits each, i.e. 1170 bytes of fabric-wide routing state, assembled by a breadth-first search from every node. It then verifies that the Holonet routes the same sampled pairs with *zero* table — the destination address is the route, every adjacency is the seven-operation symplectic test, every pair is reached in at most two hops — and that the two routers agree on reachability. The win is therefore a measured fact: $O(n^2)$ bytes of routing state and a rebuild on every topology change, reduced to nothing, because routing is stateless and local.

Honest scope: the $q = 4$ arithmetic is the true $\mathrm{GF}(4)$; the $q = 5$ check is exact but its integer program is heavy (minutes), so it is opt-in and excluded from the fast path. The routing comparison is an architectural state-and-setup comparison, not a wall-clock race: a table lookup is a cheap operation, but it presupposes the very table the Holonet never builds.

C.72 Pass 54 — the control arm: an explicit even-q ovoid, and the scaling win

Pass 53 made the parity law falsifiable in principle; Pass 54 supplies the *positive control* that makes it falsifiable in practice, and shows the routing win is a scaling law rather than a single number.

The explicit noncontextual model. The demonstrator protocol measures the $q = 3$ fabric and expects CF = 1/10; its natural control is an even-order fabric, which the parity law predicts must read CF = 0. That prediction is now a constructed object. The witness `analysis/w33_ovoid_construct.py` builds the ovoid of $W(2)$ and $W(4)$ — the five rays

$$\{0100,\ 1000,\ 1101,\ 1110,\ 1111\}$$

for $q = 2$, and seventeen rays for $q = 4$ — and verifies each three independent ways: it has size q^2+1, it meets every one of the n contexts in exactly one ray, and its rays are pairwise non-collinear. Assigning the value one to the ovoid rays and zero to all others is then a single context-independent truth assignment that satisfies every context at once: a working noncontextual hidden-variable model, so CF = 0 on the even fabric. The same witness confirms that $q = 3$ admits no such assignment (the best leaves four of forty contexts unsatisfiable), which is exactly the obstruction the positive arm detects. This converts the single-sided test into a two-arm discriminator, written up in `holonet_parity_control.tex`: contextuality must appear on the odd fabric and vanish on the even one, a contrast fixed by the geometry, so a systematic that faked a violation would have to respect the field parity to survive both arms.

The scaling win. Finally `holonetbench--compare--scale` shows that the table-free routing advantage grows without bound. For $W(q) = \mathrm{GQ}(q, q)$ with $n = (q + 1)(q^2 + 1)$ nodes, a classical all-pairs forwarding table costs $n(n - 1)$ next-hop entries of $\lceil \log_2 n \rceil$ bits — routing state of order $n^2 \log n$ that diverges with q — while the Holonet stores zero bytes and reaches any node in a constant two hops at seven modular operations per decision, because the address is the route and the generalized quadrangle has diameter two at every order. Tabulated from $q = 2$ to $q = 13$, the baseline routing state climbs from about a hundred bytes to several megabytes while the Holonet column stays identically zero and the hop count stays two.

Honest scope: the ovoid construction is an exact finite computation over F_2 and the genuine field GF(4); it is the predicted data for a physical control arm, not itself a run, and the even-order analyzer bank is a different optical object from the forty Witting tetrads. In the scaling table the forwarding-table sizes are exact closed forms, and the address-routing / diameter-two property is verified explicitly for $q \leq 5$ and holds for the whole $\mathrm{GQ}(q, q)$ family by the diameter-two theorem.

C.73 Pass 55 — the two-arm discriminator, runnable end to end

Pass 54 supplied the control model; Pass 55 makes the two-arm test executable inside the demonstrator's own estimator pipeline, and gives the scaling win a figure.

One estimator, two fabrics, opposite verdicts. The demonstrator ships two contextual-fraction estimators — a normal-window check and an exact two-sided binomial test — both written against the raw-shot schema and both targeting 1/10. The witness `analysis/holonet_control_arm.py` runs those *unmodified* estimators on two fixtures. The positive fixture is the committed synthetic $q = 3$ run; the control fixture is generated from the explicit $W(2)$ ovoid, where, because the ovoid satisfies every context, the noncontextual model has zero contextual excess and the signal

therefore clicks only at the dark-count baseline. The same estimators then return opposite verdicts on the one-tenth hypothesis:

$$\text{positive } W(3):\ \widehat{\mathrm{CF}} \approx 0.125 \text{ (compatible with } 1/10), \qquad \text{control } W(2):\ \widehat{\mathrm{CF}} \approx 0 \text{ (incompatible with } 1/10),$$

with a one-sided upper bound on the control fraction below 1/10. This is the parity law as a discriminating measurement that runs through the existing pipeline: a systematic faking a 1/10 signal on the odd fabric would have to fake it on the even fabric as well, where an explicit ovoid forbids any contextual excess. The parity law, the explicit ovoid, and this discriminator are registered at tier E in the public claim-tier spine (`analysis/BT1907_photonic_holonet_claim_tier_refactor.md`).

The scaling win, drawn. Finally `holonetbench--compare--scale--plot` renders the routing comparison as a figure: across $q = 2$ to 13 the classical forwarding table climbs from about a hundred bytes to several megabytes on a logarithmic axis, while the Holonet line stays pinned at zero bytes and two hops, written to `docs/holonet_scale.png`.

Honest scope: the control fixture is a synthetic run exercising the estimator path, not physical data; the positive arm reuses the committed synthetic fixture; the even-order analyzer bank remains a different optical object from the forty Witting tetrads. What is demonstrated is that the discriminator executes through the unmodified estimators and returns the geometry-forced verdicts, and that the figure is regenerated from the same closed-form scaling law.

C.74 Pass 56 — two contextualities, separated; and why one photon in $\mathbb{C}^4$

Pass 55 made the two-arm discriminator executable; Pass 56 computes its honest boundary, and in doing so finds a second, independent forcing of $q = 3$.

Sign versus selection. The parity law says the even fabric $W(2)$ has contextual fraction zero — yet the doily is the textbook home of the Mermin–Peres magic square. Both are true, because they are different statistics, and `analysis/w33_doily_mermin.py` computes both exactly on the same fifteen points. The *selection* system — exactly one click per context, the statistic the contextual-fraction estimators measure — is satisfied perfectly by the five-ray ovoid, so CF = 0. The *sign* system — noncontextual ± 1 values reproducing the product of each line's commuting two-qubit Pauli triple, with the fifteen signs computed as actual 4×4 matrix products (three lines multiply to $-I$) — is *unsatisfiable*: exact F_2 elimination proves it, and the minimal certificate is six lines covering every point an even number of times with an odd number of $-I$ lines — a Mermin–Peres square sitting inside the doily. So the even-order control fabric is sign-contextual yet selection-noncontextual, while the $q = 3$ fabric is contextual in *both* senses. The two-arm contrast is therefore a statement about one declared observable, and both arms must measure exactly that observable; this boundary is now stated in `holonet_parity_control.tex` and registered in the public theorem ledger.

The realization dimension bound. A complete-basis realization of $W(q)$ maps each context to an orthonormal basis, hence lives in $\mathbb{C}^{q+1}$. The witness `analysis/w33_realization_dimension.py` proves this is *impossible* for $q = 2$: a non-collinear pair of distinct rays spans two dimensions of $\mathbb{C}^3$, leaving a one-dimensional orthocomplement containing exactly one ray, while the geometry demands $\mu = 3$ distinct common neighbours there. The same count at $q = 3$ — four rays in a two-dimensional orthocomplement of $\mathbb{C}^4$ — poses no obstruction, and the Witting realization exists (cited corpus result); $q = 4$ passes this test with existence left open. Consequence: $q = 3$ is the

smallest symplectic quadrangle the one-photon $\mathbb{C}^4$ apparatus can realize at all, and by the parity law the smallest *contextual* one. Two independent forcings — one metrological, one statistical — select the same order.

Honest scope: both results are exact finite computations (matrix products and F_2 elimination; strongly-regular pair counts). The qubit-Pauli labelling of $W(2)$ is standard; the Witting existence at $q = 3$ is cited, not re-derived; $q = 4$ existence in $\mathbb{C}^5$ is open. Neither result weakens the discriminator — it sharpens what the discriminator's contrast is a contrast *of*: the selection statistic, declared in advance, measured identically on both arms.

C.75 Pass 57 — the contextuality tax: the defect is one movable point-star

Pass 57 is a synthesis pass: it joins two work streams that had converged on the same integer without a proof that they were describing the same object. The contextuality arc established max-sat = 36 of 40 contexts (CF = 1/10) and the parity law $\mathrm{CF}(q) = 1/(q^2+1)$ for odd q. Independently, the operating-system arc's line-context microkernel scheduler found 36 schedulable spreads and described its 4-context deficit as a "movable point-star double-occupancy defect" — language explicitly flagged there as an audited numerical bridge, not a proven structure. The witness `analysis/w33_contextuality_tax.py` proves the structure.

The complete classification. Iterating the max-satisfiable integer program with no-good cuts — each round forbidding the exact four-line failure set just found and re-solving — enumerates *every* failure set achievable by an optimal (36-context) assignment; the enumeration terminates when the objective drops below 36, so the classification is exhaustive rather than sampled. The result: there are exactly 40 achievable failure sets, and each is a *point-star* — the four lines through a single point — with every one of the 40 points realized as a center. So the defect of the classical layer is always one star, and it is fully movable: a gauge freedom, not an accident of one optimum. The deficit law follows structurally: for odd q the deficit is exactly $q+1$, one line's worth of contexts (verified 4 at $q = 3$; 6 at $q = 5$ under `--deep`), and 0 for even q, which restates $\mathrm{CF} = (q+1)/n = 1/(q^2+1)$ as "the tax is one star."

What the operating system pays. Operationally the classical scheduler can satisfy everything except the star of one point *of its choosing*, and may move that star to the least-loaded point. The escalation budget — the fraction of the runtime on which the priced 9^t quantum resource is spent — is therefore exactly one star, 4 contexts, 1/10 of the fabric, per classical assignment. The corollary by parity closes the loop with the control arm: on an even-order fabric the tax is zero and there is no gap to exploit even in principle, since $\alpha = q^2+1$ meets the Hoffman bound exactly (5 at $q = 2$, 17 at $q = 4$), while odd q keeps the gap ($7 < 10$ at $q = 3$). The machine's quantum advantage and its scheduling overhead are the same integer.

Honest scope: the $q = 3$ classification is exact and exhaustive; the deficit law is verified exactly at $q \in \{2, 3, 4\}$ (plus $q = 5$ opt-in) and stated as the observed closed form beyond; the identification with the scheduler arc's $36 = 36$ bridge underwrites that bridge's structural language but, like the bridge itself, claims no canonical bijection between optimal assignments and spreads; the runtime tie-in (twelve-tick admission words, the 2160-slot atlas, the 51840-tick supercycle) is accounting on committed constants.

C.76 Pass 58 — the spread side of the tax, and the anatomy of the optima

Pass 57 proved the tax theorem from the assignment side. Pass 58 (`analysis/w33_spread_star_anatomy.py`) completes the synthesis from the scheduler's side and, in doing so, lets the computation correct a guess.

The clock, counted independently. The scheduler arc's spread-clock rests on the spreads of $W(3,3)$ — sets of ten pairwise-disjoint lines partitioning the forty points — counted there by its own `find_spreads`. This witness re-enumerates them by exact-cover backtracking, a different algorithm sharing no code, and confirms: exactly 36 spreads, each line lying in exactly 9 of them. The bridge's 36 is now verified from two independent directions.

The service-rate guarantee. Every spread covers every point exactly once, hence contains exactly one line of every point-star (the scheduler arc's in-flight defect/spread tensor records the same complete incidence; it is re-verified here for all 36×40 pairs). Combined with the tax theorem — the failure set of any optimal assignment is one star — this yields the operational statement: *under any optimal classical assignment, every spread has exactly nine of its ten lines satisfied.* The spread-clock never sees a better or a worse cycle; the tax is spread-isotropic. For a fixed defect star the 36 spreads split into $q + 1 = 4$ classes of exactly 9 according to which defect line they carry.

The anatomy of the optima. Exhaustive enumeration (integer-program feasibility with no-good cuts, terminating) finds *exactly* 20 *optimal assignments per defect center* — 800 in all across the forty movable centers. The computation corrected the naive "double occupancy everywhere" guess and found a sharper structure, then pinned it: the center is *free* (optima come in center-lit/unlit pairs, exactly half each), and every optimum loads its four defect lines *uniformly* — the occupancy vector is always (c, c, c, c), never mixed, with $c \in \{2, 3, 4\}$: center-unlit optima are $(2, 2, 2, 2)$ with 11 lit rays or $(3, 3, 3, 3)$ with 12; their center-lit partners are $(3, 3, 3, 3)$ with 12 or $(4, 4, 4, 4)$ with 13. A defect line is never empty and never accidentally satisfied. The scheduler arc's "double-occupancy defect" is therefore literally the *minimal* class of optima — the ground state of the defect — while the full spectrum is uniform loading at two, three, or four rays per failed context.

Honest scope: all counts are exact finite enumerations; the optimum enumeration is exhaustive for the chosen center, with movability across centers supplied by Pass 57; the complete defect/spread incidence is the scheduler arc's observation, independently re-verified here; as before, no canonical assignment-to-spread bijection is claimed — the service-rate lemma shows the relation is many-to-many and uniform.

C.77 Pass 59 — the tax orbits: one group moves the defect's ground states

Pass 58 counted 20 optimal assignments per defect center, in classes $9 + 1 + 9 + 1$. Pass 59 (`analysis/w33_tax_orbits.py`) explains those numbers with the machine's own runtime group, and exports the scheduler consequence.

The group, rebuilt — and a distinction enforced. Symplectic transvections $T_v \colon x \mapsto x + B(x, v)\, v$ generate the symplectic group; closing a handful of transvection permutations of the forty points by breadth-first search yields the faithful point action. The check itself caught the classic subtlety the claim-tier spine warns about: on *points* the order is $25920 = 51840/2$ — the projective group $\mathrm{PSp}(4, 3)$ — because $-I$ acts trivially projectively; the 51840 matrix group is its double

cover. The witness now enforces the distinction rather than blurring it, and verifies transitivity on the forty points.

The orbit theorem. Acting with the group on the twenty optima of one center generates *all* 800 optima — twenty per center, every center reached — and they fall into exactly *four orbits*, of sizes 360, 40, 360, 40, with the pair (center lit?, uniform load c) a complete orbit invariant. The nine ground-state $(2,2,2,2)$ optima per center form one 360-orbit (their center-lit flips another), while the special $(3,3,3,3)$ optimum of each center forms a canonical 40-orbit: one distinguished twelve-ray configuration attached to each point of the fabric. The one-group-machine result thus extends to the tax at the projective level: the group that is the processor, the network, and the memory also moves the defect's ground states transitively.

The queue invariant, and the family probe. Re-verified across all 800 optima globally: the defect star's load vector is always uniform, with spectrum $\{2,3,4\}$ and ground state 2 — so a round-robin escalation queue has *zero* load imbalance in every optimal configuration, a statement exported machine-readably for the scheduler arc's in-flight queue simulator. Under `--deep`, the same anatomy question is put to $W(5)$: in a capped sample of forty optima at one center, uniform loading persists on the six-line defect star, the incidence law $L = 25 + c$ holds, and the observed load spectrum is $\{4,5,6\}$ — i.e. $\{q-1,\ q,\ q+1\}$, matching the $q = 3$ spectrum $\{2,3,4\}$ under the same formula. A parity-family load law is suggested, honestly marked as a capped sample rather than an exhaustive classification.

Honest scope: the group closure, orbit decomposition, validity of all 800 optima, and the global uniform-loading law are exact finite computations; the $q = 5$ probe is exact but capped; the queue statement is a restatement of the loading theorem in scheduler language, with no claim about the in-flight simulator's internals.

C.78 Pass 60 — the perp states: the canonical orbit named, the spectrum explained

Pass 59 found a canonical 40-orbit of special optima and asked what the object is. Pass 60 (`analysis/w33_perp_states.py`) answers: it is the oldest object in the geometry.

The identification. The special $(3,3,3,3)$ optimum at defect center p is *exactly* the neighborhood $\Gamma(p)$ — the deleted perp $p^{\perp} \setminus \{p\}$ — verified unique and equal per center; its center-lit flip is the full perp $p^{\perp}$, a classical geometric hyperplane of the quadrangle. The optimality proof is the *defining axiom* of a generalized quadrangle: a point off a line is collinear with exactly one of its points. Lighting $\Gamma(p)$ therefore satisfies every non-star line exactly once (the axiom, verified for every point–line pair at $q = 2,3,4,5$) and fails only the star, loaded uniformly with the three non-center points of each star line. The mysterious canonical configuration was the perp all along.

The spectrum, explained. Because the axiom holds in every generalized quadrangle, perp states exist at *every* order, loading the star uniformly at q (deleted) and $q+1$ (full) — verified at $q = 2,3,4,5$. This explains the tax load spectrum $\{q-1,\ q,\ q+1\}$: the top two loads are the deleted and full perp states, now *proven* present for all q (upgrading the $q = 5$ sample observation for those classes), while the bottom load $q-1$ belongs to the ground states. Parity still decides optimality: for odd q one failed star is the proven minimum, so the perp state is optimal; for even q it is strictly dominated by the ovoid.

The ground states, anatomized. Each of the nine $(2, 2, 2, 2)$ ground states per center decomposes as 8 in-perp + 3 out-of-perp points. Verified exactly: the nine out-triples are pairwise non-collinear triads, each with common perp of size exactly 4 (centric triads), and they *partition* the 27 non-neighbors of the center — the second subconstituent, regular of degree 8 on 27 vertices, the same 27-point structure the corpus ties to the Schläfli/E_6 story. The point stabilizer in $\mathrm{PSp}(4, 3)$ (order 648) is *transitive* on the nine ground states, so per center there is one ground state up to local symmetry, just as globally there is one up to the full group.

Honest scope: the perp and hyperplane are standard finite-geometry objects; the new content is the exact identification with the Pass 58/59 optima and the resulting explanation of the load spectrum. The Schläfli-adjacent observations are recorded as computed invariants (a partition of the 27 into nine centric triads; an 8-regular induced graph) with no further corpus identification claimed.

C.79 Pass 61 — every node carries a qutrit phase space

Pass 60 named the perp states and left the ground states anatomized but unnamed. Pass 61 (`analysis/w33_ground_affine_plane.py`) names them, with an exhaustive closure at two odd orders.

The optimizer was never needed. Among the 27 non-neighbors of a center p there are exactly 81 four-centric triads — each point on 9, each pair on at most one — and their center-quads split cleanly: 9 triads have all four centers inside $\Gamma(p)$, 72 have exactly one. The nine ground states are *exactly* the nine all-centers-in-perp triads (verified set-for-set against the integer-program enumeration). The defect's ground states admit a purely geometric characterization: they are the triads whose centers all live in the perp.

The affine plane law. Per defect center of $W(q)$, q odd, the optima number exactly $2(q^2 + 1)$ — twice the Hoffman bound — and close exhaustively: 20 at $q = 3$ and 52 at $q = 5$, the latter terminating below its cap and upgrading Pass 59's capped sample to a theorem. The q^2 ground states carry the structure of the affine plane $\mathrm{AG}(2, q)$: grounds are the points; the $q(q+1)$ neighbors in $\Gamma(p)$ are the lines, incident when the neighbor is *unlit* in the ground; each ground's unlit set is precisely the $q + 1$ lines through its point, a transversal of the defect star; and the $q + 1$ parallel classes of the plane *are* the $q+1$ defect lines (same-class neighbors are never co-unlit; different-class, exactly once). The two remaining optima are the perp states of Pass 60, and the ground lit-sets are pairwise equidistant (intersection 5 at $q = 3$, 19 at $q = 5$).

The phase-space reading. At $q = 3$ this affine plane is the Hesse configuration $(9_4, 12_3)$ — the single-qutrit Wigner phase space of the corpus witness `w33_hesse_mermin_contextuality`, whose four striations (the mutually unbiased bases) are realized here as the four defect contexts. Every node of the fabric carries, in its tax bookkeeping, a copy of the qutrit phase space: the nine classical ways to pay the tax at a node are the nine phase points, and moving the defect's double-occupancy among its four contexts is moving among the four striations. The point stabilizer (order 648) is 2-transitive on the nine grounds — computed as a single pair-orbit of 72 — matching the 2-transitivity of the affine group on the plane.

Honest scope: exact finite computations, exhaustive at both odd orders tested; the $\mathrm{AG}(2, q)$ identification is verified through its defining incidence properties, and the phase-space reading cites the committed Hesse identification rather than re-deriving it.

C.80 Pass 62 — the global phase-space bundle and Wigner fuel accounting

Pass 61 placed a qutrit phase space at every defect center. Pass 62 (`analysis/w33_phase_space_bundle_wigner_accounting.py`) asks whether those forty local planes remain separate local charts, or glue into one object.

The bundle theorem. Starting from the ILP-free triad characterization of the nine grounds at one center, and acting by the same projective runtime group rebuilt in Pass 59, the witness obtains a single 360-state orbit:

$$360 = 40 \times 9.$$

The fiber over each of the forty centers has size nine. The stabilizer of one ground has order 72, so $25920/72 = 360$, and the action on the bundle has rank 15, with subdegrees

$$[1, 3, 4, 8, 8, 24^{\times 8}, 72, 72].$$

This is exactly the cardinal/fiber format of the committed two-qutrit Hudson atlas — forty Lagrangian bases, nine states per basis — though no explicit Hilbert-vector labeling of every ground state is claimed here.

The gluing spectrum. The local phase planes do not merely sit side by side. Pairwise intersections of lit sets are controlled by the relation between their centers: same-center pairs all have intersection 5; collinear centers split across intersections $0, 2, 3, 8$; non-collinear centers split across $1, 2, 4, 6$. This spectrum is the measured transport interface between the local qutrit phase spaces.

The Wigner fuel ledger. On each local nine-point Hesse plane, the qutrit Strange state has one Wigner value $-1/3$ and eight values $+1/6$. Thus the negative mass is $1/3$, the positive mass is $4/3$, the L^1-norm is $5/3$, and the mana is $\log(5/3)$. The local affine symmetry can move the negative site to any of the nine grounds; globally, the bundle has 360 possible negative-site placements. The tax density $1/10$ and the local Wigner mass $1/3$ are different meters of the same contextual resource: one prices failed contexts, the other prices the single-qutrit quasiprobability fuel.

Honest scope: the bundle, rank, subdegrees, and gluing spectrum are exact finite computations; the Wigner ledger reuses the committed Gross qutrit phase-point operators; the Hudson statement is a cardinal/fiber bridge, not an explicit basis-state dictionary.

C.81 Pass 64 — the interrupt controller: the tax arc runs inside the VM

(Passes 62–63 — the global phase-space bundle with Wigner fuel accounting, and the GAP Hilbert-transport certificate — belong to the parallel VM/OS track and are documented in its own passes.) Pass 64 fuses the two tracks. The VM track's microkernel table maps "interrupt = point-star defect/escalation", "scheduler tick = spread frame", and "relocation = automorphism action" — rows that were descriptive until now. The tax arc (Passes 57–61) proved exactly the theorems those rows need. The witness `analysis/w33_interrupt_controller.py` makes the rows executable, with the theorems as *runtime invariants*, and the fusion yields two new exact laws.

The closed-form vector table. For each of the nine all-centers-in-perp triads T at a center p,

$$\mathrm{ground}(T) \;=\; T \cup \big(\Gamma(p) \setminus T^{\perp}\big),$$

verified set-for-set against the integer-program enumeration — and the unlit quad *is* the center quad $T^{\perp}$, a transversal of the defect star. The controller rebuilds its AG$(2,3)$ vector table in closed form; no optimizer runs at interrupt time.

The migration price law. Computing the lit-set overlap of every pair of the 360 ground states, classified by the relation of their defect centers: same center, overlap always 5 (re-vectoring in place costs $11-5=6$ rays); collinear centers, overlaps $\{0,2,3,8\}$ (cheapest migration 3 rays); non-collinear, $\{1,2,4,6\}$ (cheapest 5). Every ground state has exactly 8 cheap (overlap-8) channels, sitting two per center at exactly *four* collinear centers — which are the ground's own center quad. So the interrupt's escape routes are written into its own vector; it migrates cheapest along fabric edges (locality emerges in the operating-system layer); and, strikingly, moving the defect to a neighboring node (3 rays) costs *less* than reconfiguring it in place (6).

The controller, run. A seeded loop of 2100 events over the 40 contexts, including device-port injections that follow the VM track's USB mapping (interrupt-class transfers arrive as defect-star urgent packets, bulk-class as ordinary line traffic): non-defect events are serviced in spread frames, each provably 9/10; defect-line events are escalations on the priced 9^t path; overloads trigger cost-aware relocation through cheap channels to the least-loaded quad center. Across the run, every runtime invariant held — the failure set stayed exactly one star (Pass 57), every frame served 9/10 with uniform loading (Pass 58/59), the vector table stayed the nine closed-form entries (Pass 61), every relocation landed on a valid ground (Pass 59) — and the average migration cost was exactly 3.00 rays.

Honest scope: the price law and closed form are exact finite computations; the controller is a classical seeded simulation bound to the committed theorems — the interrupt layer the VM track's packet machine can adopt, not a claim about that in-flight code; escalation pricing cites the committed 9^t dial.

C.82 Pass 65 — the kernel fusion: programs, pages, and the walking defect

Pass 64 built the interrupt controller; Pass 65 wires it through the VM track's three pillars — program execution, memory placement, and scheduler telemetry — yielding three witnesses and three new exact laws.

Programs: mode-2 execution with a real kernel. `analysis/w33_packet_vm_kernel.py` lifts the committed 22-instruction TritCPU router program to a packet stream (registers and RAM embedded at points; every data-moving instruction becomes one route of one or two line transactions) and executes it *through* the controller. Over all 1600 ordered inputs the kernel-wrapped outputs equal the direct machine's and the ground-truth symplectic form; all 46,400 hops are line-legal; 90 defect-line touches escalate on the priced 9^t path; 15 relocations all use cheap channels (average cost exactly 3.00 rays); every tax theorem holds as a runtime invariant under a real workload. The VM track's in-flight packet VM is detected as the adoption target of the `service()` hook, with no dependency taken.

Pages: the loader meets the phase space. `analysis/w33_defect_aware_placement.py` gives the VM track's page loader a defect-aware directory: the 27 non-neighbors of the current defect center touch no defect line (verified), and Pass 61's ground out-triples partition them into the nine AG$(2,3)$ phase points — so pages place *page* $\to$ *phase point* $\to$ *triple slot*, never on an

escalation path. The *page bill law*, computed over all 780 center pairs: the safe-zone overlap is a constant 18/27 for adjacent *and* non-adjacent relocations — the memory bill is always exactly 9 points — so the page side is relocation-isotropic and the ray-side price law alone decides: edges win strictly. Re-keying after an edge move is all-or-nothing at triple granularity: six of the new nine triples survive intact, three rebuild.

Telemetry: the walking defect. `analysis/w33_defect_walk_telemetry.py` instruments a 20,000-event run (1023 relocations) and pins the dynamical signature: *every* step lands in the pre-move center quad (the four unlit neighbors written into the current vector), along a fabric edge, at exactly 3 rays — a quad-constrained nearest-neighbor walk — emitted as a spread-clock-compatible JSONL trace for the VM track's tooling. Coverage statistics are reported as seed-specific measurements, not ergodicity claims.

Honest scope: the embeddings and directories are bookkeeping made canonical by committed theorems; the semantic engines are the committed TritCPU and controller; the VM track's in-flight loader, packet VM, and trace tooling are named consumers, not dependencies.

C.83 Pass 66 — kernel dynamics: stationarity, re-keying, and the self-logging fabric

Pass 65 left the defect walking; Pass 66 (`analysis/w33_kernel_dynamics.py`) closes it with four results.

The stationary law. The defect walks on the cheap-channel graph: the 360 ground states with the overlap-8 adjacency of Pass 64's price law. This graph is 8-regular, *connected*, and group-invariant, hence vertex-transitive, so the walk's stationary distribution is *uniform*: every ground state, and therefore every center, is visited equally in the long run (nine grounds each). Pass 65's seed-specific 29/40 coverage was a finite-time artifact, not a law. On the exact 360×360 matrix the spectral gap is 0.32 and the second-eigenvalue mixing bound is about 23 steps.

Re-keying, made addressed. For every one of the 480 ordered fabric edges $p \to p'$, the three rebuilt phase triples of the new directory are exactly the $\mathrm{AG}(2,3)$ line of the new plane indexed by the *old* center p, and their three center-quads meet in exactly $\{p\}$. Pass 65's all-or-nothing re-keying is therefore *addressed*: the departing center's name is written, as a line of the new phase plane, onto the pages that just arrived.

The pipeline, live. The lifted router program executes through the kernel with its RAM cells dynamically placed as phase-directory pages, under a background interrupt load that drives the defect; across many mid-run relocations every output still equals the symplectic ground truth and every tax theorem holds. Process, memory, interrupt, relocation, and audit run as one object.

The fabric logs itself. Because re-keying is addressed, every relocation stamps its origin into the geometry: the loader writes one marker on each of the three rebuilt triples, and because their center-quads meet in exactly $\{p\}$, the previous center decodes *uniquely* from the three markers plus the incidence structure — no explicit interrupt log. Over a live run all 150 relocation origins are recovered correctly, zero ambiguous: audit-by-geometry at three marker points per interrupt, the operating system's replay guarantee supplied by the quadrangle itself.

Honest scope: the stationary conclusion is the standard theorem for connected vertex-transitive chains, its hypotheses verified here (gap and mixing are numerics on the exact matrix); the rebuilt-line rule and the $\{p\}$-intersection fact are verified for all 480 ordered edges; the pipeline and decode are seeded executions whose invariants are the committed theorems, the decode reading only three markers and the geometry.

C.84 Pass 67 — unifying the tracks: a self-auditing scheduler and an exact gap

Pass 67 fuses the tax-arc kernel with the parallel track's committed BT1807–1816 relocation hardware, on that track's own geometry.

The scheduler audits itself. The parallel track's BT1808 compiles all allowed cheap relocations into 1440 rows (40 centers × nine phase rows × four exits $= 3 \times 480$ directed edges) but supplies no replay. Wiring Pass 66's self-logging decode into it (`analysis/w33_scheduler_audit_backend.py`) turns replay into a theorem: for every one of the 480 directed edges $p \to q$, the three destination phase rows whose center quad contains p have quads meeting in exactly $\{p\}$, so one marker per row recovers the origin uniquely — no event log. A 400-step walk driven through the scheduler's own edges replays edge-for-edge from three markers per step, and because BT1808 covers every directed edge exactly three times, all 1440 rows are geometrically auditable.

The exact mixing time. The cheap-channel graph on the 360 ground states (`analysis/w33_cheap_channel_spectrum.py`) is 8-regular but *not* strongly regular: it has eight distinct eigenvalues, proved exact by integer trace moments,

$$\text{spec} = \left\{8^{1},\ \tfrac{1+\sqrt{97}}{2}^{15},\ 3^{84},\ 1^{111},\ (-1)^{20},\ (-3)^{90},\ (-4)^{24},\ \tfrac{1-\sqrt{97}}{2}^{15}\right\},$$

the irrational pair being roots of $x^2 - x - 24$. Hence the defect walk has exact second eigenvalue modulus $(1 + \sqrt{97})/16$ and exact spectral gap

$$1 - \frac{1+\sqrt{97}}{16} = \frac{15-\sqrt{97}}{16} \approx 0.3219,$$

with relaxation time $(15 + \sqrt{97})/8$. Pass 66's numeric gap 0.32 and $\sim$ 23-step bound were the shadow of these algebraic numbers.

One page bill, two proofs. Pass 65's safe-zone overlap derivation and the parallel track's TD$(4, 3)$ churn derivation (`analysis/w33_page_bill_unification.py`) compute the *same* set difference for all 1560 ordered moves — the retained count is the safe-zone overlap, always 18, so the bill is always nine. The edge/non-edge histogram split is the line/transversal dichotomy of the AG$(2, 3)$ directory: for an edge move the three fully-churned triads are exactly the rebuilt line indexed by the departing center (their quads meeting in $\{p\}$, so edge re-keying is phase-coherent *and* origin-addressed), while a non-edge move churns a transversal, one point per triad.

Honest scope: all three are exact finite computations on the parallel track's committed geometry plus the tax arc's structures; the audit theorem and the page-bill unification hold for all edges/-moves, the spectrum is verified by integer moments, and the mixing figure is the standard spectral bound with exact inputs.

C.85 Operator-on-photon self-applied circuit packet

One Choi leg is interpreted as the photonic mode state and the other Choi leg as the encoded optical action. The finite circuit is therefore modeled as a relation on one photons own registers.

The self-applied model represents I, X, Z, F_3, and S as encoded actions on the operator leg and checks them by trace-Choi overlap against the state leg.

The OAM operator witness distinguishes passive mode labels from active internal operator behavior by comparing label-only controls, operator-leg activation, basis covariance, and self-vs-external control tests.

C.86 Internal optic algebra, physical dictionary, and falsifier regimes

The internal operations I, X, Z, F_3, and S generate the finite single-qutrit projective Clifford action of size $216 = 9 \cdot 24$ on the state/operator Choi legs.

The operations are mapped to optical analogues: reference/no-op, OAM shift or prism step, spiral phase plate, tritter or mode mixer, and lens or phase-curvature analogue. The lens row remains calibration-level.

The falsifier simulator separates passive OAM labels from active internal-operator behavior. Only the internal-operator scenario passes the symbolic criteria: trace-Choi pattern, low leakage, basis covariance, and operator activation.

C.87 Internal Clifford census, lens calibration, and passive-active protocol

The internal operations I, X, Z, F_3, and S generate a 216-element single-qutrit projective Clifford action on the state/operator Choi legs. All 216 elements preserve the state/operator split in the internal-register model; only the identity stabilizes the identity Choi state itself. The 24 zero-translation frame changes preserve centered OAM opposition, while the 192 translated elements move the OAM origin and require recentering.

The lens calibration row is exact at the finite phase-signature level. On the centered OAM basis $\ell = -1, 0, +1$ with qutrit labels $2, 0, 1$, qutrit S has ω-exponent signature $[1, 0, 1]$, matching the centered quadratic lens phase ω^{ℓ^2}.

The passive-vs-active protocol uses centered OAM preparation, axial time-bin support, operator off/on controls, $I/X/Z/F_3/S$ settings, leakage checks, basis covariance, and external-reference comparison. It is a protocol design, not experimental evidence.

C.88 OAM recentering, exact optical calibration, protocol table, and literature bridge

The 192 translated Clifford elements split into eight nonzero shift classes, each with 24 frame choices. The recentering correction is the inverse shift, with OAM-only, phase-only, and mixed shift classes.

The S and F_3 calibrations are placed on the same centered OAM basis. The S row has phase signature $[1, 0, 1]$, and the F_3 row is the finite three-mode mixer on the same qutrit labels.

The passive-vs-active protocol is converted into a paper-ready table covering preparation, passive controls, active gate settings, leakage, covariance, reference comparison, expected readouts, thresholds, failure modes, and claim tiers.

The OAM literature bridge supports high-dimensional qudit and same-photon register directions, but requires radial leakage and mode-overlap witnesses because radial and azimuthal spatial structure are coupled in realistic modes.

C.89 Recentered witnesses, leakage regimes, and appendix splicer

The calibrated I, X, Z, F_3, S witness applies directly to the centered frame class. Translated Clifford elements require inverse recentering before the same witness table is applied.

The radial leakage simulator turns symbolic shell leakage into pass/fail regimes, separating good core-gate behavior from radial leakage, visibility mismatch, and basis-covariance failures.

The operator/OAM appendix splicer follows the dry-run and idempotent splicer pattern. It records the appendix insert packets and changes the paper only when apply mode is used in checkout.

C.90 Appendix validation, recentered protocol table, and claim ledger

The appendix packet is validated by a dry-run artifact checker: all insert paths exist, the bounded splice block is idempotent, and the target paper admits the expected splice anchor or bounded fallback.

The protocol table is expanded by recentering class. The resulting table has four Clifford recentering classes times five calibrated witnesses, with correction operators, leakage thresholds, failure modes, and claim tiers.

The claim ledger separates exact finite claims from calibration-level optics, engineering leakage, protocol witnesses, literature motivation, and blocked physical overclaims.

C.91 Full operator/OAM appendix splice and recentered transaction ABI

The operator/OAM appendix is now part of the main Holonet paper through a bounded idempotent splice. The splice carries the operator-on-photon circuit model, the internal Clifford falsifier, the recentering protocol, the leakage and claim ledger, and the present synthesis block.

The architectural closure is the recenter-to-transaction ABI:

$$216 = 9 \cdot 24 = (1 + 2 + 2 + 4) \cdot 24.$$

The factor 24 is the centered BT1495 transaction-word kernel. The nine affine shifts are one centered class, two OAM-only shifts, two phase-only shifts, and four mixed shifts. Thus the class profile is

$$24, \quad 48, \quad 48, \quad 96,$$

and every translated internal Clifford action is executed by inverse recentering followed by one of the same 24 centered 72-tick transaction words.

One operation sweep therefore has $216 \cdot 72 = 15552$ ticks. The full five-witness I, X, Z, F_3, S protocol has 77760 ticks. This is an exact finite ABI statement: it certifies the centered word reuse and the recentering burden. It does not claim measured OAM leakage, optical loss, or a finished calibrated device.

Recent OAM and high-dimensional time-bin experiments support the physical direction, including same-photon polarization/OAM gates, robust time-bin qudit control, directly measured topology in OAM-entangled states, and OAM-multiplexed diffractive mode processing [32, 33, 34, 35]. BT1588 keeps those sources in the literature-motivation tier only: they motivate the mode interface, multiplexing optics, and leakage tests, while the exact theorem remains the local finite $216 = 9 \cdot 24$ recenter ABI.

C.92 LG radial covariance, full witness lane sheet, and OAM front end

The recenter ABI now has a radial-shell falsifier. Model the first three Laguerre–Gaussian radial shells by the stochastic channel family $L(\eta)$: diagonal entries $1-\eta$, off-diagonal entries $\eta/2$. The BT1577 operation envelopes I, Z, S, X, F_3 all lie in this same channel family, so the radial recenter correction and the centered witness gate commute at shell level. For two envelopes,

$$\eta(a,b) = a + b - \frac{3}{2}ab.$$

Thus the $216 = 9 \cdot 24$ affine actions do not require 216 separate radial calibrations. They require one centered witness table plus the recenter tax. The symbolic worst case is a mixed OAM/phase recenter followed by F_3,

$$\eta_{\max} = 0.18296 < 0.20,$$

while the centered gate threshold remains the BT1577 value 0.10. This is a covariance simulator and falsifier, not measured beam leakage.

The complete witness replay is now compiled as a physical lane sheet:

$$5 \text{ gates} \times 9 \text{ recenter sectors} \times 24 \text{ centered words} \times 72 \text{ ticks} = 77760.$$

It is stored as 1080 exact 72-tick segments with the global tick formula

$$((((g \cdot 9) + s) \cdot 24 + w) \cdot 72 + t).$$

Every Hesse lane appears 12960 times, every detector slot appears 19440 times, native D_4 square-pulse words occupy 25920 ticks, and the remaining S_4 analyzer-relabel words occupy 51840 ticks.

The hardware interpretation is deliberately sharper. OAM-multiplexed diffractive optics are a proposed *front-end sectorizer*: a passive mode-processing layer can sort or fan out the nine affine recenter sectors before the exact 24-word transaction kernel runs. Recent OAM-MDNN work supports this as an optical mode-processing direction, but it does not prove a quantum gate, preserve coherence by itself, or calibrate loss. The promoted theorem remains local:

$$\boxed{9 \text{ recenter sectors} \times 24 \text{ centered words} = 216 \text{ exact finite ABI addresses},}$$

with acceptance delegated to radial tomography, sector crosstalk measurements, and the 77760-tick witness replay.

C.93 Lab tomography, LG alphabet, and the Hesse/T witness loop

The OAM front end is now written in a lab-facing form. BT1592 promotes three acceptance surfaces: a 9×9 sector confusion matrix, four radial-shell tomography rows, and six exact lane-replay checks. The synthetic sector fixture uses diagonal probability 0.93, off-diagonal probability 0.00875, and acceptance thresholds

$$p_{\text{diag}} \geq 0.90, \qquad p_{\text{off}} \leq 0.02.$$

The generated CSV ingest file has 91 rows, all passing, and is deliberately replaceable by bench data. This is a falsification harness, not measured OAM crosstalk.

BT1593 chooses the explicit Laguerre–Gaussian sector alphabet:

$$s = 3x + z, \qquad \ell = s - 4, \qquad p = x + 2z \pmod 3.$$

Thus the nine recenter sectors occupy symmetric OAM charges

$$\ell = -4, -3, -2, -1, 0, 1, 2, 3, 4,$$

with three modes in each radial shell $p = 0, 1, 2$. The 24-word centered selector is a separate handoff layer:

$$\text{address} = 24s + w, \qquad 0 \le s < 9, \quad 0 \le w < 24.$$

The architecture therefore uses 9 physical sector modes plus a 24-word selector, not 216 separate OAM channels. The 216 exact finite addresses split into 72 native D_4 square-pulse addresses and 144 S_4 analyzer-relabel addresses.

The universality port now lands in the same witness loop. BT1404 already made a Hesse/T microframe with

$$9 \text{ Hesse outcomes} \times 8 \text{ ticks} = 72 \text{ ticks}.$$

BT1590 already made each OAM witness segment 72 ticks. BT1594 overlays these rather than appending a second schedule:

$$1080 \text{ segments} \times 72 \text{ ticks} = 1080 \text{ Hesse/T microframes} = 77760 \text{ ticks}.$$

Each Hesse outcome appears once per segment, hence 1080 times total. The T-frame bit profile is $0 : 5400$ and $1 : 4320$, matching the parity rule

$$t = (r + p) \bmod 2.$$

This closes the finite architecture loop: the Clifford/OAM witness, the sector-mode front end, the tomography acceptance harness, and the explicit Hesse/T non-Clifford port now inhabit one replayable 77760-tick object. The claim boundary remains unchanged: this is ABI and schedule compatibility, not a physical Hesse-SIC device, injection-fidelity measurement, or fault-tolerant magic-state-yield theorem.

C.94 The Witting reject shell as the universal fuel rail

The deepest closure in the current architecture is that the newest OAM/Hesse witness loop is not merely a validation sweep. It is the Witting matter shell itself. In the Witting delayed-query desk, each selected ray has

$$1 \text{ same} + 12 \text{ compatible} + 27 \text{ incompatible} = 40$$

possible queried rays. Therefore the incompatible ordered-pair shell has

$$40 \cdot 27 = 1080$$

records. BT1595 constructs an explicit bijection

$$40 \cdot 27 = 5 \cdot 9 \cdot 24$$

between those rejected Witting pairs and the BT1590/BT1594 witness segments. The per-gate refinement is even sharper:

$$9 \cdot 24 = 216 = 8 \cdot 27.$$

Thus each of the five witness gates consumes the full incompatible-target shell of eight Witting source rays. Each rejected Witting pair is one 72-tick contextual fuel segment, and each such segment carries the Hesse/T overlay.

BT1596 writes the resulting runtime economy:

$$520 \cdot 72 = 37440 \qquad \text{accepted communication/control ticks,}$$

$$1080 \cdot 72 = 77760 \qquad \text{contextual fuel ticks,}$$

and

$$1600 \cdot 72 = 115200 \qquad \text{ticks for the complete Witting ordered-pair cycle.}$$

The ratio of accepted control to contextual fuel is $13 : 27$, matching the Witting split 13/40 versus 27/40.

BT1597 packages this as a single universal transaction object. Accepted Witting pairs form the communication and control rail. Rejected Witting pairs are not discarded; they are exactly the OAM/Hesse contextual-fuel rail:

$$1080 = 5 \text{ gates} \cdot 9 \text{ OAM sectors} \cdot 24 \text{ words} = 40 \text{ rays} \cdot 27 \text{ incompatible targets.}$$

The Hesse/T microframe on that fuel rail supplies the explicit non-Clifford boundary required by the universal-computation contract. The claim remains a finite ABI and timing theorem: it does not assert optical coherence, loss tolerance, cryptographic security, or a fault-tolerant threshold.

C.95 Accepted control rail and the full Witting transaction cycle

The Witting fuel rail now has its complementary control rail. BT1598 compiles the accepted 13/40 Witting ordered pairs into concrete 72-tick control frames. The only ambiguity is the same-ray case: a ray lies in four Witting bases. BT1598 resolves this by a perfect matching between the 40 rays and the 40 bases. Therefore each basis carries exactly one same-ray aperture and twelve off-diagonal compatible apertures:

$$40 \text{ bases} \cdot 13 \text{ controls} = 520 \text{ accepted frames,}$$

$$520 \cdot 72 = 37440 \text{ accepted control ticks.}$$

The detector handoff is the existing one:

$$\text{Witting analyzer slot} \to \text{detector slot} \to \text{mirror slot mod } 4 \to \text{tomotope flag.}$$

Using the selected Witting basis as a tomotope block gives

$$\text{tomotope flag} = 4\,\text{basis} + \text{detector slot,}$$

using the first 40 of the 48 tomotope blocks and leaving 8 slack blocks for non-Witting packet traffic.

BT1599 explains the 120-record surplus in the basis-local Witting table. There are 160 same-ray basis-local apertures, but BT1598 promotes only 40 of them to selected control frames. The remaining records are

$$160 - 40 = 120 = 3 \text{ local tomotope sheets} \cdot 40 \text{ W33/Witting lines,}$$

exactly the BT1365 selector phase-sheet bundle. Thus the same-ray surplus is a qutrit phase sidecar rather than extra communication throughput.

BT1600 then compiles the full ordered-pair desk:

$$40 \text{ source rays} \cdot 40 \text{ target rays} = 1600 \text{ frames,}$$

$$1600 \cdot 72 = 115200 \text{ ticks.}$$

Every source ray has

$$13 \text{ accepted control frames} + 27 \text{ contextual fuel frames.}$$

The complete cycle is therefore not two unrelated protocols. It is one finite transaction machine: accepted pairs run the Witting analyzer/mirror control rail, rejected pairs run the OAM/Hesse contextual fuel rail, and the unused same-ray contexts are exactly the ternary selector phase sheets.

C.96 Physical automaton, Fano detector bins, and the universal ABI

BT1601 turns the 1600-frame Witting transaction cycle into a single physical automaton. The carrier is one single-photon transaction packet. Each ordered pair frame keeps the common 72-tick shape:

$$1600 \cdot 72 = 115200 \text{ ticks.}$$

The frame template is now explicit:

ticks	role
$0 \ldots 7$	source switch
$8 \ldots 31$	program/delay placeholder
$32 \ldots 47$	analyzer or OAM/Hesse body
$48 \ldots 63$	detector or Hesse/T handoff
$64 \ldots 71$	dark-reference placeholder

There are 520 Witting analyzer switch frames and 1080 OAM/Hesse fuel switch frames. The four detector residues are balanced across the whole automaton:

$$400,\ 400,\ 400,\ 400.$$

Every frame has a symbolic loss channel and a dark-reference bin. These fields are intentionally placeholders: BT1601 compiles the interface, not a measured loss or dark-count model.

BT1602 identifies the old 168 active detector-bin count with the Fano plane. The active bus factors as

$$168 = 7 \cdot 24 = 7 \text{ Fano lines} \cdot 3 \text{ point slots} \cdot 8\ D_4 \text{ states.}$$

The Witting source side factors as

$$40 = 5 \text{ witness gates} \cdot 8\ D_4 \text{ source states.}$$

The five witness gates occupy five Fano lines. On those lines,

$$27 = 3 \text{ point slots} \cdot 9 \text{ Hesse/OAM residues}$$

is the contextual fuel shell. The two remaining Fano lines carry the accepted compatible controls:

$$12 = 2 \text{ reserve lines} \cdot 3 \text{ point slots} \cdot 2 \text{ detector parities.}$$

The same-ray control is the source anchor on the gate line. Thus every source ray has

$$27 \text{ fuel} + 12 \text{ compatible control} + 1 \text{ same-ray control} = 40$$

targets, and every one of the 168 active detector bins is touched. The usage profile across the 1600 frames is

$$80 \text{ bins} \times 9 \quad + \quad 88 \text{ bins} \times 10 \quad = \quad 1600.$$

BT1603 packages the architecture as a finite universal-computation ABI theorem. The accepted Witting frames provide finite Clifford transport through the analyzer/mirror/tomotope handoff. The rejected Witting frames provide the contextual OAM/Hesse fuel. The Hesse/T overlay supplies the explicit non-Clifford port required by the BT1377 universal-computation contract. The detector and row values then hand into the BT1486 retwined CSS syndrome layer and the BT1493 physical row-pulse compiler. In short,

$$\text{Witting control} + \text{contextual fuel} + \text{Hesse/T port} + \text{CSS handoff}$$

is now one finite programmable photonic-computation ABI. The theorem remains inside the claim firewall: thresholds, measured loss, detector efficiency, and magic-state yield are downstream physical requirements, not consequences of the finite compiler alone.

C.97 Fano charge, time-bin envelope, and guard-page closure

The $80 \times 9 + 88 \times 10$ detector-bin profile is not just a usage histogram. BT1648 shows that it is a conserved Fano charge. The 168 active detector bins split into three exact classes:

$$80 \cdot 9 + 40 \cdot (9 + 1) + 48 \cdot 10 = 1600.$$

The 80 bins are unanchored contextual-fuel bins. The 40 middle terms are fuel bins with one same-ray control anchor. The 48 final bins are compatible-control reserve bins. Equivalently, the seven Fano lines split as five Witting gate lines and two reserve lines:

$$5(16 \cdot 9 + 8 \cdot 10) + 2(24 \cdot 10) = 1600.$$

This explains why the high-usage side has size 88: it is exactly

$$40 \text{ same-ray anchors} + 48 \text{ compatible reserve bins}.$$

BT1649 then embeds the active automaton into an 11-bit time-bin qudit envelope, motivated by single-photon time-bin qudit universal logic [29]. The active Witting transaction uses the first 1600 time bins. The remaining addresses factor without remainder:

$$2^{11} = 2048, \qquad 2048 - 1600 = 448 = 7 \cdot 64.$$

Thus every Fano point receives a 64-slot guard page. Each guard page is typed as

$$24 \text{ dark references} + 24 \text{ loss probes} + 16 \text{ parity overflow slots}.$$

The Witting source/fuel structure remains the contextual communication desk of [28]; the time-bin envelope is the physical address wrapper around that finite desk, not a new communication assumption.

BT1650 closes the calibration interface. The $7 \cdot 24 = 168$ dark-reference guards cover all active detector bins once, and the 168 loss-probe guards also cover all active detector bins once. The remaining $7 \cdot 16 = 112$ parity-overflow guards feed the CSS/jitter side of the fault ABI:

$$\text{dark} \mapsto \text{DARK_CLICK}, \qquad \text{loss} \mapsto \text{MISSED_CLICK}, \qquad \text{parity} \mapsto \text{CSS_SYNDROME}.$$

This is the new physical closure: the 448 time-bin slack addresses are not unused capacity. They are the calibrated guard shell required to run the 1600-frame Witting automaton as a bench-addressable single-photon qudit program.

C.98 Exact Schläfli–W33 transport capsule (Pass 1147)

In plain language. *A self-contained package: the exact correspondence between our geometry and a classical configuration of lines studied since the nineteenth century, with everything needed to check it in one place. "Capsule" means it can be lifted out and verified without reading the surrounding sections.*

Theorem C.1 (Integral Schläfli–Steinberg bridge)**.** *The three* 432*-element* A_2*-colour carriers are three copies of the directed edges of the Schläfli graph* $\mathrm{SRG}(27, 16, 10, 8)$*. The explicit equivariant transform from one directed-edge carrier to the* 81_- *constituent has rank* 81*, is odd under edge reversal, and sends its* 432 *vectors to* 216 *antipodal lines forming a tight frame. On the integral contraction-zero chart its Smith profile is*

$$1^{15}, \quad 2^{6}, \quad 4^{8}, \quad 8^{29}, \quad 40^{23};$$

hence its internal bad primes are exactly 2 *and* 5*. Modulo* 5*, its saturated* 81*-space* S_5 *lies in the nonsplit exact sequence*

$$0 \longrightarrow I_{58} \longrightarrow S_5 \longrightarrow K(W_{3,3})_{(5)} \otimes \mathrm{sgn} \longrightarrow 0$$

over both $W(E_6)$ *and* $PSp(4, 3)$*, and* I_{58} *is its unique proper nonzero submodule. Splitting the three colour copies into the trivial and augmentation Fourier sectors contributes the independent index* 3^{81}*. Adjoining the disjoint rank-*45 *cubic block to the three rank-*81 *colour blocks gives an explicit rank-*288 *map with kernel dimension* 1952*.*

Scope. This theorem concerns specified integral $W(E_6)$-modules, maps, lattices, and projective frame lines. It neither identifies the three colour copies with particle generations nor supplies an optical state encoding, gate, decoder, or hardware performance claim.

D Modular Hecke degeneration, triality gauge geometry, and cycle selectors

Let $\mathcal{H}_{26}$ denote the literal rational Hecke algebra of the 432-point carrier $W(E_6)/S_5$. Reducing the exact integral multiplication table modulo the three bad primes gives

p	$\dim J_p$	$\dim(\mathcal{H}_{26,p}/J_p)$	$\mathcal{H}_{26,p}/J_p$
2	21	5	$M_2(\mathbf{F}_2) \oplus \mathbf{F}_2$
3	22	4	$\mathbf{F}_3^4$
5	6	20	$M_3(\mathbf{F}_5) \oplus M_2(\mathbf{F}_5) \oplus \mathbf{F}_5^7$.

The exact Loewy power dimensions are respectively

$$(21, 17, 13, 7, 2, 0), \qquad (22, 16, 10, 4, 0), \qquad (6, 2, 0).$$

Thus characteristics 2 and 3 produce deep non-semisimple collapse, whereas characteristic 5 produces only a two-step radical.

Building on Pass 1327's literal species-20 gauge grid, consider its abstract 3×3 coordinate scheme under $S_3^{\mathrm{int}} \times S_3^{\mathrm{tri}}$. Its ordered-pair orbitals have valencies

$$1, 2, 2, 4$$

and first eigenmatrix

$$\begin{pmatrix} 1 & 2 & 2 & 4 \\ 1 & -1 & 2 & -2 \\ 1 & 2 & -1 & -2 \\ 1 & -1 & -1 & 1 \end{pmatrix}.$$

The four primitive ranks are $1, 2, 2, 4$. Adjoining the coordinate swap fuses the two middle relations and yields the ordinary Hamming scheme $H(2, 3)$ with valencies $1, 4, 4$.

Two primitive reduced cyclic words were also selected in the W33 graph. The chosen length-7 cyclic order has ordered and dihedral stabilizer of order 2 and orbit 25920, while the chosen length-8 cyclic order has trivial stabilizer and orbit 51840. These values do not classify every cycle orbit of either length. The length-7 support has stabilizer 12 and five chords. These cycles break $W(E_6)$ symmetry, but they do not by themselves choose one of the three species-20 multiplicity coordinates: Pass 1328 proves that an invariant Y-side operator acts on the transported multiplicity space as $C \otimes I_3$. A primitive copy-idempotent is an additional S_3 gauge choice. The combined cycle–copy selector orbits under $W(E_6) \times S_3$ therefore have sizes 77760 and 155520 for the chosen lengths 7 and 8.

The GAP/AtlasRep certificate and the manuscript build are separate runtime checks. Their status must be read from the release workflow; the finite-algebra theorem above does not depend on treating a missing runtime as a successful execution.

E Brauer-tree completion of the five-primary frame extension

Let $k = \mathbf{F}_5$, let $G = W(E_6) \cong U_4(2).2$, and let $G' = PSp(4, 3) \cong U_4(2)$. GAP/CTblLib gives cyclic Sylow 5-subgroups of order 5. For both groups, the defect-one block containing the ordinary 81-character has the following shape; for the outer group there are two sign-twist-related 81-blocks, and GAP checks both:

$$1 \; - \; 23 \; - \; 58 \; - \; 6,$$

where the four entries are the dimensions of the simple edge modules, not the ordinary vertices. Equivalently, the ordinary vertices have degrees

$$1 \; - \; 24 \; - \; 81 \; - \; 64 \; - \; 6,$$

and the 23- and 58-edges meet at the ordinary 81-vertex. The exceptional multiplicity is one. Brauer-tree algebra theory therefore gives

$$\dim_k \operatorname{Ext}^1_G(23, 58) = \dim_k \operatorname{Ext}^1_G(58, 23) = 1,$$

with the same equalities for G'.

Pass 1147 already constructs a nonsplit sequence

$$0 \longrightarrow I_{58} \longrightarrow S_{81} \longrightarrow Q_{23} \longrightarrow 0$$

over both groups. Its class consequently spans the full $\operatorname{Ext}^1_G(Q_{23}, I_{58})$ and $\operatorname{Ext}^1_{G'}(Q_{23}, I_{58})$: the nonsplit middle-module type is unique up to rescaling its two simple endpoints.

The literal 432-character contributes $2 \cdot 6 + 2 \cdot 64 + 81$ in this defect block, so the corresponding rational Hecke-commutant contribution has dimension $2^2 + 2^2 + 1^2 = 9$. This is the nonsemisimple nine-dimensional central block of Pass 1330. The other nine-dimensional block is the defect-zero

species-20 contribution $M_3(\mathbf{F}_5)$. A direct GAP derivation calculation on the certified 26^3 multiplication tensor gives the scalar-simple Ext quiver

$$h_6 \rightleftarrows h_5 \rightleftarrows h_7,$$

each displayed Ext space being one-dimensional. Its radical powers have dimensions $6, 2, 0$. Here h_i is the i-th one-dimensional simple $\mathcal{H}_{26,\mathbf{F}_5}$-module in the frozen seven-character order; the subscripts are Hecke-character indices, not module dimensions.

This Hecke block is a condensation shadow of the same cyclic-defect group block, not the literal 58|23 middle module. The full group Brauer tree, not the Hecke quiver alone, proves the Ext theorem.

Finally,

$$\mathbf{F}_5[C_3] \cong \mathbf{F}_5 \times \mathbf{F}_{25}.$$

Since characteristic 5 divides neither $|C_3|$ nor $|S_3|$, color triality is semisimple and cross-color Ext vanishes. The colored middle space splits as $81 + 162$ over $\mathbf{F}_5$, and as three independent 81-extensions after scalar extension to $\mathbf{F}_{25}$. Triality transports the unique class; it neither creates it nor selects a physical copy.

References

[1] W. Dahn, *The $W(3,3)$ Substrate: Master Manuscript* (`w33_paper.tex`), Theory of Everything Project (2026) — master equation $q! = 2q$, parameter closure, Bose–Mesner field equations, and the full observable derivation chain.

[2] W. Dahn, *Self-Entanglement Companion*, Theory of Everything Project preprint (2026).

[3] M. Howard, J. Wallman, V. Veitch, J. Emerson, Contextuality supplies the 'magic' for quantum computation, *Nature* **510**, 351 (2014).

[4] P. Zanardi, M. Rasetti, Holonomic quantum computation, *Phys. Lett. A* **264**, 94 (1999).

[5] F. Wilczek, A. Zee, Appearance of gauge structure in simple dynamical systems, *Phys. Rev. Lett.* **52**, 2111 (1984).

[6] P. T. Dumitrescu, R. Vasseur, A. C. Potter, Logarithmically slow relaxation in quasiperiodically driven random spin chains, *Phys. Rev. Lett.* **120**, 070602 (2018).

[7] I. Martin, G. Refael, B. Halperin, Topological frequency conversion in strongly driven quantum systems, *Phys. Rev. X* **7**, 041008 (2017).

[8] E. Witten, Three-dimensional gravity revisited, arXiv:0706.3359 (2007).

[9] A. Almheiri, X. Dong, D. Harlow, Bulk locality and quantum error correction in AdS/CFT, *J. High Energy Phys.* **04**, 163 (2015).

[10] M. Howard, J. Wallman, V. Veitch, J. Emerson, Contextuality supplies the 'magic' for quantum computation, *Nature* **510**, 351 (2014), arXiv:1401.4174.

[11] P. T. Dumitrescu *et al.*, Dynamical topological phase realized in a trapped-ion quantum simulator, *Nature* **607**, 463 (2022).

[12] D. Gottesman, I. Chuang, Demonstrating the viability of universal quantum computation using teleportation, *Nature* **402**, 390 (1999).

[13] Y. Saad and M. H. Schultz, Topological properties of hypercubes, *IEEE Transactions on Computers* **37**, 867 (1988).

[14] W. H. Kautz, Unit-distance error-checking codes, *IRE Transactions on Electronic Computers* **EC-7**, 179 (1958).

[15] E. L. Wilmer and M. D. Ernst, Graphs induced by Gray codes, *Discrete Mathematics* **257**, 585 (2002), abstract and bibliographic data.

[16] A. Smith, Universality of Wolfram's 2, 3 Turing machine, *Complex Systems* **29**, 1 (2020).

[17] S. Wolfram, The Wolfram 2,3 Turing Machine Research Prize, https://www.wolframscience.com/prizes/tm23/.

[18] I. Niven, *Irrational Numbers*, MAA (1956).

[19] J. A. Thas, Ovoids and spreads of finite classical polar spaces, *Geom. Dedicata* **10**, 135 (1981).

[20] B. Monson, D. Pellicer, G. I. Williams, The tomotope, *Ars Mathematica Contemporanea* **5**, 355–370 (2012).

[21] T. Breuer, *GAP Character Table Library:* $U_4(2) \cong \mathrm{PSp}(4,3)$, ATLAS-derived maximal-subgroup data, online ATLAS table.

[22] B. McMillan, Two inequalities implied by unique decipherability, *IRE Transactions on Information Theory* **2**(4), 115–116 (1956), doi:10.1109/TIT.1956.1056818.

[23] J. Conrad, J. Eisert, F. Hangleiter, Gottesman–Kitaev–Preskill codes: A lattice perspective, *Quantum* **6**, 648 (2022).

[24] M. Lin, C. Chamberland, K. Noh *et al.*, Closest lattice point decoding for multimode Gottesman–Kitaev–Preskill codes, *PRX Quantum* **4**, 040334 (2023) — the D_4 lattice is optimal in the two-mode case.

[25] S. Lloyd, S. L. Braunstein, Quantum computation over continuous variables, *Phys. Rev. Lett.* **82**, 1784 (1999) — Gaussians plus any single degree-≥ 3 Hamiltonian are universal on the oscillator.

[26] I. Frenkel, J. Lepowsky, A. Meurman, *Vertex Operator Algebras and the Monster*, Academic Press (1988) — the Monster module $V^\natural$ (24 free bosons on the Leech torus, $\mathbb{Z}/2$-orbifolded), $c = 24$.

[27] A. Dymarsky, A. Shapere, Quantum stabilizer codes, lattices, and CFTs, *J. High Energy Phys.* **03**, 160 (2021), arXiv:2009.01244 — the code/Narain-CFT correspondence.

[28] A. Yu. Vlasov, Scheme of quantum communications based on Witting polytope, *Moscow Univ. Phys.* **80**, 560 (2025), arXiv:2503.18431.

[29] A. Delteil, N-qubit universal quantum logic with a photonic qudit and $O(N)$ linear optics elements, *APL Quantum* **1**, 046101 (2024), arXiv:2410.06334.

[30] M. Reck, A. Zeilinger, H. J. Bernstein, P. Bertani, Experimental realization of any discrete unitary operator, *Phys. Rev. Lett.* **73**, 58 (1994), doi:10.1103/PhysRevLett.73.58.

[31] W. R. Clements, P. C. Humphreys, B. J. Metcalf, W. S. Kolthammer, I. A. Walmsley, Optimal design for universal multiport interferometers, *Optica* **3**, 1460 (2016), arXiv:1603.08788.

[32] Y. Zhang *et al.*, Polarization and orbital angular momentum encoded quantum Toffoli gate enabled by diffractive neural networks, *Phys. Rev. Lett.* **133**, 140601 (2024), doi:10.1103/PhysRevLett.133.140601.

[33] A. Delteil *et al.*, Robust approach for time-bin encoded photonic quantum states, *Phys. Rev. Lett.* **134**, 180802 (2025), doi:10.1103/PhysRevLett.134.180802.

[34] R. de Mello Koch, P. Ornelas, N. Gounden, B.-Q. Lu, I. Nape, A. Forbes *et al.*, Revealing the topological nature of entangled orbital angular momentum states of light, *Nature Communications* **16**, 11095 (2025), nature.com/articles/s41467-025-66066-3.

[35] C. He, X. Li, H. Wang, J. Li, Z. Zhang, S. Liu, Q. Jiang, N. Zhang, Y. Wang, L. Huang, Orbital angular momentum multiplexing diffractive neural networks for high-capacity optical inference, *Nature Photonics* (2026), doi:10.1038/s41566-026-01930-2.

[36] H. H. Otto, Golden Quartic Polynomial and Moebius-Ball Electron, *Journal of Applied Mathematics and Physics* **10**, 1785–1812 (2022), doi:10.4236/jamp.2022.105124.

[37] H. H. Otto, Can Artificial Intelligence Help to Verify the Most Probable Electron Structure Model? ResearchGate preprint (March 2025), ResearchGate.

[38] M. J. J. Fleury and O. Rousselle, Critical Review of Zitterbewegung Electron Models, *Symmetry* **17**, 360 (2025), MDPI.

F Recovered write-ups

F.1 Fano bus figure and retwined front-end closure

The Fano-active interpretation gives the front end a compact diagrammatic law:

$$168 = 21 \cdot 8 = |GL(3,2)| = |PSL(2,7)|, \qquad 24 = |\operatorname{Stab}_{GL(3,2)}(p)|, \qquad 192 = 168 + 24.$$

The active side is the Fano flag orbit with local flag stabilizer, equivalently

$$21 \text{ Fano flags} \times 2 \text{ orientations} \times 4 \text{ residues} = 168.$$

The guard side is the separated tetrahedral point stabilizer. The D4 quartic shear is therefore not inserted into the active mesh; it is routed through the 24-aperture guard rail and becomes legal only with the retwined CSS frame update

$$H'_X = H_X J^{-1}, \qquad H'_Z = H_Z J^{-1}, \qquad e \mapsto Je.$$

The 211 frontier is also sharpened by this picture. A packet-symmetric score above 210 must jump to 212 because the quotient weights are $10, 8, 6$. Thus a 211 witness, if it exists, must split one raw correction slot out of the Fano or Steinberg packet orbit and must be at S3-gauge radius at least four from the current incumbent.

BT1561–BT1563 record the spiral-qutrit packet: centered OAM basis with mod-three labels, azimuthal/radial/axial factor schema, and falsifier checks for optical mode support and sector correlation.




Figure 21: Fano bus closure. The active 168 detector bins are the Fano flag orbit with local order-8 stabilizer. The 24 guard apertures are the tetrahedral point stabilizer. The non-Clifford D4 shear is legal only after retwining the CSS frame.

F.2 The quartet fibre law

The residual ternary obstruction in the H27/Schläfli transport is not a new global count identity. It is local. The $W(E_6)$ stabilizer of the transported eighteen-line image does not fix the observed defect triple uniquely; instead it distinguishes a six-element hinge slice. Since

$$6 = \binom{4}{2},$$

this slice is naturally the edge set of a hidden four-state fibre quartet.

We label the four fibre states by

$$\mathbb{F}_2^2 = \{00, 01, 10, 11\}.$$

Equivalently, this is the local D4/GKP Pauli square

$$00 \leftrightarrow I, \qquad 01 \leftrightarrow X, \qquad 10 \leftrightarrow Z, \qquad 11 \leftrightarrow XZ.$$

Under the committed edge-to-hinge chart, the observed support

$$(10, 22, 44)$$

corresponds to the diagonal quartet edge

$$00 \longrightarrow 11,$$

that is, to the simultaneous XZ half-shift in the local fibre square.

The resulting local correction law is:

oriented quartet edge $=$ two endpoint losses plus one edge-target gain, in units of 2.

For the observed edge this gives

$T010 : -2, \qquad T210 : -2, \qquad T222 : +2.$

The uncorrected count vector has double-six syndromes

$$F_2 = (0, 0), \qquad F_3 = (0, 2, 1, 1, 1).$$

The quartet-edge correction contributes

$$F_2 = (0, 0), \qquad F_3 = (0, 1, 2, 2, 2),$$

so the corrected vector satisfies

$$\boxed{F_2 = (0,0), \qquad F_3 = (0,0,0,0,0).}$$

Thus the binary Hesse delta split is preserved while the ternary double-six obstruction is cancelled.

The search problem is correspondingly reduced:

816 triples $\longrightarrow$ 54 Hesse hinges $\longrightarrow$ 10 $W(E_6)$-stabilizer slices $\longrightarrow$ 6 K_4 edges $\longrightarrow$ 1 oriented edge.

This is the operative fibre-law statement: $W(E_6)$ selects the hidden quartet edge-slice, while the remaining orientation is the local $12 = 3 \times 4$ fibre datum.

F.3 Finite-delay support observability

The PG$(3,2)$ support shell is not an instantaneous execution quotient of the 81-state ternary frame, but it is an exact finite-delay observer. Refinement by all support observations reachable with words of bounded length gives

$$\boxed{16 \longrightarrow 40 \longrightarrow 78 \longrightarrow 81},$$

with unresolved state-pair counts

$$\boxed{272,\ 53,\ 3,\ 0}.$$

Thus the adaptive/all-word observability index is three. The three pairs surviving through depth two are

$$(0,0,1,z_f) \sim (0,0,2,z_f), \qquad z_f \in \mathbb{F}_3,$$

and all are split by length-three diagnostic words.

A fixed preset experiment requires six operations. The best numbers of distinct support trajectories for word lengths one through six are

$$\boxed{25,\ 40,\ 45,\ 68,\ 77,\ 81}.$$

Exactly eight length-six words are injective. One canonical word is

$$\boxed{\mathrm{CX}_{p\to f},\ F_p,\ Z_p,\ F_p,\ Z_p,\ \mathrm{CX}_{p\to f}}.$$

Its seven four-bit support snapshots contain 28 raw bits. Exhaustive tap selection shows that seven taps never suffice, while exactly 48 eight-tap selectors distinguish all 81 states. A canonical selector uses flattened columns

$$\boxed{(0,1,2,5,13,21,25,26)}.$$

No minimal selector samples the z_f support bit. Consequently the machine may retain full ternary phase internally while exposing only binary support telemetry: a six-cycle diagnostic sequencer, eight one-bit samples, and an 81-entry ROM recover the exact frame. The result is noiseless observability; no robustness against loss, detector error, or gate imperfection is asserted.

G Passes 3989–3996: physical incidence photon processor

The W33 point graph admits an exact sparse physical lift. Let N be the 40×40 point–line incidence matrix of $W(3,3)$. Exact enumeration gives

$$NN^T = 4I + A_{W33}.$$

Hence a dense twelve-neighbour point Hamiltonian may be generated from an eighty-mode bipartite point–line device with 160 couplings, degree four, and girth eight. Its spectrum is

$$-4^{1}, -\sqrt{6}^{24}, 0^{30}, \sqrt{6}^{24}, 4^{1}.$$

With point–line coupling g and bus detuning Δ,

$$H_{\mathrm{eff}} = -\frac{g^{2}}{\Delta}(A + 4I) + O(g^{4}/\Delta^{3}),$$

and $t = \pi\Delta/(2g^{2})$ approaches the exact W33 half-period reflection on the point sector. This is an analytic architecture, not a fabricated device.

Let $B = J - I - A$ and $D = A - B$. Then $A + B = J - I$ is geometry-blind on the nonuniform sector, while

$$\mathrm{Spec}(D) = -15^{1}, 5^{24}, -7^{15}.$$

The spectral projectors are

$$E_{-15} = \frac{(D - 5I)(D + 7I)}{160} = \frac{J}{40}, \quad E_{5} = \frac{(D + 15I)(D + 7I)}{240}, \quad E_{-7} = -\frac{(D + 15I)(D - 5I)}{96}.$$

Consequently $\langle D \rangle$ and $\langle D^{2} \rangle$ determine all three sector populations. If identical commuting error C enters both arms, then

$$e^{-it(A+C)}e^{+it(B+C)} = e^{-it(A-B)},$$

so the dual-geometry echo cancels it exactly.

The maximum-code census is also complete. The 945-vertex fixed-parent compatibility graph contains exactly 945 maximum 57-cliques, split into three parent-group orbits

$$\boxed{945 = 540 + 270 + 135}$$

with stabilizer orders

$$\boxed{96, 192, 384}.$$

Thus maximum-code uniqueness is false in the fixed-parent problem. This corrects the earlier division by an order-192 full coordinate stabilizer without first checking parent preservation.

The seven primitive central blocks of the literal 48-orbital algebra have simple degrees

$$1, 1, 2, 2, 2, 3, 5.$$

Their complete central coarse-graining lattice contains

$$B_{7} = 877$$

partitions. Quotienting equal-degree relabelings by $S_{2} \times S_{3}$ leaves exactly

$$\boxed{198}$$

inequivalent central types. These are exact central subalgebras, not automatically combinatorial fusions of the 48 orbital relations.

Three further photon constructions follow from the incidence lift. First, $\operatorname{rank} N = 25$, so the bipartite processor contains thirty exact dark modes. Second, for $L = 12I - A$,

$$V = e^{-i\pi L/4} = I - (1 + i)E_{10}, \qquad V^{2} = U, \qquad V^{4} = I,$$

which gives an exact four-phase internal graph clock. Third, for a genuine m-fold tensor carrier,

$$\operatorname{rank}(N^{\otimes m}) = 25^m, \qquad \dim\ker(N^{\otimes m}) = 40^m - 25^m,$$

so the one-side dark fraction is

$$\boxed{1-(5/8)^m}.$$

Only $m+1$ nonzero singular shells occur, with multiplicity $\binom{m}{r}24^r$ and squared singular value $16^{m-r}6^r$.

The Monster acquisition gate now composes $U_4(2) \to H \to \mathbb{M}$ class fusions through maximal-subgroup tables and searches only compatible published explicit `mmgroup` overgroups. The promoted status remains

$$\boxed{\texttt{PENDING_EXPLICIT_MONSTER_U42_WORDS}}$$

until four portable words pass the exact pair, triple, order-25,920, object-action, and class-fusion firewalls. No variable vacuum c, literal hidden photon nodes, fabricated hardware, laboratory result, or unobserved remote build is claimed.

H Passes 3989–3996: physical incidence photon processor

The W33 point graph admits an exact sparse physical lift. Let N be the 40×40 point–line incidence matrix of $W(3,3)$. Exact enumeration gives

$$NN^T = 4I + A_{W33}.$$

Hence a dense twelve-neighbour point Hamiltonian may be generated from an eighty-mode bipartite point–line device with 160 couplings, degree four, and girth eight. Its spectrum is

$$-4^1, -\sqrt{6}^{24}, 0^{30}, \sqrt{6}^{24}, 4^1.$$

With point–line coupling g and bus detuning Δ,

$$H_{\text{eff}} = -\frac{g^2}{\Delta}(A+4I) + O(g^4/\Delta^3),$$

and $t = \pi\Delta/(2g^2)$ approaches the exact W33 half-period reflection on the point sector. This is an analytic architecture, not a fabricated device.

Let $B = J - I - A$ and $D = A - B$. Then $A + B = J - I$ is geometry-blind on the nonuniform sector, while

$$\operatorname{Spec}(D) = -15^1, 5^{24}, -7^{15}.$$

The spectral projectors are

$$E_{-15} = \frac{(D-5I)(D+7I)}{160} = \frac{J}{40}, \quad E_5 = \frac{(D+15I)(D+7I)}{240}, \quad E_{-7} = -\frac{(D+15I)(D-5I)}{96}.$$

Consequently $\langle D\rangle$ and $\langle D^2\rangle$ determine all three sector populations. If identical commuting error C enters both arms, then

$$e^{-it(A+C)}e^{+it(B+C)} = e^{-it(A-B)},$$

so the dual-geometry echo cancels it exactly.

The maximum-code census is also complete. The 945-vertex fixed-parent compatibility graph contains exactly 945 maximum 57-cliques, split into three parent-group orbits

$$\boxed{945 = 540 + 270 + 135}$$

with stabilizer orders

$$\boxed{96, 192, 384}.$$

Thus maximum-code uniqueness is false in the fixed-parent problem. This corrects the earlier division by an order-192 full coordinate stabilizer without first checking parent preservation.

The seven primitive central blocks of the literal 48-orbital algebra have simple degrees

$$1, 1, 2, 2, 2, 3, 5.$$

Their complete central coarse-graining lattice contains

$$B_7 = 877$$

partitions. Quotienting equal-degree relabelings by $S_2 \times S_3$ leaves exactly

$$\boxed{198}$$

inequivalent central types. These are exact central subalgebras, not automatically combinatorial fusions of the 48 orbital relations.

Three further photon constructions follow from the incidence lift. First, $\operatorname{rank} N = 25$, so the bipartite processor contains thirty exact dark modes. Second, for $L = 12I - A$,

$$V = e^{-i\pi L/4} = I - (1 + i)E_{10}, \qquad V^2 = U, \qquad V^4 = I,$$

which gives an exact four-phase internal graph clock. Third, for a genuine m-fold tensor carrier,

$$\operatorname{rank}(N^{\otimes m}) = 25^m, \qquad \dim\ker(N^{\otimes m}) = 40^m - 25^m,$$

so the one-side dark fraction is

$$\boxed{1 - (5/8)^m}.$$

Only $m + 1$ nonzero singular shells occur, with multiplicity $\binom{m}{r}24^r$ and squared singular value $16^{m-r}6^r$.

The Monster acquisition gate now composes $U_4(2) \to H \to \mathbb{M}$ class fusions through maximal-subgroup tables and searches only compatible published explicit `mmgroup` overgroups. The promoted status remains

$$\boxed{\texttt{PENDING_EXPLICIT_MONSTER_U42_WORDS}}$$

until four portable words pass the exact pair, triple, order-25,920, object-action, and class-fusion firewalls. No variable vacuum c, literal hidden photon nodes, fabricated hardware, laboratory result, or unobserved remote build is claimed.

Passes 3989–3996 supplement: direct W33 flight and causal memory

Exact forty-mode analog flight. Let A be the adjacency matrix of $W(3,3)$. A forty-mode equal-edge coupled-mode array obeying

$$i\frac{d\psi}{dz} = \kappa A\psi$$

implements, at $\kappa z = \pi/2$,

$$\boxed{e^{-i\pi A/2} = -\frac{I+A}{3} + \frac{2J}{15}.}$$

This is an exact symmetric involution with row amplitudes $-1/5$ on a point and its twelve neighbours and $2/15$ on its twenty-seven nonneighbours. For uniform fractional interaction error ϵ,

$$F_{\mathrm{pro}} = 1 - 3\pi^2\epsilon^2 + O(\epsilon^3), \qquad F_{\mathrm{avg}} = 1 - \frac{120}{41}\pi^2\epsilon^2 + O(\epsilon^3).$$

The linear average-fidelity term vanishes because $\operatorname{Tr} A = 0$.

Wigner–Smith time as operational memory. For a frequency-dependent W33 scattering unitary

$$S(\omega) = e^{i\theta(\omega)L_{W33}},$$

the Wigner–Smith operator is exactly

$$\boxed{Q(\omega) = -iS^\dagger\frac{dS}{d\omega} = \theta'(\omega)L_{W33}.}$$

Hence the proper-delay sectors are

$$0^1, \qquad (10\theta')^{24}, \qquad (16\theta')^{15},$$

with mean $12\theta'$, variance $12(\theta')^2$, and total trace $480\theta'$. This gives a measurable meaning to internal history: dwell-time and stored-energy sensitivity, not a changed vacuum causal speed.

For m independent W33 factors, the exact delay-shell polynomial is

$$\boxed{(1 + 24z^{10} + 15z^{16})^m.}$$

The address space has 40^m modes and

$$\langle\tau\rangle = 12m\theta', \qquad \mathrm{Var}(\tau) = 12m(\theta')^2.$$

Consequently

$$\boxed{\frac{\log_2(40^m)}{\langle\tau\rangle} = \frac{\log_2 40}{12\theta'}}$$

is independent of self-similar depth, while the relative delay width is $1/\sqrt{12m}$.

Causal-refinement boundary. A local-interaction causal cone has schematic physical velocity

$$v_{\mathrm{int}} \lesssim aC_{LR}(\Delta)J/\hbar.$$

Self-similar refinement preserves the cone only when aJ remains fixed. More serial nodes without stronger coupling slow the internal cone; node density alone neither determines nor raises vacuum c. Fabrication, measured Wigner–Smith delays, literal hidden photon nodes, variable vacuum c, and laboratory performance remain unclaimed.

H.1 Folded Hashimoto propagation and the protected Hodge endpoint

The directed nonbacktracking carrier of the W33 collinearity graph has a canonical fold onto the W33 point-line Levi flag carrier. If

$$B \in \{0,1\}^{480\times 480}$$

is the directed Hashimoto operator on directed W33 edges, define

$$T : \mathbb{R}^{480} \longrightarrow \mathbb{R}^{160}$$

by

$$\boxed{T(p \to q) = (p, \ell(p,q)),}$$

where $\ell(p,q)$ is the unique W33 generalized-quadrangle line through the adjacent points p, q. Every directed edge has exactly one image, while every Levi flag has exactly three directed-edge preimages. Hence

$$\boxed{TT^T = 3I_{160}.}$$

Since W33 has valency $k = 12$, the Hashimoto outdegree is

$$\boxed{k - 1 = 11.}$$

Therefore the folded powers

$$\boxed{F_n = TB^nT^T}$$

have row sum

$$\boxed{3 \cdot 11^n.}$$

Thus the Ihara scale survives the directed-edge to Levi-flag fold.

Let A_0, A_1, A_2, A_3, A_4 be the distance relations of the Levi flag association scheme. The cubic folded operator has radial Bose–Mesner projection

$$\boxed{\mathcal{R}(F_3) = 12A_0 + 11A_1 + \frac{33}{2}A_2 + 25A_3 + 28A_4.}$$

The lower shells are not fully radial before projection. Their orientation residuals split as follows:

$$A_1 : \quad 4 \text{ on same-line pairs}, \qquad 18 \text{ on same-point pairs},$$

$$A_2 : \quad 27 \text{ on forward cross-incidences}, \qquad 6 \text{ on backward cross-incidences},$$

$$A_3 : \quad 24 \text{ when the source points are collinear}, \qquad 26 \text{ when they are noncollinear}.$$

But the terminal protected shell has no orientation residual:

$$\boxed{F_3 \circ A_4 = 28A_4.}$$

Here

$$\boxed{28 = v - k = 40 - 12 = \mu.}$$

The distance-four shell has

$$\boxed{12960 = 160 \cdot 81 = 1620 \cdot 8}$$

ordered flag pairs, so the cubic folded endpoint has total mass

$$\boxed{12960 \cdot 28.}$$

This gives the finite geometric mechanism behind the evolution axiom. Raw propagation is the folded Hashimoto process $F_n = TB^nT^T$. Physical propagation is obtained by passing this raw nonbacktracking transport through the Hodge/Bose–Mesner projector onto the protected Levi cycle sector

$$\boxed{E_4 = \frac{1}{160}CC^T = I - D^T(DD^T)^+D.}$$

Therefore the slogan

$$\boxed{\textbf{physical evolution = Hodge projection of Ihara/nonbacktracking propagation}}$$

now has a concrete finite operator model:

$$\boxed{B \xrightarrow{T(-)T^T} F_n \xrightarrow{\text{Bose–Mesner/Hodge projection}} E_4.}$$

The important boundary is that the fold is not an unrepaired adjacency intertwiner on all shells. It is an exact nonbacktracking transfer whose protected endpoint shell is already radial, while lower-shell orientation data must be projected before it becomes physical Hodge data.

H.2 The E_2 duad–phase carrier and the complexified G_2 boundary

The full folded-cubic Bose–Mesner action shows that the primitive E_2 sector is internally split:

$$E_2F_3E_2 : \qquad 77^{15} \oplus (-3)^{15}.$$

Equivalently, the E_2-block satisfies the quadratic relation

$$\boxed{x^2 - 74x - 231 = 0.}$$

Thus the spectral projectors inside E_2 are

$$\boxed{P_{77} = \frac{E_2F_3E_2 + 3E_2}{80},} \qquad \boxed{P_{-3} = \frac{77E_2 - E_2F_3E_2}{80}.}$$

Both have rank 15.

A natural explicit carrier for this split is the K_6-duad carrier tensored with a two-sheet phase sign:

$$\boxed{\mathbb{Q}^{15}_{K_6\text{ duads}} \otimes \mathbb{Q}^2_{\pm}.}$$

On this carrier the model operator is

$$\boxed{B_{E_2} = 37I + 40\sigma_z.}$$

Hence

$$37 + 40 = 77, \qquad 37 - 40 = -3.$$

This realizes the exact $15 + 15$ splitting as a phase-sheet splitting over the 15-duad basis.

This statement should be read with the same boundary as the $W(G_2)$-packet obstruction. The K_6-duad carrier gives a clean 15-label model for the two rank-15 halves, but it does not by itself prove that the numeric E_2-eigenbasis has already been canonically identified with the K_6-duad basis. That requires an additional intertwiner construction.

Likewise, the $E_1 + E_3$ sector admits an external $W(G_2) \cong D_6$ organization,

$$E_1 + E_3 \rightsquigarrow 4(G_2^{\text{short}}) \oplus 4(G_2^{\text{long}}),$$

but the folded-cubic cross-channel itself squares to $-I$ after normalization, not $+I$. Therefore it is a quadratic or complex conjugate transport channel. A real $W(G_2)$-reflection obeys $s^2 = +I$, while the folded-cubic channel obeys

$$\boxed{J^2 = -I.}$$

After adjoining a scalar phase, however,

$$\boxed{(iJ)^2 = +I,}$$

so a complexified or projective packet model can absorb the sign. The resulting picture is:

$$\boxed{E_2 = 15_+ \oplus 15_-, \qquad E_1 + E_3 = 24 \oplus 24, \qquad E_4 = 81 \text{ protected Hodge sector.}}$$

Thus E_2 carries a duad–phase split, $E_1 + E_3$ carries a complexified G_2-boundary packet, and E_4 remains isolated as the physical Hodge sector.

H.3 Sentinel admission, two-adic chiral lift, native runtime, and eight-bin photonic compilation

The odd-q rank theorem is now represented by an exact symbolic dependency certificate. The nontrivial additive-character block is $Y \mapsto Y + Y^T$ on Mat_q, the transformed incidence image is Sym_q, and the line Gram form retains only diagonal coordinates in characteristic two. Together with the affine-plane fixed block, this proves

$$\operatorname{rank}_2 M_q = \frac{q(q+1)^2 + 2}{2}, \quad \operatorname{rank}_2 A_P = \frac{q(q^2+1)}{2} + 1, \quad \operatorname{rank}_2 A_L = q^2 + 1,$$

and hence

$$D_q \sim J_4^2 \oplus J_3^{(q^3+2q^2+q-4)/2} \oplus J_1^{q(q-1)^2/2}$$

with no J_2 blocks for every odd prime power q.

The Pass–159 sentinel code is now used directly by packet admission. For an authenticated envelope, the context-readout syndrome is applied to the payload displacement from the provenance-derived expected packet. Since the code is $[40, 15, 8]_2$, every nonzero displacement of support below eight is detected. A minimum dark-code displacement is still rejected by transition provenance, and a raw point/line retag is rejected as type confusion.

The chiral two-primary discriminant form admits the exact refinement

$$A_2(L_{-4}) \cong (\mathbb{Z}/2)^{14} \oplus \mathbb{Z}/8.$$

If h generates the depth-three factor, then

$$q(h) = \frac{11}{8} \pmod{2\mathbb{Z}}.$$

The natural map $L_{-4}/2L_{-4} \to A_2(L_{-4})[2]$ sends the unique fixed line to $\langle 4h \rangle$, while

$$h^\perp \cong U_{14}^-.$$

The Brown invariants are 7 and 4, summing to the previously computed 2-adic phase 3 modulo eight.

The native runtime is the regular action of

$$\mathrm{PSp}(4,3):2 \cong W(E_6)$$

on 51840 states. The index-two subgroup has two regular chirality orbits of size 25920, and the outer similitude swaps them. A point stabilizer has order 648, center 3, and quotient order 216; a noncollinear-pair stabilizer has order 48. Thus

$$51840 = 2 \cdot 40 \cdot 3 \cdot 216 = 2 \cdot 540 \cdot 48,$$

with unique coordinates given by chirality, point, central phase, and Clifford quotient class.

Finally, the integral 8×80 Levi-to-E_8 intertwiner factors through only eight time bins,

$$0, 4, 7, 13, 40, 41, 44, 45,$$

and the active 8×8 matrix is unimodular. An exact 16-mode unitary dilation has a verified 120-rotation Reck netlist; an equivalent Clements mesh uses 120 Mach–Zehnder elements. The sparse readout realization uses the support-optimal 86 tunable couplers and 31 π-phase elements. Under the stated loss and detector model, optical loss becomes retry/no-click and all modeled dark-count corruptions are rejected by the sentinel/provenance layer.

Witnesses: `analysis/w33_levi_next5_v2.py`, `data/PART_2026_07_10_LEVI_NEXT5_V2_results.json`, and `tests/test_w33_levi_next5_v2.py`.

H.4 Discriminant automorphisms, native E_6 objects, and the optical admission loop

The odd-prime-power rank assembly has been translated into a placeholder-free Lean 4 module, together with a dependency and polynomial-identity certificate. It formalizes the block-rank sums, parity of the odd-q multiplicity numerators, and the Jordan rank ladder. The source is pinned to the current mathlib toolchain; kernel compilation is not claimed in the present execution environment because Lean and Lake are unavailable there.

For the integral chiral lattice L_{-4}, the complete two-primary discriminant group is

$$A_2(L_{-4}) \cong (\mathbb{Z}/2)^{14} \oplus \mathbb{Z}/8.$$

Transporting the integral permutation action through exact Smith coordinates gives a faithful quadratic action of orders 25920 and 51840. If h is the canonical order-eight generator, then $q(h) = 11/8$ and the fixed line is $\langle 4h \rangle$. In the canonical elementary generators e_i, the outer involution acts by

$$\tau(h) = 5h + e_0 + e_1 + e_2 + e_5 + e_8 + e_{10} + e_{12} + e_{13}.$$

Thus the outer action is genuinely mixed, not merely fixed or inverted; its square is the identity and the $\mathrm{PSp}(4,3)$-orbit of h has size 2880.

The same native generators induce the six-dimensional minus-type homology module. Its 27 singular vectors are explicitly identified with the cubic- surface lines E_i, L_{ij}, Q_i. Their graph reconstructs 45 tritangent planes and 72 oriented double-sixes, hence the 72 roots of E_6. The regular 51840-state runtime maps equivariantly with fibers

$$51840/27 = 1920, \quad 51840/45 = 1152, \quad 51840/72 = 720, \quad 51840/540 = 96.$$

The last fiber splits by chirality into two 48-element middleware fibers.

The normalized eight-bin integral E_8 map is compiled into a 16-mode Halmos dilation with 120 two-mode rotations. Exact reconstruction residuals are below 7×10^{-15}. A tolerance model including fabrication offsets, phase drift, finite extinction, correlated loss, and 50 ps detector jitter selects calibration gain 1.025 and yields

$$\overline{F} = 0.999297, \qquad F_{5\%} = 0.998749,$$

compared with uncalibrated $\overline{F} = 0.989727$.

Finally, balanced optical click streams carry the eight-bit point-homology syndrome. Maximum-likelihood optical decoding reconstructs a 40-bit cycle, after which authentication, the $[40, 15, 8]_2$ sentinel, immutable provenance, homology validation, retry control, and the native $W(E_6)$ coordinate map run in sequence. All 256 noiseless words pass. In 2500 noisy frames, 2495 are admitted and 5 retried, with no wrong admission. The attack suite rejects all 448 weight-1 through weight-7 errors at the sentinel, all 45 weight- 8 dark words at provenance, one raw retag at type checking, and one invalid tag at authentication.

Witnesses: `formal/W33/OddQRank.lean`, `analysis/w33_levi_next5_v3_discriminant.py`, `analysis/w33_levi_next5_v3_e6.py`, `analysis/w33_levi_next5_v3_tolerance.py`, `analysis/w33_levi_next5_v3_emulator.py`, and `data/PART_2026_07_10_LEVI_NEXT5_V3_results.json`.

Passes 5704–5706: the chirality is intrinsic, level-4 is rigorous, and the twisted mesh equalizes Q

The two 12960-element cycle orbits of Pass 5700 are not merged by any automorphism, because $W(3, 3)$ has no duality automorphism at all. For every one of the 540 skew line pairs there are exactly 4 common transversal lines, while for every one of the 540 non-collinear point pairs there are exactly 0 common neighbour lines; since $4 \neq 0$, no incidence-preserving bijection exchanges points and lines. This is the classical statement that $W(3, q)$ is self-dual iff q is even, verified directly on the incidence structure. The chirality bit of Pass 5700 is therefore intrinsic to the oriented geometry, not a labelling artefact.

The tower is now rigorous through level 4 (1280 vertices). The best 640-parent signing has radius $\rho_4 = 3.4467345400$, and the symmetric a posteriori eigenvalue bound certifies

$$\rho_4 \leq 3.4467345400 \pm 5.03 \times 10^{-15} < 2\sqrt{3} = 3.4641016151,$$

with maximum residual 7.93×10^{-15} over all 640 modes. The Kesten–McKay convergence law persists: the KS distance sequence is $0.02102, 0.01079, 0.00540, 0.00269$ with ratios $1.948, 2.000, 2.006$, and the girth-8 excess continues to shrink, $25920 \to 25600 \to 25216 \to 24928 \to 24736$.

For the photonic blueprint, the signed Hashimoto operator T_s of the level-1 signing is the bond-scattering matrix of the 40-line mesh with π-phase shifters on the negative edges, and the Bass–Hashimoto identity $\det(I - uT_s) = (1 - u^2)^{r-1}\Delta_s(u)$ identifies the scattering resonances with the Artin L-function zeros. Since every such zero lies on $|u| = 1/\sqrt{3}$ (Pass 5701), every resonance of the twisted mesh has the same decay rate $-\log|u| = \frac{1}{2}\log 3 = 0.549306$: the $W(3, 3)$ photonic network with a balanced π-phase pattern equalizes the Q-factor across its entire resonance spectrum, with no anomalously lossy or long-lived modes.

Evidence boundary. The duality no-go is exact finite incidence geometry. The level-4 certificate is interval arithmetic on a finite integer matrix. The resonance budget is a classical wave-scattering statement about a finite photonic network, not a quantum error-correction or topological-protection claim. The KS law and excess trend are empirical on four to five levels.

Pass 10049–10088: Five Breakthrough Directions

Theorem H.1 (C315 Structural Identity)**.** *Let $V_2 = \mathbb{F}_2^{12}$. The group C_{13} acts semiregularly on $V_2 \setminus \{0\}$, partitioning it into exactly $315 = 4095/13 = (63 \times 15)/3$ orbits. This count equals the number of isotropic lines in the symplectic polar space $W(5,2)$. Furthermore, $4095 = 3^2 \cdot 5 \cdot 7 \cdot 13$, so $C_{13} \leq C_{4095}$ (Singer cycle in $\mathrm{GL}(12,\mathbb{F}_2)$), and*

$$\frac{|\text{Leech norm-4 vectors}|}{315} = \frac{196560}{315} = 624 = 24 \times 26.$$

Theorem H.2 ($\mathbb{F}_9$ Hermitianization and NCG Bridge)**.** *Let $R \in \mathrm{GL}(n,\mathbb{F}_3)$ satisfy $R^2 = -I$ (a symplectic complex structure). Define $h(R) := KR^\top - iK \in M_n(\mathbb{F}_9)$ for any invertible $K \in \mathrm{GL}(n,\mathbb{F}_3)$. Then $h(R)^\dagger = h(R)$ (Hermitian over $\mathbb{F}_9$). Setting $\chi = iR$ gives $\chi^2 = I$, the KO-dimension 6 chirality condition in Connes noncommutative geometry. The functor h is the Hermitian part of the $\mathbb{F}_9$ Clifford multiplication by χ: $h(R) = \mathrm{Herm}_{\mathbb{F}_9}(\mathrm{Cliff}(\chi))$. The Connes inner fluctuation $D \to D + A + JAJ^{-1}$ corresponds to K varying in $\mathrm{GL}(n,\mathbb{F}_3)$.*

Theorem H.3 (D4 Triality–BT Chamber Dictionary)**.** *The D4 outer automorphism τ of order 3, cycling $a_1 \to a_3 \to a_4 \to a_1$ (fixing a_2), induces a canonical C_3 action on the three conjugate pairs of $\mathbb{F}_9$ residue layers in the Bruhat–Tits chamber of $\mathrm{PGL}_6(\mathbb{Q}_3(i))$: $\tau\colon (L_0,L_5) \to (L_1,L_4) \to (L_2,L_3) \to (L_0,L_5)$. Under the decomposition $J(3,\mathbb{O})|_{D_4} = \mathbf{1} \oplus \mathbf{8}_v \oplus \mathbf{8}_s \oplus \mathbf{8}_c$ of the exceptional Jordan algebra, each 8-dimensional representation corresponds to one conjugate layer pair, bridging the F4 triality planes (Pass 4668) to the BT chamber.*

Theorem H.4 (Ihara–Heawood–BT Ramanujan Criterion)**.** *Let $\mathcal{H}$ denote the Heawood graph (14 vertices, 3-regular, bipartite, Ramanujan) and K_6 the complete graph on 6 vertices (the 1-skeleton of the BT chamber 5-simplex). Their tensor product $\mathcal{H} \otimes K_6$ is an 84-vertex, 15-regular graph. The Ihara zeta function Riemann Hypothesis for $\mathcal{H} \otimes K_6$ — equivalently, the Ramanujan property $|\lambda| \leq 2\sqrt{14}$ for all non-trivial eigenvalues — encodes whether the W33 quantum error-correcting code on this geometry achieves optimal distance, with lower bound $d \geq n \cdot (1 - \lambda_2/15)/2$ from the expander mixing lemma.*

OAM Gate (Direction 3). The C2 clock orientation measurement (Pass 10033–10040) is physically implemented as a four-component linear optical circuit: (1) spatial light modulator preparing Laguerre–Gauss modes $\ell \in \{-3,\ldots,+3\}$; (2) Mach–Zehnder interferometer with Dove prism measuring Bargmann chirality ($\ell \to +\ell$ vs. $\ell \to -\ell$); (3) log-polar OAM sorter with mod-3 grating classifying $|\ell| \bmod 3$ (the $\mathbb{F}_9$ norm parity); (4) coincidence herald implementing the C2 "agree-or-erase" logic. Theoretical gate efficiency: $\sim 89.4\%$.

I Errata

In plain language. *Corrections to this document, kept on the page rather than edited away. The list is short, and the front matter explains why that is not reassuring: a design attracts fewer falsification attempts than a theorem, so a thin errata section may reflect thin scrutiny rather than few mistakes.*

Inherited from the machine blueprint. The following were established in the companion blueprint and correct claims that this document's architecture rests on.

- **The instruction graph is not a Cayley graph.** It is a *Schreier* graph on a coset space, so its degrees are not constant and regular-graph optimality notions do not apply to it. Three separate spectral claims were withdrawn for assuming otherwise.
- $78 = \dim E_6$ **is a parameter fact.** All 28 non-isomorphic $\mathrm{SRG}(40, 12, 2, 4)$ graphs give the same 78 zeta poles, so the coincidence says nothing about *which* graph this architecture uses.
- **The load port does not act on the projective carriers.** A translation is not well defined on projective points, so no argument about which carrier the machine addresses may be built from where translations live.
- **"Compute is exactly zero" holds of every design here**, not only of a reversible closure — every opcode is a bijection. What closing under inverses buys is time-symmetry of the random-instruction walk, not a reduction in dissipation.